

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL		1. WELL NAME and NUMBER Cameron Adkins 9-35-3-1E
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>		3. FIELD OR WILDCAT RANDLETT
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO		5. UNIT or COMMUNITIZATION AGREEMENT NAME
6. NAME OF OPERATOR CRESCENT POINT ENERGY U.S. CORP		7. OPERATOR PHONE 720 880-3621
8. ADDRESS OF OPERATOR 555 17th Street, Suite 750, Denver, CO, 80202		9. OPERATOR E-MAIL abaldwin@crecidentpointenergy.com
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Fee	11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>	12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Jay L Stone		14. SURFACE OWNER PHONE (if box 12 = 'fee') 801-253-1631
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 1768 Herbert Avenue, ,		16. SURFACE OWNER E-MAIL (if box 12 = 'fee')
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')	18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>	19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>

20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	2003 FSL 727 FEL	NESE	35	3.0 S	1.0 E	U
Top of Uppermost Producing Zone	2003 FSL 727 FEL	NESE	35	3.0 S	1.0 E	U
At Total Depth	2003 FSL 727 FEL	NESE	35	3.0 S	1.0 E	U

21. COUNTY UINTAH	22. DISTANCE TO NEAREST LEASE LINE (Feet) 727	23. NUMBER OF ACRES IN DRILLING UNIT 40
25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 920	26. PROPOSED DEPTH MD: 8556 TVD: 8556	
27. ELEVATION - GROUND LEVEL 5102	28. BOND NUMBER LPM9080271	29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 43-12534

Hole, Casing, and Cement Information

String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Cond	24	16	0 - 40	65.0	H-40 ST&C	8.3	No Used	0	0.0	0.0
Surf	12.25	8.625	0 - 1500	24.0	J-55 ST&C	8.3	Class G	260	2.5	12.0
							Class G	315	1.15	15.8
Prod	7.875	5.5	0 - 8556	17.0	N-80 LT&C	10.0	Light (Hibond)	255	3.46	11.0
							Class G	495	1.76	13.1


ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP

NAME Kristen Johnson	TITLE Regulatory Technician	PHONE 303 308-6270
SIGNATURE	DATE 06/22/2015	EMAIL kjohnson@crecidentpointenergy.com
API NUMBER ASSIGNED 43047553970000	APPROVAL  Permit Manager	

T3S, R1E, U.S.B.&M.




Proposed Well Head NAD 83
 LATITUDE = 40.176912°N
 LONGITUDE = 109.843167°W

WELL LOCATION:
CAMERON ADKINS 9-35-3-1E
 ELEV. UNGRADED GROUND = 5107.1'

NOTES:

- ▲ = Section Corners Located
 - △ = Section Corners Located Not Monumented
1. Well footages are measured at right angles to the Section Lines.
 2. Bearings and distances shown on this plat are based upon a local Cartesian Grid which is oriented to Geodetic North at the SE Corner of Section 36, T3S, R1E, U.S.B.&M. the grid having a mean project height of 5,000'. Lineal units used are U.S. Survey Foot. Trimble G.P.S. equipment was used in performance of this survey.
 3. Latitude and Longitude are NAD 83 (2011) Epoch 2010. Elevations are NAVD 88. Both derived from the Utah Virtual Reference Station Control System (VRS).



SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

PROFESSIONAL LAND SURVEYOR
 LICENCE No. 6028691
 STATE OF UTAH

CRESCENT POINT ENERGY
 555 17th Street, Suite 1800 - Denver, Colorado 80202

WELL PLAT

CAMERON ADKINS 9-35-3-1E
2003' FSL, 727' FEL
NE ¼ SE ¼ OF SECTION 35, T3S, R1E,
U.S.B.&M., UINTAH COUNTY, UTAH.



(435) 789-1365

TIMBERLINE
 ENGINEERING & LAND SURVEYING, INC.
 209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 7-22-14	SURVEYED BY: J.W.	SHEET NO:
DATE DRAWN: 8-28-14	DRAWN BY: S.A.	1 OF 13
SCALE: 1" = 1000'		