

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL		1. WELL NAME and NUMBER Prickly Pear Unit Fed 9A-18D-12-15
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>		3. FIELD OR WILDCAT PRICKLY PEAR
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO		5. UNIT or COMMUNITIZATION AGREEMENT NAME PRICKLY PEAR
6. NAME OF OPERATOR BILL BARRETT CORP		7. OPERATOR PHONE 303 312-8164
8. ADDRESS OF OPERATOR 1099 18th Street Ste 2300, Denver, CO, 80202		9. OPERATOR E-MAIL dspencer@billbarrettcorp.com
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU73668	11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>	
12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		13. NAME OF SURFACE OWNER (if box 12 = 'fee')
14. SURFACE OWNER PHONE (if box 12 = 'fee')		15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')
16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')
18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>		19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>

20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	495 FNL 1447 FWL	NENW	17	12.0 S	15.0 E	S
Top of Uppermost Producing Zone	1695 FNL 339 FEL	SENE	18	12.0 S	15.0 E	S
At Total Depth	2639 FSL 549 FEL	NESE	18	12.0 S	15.0 E	S

21. COUNTY CARBON	22. DISTANCE TO NEAREST LEASE LINE (Feet) 2658	23. NUMBER OF ACRES IN DRILLING UNIT 20
24. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 666	26. PROPOSED DEPTH MD: 8400 TVD: 7400	
27. ELEVATION - GROUND LEVEL 7419	28. BOND NUMBER WYB000040	29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Nine Mile Creek

Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Cond	26	16	0 - 40	65.0	Unknown	8.6	Unknown	0	0.0	0.0
Surf	12.25	9.625	0 - 1000	36.0	J-55 ST&C	8.6	Varocem	170	2.53	12.0
							Unknown	190	1.16	15.8
Prod	8.75	4.5	0 - 8400	11.6	P-110 LT&C	9.5	Halliburton Light , Type Unknown	320	1.96	12.5
							50/50 Poz	1440	1.45	13.4

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP

NAME Tracey Fallang	TITLE Regulatory Manager	PHONE 303 312-8134
SIGNATURE	DATE 03/24/2011	EMAIL tfallang@billbarrettcorp.com
API NUMBER ASSIGNED 43007501380000	APPROVAL  Permit Manager	

DRILLING PROGRAM

BILL BARRETT CORPORATION

Prickly Pear Unit Federal 9A-18D-12-15

NENW, 495' FNL, 1447' FWL, Sec. 17, T12S-R15E (surface hole)

NESE, 2639' FSL, 549' FEL, Sec. 18, T12S-R15E (bottom hole)

Carbon County, Utah

1 – 2. Estimated Tops of Geological Markers and Formations Expected to Contain Water, Oil and Gas and Other Minerals

<u>Formation</u>	<u>Depth – MD</u>	<u>Depth – TVD</u>
Green River	Surface	Surface
Wasatch	3344'*	2790'*
North Horn	5647'*	4676'*
Dark Canyon	7443'*	6470'*
Price River	7693'*	6720'*
TD	8400'*	7400'*

PROSPECTIVE PAY: *Members of the Mesaverde formation and Wasatch formation (inclusive of the North Horn) are primary objectives for oil/gas. Any shallow water zones encountered will be adequately protected and reported. All potentially productive hydrocarbon zones will be cemented off.

3. BOP and Pressure Containment Data

<u>Depth Intervals</u>	<u>BOP Equipment</u>
0 – 1000'	No pressure control required
1000' – TD	11" 3000# Ram Type BOP 11" 3000# Annular BOP
- Drilling spool to accommodate choke and kill lines;	
- Ancillary equipment and choke manifold rated at 3,000#. All BOP and BOPE tests will be in accordance with the requirements of onshore Order No. 2;	
- The BLM and the State of Utah Division of Oil, Gas and Mining will be notified 24 hours in advance of all BOP pressure tests.	
- BOP hand wheels may be underneath the sub-structure of the rig if the drilling rig used is set up to operate most efficiently in this manner.	

Bill Barrett Corporation
 Drilling Program
 Prickly Pear Unit Federal #9A-18D-12-15
 Carbon County, Utah

4. **Casing Program**

<u>Hole Size</u>	<u>Setting Depth</u>		<u>Casing Size</u>	<u>Casing Weight</u>	<u>Casing Grade</u>	<u>Thread</u>	<u>Condition</u>
	<u>From</u>	<u>To</u>					
26"	Surface	40'	16"	65#			
12 1/4"	Surface	1000'	9 5/8"	36#	Jor K 55	ST&C	New
8 3/4" and 7 7/8"	Surface	TD	5 1/2" 4 1/2"	17.0# 11.6#	P-110 P-110	LT&C LT&C	New New

Note: BBC will use one of the options of production casing size noted above. In addition, the 7 7/8" hole size will begin at the point the bit is changed.

5. **Cementing Program**

16" Conductor Casing 9 5/8" Surface Casing	Grout cement <i>Lead</i> with approximately 170 sx Varicem cement + additives mixed at 12.0 ppg (yield = 2.53 ft ³ /sx). <i>Tail</i> with approximately and 190 sx Halcem cement with additives mixed at 15.8 ppg (yield = 1.16 ft ³ /sx) circulated to surface with 100% excess.
5 1/2" Production Casing OR 4 1/2" Production Casing	<i>Lead</i> with approximately 320 sx (4 1/2" csg) or 260 sx (5 1/2" csg) of Halliburton Light Premium cement with additives mixed at 12.5 ppg (yield = 1.96 ft ³ /sx). <i>Tail</i> with approximately 1440 sx (4 1/2" csg) or 1190 sx (5 1/2" csg) of 50/50 Poz cement + additives mixed at 13.4 ppg (yield = 1.45 ft ³ /sk), circulated to ~800' with 15% excess.

Note: Actual volumes to be calculated from caliper log.

6. **Mud Program**

<u>Interval</u>	<u>Weight</u>	<u>Viscosity</u>	<u>Fluid Loss (API filtrate)</u>	<u>Remarks</u>
0 – 40'	8.3 – 8.6	27 – 40	--	Native Spud Mud
40' – 1000'	8.3 – 8.6	27 – 40	15 cc or less	Native/Gel/Lime
1000' – TD	8.6 – 9.5	38 – 46	15 cc or less	LSND/DAP

Note: Sufficient mud materials to maintain mud properties, control lost circulation and to contain "kicks" will be available at wellsite. BBC may require minor amounts of diesel to be added to its fluid system in order to reduce torque and drag.

7. **Testing, Logging and Core Programs**

Cores	None anticipated;
Testing	None anticipated;
Sampling	30' to 50' samples; surface casing to TD. Preserve samples all show intervals;
Surveys	Run every 1000' and on trips, slope only;
Logging	DIL-GR-SP, FDC-CNL-GR-CAL-Pe-Microlog, Sonic-GR, all TD to surface.

Bill Barrett Corporation
Drilling Program
Prickly Pear Unit Federal #9A-18D-12-15
Carbon County, Utah

8. Anticipated Abnormal Pressures or Temperatures

No abnormal pressures or temperatures or other hazards are anticipated.

Maximum anticipated bottom hole pressure equals approximately 3656 psi* and maximum anticipated surface pressure equals approximately 2028 psi** (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

*Max Mud Wt x 0.052 x TD = A (bottom hole pressure)

**Maximum surface pressure = A - (0.22 x TD)

9. Auxiliary Equipment

- a) Upper kelly cock; lower Kelly cock will be installed while drilling
- b) Inside BOP or stab-in valve (available on rig floor)
- c) Safety valve(s) and subs to fit all string connections in use
- d) Mud monitoring will be visually observed

10. Drilling Schedule

Location Construction: April 16, 2011
Spud: May 8, 2011
Duration: 5 days drilling time
20 days completion time

Other -Onshore Variances Requested

Use of EFM and Flow Conditioner (Onshore Order No. 5)

Use of an electronic flow meter (EFM) for gas measurement purposes is requested with this application.

Use of a flow conditioner is also being requested (versus straightening vanes). Flow conditioners have been proven to be as or more effective than straightening vanes in conditioning gas for measurement. In addition to their superior conditioning properties, they take up less space (shorter meter runs/smaller footprint), and are less prone to corrosion and dislodging (greater reliability). In the past BBC has experienced straightening vanes becoming dislodged in normal service and compromising their conditioning effectiveness.

Make/Model: CPA 50E

Dimensions: 2" or 3" Flanged conditioners - 16" minimum up to 3 1/2' long x 2" (ID 2.067) OR 24" minimum up to 3 1/2' long x 3" (ID 3.068)

Air Drilling (Onshore Order No. 2)

Air drilling operations will be conducted with the purpose of drilling and setting surface casing with a truck mounted air rig, for all Federal wells located at this pad. Surface casing is approximately 1000'. Bill Barrett Corporation will comply with the following surface air drilling operation requirements:

1. Properly lubricated and maintained diverter system in place of a rotating head. The diverter system forces air and cutting returns to the cuttings pit and is used solely to drill the surface hole. In addition, BBC will use a properly lubricated and maintained rotating head in compliance with OOG No. 2.
2. The Blooie line will discharge at least 100 feet from the wellbore and will be securely anchored.
3. An automatic igniter or continuous pilot light will be installed at the end of the blooie line.
4. Compressors that supply energy to drill the air filled surface hole will be located 100' away from the wellbore and on the opposite side of the blooie line. The compressors will be equipped with 1) emergency kill switch, 2) pressure relief valves 3) spark arresters on the motors.

BILL BARRETT CORPORATION
 Well location, PRICKLY PEAR UNIT FEDERAL #9A-18D-12-15, located as shown in the NE 1/4 NW 1/4 of Section 17, T12S, R15E, S.L.B.&M., Carbon County, Utah.

BASIS OF ELEVATION

COTTON TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 31, T12S, R16E, S.L.B.&M. TAKEN FROM THE TWIN HOLLOW QUADRANGLE, UTAH, CARBON COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 7386 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

T12S, R15E, S.L.B.&M.
 1909 Brass Cap
 2.3' High, Pile
 of Stones N89°42'03"W - 2628.74' (Meas.)

S89°56'45"W - 2639.52' (Meas.)
 1909 Brass Cap
 1.5' High, Pile
 of Stones

**PRICKLY PEAR UNIT
 FEDERAL #9A-18D-12-15**
 Elev. Ungraded Ground = 7419'

18

17

Bottom
 Hole

549'

N00°01'38"W - 5296.92' (Meas.)

2639'

1909 Brass Cap
 2.0' High, Pile
 of Stones

S89°58'23"W
 2644.88' (Meas.)


1909 Brass Cap
 0.8' High

N00°10'05"E - 2630.06' (Meas.)

1909 Brass Cap
 2.0' High

S89°48'52"W - 5227.44' (Meas.)

N00°39'51"E - 2638.91' (Meas.)




CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAN WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY CLOSE SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

S. 1/4 Cor. Sec. 18
 1909 Brass Cap 0.6'
 High, Tee Post

REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH




UINTAH ENGINEERING & LAND SURVEYING	
85 SOUTH 200 EAST - VERNAL, UTAH 84078	
(435) 789-1017	
SCALE 1" = 1000'	DATE SURVEYED: 09-04-08
PARTY D.S. E.D. C.C.	DATE DRAWN: 03-14-11
WEATHER COOL	REFERENCES G.L.O. PLAT
	FILE BILL BARRETT CORPORATION

LEGEND:

- = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 39°46'25.28" (39.773689)	LATITUDE = 39°46'46.60" (39.779611)
LONGITUDE = 110°16'19.11" (110.271975)	LONGITUDE = 110°15'53.60" (110.264889)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 39°46'25.41" (39.773725)	LATITUDE = 39°46'46.73" (39.779647)
LONGITUDE = 110°16'16.55" (110.271264)	LONGITUDE = 110°15'51.04" (110.264178)
STATE PLANE NAD 27	STATE PLANE NAD 27
N: 526999.86 E: 2345343.40	N: 529183.87 E: 2347305.08



**R
14
E**

**R
15
E**

**PRICKLY PEAR UNIT
FEDERAL SE 8 PAD**

SW 7 PAD

SE 7 PAD

NW 17 PAD

T12S

LEGEND:

- AS-BUILT LOCATION
- EXISTING LOCATION (OTHER)
- AS-BUILT ROAD
- AS-BUILT PIPELINE
- AS-BUILT WELLHEAD
- EXISTING ROAD
- EXISTING PIPELINE

BILL BARRETT CORPORATION

PRICKLY PEAR UNIT FEDERAL SE 8 PAD & CTB
 PRICKLY PEAR UNIT FEDERAL #16-8D-12-15, #15-8D-12-15,
 #1A-17D-12-15 & #2-17D-12-15
 SECTION 8, T12S, R15E, S.L.B.&M.
 SE 1/4 SE 1/4



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789 1813



As-Built Access Road & Pipeline Route

03	18	11
MONTH	DAY	YEAR

SCALE: 1" = 2000' DRAWN BY: C.C. REVISED: 00-00-00

2

FIGURE



Bill Barrett Corporation

Bill Barrett Corp.

Carbon County, UT [NAD27]
Prickly Pear NW 17 Pad
Prickly Pear UF 9A-18D-12-15

Wellbore #1

Plan: plan1 24mar11 smw




Standard Planning Report

24 March, 2011






+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	529184.07	2347305.00	39° 46' 46.73 N	110° 15' 51.04 W



SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect	Target
0.00	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
500.00	0.000	0.00	500.00	0.00	0.00	0.00	0.00	0.00	
1310.79	40.540	222.72	1244.82	-202.09	-186.61	5.00	222.72	275.07	
4628.71	40.540	222.72	3766.29	-1786.46	-1649.65	0.00	0.00	2431.63	
5646.69	10.000	222.72	4676.00	-2101.96	-1940.99	3.00	-180.00	2861.06	PPU Fed 9A-18D Target 1
5913.36	2.000	222.72	4940.99	-2122.42	-1959.88	3.00	180.00	2888.91	
8323.84	2.000	222.72	7350.00	-2184.22	-2016.96	0.00	0.00	2973.04	PPU Fed 9A-18D PBHL



Azimuths to True North
Magnetic North: 11.36°

Magnetic Field
Strength: 52141.4snT
Dip Angle: 65.55°
Date: 03/24/2011
Model: IGRF200510






WELL DETAILS: Prickly Pear NW 17 Pad

US State Plane 1927 (Exact solution) , NAD 1927 (NADCON CONUS) , Utah Central 4302

Ground Level: 7417.00

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	529194.10	2347292.49	39° 46' 46.83 N	110° 15' 51.20 W





Database:	Compass VM	Local Co-ordinate Reference:	Well Prickly Pear UF 9A-18D-12-15
Company:	Bill Barrett Corp.	TVD Reference:	GL @ 7417.00ft
Project:	Carbon County, UT [NAD27]	MD Reference:	GL @ 7417.00ft
Site:	Prickly Pear NW 17 Pad	North Reference:	True
Well:	Prickly Pear UF 9A-18D-12-15	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	plan1 24mar11 smw		

Project	Carbon County, UT [NAD27]		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		Using geodetic scale factor

Site	Prickly Pear NW 17 Pad				
Site Position:		Northing:	529,194.10 usft	Latitude:	39° 46' 46.83 N
From:	Lat/Long	Easting:	2,347,292.50 usft	Longitude:	110° 15' 51.20 W
Position Uncertainty:	0.00 ft	Slot Radius:	1.10 ft	Grid Convergence:	0.79 °

Well	Prickly Pear UF 9A-18D-12-15					
Well Position	+N/-S	-10.21 ft	Northing:	529,184.07 usft	Latitude:	39° 46' 46.73 N
	+E/-W	12.37 ft	Easting:	2,347,305.00 usft	Longitude:	110° 15' 51.04 W
Position Uncertainty		0.00 ft	Wellhead Elevation:		Ground Level:	7,417.00 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	03/24/11	11.36	65.55	52,141

Design	plan1 24mar11 smw			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	222.72

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
500.00	0.000	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,310.79	40.540	222.72	1,244.82	-202.09	-186.61	5.00	5.00	0.00	222.72	
4,628.71	40.540	222.72	3,766.29	-1,786.46	-1,649.65	0.00	0.00	0.00	0.00	
5,646.69	10.000	222.72	4,676.00	-2,101.96	-1,940.99	3.00	-3.00	0.00	-180.00	PPU Fed 9A-18D Tan
5,913.36	2.000	222.72	4,940.99	-2,122.42	-1,959.88	3.00	-3.00	0.00	180.00	
8,323.84	2.000	222.72	7,350.00	-2,184.22	-2,016.96	0.00	0.00	0.00	0.00	PPU Fed 9A-18D PB



Database:	Compass VM	Local Co-ordinate Reference:	Well Prickly Pear UF 9A-18D-12-15
Company:	Bill Barrett Corp.	TVD Reference:	GL @ 7417.00ft
Project:	Carbon County, UT [NAD27]	MD Reference:	GL @ 7417.00ft
Site:	Prickly Pear NW 17 Pad	North Reference:	True
Well:	Prickly Pear UF 9A-18D-12-15	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	plan1 24mar11 smw		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
500.00	0.000	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 5.00										
600.00	5.000	222.72	599.87	-3.20	-2.96	4.36	5.00	5.00	5.00	0.00
700.00	10.000	222.72	698.99	-12.79	-11.81	17.41	5.00	5.00	5.00	0.00
800.00	15.000	222.72	796.58	-28.69	-26.49	39.05	5.00	5.00	5.00	0.00
900.00	20.000	222.72	891.93	-50.77	-46.88	69.11	5.00	5.00	5.00	0.00
1,000.00	25.000	222.72	984.28	-78.88	-72.84	107.36	5.00	5.00	5.00	0.00
9 5/8"										
1,100.00	30.000	222.72	1,072.96	-112.79	-104.15	153.52	5.00	5.00	5.00	0.00
1,200.00	35.000	222.72	1,157.27	-152.25	-140.59	207.24	5.00	5.00	5.00	0.00
1,300.00	40.000	222.72	1,236.58	-196.96	-181.88	268.09	5.00	5.00	5.00	0.00
1,310.79	40.540	222.72	1,244.82	-202.09	-186.61	275.07	5.00	5.00	5.00	0.00
Start 3317.91 hold at 1310.79 MD										
1,400.00	40.540	222.72	1,312.61	-244.69	-225.95	333.05	0.00	0.00	0.00	0.00
1,500.00	40.540	222.72	1,388.60	-292.44	-270.04	398.05	0.00	0.00	0.00	0.00
1,600.00	40.540	222.72	1,464.60	-340.19	-314.14	463.05	0.00	0.00	0.00	0.00
1,700.00	40.540	222.72	1,540.60	-387.94	-358.23	528.04	0.00	0.00	0.00	0.00
1,800.00	40.540	222.72	1,616.59	-435.69	-402.33	593.04	0.00	0.00	0.00	0.00
1,900.00	40.540	222.72	1,692.59	-483.45	-446.42	658.04	0.00	0.00	0.00	0.00
2,000.00	40.540	222.72	1,768.58	-531.20	-490.52	723.04	0.00	0.00	0.00	0.00
2,100.00	40.540	222.72	1,844.58	-578.95	-534.61	788.03	0.00	0.00	0.00	0.00
2,200.00	40.540	222.72	1,920.57	-626.70	-578.71	853.03	0.00	0.00	0.00	0.00
2,300.00	40.540	222.72	1,996.57	-674.46	-622.81	918.03	0.00	0.00	0.00	0.00
2,400.00	40.540	222.72	2,072.57	-722.21	-666.90	983.03	0.00	0.00	0.00	0.00
2,500.00	40.540	222.72	2,148.56	-769.96	-711.00	1,048.02	0.00	0.00	0.00	0.00
2,600.00	40.540	222.72	2,224.56	-817.71	-755.09	1,113.02	0.00	0.00	0.00	0.00
2,700.00	40.540	222.72	2,300.55	-865.46	-799.19	1,178.02	0.00	0.00	0.00	0.00
2,800.00	40.540	222.72	2,376.55	-913.22	-843.28	1,243.02	0.00	0.00	0.00	0.00
2,900.00	40.540	222.72	2,452.54	-960.97	-887.38	1,308.01	0.00	0.00	0.00	0.00
3,000.00	40.540	222.72	2,528.54	-1,008.72	-931.47	1,373.01	0.00	0.00	0.00	0.00
3,100.00	40.540	222.72	2,604.54	-1,056.47	-975.57	1,438.01	0.00	0.00	0.00	0.00
3,200.00	40.540	222.72	2,680.53	-1,104.22	-1,019.66	1,503.00	0.00	0.00	0.00	0.00
3,300.00	40.540	222.72	2,756.53	-1,151.98	-1,063.76	1,568.00	0.00	0.00	0.00	0.00
3,344.05	40.540	222.72	2,790.00	-1,173.01	-1,083.18	1,596.63	0.00	0.00	0.00	0.00
Wasatch										
3,400.00	40.540	222.72	2,832.52	-1,199.73	-1,107.85	1,633.00	0.00	0.00	0.00	0.00
3,500.00	40.540	222.72	2,908.52	-1,247.48	-1,151.95	1,698.00	0.00	0.00	0.00	0.00
3,600.00	40.540	222.72	2,984.51	-1,295.23	-1,196.04	1,762.99	0.00	0.00	0.00	0.00
3,700.00	40.540	222.72	3,060.51	-1,342.99	-1,240.14	1,827.99	0.00	0.00	0.00	0.00
3,800.00	40.540	222.72	3,136.50	-1,390.74	-1,284.23	1,892.99	0.00	0.00	0.00	0.00
3,900.00	40.540	222.72	3,212.50	-1,438.49	-1,328.33	1,957.99	0.00	0.00	0.00	0.00
4,000.00	40.540	222.72	3,288.50	-1,486.24	-1,372.42	2,022.98	0.00	0.00	0.00	0.00
4,100.00	40.540	222.72	3,364.49	-1,533.99	-1,416.52	2,087.98	0.00	0.00	0.00	0.00
4,200.00	40.540	222.72	3,440.49	-1,581.75	-1,460.62	2,152.98	0.00	0.00	0.00	0.00
4,300.00	40.540	222.72	3,516.48	-1,629.50	-1,504.71	2,217.98	0.00	0.00	0.00	0.00
4,400.00	40.540	222.72	3,592.48	-1,677.25	-1,548.81	2,282.97	0.00	0.00	0.00	0.00
4,500.00	40.540	222.72	3,668.47	-1,725.00	-1,592.90	2,347.97	0.00	0.00	0.00	0.00
4,600.00	40.540	222.72	3,744.47	-1,772.75	-1,637.00	2,412.97	0.00	0.00	0.00	0.00
4,628.71	40.540	222.72	3,766.29	-1,786.46	-1,649.65	2,431.63	0.00	0.00	0.00	0.00
Start DLS 3.00 TFO -180.00										
4,700.00	38.401	222.72	3,821.32	-1,819.76	-1,680.40	2,476.94	3.00	-3.00	3.00	0.00
4,800.00	35.401	222.72	3,901.28	-1,863.86	-1,721.13	2,536.98	3.00	-3.00	3.00	0.00
4,900.00	32.401	222.72	3,984.27	-1,904.84	-1,758.96	2,592.75	3.00	-3.00	3.00	0.00
5,000.00	29.401	222.72	4,070.06	-1,942.56	-1,793.80	2,644.10	3.00	-3.00	3.00	0.00



Database:	Compass VM	Local Co-ordinate Reference:	Well Prickly Pear UF 9A-18D-12-15
Company:	Bill Barrett Corp.	TVD Reference:	GL @ 7417.00ft
Project:	Carbon County, UT [NAD27]	MD Reference:	GL @ 7417.00ft
Site:	Prickly Pear NW 17 Pad	North Reference:	True
Well:	Prickly Pear UF 9A-18D-12-15	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	plan1 24mar11 smw		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,100.00	26.401	222.72	4,158.43	-1,976.94	-1,825.54	2,690.89	3.00	-3.00	0.00
5,200.00	23.401	222.72	4,249.12	-2,007.87	-1,854.10	2,732.99	3.00	-3.00	0.00
5,300.00	20.401	222.72	4,341.90	-2,035.27	-1,879.40	2,770.28	3.00	-3.00	0.00
5,400.00	17.401	222.72	4,436.49	-2,059.06	-1,901.38	2,802.67	3.00	-3.00	0.00
5,500.00	14.401	222.72	4,532.66	-2,079.19	-1,919.96	2,830.07	3.00	-3.00	0.00
5,600.00	11.401	222.72	4,630.12	-2,095.59	-1,935.11	2,852.39	3.00	-3.00	0.00
5,646.69	10.000	222.72	4,676.00	-2,101.96	-1,940.99	2,861.06	3.00	-3.00	0.00
Start DLS 3.00 TFO 180.00 - North Horn - PPU Fed 9A-18D Target 1									
5,658.69	9.640	222.72	4,687.82	-2,103.46	-1,942.38	2,863.11	3.00	-3.00	0.00
PPU Fed 9A-18D Target									
5,700.00	8.401	222.72	4,728.62	-2,108.22	-1,946.77	2,869.58	3.00	-3.00	0.00
5,800.00	5.401	222.72	4,827.88	-2,117.05	-1,954.92	2,881.60	3.00	-3.00	0.00
5,900.00	2.401	222.72	4,927.64	-2,122.04	-1,959.54	2,888.40	3.00	-3.00	0.00
5,913.36	2.000	222.72	4,940.99	-2,122.42	-1,959.88	2,888.91	3.00	-3.00	0.00
Start 2410.48 hold at 5913.36 MD									
6,000.00	2.000	222.72	5,027.58	-2,124.64	-1,961.94	2,891.94	0.00	0.00	0.00
6,100.00	2.000	222.72	5,127.52	-2,127.20	-1,964.30	2,895.43	0.00	0.00	0.00
6,200.00	2.000	222.72	5,227.46	-2,129.77	-1,966.67	2,898.92	0.00	0.00	0.00
6,300.00	2.000	222.72	5,327.40	-2,132.33	-1,969.04	2,902.41	0.00	0.00	0.00
6,400.00	2.000	222.72	5,427.33	-2,134.90	-1,971.41	2,905.90	0.00	0.00	0.00
6,500.00	2.000	222.72	5,527.27	-2,137.46	-1,973.77	2,909.39	0.00	0.00	0.00
6,600.00	2.000	222.72	5,627.21	-2,140.02	-1,976.14	2,912.88	0.00	0.00	0.00
6,700.00	2.000	222.72	5,727.15	-2,142.59	-1,978.51	2,916.37	0.00	0.00	0.00
6,800.00	2.000	222.72	5,827.09	-2,145.15	-1,980.88	2,919.85	0.00	0.00	0.00
6,900.00	2.000	222.72	5,927.03	-2,147.72	-1,983.24	2,923.34	0.00	0.00	0.00
7,000.00	2.000	222.72	6,026.97	-2,150.28	-1,985.61	2,926.83	0.00	0.00	0.00
7,100.00	2.000	222.72	6,126.91	-2,152.84	-1,987.98	2,930.32	0.00	0.00	0.00
7,200.00	2.000	222.72	6,226.85	-2,155.41	-1,990.35	2,933.81	0.00	0.00	0.00
7,300.00	2.000	222.72	6,326.79	-2,157.97	-1,992.72	2,937.30	0.00	0.00	0.00
7,400.00	2.000	222.72	6,426.73	-2,160.54	-1,995.08	2,940.79	0.00	0.00	0.00
7,443.30	2.000	222.72	6,470.00	-2,161.65	-1,996.11	2,942.31	0.00	0.00	0.00
Dark Canyon									
7,500.00	2.000	222.72	6,526.66	-2,163.10	-1,997.45	2,944.28	0.00	0.00	0.00
7,600.00	2.000	222.72	6,626.60	-2,165.66	-1,999.82	2,947.77	0.00	0.00	0.00
7,693.45	2.000	222.72	6,720.00	-2,168.06	-2,002.03	2,951.04	0.00	0.00	0.00
Price River									
7,700.00	2.000	222.72	6,726.54	-2,168.23	-2,002.19	2,951.26	0.00	0.00	0.00
7,800.00	2.000	222.72	6,826.48	-2,170.79	-2,004.55	2,954.75	0.00	0.00	0.00
7,900.00	2.000	222.72	6,926.42	-2,173.36	-2,006.92	2,958.24	0.00	0.00	0.00
8,000.00	2.000	222.72	7,026.36	-2,175.92	-2,009.29	2,961.73	0.00	0.00	0.00
8,027.66	2.000	222.72	7,054.00	-2,176.63	-2,009.94	2,962.70	0.00	0.00	0.00
Price River 6840' Sand									
8,073.69	2.000	222.72	7,100.00	-2,177.81	-2,011.03	2,964.31	0.00	0.00	0.00
Price River 6840' Base									
8,100.00	2.000	222.72	7,126.30	-2,178.48	-2,011.66	2,965.22	0.00	0.00	0.00
8,200.00	2.000	222.72	7,226.24	-2,181.05	-2,014.02	2,968.71	0.00	0.00	0.00
8,300.00	2.000	222.72	7,326.18	-2,183.61	-2,016.39	2,972.20	0.00	0.00	0.00
8,322.55	2.000	222.72	7,348.71	-2,184.19	-2,016.93	2,972.99	0.00	0.00	0.00
PPU Fed 9A-18D PBHL									
8,323.84	2.000	222.72	7,350.00	-2,184.22	-2,016.96	2,973.04	0.00	0.00	0.00
TD at 8323.84									



Database:	Compass VM	Local Co-ordinate Reference:	Well Prickly Pear UF 9A-18D-12-15
Company:	Bill Barrett Corp.	TVD Reference:	GL @ 7417.00ft
Project:	Carbon County, UT [NAD27]	MD Reference:	GL @ 7417.00ft
Site:	Prickly Pear NW 17 Pad	North Reference:	True
Well:	Prickly Pear UF 9A-18D-12-15	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	plan1 24mar11 smw		

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PPU Fed 9A-18D Target - hit/miss target - Shape	0.000	0.00	4,676.00	-2,157.10	-1,991.83	526,999.88	2,345,343.37	39° 46' 25.41 N	110° 16' 16.55 W
- plan misses target center by 73.91ft at 5658.69ft MD (4687.82 TVD, -2103.46 N, -1942.38 E)									
- Circle (radius 100.00)									
PPU Fed 9A-18D Target - plan hits target center - Point	0.000	0.00	4,676.00	-2,101.96	-1,940.99	527,055.71	2,345,393.43	39° 46' 25.95 N	110° 16' 15.90 W
PPU Fed 9A-18D PBHL - plan misses target center by 36.95ft at 8322.55ft MD (7348.71 TVD, -2184.19 N, -2016.93 E) - Point	0.000	0.00	7,350.00	-2,157.10	-1,991.83	526,999.88	2,345,343.37	39° 46' 25.41 N	110° 16' 16.55 W

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (ft)	Hole Diameter (ft)	
1,000.00	984.28	9 5/8"	0.80	1.02	

Formations					
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
3,344.05	2,790.00	Wasatch		0.00	
5,646.69	4,676.00	North Horn		0.00	
7,443.30	6,470.00	Dark Canyon		0.00	
7,693.45	6,720.00	Price River		0.00	
8,027.66	7,054.00	Price River 6840' Sand		0.00	
8,073.69	7,100.00	Price River 6840' Base		0.00	

Plan Annotations					
Measured Depth (ft)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment	
500.00	500.00	0.00	0.00	Start Build 5.00	
1,310.79	1,244.82	-202.09	-186.61	Start 3317.91 hold at 1310.79 MD	
4,628.71	3,766.29	-1,786.46	-1,649.65	Start DLS 3.00 TFO -180.00	
5,646.69	4,676.00	-2,101.96	-1,940.99	Start DLS 3.00 TFO 180.00	
5,913.36	4,940.99	-2,122.42	-1,959.88	Start 2410.48 hold at 5913.36 MD	
8,323.84	7,350.00	-2,184.22	-2,016.96	TD at 8323.84	

SURFACE USE PLAN

BILL BARRETT CORPORATION
Prickly Pear Unit Federal NW 17 Pad SUP (revised 3/24/11)
Carbon County, UT

<u>Prickly Pear Unit Federal 3-17D-12-15</u> NENW, 497' FNL, 1466' FWL, Sec. 17, T12S-R15E (surface hole) NENW, 659' FNL, 2015' FWL, Sec. 17, T12S-R15E (bottom hole)	<u>Prickly Pear Unit Federal 3A-17D-12-15</u> NENW, 492' FNL, 1460' FWL, Sec. 17, T12S-R15E (surface hole) NENW, 5' FNL, 1460' FWL, Sec. 17, T12S-R15E (bottom hole)
<u>Prickly Pear Unit Federal 4-17D-12-15</u> NENW, 477' FNL, 1441' FWL, Sec. 17, T12S-R15E (surface hole) NWNW, 666' FNL, 685' FWL, Sec. 17, T12S-R15E (bottom hole)	<u>Prickly Pear Unit Federal 4A-17D-12-15</u> NENW, 472' FNL, 1435' FWL, Sec. 17, T12S-R15E (surface hole) NWNW, 9' FNL, 716' FWL, Sec. 17, T12S-R15E (bottom hole)
<u>Prickly Pear Unit Federal 5A-17D-12-15</u> NENW, 482' FNL, 1447' FWL, Sec. 17, T12S-R15E (surface hole) SWNW, 1327' FNL, 690' FWL, Sec. 17, T12S-R15E (bottom hole)	<u>Prickly Pear Unit Federal 6-17D-12-15</u> NENW, 502' FNL, 1472' FWL, Sec. 17, T12S-R15E (surface hole) SENE, 1983' FNL, 2021' FWL, Sec. 17, T12S-R15E (bottom hole)
<u>Prickly Pear Unit Federal 6A-17D-12-15</u> NENW, 507' FNL, 1478' FWL, Sec. 17, T12S-R15E (surface hole) SENE, 1324' FNL, 2012' FWL, Sec. 17, T12S-R15E (bottom hole)	<u>Prickly Pear Unit Federal 7A-17D-12-15</u> NENW, 513' FNL, 1484' FWL, Sec. 17, T12S-R15E (surface hole) SWNE, 1351' FNL, 1975' FEL, Sec. 17, T12S-R15E (bottom hole)
<u>Prickly Pear Unit Federal 12A-17D-12-15</u> NENW, 487' FNL, 1454' FWL, Sec. 17, T12S-R15E (surface hole) NWSW, 2633' FSL, 696' FWL, Sec. 17, T12S-R15E (bottom hole)	<u>Prickly Pear Unit Federal 7A-18D-12-15</u> NENW, 484' FNL, 1435' FWL, Sec. 17, T12S-R15E (surface hole) SWNE, 1334' FNL, 1752' FEL, Sec. 18, T12S-R15E (bottom hole)
<u>Prickly Pear Unit Federal 8A-18D-12-15</u> NENW, 490' FNL, 1441' FWL, Sec. 17, T12S-R15E (surface hole) SENE, 1336' FNL, 545' FEL, Sec. 18, T12S-R15E (bottom hole)	<u>Prickly Pear Unit Federal 9A-18D-12-15</u> NENW, 495' FNL, 1447' FWL, Sec. 17, T12S-R15E (surface hole) NESE, 2639' FSL, 549' FEL, Sec. 18, T12S-R15E (bottom hole)

This is a new pad with a total of **twelve** directional wells proposed to be drilled. Onsites for this pad occurred on December 1, 2008 and again on June 30, 2010 to review pad changes. During the June 30 onsite, BLM requested the following:

- 1) Bring Corner #2 in towards the center of the pad to get it further from the edge of the cliff.
- 2) Leave as much tree cover as possible to minimize visual impacts.
- 3) Take several pre-construction photos as this location is placed on thick, extensive rock and reclamation will be difficult.

The excavation contractor would be provided with an approved copy of the surface use plan of operations before initiating construction.

1. **Existing Roads:**

- a. The proposed pad is located approximately 44 miles from Myton, Utah. Maps reflecting directions to the proposed pad are included (see Topographic maps A and B).
- b. Primary access to this pad (approximately 0.9 miles) **was constructed** in 2010 to access a pad to the east of this pad. Further details are in 2 (a) below.
- c. The use of roads under State and County Road Department maintenance is necessary to access the Prickly Pear Unit. However, an encroachment permit is not anticipated as there are no upgrades to the State or County road systems proposed at this time.
- d. No topsoil stripping would occur as there are no improvements proposed to existing State, County or main BLM access roads.
- e. Project roads would require routine year-round maintenance to provide year-round access. Maintenance would include inspections, reduction of ruts and holes, maintenance to keep water off the road, replacement of surfacing materials, and clearing of sediment blocking ditches and culverts. Should snow removal become necessary, roads would be cleared with a scraper and snow would be stored along the down gradient side to prohibit runoff onto the road. Aggregate would be used as necessary to maintain a solid running surface and minimize dust generation.

Bill Barrett Corporation
Surface Use Plan
Prickly Pear NW 17 Pad
Carbon County, Utah

- f. Vehicle operators would obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions. Travel would be limited to the existing access roads and proposed access road.
- g. To address safety-related traffic concerns, drivers and rig crews would be advised of the hazards to recreational traffic along the existing and proposed access roads, as well as hazards present due to blind corners, cars parked on the road, pedestrian traffic, and mountain bikers. In addition, appropriate signs would be erected to warn non-project personnel about traffic hazards associated with project-related activities and during times of rig moves, when there is heavy equipment, traffic may be controlled on sections of roads. Traffic would be controlled using roadside signs, flagmen, and barricades as appropriate.
- h. Dust suppression and monitoring would be implemented where necessary and as prescribed by the BLM.
- i. An off-lease federal right-of-way for the access road and utility corridor is not anticipated at this time since existing roads are being utilized into the Prickly Pear Unit area. All new construction would be within the Unit.

2. Planned Access Road:

- a. BBC constructed the majority of the access and pipeline to this location at the time the SE 7 to the west and the SE 8 pad to the east was constructed in 2010. New construction, approximately 528 feet in length, proposed with this pad would be the access indicated in blue on Topographic Map B. A road design plan is not anticipated at this time.
- b. The new proposed access road would be co-located by pipeline(s) and the requested corridor disturbance would be 100 ft with a short-term corridor disturbance of 80 ft (0.96 acres) reclaimed to a long-term corridor of 30 ft (0.36 acres).
- c. The proposed road would be constructed to facilitate drainage, control erosion and minimize visual impacts by following natural contours where practical. No unnecessary side-casting of material would occur on steep slopes.
- d. Intervisible turnouts would be constructed, where necessary and as topographic conditions allow, to improve traffic safety. A maximum grade of 10 percent would be maintained with minimum cuts and fills, as necessary, to access the well pad.
- e. New road construction and improvements of existing roads would typically require the use of motorgraders, crawler tractors, 10-yard end dump trucks, and water trucks. The standard methodology for building new roads involves the use of a crawler tractor or track hoe to windrow the vegetation to one side of the road corridor, remove topsoil to the opposing side of the corridor, and rough-in the roadway. This is followed by a grader or bulldozer to establish barrow ditches and crown the road surface. Where culverts are required, a track hoe or backhoe would trench the road and install the culverts. Some hand labor would be required when installing and armoring culverts. Road base or gravel in some instances would be necessary and would be hauled in and a grader used to smooth the running surface.
- f. Excess rock from construction of the pad may be used for surfacing of the access road if necessary. Any additional aggregate necessary would be obtained from private, State of Utah, or federal lands in conformance with applicable regulations. Aggregate would be of sufficient size, type, and amount to allow all weather access and alleviate dust.
- g. Where topsoil removal is necessary, it would be windrowed (i.e. stockpiled/accumulated along the edge of the ROW and in a low row/pile parallel with the ROW) and re-spread over the disturbed area after construction and backfilling are completed. Vegetation removed from the disturbed area would also be re-spread to provide protection, nutrient recycling, and a seed source for reclamation.

Bill Barrett Corporation
 Surface Use Plan
 Prickly Pear NW 17 Pad
 Carbon County, Utah

- h. Adequate drainage structures would be incorporated and culverts, with a minimum diameter of 18 inches, would be installed as necessary.
- g. No gates or cattle guards are anticipated at this time.
- h. Surface disturbance and vehicular travel would be limited to the approved location access road. Adequate signs would be posted, as necessary, to warn the public of project related traffic.
- i. All access roads and surface disturbing activities would conform to the appropriate standard, no higher than necessary, to accommodate their intended function adequately as outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition – Revised 2007. BBC would be responsible for all maintenance of the access road.

3. Location of Existing Wells (see One-Mile Radius Map):

- a. Following is a list of wells with surface hole locations within a one-mile radius of the proposed pad:

i. water wells	none
ii. injection wells	none
iii. disposal wells	none
iv. drilling wells	none
v. temp shut-in wells	none
vi. producing wells	twenty-two
vii. abandoned wells	one

4. Location of Production Facilities:

- a. Each proposed well would have its own meter run and separator. Proposed wellheads and christmas trees would be contained below location grade in pre-cast concrete trenches. All wellheads associated with the drilling operations for this pad would be contained in the same trench measuring approximately 12 ft wide, 10 ft deep, and 96 ft long (# wells x 8 ft + 16 ft for two end pieces). Drawings of below ground cellars can be provided by BBC upon request.
- b. Tank facilities for this pad would be located at a centralized tank battery facility at the proposed Prickly Pear SE 8 well pad in the SESE, Sec. 8, T12S-R15E within the Prickly Pear unit. Up to ten 300-bbl low-profile tanks would be located on the proposed SE 8 CTB/well pad for production associated with this pad and for additional proposed pads that would also use this as a CTB. Although the pad is outside of the Participating Area boundary, bottom holes for all proposed wells located on this pad are within the Participating Area (PA).
- c. Because the SE 8 CTB would have non-PA wells as well as PA wells, production for non-PA wells would be combined in one set of tanks while production for PA wells would be combined in a separate set of tanks. Figure 1, Location Layout for the CTB.
- d. CTBs would be surrounded by a secondary containment berm of sufficient capacity to contain the 1.1 times the entire capacity of the largest single tank and sufficient freeboard to contain precipitation. All loading lines and valves would be placed inside the berm surrounding the CTB or would utilize catchment basins to contain spills. All liquid hydrocarbon production and measurement shall conform to the provisions of 43 CFR 3162.7-2 and Onshore Oil and Gas Order No. 4 for the measurement of oil. Any variances from this would be submitted via a sundry notice. BBC requests permission to install the necessary production/operation facilities with this application.
- e. Most wells would be fitted with plunger lift systems to assist liquid production. However, pump jacks may be used if liquid volumes and/or low formation pressures require it. Plunger lift systems

Bill Barrett Corporation
Surface Use Plan
Prickly Pear NW 17 Pad
Carbon County, Utah

do not require any outside source of energy. The prime mover for pump jacks would be small (50 horsepower or less), natural gas-fired internal combustion engines.

- f. Gas meter run(s) would be constructed and located on lease within 500 feet of the wellheads. Meter runs would be housed and/or fenced. As practicably feasible, meters would be equipped with remote telemetry monitoring systems. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3 and any variances would be included with this submittal or submitted via sundry notice.
 - g. A combustor may be installed at the Prickly Pear SE 8 pad CTB for control of associated condensate tank emissions. A combustor ranges from 24 inches to 48 inches wide and is approximately 10 ft -27 ft tall. Combustor placement would be on existing disturbance and would not be closer than 100 ft to any tank or wellhead(s). No combustor is planned currently on this pad.
 - h. Refer to 2(a) and (b) above for details on lengths of requested pipeline. A gas gathering pipeline (up to 8 inch diameter) and one liquids line (up to 6 inch maximum diameter) is associated with this application and is being applied for at this time (see Topographic Map C). The pipelines would leave the north end of the pad and traverse west to where both would tie into lines laid for the SE 8 pad.
 - j. The proposed new gas pipeline would be constructed of steel while the liquids lines would be constructed of steel, polyethylene, or fiberglass. The gas pipeline and liquids line would be buried, where soil conditions permit, within the proposed co-located access road and pipeline corridor.
 - k. This well pad lies almost entirely on bedrock; therefore, burial of pipelines would be unlikely. However, BBC would final this decision at the time of the pre-construction meeting with the BLM Authorized Officer.
 - l. BBC intends on stringing the pipeline on the surface, welding many joints into long lengths, dragging the long lengths into position and then completing a final welding pass to join the long lengths together. The welded joints would either remain on the surface or would be placed within the trench, depending on the scenario. BBC intends on connecting the pipeline together utilizing conventional welding technology.
 - m. Pipeline construction methods and practices would be planned and conducted by BBC with the objective of enhancing reclamation and fostering the re-establishment of the native plant community.
 - n. To limit erosion potential, backfill over pipeline trenches would be compacted so as not to extend above the original ground level after the fill has settled. Wheel or other methods of compacting backfill would be utilized as practicably feasible to reduce trench settling and water channeling.
 - o. All **permanent** above-ground structures would be painted a flat, non-reflective Olive Black to match the standard environmental colors. These structures would be painted the designated color at the time of installation or within 6 months of being located on site. Facilities that are required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.
 - p. Site security guidelines identified in 43 CFR 3162.7-5 and Onshore Oil and Gas Order No. 3 would be adhered to. Any changes to facilities proposed within this surface use plan would be depicted on the site security diagram submitted.
 - q. The site would require periodic maintenance to ensure that drainages are kept open and free of debris, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.
5. Location and Type of Water Supply:

Bill Barrett Corporation
Surface Use Plan
Prickly Pear NW 17 Pad
Carbon County, Utah

- a. Bill Barrett Corporation would use water consistent with approvals granted by the Utah State Engineer's Office under:
 - Application Number 90-1863, expires June 6, 2011
 - Application Number 98-1864, expires September 7, 2011
 - Application Number 90-4, expires December 31, 2014
 - Application Number 90-1861, expires May 11, 2011
 - b. Water use for this location would most likely be diverted from Nine Mile Creek, the N¼ of Section 3, T12S-R14E. Bobtail trucks would haul the water, traveling Prickly Pear road to Harmon Canyon, traveling north to this point of diversion.
 - c. Water use would vary in accordance with the formations to be drilled but would average approximately 1 acre-foot (7,758 barrels) during drilling operations and 1 acre-foot (7,758 barrels) during completion operations.
6. Source of Construction Material:
- a. The use of materials would conform to 43 CFR 3610.2-3.
 - b. No construction materials would be taken out of the Prickly Pear Unit.
 - c. If any additional gravel is required, it would be obtained from SITLA materials permits, federal BBC locations within the Prickly Pear unit or from private sources.
7. Methods of Handling Waste Disposal:
- a. All wastes associated with this application would be contained and disposed of utilizing approved facilities.

Closed Loop Drilling System
 - b. BBC intends to employ a closed loop drilling system in which drilling fluids and cuttings would be thoroughly processed such that the separated cuttings are relatively dry. The cuttings would be stored on location in either secured piles or in a 265 ft x 50 ft cuttings trench (indicated as reserve pit/cuttings trench on Figure 1 located outboard of the location along the south side of the pad).
 - c. The cuttings trench would not be lined. Three sides of the trench would be fenced before drilling starts and the fourth side would be fenced at the time drilling is completed on the last well on the pad and shall remain until cuttings trench has been reclaimed.
 - d. Upon completion of drilling, the cuttings would be tested and further processed as necessary to meet standards for burial on site or other BLM approved uses such as a media for road surfacing or growing media for reclamation.

Conventional or Semi-Closed Loop Drilling System
 - e. In the event closed loop drilling is not employed, a conventional or semi-closed loop system would be used where a small amount of fluid is retained in the cuttings and the cuttings are placed in the reserve pit. The reserve pit would also store water to make up losses and store any excess drilling fluids. Reserve pits would be constructed with an impermeable liner so as to prevent releases. The pit liner would overlap the pit walls and be anchored with soil and/or rocks to hold it in place. No trash, scrap pipe, etc. that could puncture the liner would be disposed of in the pit and a minimum of 2 ft of freeboard would be maintained in the pit at all times. Reserve pits would be constructed and maintained according to BLM or UDOGM requirements as appropriate.

Bill Barrett Corporation
Surface Use Plan
Prickly Pear NW 17 Pad
Carbon County, Utah

- f. Three sides of the reserve pit would be fenced before drilling starts and the fourth side would be fenced at the time drilling is completed on the last well on the pad and shall remain until the pit is dry.
- g. Any hydrocarbons floating on the surface of the reserve pit would be removed as soon as possible after drilling and completion operations are finished. In some cases, the reserve pit may be flagged overhead or covered with wire or plastic mesh to protect migrating birds.

Completion Pit

- h. Where closed loop drilling is employed, the cuttings trench disturbed area would typically also be used to store water for completion activities. The completion pit would be constructed with an impermeable liner to prevent releases and would be fenced and constructed and maintained according to BLM or UDOGM requirements.

Other

- i. Produced fluids from the wells other than water would be decanted into steel test tanks until such time as construction of production facilities is completed. Produced water may be used in further drilling and completion activities, evaporated in the pit or would be hauled to a state approved disposal facility.
- j. After initial clean-up and based on volumes, BBC would install a tank (maximum size 400 barrel capacity) to contain produced waste water. After first production, produced wastewater would be confined to tanks within the CTB for a period not to exceed ninety (90) days. Thereafter, produced water would be used in further drilling and completion activities or hauled to a State approved disposal facility.
- k. Any salts and/or chemicals, which are an integral part of the drilling system, would be disposed of in the same manner as the drilling fluid.
- l. Any spills of oil, condensate, produced or frac water, drilling fluids, or other potentially deleterious substances would be recovered and either returned to its origin or disposed of at an approved disposal site, most likely in Duchesne, Utah.
- m. Chemicals on the EPA's Consolidated List of Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA) may be used or stored in quantities over reportable quantities. In the course of drilling, BBC could potentially store and use diesel fuel, sand (silica), hydrochloric acid, and CO₂ gas, all described as hazardous substances in 40 CFR Part 302, Section 302.4, in quantities exceeding 10,000 pounds. In addition, natural gas condensate and crude oil and methanol may be stored or used in reportable quantities. Small quantities of retail products (paint/spray paints, solvents {e.g., WD-40}, and lubrication oil) containing non-reportable volumes of hazardous substances may be stored and used on site at any time. No extremely hazardous substances, as defined in 40 CFR 355, would be used, produced, stored, transported or disposed of in association with the drilling, testing or completion of the wells.
- n. Portable toilets and trash containers would be located onsite during drilling and completion operations. A commercial supplier would install and maintain portable toilets and equipment and would be responsible for removing sanitary waste. Sanitary waste facilities (i.e. toilet holding tanks) would be regularly pumped and their contents disposed of at approved sewage disposal facilities in Carbon, Duchesne, and/or Uintah Counties, in accordance with applicable rules and regulations regarding sewage treatment and disposal. Accumulated trash and nonflammable waste materials would be hauled to an approved landfill once a week or as often as necessary. All debris and waste materials not contained in the trash containers would be cleaned up, removed from the construction ROW, well pad, or worker housing location, and disposed of at an approved landfill. Trash would be cleaned up everyday.

Bill Barrett Corporation
 Surface Use Plan
 Prickly Pear NW 17 Pad
 Carbon County, Utah

minimize erosion and surface runoff during well pad construction and operation. Cut and fill slopes would be constructed such that stability would be maintained for the life of the activity.

- h. Construction of the well pad would take from 1 to 3 weeks depending on the features at the particular site.
- i. Dust suppression may be implemented if necessary to minimize the amount of fugitive dust.

10. Plan for Restoration of the Surface:

Interim Reclamation (see Figure 4)

- a. Portions of the disturbed area within a construction ROW or portions of well pads not needed for production would be reclaimed according to specifications of the BLM as appropriate.
- b. Prior to interim reclamation activities, all solid wastes and refuse would be removed and placed at approved landfills. The portions of the well pad or access and pipeline corridor not needed for production would be re-contoured to promote proper drainage, salvaged topsoil would be replaced, and side slopes would be ripped and disked on the contour. Following site preparation, reseeding would be completed during either the spring or fall planting season, when weather conditions are most favorable. Seed mixtures for reclaimed areas would be site-specific and would require approval by the BLM. BBC would apply and meet BLM's Green River District Reclamation Standards, where practicable.
- c. The operator would control noxious weeds along access road use authorizations, pipeline route authorizations, well sites or other applicable facilities by spraying or mechanical removal. A list of noxious weeds may be obtained from the BLM or the appropriate county extension office. On BLM administered land it is required that a Pesticide Use Proposal be submitted and approved prior to the application of herbicides, pesticides or possibly hazardous chemicals.
- d. Following interim reclamation, access roads (including roads co-located with pipeline) would be reduced to approximately 30 feet of disturbance. Roads leading to well sites that would not have surface production equipment would be designed and reclaimed in a way that minimizes impacts to the visual character of the host lands.
- e. Weather permitting, earthwork for interim reclamation would be completed within 6 months of completion of the final well on the pad or plugging and would continue until satisfactory revegetation cover is established. Inter-seeding (i.e. seeding into existing vegetation), secondary seeding, or staggered seeding may be used to accomplish revegetation objectives. During rehabilitation of areas in important wildlife habitat, provisions would be made for the establishment of native browse and forb species. Follow-up seeding or corrective erosion control measures would occur on areas where initial reclamation efforts are unsuccessful, as determined by the BLM or the appropriate surface management agency.

Dry Hole/Final Reclamation

- f. All disturbed lands associated with this project, including the pipelines, access roads, water management facilities, etc. would be expediently reclaimed and reseeded in accordance with the reclamation plan and any pertinent site-specific COAs.
- g. When a well is to be plugged and abandoned, BBC would submit a Notice of Intent to Abandon (NOA) to the BLM or UDOGM as appropriate. The BLM or UDOGM would then attach the appropriate surface rehabilitation COAs for the well pad, and as appropriate, for the associated access road, pipeline, and ancillary facilities. During plugging and abandonment, all structures and equipment would be removed from the well pad. Backfilling, leveling, and re-contouring would then be performed according to the BLM or UDOGM order.

Bill Barrett Corporation
Surface Use Plan
Prickly Pear NW 17 Pad
Carbon County, Utah

- h. Any mulch used by BBC would be weed-free and free from mold, fungi, or noxious weeds. Mulch may include native hay, small grain straw, wood fiber, live mulch, cotton, jute, synthetic netting or rock.
- i. BBC would reshape disturbed channel beds to their approximate original configuration.
- j. Reclamation of abandoned roads may include re-shaping, re-contouring, re-surfacing with topsoil, installation of water bars, and seeding on the contours. Road beds, well pads, and other compacted areas would be ripped to a depth of approximately 1 foot on 1.5 foot centers to reduce compaction prior to spreading the topsoil across the disturbed area. Stripped vegetation would be spread over the disturbance area for nutrient recycling, where practical. Additional erosion control measures (e.g. fiber matting) and road barriers to discourage travel may be constructed if appropriate. Graveled roads, well pads, and other sites would be stripped of usable gravel prior to ripping as deemed necessary. Culverts, cattleguards, and signs would be removed as roads are abandoned.

11. Surface and Mineral Ownership:

- a. Surface ownership – Federal under the management of the Bureau of Land Management – Price Field Office, 125 South 600 West, Price Utah 84078; (435) 636-3600.
- b. Mineral ownership – Federal under the management of the Bureau of Land Management – Price Field Office, 125 South 600 West, Price Utah 84078; (435) 636-3600.

12. Other Information:

- a. Montgomery Archaeological Consultants conducted a cultural resource inventory for this pad under MOAC 08-251, dated 11/4/08
- b. BBC would require that their personnel, contractors, and subcontractors to comply with Federal regulations intended to protect archeological and cultural resources.
- c. Project personnel and contractors would be educated on and subject to the following requirements:
 - No dogs within the WTP Project Area;
 - No firearms within the WTP Project Area;
 - No littering within the WTP Project Area;
 - Smoking within the WTP Project Area would only be allowed in off-operator active locations or in specifically designated smoking areas. All cigarette butts would be placed in appropriate containers and not thrown on the ground or out windows of vehicles; personnel and contractors would abide by all fire restriction orders;
 - Campfires or uncontained fires of any kind would be prohibited within the WTP Project Area;
 - Portable generators used in the WTP Project Area would have spark arrestors.
- d. All proposed disturbances are within the Prickly Pear unit: Surface and bottom hole disturbances occur on lease UTU-73006 and UTU-73668.

OPERATOR CERTIFICATION

Certification:


I hereby certify that I, or someone under my direction supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein would be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filings of false statements.

Executed this 24th day of Mar 2011
Name: Tracey Fallang
Position Title: Regulatory Analyst
Address: 1099 18th Street, Suite 2300, Denver, CO 80202
Telephone: 303-312-8134
Field Representative Brandon Murdock
Address: 1820 W. Hwy 40, Roosevelt, UT 84066
Telephone: 435-724-5252
E-mail: bmurdock@billbarrettcorp.com

Tracey Fallang, Regulatory Manager
Tracey Fallang, Regulatory Manager


BILL BARRETT CORPORATION

TYPICAL 3,000 p.s.i. BLOWOUT PREVENTER



BILL BARRETT CORPORATION

TYPICAL 3,000 p.s.i. CHOKE MANIFOLD





March 24, 2011

Ms. Diana Mason
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Directional Drilling R649-3-11
Prickly Pear Unit Federal #9A-18D-12-15
SHL: 495' FNL & 1447' FWL, NENW 17-T12S-R15E
BHL: 2639' FSL & 549' FEL, NESE 18-T12S-R15E
Carbon County, Utah

Dear Ms. Mason:

Pursuant to the filing of Bill Barrett Corporation's ("BBC") Application for Permit to Drill ("APD") regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the "Exception to Location and Siting of Wells."

- The above-mentioned proposed location is within the Prickly Pear Unit Area;
- BBC is permitting this well as a directional well in order to minimize surface disturbance. By locating the well at the surface location and directionally drilling from this location, BBC will be able to utilize the existing road and pipelines in the area;
- BBC hereby certifies this well is located within 460 feet of the unit boundary.
- Additional working interest owner includes XTO Energy, Inc. BBC will consult with this owner regarding the drilling of this well.

Based on the information provided, BBC requests that the permit be granted pursuant to R649-3-11. If you should have any questions or need further information, please contact Vicki Wambolt, Landman at 303-312-8513.

Sincerely,



Vicki Wambolt
Vicki Wambolt
Landman *by TLF*

1099 18TH STREET
SUITE 2300
DENVER, CO 80202
P 303.293.9100
F 303.291.0420

BILL BARRETT CORPORATION
LOCATION LAYOUT FOR


PRICKLY PEAR UNIT FEDERAL #4A-17D-12-15, #4-17D-12-15,
#5A-17D-12-15, #12A-17D-12-15, #3A-17D-12-15, #3-17D-12-15,
#6-17D-12-15, #6A-17D-12-15, #7A-17D-12-15, #7A-18D-12-15,
#8A-18D-12-15 & #9A-18D-12-15
SECTION 17, T12S, R15E, S.L.B.&M.
NE 1/4 NW 1/4

FIGURE #1



SCALE: 1" = 50'
DATE: 10-14-08
DRAWN BY: C.C.
Revised: 02-01-10
Revised: 06-21-10
Revised: 03-14-11

NOTE:
Flare Pit is to be located a min. of 100' from the Well Head.



Total Pit Capacity
W/2' of Freeboard
= 12,740 Bbls.±
Total Pit Volume
= 3,560 Cu. Yds

Elev. Ungraded Ground At #4A-17D Loc. Stake = 7418.3'
FINISHED GRADE ELEV. AT #4A-17D LOC. STAKE = 7416.7'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017






BILL BARRETT CORPORATION
 TYPICAL CROSS SECTIONS FOR

FIGURE #2

X-Section Scale
 1" = 20'
 1" = 50'

DATE: 10-14-08
 DRAWN BY: C.C.
 Revised: 02-01-10
 Revised: 07-16-10
 Revised: 03-14-11

PRICKLY PEAR UNIT FEDERAL #4A-17D-12-15, #4-17D-12-15,
 #5A-17D-12-15, #12A-17D-12-15, #3A-17D-12-15, #3-17D-12-15,
 #6-17D-12-15, #6A-17D-12-15, #7A-17D-12-15, #7A-18D-12-15,
 #8A-18D-12-15 & #9A-18D-12-15
 SECTION 17, T12S, R15E, S.L.B.&M.
 NE 1/4 NW 1/4



NOTE:
 Topsoil should not be Stripped Below Finished Grade on Substructure Area.

* NOTE:
 FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

(6") Topsoil Stripping	=	3,110 Cu. Yds.
Remaining Location	=	19,360 Cu. Yds.
TOTAL CUT	=	22,470 CU.YDS.
FILL	=	12,200 CU.YDS.

EXCESS MATERIAL	=	10,270 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	4,890 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	=	5,380 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
 85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

March 29, 2011

Memorandum

To: Associate Field Office Manager,
Price Field Office

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Prickly Pear Unit
Carbon County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Prickly Pear Unit, Carbon County, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ Wasatch-Mesaverde)		
43-007-50136	PPear Unit 7A-18D-12-15	Sec 17 T12S R15E 0484 FNL 1435 FWL BHL Sec 18 T12S R15E 1334 FNL 1752 FEL
43-007-50137	PPear Unit 8A-18D-12-15	Sec 17 T12S R15E 0490 FNL 1441 FWL BHL Sec 18 T12S R15E 1336 FNL 0545 FEL
43-007-50138	PPear Unit 9A-18D-12-15	Sec 17 T12S R15E 0495 FNL 1447 FWL BHL Sec 18 T12S R15E 2639 FSL 0549 FEL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2011.03.29 15:34:44 -06'00'


bcc: File - Prickly Pear Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:3-29-11


RECEIVED: Mar. 30, 2011

API Number: 4300750138
Well Name: Prickly Pear Unit Fed 9A-18D-12-15
Township T1.2 . Range R1.5 . Section 17
Meridian: SLBM
Operator: BILL BARRETT CORP

Map Prepared:
 Map Produced by Diana Mason



- | | |
|---------------|------------------------------------|
| Units | Wells Query |
| STATUS | Status |
| ACTIVE | APD - Approved Permit |
| EXPLORATORY | DRL - Spudded (Drilling Commenced) |
| GAS STORAGE | GIW - Gas Injection |
| NF PP OIL | GS - Gas Storage |
| NF SECONDARY | LA - Location Abandoned |
| PI OIL | LOC - New Location |
| PP GAS | OPS - Operation Suspended |
| PP GEOTHERML | PA - Plugged Abandoned |
| PP OIL | PGW - Producing Gas Well |
| SECONDARY | POW - Producing Oil Well |
| TERMINATED | RET - Returned APD |
| STATUS | SGW - Shut-in Gas Well |
| Unknown | SOW - Shut-in Oil Well |
| ABANDONED | TA - Temp. Abandoned |
| ACTIVE | TW - Test Well |
| COMBINED | WDW - Water Disposal |
| INACTIVE | WIW - Water Injection Well |
| STORAGE | WSW - Water Supply Well |
| TERMINATED | |
| Sections | |
| Township | |



WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 3/24/2011**API NO. ASSIGNED:** 43007501380000**WELL NAME:** Prickly Pear Unit Fed 9A-18D-12-15**OPERATOR:** BILL BARRETT CORP (N2165)**PHONE NUMBER:** 303 312-8134**CONTACT:** Tracey Fallang**PROPOSED LOCATION:** NENW 17 120S 150E**Permit Tech Review:** **SURFACE:** 0495 FNL 1447 FWL**Engineering Review:** **BOTTOM:** 2639 FSL 0549 FEL**Geology Review:** **COUNTY:** CARBON**LATITUDE:** 39.77962**LONGITUDE:** -110.26397**UTM SURF EASTINGS:** 563031.00**NORTHINGS:** 4403348.00**FIELD NAME:** PRICKLY PEAR**LEASE TYPE:** 1 - Federal**LEASE NUMBER:** UTU73668**PROPOSED PRODUCING FORMATION(S):** WASATCH-MESA VERDE**SURFACE OWNER:** 1 - Federal**COALBED METHANE:** NO**RECEIVED AND/OR REVIEWED:**

- PLAT**
- Bond:** FEDERAL - WYB000040
- Potash**
- Oil Shale 190-5**
- Oil Shale 190-3**
- Oil Shale 190-13**
- Water Permit:** Nine Mile Creek
- RDCC Review:**
- Fee Surface Agreement**
- Intent to Commingle**

Commingle Approved**LOCATION AND SITING:**

- R649-2-3.**
- Unit:** PRICKLY PEAR
- R649-3-2. General**
- R649-3-3. Exception**
- Drilling Unit**
- Board Cause No:** Cause 256-01
- Effective Date:** 12/16/2004
- Siting:** Suspends General Siting
- R649-3-11. Directional Drill**

Comments: Presite Completed**Stipulations:** 4 - Federal Approval - dmason
15 - Directional - dmason



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Prickly Pear Unit Fed 9A-18D-12-15
API Well Number: 43007501380000
Lease Number: UTU73668
Surface Owner: FEDERAL
Approval Date: 3/31/2011

Issued to:

BILL BARRETT CORP, 1099 18th Street Ste 2300, Denver, CO 80202

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 256-01. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>

Reporting Requirements:


All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written in a cursive style.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU73668
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: PRICKLY PEAR
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: Prickly Pear Unit Fed 9A-18D-12-15	
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43007501380000	
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext	9. FIELD and POOL or WILDCAT: PRICKLY PEAR
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0495 FNL 1447 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 17 Township: 12.0S Range: 15.0E Meridian: S		COUNTY: CARBON
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/28/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input checked="" type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
<p>In accordance with Utah Division of Oil, Gas, and Mining's Rule 649-3-22, Completion Into Two or More Pools, BBC is submitting this sundry to request commingling approval for the Wasatch and Mesaverde formations. Gas composition is similar across all formations. The pressure profile across the formations is similar and BBC does not anticipate any cross flow. Production is considered to be from one pool. In the event that allocation by zone or interval is required, BBC would use representative sampling obtained from production logs and allocate on a percentage basis by zone or interval. A letter and affidavit of notice is attached. As per Marvin Hendrickson with the Prickly Pear BLM, federal authority of this action is not necessary.</p>		
		Accepted by the Utah Division of Oil, Gas and Mining Date: 05/04/2011 By: 
NAME (PLEASE PRINT) Brady Riley	PHONE NUMBER 303 312-8115	TITLE Permit Analyst
SIGNATURE N/A	DATE 4/10/2011	



AFFIDAVIT

My name is Vicki L. Wambolt and I am a Landman with Bill Barrett Corporation (BBC). BBC has submitted Sundry Notices to commingle production from the Wasatch and Mesaverde formations in the Prickly Pear Unit Federal 7A-18D-12-15, 8A-18D-12-15 & 9A-18D-12-15 wells drilled from a pad located in the NW of Section 17, Township 12 South, Range 15 East. In compliance with the Utah OGM regulation R649-3-22, I have provided a copy of the Sundry Notices, by certified mail, to the owners as listed below of all contiguous oil and gas leases or drilling units overlying the pool.


State of Utah, acting by and through the School
and Institutional Trust Lands Administration
675 East 500 South, Suite 500
Salt Lake City, UT 84102

Bureau of Land Management
Price Field Office
125 South 600 West
Price, Utah 84501

XTO Energy, Inc.
810 Houston St.
Fort Worth, TX 76102-6298

Date: April 4, 2011

Affiant



Vicki L. Wambolt

1099 18TH STREET
SUITE 2300
DENVER, CO 80202

Apr. 10, 2011



April 4, 2011

Utah Division of Oil, Gas & Mining
1594 W. North Temple, Suite 1210
Salt Lake City, UT 84116

Attention: Dustin Doucet

RE: Sundry Notices
Prickly Pear Unit
NW 17 T12S R15E
Carbon Co., UT

Bill Barrett Corporation has submitted Sundry Notices to commingle production from the Wasatch and Mesaverde Formations in the Prickly Pear Unit Federal 7A-18D-12-15, 8A-18D-12-15 & 9A-18D-12-15 wells drilled from a pad located in the NW of Section 17, Township 12 South, Range 15 East. As required by the Utah OGM regulations R649-3-22, BBC has enclosed copies of the completed Sundry Notices.

Should you require additional information in this regard, please feel free to contact me at 303-312-8513 or vwambolt@billbarrettcorp.com.

BILL BARRETT CORPORATION

A handwritten signature in blue ink, which appears to read 'Vicki L. Wambolt', is written over the typed name.

Vicki L. Wambolt
Landman

Enclosures

1099 18TH STREET
SUITE 2300
DENVER, CO 80202

Apr. 10, 2011



April 4, 2011

Bureau of Land Management
Price Field Office
125 South 600 West
Price, UT 84501

Certified Mail 7010 0290 0003 4153 6654

Attention: Marvin Hendricks

RE: Sundry Notices
Prickly Pear Unit
NW 17 T12S R15E
Carbon Co., UT

Bill Barrett Corporation has submitted Sundry Notices to commingle production from the Wasatch and Mesaverde Formations in the Prickly Pear Unit Federal 7A-18D-12-15, 8A-18D-12-15 & 9A-18D-12-15 wells drilled from a pad located in the NW of Section 17, Township 12 South, Range 15 East. As required by the Utah OGM regulations R649-3-22, BBC has enclosed copies of the completed Sundry Notices.

Should you require additional information in this regard, please feel free to contact me at 303-312-8513 or vwambolt@billbarrettcorp.com.

BILL BARRETT CORPORATION

A handwritten signature in black ink that reads 'Vicki L. Wambolt'.

Vicki L. Wambolt
Landman

Enclosures

1099 18TH STREET
SUITE 2300
DENVER, CO 80202

Apr. 10, 2011



April 4, 2011

State of Utah
School and Institutional Trust Lands Administration
675 East 500 South, Suite 500
Salt Lake City, UT 84102

Certified Mail 7010 0290 0003 4153 6661

Attention: LaVonne Garrison

RE: Sundry Notices
Prickly Pear Unit
NW 17 T12S R15E
Carbon Co., UT

Bill Barrett Corporation has submitted Sundry Notices to commingle production from the Wasatch and Mesaverde Formations in the Prickly Pear Unit Federal 7A-18D-12-15, 8A-18D-12-15 & 9A-18D-12-15 wells drilled from a pad located in the NW of Section 17, Township 12 South, Range 15 East. As required by the Utah OGM regulations R649-3-22, BBC has enclosed copies of the completed Sundry Notices.

Should you require additional information in this regard, please feel free to contact me at 303-312-8513 or vwambolt@billbarrettcorp.com.

BILL BARRETT CORPORATION

A handwritten signature in black ink that reads 'Vicki L. Wambolt'.

Vicki L. Wambolt
Landman

Enclosures

1099 18TH STREET
SUITE 2300
DENVER, CO 80202

Apr. 10, 2011



April 4, 2011

XTO Energy, Inc.
810 Houston St.
Fort Worth, TX 76102-6298

Certified Mail 7010 0290 0003 4153 6678

Attention: Shannon Nichols

RE: Sundry Notices
Prickly Pear Unit
NW 17 T12S R15E
Carbon Co., UT

Bill Barrett Corporation has submitted Sundry Notices to commingle production from the Wasatch and Mesaverde Formations in the Prickly Pear Unit Federal 7A-18D-12-15, 8A-18D-12-15 & 9A-18D-12-15 wells drilled from a pad located in the NW of Section 17, Township 12 South, Range 15 East. As required by the Utah OGM regulations R649-3-22, BBC has enclosed copies of the completed Sundry Notices.

Should you require additional information in this regard, please feel free to contact me at 303-312-8513 or vwambolt@billbarrettcorp.com.

BILL BARRETT CORPORATION

A handwritten signature in black ink that reads 'Vicki L. Wambolt'.

Vicki L. Wambolt
Landman


Enclosures

1099 18TH STREET
SUITE 2300
DENVER, CO 80202

Apr. 10, 2011

Prickly Pear Unit

T12S-R15E



 **Bill Barrett Corporation**

Uinta Basin

West Tavaputs Plateau



-  Abandoned GAS Well
-  Dry hole
-  ENGINEERING WELLS
-  Gas Well
-  Location
-  Plugged and Abandoned
-  Salt Water Disposal
-  Waiting on Completion

By: LH

RECEIVED Apr. 10, 2011

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

COPY

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU73668
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator BILL BARRETT CORPORATION Contact: TRACEY FALLANG E-Mail: tfallang@billbarrettcorp.com		7. If Unit or CA Agreement, Name and No. UTU79487H
3a. Address 1099 18TH STREET SUITE 2300 DENVER, CO 80202		8. Lease Name and Well No. PRICKLY PEAR UNIT FEDERAL 9A-18D-12-15
3b. Phone No. (include area code) Ph: 303.312.8134 Fx: 303.291.0420		9. API Well No. 43-007-50138
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NENW 495FNL 1447FWL <i>Sec 17</i> At proposed prod. zone NESE 2639FSL 549FEL <i>Sec 18</i>		10. Field and Pool, or Exploratory PRICKLY PEAR
14. Distance in miles and direction from nearest town or post office* 45 MILES FROM MYTON UT		11. Sec., T., R., M., or Blk. and Survey or Area Sec 17 T12S R15E Mer SLB SME: BLM
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 2658	16. No. of Acres in Lease 899.77	12. County or Parish CARBON
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 631	19. Proposed Depth 8400 MD 7400 TVD	13. State UT
21. Elevations (Show whether DF, KB, RT, GL, etc.) 7419 GL	22. Approximate date work will start 04/16/2011	17. Spacing Unit dedicated to this well 20.00
		20. BLM/BIA Bond No. on file WYB000040
		23. Estimated duration 25

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature (Electronic Submission)	Name (Printed/Typed) TRACEY FALLANG Ph: 303.312.8134	Date 03/24/2011
Title REGULATORY MANAGER		
Approved by (Signature) <i>Geoff Beyersdorf</i>	Name (Printed/Typed) Geoff Beyersdorf	Date April 26, 2011
Title AFM LANDS & MINERALS		
Office PRICE FIELD OFFICE		

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #105169 verified by the BLM Well Information System
For BILL BARRETT CORPORATION, sent to the Price
Committed to AFMSS for processing by ANITA JONES on 04/01/2011 (11AIJ0359AE)

RECEIVED

MAY 02 2011

DIV. OF OIL, GAS & MINING

CONDITIONS OF APPROVAL ATTACHED

NOTICE OF APPROVAL

** BLM REVISED **



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
PRICE FIELD OFFICE



125 SOUTH 600 WEST PRICE, UT 84501 (435) 636-3600

CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Bill Barrett Corporation Surface Location: NENW-Sec 17-T12S-R15E
Well No: Prickly Pear Unit Federal 9A-18D-12-15 Lease No: UTU-73668
API No: 43-007-50138 Agreement: UTU-79487H

OFFICE NUMBER: (435) 636-3600

OFFICE FAX NUMBER: (435) 636-3657

RECEIVED
MAY 02 2011

A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE **DIV. OF OIL, GAS & MINING**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify NRS)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify NRS)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Petroleum Eng. Technician)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Petroleum Eng. Technician)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

UDOGM

**DRILLING PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DRILLING & PRODUCTION COAs

- While drilling the surface hole with air, a float valve shall be run above the bit, per Onshore Order #2 Part III.E Special Drilling Operations.
- A cement bond log (CBL) shall be run to determine the top of cement behind the production casing, and a field copy sent to the Price Field Office.
- A complete set of angular deviation and directional surveys for this directional well will be submitted to the Price Field Office petroleum engineer within 30 days of completing the well.
- A copy of the approved Application for Permit to Drill (APD) for this well shall be on location at all times once drilling operations have commenced.

VARIANCES GRANTED

- BBC's request for variance to not use de-duster equipment (Onshore Order #2 Part III.E Special Drilling Operations) is granted, unless the air/mist system is not used.
- BBC's request for variance to use an electronic flow meter for gas measurement (Onshore Order #5 Measurement of Gas) is granted as long as it meets or exceeds the requirements of Utah NTL 2007-1 regarding the use of Electronic Flow Computers.
- BBC's request for variance from Onshore Order #5 Part III.C.3 Gas Measurement by Orifice Meter to use a flow conditioner on this well instead of straightening vanes is approved with the following conditions:
 1. Flow conditioners must be installed in accordance with the manufacturer's specifications.
 2. The make, model, and location of flow conditioner must be clearly identified and available to BLM on-site at all times.
 3. This is a provisional approval that is subject to change pending final review and analysis by BLM. If BLM determines that this flow conditioner cannot meet or exceed the minimum standards required by Onshore Order #5, you will be required to retrofit the installation to comply with BLM requirements, or replace the installation with one that complies with AGA Report Number 3, 1985. The time frame for compliance will be specified by the Price Field Office.

STANDARD OPERATING REQUIREMENTS

- The requirements included in Onshore Order #2 Drilling Operations shall be followed.
- The Price Field Office petroleum engineer will be notified 24 hours verbally prior to spudding the well.
- Notify the BLM petroleum engineering technician at least 24 hours in advance of casing cementing operations, BOPE tests and casing pressure or mud weight equivalency tests.
- Should H₂S be encountered in concentrations greater than 100 ppm, the requirements of Onshore Order #6 Hydrogen Sulfide Operations shall be followed.
- Any deviation from the permitted APD's proposed drilling program shall have prior approval from the petroleum engineer. Changes may be requested verbally (to be followed by a written sundry sent to this office), or submitted by written sundry if time warrants.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed. The closing unit controls shall remain unobstructed and readily accessible at all times, and choke manifolds shall be located outside of the rig substructure.
- BOP testing shall be conducted within 24 hours of drilling out from under the surface casing, and weekly thereafter as specified in Onshore Order #2.
- All BOPE components shall be inspected daily, and the inspections recorded in the daily drilling report. Components shall be operated and tested, as required by Onshore Order #2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder, and not by the rig pumps. Test results shall be reported in the driller's log.
- All casing strings below the conductor pipe shall be pressure tested to .22 psi/foot or 1500 psi (whichever is greater), but not to exceed 70% of the internal yield pressure.
- No aggressive/fresh hard-banded drill pipe shall be used in the casing design. The proposed use of non-API standard casing must be approved in advance by the petroleum engineer.
- During drilling operations, daily drilling reports shall be submitted by sundry on a weekly basis to the Price Field Office. Within 30 days of finishing drilling and completion operations, a chronological daily operations history shall be submitted by sundry to this office.
- A copy of all logs run on this well shall be submitted digitally (in PDF or TIFF format) to the Price Field Office.
- The venting or flaring of gas while initially testing the well shall be done in accordance with the requirements specified in Notice to Lessees #4A, and shall not exceed a period of 30 days or the production of 50 MMCF of gas, whichever occurs first. Additional time needed to vent or flare gas during production operations requires prior approval from the Price Field Office.
- Should this well be successfully completed as a producing well, the Price Field Office must be notified within 5 business days following the date the well has first sales.

STANDARD OPERATING REQUIREMENTS (cont.)

- Proposed production operations that involve: 1) the commingling of production from wells located on-lease or off-lease, 2) off-lease measurement, or 3) off-lease storage shall have prior written approval from the Price Field Office.
- Operators shall meet the requirements listed in Onshore Order #4 Measurement of Oil and Onshore Order #5 Measurement of Gas. New oil and gas meters shall be calibrated prior to initial product sales. The operator (or its contractors) is responsible for providing the date and time of the initial meter calibration (and all future meter proving schedules) to the petroleum engineering technician. Copies of all meter calibration reports that are performed shall be submitted to the Price Field Office.
- In accordance with 43 CFR 3162.4-3, this well's production data shall be reported on the "Monthly Report of Operations" starting with the month in which operations commence and continue each month until the well is plugged and abandoned.
- The operator is responsible for submitting the information required in 43 CFR 3162.4-1 Well Records and Reports, including BLM Form 3160-4, Well Completion and Recompletion Report and Log which must be submitted to the Price Field Office within 30 days of completing the well.
- Onshore Order #7 authorizes the disposal of water produced from this well in the reserve pit for a period of 90 days after the date of initial production. A permanent disposal method must be submitted and approved by this office, and in operation prior to the end of this 90-day period.
- The requirements of Onshore Order #3 Site Security shall be implemented, and include (as applicable): 1) all lines entering and leaving hydrocarbon storage tanks shall be effectively sealed and seal records maintained, 2) no by-passes are allowed to be constructed around gas meters, 3) a site facility diagram shall be submitted to the Price Field Office within 60 days following construction of the facilities.
- Additional construction that is proposed, or the proposed alteration of existing facilities (including roads, gathering lines, batteries, etc.), which will result in the disturbance of new ground, requires prior approval of the Price Field Office natural resource specialist.
- This well and its associated facilities shall have identifying signs on location in accordance with 43 CFR 3162.6 requirements.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the Price Field Office natural resource specialist.
- The Price Field Office petroleum engineer shall be notified 24 hours in advance of the plugging of the well (unless the plugging is to take place immediately upon receipt of oral approval), so that a technician may have sufficient time to schedule and witness the plugging operations.
- If operations are to be suspended on a well for more than 30 days, prior approval of the Price Field Office shall be obtained, and notification also given before operations resume.

**SURFACE USE
CONDITIONS OF APPROVAL**

Project Name: BBC Prickly Pear NW 17 Pad

Operator: Bill Barrett Corporation

List of Wells:

Name	Number	Section	TWP/RNG
Prickly Pear Unit Federal	9A-18D-12-15	17	12S/15E
Prickly Pear Unit Federal	8A-18D-12-15		
Prickly Pear Unit Federal	7A-18D-12-15		

I To be followed as Conditions of Approval:

The following attachments from the Record of Decision West Tavaputs Plateau Natural Gas Full Field Development Plan:

Attachment 2	Conditions of Approval and Stipulations
Attachment 3	Green River District Reclamation Guidelines
Attachment 4	Programmatic Agreement
Attachment 5	Special Protection Measures for Wildlife
Attachment 6	Agency Wildlife Mitigation Plan
Attachment 7	Long-Term Monitoring Plan for Water Resources
Attachment 8	Mitigation Compliance and Monitoring Plan

II Site Specific Conditions of Approval

1. A pre-construction field meeting may be conducted prior to beginning any dirt work approved under this APD. The operator shall contact Don Stephens with the Price BLM Field Office @ 435-636-3608 at least 48-hours prior to beginning operations so that the meeting can be scheduled. The operator is responsible for having all contractors present (dirt contractors, drilling contractor, pipeline contractor, project oversight personnel, etc.) including the overall field operations superintendent, and for providing all contractors copies of the approved APD(s), project map and BLM Conditions of Approval pertinent to the work that each will be doing.
2. BBC shall mulch trees as appropriate to increase the potential for reclamation success in planned surface disturbance areas. Mulching will be used to avoid the accumulation of large debris piles when clearing trees in these areas. Mulch shall not exceed 4 inches in depth when spread out for interim or final reclamation.
3. As many trees as possible shall be left to provide a buffer between the well pad and the canyon rim for visual screening.
4. The cuttings trench shall be lined.
5. The cuttings shall not be removed from the location without prior approval of the Authorized Officer.

6. The operator shall on an annual basis report to the BLM the acre feet of water used for the project with a total for each type of source. This report shall contain the information found under monitoring on page 53 of attachment 9 (Biological Opinion) of the WTP ROD and shall be reported to BLM by September 15, of each year.
7. When water is pumped directly from Nine Mile Creek or perennial drainages, the following measures shall be applied to reduce or eliminate direct impacts to habitat for the Colorado River fish species. Where directed by the BLM, the operator will construct erosion control devices (e.g., riprap, bales, and heavy vegetation) at culvert outlets. All construction activities shall be performed to retain natural water flows.
8. Contact Don Stephens, Natural Resource Specialist, (435) 636-3608, Bureau of Land Management, Price Field Office, if there are any questions concerning these surface use COAs.

III Standard Conditions of Approval

A. General

1. If any cultural values [sites, artifacts, human remains] are observed during operation of this lease/permit/right-of-way, they will be left intact and the Price Field Manager notified. The authorized officer will conduct an evaluation of the cultural values to establish appropriate mitigation, salvage or treatment. The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized BLM officer (AO).

B. Construction

1. Remove all available topsoil from constructed well locations including areas of cut and fill, and stockpile at the site. Topsoil will also be salvaged for use in reclamation on all other areas of surface disturbance (roads, pipelines, etc.). Clearly segregate topsoil from excess spoil material.
2. During construction, emissions of particulate matter from well pad and road construction would be minimized by application of water or other non-saline dust suppressants with at least 50 percent control efficiency. Dust inhibitors (surfacing materials, non-saline dust suppressants, and water) will be used as necessary on unpaved roads that present a fugitive dust problem. The use of chemical dust suppressants on public surface will require prior approval from the BLM Authorized Officer.
3. The operator shall submit a Sundry Notice (Form 3160-5) to BLM for approval prior to construction of any new surface disturbing activities that are not specifically addressed in the approved APD.

C. Operations/Maintenance

1. In accordance with OSHA requirements, a file will be maintained onsite containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds and/or substances which are used in the course of construction, drilling, completion and production operations.

D. Dry Hole/Reclamation

1. Phased reclamation plans will be submitted to BLM for approval prior to individual POD facility abandonment via a Notice of Intent (NOI) Sundry Notice.
2. BLM will not release the performance bond until all disturbed areas associated with the APD/POD have been successfully revegetated (evaluation will be made after the second complete growing season) and has met all other reclamation goals of the surface owner and surface management agency.
3. A Notice of Intent to Abandon and a Subsequent Report of Abandonment must be submitted for abandonment approval.
4. For performance bond release approval, a Final Abandonment Notice (with a surface owner release letter on split-estate) must be submitted prior to a final abandonment evaluation by BLM.

E. Producing Well

1. An interim reclamation plan shall be submitted to BLM within 90 days of APD approval.
2. Upgrade and maintain access roads and drainage control (e.g., culverts, drainage dips, ditching, crowning, surfacing, etc.) as necessary and as directed by the BLM Authorized Officer to prevent soil erosion and accommodate safe, environmentally-sound access.
3. Prior to construction of production facilities not specifically addressed in the APD, the operator shall submit a Sundry Notice to the BLM Authorized Officer for approval.

F. Roads and Pipelines

1. Roads constructed on BLM lands shall be constructed to allow for drainage and erosion control. The operator is responsible for maintenance of all roads authorized through the lease or right-of-way. Construction and maintenance shall comply with Class III Road Standards with a 16-ft wide graveled travel surface as described in BLM Manual Section 9113, and the BLM Gold Book standards, except as modified by BLM. Maintenance may include but is not limited to grading, applying gravel, snow removal, ditch cleaning, and headcut restoration/prevention.
2. The operator may be required to provide an inspector under the direction of a registered professional engineer (PE) at all times during road construction. A PE shall certify (statement with PE stamp) that the road was constructed to the required Bureau of Land Management (BLM) road standards.
3. Erosion-control structures such as water bars, diversion channels, and terraces will be constructed to divert water and reduce soil erosion on the disturbed area. Road ditch turnouts shall be equipped with energy dissipaters as needed to avoid erosion. Where roads interrupt overland sheet-flow and convert this runoff to channel flow, ditch turnouts shall be designed to reconvert channel flow to sheet flow. As necessary cut banks, road drainages, and road crossings shall be armored or otherwise engineered to prevent headcutting.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU73668
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: PRICKLY PEAR
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: PRICKLY PEAR UF 9A-18D-12-15	
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43007501380000	
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext	9. FIELD and POOL or WILDCAT: PRICKLY PEAR
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0495 FNL 1447 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 17 Township: 12.0S Range: 15.0E Meridian: S		COUNTY: CARBON
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 5/16/2011 <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	
<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
<p style="font-size: 1.2em; margin: 0;">Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY</p>		
NAME (PLEASE PRINT) Brady Riley	PHONE NUMBER 303 312-8115	TITLE Permit Analyst
SIGNATURE N/A	DATE 5/17/2011	

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: BILL BARRETT CORPORATION

Well Name: PRICKLY PEAR U FED 9A-18D-12-15

Api No: 43-007-50138 Lease Type FEDERAL

Section 17 Township 12S Range 15E County CARBON

Drilling Contractor TRIPLE A DRILLING RIG #

SPUDDED:

Date 05/16/2011

Time

How DRY

Drilling will Commence:

Reported by JODY SOUTH

Telephone # (303) 312-8174

Date 05/17/2011 Signed CHD

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: BILL BARRETT CORPORATION

Well Name: PRICKLY PEAR U FED 9A-18D-12-15

Api No: 43-007-50138 Lease Type FEDERAL

Section 17 Township 12S Range 15E County CARBON

Drilling Contractor TRIPLE A DRILLING RIG #

SPUDDED:

Date 05/16/2011

Time

How DRY

Drilling will Commence:

Reported by JODY SOUTH

Telephone # (303) 312-8174

Date 05/17/2011 Signed CHD

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: BILL BARRETT CORPORATION

Well Name: PRICKLY PEAR U FED 9A-18D-12-15

Api No: 43-007-50138 Lease Type FEDERAL

Section 17 Township 12S Range 15E County CARBON

Drilling Contractor TRIPLE A DRILLING RIG #

SPUDDED:

Date 05/16/2011

Time

How DRY

Drilling will Commence:

Reported by JODY SOUTH

Telephone # (303) 312-8174

Date 05/17/2011 Signed CHD

Carol Daniels - Prickly Pear 9A-18D surface

T125 RISES-17 43-007-50138

From: Jody South
To: Carol Daniels , Dennis Ingram , Wiler
Date: 5/23/2011 8:19 AM
Subject: Prickly Pear 9A-18D surface
CC: Alan Walker , Brady Riley , Doug Sproul , Marvin Hendricks , Randy Bywater , Tracey Fallang

This morning Bill Barrett Corp. will use the Pro Petro No. 8 air rig to spud surface on the Prickly Pear 9A-18D-12-15, API# 43-007-50138, then run casing and cement casing tomorrow morning at approx. 3:00am.

Jody South

RECEIVED

MAY 23 2011

DIV. OF OIL, GAS & MINING

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: BILL BARRETT CORPORATION

Well Name: PRICKLY PEAR U FED 9A-18D-12-15

Api No: 43-007-50138 Lease Type FEDERAL

Section 17 Township 12S Range 15E County CARBON

Drilling Contractor TRIPLE A DRILLING RIG #

SPUDDED:

Date 05/16/2011

Time

How DRY

Drilling will Commence:

Reported by JODY SOUTH

Telephone # (303) 312-8174

Date 05/17/2011 Signed CHD

Carol Daniels - Prickly Pear 9A-18D surface

T125 RISES-17 43-007-50138

From: Jody South
To: Carol Daniels , Dennis Ingram , Wiler
Date: 5/23/2011 8:19 AM
Subject: Prickly Pear 9A-18D surface
CC: Alan Walker , Brady Riley , Doug Sproul , Marvin Hendricks , Randy Bywater , Tracey Fallang

This morning Bill Barrett Corp. will use the Pro Petro No. 8 air rig to spud surface on the Prickly Pear 9A-18D-12-15, API# 43-007-50138, then run casing and cement casing tomorrow morning at approx. 3:00am.

Jody South

RECEIVED

MAY 23 2011

DIV. OF OIL, GAS & MINING

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: BILL BARRETT CORPORATION

Well Name: PRICKLY PEAR U FED 9A-18D-12-15

Api No: 43-007-50138 Lease Type FEDERAL

Section 17 Township 12S Range 15E County CARBON

Drilling Contractor TRIPLE A DRILLING RIG #

SPUDDED:

Date 05/16/2011

Time

How DRY

Drilling will Commence:

Reported by JODY SOUTH

Telephone # (303) 312-8174

Date 05/17/2011 Signed CHD

Carol Daniels - Prickly Pear 9A-18D surface

T125 RISES-17 43-007-50138

From: Jody South
To: Carol Daniels , Dennis Ingram , Wiler
Date: 5/23/2011 8:19 AM
Subject: Prickly Pear 9A-18D surface
CC: Alan Walker , Brady Riley , Doug Sproul , Marvin Hendricks , Randy Bywater , Tracey Fallang

This morning Bill Barrett Corp. will use the Pro Petro No. 8 air rig to spud surface on the Prickly Pear 9A-18D-12-15, API# 43-007-50138, then run casing and cement casing tomorrow morning at approx. 3:00am.

Jody South

RECEIVED

MAY 23 2011

DIV. OF OIL, GAS & MINING

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: BILL BARRETT CORPORATION

Well Name: PRICKLY PEAR U FED 9A-18D-12-15

Api No: 43-007-50138 Lease Type FEDERAL

Section 17 Township 12S Range 15E County CARBON

Drilling Contractor TRIPLE A DRILLING RIG #

SPUDDED:

Date 05/16/2011

Time

How DRY

Drilling will Commence:

Reported by JODY SOUTH

Telephone # (303) 312-8174

Date 05/17/2011 Signed CHD

Carol Daniels - Prickly Pear 9A-18D surface

T125 RISES-17 43-007-50138

From: Jody South
To: Carol Daniels , Dennis Ingram , Wiler
Date: 5/23/2011 8:19 AM
Subject: Prickly Pear 9A-18D surface
CC: Alan Walker , Brady Riley , Doug Sproul , Marvin Hendricks , Randy Bywater , Tracey Fallang

This morning Bill Barrett Corp. will use the Pro Petro No. 8 air rig to spud surface on the Prickly Pear 9A-18D-12-15, API# 43-007-50138, then run casing and cement casing tomorrow morning at approx. 3:00am.

Jody South

RECEIVED

MAY 23 2011

DIV. OF OIL, GAS & MINING

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: BILL BARRETT CORPORATION

Well Name: PRICKLY PEAR U FED 9A-18D-12-15

Api No: 43-007-50138 Lease Type FEDERAL

Section 17 Township 12S Range 15E County CARBON

Drilling Contractor TRIPLE A DRILLING RIG #

SPUDDED:

Date 05/16/2011

Time

How DRY

Drilling will Commence:

Reported by JODY SOUTH

Telephone # (303) 312-8174

Date 05/17/2011 Signed CHD

Carol Daniels - Prickly Pear 9A-18D surface

T125 RISES-17 43-007-50138

From: Jody South
To: Carol Daniels , Dennis Ingram , Wiler
Date: 5/23/2011 8:19 AM
Subject: Prickly Pear 9A-18D surface
CC: Alan Walker , Brady Riley , Doug Sproul , Marvin Hendricks , Randy Bywater , Tracey Fallang

This morning Bill Barrett Corp. will use the Pro Petro No. 8 air rig to spud surface on the Prickly Pear 9A-18D-12-15, API# 43-007-50138, then run casing and cement casing tomorrow morning at approx. 3:00am.

Jody South

RECEIVED

MAY 23 2011

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Bill Barrett Corporation
Address: 1099 18th Street, Suite 2300
city Denver
state CO zip 80202

Operator Account Number: N 2165
Phone Number: (303) 312-8115

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4300750138	Prickly Pear Unit Federal 9A-18D-12-15		NENW	17	12S	15E	Carbon
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>AB</i>	<i>99999</i>	<i>14794</i>	<i>5/16/2011</i>		<i>5/26/11</i>		
Comments: Spudding Operation was conducted by Triple A Drilling <i>WSMVD BHL = Section 18 NESE</i>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4300750137	Prickly Pear Unit Federal 8A-18D-12-15		NENW	17	12S	15E	Carbon
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>AB</i>	<i>99999</i>	<i>14794</i>	<i>5/17/2011</i>		<i>5/26/11</i>		
Comments: Spudding Operation was conducted by Triple A Drilling <i>WSMVD BHL Section 18 SENE</i>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED
MAY 18 2011

Brady Riley

Name (Please Print)
Brady Riley

Signature
Permit Analyst

Title

5/17/2011

Date

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU73668
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: PRICKLY PEAR
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: PRICKLY PEAR UF 9A-18D-12-15	
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43007501380000	
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext	9. FIELD and POOL or WILDCAT: PRICKLY PEAR
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0495 FNL 1447 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 17 Township: 12.0S Range: 15.0E Meridian: S		COUNTY: CARBON
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/25/2011 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	
	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text" value="production facilities"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
This sundry is being submitted to further clarify testing procedures discussed and verbally approved by the BLM as well as final equipment installations for the Prickly Pear NW 17 pad. See attached for details and map.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Brady Riley	PHONE NUMBER 303 312-8115	TITLE Permit Analyst
SIGNATURE N/A	DATE 7/26/2011	

General Well Testing

Initial testing of wells would occur within 15 days of first sales and would be a 1-3 day test to get a baseline for allocation. After the initial test is performed, testing would occur within 90 days thereafter, testing each well for approximately 3 days and rotating through the wells without any downtime between tests.

As both Prickly Pear and Peter's Point have participating areas (PA) and wells drilled from each pad could include both PA and non-PA wells, specific procedures are implemented for these situations. PA and non-PA will always be measured separately and production would not be combined together within the same tanks. All wells drilled are within units. These procedures are as follows:

- 1) Isolate the PA test tank(s);
- 2) Transfer any remaining liquids from the test tank(s) to the PA production tank(s);
- 3) Strap the starting fluid levels in the test tank(s);
- 4) Note date and time of beginning test, document and record in eVIN;
- 5) Flow test well into test tank(s) for pre-determined period, not to be less than a 24 hour period;
- 6) Isolate the test tank(s), divert the test well's production to the in PA production tank(s);
- 7) Strap the ending fluid levels in the test tank(s);
- 8) Record and document the length of test time, amount of oil produced, amount of water produced and amount of gas produced (through wellhead meter) for the test period into eVIN;
- 9) Procedures for non-PA would be same steps as 1-8.

Details specific to the **Prickly Pear S2NE 21 pad** are as follows:

Well Name Prickly Pear Unit Fed	API	Drill Phase ¹	Lease UTU-	PA Boundary	Facilities (S2NE 21 pad)
5A-22D-12-15	4300750054	1	11604	In	1) All wells proposed on this pad are within the PA; 2) Liquids trucked to a central tank battery (CTB) on the existing Prickly Pear 3-22 pad/CTB location. 3) One 12" inch buried gas line to the main tie-in was laid (adjacent to the existing line). 4) Up to five low-profile 300 bbl tank may be located on the pad and up to 13 625-bbl and 400-bbl tanks would be located on the CTB.
4A-22D-12-15	4300750053	1	11604	In	
1-21D-12-15	4300750050	1	73670	In	
8A-21D-12-15	4300750058	1	73670	In	
2A-21D-12-15	4300750052	1	73670	In	
2-21D-12-15	4300750051	1	73670	In	
7A-21D-12-15	4300750056	1	73670	In	
7-21D-12-15	4300750055	1	73670	In	
8-21D-12-15	4300750057	1	73670	In	
5A-22D-12-15	4300750054	1	11604	In	

¹Drill Phase 2 indicates that well(s) not initially planned to be drilled during the first phase of drilling on the pad.

Details specific to the **Prickly Pear NW 17 pad** are as follows:

Well Name Prickly Pear Unit Fed	API	Drill Phase ¹	Lease UTU-	PA Boundary	Facilities (NW 17 pad)
7A-17D-12-15	4300750086	1	73006	In	<p>1) All wells proposed on this pad are within the PA; 2) Liquids will be piped into a CTB on the SE 8 CTB, SE 7 CTB and Then piped on to the existing Prickly Pear 4-18 pad/CTB location. Three buried liquids lines were laid from the pad to the 4-18 CTB (1-2" test line; 1-2" out of PA line; 1-6" in PA line). PA liquids from this pad would be combined with PA production from the existing 4-18 pad wells and other future pad production and same process for non-PA liquids (combined separately from PA wells). 3) One 12 inch buried gas line to the main tie-in was laid. 4) Up to ten 625-bbl and four 400-bbl tanks would be located on the 4-18 CTB. One 300 bbl low profile tank would be located on the SE 8 CTB. Up to ten 300 bbl low profile tanks on the SE 7 CTB. One low-profile 300 bbl tank would be located on the well pad.</p>
6A-17D-12-15	4300750085	1	73668	In	
6-17D-12-15	4300750084	1	73668	In	
3-17D-12-15	4300750079	1	73668	In	
3A-17D-12-15	4300750080	1	73668	In	
12A-17D-12-15	4300750087	1	73668	In	
5A-17D-12-15	4300750083	1	73668	In	
4-17D-12-15	4300750081	1	73668	In	
4A-17D-12-15	4300750082	1	73668	In	
7A-18D-12-15	4300750136	1	73668	In	
8A-18D-12-15	4300750137	1	73668	In	
9A-18D-12-15	4300750138	1	73668	In	

²Drill Phase 2 indicates that well(s) not initially planned to be drilled during the first phase of drilling on the pad.

Details specific to the **Prickly Pear SE 8 pad** are as follows:

Well Name Prickly Pear Unit Fed	API	Drill Phase ¹	Lease UTU-	PA Boundary	Facilities (SE 8 pad)
2-17D-12-15	4300750061	1	73006	Out	1) Wells proposed on this pad are a combination of PA and non-PA wells; 2) Liquids will be piped into a CTB on this pad and then piped on to the existing SE 7 then on to the Prickly Pear 4-18 pad/CTB location. Two buried liquids lines were laid from the pad to the 4-18 CTB, one 6 inch In-PA and one 2 inch non-PA. PA liquids from this pad would be combined with PA production from the existing 4-18 pad wells and other future pad production and same process for non-PA liquids (combined separately from PA wells). 3) One 12 inch buried gas line to the main tie-in was laid. 4) Up to ten 625-bbl and four 400-bbl tanks would be located on the 4-18 CTB. One 300 bbl low profile tank would be located on this pad CTB with up to ten 300 bbl low profile tanks on the SE 7 CTB.
2A-17D-12-15	4300750147	1	73006	Out	
1A-17D-12-15	4300750062	1	73006	Out	
15-8D-12-15	4300750060	1	73006	In	
15A-8D-12-15	4300750141	1	73006	In	
16-8D-12-15	4300750059	1	73006	In	
16A-8D-12-15	4300750140	1	73006	In	
10-8D-12-15	4300750145	1	73006	In	
9-8D-12-15	4300750146	1	73006	In	
12-9D-12-15	4300750144	1	73006	In	
13A-9D-12-15	4300750142	1	73006	In	
13-9D-12-15	4300750143	1	73006	In	

¹Drill Phase 2 indicates that well(s) not initially planned to be drilled during the first phase of drilling on the pad.

For any questions you may have, please contact me at 303-312-8115.

Prickly Pear



12S/15E

12S/14E

13S/15E

14E

Legend

-  CTB
-  PAD
-  Access Roads
-  Pipeline
-  GAS
-  Drilling
-  Prickly Pear Fed Unit
-  Approved PA
-  Lease Boundaries



Bill Barrett Corporation

S2NE 21, NW 17 and SE 8 Pads
 Sections 8, 17, 21, T12S R15E
 Carbon County, Utah

Jul. 26, 2011

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU73668
SUNDRY NOTICES AND REPORTS ON WELLS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		7. UNIT or CA AGREEMENT NAME: PRICKLY PEAR
1. TYPE OF WELL Gas Well		8. WELL NAME and NUMBER: PRICKLY PEAR UF 9A-18D-12-15
2. NAME OF OPERATOR: BILL BARRETT CORP		9. API NUMBER: 43007501380000
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext	9. FIELD and POOL or WILDCAT: PRICKLY PEAR
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0495 FNL 1447 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 17 Township: 12.0S Range: 15.0E Meridian: S		COUNTY: CARBON
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 7/1/2011	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER
		OTHER: <input type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
No July 2011 Monthly Drilling Activity to report.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Brady Riley	PHONE NUMBER 303 312-8115	TITLE Permit Analyst
SIGNATURE N/A		DATE 8/4/2011

*T12S R15E S-17 43-007-50138
Prickly Pear UF 9A-18D-12-15*

From: Pat313 <pat313@billbarrettcorp.com>
To: "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "mhendric@blm.gov" <mhe...
Date: 9/7/2011 12:44 PM
Subject: PAT # 313 NOTICE

BILL BARRETT CO.
PATTERSON #313
303-353-5394 OR 970-309-0755

WE'RE APPROX. 24 HRS FROM BOP TESTING & 30 HRS. FROM SPUDDING THE PPF #
9A-18D-12-15 WELL WITH PATTERSON RIG # 313.
API # 43-007-50138.
ANY QUESTIONS OR CONCERNS E-MAIL OR CALL ME AT ABOVE PHONE #'S.

THANKS / ROBERT

RECEIVED
SEP 07 2011
DIV. OF OIL, GAS & MINING

*T1251915E S-17 43-007-50138
Prickly Pear UF 9A-18D-12-15*

From: Pat313 <pat313@billbarrettcorp.com>
To: "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "mhendric@blm.gov" <mhe...
Date: 9/13/2011 9:58 PM
Subject: PAT # 313 NOTICE

BILL BARRETT CO.
PATTERSON #313
303-353-5394 OR 970-309-0755

WE'RE APPROX. 24 HRS. FROM RUNNING CASING & 30 HRS FROM CEMENTING THE PPF #
9A-18D-12-15
API # 43-007-50138
WITH PATTERSON RIG # 313 , ANY QUESTIONS OR CONCERNS E-MAIL OR CALL ME AT ABOVE
PHONE #'S.

THANKS / ROBERT

RECEIVED

SEP 13 2011

DIV. OF OIL, GAS & MINING


Prickly Pear Fed. #9A-18D-12-15 9/8/2011 09:00 - 9/9/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
09:00	3.00	12:00	1	RIGUP & TEARDOWN	PREP RIG FOR SKID - SKID & CENTER & LEVEL SUB	
12:00	2.00	14:00	14	NIPPLE UP B.O.P	NIPPLE UP BOP & FLOW LINE & CHOKE LINE	
14:00	4.00	18:00	15	TEST B.O.P	TEST BOP EQUIPMENT W/ B&C QUICK TESTS VIRGIL ALLRED - UPPER TOP DRIVE VALVE & I BOP - DART & FLOOR VALVE - BLIND & PIPE RAMS - HCR & OUTSIDE KILL LINE VALVES- CHOKE LINE & CHECK VALVE - INSIDE & OUTSIDE MANIFOLD - TO 5000 PSI FOR 10 MIN - ANNULAR TO 1500 PSI FOR 10 MIN - SURFACE CASING TO 1500 PSI FOR 30 MIN - MANUAL & SUPER CHOKES FOR 500 PSI FOR 5 MIN - GOOD TEST	
18:00	0.50	18:30	21	OPEN	INSTALL WEAR RING	
18:30	0.50	19:00	20	DIRECTIONAL WORK	MAKE UP GYRO TOOLS & ORIENTATE TOOLS	
19:00	0.50	19:30	6	TRIPS	TRIP INTO HOLE	
19:30	2.50	22:00	22	OPEN	DRLG CEMENT - FLOAT @ 979' & SHOE @ 1024'	
22:00	0.50	22:30	10	DEVIATION SURVEY	RUN SURVEY & ORIENTATE	
22:30	0.50	23:00	2	DRILL ACTUAL	GYRO DRILLING	
23:00	0.50	23:30	10	DEVIATION SURVEY	RUN SURVEY & ORIENTATE	
23:30	1.50	01:00	2	DRILL ACTUAL	GYRO DRILLING	
01:00	0.50	01:30	10	DEVIATION SURVEY	RUN SURVEY & ORIENTATE	
01:30	0.50	02:00	2	DRILL ACTUAL	GYRO DRILLING	
02:00	0.50	02:30	10	DEVIATION SURVEY	RUN SURVEY & ORIENTATE	
02:30	1.00	03:30	2	DRILL ACTUAL	GYRO DRILLING	
03:30	0.50	04:00	10	DEVIATION SURVEY	RUN SURVEY & ORIENTATE	
04:00	1.00	05:00	8	REPAIR RIG	CHANGE OUT SAVER SUB - DRILLER CROSSED THREADED SUB	
05:00	1.00	06:00	2	DRILL ACTUAL	GYRO DRILLING	

Prickly Pear Fed. #9A-18D-12-15 9/9/2011 06:00 - 9/10/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	1.00	07:00	6	TRIPS	TRIP OUT & INSPECT BIT & MOTOR - OK - WELL STATIC - FUNCTION BLIND & PIPE RAMS	
07:00	0.50	07:30	6	TRIPS	TRIP INTO HOLE	
07:30	0.50	08:00	10	DEVIATION SURVEY	GYRO SURVEY & ORIENTATE TOOLS	
08:00	0.50	08:30	2	DRILL ACTUAL	GYRO DRILLING HOLE	
08:30	0.50	09:00	10	DEVIATION SURVEY	GYRO SURVEY & ORIENTATING TOOLS	
09:00	1.50	10:30	2	DRILL ACTUAL	GYRO DRILLING HOLE	
10:30	1.00	11:30	10	DEVIATION SURVEY	SURVEY & ORIENTATE TOOLS	
11:30	1.00	12:30	2	DRILL ACTUAL	GYRO DRILLING HOLE	
12:30	0.50	13:00	10	DEVIATION SURVEY	SURVEY & ORIENTATE TOOLS	
13:00	1.50	14:30	2	DRILL ACTUAL	GYRO DRILLING HOLE	
14:30	0.50	15:00	10	DEVIATION SURVEY	SURVEY & ORIENTATE TOOLS	
15:00	1.00	16:00	6	TRIPS	TRIP OUT & LAY DOWN GYRO TOOLS -FUNCTION BLIND & PIPE RAMS - WELL STATIC	
16:00	0.50	16:30	20	DIRECTIONAL WORK	PICKUP NEW BIT & SHAREWELL TOOLS & ORIENTATE TOOLS	
16:30	1.00	17:30	6	TRIPS	TRIP INTO HOLE	
17:30	12.50	06:00	2	DRILL ACTUAL	DRILLING 8 3/4" HOLE	

Prickly Pear Fed. #9A-18D-12-15 9/10/2011 06:00 - 9/11/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	0.50	06:30	2	DRILL ACTUAL	DRILLING 8 3/4" HOLE	
06:30	0.50	07:00	5	COND MUD & CIRC	CIRC & COND. HOLE	
07:00	4.00	11:00	6	TRIPS	WIPER TRIP TO SHOE - BACK REAM FROM 3677' TO 1015'	
11:00	1.00	12:00	6	TRIPS	TRIP INTO HOLE - CLEAN TRIP IN	
12:00	4.50	16:30	2	DRILL ACTUAL	DRILLING 8 3/4" HOLE	
16:30	0.50	17:00	7	LUBRICATE RIG	SERVICE RIG & TOP DRIVE	



Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
17:00	12.00	05:00	2	DRILL ACTUAL	DRILLING 8 3/4" HOLE	
05:00	1.00	06:00	6	TRIPS	WIPER TRIP HOLE - BACK REAM OUT OF HOLE	

Prickly Pear Fed. #9A-18D-12-15 9/11/2011 06:00 - 9/12/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	3.50	09:30	6	TRIPS	WIPER TRIP 27 STANDS FROM 6053' TO 3392' - BACKREAM OUT OF HOLE	
09:30	1.00	10:30	6	TRIPS	TRIP INTO HOLE - CLEAN TRIP	
10:30	1.50	12:00	5	COND MUD & CIRC	CIRC & TROUBLE SHOOT ON SURFACE MWD FAILURE - WAS WORKING FINE WHEN WE LEFT BOTTOM FOR WIPER TRIP	
12:00	3.00	15:00	6	TRIPS	TRIP OUT DUE TO MWD FAILURE -	
15:00	1.00	16:00	20	DIRECTIONAL WORK	FUNCTION BLIND & PIPE RAMS - WELL STATIC - INSPECT BATTERIES & GAP SUB - BAD GAP SUB - MOTOR & BIT OK - CHECK NEW GAP SUB - OK	
16:00	2.50	18:30	6	TRIPS	TRIP INTO HOLE	
18:30	6.00	00:30	2	DRILL ACTUAL	DRILLING 8 3/4" HOLE	
00:30	0.50	01:00	7	LUBRICATE RIG	SERVICE RIG & TOP DRIVE	
01:00	5.00	06:00	2	DRILL ACTUAL	DRILLING 8 3/4" HOLE	

Prickly Pear Fed. #9A-18D-12-15 9/12/2011 06:00 - 9/13/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	7.50	13:30	2	DRILL ACTUAL	DRILLING 8 3/4" HOLE	
13:30	1.00	14:30	5	COND MUD & CIRC	CIRC & COND. HOLE	
14:30	5.00	19:30	6	TRIPS	BACK REAM OUT OF HOLE FOR BIT	
19:30	0.50	20:00	20	DIRECTIONAL WORK	FUNCTION BLIND & PIPE RAMS - INSPECT GAP SUB & BATTERIES - SURFACE TEST MOTOR - OK - CHANGE OUT BITS	
20:00	0.50	20:30	6	TRIPS	TRIP INTO SHOE & INSTALL ROTATING RUBBER	
20:30	1.50	22:00	9	CUT OFF DRILL LINE	SLIP & CUT 13' OF DRILLING LINE	
22:00	3.00	01:00	6	TRIPS	TRIP INTO HOLE	
01:00	0.50	01:30	2	DRILL ACTUAL	DRILLING 7 7/8" HOLE	
01:30	0.50	02:00	7	LUBRICATE RIG	SERVICE RIG & TOP DRIVE	
02:00	4.00	06:00	2	DRILL ACTUAL	DRILLING 7 7/8" HOLE	

Prickly Pear Fed. #9A-18D-12-15 9/13/2011 06:00 - 9/14/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	11.50	17:30	2	DRILL ACTUAL	DRILLING 7 7/8" HOLE TO T.D.	
17:30	1.50	19:00			CIRC & COND. HOLE - COULD NOT ROTATE PIPE - TOP DRIVE WAS TORQUED OUT DUE TO TIGHT HOLE	
19:00	11.00	06:00	6	TRIPS	BACKREAM OUT OF HOLE & RACK 44 STANDS IN DERRICK - PUMP DRY JOB & BEGIN TO LAY DOWN DRILL PIPE & BHA	

Prickly Pear Fed. #9A-18D-12-15 9/14/2011 06:00 - 9/15/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	6.00	12:00	6	TRIPS	TRIP OUT LAYING DOWN DRILL PIPE	
12:00	0.50	12:30	21	OPEN	PULL WEAR RING	
12:30	7.00	19:30	12	RUN CASING & CEMENT	RIG UP WEATHERFORD & HELD SAFETY MEETING - RAN 200 JOINTS OF 4.5" - P 110 - 11.60# - LT&C CASING TO 8383' - 76 CENTRALIZER'S FROM 8319' THROUGH TO 1509' - MAKERS @ 6933' & 5734'	
19:30	1.00	20:30	5	COND MUD & CIRC	CIRC & RIG DOWN CASER'S & RIG UP HALCO	

**Time Log**

Start Time	Dur (hr)	End Time	Code	Category	Com
20:30	2.50	23:00	12	RUN CASING & CEMENT	HELD SAFETY MEETING - PSI TEST TO 5000 PSI - PUMP PUMP 5 BBLs. H 2/0 - 40 BBLs. SUPERFLUSH - 10 BBLs. H 2/0 - MIX 189 BBLs. WITH 555 SK OF LEAD @ 12.5 PPG - 1.91 YIELD - 10.31 GAL/SK - MIX 323 BBLs WITH 1245 SK OF TAIL @ 13.4 PPG - 1.46 YIELD - 6.92 GAL/SK - DROP PLUG - SLOW RATE TO 1700 PSI @ 3 BPM - BUMP PLUG @ 3 BPM @ 2050 PSI - FLOATS HELD - GOOD RETURNS - 62 BBLs CEMENT TO SURFACE - RIG DOWN
23:00	1.00	00:00	14	NIPPLE UP B.O.P	NIPPLE DOWN & SET SLIPS @ 120 K - CUT OFF CASING - CASING HUNG @ 8383' - RIG RELEASED @ 12:00 AM 9/14/11


Prickly Pear Fed. #9A-18D-12-15 10/1/2011 06:00 - 10/2/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	10.50	16:30	LOCL	Lock Wellhead & Secure	SI
16:30	1.00	17:30	SRIG	Rig Up/Down	Rig HES frac & Cutters Wire line on well.
17:30	1.00	18:30	PFRT	Perforating	Cutters EL stage 1 Price River. PU 8 ft. perf guns. RIH correlate to short jt. run to perf depth check depth to casing collar. Perforate @ 8181-8185, 8170-8172 & 8156-8158. 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.
18:30	1.00	19:30	FRAC	Frac. Job	HES frac stage 1 Price River 70Q foam frac. Load & Break @ 3958 PSI @ 5 BPM. Avg Wellhead Rate: 29.2 BPM. Avg Slurry Rate: 11.6 BPM. Avg CO2 Rate: 16.1 BPM. Avg Pressure: 5632 PSI. Max Wellhead Rate: 30.5 BPM. Max Slurry Rate: 13.6 BPM. Max CO2 Rate: 20.7 BPM. Max Pressure: 5947 PSI. Total Fluid Pumped: 16,360 gal. Total Sand in Formation: 64,000 lb. (30/50 P. White) Praxair CO2 Downhole: 96 ton. CO2 Cooldown: 5 ton. ISIP: 3,543 PSI. Frac Gradient: 0.88 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.
19:30	2.00	21:30	PFRT	Perforating	Cutters EL stage 2 Price River. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 8140 ft. PU. Pressure up casing. Perforate @ 8090-8092, 8003-8005, 7967-7969, 7922-7924 & 7870-7872. 3 SPF, 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.
21:30	1.00	22:30	FRAC	Frac. Job	HES frac stage 2 Price River 70Q foam frac. Load & Break @ 4609 PSI @ 17.5 BPM. Avg. Wellhead Rate: 39.3 BPM. Avg. Slurry Rate: 20.9 BPM. Avg CO2 Rate: 16.3 BPM. Avg Pressure: 6914 PSI. Max Wellhead Rate: 40.4 BPM. Max Slurry Rate: 18.2 BPM. Max CO2 Rate: 25.5 BPM. Max Pressure: 7588 PSI. Total Fluid Pumped: 20,266 gal. Total Sand in Formation: 108,300 lb. (20/40 White) Praxair CO2 Downhole: 125 ton CO2 Cooldown: 6 ton. ISIP 3,503 :PSI. Frac Gradient: 0.88 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.
22:30	7.50	06:00	LOCL	Lock Wellhead & Secure	SIFN Wait on sand

Prickly Pear Fed. #9A-18D-12-15 10/17/2011 06:00 - 10/18/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	IWHD	Install Wellhead	Install frac tree
07:00	23.00	06:00	LOCL	Lock Wellhead & Secure	Well secure

Prickly Pear Fed. #9A-18D-12-15 10/18/2011 06:00 - 10/19/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	PTST	Pressure Test	Test Casing to 8500 and frac tree to 8500 held
07:00	23.00	06:00	LOCL	Lock Wellhead & Secure	Well secure

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU73668
SUNDRY NOTICES AND REPORTS ON WELLS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		7. UNIT or CA AGREEMENT NAME: PRICKLY PEAR
1. TYPE OF WELL Gas Well		8. WELL NAME and NUMBER: PRICKLY PEAR UF 9A-18D-12-15
2. NAME OF OPERATOR: BILL BARRETT CORP		9. API NUMBER: 43007501380000
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext	9. FIELD and POOL or WILDCAT: PRICKLY PEAR
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0495 FNL 1447 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 17 Township: 12.0S Range: 15.0E Meridian: S		COUNTY: CARBON
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/31/2011	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	
		<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
October 2011 monthly drilling activity report attached.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Brady Riley	PHONE NUMBER 303 312-8115	TITLE Permit Analyst
SIGNATURE N/A		DATE 11/4/2011


Prickly Pear Fed. #9A-18D-12-15 10/1/2011 06:00 - 10/2/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	10.50	16:30	LOCL	Lock Wellhead & Secure	SI
16:30	1.00	17:30	SRIG	Rig Up/Down	Rig HES frac & Cutters Wire line on well.
17:30	1.00	18:30	PFRT	Perforating	Cutters EL stage 1 Price River. PU 8 ft. perf guns. RIH correlate to short jt. run to perf depth check depth to casing collar. Perforate @ 8181-8185, 8170-8172 & 8156-8158. 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.
18:30	1.00	19:30	FRAC	Frac. Job	HES frac stage 1 Price River 70Q foam frac. Load & Break @ 3958 PSI @ 5 BPM. Avg Wellhead Rate: 29.2 BPM. Avg Slurry Rate: 11.6 BPM. Avg CO2 Rate: 16.1 BPM. Avg Pressure: 5632 PSI. Max Wellhead Rate: 30.5 BPM. Max Slurry Rate: 13.6 BPM. Max CO2 Rate: 20.7 BPM. Max Pressure: 5947 PSI. Total Fluid Pumped: 16,360 gal. Total Sand in Formation: 64,000 lb. (30/50 P. White) Praxair CO2 Downhole: 96 ton. CO2 Cooldown: 5 ton. ISIP: 3,543 PSI. Frac Gradient: 0.88 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.
19:30	2.00	21:30	PFRT	Perforating	Cutters EL stage 2 Price River. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 8140 ft. PU. Pressure up casing. Perforate @ 8090-8092, 8003-8005, 7967-7969, 7922-7924 & 7870-7872. 3 SPF, 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.
21:30	1.00	22:30	FRAC	Frac. Job	HES frac stage 2 Price River 70Q foam frac. Load & Break @ 4609 PSI @ 17.5 BPM. Avg. Wellhead Rate: 39.3 BPM. Avg. Slurry Rate: 20.9 BPM. Avg CO2 Rate: 16.3 BPM. Avg Pressure: 6914 PSI. Max Wellhead Rate: 40.4 BPM. Max Slurry Rate: 18.2 BPM. Max CO2 Rate: 25.5 BPM. Max Pressure: 7588 PSI. Total Fluid Pumped: 20,266 gal. Total Sand in Formation: 108,300 lb. (20/40 White) Praxair CO2 Downhole: 125 ton CO2 Cooldown: 6 ton. ISIP 3,503 :PSI. Frac Gradient: 0.88 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.
22:30	7.50	06:00	LOCL	Lock Wellhead & Secure	SIFN Wait on sand

Prickly Pear Fed. #9A-18D-12-15 10/17/2011 06:00 - 10/18/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	IWHD	Install Wellhead	Install frac tree
07:00	23.00	06:00	LOCL	Lock Wellhead & Secure	Well secure

Prickly Pear Fed. #9A-18D-12-15 10/18/2011 06:00 - 10/19/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	PTST	Pressure Test	Test Casing to 8500 and frac tree to 8500 held
07:00	23.00	06:00	LOCL	Lock Wellhead & Secure	Well secure



Prickly Pear Fed. #9A-18D-12-15 11/1/2011 06:00 - 11/2/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	10.50	16:30	LOCL	Lock Wellhead & Secure	SI	
16:30	1.00	17:30	SRIG	Rig Up/Down	Rig HES frac & Cutters Wire line on well.	
17:30	1.00	18:30	PFRT	Perforating	Cutters EL stage 1 Price River. PU 8 ft. perf guns. RIH correlate to short jt. run to perf depth check depth to casing collar. Perforate @ 8181-8185, 8170-8172 & 8156-8158. 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.	
18:30	1.00	19:30	FRAC	Frac. Job	HES frac stage 1 Price River 70Q foam frac. Load & Break @ 3958 PSI @ 5 BPM. Avg Wellhead Rate: 29.2 BPM. Avg Slurry Rate: 11.6 BPM. Avg CO2 Rate: 16.1 BPM. Avg Pressure: 5632 PSI. Max Wellhead Rate: 30.5 BPM. Max Slurry Rate: 13.6 BPM. Max CO2 Rate: 20.7 BPM. Max Pressure: 5947 PSI. Total Fluid Pumped: 16,360 gal. Total Sand in Formation: 64,000 lb. (30/50 P. White) Praxair CO2 Downhole: 96 ton. CO2 Cooledown: 5 ton. ISIP: 3,543 PSI. Frac Gradient: 0.88 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.	
19:30	2.00	21:30	PFRT	Perforating	Cutters EL stage 2 Price River. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 8140 ft. PU. Pressure up casing. Perforate @ 8090-8092, 8003-8005, 7967-7969, 7922-7924 & 7870-7872. 3 SPF, 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.	
21:30	1.00	22:30	FRAC	Frac. Job	HES frac stage 2 Price River 70Q foam frac. Load & Break @ 4609 PSI @ 17.5 BPM. Avg. Wellhead Rate: 39.3 BPM. Avg. Slurry Rate: 20.9 BPM. Avg CO2 Rate: 16.3 BPM. Avg Pressure: 6914 PSI. Max Wellhead Rate: 40.4 BPM. Max Slurry Rate: 18.2 BPM. Max CO2 Rate: 25.5 BPM. Max Pressure: 7588 PSI. Total Fluid Pumped: 20,266 gal. Total Sand in Formation: 108,300 lb. (20/40 White) Praxair CO2 Downhole: 125 ton CO2 Cooledown: 6 ton. ISIP 3,503 :PSI. Frac Gradient: 0.88 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.	
22:30	7.50	06:00	LOCL	Lock Wellhead & Secure	SIFN Wait on sand	

Prickly Pear Fed. #9A-18D-12-15 11/2/2011 06:00 - 11/3/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	6.00	12:00	LOCL	Lock Wellhead & Secure	SI.	
12:00	1.50	13:30	PFRT	Perforating	Cutters EL stage 3 Dark Canyon. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP 7850 ft. PU. Pressure up casing. Perforate @ 7808-7810, 7782-7784, 7762-7764, 7748-7750 & 7707-7709. 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.	
13:30	0.25	13:45	SMTG	Safety Meeting	Safety Meet. Frac , CO2, Sand, Flow back. Wire line. Pressure lines. PPE.	
13:45	1.00	14:45	FRAC	Frac. Job	HES frac stage 3 Dark Canyon 70Q foam frac. Load & Break @ 5434 PSI @ 24.5 BPM. Avg Wellhead Rate: 39.39 BPM. Avg Slurry Rate: 16.5 BPM. Avg. CO2 Rate: 20.5 BPM. Avg Pressure: 7363 PSI. Max Wellhead Rate: 40.4 BPM. Max Slurry Rate: 18.9 BPM. Max CO2 Rate: 23.1 BPM. Max Pressure: 7853 PSI. Total Fluid Pumped: 27,071 gal. Total Sand in Formation: 131,000 (30/50 P.White) Linde CO2 Downhole: 176 ton. ISIP: 6 PSI. Frac Gradient: 0.92 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.	
14:45	1.75	16:30	PFRT	Perforating	Cutters EL stage 4 Dark Canyon. PU HES CFP with 10ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 7640 ft. PU. Pressure up casing. Perforate @ 7592-7596, 7540-7542, 7527-7529 & 7514-7516. 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.	
16:30	1.00	17:30	FRAC	Frac. Job	HES frac stage 4 Dark Canyon 70 Q foam frac. Load & Break @ 3935 PSI @ 17.5 BPM. Avg Wellhead Rate: 39.4 BPM. Avg Slurry Rate: 16.6 BPM. Avg CO2 Rate: 20.5 BPM. Avg Pressure: 7361 PSI. Max Wellhead Rate: 40.4 BPM. Max Slurry Rate: 19.8 BPM. Max CO2 Rate: 23.1 BPM. Max Pressure: 7720 PSI. Total Fluid Pumped: 25,200 gal. Total Sand in Formation: 120,100 lb. (30/50 P.White) Linde CO2 Dowhole: 163 ton. CO2 Cooledown: 5 ton. ISIP: 3,747 PSI. Frac Gradient: 0.94 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.	
17:30	1.75	19:15	PFRT	Perforating	Cutters El stage 5 North Horn. PU HES CFP with 8 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 7420 ft. PU. Pressure up casing. Perforate @ 7356-7358, 7340-7342, 7267-7269 & 7212-7214. 3 SPF. 120 phasing, 23 gram charge. .350 holes. POOH turn well over to frac.	

**Time Log**

Start Time	Dur (hr)	End Time	Code	Category	Com
19:15	1.00	20:15	FRAC	Frac. Job	HES frac stage 5 North Horn 50Q foam frac. Load & Break @ 3189 PSI @ 19.6 BPM. Avg Wellhead Rate: 40.2 BPM. Avg Slurry Rate: 24.4 BPM. Avg CO2 Rate: 13.6 BPM. Avg Pressure: 5882 PSI. Max Wellhead Rate: 41.2 BPM. Max Slurry Rate: 26.2 BPM. Max CO2 Rate: 24.5 BPM. Max Pressure: 6757 PSI. Total Fluid Pumped: 39,803 gal. Total Sand in Formation: 140,100 lb. (30/50 P. White) Praxair CO2 Downhole: 143 ton. CO2 Cooledown: 5 ton. ISIP: 3,800 PSI. Frac Gradient: 0.96 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.
20:15	1.75	22:00	PFRT	Perforating	Cutters EL stage 6 North Horn. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 7000 ft. PU Pressure up casing. Perforate @ 6920-6924, 6767-6769, 6746-6748 & 6638-6640. 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.
22:00	1.00	23:00	FRAC	Frac. Job	HES frac stage 6 North Horn 50Q foam frac. Load & Break @ 3654 PSI @ 17.6 BPM. Avg Wellhead Rate: 40.3 BPM. Avg Slurry Rate: 24.4 BPM. Avg CO2 Rate: 13.5 BPM. Avg Pressure: 6090 PSI. Max Wellhead Rate: 41.2 BPM. Max Slurry Rate: 26.2 BPM. Max CO2 Rate: 17.5 BPM. Max Pressure: 7248 PSI. Total Fluid Pumped: 40,008 gal. Total Sand in Formation: 140,300 lb. (30/50 P. White) Linde CO2 Downhole: 143 ton. CO2 Cooledown: 5 ton. ISIP: 3,796 PSI. Frac Gradient: 1.00 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.
23:00	7.00	06:00	LOCL	Lock Wellhead & Secure	SI.

Prickly Pear Fed. #9A-18D-12-15 11/3/2011 06:00 - 11/4/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	6.00	12:00	LOCL	Lock Wellhead & Secure	SICP: 1100
12:00	1.75	13:45	PFRT	Perforating	Cutters EL stage 7 North Horn. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 6550 ft. PU. Pressure up casing. Perforate @ 6480-6484, 6345-6347, 6259-6261 & 6197-6199. 3 SPF, 120 phasing, 23 gram charge. .350 holes. POOH turn well over to frac.
13:45	0.25	14:00	SMTG	Safety Meeting	Safety Meet. Fracs. Flow back. CO2. Wire line. Rig off well. pressure lines.
14:00	1.00	15:00	FRAC	Frac. Job	HES frac stage 7 North Horn 50Q foam frac. Load & Break @ 3426 PSI @ 18 BPM. Avg Wellhead Rate: 40.4 BPM. Avg Slurry Rate: 24.5 BPM. Avg CO2 Rate: 13.5 BPM. Avg Pressure: 4717 PSI. Max Wellhead Rate: 41.4 BPM. Max Slurry Rate: 26.2 BPM. Max CO2 Rate: 17.9 BPM. Max Pressure: 5512 PSI. Total Fluid Pumped: 41,994 gal. Total Sand in Formation: 148,100 lb. (30/50 P. White) Praxair CO2 Downhole: 150 ton. CO2 Cooledown: 6 ton. ISIP: 2,892 PSI. Frac Gradient: 0.90 psi/ft. Successfully flushed wellbore with 50Q foam 50 bbl over flush with 500 gal. fluid cap.
15:00	1.75	16:45	PFRT	Perforating	Cutters EL stage 8 Middle Wasatch. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 5850 ft. PU. Pressure up casing. Perforate @ 5790--5792, 5752-5754, 5699-5701, 5682-5684 & 5562-5564. 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.
16:45	1.00	17:45	FRAC	Frac. Job	HES frac stage 8 Middle Wasatch 40Q foam frac. Load & Break @ 3493 PSI @ 19.1 BPM. Avg Wellhead Rate: 40.5 BPM. Avg Slurry Rate: 28.4 BPM. Avg CO2 Rate: 9.8 BPM. Avg Pressure: 4541 PSI. Max Wellhead Rate: 42.3 BPM. Max Slurry Rate: 30.2 BPM. Max CO2 Rate: 14 BPM. Max Pressure: 5754 PSI. Total fluid Pumped: 34,262 gal. Total Sand in Formation: 100,200 lb. (30/50 White) Praxair CO2 Downhole: 85 ton. CO2 Cooledown: 5 ton. ISIP: 2,717 PSI. Frac Gradient: 0.92 psi/ft. Successfully flushed wellbore with 40Q foam 50 bbl over flush with 500 gal. fluid cap.
17:45	1.75	19:30	PFRT	Perforating	Cutters EL stage 9 Middle Wasatch. PU HES CFP with 10 ft. perf guns. RIH correlate to short jt. run to setting depth set CFP @ 5470 ft. PU. Pressure up casing. Perforate @ 5425-5427, 5358-5360, 5331-5333, 5266-5268, 5250-5252, 3 SPF. 120 phasing. 23 gram charge. .350 holes. POOH turn well over to frac.
19:30	1.00	20:30	FRAC	Frac. Job	HES frac stage 9 Middle Wasatch 40Q foam frac. Load & Break @ 3538 PSI @ 17 BPM. Avg. Wellhead Rate: 40.5 BPM. Avg Slurry Rate: 28.3 BPM. Avg CO2 Rate: 9.9 BPM. Avg Pressure: 3921 PSI. Max Wellhead Rate: 42.3 BPM. Max Slurry Rate: 30.3 BPM. Max CO2 Rate: 14.1 BPM. Max Pressure: 5266 PSI. Total fluid Pumped: 48,130 gal. Total Sand in Formation: lb. (30/50 White 50,900 lb. 20/40 White: 101,400 lbs.) Total Sand in Formation: 253,700 lbs.) Linde CO2 Downhole: 120 ton. CO2 Cooledown: 5 ton. ISIP: 2,439 PSI. Frac Gradient: 0.90 psi/ft. Successfully flushed with 40Q foam 10 bbl over flush with 500 gal. fluid cap.
20:30	4.00	00:30	SRIG	Rig Up/Down	SI. Rig Cutters and HES frac off well. move equipment to 3A-17D.
00:30	5.50	06:00	FBCK	Flowback Well	Flow back stages 1-9 thru. Cathedral flow equipment. Shut in longer due to 50 ppm H2S flowing in 8A-18D


Prickly Pear Fed. #9A-18D-12-15 11/4/2011 06:00 - 11/5/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	6.00	12:00	FBCK	Flowback Well	Flow back stages 1-9 FCP: 725 psi on 44 ck. recovered 406 bbl in 14.5 hours avg of 28 BPH. Co2 over 40%. H2S:0.5 ppm.
12:00	18.00	06:00	FBCK	Flowback Well	Flow back stages 1-9

Prickly Pear Fed. #9A-18D-12-15 11/5/2011 06:00 - 11/6/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	6.00	12:00	FBCK	Flowback Well	Flow back stages 1-9 FCP: 500 psi on 3/4 ck. recovered 237 bbl in 24 hours avg of 9.87 BPH. CO2: 34%. H2S: 1.5 ppm. gas rate of 2543 MMCFD. fluid left to recover 6363 bbls.
12:00	18.00	06:00	FBCK	Flowback Well	Flow back stages 1-9

Prickly Pear Fed. #9A-18D-12-15 11/6/2011 06:00 - 11/7/2011 06:00

API/UWI 43-007-50138	State/Province	County	Field Name West Tavaputs	Well Status	Total Depth (ftKB) 8,400.0	Primary Job Type Drilling & Completion
-------------------------	----------------	--------	-----------------------------	-------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	6.00	12:00	FBCK	Flowback Well	Flow back stages 1-9 FCP: 380 psi on 48 ck. recovered 9 bbl in 24 hours. CO2: 20%. H2S: 1 ppm. gas rate of 2041 mmcf Total fluid left to recover 6327
12:00	6.00	18:00	FBCK	Flowback Well	Flowing to production sales
18:00	12.00	06:00		Flowback Well	flow back

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No. UTU73668

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No. UTU79487H

8. Lease Name and Well No. PRICKLY PEAR UNIT FEDERAL 9A-18D-12-15

9. API Well No. 43-007-50138

10. Field and Pool, or Exploratory PRICKLY PEAR

11. Sec., T., R., M., or Block and Survey or Area Sec 17 T12S R15E Mer SLB

12. County or Parish CARBON 13. State UT

17. Elevations (DF, KB, RT, GL)* 7419 GL

1. a. Type of Well Oil Well Gas Well Dry Other
b. Type of Completion New Well Work Over Deepen Plug Back Diff. Resvr.
Other _____

2. Name of Operator BILL BARRETT CORPORATION Contact: MEGAN FINNEGAN E-Mail: mfinnegan@billbarretcorp.com

3. Address 1099 18TH STREET SUITE 2300 DENVER, CO 80202 3a. Phone No. (include area code) Ph: 303-299-9949

4. Location of Well (Report location clearly and in accordance with Federal requirements)*
At surface NENW 495FNL 1447FWL
At top prod interval reported below Sec 18 T12S R15E Mer SLB SENE 2464FNL 387FEL
At total depth Sec 18 T12S R15E Mer SLB NESE 2626FSL 637FEL
BHL by HSM
638 FEL to 125 15E

14. Date Spudded 05/16/2011 15. Date T.D. Reached 09/13/2011 16. Date Completed D & A Ready to Prod. 11/06/2011

18. Total Depth: MD 8400 TVD 7278 19. Plug Back T.D.: MD 8339 TVD 7217-7220 20. Depth Bridge Plug Set: MD TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each) CBL, TRIPLE COMBO, MUD 22. Was well cored? No Yes (Submit analysis)
Was DST run? No Yes (Submit analysis)
Directional Survey? No Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
24.000	14.000 COND	36.0	0	40	40			0	
12.250	9.625 J-55	36.0	0	1025	1003	495	111	0	
7.875	4.500 P-110	11.6	0	8400	8383	1800	511	650	15000

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	6628							

25. Producing Intervals 26. Perforation Record

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) WASATCH	5250	7542	5250 TO 7542	0.340	156	OPEN
B) MESAVERDE	7592	8185	7592 TO 8185	0.340	102	OPEN
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
5250 TO 7542	WASATCH: SEE TREATMENT STAGES 4 - 9
7592 TO 8185	MESAVERDE: SEE TREATMENT STAGES 1 - 3

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
11/06/2011	11/07/2011	24	→	0.0	2066.0	0.0			FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg. SI	Cog. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
38/64		293.0	→	0	2066	0	0	PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Cog. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

RECEIVED

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #125875 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

MAR 08 2012

Div. of Oil, Gas & Mining

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				WASATCH NORTH HORN DARK CANYON PRICE RIVER TD	3267 5680 7579 7818 8400

32. Additional remarks (include plugging procedure):

TOC was calculated by CBL. First sales was on 11/06/2011. Conductor was set with grout. 8 3/4 hole size was used to drill from the bottom of surface casing to 7407' then 7 7/8 hole size was drilled to TD.

Tubing was set on 12/4/2011 after the production test date. There is no tubing pressure for the test data that was taken on 11/07/2011.

33. Circle enclosed attachments:

- 1. Electrical/Mechanical Logs (1 full set req'd.)
- 2. Geologic Report
- 3. DST Report
- 4. Directional Survey
- 5. Sundry Notice for plugging and cement verification
- 6. Core Analysis
- 7. Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #125875 Verified by the BLM Well Information System.
For BILL BARRETT CORPORATION, sent to the Price**

Name (please print) MEGAN FINNEGAN Title PERMIT ANALYST

Signature  (Electronic Submission) Date 12/15/2011

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Prickly Pear Unit Federal 9A-18D-12-15 Completion Report Continued*

44. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. (cont.)		
AMOUNT AND TYPE OF MATERIAL		
<i>Stage</i>	<i>BBLs Slurry</i>	<i>lbs 30/50 White Sand</i>
1	458	64,000
2	599	108,300
3	786	131,000
4	729	120,100
5	1,099	140,100
6	1,104	140,300
7	1,159	148,100
8	1,310	152,300
9	924	100,200

*Depth intervals for frac information same as perforation record intervals.

Bill Barrett Corp.

Carbon County, UT [NAD27]
Prickly Pear NW 17 Pad
Prickly Pear UF 9A-18D-12-15

Wellbore #1

Design: Wellbore #1

Standard Survey Report

14 September, 2011









Well Details: Prickly Pear UF 9A-18D-12-15

US State Plane 1927 (Exact solution) , Utah Central 4302 , NAD 1927 (NADCON CONUS)

Ground Level: 7417.00

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	529184.06	2347305.28	39° 46' 46.73 N	110° 15' 51.04 W



ANNOTATIONS

TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation
899.98	900.00	0.630	158.44	-3.70	-1.09	3.46	5.77	End of Gyro Surveys
1099.83	1100.00	5.080	229.07	-7.89	-4.70	8.99	11.66	As of Sept 9
5834.35	6956.00	1.300	71.90	-2160.56	-1990.08	2937.42	2965.86	As of Sept 12
6594.25	7716.00	0.600	206.30	-2160.82	-1979.60	2930.50	2978.05	As of Sept 13
7278.04	8400.00	2.000	201.60	-2175.99	-1984.66	2945.07	2994.31	Projected TD



Sharewell
Survey Report



Company: Bill Barrett Corp.
Project: Carbon County, UT [NAD27]
Site: Prickly Pear NW 17 Pad
Well: Prickly Pear UF 9A-18D-12-15
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well Prickly Pear UF 9A-18D-12-15
TVD Reference: GL @ 7417.00ft
MD Reference: GL @ 7417.00ft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: Compass VM

Project	Carbon County, UT [NAD27]		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		Using geodetic scale factor

Site	Prickly Pear NW 17 Pad		
Site Position:		Northing:	529,194.10 usft
From:	Lat/Long	Easting:	2,347,292.50 usft
Position Uncertainty:	0.00 ft	Slot Radius:	1.10 ft
		Latitude:	39° 46' 46.83 N
		Longitude:	110° 15' 51.20 W
		Grid Convergence:	0.79 °

Well	Prickly Pear UF 9A-18D-12-15		
Well Position	+N/-S	0.00 ft	Northing: 529,184.06 usft
	+E/-W	0.00 ft	Easting: 2,347,305.28 usft
Position Uncertainty	0.00 ft	Wellhead Elevation:	ft
		Latitude:	39° 46' 46.73 N
		Longitude:	110° 15' 51.04 W
		Ground Level:	7,417.00 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	03/24/11	11.36	65.55	52,141

Design	Wellbore #1				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	222.72	

Survey Program	Date	09/14/11			
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
100.00	900.00	Gyro Surveys (Wellbore #1)	MWD	MWD - Standard	
1,004.00	8,400.00	Survey #2 (Wellbore #1)	MWD	MWD - Standard	

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.480	194.75	100.00	-0.41	-0.11	0.37	0.48	0.48	0.00
200.00	0.330	195.47	200.00	-1.09	-0.29	1.00	0.15	-0.15	0.72
300.00	0.320	221.26	299.99	-1.58	-0.55	1.53	0.15	-0.01	25.79
400.00	0.160	237.15	399.99	-1.86	-0.85	1.95	0.17	-0.16	15.89
500.00	0.350	262.70	499.99	-1.98	-1.27	2.31	0.22	0.19	25.55
600.00	0.310	296.51	599.99	-1.89	-1.82	2.62	0.20	-0.04	33.81
700.00	0.410	116.81	699.99	-1.93	-1.74	2.60	0.72	0.10	-179.70
800.00	0.630	173.20	799.99	-2.64	-1.36	2.86	0.53	0.22	56.39
900.00	0.630	158.44	899.98	-3.70	-1.09	3.46	0.16	0.00	-14.76

Sharewell
Survey Report



Company: Bill Barrett Corp.
Project: Carbon County, UT [NAD27]
Site: Prickly Pear NW 17 Pad
Well: Prickly Pear UF 9A-18D-12-15
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well Prickly Pear UF 9A-18D-12-15
TVD Reference: GL @ 7417.00ft
MD Reference: GL @ 7417.00ft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: Compass VM

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
1,004.00	0.610	215.06	1,003.98	-4.68	-1.20	4.25	0.57	-0.02	54.44
1,100.00	5.080	229.07	1,099.83	-7.89	-4.70	8.99	4.68	4.66	14.59
1,128.00	5.130	232.01	1,127.72	-9.47	-6.63	11.45	0.95	0.18	10.50
1,162.00	7.280	229.43	1,161.52	-11.81	-9.46	15.09	6.37	6.32	-7.59
1,194.00	9.310	219.22	1,193.19	-15.13	-12.64	19.69	7.81	6.34	-31.91
1,227.00	10.620	216.22	1,225.69	-19.65	-16.12	25.38	4.27	3.97	-9.09
1,250.00	12.400	220.80	1,248.23	-23.23	-18.99	29.95	8.69	7.74	19.91
1,345.00	17.800	229.50	1,339.92	-40.40	-36.71	54.59	6.15	5.68	9.16
1,440.00	22.200	227.00	1,429.17	-62.08	-60.89	86.92	4.72	4.63	-2.63
1,535.00	25.800	232.10	1,515.96	-87.03	-90.34	125.23	4.37	3.79	5.37
1,630.00	33.000	233.20	1,598.67	-115.27	-127.42	171.13	7.60	7.58	1.16
1,725.00	38.800	232.10	1,675.59	-149.07	-171.66	225.98	6.14	6.11	-1.16
1,820.00	43.400	229.90	1,747.16	-188.40	-220.14	287.76	5.08	4.84	-2.32
1,915.00	47.100	225.90	1,814.05	-233.67	-270.12	354.92	4.91	3.89	-4.21
2,010.00	49.200	223.20	1,877.43	-284.10	-319.73	425.64	3.06	2.21	-2.84
2,106.00	48.500	222.30	1,940.60	-337.18	-368.80	497.92	1.01	-0.73	-0.94
2,201.00	49.200	219.70	2,003.12	-391.17	-415.72	569.41	2.19	0.74	-2.74
2,296.00	48.100	217.90	2,065.89	-446.73	-460.41	640.55	1.83	-1.16	-1.89
2,391.00	45.100	216.80	2,131.15	-501.59	-502.29	709.27	3.27	-3.16	-1.16
2,486.00	44.800	215.10	2,198.39	-555.91	-541.69	775.91	1.30	-0.32	-1.79
2,581.00	44.500	213.60	2,265.97	-611.03	-579.36	841.96	1.15	-0.32	-1.58
2,676.00	44.100	217.60	2,333.98	-664.96	-617.96	907.77	2.97	-0.42	4.21
2,771.00	43.700	219.70	2,402.43	-716.40	-659.10	973.47	1.59	-0.42	2.21
2,866.00	43.200	225.10	2,471.43	-764.62	-703.11	1,038.75	3.94	-0.53	5.68
2,961.00	42.000	224.40	2,541.35	-810.28	-748.38	1,103.01	1.36	-1.26	-0.74
3,057.00	42.500	225.50	2,612.42	-855.96	-793.98	1,167.51	0.93	0.52	1.15
3,152.00	45.100	229.90	2,680.99	-900.14	-842.63	1,232.97	4.21	2.74	4.63
3,247.00	45.300	230.90	2,747.93	-943.11	-894.57	1,299.77	0.78	0.21	1.05
3,342.00	47.800	230.10	2,813.26	-986.98	-947.77	1,368.10	2.70	2.63	-0.84
3,437.00	47.000	229.70	2,877.57	-1,032.02	-1,001.26	1,437.48	0.90	-0.84	-0.42
3,532.00	49.300	228.40	2,940.95	-1,078.41	-1,054.69	1,507.81	2.63	2.42	-1.37
3,627.00	48.100	228.70	3,003.65	-1,125.65	-1,108.19	1,578.81	1.29	-1.26	0.32
3,722.00	48.500	224.50	3,066.86	-1,174.38	-1,159.70	1,649.55	3.33	0.42	-4.42
3,817.00	48.200	221.30	3,130.00	-1,226.36	-1,208.01	1,720.51	2.54	-0.32	-3.37
3,912.00	47.200	221.20	3,193.94	-1,279.19	-1,254.34	1,790.76	1.06	-1.05	-0.11
4,008.00	46.400	217.80	3,259.66	-1,333.16	-1,298.85	1,860.61	2.71	-0.83	-3.54
4,103.00	48.600	215.80	3,323.84	-1,389.25	-1,340.78	1,930.26	2.79	2.32	-2.11
4,198.00	47.500	215.70	3,387.35	-1,446.59	-1,382.06	2,000.39	1.16	-1.16	-0.11
4,293.00	46.600	215.70	3,452.08	-1,503.06	-1,422.64	2,069.40	0.95	-0.95	0.00
4,388.00	46.800	219.10	3,517.24	-1,557.96	-1,464.62	2,138.22	2.61	0.21	3.58
4,483.00	45.400	219.20	3,583.11	-1,611.05	-1,507.84	2,206.54	1.48	-1.47	0.11
4,578.00	46.700	221.50	3,649.05	-1,663.15	-1,552.12	2,274.87	2.22	1.37	2.42
4,673.00	45.700	222.50	3,714.80	-1,714.11	-1,598.00	2,343.43	1.30	-1.05	1.05

Sharewell
Survey Report



Company: Bill Barrett Corp.
Project: Carbon County, UT [NAD27]
Site: Prickly Pear NW 17 Pad
Well: Prickly Pear UF 9A-18D-12-15
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well Prickly Pear UF 9A-18D-12-15
TVD Reference: GL @ 7417.00ft
MD Reference: GL @ 7417.00ft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: Compass VM

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,768.00	42.700	223.50	3,782.90	-1,762.55	-1,643.15	2,409.65	3.24	-3.16	1.05
4,863.00	41.000	224.00	3,853.66	-1,808.34	-1,686.97	2,473.02	1.82	-1.79	0.53
4,959.00	38.600	221.60	3,927.42	-1,853.39	-1,728.74	2,534.45	2.97	-2.50	-2.50
5,054.00	34.300	223.40	4,003.82	-1,895.02	-1,766.83	2,590.88	4.66	-4.53	1.89
5,149.00	31.600	221.90	4,083.53	-1,933.01	-1,801.85	2,642.54	2.97	-2.84	-1.58
5,244.00	29.600	221.90	4,165.30	-1,969.00	-1,834.14	2,690.89	2.11	-2.11	0.00
5,339.00	26.200	221.00	4,249.24	-2,002.30	-1,863.58	2,735.33	3.61	-3.58	-0.95
5,434.00	24.000	219.50	4,335.27	-2,033.04	-1,889.63	2,775.58	2.41	-2.32	-1.58
5,529.00	20.200	220.00	4,423.27	-2,060.52	-1,912.47	2,811.27	4.00	-4.00	0.53
5,624.00	17.900	221.60	4,513.06	-2,084.01	-1,932.71	2,842.25	2.48	-2.42	1.68
5,719.00	15.600	217.50	4,604.03	-2,105.06	-1,950.18	2,869.57	2.72	-2.42	-4.32
5,814.00	12.900	221.60	4,696.10	-2,123.13	-1,965.00	2,892.90	3.03	-2.84	4.32
5,910.00	10.000	217.80	4,790.18	-2,137.73	-1,977.22	2,911.92	3.12	-3.02	-3.96
6,005.00	7.200	221.80	4,884.10	-2,148.69	-1,986.25	2,926.10	3.01	-2.95	4.21
6,100.00	4.700	229.70	4,978.59	-2,155.65	-1,993.19	2,935.92	2.76	-2.63	8.32
6,195.00	1.600	210.00	5,073.43	-2,159.31	-1,996.82	2,941.07	3.41	-3.26	-20.74
6,290.00	0.800	167.90	5,168.41	-2,161.11	-1,997.34	2,942.75	1.20	-0.84	-44.32
6,385.00	1.000	108.10	5,263.40	-2,162.02	-1,996.42	2,942.79	0.96	0.21	-62.95
6,480.00	1.000	104.80	5,358.39	-2,162.48	-1,994.83	2,942.05	0.06	0.00	-3.47
6,575.00	0.300	82.10	5,453.38	-2,162.66	-1,993.78	2,941.47	0.77	-0.74	-23.89
6,670.00	0.400	26.20	5,548.38	-2,162.33	-1,993.39	2,940.96	0.36	0.11	-58.84
6,765.00	0.600	81.00	5,643.38	-2,161.96	-1,992.75	2,940.25	0.52	0.21	57.68
6,860.00	0.900	49.50	5,738.37	-2,161.39	-1,991.69	2,939.12	0.53	0.32	-33.16
6,956.00	1.300	71.90	5,834.35	-2,160.56	-1,990.08	2,937.42	0.60	0.42	23.33
7,051.00	0.800	64.50	5,929.34	-2,159.94	-1,988.46	2,935.87	0.54	-0.53	-7.79
7,146.00	1.100	57.40	6,024.32	-2,159.17	-1,987.09	2,934.37	0.34	0.32	-7.47
7,241.00	0.500	76.20	6,119.31	-2,158.58	-1,985.92	2,933.14	0.68	-0.63	19.79
7,336.00	0.700	83.50	6,214.31	-2,158.41	-1,984.94	2,932.36	0.22	0.21	7.68
7,431.00	1.000	99.10	6,309.30	-2,158.48	-1,983.55	2,931.46	0.40	0.32	16.42
7,526.00	1.200	111.10	6,404.28	-2,158.97	-1,981.80	2,930.63	0.32	0.21	12.63
7,621.00	1.100	125.00	6,499.26	-2,159.85	-1,980.13	2,930.14	0.31	-0.11	14.63
7,716.00	0.600	206.30	6,594.25	-2,160.82	-1,979.60	2,930.50	1.23	-0.53	85.58
7,811.00	0.900	213.40	6,689.25	-2,161.89	-1,980.23	2,931.71	0.33	0.32	7.47
7,907.00	1.100	189.10	6,785.23	-2,163.43	-1,980.79	2,933.22	0.48	0.21	-25.31
8,002.00	0.900	173.20	6,880.22	-2,165.07	-1,980.85	2,934.46	0.36	-0.21	-16.74
8,097.00	1.500	208.20	6,975.20	-2,166.90	-1,981.35	2,936.15	0.97	0.63	36.84
8,192.00	1.800	197.40	7,070.16	-2,169.42	-1,982.38	2,938.71	0.45	0.32	-11.37
8,287.00	1.900	197.40	7,165.11	-2,172.35	-1,983.30	2,941.48	0.11	0.11	0.00
8,350.00	2.000	201.60	7,228.07	-2,174.37	-1,984.01	2,943.45	0.28	0.16	6.67
8,400.00	2.000	201.60	7,278.04	-2,175.99	-1,984.66	2,945.07	0.00	0.00	0.00

Sharewell
Survey Report



Company: Bill Barrett Corp.
Project: Carbon County, UT [NAD27]
Site: Prickly Pear NW 17 Pad
Well: Prickly Pear UF 9A-18D-12-15
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well Prickly Pear UF 9A-18D-12-15
TVD Reference: GL @ 7417.00ft
MD Reference: GL @ 7417.00ft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: Compass VM

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
900.00	899.98	-3.70	-1.09	End of Gyro Surveys
1,100.00	1,099.83	-7.89	-4.70	As of Sept 9
6,956.00	5,834.35	-2,160.56	-1,990.08	As of Sept 12
7,716.00	6,594.25	-2,160.82	-1,979.60	As of Sept 13
8,400.00	7,278.04	-2,175.99	-1,984.66	Projected TD

Checked By: _____ Approved By: _____ Date: _____

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5.LEASE DESIGNATION AND SERIAL NUMBER: UTU73668
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7.UNIT or CA AGREEMENT NAME: PRICKLY PEAR
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: PRICKLY PEAR UF 9A-18D-12-15
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43007501380000
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0495 FNL 1447 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 17 Township: 12.0S Range: 15.0E Meridian: S	9. FIELD and POOL or WILDCAT: PRICKLY PEAR COUNTY: CARBON STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/31/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <input type="text" value="pit closure"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The pit was closed on the above referenced well location, Prickly Pear NW 17 pad on 7/31/2012.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY
 July 31, 2012**

NAME (PLEASE PRINT) Megan Finnegan	PHONE NUMBER 303 299-9949	TITLE Permit Analyst
SIGNATURE N/A	DATE 7/31/2012	

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET (for state use only)

ROUTING
 CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

1/1/2014

FROM: (Old Operator): N2165-Bill Barrett Corporation 1099 18th Street, Suite 230 Denver, CO 80202 Phone: 1 (303) 312-8134	TO: (New Operator): N4040-EnerVest Operating, LLC 1001 Fannin Street, Suite 800 Houston, TX 77002 Phone: 1 (713) 659-3500
--	---

CA No.		Unit: Prickly Pear		WELL NAME	SEC	TWN	RNG	API NO.	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
See Attached List												

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 1/7/2014
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 1/7/2014
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 1/28/2014
- a. Is the new operator registered in the State of Utah: Business Number: 8850806-0161
- a. (R649-9-2)Waste Management Plan has been received on: Not Yet
- b. Inspections of LA PA state/fee well sites complete on: Yes
- c. Reports current for Production/Disposition & Sundries on: 1/24/2014
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM Not Yet BIA N/A
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: Not Yet
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: N/A
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to **Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: Yes

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 1/28/2014
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 1/28/2014
- Bond information entered in RBDMS on: 1/28/2014
- Fee/State wells attached to bond in RBDMS on: 1/28/2014
- Injection Projects to new operator in RBDMS on: 1/28/2014
- Receipt of Acceptance of Drilling Procedures for APD/New on: 1/7/2014
- Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: 1/7/2014

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: RLB7886
- Indian well(s) covered by Bond Number: RLB7886
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number B008371
- b. The **FORMER** operator has requested a release of liability from their bond on: N/A

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 1/28/2014

COMMENTS:

Bill Barrett Corporation (N2165) to EnerVest Operating, LLC (N4040)

Effective 1/1/2014

Prickly Pear Unit

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	Well Status
PPU FED 11-23D-12-15	23	120S	150E	4300731440		Federal	Federal	GW	APD
PPU FED 4-26D-12-15	23	120S	150E	4300731441		Federal	Federal	GW	APD
PPU FED 14-23D-12-15	23	120S	150E	4300731442		Federal	Federal	GW	APD
PPU FED 12-23D-12-15	23	120S	150E	4300731443		Federal	Federal	GW	APD
PRICKLY PEAR U FED 12-7D-12-15	7	120S	150E	4300750094		Federal	Federal	GW	APD
PRICKLY PEAR U FED 11-7D-12-15	7	120S	150E	4300750095		Federal	Federal	GW	APD
PRICKLY PEAR U FED 13-7D-12-15	7	120S	150E	4300750096		Federal	Federal	GW	APD
PRICKLY PEAR U FED 14-7D-12-15	7	120S	150E	4300750097		Federal	Federal	GW	APD
PRICKLY PEAR UF 11-8D-12-15	8	120S	150E	4300750124		Federal	Federal	GW	APD
PRICKLY PEAR UF 12-8D-12-15	8	120S	150E	4300750125		Federal	Federal	GW	APD
PRICKLY PEAR UF 13-8D-12-15	8	120S	150E	4300750126		Federal	Federal	GW	APD
PRICKLY PEAR UF 14-8D-12-15	8	120S	150E	4300750127		Federal	Federal	GW	APD
PRICKLY PEAR UF 9-21D-12-15	21	120S	150E	4300750128		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-21D-12-15	21	120S	150E	4300750129		Federal	Federal	GW	APD
PRICKLY PEAR UF 10-21D-12-15	21	120S	150E	4300750130		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-21D-12-15	21	120S	150E	4300750131		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-21D-12-15	21	120S	150E	4300750132		Federal	Federal	GW	APD
PRICKLY PEAR UF 15X-21D-12-15	21	120S	150E	4300750133		Federal	Federal	GW	APD
PRICKLY PEAR UF 16-21D-12-15	21	120S	150E	4300750134		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-21D-12-15	21	120S	150E	4300750135		Federal	Federal	GW	APD
PRICKLY PEAR UF 13A-22D-12-15	21	120S	150E	4300750148		Federal	Federal	GW	APD
PRICKLY PEAR UF 1A-27D-12-15	22	120S	150E	4300750161		Federal	Federal	GW	APD
PRICKLY PEAR UF 2A-27D-12-15	22	120S	150E	4300750162		Federal	Federal	GW	APD
PRICKLY PEAR UF 3A-27D-12-15	22	120S	150E	4300750163		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-22D-12-15	22	120S	150E	4300750164		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-22D-12-15	22	120S	150E	4300750165		Federal	Federal	GW	APD
PRICKLY PEAR UF 11A-22D-12-15	22	120S	150E	4300750166		Federal	Federal	GW	APD
PRICKLY PEAR UF 12A-22D-12-15	22	120S	150E	4300750167		Federal	Federal	GW	APD
PRICKLY PEAR UF 14A-22D-12-15	22	120S	150E	4300750168		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-22D-12-15	22	120S	150E	4300750169		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-22D-12-15	22	120S	150E	4300750170		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-15D-12-15	15	120S	150E	4300750180		Federal	Federal	GW	APD
PRICKLY PEAR UF 11B-15D-12-15	15	120S	150E	4300750181		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-15D-12-15	15	120S	150E	4300750184		Federal	Federal	GW	APD
PRICKLY PEAR UF 3A-18D-12-15	7	120S	150E	4300750185		Federal	Federal	GW	APD
PRICKLY PEAR UF 4A-18D-12-15	7	120S	150E	4300750186		Federal	Federal	GW	APD
PRICKLY PEAR UF 11A-7D-12-15	7	120S	150E	4300750187		Federal	Federal	GW	APD
PRICKLY PEAR UF 2-18D-12-15	7	120S	150E	4300750188		Federal	Federal	GW	APD
PRICKLY PEAR UF 12A-7D-12-15	7	120S	150E	4300750189		Federal	Federal	GW	APD
PRICKLY PEAR UF 13A-7D-12-15	7	120S	150E	4300750190		Federal	Federal	GW	APD
PRICKLY PEAR UF 14A-7D-12-15	7	120S	150E	4300750191		Federal	Federal	GW	APD
PRICKLY PEAR FEDERAL 1-12D-12-14	12	120S	140E	4300750205		Federal	Federal	GW	APD
PRICKLY PEAR UF 2-12D-12-14	12	120S	140E	4300750206		Federal	Federal	GW	APD
PRICKLY PEAR UF 7-12D-12-14	12	120S	140E	4300750207		Federal	Federal	GW	APD
PRICKLY PEAR UF 7A-12D-12-14	12	120S	140E	4300750208		Federal	Federal	GW	APD
PRICKLY PEAR UF 8-12D-12-14	12	120S	140E	4300750209		Federal	Federal	GW	APD
PRICKLY PEAR UF 4-7D-12-15	12	120S	140E	4300750210		Federal	Federal	GW	APD
PRICKLY PEAR UF 5-7D-12-15	12	120S	140E	4300750211		Federal	Federal	GW	APD
PRICKLY PEAR UF 8A-12D-12-14	12	120S	140E	4300750212		Federal	Federal	GW	APD
PRICKLY PEAR UF 5A-7D-12-15	12	120S	140E	4300750213		Federal	Federal	GW	APD
PRICKLY PEAR UF 7-14D-12-15	14	120S	150E	4300750214		Federal	Federal	GW	APD
PRICKLY PEAR UF 7A-14D-12-15	14	120S	150E	4300750215		Federal	Federal	GW	APD
PRICKLY PEAR UF 9-14D-12-15	14	120S	150E	4300750217		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-14D-12-15	14	120S	150E	4300750218		Federal	Federal	GW	APD
PRICKLY PEAR UF 10-14D-12-15	14	120S	150E	4300750219		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-14D-12-15	14	120S	150E	4300750220		Federal	Federal	GW	APD

Bill Barrett Corporation (N2165) to EnerVest Operating, LLC (N4040)

Effective 1/1/2014

Prickly Pear Unit

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	Well Status
PRICKLY PEAR UF 15A-14D-12-15	14	120S	150E	4300750222		Federal	Federal	GW	APD
PRICKLY PEAR UF 16-14D-12-15	14	120S	150E	4300750223		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-14D-12-15	14	120S	150E	4300750224		Federal	Federal	GW	APD
PRICKLY PEAR UF 1A-18D-12-15	7	120S	150E	4300750225		Federal	Federal	GW	APD
PRICKLY PEAR UF 2A-18D-12-15	7	120S	150E	4300750226		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-7D-12-15	7	120S	150E	4300750227		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-7D-12-15	7	120S	150E	4300750228		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-7D-12-15	7	120S	150E	4300750229		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-7D-12-15	7	120S	150E	4300750230		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-12D-12-14	12	120S	140E	4300750233		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-12D-12-14	12	120S	140E	4300750234		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-12D-12-14	12	120S	140E	4300750235		Federal	Federal	GW	APD
PRICKLY PEAR UF 12A-8D-12-15	8	120S	150E	4300750236		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-12D-12-14	12	120S	140E	4300750237		Federal	Federal	GW	APD
PRICKLY PEAR UF 11A-8D-12-15	8	120S	150E	4300750238		Federal	Federal	GW	APD
PRICKLY PEAR UF 13A-8D-12-15	8	120S	150E	4300750239		Federal	Federal	GW	APD
PRICKLY PEAR UF 14A-8D-12-15	8	120S	150E	4300750240		Federal	Federal	GW	APD
PRICKLY PEAR UF 5A-8D-12-15	8	120S	150E	4300750260		Federal	Federal	GW	APD
PRICKLY PEAR UF 6A-8D-12-15	8	120S	150E	4300750261		Federal	Federal	GW	APD
PRICKLY PEAR UF 4-8D-12-15	8	120S	150E	4300750262		Federal	Federal	GW	APD
PRICKLY PEAR UF 3-8D-12-15	8	120S	150E	4300750263		Federal	Federal	GW	APD
PRICKLY PEAR UF 2-8D-12-15	8	120S	150E	4300750264		Federal	Federal	GW	APD
PRICKLY PEAR UF 7A-8D-12-15	8	120S	150E	4300750265		Federal	Federal	GW	APD
PRICKLY PEAR UF 7-8D-12-15	8	120S	150E	4300750266		Federal	Federal	GW	APD
PRICKLY PEAR UF 5-8D-12-15	8	120S	150E	4300750267		Federal	Federal	GW	APD
PRICKLY PEAR UF 6-8D-12-15	8	120S	150E	4300750268		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-8D-12-15	8	120S	150E	4300750269		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-8D-12-15	8	120S	150E	4300750270		Federal	Federal	GW	APD
PRICKLY PEAR UF 8-8D-12-15	8	120S	150E	4300750271		Federal	Federal	GW	APD
PRICKLY PEAR UF 1-8D-12-15	8	120S	150E	4300750272		Federal	Federal	GW	APD
PRICKLY PEAR UF 8A-8D-12-15	8	120S	150E	4300750273		Federal	Federal	GW	APD
PRICKLY PEAR UF 5-9D-12-15	9	120S	150E	4300750274		Federal	Federal	GW	APD
PRICKLY PEAR UF 5A-9D-12-15	9	120S	150E	4300750275		Federal	Federal	GW	APD
PRICKLY PEAR UF 4-9D-12-15	9	120S	150E	4300750276		Federal	Federal	GW	APD
PRICKLY PEAR UF 3-9D-12-15	9	120S	150E	4300750277		Federal	Federal	GW	APD
PRICKLY PEAR UF 6A-9D-12-15	9	120S	150E	4300750278		Federal	Federal	GW	APD
PRICKLY PEAR UF 11-9D-12-15	9	120S	150E	4300750279		Federal	Federal	GW	APD
PRICKLY PEAR UF 12A-9D-12-15	9	120S	150E	4300750280		Federal	Federal	GW	APD
PRICKLY PEAR UF 6-9D-12-15	9	120S	150E	4300750281		Federal	Federal	GW	APD
PRICKLY PEAR UF 11A-9D-12-15	9	120S	150E	4300750282		Federal	Federal	GW	APD
PRICKLY PEAR US 1X-16D-12-15	10	120S	150E	4300750283		State	Federal	GW	APD
PRICKLY PEAR UF 5A-15D-12-15	10	120S	150E	4300750284		Federal	Federal	GW	APD
PRICKLY PEAR UF 6A-15D-12-15	10	120S	150E	4300750285		Federal	Federal	GW	APD
PRICKLY PEAR UF 3-15D-13-15	10	120S	150E	4300750286		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-10D-12-15	15	120S	150E	4300750287		Federal	Federal	GW	APD
PRICKLY PEAR UF 13-10D-12-15	10	120S	150E	4300750288		Federal	Federal	GW	APD
PRICKLY PEAR UF 15-10D-12-15	15	120S	150E	4300750289		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-10D-12-15	15	120S	150E	4300750290		Federal	Federal	GW	APD
PRICKLY PEAR UF 9-10D-12-15	15	120S	150E	4300750291		Federal	Federal	GW	APD
PRICKLY PEAR UF 14A-10D-12-15	10	120S	150E	4300750292		Federal	Federal	GW	APD
PRICKLY PEAR UF 10-10D-12-15	15	120S	150E	4300750293		Federal	Federal	GW	APD
PRICKLY PEAR UF 16-10D-12-15	15	120S	150E	4300750294		Federal	Federal	GW	APD
PRICKLY PEAR UF 13-11D-12-15	15	120S	150E	4300750295		Federal	Federal	GW	APD
PRICKLY PEAR UF 13A-11D-12-15	15	120S	150E	4300750296		Federal	Federal	GW	APD
PRICKLY PEAR UF 12-11D-12-15	15	120S	150E	4300750297		Federal	Federal	GW	APD
PRICKLY PEAR UF 13A-10D-12-15	10	120S	150E	4300750298		Federal	Federal	GW	APD

Bill Barrett Corporation (N2165) to EnerVest Operating, LLC (N4040)

Effective 1/1/2014

Prickly Pear Unit

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	Well Status
PRICKLY PEAR UF 12-10D-12-15	10	120S	150E	4300750299		Federal	Federal	GW	APD
PRICKLY PEAR UF 11-10D-12-15	10	120S	150E	4300750300		Federal	Federal	GW	APD
PRICKLY PEAR UF 3A-15D-12-15	10	120S	150E	4300750301		Federal	Federal	GW	APD
PRICKLY PEAR UF 12-14D-12-15	14	120S	150E	4300750302		Federal	Federal	GW	APD
PRICKLY PEAR UF 4-15D-12-15	10	120S	150E	4300750303		Federal	Federal	GW	APD
PRICKLY PEAR UF 4A-15D-12-15	10	120S	150E	4300750304		Federal	Federal	GW	APD
PRICKLY PEAR UF 14-10D-12-15	10	120S	150E	4300750305		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-17D-12-15	17	120S	150E	4300750306		Federal	Federal	GW	APD
PRICKLY PEAR UF 8A-17D-12-15	17	120S	150E	4300750307		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-17D-12-15	17	120S	150E	4300750308		Federal	Federal	GW	APD
PRICKLY PEAR UF 3-7D-12-15	7	120S	150E	4300750309		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-17D-12-15	17	120S	150E	4300750310		Federal	Federal	GW	APD
PRICKLY PEAR UF 6-7D-12-15	7	120S	150E	4300750311		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-17D-12-15	17	120S	150E	4300750312		Federal	Federal	GW	APD
PRICKLY PEAR UF 6A-7D-12-15	7	120S	150E	4300750313		Federal	Federal	GW	APD
PRICKLY PEAR UF 7A-7D-12-15	7	120S	150E	4300750314		Federal	Federal	GW	APD
PRICKLY PEAR UF 8A-7D-12-15	7	120S	150E	4300750315		Federal	Federal	GW	APD
PRICKLY PEAR UF 6X-17D-12-15	17	120S	150E	4300750316		Federal	Federal	GW	APD
PRICKLY PEAR UF 11A-17D-12-15	17	120S	150E	4300750317		Federal	Federal	GW	APD
PRICKLY PEAR UF 15B-17D-12-15	17	120S	150E	4300750318		Federal	Federal	GW	APD
PRICKLY PEAR UF 8A-20D-12-15	20	120S	150E	4300750319		Federal	Federal	GW	APD
PRICKLY PEAR UF 1-7D-12-15	7	120S	150E	4300750320		Federal	Federal	GW	APD
PRICKLY PEAR UF 7A-20D-12-15	20	120S	150E	4300750321		Federal	Federal	GW	APD
PRICKLY PEAR UF 9A-20D-12-15	20	120S	150E	4300750322		Federal	Federal	GW	APD
PRICKLY PEAR UF 10A-20D-12-15	20	120S	150E	4300750323		Federal	Federal	GW	APD
PRICKLY PEAR UF 10-20D-12-15	20	120S	150E	4300750324		Federal	Federal	GW	APD
PRICKLY PEAR UF 2-7D-12-15	7	120S	150E	4300750325		Federal	Federal	GW	APD
PRICKLY PEAR UF 14A-20D-12-15	20	120S	150E	4300750326		Federal	Federal	GW	APD
PRICKLY PEAR UF 16A-20D-12-15	20	120S	150E	4300750327		Federal	Federal	GW	APD
PRICKLY PEAR UF 15A-20D-12-15	20	120S	150E	4300750328		Federal	Federal	GW	APD
PRICKLY PEAR UF 8-7D-12-15	7	120S	150E	4300750329		Federal	Federal	GW	APD
PRICKLY PEAR UF 15-20D-12-15	20	120S	150E	4300750330		Federal	Federal	GW	APD
PRICKLY PEAR UF 7-7D-12-15	7	120S	150E	4300750331		Federal	Federal	GW	APD
PRICKLY PEAR UF 6-10D-12-15	9	120S	150E	4300750332		Federal	Federal	GW	APD
PRICKLY PEAR UF 5A-10D-12-15	9	120S	150E	4300750333		Federal	Federal	GW	APD
PRICKLY PEAR UF 11A-10D-12-15	9	120S	150E	4300750334		Federal	Federal	GW	APD
PRICKLY PEAR UF 6A-10D-12-15	9	120S	150E	4300750335		Federal	Federal	GW	APD
PRICKLY PEAR UF 5-10D-12-15	9	120S	150E	4300750336		Federal	Federal	GW	APD
PRICKLY PEAR UF 12A-10D-12-15	9	120S	150E	4300750338		Federal	Federal	GW	APD
PRICKLY PEAR UF 3-10D-12-15	9	120S	150E	4300750339		Federal	Federal	GW	APD
PRICKLY PEAR UF 4-10D-12-15	9	120S	150E	4300750340		Federal	Federal	GW	APD
PRICKLY PEAR UF 8-9D-12-15	9	120S	150E	4300750341		Federal	Federal	GW	APD
PRICKLY PEAR UF 8A-9D-12-15	9	120S	150E	4300750342		Federal	Federal	GW	APD
PRICKLY PEAR UF 7A-9D-12-15	9	120S	150E	4300750343		Federal	Federal	GW	APD
PRICKLY PEAR UF 7-9D-12-15	9	120S	150E	4300750344		Federal	Federal	GW	APD
PRICKLY PEAR UF 1-9D-12-15	9	120S	150E	4300750345		Federal	Federal	GW	APD
PRICKLY PEAR UF 2-9D-12-15	9	120S	150E	4300750346		Federal	Federal	GW	APD
PRICKLY PEAR UF 1-24D-12-1	24	120S	150E	4300750348		Federal	Federal	GW	APD
PRICKLY PEAR UF 9-13D-12-15	13	120S	150E	4300750349		Federal	Federal	GW	APD
PRICKLY PEAR U FED 7-21D-12-15	21	120S	150E	4300750055	14794	Federal	Federal	GW	OPS
PRICKLY PEAR US 1A-16D-12-15	9	120S	150E	4300750192	14794	State	Federal	GW	OPS
PRICKLY PEAR US 2A-16D-12-15	9	120S	150E	4300750193	14794	State	Federal	GW	OPS
PRICKLY PEAR US 2-16D-12-15	9	120S	150E	4300750194	14794	State	Federal	GW	OPS
PRICKLY PEAR UF 9A-9D-12-15	9	120S	150E	4300750196	14794	Federal	Federal	GW	OPS
PRICKLY PEAR UF 10-9D-12-15	9	120S	150E	4300750197	14794	Federal	Federal	GW	OPS
PRICKLY PEAR UF 10A-9D-12-15	9	120S	150E	4300750198	14794	Federal	Federal	GW	OPS

Bill Barrett Corporation (N2165) to EnerVest Operating, LLC (N4040)

Effective 1/1/2014

Prickly Pear Unit

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	Well Status
PRICKLY PEAR UF 14-9D-12-15	9	120S	150E	4300750199	14794	Federal	Federal	GW	OPS
PRICKLY PEAR UF 14A-9D-12-15	9	120S	150E	4300750200	14794	Federal	Federal	GW	OPS
PRICKLY PEAR UF 15-9D-12-15	9	120S	150E	4300750201	14794	Federal	Federal	GW	OPS
PRICKLY PEAR UF 15A-9D-12-15	9	120S	150E	4300750203	14794	Federal	Federal	GW	OPS
PRICKLY PEAR UF 16A-9D-12-15	9	120S	150E	4300750204	14794	Federal	Federal	GW	OPS
STONE CABIN FED 2-B-27	27	120S	150E	4300730018	14794	Federal	Federal	GW	P
PRICKLY PEAR ST 16-15	16	120S	150E	4300730522	14794	State	State	GW	P
PRICKLY PEAR UNIT 21-2	21	120S	150E	4300730828	14794	Federal	Federal	GW	P
PRICKLY PEAR U ST 13-16	16	120S	150E	4300730933	14794	State	State	GW	P
PRICKLY PEAR U ST 11-16	16	120S	150E	4300730944	14794	State	State	GW	P
PRICKLY PEAR U ST 7-16	16	120S	150E	4300730945	14794	State	State	GW	P
PRICKLY PEAR U FED 7-25	25	120S	150E	4300730954	14794	Federal	Federal	GW	P
PRICKLY PEAR U ST 36-06	36	120S	150E	4300731018	14794	State	State	GW	P
PRICKLY PEAR U FED 13-23-12-15	23	120S	150E	4300731073	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 1-27D-12-15	23	120S	150E	4300731074	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3-26D-12-15	23	120S	150E	4300731075	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 15-22D-12-15	23	120S	150E	4300731076	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3-28D-12-15	21	120S	150E	4300731121	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 15-21-12-15	21	120S	150E	4300731164	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 13-21D-12-15	21	120S	150E	4300731166	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 11-17D-12-15	17	120S	150E	4300731184	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 7-22D-12-15	22	120S	150E	4300731186	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3-22-12-15	22	120S	150E	4300731187	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 5-22D-12-15	22	120S	150E	4300731188	14794	Federal	Federal	GW	P
PRICKLY PEAR 11-15D-12-15	22	120S	150E	4300731189	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 9-18D-12-15	18	120S	150E	4300731192	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 15-18-12-15	18	120S	150E	4300731193	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 16-27D-12-15	27	120S	150E	4300731194	15569	Federal	Federal	GW	P
PRICKLY PEAR U FED 12-27D-12-15	27	120S	150E	4300731195	15568	Federal	Federal	GW	P
PRICKLY PEAR U FED 9-20D-12-15	20	120S	150E	4300731197	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 7-20-12-15	20	120S	150E	4300731198	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 1-20-12-15	20	120S	150E	4300731206	14794	Federal	Federal	GW	P
PRICKLY PEAR U ST 4-36-12-15	36	120S	150E	4300731227	14794	State	State	GW	P
PRICKLY PEAR U FED 4-27D-12-15	22	120S	150E	4300731237	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 13-22-12-15	22	120S	150E	4300731238	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3-27D-12-15	22	120S	150E	4300731239	14794	Federal	Federal	GW	P
PRICKLY PEAR U ST 9-16-12-15	16	120S	150E	4300731240	14794	State	State	GW	P
PRICKLY PEAR U FED 9-28D-12-15	28	120S	150E	4300731241	16028	Federal	Federal	GW	P
PRICKLY PEAR U FED 5-27D-12-15	28	120S	150E	4300731242	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 1-28-12-15	28	120S	150E	4300731243	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 8-28D-12-15	28	120S	150E	4300731244	14794	Federal	Federal	GW	P
PRICKLY PEAR U ST 1-16-12-15	16	120S	150E	4300731245	14794	State	State	GW	P
PPU FED 11-18D-12-15	18	120S	150E	4300731257	14794	Federal	Federal	GW	P
PPU FED 11-20D-12-15	20	120S	150E	4300731258	14794	Federal	Federal	GW	P
PPU FED 4-25D-12-15	25	120S	150E	4300731259	14794	Federal	Federal	GW	P
PPU FED 12-25D-12-15	25	120S	150E	4300731260	16068	Federal	Federal	GW	P
PPU FED 14-26D-12-15	35	120S	150E	4300731282	16224	Federal	Federal	GW	P
PPU FED 2-35-12-15	35	120S	150E	4300731283	14794	Federal	Federal	GW	P
PPU FED 10-26D-12-15	35	120S	150E	4300731284	14794	Federal	Federal	GW	P
PPU FED 9-17-12-15	17	120S	150E	4300731287	14794	Federal	Federal	GW	P
PPU FED 1-17D-12-15	17	120S	150E	4300731288	14794	Federal	Federal	GW	P
PPU FED 7-17D-12-15	17	120S	150E	4300731289	14794	Federal	Federal	GW	P
PPU FED 1-18D-12-15	18	120S	150E	4300731294	14794	Federal	Federal	GW	P
PPU FED 7-18D-12-15	18	120S	150E	4300731295	14794	Federal	Federal	GW	P
PPU FED 5-17D-12-15	18	120S	150E	4300731296	14794	Federal	Federal	GW	P
PPU FED 10-17D-12-15	17	120S	150E	4300731307	14794	Federal	Federal	GW	P

Bill Barrett Corporation (N2165) to EnerVest Operating, LLC (N4040)

Effective 1/1/2014

Prickly Pear Unit

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	Well Status
PPU FED 8-17D-12-15	17	120S	150E	4300731308	14794	Federal	Federal	GW	P
PPU FED 12-17D-12-15	17	120S	150E	4300731309	14794	Federal	Federal	GW	P
PPU FED 13-17D-12-15	17	120S	150E	4300731310	14794	Federal	Federal	GW	P
PPU FED 14-17D-12-15	17	120S	150E	4300731311	14794	Federal	Federal	GW	P
PPU FED 16-18D-12-15	17	120S	150E	4300731312	14794	Federal	Federal	GW	P
PPU FED 8-18D-12-15	18	120S	150E	4300731313	14794	Federal	Federal	GW	P
PPU FED 3-18D-12-15	18	120S	150E	4300731314	14794	Federal	Federal	GW	P
PPU FED 4-18-12-15	18	120S	150E	4300731315	14794	Federal	Federal	GW	P
PPU FED 5-18D-12-15	18	120S	150E	4300731316	14794	Federal	Federal	GW	P
PPU FED 6-18D-12-15	18	120S	150E	4300731317	14794	Federal	Federal	GW	P
PPU FED 16-17D-12-15	17	120S	150E	4300731321	14794	Federal	Federal	GW	P
PPU ST 15-16D-12-15	16	120S	150E	4300731322	14794	State	State	GW	P
PPU ST 16-16D-12-15	16	120S	150E	4300731323	14794	State	State	GW	P
PPU ST 14-16D-12-15	16	120S	150E	4300731324	14794	State	State	GW	P
PPU FED 3-21D-12-15	21	120S	150E	4300731328	14794	Federal	Federal	GW	P
PPU FED 4-21D-12-15	21	120S	150E	4300731329	14794	Federal	Federal	GW	P
PPU FED 13-15D-12-15	22	120S	150E	4300731358	14794	Federal	Federal	GW	P
PPU FED 14-15D-12-15	22	120S	150E	4300731359	14794	Federal	Federal	GW	P
PPU FED 4-22D-12-15	22	120S	150E	4300731360	14794	Federal	Federal	GW	P
PPU FED 6-22D-12-15	22	120S	150E	4300731361	14794	Federal	Federal	GW	P
PPU FED 2-28D-12-15	28	120S	150E	4300731362	14794	Federal	Federal	GW	P
PPU FED 16X-21D-12-15	28	120S	150E	4300731363	14794	Federal	Federal	GW	P
PPU FED 5A-27D-12-15	28	120S	150E	4300731364	14794	Federal	Federal	GW	P
PPU FED 1A-28D-12-15	28	120S	150E	4300731368	14794	Federal	Federal	GW	P
PPU FED 14A-18D-12-15	18	120S	150E	4300731393	14794	Federal	Federal	GW	P
PPU FED 10-18D-12-15	18	120S	150E	4300731394	14794	Federal	Federal	GW	P
PPU FED 15A-18D-12-15	18	120S	150E	4300731395	14794	Federal	Federal	GW	P
PPU FED 16A-18D-12-15	18	120S	150E	4300731396	14794	Federal	Federal	GW	P
PPU FED 12-22D-12-15	22	120S	150E	4300731398	14794	Federal	Federal	GW	P
PPU FED 11-22D-12-15	22	120S	150E	4300731399	14794	Federal	Federal	GW	P
PPU FED 14-22D-12-15	22	120S	150E	4300731400	14794	Federal	Federal	GW	P
PPU FED 4A-27D-12-15	22	120S	150E	4300731401	14794	Federal	Federal	GW	P
PPU FED 11-21D-12-15	21	120S	150E	4300731412	14794	Federal	Federal	GW	P
PPU FED 6-21D-12-15	21	120S	150E	4300731413	14794	Federal	Federal	GW	P
PPU FED 12-21D-12-15	21	120S	150E	4300731414	14794	Federal	Federal	GW	P
PPU FED 8-20D-12-15	20	120S	150E	4300731419	14794	Federal	Federal	GW	P
PPU FED 1A-20D-12-15	20	120S	150E	4300731420	14794	Federal	Federal	GW	P
PPU FED 2-20D-12-15	20	120S	150E	4300731421	14794	Federal	Federal	GW	P
PPU ST 7A-16D-12-15	16	120S	150E	4300731422	14794	State	State	GW	P
PPU ST 6-16D-12-15	16	120S	150E	4300731423	14794	State	State	GW	P
PPU ST 10A-16D-12-15	16	120S	150E	4300731424	14794	State	State	GW	P
PPU ST 3-16D-12-15	16	120S	150E	4300731425	14794	State	State	GW	P
PPU FED 5-21D-12-15	21	120S	150E	4300731451	14794	Federal	Federal	GW	P
PPU ST 8-16D-12-15	16	120S	150E	4300731455	14794	State	State	GW	P
PPU ST 12-16D-12-15	16	120S	150E	4300731456	14794	State	State	GW	P
PPU ST 12A-16D-12-15	16	120S	150E	4300731457	14794	State	State	GW	P
PPU ST 15A-16D-12-15	16	120S	150E	4300731458	14794	State	State	GW	P
PPU ST 10-16D-12-15	16	120S	150E	4300731459	14794	State	State	GW	P
PPU ST 11A-16D-12-15	16	120S	150E	4300731460	14794	State	State	GW	P
PPU ST 13A-16D-12-15	16	120S	150E	4300731461	14794	State	State	GW	P
PPU FED 10-7D-12-15	7	120S	150E	4300731470	14794	Federal	Federal	GW	P
PPU FED 15-7D-12-15	7	120S	150E	4300731471	14794	Federal	Federal	GW	P
PPU FED 9-7D-12-15	7	120S	150E	4300731472	14794	Federal	Federal	GW	P
PPU FED 16-7D-12-15	7	120S	150E	4300731473	14794	Federal	Federal	GW	P
PPU ST 6A-16D-12-15	16	120S	150E	4300731477	14794	State	State	GW	P
PPU ST 4-16D-12-15	16	120S	150E	4300731478	14794	State	State	GW	P

Bill Barrett Corporation (N2165) to EnerVest Operating, LLC (N4040)

Effective 1/1/2014

Prickly Pear Unit

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	Well Status
PPU ST 4A-16D-12-15	16	120S	150E	4300731479	14794	State	State	GW	P
PPU ST 5A-16D-12-15	16	120S	150E	4300731480	14794	State	State	GW	P
PPU ST 3A-16D-12-15	16	120S	150E	4300731481	14794	State	State	GW	P
PPU ST 16A-16D-12-15	16	120S	150E	4300731484	14794	State	State	GW	P
PPU ST 9A-16D-12-15	16	120S	150E	4300731485	14794	State	State	GW	P
PPU ST 16B-16D-12-15	16	120S	150E	4300731514	14794	State	State	GW	P
PPU ST 14B-16D-12-15	16	120S	150E	4300731515	14794	State	State	GW	P
PPU ST 13B-16D-12-15	16	120S	150E	4300731516	14794	State	State	GW	P
PRICKLY PEAR U FED 9-22D-12-15	22	120S	150E	4300750041	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 10-22D-12-15	22	120S	150E	4300750042	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 16-22D-12-15	22	120S	150E	4300750043	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 2-27D-12-15	22	120S	150E	4300750044	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 16-15D-12-15	15	120S	150E	4300750045	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 15-15D-12-15	15	120S	150E	4300750046	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 10-15D-12-15	15	120S	150E	4300750047	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 9-15D-12-15	15	120S	150E	4300750048	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 11A-15D-12-15	15	120S	150E	4300750049	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 1-21D-12-15	21	120S	150E	4300750050	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 2-21D-12-15	21	120S	150E	4300750051	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 2A-21D-12-15	21	120S	150E	4300750052	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 4A-22D-12-15	21	120S	150E	4300750053	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 5A-22D-12-15	21	120S	150E	4300750054	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 7A-21D-12-15	21	120S	150E	4300750056	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 8-21D-12-15	21	120S	150E	4300750057	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 8A-21D-12-15	21	120S	150E	4300750058	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 16-8D-12-15	8	120S	150E	4300750059	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 15-8D-12-15	8	120S	150E	4300750060	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 2-17D-12-15	8	120S	150E	4300750061	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 1A-17D-12-15	8	120S	150E	4300750062	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 1-22D-12-15	22	120S	150E	4300750076	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 2-22D-12-15	22	120S	150E	4300750077	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 8-22D-12-15	22	120S	150E	4300750078	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3-17D-12-15	17	120S	150E	4300750079	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3A-17D-12-15	17	120S	150E	4300750080	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 4-17D-12-15	17	120S	150E	4300750081	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 4A-17D-12-15	17	120S	150E	4300750082	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 5A-17D-12-15	17	120S	150E	4300750083	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 6-17D-12-15	17	120S	150E	4300750084	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 6A-17D-12-15	17	120S	150E	4300750085	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 7A-17D-12-15	17	120S	150E	4300750086	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 9-12D-12-14	12	120S	140E	4300750088	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 10-12D-12-14	12	120S	140E	4300750089	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 15-12D-12-14	12	120S	140E	4300750090	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 16-12D-12-14	12	120S	140E	4300750091	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3-20D-12-15	20	120S	150E	4300750098	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 3A-20D-12-15	20	120S	150E	4300750099	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 4-20D-12-15	20	120S	150E	4300750100	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 4A-20D-12-15	20	120S	150E	4300750101	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 5-20D-12-15	20	120S	150E	4300750102	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 5A-20D-12-15	20	120S	150E	4300750103	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 6-20D-12-15	20	120S	150E	4300750104	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 6A-20D-12-15	20	120S	150E	4300750105	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 11A-20D-12-15	20	120S	150E	4300750106	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 12A-20D-12-15	20	120S	150E	4300750107	14794	Federal	Federal	GW	P
PRICKLY PEAR U FED 13A-17D-12-15	20	120S	150E	4300750108	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 7A-18D-12-15	17	120S	150E	4300750136	14794	Federal	Federal	GW	P

Bill Barrett Corporation (N2165) to EnerVest Operating, LLC (N4040)

Effective 1/1/2014

Prickly Pear Unit

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	Well Status
PRICKLY PEAR UF 8A-18D-12-15	17	120S	150E	4300750137	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 9A-18D-12-15	17	120S	150E	4300750138	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 12-20D-12-15	20	120S	150E	4300750139	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 16A-8D-12-15	8	120S	150E	4300750140	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 15A-8D-12-15	8	120S	150E	4300750141	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 13A-9D-12-15	8	120S	150E	4300750142	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 13-9D-12-15	8	120S	150E	4300750143	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 12-9D-12-15	8	120S	150E	4300750144	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 10-8D-12-15	8	120S	150E	4300750145	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 9-8D-12-15	8	120S	150E	4300750146	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 2A-17D-12-15	8	120S	150E	4300750147	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 1A-22D-12-15	22	120S	150E	4300750171	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 2A-22D-12-15	22	120S	150E	4300750172	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 6A-22D-12-15	22	120S	150E	4300750173	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 7A-22D-12-15	22	120S	150E	4300750174	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 8A-22D-12-15	22	120S	150E	4300750175	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 14B-15D-12-15	22	120S	150E	4300750176	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 9-9D-12-15	9	120S	150E	4300750195	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 16-9D-12-15	9	120S	150E	4300750202	14794	Federal	Federal	GW	P
PRICKLY PEAR UF 8-14D-12-15	14	120S	150E	4300750216	18289	Federal	Federal	GW	P
PRICKLY PEAR UF 15-14D-12-15	14	120S	150E	4300750221	18290	Federal	Federal	GW	P
PRICKLY PEAR U ST 5-16	16	120S	150E	4300730943	14794	State	State	GW	S
PRICKLY PEAR U FED 7-28D-12-15	21	120S	150E	4300731165	14794	Federal	Federal	GW	S
PRICKLY PEAR U FED 15-17-12-15	17	120S	150E	4300731183	14794	Federal	Federal	GW	S
PRICKLY PEAR U FED 10-27-12-15	27	120S	150E	4300731196	15570	Federal	Federal	GW	S
PPU FED 4-35D-12-15	35	120S	150E	4300731285	16223	Federal	Federal	GW	S
PRICKLY PEAR U FED 12A-17D-12-15	17	120S	150E	4300750087	14794	Federal	Federal	GW	S

COPY

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: (see attached well list)
2. NAME OF OPERATOR: ENERVEST OPERATING, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 1001 FANNIN, ST. STE 800 CITY HOUSTON STATE TX ZIP 77002		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: (see attached well list) QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		8. WELL NAME and NUMBER: (see attached well list)
PHONE NUMBER: (713) 659-3500		9. API NUMBER:
		10. FIELD AND POOL, OR WILDCAT:
		COUNTY:
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>1/1/2014</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
ENERVEST OPERATING, LLC IS SUBMITTING THIS SUNDRY AS NOTIFICATION THAT THE WELLS LISTED ON THE ATTACHED LIST HAVE BEEN SOLD TO ENERVEST OPERATING, LLC BY BILL BARRETT CORPORATION EFFECTIVE 1/1/2014. PLEASE REFER ALL FUTURE CORRESPONDENCE TO THE ADDRESS BELOW.

EnerVest Operating, L.L.C.
1001 Fannin, Suite 800
Houston, Texas 77002
713-659-3500
(BLM BOND # RLB 7886, STATE/FEE BOND # B008321)

BILL BARRETT CORPORATION
Duane Zavadil NAME (PLEASE PRINT)
Duane Zavadil SIGNATURE
Senior Vice President -
EH&S, Government and Regulatory Affairs N2165

ENERVEST OPERATING, LLC
RONNIE L YOUNG NAME (PLEASE PRINT)
Ronnie L Young SIGNATURE
DIRECTOR - REGULATORY N4040

NAME (PLEASE PRINT) RONNIE YOUNG TITLE DIRECTOR - REGULATORY
SIGNATURE Ronnie L Young DATE 12/10/2013

(This space for State use on) **APPROVED**
JAN 28 2014 4-PM
DIV. OF OIL, GAS & MINING
Rachel Medina

RECEIVED
JAN 07 2014

UDOGM CHANGE OF OPERATOR WELL LIST

Well Name	Sec	TWN	RNG	API Number	Entity	Lease	Well Type	Well Status	Unit
JACK CANYON UNIT 8-32	32	120S	160E	4300730460	15167	State	WI	A	
JACK CYN U ST 14-32	32	120S	160E	4300730913	15166	State	WD	A	
PRICKLY PEAR U FED 12-24	24	120S	140E	4300730953	14467	Federal	WD	A	
PPU FED 11-23D-12-15	23	120S	150E	4300731440		Federal	GW	APD	PRICKLY PEAR
PPU FED 4-26D-12-15	23	120S	150E	4300731441		Federal	GW	APD	PRICKLY PEAR
PPU FED 14-23D-12-15	23	120S	150E	4300731442		Federal	GW	APD	PRICKLY PEAR
PPU FED 12-23D-12-15	23	120S	150E	4300731443		Federal	GW	APD	PRICKLY PEAR
PPU FED 11-34D-12-16	34	120S	160E	4300731465		Federal	GW	APD	PETERS POINT
PPU FED 10-34D-12-16	34	120S	160E	4300731469		Federal	GW	APD	PETERS POINT
HORSE BENCH FED 4-27D-12-16	27	120S	160E	4300750092		Federal	GW	APD	
HORSE BENCH FED 5-27D-12-16	27	120S	160E	4300750093		Federal	GW	APD	
PRICKLY PEAR U FED 12-7D-12-15	07	120S	150E	4300750094		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR U FED 11-7D-12-15	07	120S	150E	4300750095		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR U FED 13-7D-12-15	07	120S	150E	4300750096		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR U FED 14-7D-12-15	07	120S	150E	4300750097		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11-8D-12-15	08	120S	150E	4300750124		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12-8D-12-15	08	120S	150E	4300750125		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13-8D-12-15	08	120S	150E	4300750126		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 14-8D-12-15	08	120S	150E	4300750127		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9-21D-12-15	21	120S	150E	4300750128		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-21D-12-15	21	120S	150E	4300750129		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10-21D-12-15	21	120S	150E	4300750130		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10A-21D-12-15	21	120S	150E	4300750131		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-21D-12-15	21	120S	150E	4300750132		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15X-21D-12-15	21	120S	150E	4300750133		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16-21D-12-15	21	120S	150E	4300750134		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-21D-12-15	21	120S	150E	4300750135		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13A-22D-12-15	21	120S	150E	4300750148		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 1A-27D-12-15	22	120S	150E	4300750161		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 2A-27D-12-15	22	120S	150E	4300750162		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3A-27D-12-15	22	120S	150E	4300750163		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-22D-12-15	22	120S	150E	4300750164		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10A-22D-12-15	22	120S	150E	4300750165		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11A-22D-12-15	22	120S	150E	4300750166		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12A-22D-12-15	22	120S	150E	4300750167		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 14A-22D-12-15	22	120S	150E	4300750168		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-22D-12-15	22	120S	150E	4300750169		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-22D-12-15	22	120S	150E	4300750170		Federal	GW	APD	PRICKLY PEAR
PETERS POINT UF 15X-36D-12-16	36	120S	160E	4300750178		Federal	GW	APD	PETERS POINT
PRICKLY PEAR UF 15A-15D-12-15	15	120S	150E	4300750180		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11B-15D-12-15	15	120S	150E	4300750181		Federal	GW	APD	PRICKLY PEAR
PETERS POINT UF 10-1D-13-16	36	120S	160E	4300750182		Federal	GW	APD	PETERS POINT
PETERS POINT UF 9-1D-13-16	36	120S	160E	4300750183		Federal	GW	APD	PETERS POINT
PRICKLY PEAR UF 16A-15D-12-15	15	120S	150E	4300750184		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3A-18D-12-15	07	120S	150E	4300750185		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 4A-18D-12-15	07	120S	150E	4300750186		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11A-7D-12-15	07	120S	150E	4300750187		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 2-18D-12-15	07	120S	150E	4300750188		Federal	GW	APD	PRICKLY PEAR

UDOGM CHANGE OF OPERATOR WELL LIST

PRICKLY PEAR UF 12A-7D-12-15	07	120S	150E	4300750189	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13A-7D-12-15	07	120S	150E	4300750190	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 14A-7D-12-15	07	120S	150E	4300750191	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR FEDERAL 1-12D-12-14	12	120S	140E	4300750205	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 2-12D-12-14	12	120S	140E	4300750206	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7-12D-12-14	12	120S	140E	4300750207	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7A-12D-12-14	12	120S	140E	4300750208	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8-12D-12-14	12	120S	140E	4300750209	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 4-7D-12-15	12	120S	140E	4300750210	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5-7D-12-15	12	120S	140E	4300750211	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8A-12D-12-14	12	120S	140E	4300750212	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5A-7D-12-15	12	120S	140E	4300750213	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7-14D-12-15	14	120S	150E	4300750214	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7A-14D-12-15	14	120S	150E	4300750215	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9-14D-12-15	14	120S	150E	4300750217	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-14D-12-15	14	120S	150E	4300750218	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10-14D-12-15	14	120S	150E	4300750219	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10A-14D-12-15	14	120S	150E	4300750220	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-14D-12-15	14	120S	150E	4300750222	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16-14D-12-15	14	120S	150E	4300750223	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-14D-12-15	14	120S	150E	4300750224	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 1A-18D-12-15	07	120S	150E	4300750225	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 2A-18D-12-15	07	120S	150E	4300750226	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-7D-12-15	07	120S	150E	4300750227	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10A-7D-12-15	07	120S	150E	4300750228	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-7D-12-15	07	120S	150E	4300750229	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-7D-12-15	07	120S	150E	4300750230	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-12D-12-14	12	120S	140E	4300750233	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10A-12D-12-14	12	120S	140E	4300750234	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-12D-12-14	12	120S	140E	4300750235	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12A-8D-12-15	08	120S	150E	4300750236	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-12D-12-14	12	120S	140E	4300750237	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11A-8D-12-15	08	120S	150E	4300750238	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13A-8D-12-15	08	120S	150E	4300750239	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 14A-8D-12-15	08	120S	150E	4300750240	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5A-8D-12-15	08	120S	150E	4300750260	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6A-8D-12-15	08	120S	150E	4300750261	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 4-8D-12-15	08	120S	150E	4300750262	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3-8D-12-15	08	120S	150E	4300750263	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 2-8D-12-15	08	120S	150E	4300750264	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7A-8D-12-15	08	120S	150E	4300750265	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7-8D-12-15	08	120S	150E	4300750266	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5-8D-12-15	08	120S	150E	4300750267	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6-8D-12-15	08	120S	150E	4300750268	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10A-8D-12-15	08	120S	150E	4300750269	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-8D-12-15	08	120S	150E	4300750270	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8-8D-12-15	08	120S	150E	4300750271	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 1-8D-12-15	08	120S	150E	4300750272	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8A-8D-12-15	08	120S	150E	4300750273	Federal	GW	APD	PRICKLY PEAR

UDOGM CHANGE OF OPERATOR WELL LIST

PRICKLY PEAR UF 5-9D-12-15	09	120S	150E	4300750274	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5A-9D-12-15	09	120S	150E	4300750275	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 4-9D-12-15	09	120S	150E	4300750276	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3-9D-12-15	09	120S	150E	4300750277	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6A-9D-12-15	09	120S	150E	4300750278	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11-9D-12-15	09	120S	150E	4300750279	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12A-9D-12-15	09	120S	150E	4300750280	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6-9D-12-15	09	120S	150E	4300750281	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11A-9D-12-15	09	120S	150E	4300750282	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR US 1X-16D-12-15	10	120S	150E	4300750283	State	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5A-15D-12-15	10	120S	150E	4300750284	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6A-15D-12-15	10	120S	150E	4300750285	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3-15D-13-15	10	120S	150E	4300750286	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-10D-12-15	15	120S	150E	4300750287	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13-10D-12-15	10	120S	150E	4300750288	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15-10D-12-15	15	120S	150E	4300750289	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-10D-12-15	15	120S	150E	4300750290	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9-10D-12-15	15	120S	150E	4300750291	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 14A-10D-12-15	10	120S	150E	4300750292	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10-10D-12-15	15	120S	150E	4300750293	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16-10D-12-15	15	120S	150E	4300750294	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13-11D-12-15	15	120S	150E	4300750295	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13A-11D-12-15	15	120S	150E	4300750296	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12-11D-12-15	15	120S	150E	4300750297	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 13A-10D-12-15	10	120S	150E	4300750298	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12-10D-12-15	10	120S	150E	4300750299	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11-10D-12-15	10	120S	150E	4300750300	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3A-15D-12-15	10	120S	150E	4300750301	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12-14D-12-15	14	120S	150E	4300750302	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 4-15D-12-15	10	120S	150E	4300750303	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 4A-15D-12-15	10	120S	150E	4300750304	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 14-10D-12-15	10	120S	150E	4300750305	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-17D-12-15	17	120S	150E	4300750306	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8A-17D-12-15	17	120S	150E	4300750307	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10A-17D-12-15	17	120S	150E	4300750308	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3-7D-12-15	07	120S	150E	4300750309	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-17D-12-15	17	120S	150E	4300750310	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6-7D-12-15	07	120S	150E	4300750311	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-17D-12-15	17	120S	150E	4300750312	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6A-7D-12-15	07	120S	150E	4300750313	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7A-7D-12-15	07	120S	150E	4300750314	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8A-7D-12-15	07	120S	150E	4300750315	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6X-17D-12-15	17	120S	150E	4300750316	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11A-17D-12-15	17	120S	150E	4300750317	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15B-17D-12-15	17	120S	150E	4300750318	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8A-20D-12-15	20	120S	150E	4300750319	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 1-7D-12-15	07	120S	150E	4300750320	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7A-20D-12-15	20	120S	150E	4300750321	Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9A-20D-12-15	20	120S	150E	4300750322	Federal	GW	APD	PRICKLY PEAR

UDOGM CHANGE OF OPERATOR WELL LIST

PRICKLY PEAR UF 10A-20D-12-15	20	120S	150E	4300750323		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 10-20D-12-15	20	120S	150E	4300750324		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 2-7D-12-15	07	120S	150E	4300750325		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 14A-20D-12-15	20	120S	150E	4300750326		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 16A-20D-12-15	20	120S	150E	4300750327		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15A-20D-12-15	20	120S	150E	4300750328		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8-7D-12-15	07	120S	150E	4300750329		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 15-20D-12-15	20	120S	150E	4300750330		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7-7D-12-15	07	120S	150E	4300750331		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6-10D-12-15	09	120S	150E	4300750332		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5A-10D-12-15	09	120S	150E	4300750333		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 11A-10D-12-15	09	120S	150E	4300750334		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 6A-10D-12-15	09	120S	150E	4300750335		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 5-10D-12-15	09	120S	150E	4300750336		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 12A-10D-12-15	09	120S	150E	4300750338		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 3-10D-12-15	09	120S	150E	4300750339		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 4-10D-12-15	09	120S	150E	4300750340		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8-9D-12-15	09	120S	150E	4300750341		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 8A-9D-12-15	09	120S	150E	4300750342		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7A-9D-12-15	09	120S	150E	4300750343		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 7-9D-12-15	09	120S	150E	4300750344		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 1-9D-12-15	09	120S	150E	4300750345		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 2-9D-12-15	09	120S	150E	4300750346		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 1-24D-12-1	24	120S	150E	4300750348		Federal	GW	APD	PRICKLY PEAR
PRICKLY PEAR UF 9-13D-12-15	13	120S	150E	4300750349		Federal	GW	APD	PRICKLY PEAR
HORSE BENCH FED 4-20D-12-17	19	120S	170E	4300750350		Federal	GW	APD	
Horse Bench Federal 16-18D-12-17	19	120S	170E	4300750351		Federal	GW	APD	
PPU FED 9-34D-12-16	34	120S	160E	4300731430	17225	Federal	GW	OPS	PETERS POINT
PPU FED 15-35D-12-16	35	120S	160E	4300731475	2470	Federal	GW	OPS	PETERS POINT
PETERS POINT U FED 12A-6D-13-17	31	120S	170E	4300750034	2470	Federal	GW	OPS	PETERS POINT
PETERS POINT U FED 11A-31D-12-17	31	120S	170E	4300750036	2470	Federal	GW	OPS	PETERS POINT
PRICKLY PEAR U FED 7-21D-12-15	21	120S	150E	4300750055	14794	Federal	GW	OPS	PRICKLY PEAR
PETERS POINT U FED 9-6D-13-17	06	130S	170E	4300750120	2470	Federal	GW	OPS	PETERS POINT
PETERS POINT U FED 14-6D-13-17	06	130S	170E	4300750121	2470	Federal	GW	OPS	PETERS POINT
PETERS POINT U FED 15-6D-13-17	06	130S	170E	4300750122	2470	Federal	GW	OPS	PETERS POINT
PETERS POINT UF 2-7D-13-17	06	130S	170E	4300750149	2470	Federal	GW	OPS	PETERS POINT
PETERS POINT UF 1-7D-13-17	06	130S	170E	4300750150	2470	Federal	GW	OPS	PETERS POINT
PRICKLY PEAR US 1A-16D-12-15	09	120S	150E	4300750192	14794	State	GW	OPS	PRICKLY PEAR
PRICKLY PEAR US 2A-16D-12-15	09	120S	150E	4300750193	14794	State	GW	OPS	PRICKLY PEAR
PRICKLY PEAR US 2-16D-12-15	09	120S	150E	4300750194	14794	State	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 9A-9D-12-15	09	120S	150E	4300750196	14794	Federal	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 10-9D-12-15	09	120S	150E	4300750197	14794	Federal	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 10A-9D-12-15	09	120S	150E	4300750198	14794	Federal	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 14-9D-12-15	09	120S	150E	4300750199	14794	Federal	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 14A-9D-12-15	09	120S	150E	4300750200	14794	Federal	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 15-9D-12-15	09	120S	150E	4300750201	14794	Federal	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 15A-9D-12-15	09	120S	150E	4300750203	14794	Federal	GW	OPS	PRICKLY PEAR
PRICKLY PEAR UF 16A-9D-12-15	09	120S	150E	4300750204	14794	Federal	GW	OPS	PRICKLY PEAR
SHARPLES 1 GOVT PICKRELL	11	120S	150E	4300716045	7030	Federal	GW	P	

UDOGM CHANGE OF OPERATOR WELL LIST

STONE CABIN UNIT 1	13	120S	140E	4300716542	12052 Federal	GW	P	
STONE CABIN FED 1-11	11	120S	140E	4300730014	6046 Federal	GW	P	
STONE CABIN FED 2-B-27	27	120S	150E	4300730018	14794 Federal	GW	P	PRICKLY PEAR
JACK CANYON 101-A	33	120S	160E	4300730049	2455 Federal	GW	P	
PETERS POINT ST 2-2-13-16	02	130S	160E	4300730521	14387 State	GW	P	
PRICKLY PEAR ST 16-15	16	120S	150E	4300730522	14794 State	GW	P	PRICKLY PEAR
PETERS POINT U FED 36-2	36	120S	160E	4300730761	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 36-3	36	120S	160E	4300730762	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 36-4	36	120S	160E	4300730763	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 14-25D-12-16	36	120S	160E	4300730764	2470 Federal	GW	P	PETERS POINT
HUNT RANCH 3-4	03	120S	150E	4300730775	13158 State	GW	P	
PETERS POINT U FED 4-31D-12-17	36	120S	160E	4300730810	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 16-26D-12-16	36	120S	160E	4300730812	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR UNIT 13-4	13	120S	140E	4300730825	14353 Federal	GW	P	
PRICKLY PEAR UNIT 21-2	21	120S	150E	4300730828	14794 Federal	GW	P	PRICKLY PEAR
PETERS POINT U FED 6-7D-13-17	06	130S	170E	4300730859	14692 Federal	GW	P	PETERS POINT
PETERS POINT ST 4-2-13-16	02	130S	160E	4300730866	14386 State	GW	P	
PRICKLY PEAR U ST 13-16	16	120S	150E	4300730933	14794 State	GW	P	PRICKLY PEAR
PRICKLY PEAR U ST 11-16	16	120S	150E	4300730944	14794 State	GW	P	PRICKLY PEAR
PRICKLY PEAR U ST 7-16	16	120S	150E	4300730945	14794 State	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 7-25	25	120S	150E	4300730954	14794 Federal	GW	P	PRICKLY PEAR
PETERS POINT U FED 16-35	35	120S	160E	4300730965	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 11-6-13-17	06	130S	170E	4300730982	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 16-6D-13-17	06	130S	170E	4300731004	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 16-31D-12-17	06	130S	170E	4300731005	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR U FED 5-13-12-14	13	120S	140E	4300731008	14897 Federal	GW	P	
PETERS POINT U FED 12-31D-12-17	36	120S	160E	4300731009	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 2-36D-12-16	36	120S	160E	4300731010	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 9-36-12-16	36	120S	160E	4300731011	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR U ST 36-06	36	120S	150E	4300731018	14794 State	GW	P	PRICKLY PEAR
PETERS POINT U FED 8-35D-12-16	36	120S	160E	4300731024	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 4-12D-13-16	02	130S	160E	4300731049	14692 Federal	GW	P	PETERS POINT
PETERS POINT ST 5-2D-13-16 DEEP	02	130S	160E	4300731056	15909 State	GW	P	
PRICKLY PEAR U FED 13-23-12-15	23	120S	150E	4300731073	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 1-27D-12-15	23	120S	150E	4300731074	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 3-26D-12-15	23	120S	150E	4300731075	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 15-22D-12-15	23	120S	150E	4300731076	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 3-28D-12-15	21	120S	150E	4300731121	14794 Federal	GW	P	PRICKLY PEAR
PETERS POINT U FED 2-12D-13-16	06	130S	170E	4300731158	14692 Federal	GW	P	PETERS POINT
PRICKLY PEAR U FED 15-21-12-15	21	120S	150E	4300731164	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 7-28D-12-15	21	120S	150E	4300731165	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 13-21D-12-15	21	120S	150E	4300731166	14794 Federal	GW	P	PRICKLY PEAR
PETERS POINT U FED 10-36D-12-16	36	120S	160E	4300731174	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 12-36D-12-16	36	120S	160E	4300731175	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR U FED 15-17-12-15	17	120S	150E	4300731183	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 11-17D-12-15	17	120S	150E	4300731184	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 7-22D-12-15	22	120S	150E	4300731186	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 3-22-12-15	22	120S	150E	4300731187	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 5-22D-12-15	22	120S	150E	4300731188	14794 Federal	GW	P	PRICKLY PEAR

UDOGM CHANGE OF OPERATOR WELL LIST

PRICKLY PEAR 11-15D-12-15	22	120S	150E	4300731189	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 9-18D-12-15	18	120S	150E	4300731192	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 15-18-12-15	18	120S	150E	4300731193	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 16-27D-12-15	27	120S	150E	4300731194	15569	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 12-27D-12-15	27	120S	150E	4300731195	15568	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 10-27-12-15	27	120S	150E	4300731196	15570	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 9-20D-12-15	20	120S	150E	4300731197	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 7-20-12-15	20	120S	150E	4300731198	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 1-20-12-15	20	120S	150E	4300731206	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U ST 2-36-12-15	36	120S	150E	4300731226	15719	State	GW	P	
PRICKLY PEAR U ST 4-36-12-15	36	120S	150E	4300731227	14794	State	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 4-27D-12-15	22	120S	150E	4300731237	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 13-22-12-15	22	120S	150E	4300731238	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 3-27D-12-15	22	120S	150E	4300731239	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U ST 9-16-12-15	16	120S	150E	4300731240	14794	State	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 9-28D-12-15	28	120S	150E	4300731241	16028	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 5-27D-12-15	28	120S	150E	4300731242	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 1-28-12-15	28	120S	150E	4300731243	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 8-28D-12-15	28	120S	150E	4300731244	14794	Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U ST 1-16-12-15	16	120S	150E	4300731245	14794	State	GW	P	PRICKLY PEAR
PPU FED 11-18D-12-15	18	120S	150E	4300731257	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 11-20D-12-15	20	120S	150E	4300731258	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 4-25D-12-15	25	120S	150E	4300731259	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 12-25D-12-15	25	120S	150E	4300731260	16068	Federal	GW	P	PRICKLY PEAR
PPU FED 15-6D-13-17	06	130S	170E	4300731261	16103	Federal	GW	P	PETERS POINT
PP UF 3-36-12-16	36	120S	160E	4300731271	2470	Federal	GW	P	PETERS POINT
PP UF 6-36-12-16	36	120S	160E	4300731272	2470	Federal	GW	P	PETERS POINT
PPU FED 6-35D-12-16	35	120S	160E	4300731275	2470	Federal	GW	P	PETERS POINT
PPU FED 14-26D-12-16	26	120S	160E	4300731277	2470	Federal	GW	P	PETERS POINT
PPU FED 8-34-12-16	34	120S	160E	4300731279	2470	Federal	GW	P	PETERS POINT
PP ST 8-2D-13-16 (DEEP)	02	130S	160E	4300731280	16069	State	GW	P	
PPU FED 6-34D-12-16	34	120S	160E	4300731281	2470	Federal	GW	P	PETERS POINT
PPU FED 14-26D-12-15	35	120S	150E	4300731282	16224	Federal	GW	P	PRICKLY PEAR
PPU FED 2-35-12-15	35	120S	150E	4300731283	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 10-26D-12-15	35	120S	150E	4300731284	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 9-17-12-15	17	120S	150E	4300731287	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 1-17D-12-15	17	120S	150E	4300731288	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 7-17D-12-15	17	120S	150E	4300731289	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 7-1D-13-16 ULTRA DEEP	06	130S	170E	4300731293	14692	Federal	GW	P	PETERS POINT
PPU FED 1-18D-12-15	18	120S	150E	4300731294	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 7-18D-12-15	18	120S	150E	4300731295	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 5-17D-12-15	18	120S	150E	4300731296	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 10-17D-12-15	17	120S	150E	4300731307	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 8-17D-12-15	17	120S	150E	4300731308	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 12-17D-12-15	17	120S	150E	4300731309	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 13-17D-12-15	17	120S	150E	4300731310	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 14-17D-12-15	17	120S	150E	4300731311	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 16-18D-12-15	17	120S	150E	4300731312	14794	Federal	GW	P	PRICKLY PEAR
PPU FED 8-18D-12-15	18	120S	150E	4300731313	14794	Federal	GW	P	PRICKLY PEAR

UDOGM CHANGE OF OPERATOR WELL LIST

PPU FED 3-18D-12-15	18	120S	150E	4300731314	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 4-18-12-15	18	120S	150E	4300731315	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 5-18D-12-15	18	120S	150E	4300731316	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 6-18D-12-15	18	120S	150E	4300731317	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 16-27-12-16	27	120S	160E	4300731318	2470 Federal	GW	P	PETERS POINT
PPU FED 10-27D-12-16	27	120S	160E	4300731319	2470 Federal	GW	P	PETERS POINT
PPU FED 2-34D-12-16	34	120S	160E	4300731320	2470 Federal	GW	P	PETERS POINT
PPU FED 16-17D-12-15	17	120S	150E	4300731321	14794 Federal	GW	P	PRICKLY PEAR
PPU ST 15-16D-12-15	16	120S	150E	4300731322	14794 State	GW	P	PRICKLY PEAR
PPU ST 16-16D-12-15	16	120S	150E	4300731323	14794 State	GW	P	PRICKLY PEAR
PPU ST 14-16D-12-15	16	120S	150E	4300731324	14794 State	GW	P	PRICKLY PEAR
PPU FED 2-7D-13-17 DEEP	06	130S	170E	4300731326	14692 Federal	GW	P	PETERS POINT
PPU FED 3-21D-12-15	21	120S	150E	4300731328	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 4-21D-12-15	21	120S	150E	4300731329	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 2-35D-12-16	35	120S	160E	4300731345	2470 Federal	GW	P	PETERS POINT
PPU FED 7-35D-12-16	35	120S	160E	4300731346	2470 Federal	GW	P	PETERS POINT
PPU FED 4-35D-12-16	35	120S	160E	4300731347	2470 Federal	GW	P	PETERS POINT
PPU FED 7-36D-12-16	36	120S	160E	4300731348	2470 Federal	GW	P	PETERS POINT
PPU FED 11-36D-12-16	36	120S	160E	4300731349	2470 Federal	GW	P	PETERS POINT
PPU FED 15-25D-12-16	36	120S	160E	4300731351	2470 Federal	GW	P	PETERS POINT
PPU FED 13-25D-12-16	36	120S	160E	4300731352	2470 Federal	GW	P	PETERS POINT
PPU FED 4-36D-12-16	36	120S	160E	4300731353	2470 Federal	GW	P	PETERS POINT
PPU FED 13-15D-12-15	22	120S	150E	4300731358	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 14-15D-12-15	22	120S	150E	4300731359	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 4-22D-12-15	22	120S	150E	4300731360	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 6-22D-12-15	22	120S	150E	4300731361	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 2-28D-12-15	28	120S	150E	4300731362	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 16X-21D-12-15	28	120S	150E	4300731363	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 5A-27D-12-15	28	120S	150E	4300731364	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 1-35D-12-16	35	120S	160E	4300731365	2470 Federal	GW	P	PETERS POINT
PPU FED 1A-28D-12-15	28	120S	150E	4300731368	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 14A-18D-12-15	18	120S	150E	4300731393	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 10-18D-12-15	18	120S	150E	4300731394	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 15A-18D-12-15	18	120S	150E	4300731395	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 16A-18D-12-15	18	120S	150E	4300731396	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 12-22D-12-15	22	120S	150E	4300731398	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 11-22D-12-15	22	120S	150E	4300731399	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 14-22D-12-15	22	120S	150E	4300731400	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 4A-27D-12-15	22	120S	150E	4300731401	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 13-26D-12-16	26	120S	160E	4300731403	2470 Federal	GW	P	PETERS POINT
PPU FED 15-26D-12-16	26	120S	160E	4300731404	2470 Federal	GW	P	PETERS POINT
PPU FED 3-35D-12-16	26	120S	160E	4300731405	2470 Federal	GW	P	PETERS POINT
PPU FED 10-26D-12-16	26	120S	160E	4300731406	2470 Federal	GW	P	PETERS POINT
PPU FED 11-26D-12-16	26	120S	160E	4300731407	2470 Federal	GW	P	PETERS POINT
PPU FED 12-26D-12-16	26	120S	160E	4300731408	2470 Federal	GW	P	PETERS POINT
PPU FED 11-27D-12-16	27	120S	160E	4300731409	2470 Federal	GW	P	PETERS POINT
PPU FED 15-27D-12-16	27	120S	160E	4300731410	2470 Federal	GW	P	PETERS POINT
PPU FED 9-27D-12-16	27	120S	160E	4300731411	2470 Federal	GW	P	PETERS POINT
PPU FED 11-21D-12-15	21	120S	150E	4300731412	14794 Federal	GW	P	PRICKLY PEAR

UDOGM CHANGE OF OPERATOR WELL LIST

PPU FED 6-21D-12-15	21	120S	150E	4300731413	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 12-21D-12-15	21	120S	150E	4300731414	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 8-20D-12-15	20	120S	150E	4300731419	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 1A-20D-12-15	20	120S	150E	4300731420	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 2-20D-12-15	20	120S	150E	4300731421	14794 Federal	GW	P	PRICKLY PEAR
PPU ST 7A-16D-12-15	16	120S	150E	4300731422	14794 State	GW	P	PRICKLY PEAR
PPU ST 6-16D-12-15	16	120S	150E	4300731423	14794 State	GW	P	PRICKLY PEAR
PPU ST 10A-16D-12-15	16	120S	150E	4300731424	14794 State	GW	P	PRICKLY PEAR
PPU ST 3-16D-12-15	16	120S	150E	4300731425	14794 State	GW	P	PRICKLY PEAR
PPU FED 1-34D-12-16	34	120S	160E	4300731427	2470 Federal	GW	P	PETERS POINT
PPU FED 7-34D-12-16	34	120S	160E	4300731428	2470 Federal	GW	P	PETERS POINT
PPU FED 5-35D-12-16	34	120S	160E	4300731429	2470 Federal	GW	P	PETERS POINT
PPU FED 5-21D-12-15	21	120S	150E	4300731451	14794 Federal	GW	P	PRICKLY PEAR
PPU ST 8-16D-12-15	16	120S	150E	4300731455	14794 State	GW	P	PRICKLY PEAR
PPU ST 12-16D-12-15	16	120S	150E	4300731456	14794 State	GW	P	PRICKLY PEAR
PPU ST 12A-16D-12-15	16	120S	150E	4300731457	14794 State	GW	P	PRICKLY PEAR
PPU ST 15A-16D-12-15	16	120S	150E	4300731458	14794 State	GW	P	PRICKLY PEAR
PPU ST 10-16D-12-15	16	120S	150E	4300731459	14794 State	GW	P	PRICKLY PEAR
PPU ST 11A-16D-12-15	16	120S	150E	4300731460	14794 State	GW	P	PRICKLY PEAR
PPU ST 13A-16D-12-15	16	120S	150E	4300731461	14794 State	GW	P	PRICKLY PEAR
PPU FED 3-34D-12-16	34	120S	160E	4300731466	2470 Federal	GW	P	PETERS POINT
PPU FED 5-34D-12-16	34	120S	160E	4300731467	2470 Federal	GW	P	PETERS POINT
PPU FED 4-34D-12-16	34	120S	160E	4300731468	2470 Federal	GW	P	PETERS POINT
PPU FED 10-7D-12-15	07	120S	150E	4300731470	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 15-7D-12-15	07	120S	150E	4300731471	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 9-7D-12-15	07	120S	150E	4300731472	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 16-7D-12-15	07	120S	150E	4300731473	14794 Federal	GW	P	PRICKLY PEAR
PPU FED 10-35D-12-16	35	120S	160E	4300731474	2470 Federal	GW	P	PETERS POINT
PPU FED 9-35D-12-16	35	120S	160E	4300731476	2470 Federal	GW	P	PETERS POINT
PPU ST 6A-16D-12-15	16	120S	150E	4300731477	14794 State	GW	P	PRICKLY PEAR
PPU ST 4-16D-12-15	16	120S	150E	4300731478	14794 State	GW	P	PRICKLY PEAR
PPU ST 4A-16D-12-15	16	120S	150E	4300731479	14794 State	GW	P	PRICKLY PEAR
PPU ST 5A-16D-12-15	16	120S	150E	4300731480	14794 State	GW	P	PRICKLY PEAR
PPU ST 3A-16D-12-15	16	120S	150E	4300731481	14794 State	GW	P	PRICKLY PEAR
PPU ST 16A-16D-12-15	16	120S	150E	4300731484	14794 State	GW	P	PRICKLY PEAR
PPU ST 9A-16D-12-15	16	120S	150E	4300731485	14794 State	GW	P	PRICKLY PEAR
PPU ST 16B-16D-12-15	16	120S	150E	4300731514	14794 State	GW	P	PRICKLY PEAR
PPU ST 14B-16D-12-15	16	120S	150E	4300731515	14794 State	GW	P	PRICKLY PEAR
PPU ST 13B-16D-12-15	16	120S	150E	4300731516	14794 State	GW	P	PRICKLY PEAR
PETERS POINT U FED 9-26D-12-16	25	120S	160E	4300750021	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 11-25D-12-16	25	120S	160E	4300750022	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 10-31D-12-17	31	120S	170E	4300750023	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 11-31D-12-17	31	120S	170E	4300750024	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 13A-31D-12-17	31	120S	170E	4300750025	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 13-31D-12-17	31	120S	170E	4300750026	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 14-31D-12-17	31	120S	170E	4300750027	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 14A-31D-12-17	31	120S	170E	4300750028	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 12-25D-12-16	25	120S	160E	4300750029	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 12-6D-13-17	31	120S	170E	4300750033	2470 Federal	GW	P	PETERS POINT

UDOGM CHANGE OF OPERATOR WELL LIST

PETERS POINT U FED 10-25D-12-16	25	120S	160E	4300750035	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 13-36D-12-16	36	120S	160E	4300750037	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 15-36D-12-16	36	120S	160E	4300750038	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 11-1D-13-16	36	120S	160E	4300750039	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 12-1D-13-16	36	120S	160E	4300750040	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR U FED 9-22D-12-15	22	120S	150E	4300750041	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 10-22D-12-15	22	120S	150E	4300750042	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 16-22D-12-15	22	120S	150E	4300750043	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 2-27D-12-15	22	120S	150E	4300750044	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 16-15D-12-15	15	120S	150E	4300750045	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 15-15D-12-15	15	120S	150E	4300750046	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 10-15D-12-15	15	120S	150E	4300750047	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 9-15D-12-15	15	120S	150E	4300750048	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 11A-15D-12-15	15	120S	150E	4300750049	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 1-21D-12-15	21	120S	150E	4300750050	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 2-21D-12-15	21	120S	150E	4300750051	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 2A-21D-12-15	21	120S	150E	4300750052	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 4A-22D-12-15	21	120S	150E	4300750053	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 5A-22D-12-15	21	120S	150E	4300750054	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 7A-21D-12-15	21	120S	150E	4300750056	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 8-21D-12-15	21	120S	150E	4300750057	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 8A-21D-12-15	21	120S	150E	4300750058	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 16-8D-12-15	08	120S	150E	4300750059	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 15-8D-12-15	08	120S	150E	4300750060	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 2-17D-12-15	08	120S	150E	4300750061	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 1A-17D-12-15	08	120S	150E	4300750062	14794 Federal	GW	P	PRICKLY PEAR
PETERS POINT U FED 3A-34D-12-16	27	120S	160E	4300750063	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 4A-34D-12-16	27	120S	160E	4300750064	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 12-27D-12-16	27	120S	160E	4300750065	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 13-27D-12-16	27	120S	160E	4300750066	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 13A-27D-12-16	27	120S	160E	4300750067	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 14-27D-12-16	27	120S	160E	4300750068	18204 Federal	GW	P	
PETERS POINT U FED 14A-27D-12-16	27	120S	160E	4300750069	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR U FED 1-22D-12-15	22	120S	150E	4300750076	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 2-22D-12-15	22	120S	150E	4300750077	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 8-22D-12-15	22	120S	150E	4300750078	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 3-17D-12-15	17	120S	150E	4300750079	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 3A-17D-12-15	17	120S	150E	4300750080	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 4-17D-12-15	17	120S	150E	4300750081	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 4A-17D-12-15	17	120S	150E	4300750082	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 5A-17D-12-15	17	120S	150E	4300750083	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 6-17D-12-15	17	120S	150E	4300750084	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 6A-17D-12-15	17	120S	150E	4300750085	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 7A-17D-12-15	17	120S	150E	4300750086	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 12A-17D-12-15	17	120S	150E	4300750087	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 9-12D-12-14	12	120S	140E	4300750088	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 10-12D-12-14	12	120S	140E	4300750089	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 15-12D-12-14	12	120S	140E	4300750090	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 16-12D-12-14	12	120S	140E	4300750091	14794 Federal	GW	P	PRICKLY PEAR

UDOGM CHANGE OF OPERATOR WELL LIST

PRICKLY PEAR U FED 3-20D-12-15	20	120S	150E	4300750098	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 3A-20D-12-15	20	120S	150E	4300750099	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 4-20D-12-15	20	120S	150E	4300750100	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 4A-20D-12-15	20	120S	150E	4300750101	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 5-20D-12-15	20	120S	150E	4300750102	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 6-20D-12-15	20	120S	150E	4300750104	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 6A-20D-12-15	20	120S	150E	4300750105	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 11A-20D-12-15	20	120S	150E	4300750106	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR U FED 12A-20D-12-15	20	120S	150E	4300750107	14794 Federal	GW	P	PRICKLY PEAR
PETERS POINT U FED 5-31D-12-17	36	120S	160E	4300750109	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 6-31D-12-17	36	120S	160E	4300750116	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 9X-36D-12-16	36	120S	160E	4300750117	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 1-36D-12-16	36	120S	160E	4300750118	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 10-6D-13-17	06	130S	170E	4300750119	2470 Federal	GW	P	PETERS POINT
PETERS POINT U FED 15-31D-12-17	06	130S	170E	4300750123	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR UF 7A-18D-12-15	17	120S	150E	4300750136	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 8A-18D-12-15	17	120S	150E	4300750137	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 9A-18D-12-15	17	120S	150E	4300750138	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 12-20D-12-15	20	120S	150E	4300750139	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 16A-8D-12-15	08	120S	150E	4300750140	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 15A-8D-12-15	08	120S	150E	4300750141	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 13A-9D-12-15	08	120S	150E	4300750142	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 13-9D-12-15	08	120S	150E	4300750143	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 12-9D-12-15	08	120S	150E	4300750144	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 10-8D-12-15	08	120S	150E	4300750145	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 9-8D-12-15	08	120S	150E	4300750146	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 2A-17D-12-15	08	120S	150E	4300750147	14794 Federal	GW	P	PRICKLY PEAR
PETERS POINT UF 12-5D-13-17	06	130S	170E	4300750151	2470 Federal	GW	P	PETERS POINT
PETERS POINT UF 13-5D-13-17	06	130S	170E	4300750152	2470 Federal	GW	P	PETERS POINT
PETERS POINT UF 13-30D-12-17	30	120S	170E	4300750153	18347 Federal	GW	P	PETERS POINT
PETERS POINT UF 14-30D-12-17	30	120S	170E	4300750154	18350 Federal	GW	P	PETERS POINT
PETERS POINT UF 12-30D-12-17	30	120S	170E	4300750155	18346 Federal	GW	P	PETERS POINT
PETERS POINT UF 11-30D-12-17	30	120S	170E	4300750156	18348 Federal	GW	P	PETERS POINT
PETERS POINT UF 3-31D-12-17	30	120S	170E	4300750157	2470 Federal	GW	P	PETERS POINT
PETERS POINT UF 2-31D-12-17	30	120S	170E	4300750158	18349 Federal	GW	P	PETERS POINT
PETERS POINT UF 16-25D-12-16	30	120S	170E	4300750159	2470 Federal	GW	P	PETERS POINT
PETERS POINT UF 9-25D-12-16	30	120S	170E	4300750160	2470 Federal	GW	P	PETERS POINT
PRICKLY PEAR UF 1A-22D-12-15	22	120S	150E	4300750171	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 6A-22D-12-15	22	120S	150E	4300750173	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 7A-22D-12-15	22	120S	150E	4300750174	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 8A-22D-12-15	22	120S	150E	4300750175	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 14B-15D-12-15	22	120S	150E	4300750176	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 9-9D-12-15	09	120S	150E	4300750195	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 16-9D-12-15	09	120S	150E	4300750202	14794 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 8-14D-12-15	14	120S	150E	4300750216	18289 Federal	GW	P	PRICKLY PEAR
PRICKLY PEAR UF 15-14D-12-15	14	120S	150E	4300750221	18290 Federal	GW	P	PRICKLY PEAR
PETERS POINT UF 7X-36D-12-16	36	120S	160E	4300750231	2470 Federal	GW	P	PETERS POINT
PETERS POINT UF 8-36D-12-16	36	120S	160E	4300750232	2470 Federal	GW	P	PETERS POINT
PETERS POINT ST 6-2D-13-16	02	130S	160E	4300731017	14472 State	D	PA	

UDOGM CHANGE OF OPERATOR WELL LIST

PTS 33-36 STATE	36	110S	140E	4301330486	6190 State	GW	PA	ARGYLE
PRICKLY PEAR U FED 10-4	10	120S	140E	4300730823	14462 Federal	GW	S	
PRICKLY PEAR U FASSELIN 5-19-12-15	19	120S	150E	4300730860	14853 Fee	GW	S	
PRICKLY PEAR U ST 5-16	16	120S	150E	4300730943	14794 State	GW	S	PRICKLY PEAR
PRICKLY PEAR U FED 7-33D-12-15	33	120S	150E	4300730985	14771 Federal	GW	S	
PETERS POINT ST 8-2D-13-16	02	130S	160E	4300731016	14471 State	GW	S	
PPU FED 4-35D-12-15	35	120S	150E	4300731285	16223 Federal	GW	S	PRICKLY PEAR
PPU FED 5-36D-12-16	36	120S	160E	4300731350	2470 Federal	GW	S	PETERS POINT
PRICKLY PEAR U FED 5A-20D-12-15	20	120S	150E	4300750103	14794 Federal	GW	S	PRICKLY PEAR
PRICKLY PEAR U FED 13A-17D-12-15	20	120S	150E	4300750108	14794 Federal	GW	S	PRICKLY PEAR
PRICKLY PEAR UF 2A-22D-12-15	22	120S	150E	4300750172	14794 Federal	GW	S	PRICKLY PEAR