

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPlicate

Form approved.

Budget Bureau No. 1004-0136
Expires: December 31, 1991

RECEIVED
MAY 31 1995
DIV. OF OIL, GAS & MINING

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
DRILL DEEPEN

b. TYPE OF WELL
OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
PETROGLYPH OPERATING CO., INC.

3. ADDRESS AND TELEPHONE NO.
P.O. BOX 1839 HUTCHINSON, KS 67504-1839

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)
At surface
614' FNL & 1983' FWL NE/NW
At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
17.4 miles southwest of Myton, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)
614'

16. NO. OF ACRES IN LEASE
640

17. NO. OF ACRES ASSIGNED TO THIS WELL
40

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.
6094'

19. PROPOSED DEPTH
6094'

20. ROTARY OR CABLE TOOLS
ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
6148.4' Graded Ground

22. APPROX. DATE WORK WILL START*
May 1995

8. FARMER LEASE NAME, WELL NO.
UTE TRIBAL

9. APL WELL NO.
#3-18

10. FIELD AND POOL, OR WILDCAT
ANTELOPE CREEK

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 18, T5S, R3W

12. COUNTY OR PARISH
DUCHESNE

13. STATE
UTAH

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4	8 5/8	24.0#	400'	350 sx class "G" + 2% CaCl ₂ + 1/4 #/sx celloflake. 50/50 POZMIX + 2% GEL + 10% SALT TO 400' ABOVE ALL ZONES OF INTEREST (+ 10% EXCESS) LIGHT CEMENT (11 PPG +) + LCM TO 200' ABOVE OIL SHALE OR FRESH WATER INTERVALS (+ 5% EXCESS.)
7 7/8	5 1/2	15.5#	6094'	

PETROGLYPH OPERATING CO., INC.
WILL BE THE DESIGNATED OPERATOR
OF THE SUBJECT WELL UNDER BOND
#B04556.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

SIGNED [Signature] TITLE AGENT DATE 5-22-1995

(This space for Federal or State office use)


PERMIT NO. 43-013-31528 APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY [Signature] TITLE Petroleum Engineer DATE 6/13/95

*See Instructions On Reverse Side

T5S, R3W, U.S.B.&M.




PETROGLYPH OPERATING CO., INC.

Well Location, UTE TRIBAL #3-18, located as shown in NE 1/4 NW 1/4 of Section 18, T5S, R3W, U.S.B.&M. Duchesne County, Utah.

BASIS OF ELEVATION


SPOT ELEVATION ON A RIDGE TOP LOCATED IN THE NW 1/4 NW 1/4 OF SECTION 18, T5S, R3W, U.S.B.&M. TAKEN FROM THE DUCHESNE SE QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 6230 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.


 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 181319
 STATE OF UTAH

LEGEND:

-  = 90° SYMBOL
-  = PROPOSED WELL HEAD.
-  = SECTION CORNERS LOCATED.
-  = SECTION CORNERS RE-ESTABLISHED USING BEARING TREE INFORMATION.

UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(801) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 4-21-95	DATE DRAWN: 4-24-95
PARTY G.S. R.A. D.J.S.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE PETROGLYPH OPERATING CO., INC.	

EIGHT POINT PLAN

UTE TRIBAL # 3-18
NE/NW SEC. 18, T5S R3W
DUCHESNE COUNTY, UTAH

1. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

<u>FORMATIONS</u>	<u>DEPTH</u>	<u>SUBSEA</u>
Uintah Formation	surface	
Green River Formation	1470	+4688
Garden Gulch	3509	+2649
Point Three	4122	+2036
'X' marker	4398	+1760
'Y' marker	4431	+1727
Douglas Creek	4542	+1616
B Limestone	4898	+1260
Castle Peak	5458	+700
Basal Limestone	5994	+164
R.T.D./E+	6094	+64

Anticipated BHP 2600 psi

2. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS FORMATIONS:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Oil/Gas	Garden Gulch	3509
Oil/Gas	Douglas Creek	4542
Oil/Gas	Castle Peak	5458
Other Mineral Zones	N/A	

Cuttings to be collected in 20' intervals until top of 'B' marker (3857'), after 'B' marker samples will be collected in 10' intervals until T.D..

Geologist may alter sample collection at discretion.

3. PRESSURE CONTROL EQUIPMENT : BOP Schematic Diagram attached.

4. CASING PROGRAM :

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>MINIMUM SAFETY FACTOR</u>		
						<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
12 1/4	0' - 400'	400'	8 5/8	24.0 #	J-55	1370 PSI	2950 PSI	263,000#
7 7/8	0' - 6094'	6094'	5 1/2	15.5 #	J-55	4040 PSI	4810 PSI	202,000#

All casing will be new or inspected.

EIGHT POINT PLAN

UTE TRIBAL # 3-18
NE/NW SEC. 18, T5S R3W
DUCHESNE COUNTY, UTAH

5. MUD PROGRAM

INTERVAL

0' - 400'
400' - 4000'
4000' - TD
TD

MUD TYPE

Air
Air/Mist & Aerated Water
Air/3% KCL water or KCL substitute
Gel/polyacrylamide polymer w/5-10% LCM

Sufficient mud inventory will be maintained on location during drilling to handle any adverse conditions that may arise.

6. VARIANCE REQUESTS:

- A. Petroglyph Operating Co., Inc. requests a variance to regulations requiring a straight run blooie line.
- B. Petroglyph Operating Co., Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line.

7. EVALUATION PROGRAM:

Logs: Mud Logging	T.D. to base of surface csg.
Compensated Density-Compensated Neutron Log	T.D. to base of surface csg.
Dual Laterolog - Micro-SFL	T.D. to base of surface csg.
Numar (Magnetic Resonance Imaging Log)	@ Geologists discretion

Cores: None Programmed
DST': None Programmed

Completion: To be submitted at a later date.

8. ABNORMAL CONDITIONS:

None anticipated.

EIGHT POINT PLAN

UTE TRIBAL # 3-18
NE/NW SEC. 18, T5S R3W
DUCHESNE COUNTY, UTAH

9. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

10. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

2000 PSIG DIAGRAM

BOTH RAMS ARE 2000 PSIG RATED.
CASING FLANGE IS 9" 2000 PSIG RATED.
BOPE 9" 2000 PSIG

TESTING PROCEDURE:

1. BOPE 's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 2000 psig
3. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
4. All lines subject to well pressure will be pressure tested to the same pressure as blind & pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 2000 psig BOPE specifications.



CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Petroglyph Operating Co., Inc.
Well Name & Number: Ute Tribal #3-18
Lease Number: BIA 14-20-H62-3513
Location: 614' FNL & 1983' FWL NE/NW, Sec. 18, T5S R3W
Surface Ownership: Ute Indian Tribe

NOTIFICATION REQUIREMENTS

Location Construction - forty-eight (48) hours prior to construction of location and access roads.

Location Completion - prior to moving on the drilling rig.

Spud Notice - at least twenty-four (24) hours prior to spudding the well.

Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.

BOP and related Equipment Tests - twenty-four (24) hours prior to running casing and tests.

First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice To Drill and Surface Use Program.

THIRTEEN POINT SURFACE USE PROGRAM

1. EXISTING ROADS

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing road.
- B. The proposed well site is located approximately 17.4 miles southwest of Myton, Utah - See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. PLANNED ACCESS ROAD

- A. The access road will be approximately 0.2 miles in length. See attached TOPO Map "B"
- B. The access road has a 30 foot ROW w/18 foot running surface.
- C. Maximum grade on access road will be 8%
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. One 18" CMP X 40' culvert shall be installed in drainage North of location.
- G. The access road will be dirt surface.
- H. No gates, cattleguards or fences will be required or encountered.

New or reconstructed roads will be centerlined - flagged at time of location staking.

All travel will be confined to existing access road Right-of-Way. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service Publication: Surface Operating Standards For Oil & Gas Exploration and Development, (1989).

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, drainage, graveling, crowning, and capping the

roadbed as necessary to provide a well-constructed safe road.

Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot Right-of- Way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, Petroglyph Operating Co., Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

3. LOCATION OF EXISTING WELLS WITHIN A ONE MILE RADIUS OF PROPOSED WELL LOCATION

- A. Water wells - 2*
- B. Abandoned wells - None
- C. Temporarily abandoned wells - None.
- D. Disposal wells - None.
- E. Drilling wells - None.
- F. Producing wells - 7*
- G. Shut in wells - None
- H. Injection wells - None

(*See attached TOPO map "C" for location)

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

A. ON WELL PAD

- 1. Tank batteries - None
- 2. Production facilities-To be submitted later
- 3. Oil gathering lines - 1

4. Gas gathering lines-None
5. Injection lines - None
6. Disposal lines - None
7. Surface pits - None

B. OFF WELL PAD

1. Proposed location of attendant off pad flowlines shall be flagged prior to archaeological clearance.
2. A 4 1/2" OD steel above ground production pipeline will be laid approximately 1300' from proposed location to a point in the SE/SW of Section 7, T5S, R3W, where it will tie into Petroglyph Operating Co., Inc.'s existing facility at the Ute Tribal #1-7 tank battery. Proposed pipeline crosses Ute Tribe lands, thus a Right-of-Way grant will be required. See attached TOPO Map D showing pipeline route.
3. Proposed pipeline will be a 4 1/2" OD steel, welded line laid on the surface.
4. Protective measures and devices for livestock and wildlife will be taken and/or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

The production facilities will be placed on the Ute Tribal #1-7 location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities required will be painted within 6 months of installation. Facilities required to comply with O.S.H.A.

(Occupational Safety and Health Act) will be excluded.
The required paint color is Desert Brown.

5. LOCATION & TYPE OF WATER SUPPLY

- A. Water supply will be from Target Trucking's Roosevelt Brine Storage and/or Target's water source in SE 1/4, Sec. 1, T 4S, R 5W Duchesne County, Utah (State water right #43-10152). All water will come from a non-depletable source.
- B. Water will be hauled by Target Trucking.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIAL

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of location.
- B. All construction material will come from Ute Tribal Land.
- C. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at an approved waste disposal facility.
- 4. Produced waste water will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. During the 90 day period, an application for approval of a permanent disposal method and location, together with the required water analysis, will be submitted for the AO's approval.

5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on drilling rig to avoid leakage of oil to pit.

B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in reserve pit or be removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to reserve pit will be avoided by flaring them off in flare pit at time of recovery.

Burning of trash will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BIA administered land:

All reserve pits will be lined with either native clay, commercial bentonite or plastic sufficient to prevent seepage. (If a plastic nylon reinforced liner is used, it shall be torn and perforated after the pit dries and before backfilling of the reserve pit).

A 12 mill liner shall be installed in the reserve pit on the Ute Tribal #3-18.

To protect the environment:

If the reserve pit is lined the operator will provide the BIA with a chemical analysis of the fluids in that pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements described by part II, Standards of Quality for Waters of the State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.

To protect the environment (without a chemical analysis)
reserve pits will be constructed so as not to leak, break, or allow discharge of liquids.

Storage tanks will be used if drill sites are located on tribal

irrigable land, flood plains, or on lands under crop production. After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. ANCILLARY FACILITIES

- A. No airstrips or camps are planned for this well.

9. WELL SITE LAYOUT

- A. Refer to attached well site plat for related topography cuts and fills & cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation parking areas, and access road.

The reserve pit will be located on the North side of the location.

The flare pit will be located downwind of the prevailing wind direction on the North side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil will be stored on the East end.

Access to the well pad will be from the Northwest.

N/A Diversion ditch(es) shall be constructed on the _____ side of the location (above/below) the cut slope, draining to the _____

N/A Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____

N/A The drainage(s) shall be diverted around the sides of the well pad location.

X The reserve pit and/or pad locations shall be constructed long and narrow for topographic reasons.

X Corners No. 4 & 8 will be rounded off to minimize the fill.

FENCING REQUIREMENTS

All pits will be fenced according to the following minimum standards:

- A. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16'.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BIA or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguards (shall/ shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BIA, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to

satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RESTORATION OF SURFACE

A. PRODUCING LOCATION

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 120 days from the date of well completion (weather permitting). Before any dirt work takes place, the reserve pit will be completely dry and all cans, barrels, pipe, fluid, and hydrocarbons, will be removed.

Contact appropriate surface management agency for required seed mixture.

B. DRY HOLE/ABANDONED LOCATION

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and BIA will attach the appropriate surface rehabilitation conditions of approval.

ON BIA Administered lands:

Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) reestablishing irrigation systems where applicable, (b) reestablishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and, (c) ensuring revegetation of the disturbed areas to the specifications of the Ute Indian Tribe or the BIA at the time of abandonment.

11. SURFACE OWNERSHIP

Access road: Ute Indian Tribe
Location: Ute Indian Tribe

12. OTHER INFORMATION

- A. Petroglyph Operating Co., Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the AO. Within five working days the AO will inform the operator as to:
-whether the materials appear eligible for the National Register of historic Places;

the mitigation measures the operator will likely have to undertake before the site can be used.

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, Petroglyph Operating Co., Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BIA,

or the appropriate County Extension Office. On BIA administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Tribal Lands after the conclusion of drilling operations or at any other time without BIA authorization. However, if BIA authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

On BIA administered land:

Operator's employees, including subcontractors, will not gather firewood along roads constructed by operators. If wood cutting is required, a permit will be obtained from the Forestry Department of the BIA pursuant to 25 CFR 169.13 "Assessed Damages Incident to Right-of-Way authorization". All operators, subcontractors, vendors, and their employees or agents may not disturb saleable timber (including firewood) without a duly granted wood permit from the BIA Forester.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved right-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

All roads constructed by operators on the Uintah and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) that the land is owned by the Ute Indian Tribe, (b) the name of the operator, (c) that firearms are prohibited to all non-Ute Tribal members (d) that permits must be obtained from the BIA before cutting firewood or other timber products, and (e) only authorized personnel permitted. All well site locations on the Uintah and Ouray Indian Reservation will have an appropriate sign indicating the name of the operator,

the lease serial number, the well name and number, the survey description of the well (either footage or the quarter-quarter section, the section, township, and range).

Additional Surface Stipulations

N/A No construction or drilling activities shall be conducted between _____ and _____ because of _____

N/A No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.

N/A No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.

N/A There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).

N/A No cottonwood trees will be removed or damaged.

N/A Pond will be constructed according to BLM specifications approximately _____ ft. _____ of the location, as flagged on onsite.

LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION

PERMITTING

Ed Trotter
1620 West 750 North
Vernal UT 84078
Telephone # (801)789-4120
Fax # (801) 789-1420

OPERATIONS

Dan Lindsey
P.O. Box 607
Roosevelt, UT 84066
(801) 722-2531
Fax # (801) 722-9145

All lease/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approval plan of operations, and any applicable Notice to Lessees. Petroglyph Operating Co., Inc. is fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

A copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The BIA Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in the Plan are to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Petroglyph Operating Co., Inc. and its contractors and sub-contractors in conformity with this Plan and the terms and conditions under which it is approved.


5-22-95
Date

Red J. Potter

PETROGLYPH OPERATING CO., INC.

LOCATION LAYOUT FOR

**UTE TRIBAL #3-18
SECTION 18, T5S, R3W, U.S.B.&M.
614' FNL 1983' FWL**




SCALE: 1" = 50'
DATE: 4-24-95
Drawn By: D.J.S.

NOTE:
Flare Pit is to be located
a min. of 100' from the
Well Head.



NOTE:
Pit Capacity W/2'
of Freeboard is
±4,888 Bbls.

Exist. Drainage




Elev. Ungraded Ground at Location Stake = **6156.9'**
Elev. Graded Ground at Location Stake = **6148.4'**

PETROGLYPH OPERATING CO., INC.


TYPICAL CROSS SECTIONS FOR

UTE TRIBAL #3-18
SECTION 18, T5S, R3W, U.S.B.&M.
614' FNL 1983' FWL



1" = 20'
X-Section Scale
1" = 50'

DATE: 4-24-95
Drawn By: D.J.S.




APPROXIMATE YARDAGES

(12") Topsoil Stripping	=	1,610 Cu. Yds.
Remaining Location	=	5,890 Cu. Yds.
TOTAL CUT	=	7,500 CU.YDS.
FILL	=	4,950 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	=	2,290 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	2,290 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah, 84078 • (801) 789-1017




TOPOGRAPHIC
MAP "A"

DATE: 4-24-95 D.J.S.



PETROGLYPH OPERATING CO., INC.

UTE TRIBAL #3-18
SECTION 18, T5S, R3W, U.S.B.&M.
614' FNL 1983' FWL



TOPOGRAPHIC

MAP "B"


SCALE: 1" = 2000'

DATE: 4-24-95 D.J.S.



PETROGLYPH OPERATING CO., INC.

UTE TRIBAL #3-18
SECTION 18, T5S, R3W, U.S.B.&M.
614' FNL 1983' FWL



LEGEND:

- ⊕ = Water Wells
- = Abandoned Wells
- = Temporarily Abandoned Wells
- ⊖ = Disposal Wells
- = Drilling Wells
- = Producing Wells
- = Shut-in Wells




PETROGLYPH OPERATING CO., INC.

UTE TRIBAL #3-18

SECTION 18, T5S, R3W, U.S.B.&M.

T O P O M A P " C "

DATE: 4-24-95 D.J.S.



TOPOGRAPHIC
MAP "D"

Legend

- EXISTING PIPELINE
- - - - - Proposed Pipeline




PETROGLYPH OPERATING CO., INC.

UTE TRIBAL #3-18
SECTION 18, T5S, R3W, U.S.B.&M.
614' FNL 1983' FWL

DATE: 4-25-95 D.J.S.

Petroglyph Operating Co., Inc.
P.O. Box 1839
Hutchinson, KS 67504-1839



Mr. Frank Matthews, Petroleum Engineer,
Utah Division of Oil, Gas, and Mining
3 Triad Center, Ste. 350
Salt Lake City, UT 84180-1203

RE: APPLICATION FOR PERMIT TO DRILL
UTE TRIBAL #3-18
NE/NW SEC. 18, T5S, R3W
DUCHESNE COUNTY, UTAH
LEASE NO. BIA 14-20-H62-3513
UTE TRIBAL LANDS

Dear Mr. Matthews:

Enclosed please find a copy of the Application for Permit to Drill and associated attachments for the referenced well.

Please address further communication regarding this matter (including approval) to:

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Phone # (801) 789-4120

Sincerely,



Ed Trotter
Agent

Petroglyph Operating Co., Inc.

Attachments

/EHT/dmt

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 05/31/95

API NO. ASSIGNED: 43-013-31528

WELL NAME: UTE TRIBAL 3-18
OPERATOR: PETROGLYPH OPERATING (N3800)

PROPOSED LOCATION:

NENW 18 - T05S - R03W
SURFACE: 0614-FNL-1983-FWL
BOTTOM: 0614-FNL-1983-FWL
DUCHESNE COUNTY
ANTELOPE CREEK FIELD (060)

LEASE TYPE: IND
LEASE NUMBER: 14-20-H62-3513

PROPOSED PRODUCING FORMATION: GRRV

INSPECT LOCATION BY: / /		
TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

Y Plat
Y Bond: Federal State Fee
(Number 304556)
N Potash (Y/N)
N Oil shale (Y/N)
Y Water permit
(Number 43-10152)
N RDCC Review (Y/N)
(Date: _____)



LOCATION AND SITING:

___ R649-2-3. Unit: _____
 R649-3-2. General.
___ R649-3-3. Exception.
___ Drilling Unit.
___ Board Cause no: _____
___ Date: _____

COMMENTS: _____

STIPULATIONS: _____

PETROGLYPH OPERATING ANTELOPE CREEK DEVELOPMENT DUCHESNE COUNTY NO SPACING





State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

June 13, 1995

Petroglyph Operating Company, Inc.
P. O. Box 1839
Hutchinson, Kansas 67504-1839


Re: Ute Tribal #3-18 Well, 614' FNL, 1983' FWL, NE NW, Sec. 18, T. 5 S., R. 3 W.,
Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-31528.

Sincerely,


R. J. Erth
Associate Director

ldc

Enclosures

cc: Duchesne County Assessor
Bureau of Land Management, Vernal District Office
WAPD



Operator: Petroglyph Operating Company, Inc.

Well Name & Number: Ute Tribal #3-18

API Number: 43-013-31528

Lease: 14-20-H62-3513

Location: NE NW Sec. 18 T. 5 S. R. 3 W.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
 DRILL DEEPEN

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER
 SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 PETROGLYPH OPERATING CO., INC.

3. ADDRESS AND TELEPHONE NO.
 P.O. BOX 1839 HUTCHINSON, KS 67504-1839

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
 At surface
 614' FNL & 1983' FWL NE/NW
 At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 17.4 miles southwest of Myton, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 614'

16. NO. OF ACRES IN LEASE 640

17. NO. OF ACRES ASSIGNED TO THIS WELL 40

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.

19. PROPOSED DEPTH 6094'

20. ROTARY OR CABLE TOOLS ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
 6148.4' Graded Ground

22. APPROX. DATE WORK WILL START*
 May 1995

5. LEASE DESIGNATION AND SERIAL NO.
 14-20-H62-3513

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
 UINTAH & OURAY TRIBE

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME, WELL NO.
 UTE TRIBAL

9. API WELL NO.
 #3-18

10. FIELD AND POOL, OR WILDCAT
 ANTELOPE CREEK

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
 Sec. 18, T5S, R3W


12. COUNTY OR PARISH DUCHESNE

13. STATE UTAH

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4	8 5/8	24.0#	400'	350 sx class "G" + 2% CaCl ₂ + 1/4 #/sx celloflake.
7 7/8	5 1/2	15.5#	6094'	

50/50 POZMIX + 2% GEL + 10% SALT TO 400' ABOVE ALL ZONES OF INTEREST (+ 10% EXCESS) LIGHT CEMENT (11 PPG +) + LCM TO 200' ABOVE OIL SHALE OR FRESH WATER INTERVALS (+ 5% EXCESS.)



RECEIVED
MAY 30 1995

PETROGLYPH OPERATING CO., INC. WILL BE THE DESIGNATED OPERATOR OF THE SUBJECT WELL UNDER BOND #B04556.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED [Signature] TITLE AGENT DATE 5-22-1995

(This space for Federal or State office use)

PERMIT NO. **NOTICE OF APPROVAL** APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY [Signature] TITLE ASSISTANT DISTRICT MANAGER MINERALS DATE JUN 15 1995

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL ATTACHED TO OPERATOR'S COPY

memorandum

DATE: JUN 8 1995

REPLY TO
ATTN OF:

Superintendent, Uintah & Ouray Agency

SUBJECT:

Concurrence Letter for Petroglyph Operating Company
Ute Tribal 3-18, SWNE, Section 18, T5S, R3W

TO:

Bureau of Land Management, Vernal District Office
Attention: Minerals and Mining Division

We recommend approval of the Application for Permit to Drill on the subject well.

Based on available information received on June 07, 1995, we cleared the proposed location in the following areas of environmental impact.

YES NO Listed threatened or endangered species
 YES NO Critical wildlife habitat
 YES NO Archaeological or cultural resources
 YES NO Air quality aspects (to be used only
 if project is in or adjacent to a Class I
 area of attainment.
 YES NO Other (if necessary)

COMMENTS: The Ute Indian Tribe Energy & Minerals Department concurs and is recommending that the following stipulations should be strictly adhered.

1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the areas examined, as referenced in report and to the existing roadways and/or evaluated access routes.
2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural or paleontological resources in the area.
3. All personnel should refrain from collecting artifacts and from disturbing any significant cultural or paleontological resources in the area.
4. The personnel from the Ute Tribe Energy & Minerals Department should be consulted should cultural remains from subsurface deposits be exposed during construction work.

****See attached Bureau of Indian Affairs, Environmental Analysis dated 5/22/95**

Charles H. Cameron

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Petroglyph Operating Co., Inc.

Well Name & Number: Ute Tribal 3-18

API Number: 43-013-31528

Lease Number: 14-20-H62-3513

Location: NENW Sec. 18 T. 5S R. 3W

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Mahogany Oil shale zone identified at $\pm 2,010$ ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to $\pm 1,810$ ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours prior to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.), and shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted following initial installation and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Wayne Bankert (801) 789-4170
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

BLM FAX Machine (801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

SURFACE USE PLAN OF OPERATION
Conditions of Approval (COAs)

1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the areas examined, as referenced in report, and to the existing roadways and/or evaluated access routes.
2. All recommendations of the Bureau of Indian Affairs, confined site specific Environmental Analysis (EA) report shall be strictly adhered, during and after construction.
3. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
4. The personnel from the Ute Tribe Energy & Minerals Department should be consulted should cultural remains from subsurface deposits be exposed during construction work.

Mitigation stipulations from the combined site specific Environmental Analysis.

1. Before the site is abandoned the company will be required to restore the well pad and access road to near their original state. The disturbed area will be reseeded with desirable perennial vegetation.

Although the road rights-of-way will be 30 feet wide, the graded area of the road will be limited in most places to 21 feet between the two outer edges of the barrow pits. Where deep cuts are required for road construction, or where intersections or sharp curves occur the road may be constructed wider than 21 feet so that large pieces of equipment will have enough room to make turns.

2. Noxious weeds will be controlled on well sites and rights-of-way. If noxious weeds spread from the well sites or rights-of-way onto adjoining land, the company will be responsible for their control.
3. The reserve pit will be lined with an impervious synthetic liner.
4. Have a closed production system. All produced waters and by products will either be piped to approved injection wells or approved disposal sites.
5. Production water, oil, and other by-products will not be applied to roads or well pads for the control of dust or weeds. Indiscriminate dumping of oil field by-products on tribal lands will not be allowed.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.
14-20-H62-3513

6. If Indian, Allottee or Tribe Name
Ute Indian Tribe

SUBMIT IN TRIPLICATE

7. If Unit or CA, Agreement Designation

14-20-H62-4650

1. Type of Well
 Oil Well Gas Well Other

8. Well Name and No.
Ute Tribal 3-18

2. Name of Operator
Petroglyph Operating Company, Inc.

9. API Well No.
43-013-31528

3. Address and Telephone No.
6209 N. Highway 61 Hutchinson, KS 67502 (316) 665-8500

10. Field and Pool, or Exploratory Area
Antelope Creek

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
**NENW 614 FNL & 1983 FWL
18-5S-3W**

11. County or Parish, State
Duchesne County, UT

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other <u>well name change</u>
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)


13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

In an effort to bring all of the existing wells and the anticipated wells to be drilled into a uniform numbering system, based on 40 acre locations, each well name will be changed to consist of its section location followed by the correct number of its well spot, based upon 16 wells per section.

Petroglyph Operating Company, Inc. would like to notify by subsequent report that the above referenced well name has been changed to **Ute Tribal 18-03**. This will be effective January 1, 1996.

14. I hereby certify that the foregoing is true and correct

Signed



Title

President

Date

1/25/96

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

January 26, 1996

Ron Firth
State of Utah
Division of Oil, Gas & Mining
3 Triad Center, Suite 350
355 West North Temple
Salt Lake City, UT 84180-1203

RE: Well Name Change for Wells in the Antelope Creek Field, Duchesne County, UT

Mr. Firth:

In an effort to bring all of the existing wells and wells to be drilled into a uniform numbering system, based on 40 acre locations and 16 wells per section, each well name will be changed to consist of its section location followed by the correct number of its well spot.

Enclosed please find sundry notices changing the well name for all wells located in Antelope Creek. We are making this change effective January 1, 1996. Also enclosed for your convenience is a list consisting of the "old" well names and the "new" well names.

Your assistance during this time of transition is greatly appreciated. If you have any questions regarding the enclosed information, please do not hesitate to contact me at (316) 665-8500.

Sincerely,



Angela R. Ely
Administrative Operations Manager

ARE/ms

Enclosures

pc: Dennis Ingram
Lisha Cordova

96WELLÇ.XLS

AgmtNbt	LeaseNbr	LeaseName	Old	New	API	Footage	Field	Town	Range	Sec	Qtr
14-20-H62-4650	14-20-H62-3509	Ute Tribal	1-10	10-12	43-013-30805	2001 FSL & 600 FWL	Antelope Creek	5S	3W	10	NWSW
14-20-H62-4650	14-20-H62-3510	Ute Tribal	1-15	15-04	43-013-30880	907 FNL & 515 FWL	Antelope Creek	5S	3W	15	NWNW
14-20-H62-4650	14-20-H62-3511	Ute Tribal	1-16	16-16	43-013-30804	505 FSL & 600 FEL	Antelope Creek	5S	3W	16	SESE
14-20-H62-4650	14-20-H62-4633	Ute Tribal	1-17	17-01	43-013-30790	638 FNL & 610 FEL	Antelope Creek	5S	3W	17	NENE
14-20-H62-4650	14-20-H62-3513	Ute Tribal	1-18	18-01	43-013-30761	550 FNL & 521 FEL	Antelope Creek	5S	3W	18	NENE
14-20-H62-4650	14-20-H62-3514	Ute Tribal	1-19	19-16	43-013-30803	556 FSL & 603 FEL	Antelope Creek	5S	3W	19	SESE
14-20-H62-4650	14-20-H62-3515	Ute Tribal	1-20	20-02	43-013-30764	404 FNL & 1539 FEL	Antelope Creek	5S	3W	20	NWNE
14-20-H62-4650	14-20-H62-3516	Ute Tribal	1-21	21-13	43-013-30883	611 FSL & 786 FWL	Antelope Creek	5S	3W	21	SWSW
14-20-H62-4650	14-20-H62-3517	Ute Tribal	1-28	28-05	43-013-30802	2583 FNL & 712 FWL	Antelope Creek	5S	3W	28	SWNW
14-20-H62-4650	14-20-H62-3518	Ute Tribal	1-29 inj	29-09 inj	43-013-30763	1324 FSL & 1160 FEL	Antelope Creek	5S	3W	29	NESE
14-20-H62-4650	14-20-H62-3502	Ute Tribal	1-3	03-13	43-013-30823	659 FSL & 659 FWL	Antelope Creek	5S	3W	3	SWSW
14-20-H62-4650	14-20-H62-3519	Ute Tribal	1-30	30-07	43-013-30852	1980 FNL & 1980 FEL	Antelope Creek	5S	3W	30	SWNE
14-20-H62-4650	14-20-H62-3520	Ute Tribal	1-31	31-02	43-013-30827	519 FNL & 1942 FEL	Antelope Creek	5S	3W	31	NWNE
14-20-H62-4650	14-20-H62-3521	Ute Tribal	1-32	32-08	43-013-30853	2100 FNL & 660 FEL	Antelope Creek	5S	3W	32	SENE
14-20-H62-4650	14-20-H62-3522	Ute Tribal	1-33	33-04	43-013-30806	723 FNL & 802 FWL	Antelope Creek	5S	3W	33	NWNW
14-20-H62-4650	14-20-H62-3503	Ute Tribal	1-4	04-01	43-013-30762	1331 FNL & 1277 FEL	Antelope Creek	5S	3W	4	NENE
14-20-H62-4650	14-20-H62-3504	Ute Tribal	1-5	05-07	43-013-30785	2430 FNL & 1777 FEL	Antelope Creek	5S	3W	5	SWNE
14-20-H62-4650	14-20-H62-3505	Ute Tribal	1-6	06-16	43-013-30793	833 FSL & 902 FEL	Antelope Creek	5S	3W	6	SESE
14-20-H62-4650	14-20-H62-3506	Ute Tribal	1-7	07-14	43-013-30788	559 FSL & 1957 FWL	Antelope Creek	5S	3W	7	SESW
14-20-H62-4650	14-20-H62-3507	Ute Tribal	1-8 inj	08-04 inj	43-013-30759	754 FNL & 888 FWL	Antelope Creek	5S	3W	8	NWNW
14-20-H62-4650	14-20-H62-3504	Ute Tribal	11-5	05-09	43-013-31468	2150 FSL & 639 FEL	Antelope Creek	5S	3W	5	NESE
14-20-H62-4650	14-20-H62-3517	Ute Tribal	12-28	28-12	43-013-31629	1861 FSL & 496 FWL	Antelope Creek	5S	3W	28	NWSW
14-20-H62-4650	14-20-H62-3503	Ute Tribal	12-4	04-12	43-013-31470	2000 FSL & 600 FWL	Antelope Creek	5S	3W	4	NWSW
14-20-H62-4650	14-20-H62-3504	Ute Tribal	12-5	05-11	43-013-31454	1856 FSL & 1457 FWL	Antelope Creek	5S	3W	5	NESW
14-20-H62-4650	14-20-H62-3507	Ute Tribal	13-8	08-13	43-013-31468	660 FSL & 660 FWL	Antelope Creek	5S	3W	8	SWSW
14-20-H62-4650	14-20-H62-3518	Ute Tribal	14-29	29-10	43-013-31475	1955 FSL & 2125 FEL	Antelope Creek	5S	3W	29	NWSE
14-20-H62-4650	14-20-H62-3504	Ute Tribal	14-5	05-14	43-013-31455	590 FSL & 1984 FWL	Antelope Creek	5S	3W	5	SESW
14-20-H62-4650	14-20-H62-3518	Ute Tribal	15-29	29-15	43-013-31530	649 FSL & 1831 FEL	Antelope Creek	5S	3W	29	SWSE
14-20-H62-4650	14-20-H62-3504	Ute Tribal	15-5	05-15	43-013-31461	990 FSL & 1900 FEL	Antelope Creek	5S	3W	5	SWSE
14-20-H62-4650	14-20-H62-3506	Ute Tribal	16-5	05-16	43-013-31527	708 FSL & 523 FEL	Antelope Creek	5S	3W	5	SESE
14-20-H62-4650	14-20-H62-3507	Ute Tribal	16-7	07-16	43-013-31463	440 FSL & 410 FEL	Antelope Creek	5S	3W	7	SESE
14-20-H62-4650	14-20-H62-3509	Ute Tribal	1A-8	08-01	43-013-31568	660 FSL & 660 FEL	Antelope Creek	5S	3W	8	NENE
14-20-H62-4650	14-20-H62-3511	Ute Tribal	2-10	10-03	43-013-31187	600 FNL & 1650 FWL	Antelope Creek	5S	3W	10	NENW
14-20-H62-4650	14-20-H62-3513	Ute Tribal	2-16	16-13	43-013-31166	750 FSL & 500 FWL	Antelope Creek	5S	3W	16	SWSW
14-20-H62-4650	14-20-H62-3515	Ute Tribal	2-18	18-08	43-013-30881	1929 FNL & 612 FEL	Antelope Creek	5S	3W	18	SENE
14-20-H62-4650	14-20-H62-3518	Ute Tribal	2-20	20-07	43-013-30882	1980 FNL & 1980 FEL	Antelope Creek	5S	3W	20	SWNE
14-20-H62-4650	14-20-H62-3518	Ute Tribal	2-29	29-16	43-013-30849	500 FSL & 500 FEL	Antelope Creek	5S	3W	29	SESE
14-20-H62-4650	14-20-H62-3502	Ute Tribal	2-3	03-14	43-013-31097	1050 FSL & 1980 FWL	Antelope Creek	5S	3W	3	SESW
14-20-H62-4650	14-20-H62-3520	Ute Tribal	2-31	31-03	43-013-31188	442 FNL & 2338 FWL	Antelope Creek	5S	3W	31	NENW
14-20-H62-4650	14-20-H62-3503	Ute Tribal	2-4 inj	04-07 inj	43-013-30879	2551 FNL & 1900 FEL	Antelope Creek	5S	3W	4	SWNE
14-20-H62-4650	14-20-H62-3504	Ute Tribal	2-5	05-13	43-013-30824	723 FSL & 588 FWL	Antelope Creek	5S	3W	5	SWSW
14-20-H62-4650		State	2-6	06-10	43-013-30891	2525 FSL & 1836 FEL	Antelope Creek	5S	3W	6	NW SE
14-20-H62-4650	14-20-H62-3506	Ute Tribal	2-7	07-01	43-013-30825	567 FNL & 706 FEL	Antelope Creek	5S	3W	7	NENE
14-20-H62-4650	14-20-H62-3507	Ute Tribal	2-8	08-05	43-013-30826	1980 FNL & 500 FWL	Antelope Creek	5S	3W	8	SWNW
14-20-H62-4650	14-20-H62-3508	Ute Tribal	2-9	09-01	430-13-30789	770 FNL & 1059 FEL	Antelope Creek	5S	3W	9	NENE
14-20-H62-4650	14-20-H62-3507	Ute Tribal	2A-8	08-02	43-013-31569	506 FNL & 1956 FEL	Antelope Creek	5S	3W	8	NWNE
14-20-H62-4650	14-20-H62-3513	Ute Tribal	3-18	18-03	43-013-31528	614 FNL & 1983 FWL	Antelope Creek	5S	3W	18	NENW

96WELLÇ.XLS

AgmtNbt	LeaseNbr	LeaseName	Old	New	API	Footage	Field	Town	Range	Sec	Qtr
14-20-H62-4650	14-20-H62-3515	Ute Tribal	3-20	20-06	43-013-31175	2050 FNL & 1950 FWL	Antelope Creek	5S	3W	20	SENW
14-20-H62-4650	14-20-H62-3518	Ute Tribal	3-29	29-06	43-013-30850	1900 FNL & 1980 FWL	Antelope Creek	5S	3W	29	SENW
14-20-H62-4650	14-20-H62-3503	Ute Tribal	3-4	04-11	43-013-30878	1999 FSL & 1738 FWL	Antelope Creek	5S	3W	4	NESW
14-20-H62-4650	14-20-H62-3504	Ute Tribal	3-5 E3 inj	05-10 inj	43-013-30938	2068 FSL & 2093 FEL	Antelope Creek	5S	3W	5	NWSE
14-20-H62-4650	14-20-H62-3505	Ute Tribal	3-6	06-08	43-013-31189	2323 FNL & 691 FEL Lot # 9	Antelope Creek	5S	3W	6	SENE
14-20-H62-4650	14-20-H62-3506	Ute Tribal	3-7	07-08	43-013-30828	1864 FNL & 972 FEL	Antelope Creek	5S	3W	7	SENE
14-20-H62-4650	14-20-H62-3507	Ute Tribal	3-8	08-03	43-013-31101	505 FNL & 439 FWL	Antelope Creek	5S	3W	8	NENW
14-20-H62-4650	14-20-H62-4633	Ute Tribal	4-17	17-04	43-013-31464	697 FNL & 636 FWL	Antelope Creek	5S	3W	17	NWNW
14-20-H62-4650	14-20-H62-3513	Ute Tribal	4-18 inj	18-02 inj	43-013-31099	812 FNL & 1768 FEL	Antelope Creek	5S	3W	18	NWNE
14-20-H62-4650	14-20-H62-3518	Ute Tribal	4-29	29-04	43-013-30851	660 FNL & 660 FWL	Antelope Creek	5S	3W	29	NWNW
14-20-H62-4650	14-20-H62-3503	Ute Tribal	4-4	04-13	43-013-30848	807 FSL & 886 FWL	Antelope Creek	5S	3W	4	SWSW
14-20-H62-4650	14-20-H62-3504	Ute Tribal	4-5	05-08	43-013-31306	2500 FNL & 550 FEL	Antelope Creek	5S	3W	5	SENE
14-20-H62-4650	14-20-H62-3507	Ute Tribal	4-8	08-12	43-013-31164	2100 FSL & 515 FWL	Antelope Creek	5S	3W	8	NWSW
14-20-H62-4650	14-20-H62-3508	Ute Tribal	4-9	09-15	43-013-31165	550 FSL & 2000 FEL	Antelope Creek	5S	3W	9	SWSE
14-20-H62-4650	14-20-H62-3503	Ute Tribal	4A-4	04-04	43-013-31574	1205 FNL & 660 FWL Lot # 5	Antelope Creek	5S	3W	4	NWNW
14-20-H62-4650	14-20-H62-3513	Ute Tribal	5-18 inj	18-09 inj	43-013-31180	2151 FSL & 667 FEL	Antelope Creek	5S	3W	18	NESE
14-20-H62-4650	14-20-H62-3518	Ute Tribal	5-29 E3	29-07	43-013-30939	1969 FNL & 2093 FEL	Antelope Creek	5S	3W	29	SWNE
14-20-H62-4650	14-20-H62-3503	Ute Tribal	5-4	04-05	43-013-31462	1969 FNL & 660 FWL Lot # 12	Antelope Creek	5S	3W	4	SWNW
14-20-H62-4650	14-20-H62-3507	Ute Tribal	5-8 inj	08-06 inj	43-013-31307	1550 FNL & 1550 FWL	Antelope Creek	5S	3W	8	SENW
14-20-H62-4650	14-20-H62-3518	Ute Tribal	6-29	29-08A	43-013-31305	2600 FNL & 600 FEL	Antelope Creek	5S	3W	29	SENE
14-20-H62-4650	14-20-H62-3503	Ute Tribal	6-4	04-14	43-013-31100	660 FSL & 2000 FWL	Antelope Creek	5S	3W	4	SESW
14-20-H62-4650	14-20-H62-3503	Ute Tribal	6A-4	04-06	43-013-31526	2427 FNL & 2028 FWL Lot # 11	Antelope Creek	5S	3W	4	SENW
14-20-H62-4650	14-20-H62-3513	Ute Tribal	7-18	18-07	43-013-31533	2236 FNL & 1855 FEL	Antelope Creek	5S	3W	18	SWNE
14-20-H62-4650	14-20-H62-3518	Ute Tribal	7-29	29-08B	43-013-31339	2675 FNL & 725 FEL	Antelope Creek	5S	3W	29	NESE
14-20-H62-4650	14-20-H62-3517	Ute Tribal	11-28	28-11	43-013-31575	2171 FSL & 2107 FWL	Antelope Creek	5S	3W	28	NESE
14-20-H62-4650	14-20-H62-3513	Ute Tribal	10-18	18-10	43-013-31595	1954 FSL & 1894 FEL	Antelope Creek	5S	3W	18	NWSE
14-20-H62-4650	14-20-H62-3517	Ute Tribal	13-28	28-13	43-013-31576	712 FSL & 553 FWL	Antelope Creek	5S	3W	28	SWSW
14-20-H62-4650	14-20-H62-3517	Ute Tribal	6-28	28-06	43-013-31576		Antelope Creek	5S	3W	28	SENW
14-20-H62-4650	14-20-H62-3521	Ute Tribal	1A-32	32-01	43-013-31577	759 FNL & 502 FEL	Antelope Creek	5S	3W	32	NENE

PETROGLYPH Operating Company, Inc.

6209 North Highway 61, Hutchinson, Kansas 67502 • P.O. Box 1839, Hutchinson, Kansas 67504-1839



VIA FACSIMILE (303) 359-3940

March 25, 1996

Ron Firth
State of Utah
Division of Oil, Gas & Mining
3 Triad Center, Suite 350
355 West North Temple
Salt Lake City, UT 84180-1203

Mr. Firth:

Please let this notice serve as a request from Petroglyph Operating Company, Inc. for your agency to keep all log information in a "TIGHT HOLE" confidential status for a period of two (2) years.

If you have any questions, please do not hesitate to contact me at (316) 665-8500.

Sincerely,

Angela R. Ely
Administrative Operations Manager

DOG M can
only allow
1yr. by
rule

ARE/ms

SPUDDING INFORMATION

Name of Company: PETROGLYPH OPERATING

Well Name: UTE TRIBAL 18-03

Api No. 43-013-31528

Section 18 Township 5S Range 3W County DUCHESNE

Drilling Contractor _____

Rig #: _____

SPUDDED:

Date: 6/23/96

Time: _____

How: DRY HOLE

Drilling will commence: _____

Reported by: D. INGRAM-DOGM

Telephone #: _____

Date: 6/28/96 Signed: FRM

Petroglyph Oper. Co.

OPERATOR *Petroglyph Operating Company, Inc.*

OPERATOR ACCT. NO

N3800

ADDRESS P.O. Box 1839


Hutchinson, KS 67504-1839

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	11943	43-013-31528	Ute Tribal 18-03	NENW	18	5S	3W	Duchesne	6-22-96	
WELL 1 COMMENTS:											
Battery of its own <i>Entity added 7-3-96. Lee</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

- ACTION CODES** (See instructions on back of form):
- A - Establish new entity for new well (single well) only
 - B - Add new well to existing entity (group or unit well)
 - C - Re-assign well from one existing entity to another existing entity
 - D - Re-assign well from one existing entity to a new entity
 - E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)




Deanna K. Bell
Signature Deanna K. Bell
Operations Coordinator 6-25-96
Title _____ Date _____
Phone No. (801) 722-2531

CONFIDENTIAL

VIA UPS

July 5, 1996

Ron Firth
State of Utah
Division of Oil, Gas & Mining
3 Triad Center, Suite 350
355 West North Temple
Salt Lake City, UT 84180-1203



Mr. Firth:

Enclosed please find the logs listed below for the wells located in Duchesne County, Utah.

<u>Well Name</u>	<u>Log</u>
Ute Tribal 04-02 4301315656	CNL, AIL 55 3W 4
Ute Tribal 04-03 4301331617	CBL55 3W 4
Ute Tribal 04-04 4301331574	CBL55 3W 4
Ute Tribal 05-01 4301331658	CNL, AIL, CBL55 3W 5
Ute Tribal 09-04 4301331660	CNL, AIL, CBL55 3W 9
Ute Tribal 18-03 4301331528	CNL, AIL 55 3W 18
Ute Tribal 18-10 4301331595	CNL, AIL, CBL55 3W 18
Ute Tribal 28-06 4301331594	CBL55 3W 28
Ute Tribal 28-11 4301331575	CBL55 3W 28
Ute Tribal 28-13 4301331576	CBL55 3W 28
Ute Tribal 32-01 4301331577	CBL55 3W 32

If you have any questions, please do not hesitate to contact me at (316) 665-8500.

Sincerely,

CONFIDENTIAL

Angela R. Ely
Angela R. Ely
Administrative Operations Manager

ARE/ms

Enclosures

OPERATOR Petroglyph Operating Company, Inc.

OPERATOR ACCT. NO

N3800

ADDRESS P.O. Box 1839

Hutchinson, KS 67504-1839


ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	11943		43-013-31528	Ute Tribal 18-03	NENW	18	5S	3W	Duchesne	6-22-96	
WELL 1 COMMENTS:											
Battery of its own <i>Entity previously added 7-3-96. Lee</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)


- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)



Deanna K. Bell
Signature Deanna K. Bell
Operations Coordinator 6-25-96
Title _____ Date _____
Phone No. (801) 722-2531



REPORT OF WATER ENCOUNTERED DURING DRILLING

1. Well name and number: LITE TRIBAL 18-03

API number: 43-013-31528

2. Well Location: QQ _____ Section 5 Township 4S Range 3W County Duchesne

3. Well operator: Petroglyph Operating Co.

Address: P.O. Box 1839
Hutchinson, KS 67504-1839

Phone: (316) 665-8500

4. Drilling contractor: UNION 12

Address: P.O. Drawer 40
Buckhannon, WV 26201

Phone: (304) 472-4610

5. Water encountered (attach additional pages as needed):

DEPTH		VOLUME (FLOW RATE OR HEAD)	QUALITY (FRESH OR SALTY)
FROM	TO		
0	455'	No water @ Blowtest	
0	1230'	1gal/min @ Blowtest	Fresh

6. Formation tops: _____

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I hereby certify that this report is true and complete to the best of my knowledge.

Date: 6/30/96

Name & Signature: [Signature]

Title: Field Operations Supervisor

RECEIVED
SUBMIT IN DUPLICATE
SEP 17 1996
DIV OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL GAS WELL DRY OTHER

b. TYPE OF COMPLETION:
NEW WELL WORK OVER DEEP EN PLUG BACK DIFF. RESVR. Other _____

2. NAME OF OPERATOR
Petroglyph Operating Company, Inc.

3. ADDRESS OF OPERATOR
P.O. Box 1839 Hutchinson, KS 67504-1839

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface **NE NW 614' FNL & 1983' FWL**
At top prod. interval reported below

At total depth **6280 RID**

14. PERMIT NO. **43-013-31528** DATE ISSUED _____

5. LEASE DESIGNATION AND SERIAL NO.
14-20-H62-3513

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Ute Indian Tribe

7. UNIT AGREEMENT NAME
14-20-H62-4650

8. FARM OR LEASE NAME
Ute Tribal

9. WELL NO.
18-03

10. FIELD AND POOL, OR WILDCAT
Antelope Creek

11. SEC. T. R. M. OR BLOCK AND SURVEY OR AREA
Sec. 18-T5S-R3W

12. COUNTY OR PARISH **Duchesne** 13. STATE **Utah**

15. DATE SPUDDED **6/22/96** 16. DATE T.D. REACHED **6/30/96** 17. DATE COMPL. (Ready to prod.) **8/29/96** 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* **6148 GL** 19. ELEV. CASINGHEAD _____

20. TOTAL DEPTH, MD & TVD **6280 RID** 21. PLUG. BACK T.D., MD & TVD **6249** 22. IF MULTIPLE COMPL., HOW MANY* _____ 23. INTERVALS FILLED BY _____ ROTARY TOOLS _____ CABLE TOOLS _____

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*
Green River

26. TYPE ELECTRIC AND OTHER LOGS RUN
CNL, AIT

25. WAS DIRECTIONAL SURVEY MADE _____

27. WAS WELL CORED _____

CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8-5/8"	24#	417	12-1/2"	250 sx class G	
5-1/2"	15.5#	6276	7-7/8"	120 sx hilift, 315 sx 10-0 RFC	

LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8"	5607	

31. PERFORATION RECORD (Interval, size and number)

5564-68 (17 holes) 5140-52 (49 holes)
5158-62 (17 holes) 5008-09 (2 holes)
5006-09 (13 holes) 4652-57 (21 holes)
4580-96 (65 holes)

32. ACID. SHOT. FRACTURE. CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
5564-68	3730 gal fluid, 12000# prop
5140-62	8680 gal fluid, 28100# prop
5006-09	4500 gal fluid, 16400# prop
4652-57	4000 gal fluid, 14300# prop
PRODUCTION 4580-96	8250 gal fluid, 34000# prop

33.* DATE FIRST PRODUCTION **9-3-96** PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) **2 1/2" x 1 1/2" x 17' pump** WELL STATUS (Producing or shut-in) **producing**

DATE OF TEST **9-7-96** HOURS TESTED **24** CHOKER SIZE _____ PROD'N. FOR TEST PERIOD **70** OIL—BBL. **0** GAS—MCF. **27** WATER—BBL. _____ GAS-OIL RATIO _____

FLOW. TUBING PRESS. _____ CASING PRESSURE **550** CALCULATED 24-HOUR RATE _____ OIL—BBL. _____ GAS—MCF. _____ WATER—BBL. _____ OIL GRAVITY-API (CORR.) _____

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) _____ TEST WITNESSED BY **Dave Schreiner**

35. LIST OF ATTACHMENTS _____

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED **Angela R. Ely** TITLE **Administrative Operations Manager** DATE **9/24/96**

*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);

38. GEOLOGIC MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
X Marker	4407					
Douglas Creek	4540					
B Limestone	4933					
Castle Peak	5507					
Basal Carbonate	5914					

CONFIDENTIAL

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.
14-20-H62-3513

6. If Indian, Allottee or Tribe Name
Ute Indian Tribe

7. If Unit or CA, Agreement Designation
14-29-H62-4650

8. Well Name and No.
Ute Tribal #18-03

9. API Well No.
43-013-31528

10. Field and Pool, or Exploratory Area
Antelope Creek

11. County or Parish, State
Duchesne County, UT

SUBMIT IN TRIPLICATE

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
Petroglyph Operating Co., Inc.

3. Address and Telephone No.
P.O. Box 1839, Hutchinson, KS 67504-1839 (316) 665-8500

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
NE NW 18-T5S-R3W
614' FNL 1983' FWL


12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input type="checkbox"/> Other
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input checked="" type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Petroglyph Operating Company, Inc. has submitted an application for a UIC permit to convert the Ute Tribal 18-03 from a producing well to an injection well under the EPA Area Permit #UT2736-00000 within the Antelope Creek Waterflood Project Area located in Duchesne County, Utah.



14. I hereby certify that the foregoing is true and correct

Signed April Menzies Title Geo./Petroleum Eng. Tech. Date April 3, 1997

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: 1420H624650
2. NAME OF OPERATOR: Petroglyph Operating Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute Indian Tribe
3. ADDRESS OF OPERATOR: P.O. Box 607 CITY Roosevelt STATE UT ZIP 84066		7. UNIT OR CA AGREEMENT NAME: Ute Tribal 07-14
4. LOCATION OF WELL FOOTAGES AT SURFACE: Multiple/See Below		8. WELL NAME and NUMBER: See Below
PHONE NUMBER: 722-2531		9. API NUMBER: See Below
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT: Antelope Creek

COUNTY: Duchesne

STATE: UT

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Facility Changes
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Well Name	API#	S/T/R	Type	Status	Entity#
Ute 18-03	430133152800S1	18;05S;03W	Oil	POW	11943

This well was moved to the Ute Tribal 07-14 Tank Battery.
Ute 07-14 Oil POW 09392

NAME (PLEASE PRINT) Callie Peatross

TITLE Production Clerk

SIGNATURE *Callie Peatross*

DATE 5-28-03

(This space for State use only)

RECEIVED

MAY 29 2003

DIV. OF OIL, GAS & MINING

JUL-07-2003 MON 09:40 AM OIL, GAS & MINING

FAX NO. 801 359 3940

P. 02/03

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

April

ENTITY ACTION FORM

Operator: Petroglyph
Address: P.O. Box 607
city Roosevelt
state Utah zip 84066

Operator Account Number: N 3800

Phone Number: 435-722-2531

Well 1

API Number	Well Name	QQ	Sec	Twp	Rng	County
4301331390051	Ute Tribal 34-05D3	NNNW	34	4S	3W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date	
C	12309	12270	12/1/1997		April-03	
Comments:						7/9/03 ✓
Now on 34-12D3TB.						

Well 2

API Number	Well Name	QQ	Sec	Twp	Rng	County
43013315280051	Ute Tribal 18-03	NEENW	19	5S	3W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date	
C	11943	09392	6/22/1996		April-03	
Comments:						7/9/03 ✓
Now on 07-14TB						

Well 3

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date	
Comments:						

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Callie Pentross
Name (Please Print)
Callie Pentross
Signature
Production Assistant 7-7-03
Title Date

RECEIVED

JUL 07 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-3513
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute Indian Tribe
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Water Injection Conversion</u>		7. UNIT or CA AGREEMENT NAME: 14-20-H62-4650
2. NAME OF OPERATOR: Petroglyph Operating Company Inc.		8. WELL NAME and NUMBER: Ute Tribal 18-03
3. ADDRESS OF OPERATOR: P.O. Box 607 Roosevelt STATE UT ZIP 84066		9. API NUMBER: 4301331528
4. LOCATION OF WELL FOOTAGES AT SURFACE: 514' FNL 1983' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 18 T5S R3W		10. FIELD AND POOL, OR WILDCAT: Antelope Creek COUNTY: Duchesne STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This sundry is serving notice that Petroglyph Operating Company Inc. (POCI) plans to convert the Ute Tribal 18-03 to an injection well from a producing well. This work is being performed under our area UIC permit number UT20736-00000. POCI has obtained approval to perform the conversion on the Ute Tribal 18-03 from the EPA. After the conversion on the Ute Tribal 18-03 is complete, POCI will submit the necessary information to the EPA to obtain approval to being injection operations.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

NAME (PLEASE PRINT) <u>Steve Wall</u>	TITLE <u>MANAGER</u>
SIGNATURE <u>Steve Wall</u>	DATE <u>1-3-06</u>

(This space for State use only)

RECEIVED
JAN 09 2006



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 8

999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

JAN 13 2006

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

Mr. Kenneth Smith
Executive Vice President and Chief Operating Officer
Petroglyph Energy, Inc.
555 S. Cole Blvd
Boise, ID 83709

43,013,31528

RE: Additional Well to Antelope Creek Area Permit
UIC Permit No. UT20736-00000
Well ID: UT20736-06701
Ute Tribal No. 18-03, Duchesne County, Utah

Dear Mr. Smith:

The Petroglyph Operating Company, Inc. (Petroglyph) request to convert the former Green River Formation oil well Ute Tribal No. 18-03 to an enhanced recovery injection well in the Antelope Creek Waterflood project is hereby authorized by the Environmental Protection Agency (EPA) under the terms and conditions of the Authorization For Additional Well.

The addition of the proposed injection well, within the exterior boundary of the Uintah & Ouray Indian Reservation, is being made under the authority of 40 CFR §144.33 (c) and terms of the Antelope Creek Waterflood UIC Area Permit No. UT20736-00000. Unless specifically mentioned in the enclosed Authorization For Additional Well, the Ute Tribal No. 18-03 is subject to all terms and conditions of the UIC Area Permit UT20736-00000 as modified.

Please be aware that Petroglyph does not have authorization to begin injection operations into the well until all Prior to Commencing Injection requirements have been submitted and evaluated by the EPA, and Petroglyph has received written authorization from the Director to begin injection.

Prior to receiving authorization to inject, the EPA requires that Petroglyph submit for review and approval the following: (1) the results of a **Part I (Internal) mechanical integrity test (MIT)**, (2) a **pore pressure** calculation of the injection interval, and (3) a completed **EPA Form No. 7520-12 Well Rework Record**.

RECEIVED
JAN 20 2006

The initial Maximum Allowable Injection Pressure (MAIP) for the Ute Tribal No. 18-03 was determined to be **1675 psig**. UIC Area Permit UT20736-00000 also provides the opportunity for the permittee to request a change in the MAIP based upon results of a step rate test that demonstrates that the formation breakdown pressure will not be exceeded.

If you have any questions, please call Ms. Patricia Pfeiffer at (303) 312-6271 or 1.800.227.8917 (Ext. 6271). Please submit the required data to **ATTENTION: Patricia Pfeiffer**, at the letterhead address, citing **MAIL CODE: 8P-W-GW** very prominently.

Sincerely,



for Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

encl: Authorization For Conversion of An Additional Well
EPA Form No. 7520-12 (Well Rework Record)

cc: without enclosures

Maxine Natchees, Acting Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe
P.O. Box 190
Fort Duchesne, UT 84026

Chester Mills, Superintendent
BIA - Uintah & Ouray Indian Agency
P.O. Box 130
Fort Duchesne, UT 84026

cc: with enclosures;

S. Elaine Willie
Environmental Coordinator
Ute Indian Tribe
P.O. Box 460
Fort Duchesne, UT 84026

Gil Hunt
Technical Services Manager
Utah Division of Oil, Gas, and Mining
1594 West North Temple - Suite 1220
Salt Lake City, UT 84114-5801

Kirk Fleetwood, PE
BLM - Vernal District
170 South 500 East
Vernal, UT 84078



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-277-8917
http://www.epa.gov/region08

AUTHORIZATION FOR AN ADDITIONAL WELL

UIC Area Permit No: UT20736-00000

The Antelope Creek Waterflood Final UIC Area Permit No. UT20736-00000, effective July 12, 1994, authorizes injection for the purpose of enhanced oil recovery into multiple lenticular sand units which are distributed throughout the lower portion of the Green River Formation. On December 27, 2004, the permittee provided notice to the Director concerning the following additional enhanced recovery injection well:

Well Name: Ute Tribal 18-03
EPA Well ID Number: UT20736-06701
Location: 614 ft FNL & 1983 ft FWL
NE NW Sec. 18 - T5S - R3W
Duchesne County, Utah.

Pursuant to 40 CFR §144.33, Area UIC Permit No. UT20736-00000 authorizes the permittee to construct and operate, convert, or plug and abandon additional enhanced recovery injection wells within the area permit. This well was determined to satisfy additional well criteria required by the permit.

This well is subject to all provisions of UIC Area Permit No. UT20736-00000, as modified and as specified in the Well Specific Requirements detailed below. This Authorization shall expire one year after the Effective Date unless the permittee has converted the well to injection or submits a written request to extend this Authorization prior to the expiration date.

This Authorization is effective upon signature.

Date: JAN 13 2006

Signature of Stephen S. Tuber

for Stephen S. Tuber
*Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

RECEIVED
JAN 20 2006

DIV. OF OIL, GAS & MINING

* The person holding this title is referred to as the Director throughout the Permit and Authorization

WELL-SPECIFIC REQUIREMENTS

Well Name: Ute Tribal 18-03
EPA Well ID Number: UT 20736-06701

Prior to commencing injection operations, the permittee shall submit the following information and receive written Authority to Inject from the Director:

1. a successful Part I (Internal) Mechanical Integrity test (MIT);
2. pore pressure calculation of the proposed injection zone; and
3. completed Well Rework Record EPA Form No. 7520-12 and schematic diagram.

Approved Injection Zone: Injection is approved between the base of the Green River A Lime Marker, at approximately 3902 ft, to the top of the Basal Carbonate, at approximately 5914 ft.

Maximum Allowable Injection Pressure (MAIP): The initial MAIP is 1675 psig, based on the following calculation:

$$\text{MAIP} = [\text{FG} - (0.433)(\text{SG})] * \text{D}, \text{ where}$$
$$\text{FG} = 0.80 \text{ psi/ft} \quad \text{SG} = 1.002 \quad \text{D} = \underline{4580 \text{ ft}} \text{ (top perforation depth KB)}$$
$$\text{MAIP} = \underline{1675 \text{ psi}}$$

UIC Area Permit No. UT20736-00000 also provides the opportunity for the permittee to request a change of the MAIP based upon results of a step rate test that demonstrates the formation breakdown pressure will not be exceeded.

Well Construction and Corrective Action: No Corrective Action is required Based on review of well construction and cementing records, including CBL, well construction is considered adequate to prevent fluid movement out of the injection zone and into USDWs.

Tubing and Packer: 2-3/8" or similar size injection tubing is approved; the packer shall be set at a depth no more than 100 ft above the top perforation.

Corrective Action for Wells in Area of Review: No Corrective Action is required. The following wells that penetrate the confining zone are within or proximate to a 1/4 mile radius around the Ute Tribal No. 18-03 were evaluated to determine if any corrective action is necessary to prevent fluid movement into USDWs:

Well: Ute Tribal No. 07-14 ● Location: SE SW Sec. 07 - T5S - R3W
Well: Ute Tribal No. 18-04E ● Location: NW NW Sec. 18 - T5S - R3W

Demonstration of Mechanical Integrity: A successful demonstration of Part I (Internal) Mechanical Integrity using a standard Casing-Tubing pressure test is required prior to injection and at least once every five years thereafter. EPA reviewed the cement bond log and determined the cement will provide an effective barrier to significant upward movement of fluids through vertical channels adjacent to the well bore pursuant to 40 CFR 146.8 (a)(2). Therefore, further demonstration of Part II (External) Mechanical Integrity is not required at this time.

Demonstration of Financial Responsibility: The applicant has demonstrated financial responsibility in the amount of \$15,000 via a Surety Bond that has been reviewed and approved by the EPA.

Plugging and Abandonment: The well shall be plugged in a manner that isolates the injection zone and prevents movement of fluids into or between USDWs. Tubing, packers, and any downhole apparatus shall be removed. Class A, C, G, and H cements, with additives such as accelerators and retarders that control or enhance cement properties, may be used for plugs; however, volume extending additives and gel cements are not approved for plug use. Plug placement shall be verified by tagging. Plugging gel of at least 9.2 lb/gal shall be placed between all plugs. A minimum 50 ft surface plug shall be set inside and outside of the surface casing to seal pathways for fluid migration into the subsurface. Within sixty (60) days after plugging the owner or operator shall submit Plugging Record (EPA Form 7520-13) to the Director. The Plugging Record must be certified as accurate and complete by the person responsible for the plugging operation. At a minimum, the following plugs are required:

- PLUG NO. 1: Set a cast iron bridge plug (CIBP) no more than 50 ft above the top perforation at 4580 ft with a minimum 20 ft cement plug on top of the CIBP.
- PLUG NO. 2: Set a minimum 200 ft cement plug inside of the 5-1/2" casing across the Trona Zone and the Mahogany Shale, between approximately 2641 ft to 2841 ft.
- PLUG NO. 3: Set a minimum 200 ft cement plug inside of the 5-1/2" casing and on the backside of the 5-1/2" casing across the base of the USDW, between approximately 1040 ft to 1240 ft. This plug fulfills the Utah BLM P&A requirement.
- PLUG NO. 4: Set a minimum 50 ft cement plug on the backside of the 5-1/2" casing, across the surface casing shoe at 431 ft (unless pre-existing backside cement precludes cement-squeezing this interval.)
- PLUG NO. 5: Set a cement plug inside of the 5-1/2" casing, from at least 406 ft to 456 ft.
- PLUG NO. 6: Set a cement plug on the backside of the 5-1/2" casing, from surface to a depth of at least 50 ft.
- PLUG NO. 7: Set a cement plug inside of the 5-1/2" casing from surface to a depth of at least 50 ft.

Cut off surface and 5-1/2" casing at least 4 ft below ground level and set P&A marker; submit Sundry Notices and all necessary data as required by the EPA and other regulatory agencies.

Reporting of Noncompliance:

- (a) **Anticipated Noncompliance.** The operator shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.
- (b) **Compliance Schedules.** Reports of compliance or noncompliance with, or any progress on, interim and final requirements contained in any compliance schedule of this Permit shall be submitted no later than thirty (30) days following each schedule date.
- (c) **Written Notice of any noncompliance which may endanger health or the environment shall be reported to the Director within five (5) days of the time the operator becomes aware of the noncompliance.** The written notice shall contain a description of the noncompliance and its cause; the period of noncompliance including dates and times; if the noncompliance has not been corrected the anticipated time it is expected to continue; and steps taken or planned to prevent or reduce recurrence of the noncompliance.

Twenty-Four Hour Noncompliance Reporting:

The operator shall report to the Director any noncompliance which may endanger health or environment. Information shall be provided, either orally or by leaving a message, within twenty-four (24) hours from the time the operator becomes aware of the circumstances by telephoning 1.800.227-8917 and asking for the EPA Region 8 UIC Program Compliance and Enforcement Director, or by contacting the Region 8 Emergency Operations Center at 303.293.1788 if calling from outside EPA Region 8. The following information shall be included in the verbal report:

- (a) Any monitoring or other information which indicates that any contaminant may cause an endangerment to a USDW.
- (b) Any noncompliance with a Permit condition or malfunction of the injection system which may cause fluid migration into or between underground sources of drinking water.

Oil Spill and Chemical Release Reporting:

The operator shall comply with all other reporting requirements related to oil spills and chemical releases or other potential impacts to human health or the environment by contacting the National Response Center (NRC) 1.800.424.8802 or 202.267.2675, or through the NRC website at <http://www.nrc.uscg.mil/index.htm>.

Other Noncompliance:

The operator shall report all other instances of noncompliance not otherwise reported at the time monitoring reports are submitted.

Other Information:

Where the operator becomes aware that he failed to submit any relevant facts in the Permit application, or submitted incorrect information in a Permit application, or in any report to the Director, the operator shall submit such correct facts or information within two (2) weeks of the time such information became known to him.

WELL-SPECIFIC CONSIDERATIONS

Well Name: Ute Tribal 18-03
EPA Well ID Number: UT20736-00000

Underground Sources of Drinking Water (USDWs): USDWs in the Antelope Creek Waterflood area generally may occur within the Uinta Formation, which extends from the surface to the top of the Green River Formation at approximately 1490 ft. According to "*Base of Moderately Saline Ground Water in the Uinta Basin, Utah, State of Utah Technical Publication No. 92,*" the base of moderately saline ground water may be found at approximately 52 ft below ground surface at this well location. Based on information reported by Petroglyph, the base of a USDW was found at 1140 ft KB in the Ute Tribal 18-03. Based on analysis of the submitted cement bond log (CBL) the top of casing cement in this well is at approximately 1910 ft (KB).

Confining Zone: The Confining Zone at this location is approximately 214 ft of interbedded limestone and shale between the depths of 3688 ft to 3902 ft (KB) which directly overlies the Injection Zone, based on correlation to the Antelope Creek Ute Tribal 04-03 well Type Log. Additional impermeable lacustrine shale beds above the Confining Zone provide for further protection for any overlying USDW.

Injection Zone: The Injection Zone at this well location is an approximately 2012 ft section of multiple lenticular sand units interbedded with shale, marlstone and limestone from the base of the Confining Zone at 3902 ft (KB) to the top of the Basal Carbonate Formation at 5914 ft (KB), based on correlation to the Antelope Creek Ute Tribal 04-03 well Type Log.

Well Construction: The CBL shows more than 214 ft of 80% or greater bond across the confining zone, approximately 3688 ft to 3902 ft..

Surface casing: 8-5/8" casing is set at 431 ft (KB) in a 12-1/4" hole, using 250 sacks cement circulated to the surface.

Longstring casing: 5-1/2" casing is set at 6280 ft (KB) in a 7-7/8" 6280 ft Total Depth hole with a plugged back total depth (PBD) of 6249 ft, cemented with 435 sacks cement. Top of Cement (TOC): 1910 ft (KB) CBL.

Perforations: top perforation: **4580 ft** Bottom perforation: **5568 ft**

Wells in Area of Review (AOR): Construction and cementing records, including cement bond logs (CBL) as available, for two wells in the 1/4 mile AOR that penetrated the confining zone were reviewed and found adequate to prevent fluid movement out of the injection zone and into USDWs.

Well: Ute Tribal No. 07-14 ●
Well: Ute Tribal No. 18-04E ●

Casing Cement top: circulated to surface
Casing Cement top: 1537 ft (CBL)



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

MAR 10 2006

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Steve Wall, District Manager
Petroglyph Energy, Inc.
4116 West 3000 So. Ioka Lane
Roosevelt, UT 84066

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

43-013-31528
5S 3W 18

RE: Additional Well to Antelope Creek Area Permit
UIC Permit No. UT20736-00000
Well ID: UT20736-06701
Ute Tribal No.18-03, Duchesne County, Utah

Dear Mr. Wall:

Thank you for submitting information pertaining to the newly constructed or converted Ute Tribal 18-03 enhanced recovery injection well to the Region 8 Ground Water Program office of the Environmental Protection Agency (EPA). The "Prior To Commencing Injection" requirements for the Ute Tribal 18-06 injection well required well owner and operator Petroglyph Energy, Inc. to submit the following information to the Director:

1. A successful mechanical integrity test (MIT) demonstrating Part I Internal MI,
2. Pore pressure calculation of the proposed injection zone, and
3. completed EPA Form No. 7520-12.

All required information has been submitted, and has been reviewed and approved by the EPA. Therefore, effective upon your receipt of this letter, Administrative approval hereby is granted for injection into the Ute Tribal 18-03 enhanced recovery injection well under the conditions of the Authorization for Additional Well and UIC Area Permit UT20736-00000 as modified.

RECEIVED

MAR 13 2006

DIV. OF OIL, GAS & MINING



Printed on Recycled Paper

As of this approval, responsibility for permit compliance and enforcement is transferred to the Region 8 UIC Technical Enforcement Program office. Therefore, please direct all future notification, reporting, monitoring and compliance correspondence to the following address, referencing your well and UIC Permit number on all correspondence regarding this well.

Technical Enforcement Program - UIC
U.S. EPA Region 8, Mail Code 8ENF-UFO
999 18th Street, Suite 300
Denver, Colorado 80202-2466

The Director has determined that the maximum allowable surface injection pressure (MAIP) for the Ute Tribal 18-03 is 1675 psig. Please be reminded that it is the responsibility of the owner/operator to be aware of, and to comply with, all conditions of Authorization for Additional Well UT20736-06701 and EPA UIC Area Permit UT20736-00000 and relevant modifications as issued.

If you have any questions regarding this Authorization, please call Tricia Pfeiffer of my staff at (303) 312-6271. For questions regarding notification, testing, monitoring, reporting or other Permit requirements, the UIC Technical Enforcement Program may be reached by calling (800) 227-8917.

Sincerely,



Tracy M. Eagle
Director
Ground Water Program

cc: Maxine Natchees, Acting Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe
P.O. Box 190
Fort Duchesne, UT 84026

Chester Mills, Superintendent
BIA - Uintah & Ouray Indian Agency
P.O. Box 130
Fort Duchesne, UT 84026

Mr. Kenneth Smith
Executive Vice President and Chief Operating Officer
Petroglyph Energy, Inc.
555 S. Cole Blvd
Boise, ID 83709

S. Elaine Willie
Environmental Coordinator
Ute Indian Tribe
P.O. Box 460
Fort Duchesne, UT 84026

Gil Hunt
Technical Services Manager
Utah Division of Oil, Gas, and Mining
1594 West North Temple - Suite 1220
Salt Lake City, UT 84114-5801

Kirk Fleetwood, PE
BLM - Vernal District
170 South 500 East
Vernal, UT 84078

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-3513
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute Indian Tribe
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>WIW Conversion</u>		7. UNIT or CA AGREEMENT NAME: 14-20-H62-4650
2. NAME OF OPERATOR: Petroglyph Operating Company Inc.		8. WELL NAME and NUMBER: Ute Tribal 18-03
3. ADDRESS OF OPERATOR: P.O. Box 607 Roosevelt UT 84066	PHONE NUMBER: (435) 722-2531	10. FIELD AND POOL, OR WILDCAT: Antelope Creek
4. LOCATION OF WELL FOOTAGES AT SURFACE: ⁶ 514' FNL, 1983' FWL		COUNTY: Duchesne
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 18 T5S R3W		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
First date of injection March 14, 2006.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) <u>Steve Wall</u>	TITLE <u>District Manager</u>
SIGNATURE <u><i>Steve Wall</i></u>	DATE <u>3/16/2006</u>

(This space for State use only)

**RECEIVED
MAR 17 2006**

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-3513
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute Indian Tribe
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>WIW Conversion</u>		7. UNIT or CA AGREEMENT NAME: 14-20-H62-4650
2. NAME OF OPERATOR: Petroglyph Operating Company Inc.		8. WELL NAME and NUMBER: Ute Tribal 18-03
3. ADDRESS OF OPERATOR: P.O. Box 607	Roosevelt	9. API NUMBER: 4301331528
	STATE UT ZIP 84066	10. FIELD AND POOL, OR WILDCAT: Antelope Creek
4. LOCATION OF WELL FOOTAGES AT SURFACE: 514' FNL, 1983' FWL		COUNTY: Duchesne
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 18 T5S R3W		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This well has been converted to a water injection well to support the ongoing secondary waterflood currently active in Antelope Creek. The rods and tubing have been pulled from this well. The injection string consists of 2 3/8", 4.7# J-55 EUE tubing. The packer is installed at 4523' +/- KB. Packer fluid has been circulated on the backside and a successful MIT test performed and submitted to the EPA.

NAME (PLEASE PRINT) <u>Steve Wall</u>	TITLE <u>District Manager</u>
SIGNATURE <u><i>Steve Wall</i></u>	DATE <u>3/16/2006</u>

(This space for State use only)

RECEIVED
MAR 17 2006



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

MAR 10 2006

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Steve Wall, District Manager
Petroglyph Energy, Inc.
4116 West 3000 So. Ioka Lane
Roosevelt, UT 84066

RE: **Additional Well to Antelope Creek Area Permit**
UIC Permit No. UT20736-00000
Well ID: UT20736-06701
Ute Tribal No.18-03, Duchesne County, Utah

Dear Mr. Wall:

Thank you for submitting information pertaining to the newly constructed or converted Ute Tribal 18-03 enhanced recovery injection well to the Region 8 Ground Water Program office of the Environmental Protection Agency (EPA). The "Prior To Commencing Injection" requirements for the Ute Tribal 18-06 injection well required well owner and operator Petroglyph Energy, Inc. to submit the following information to the Director:

1. A successful mechanical integrity test (MIT) demonstrating Part I Internal MI,
2. Pore pressure calculation of the proposed injection zone, and
3. completed EPA Form No. 7520-12.

All required information has been submitted, and has been reviewed and approved by the EPA. Therefore, effective upon your receipt of this letter, Administrative approval hereby is granted for injection into the Ute Tribal 18-03 enhanced recovery injection well under the conditions of the Authorization for Additional Well and UIC Area Permit UT20736-00000 as modified.



As of this approval, responsibility for permit compliance and enforcement is transferred to the Region 8 UIC Technical Enforcement Program office. Therefore, please direct all future notification, reporting, monitoring and compliance correspondence to the following address, referencing your well and UIC Permit number on all correspondence regarding this well.

Technical Enforcement Program - UIC
U.S. EPA Region 8, Mail Code 8ENF-UFO
999 18th Street, Suite 300
Denver, Colorado 80202-2466

The Director has determined that the maximum allowable surface injection pressure (MAIP) for the Ute Tribal 18-03 is 1675 psig. Please be reminded that it is the responsibility of the owner/operator to be aware of, and to comply with, all conditions of Authorization for Additional Well UT20736-06701 and EPA UIC Area Permit UT20736-00000 and relevant modifications as issued.

If you have any questions regarding this Authorization, please call Tricia Pfeiffer of my staff at (303) 312-6271. For questions regarding notification, testing, monitoring, reporting or other Permit requirements, the UIC Technical Enforcement Program may be reached by calling (800) 227-8917.

Sincerely,



Tracy M. Eagle
Director
Ground Water Program

cc: Maxine Natchees, Acting Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe
P.O. Box 190
Fort Duchesne, UT 84026

Chester Mills, Superintendent
BIA - Uintah & Ouray Indian Agency
P.O. Box 130
Fort Duchesne, UT 84026

Mr. Kenneth Smith
Executive Vice President and Chief Operating Officer
Petroglyph Energy, Inc.
555 S. Cole Blvd
Boise, ID 83709

S. Elaine Willie
Environmental Coordinator
Ute Indian Tribe
P.O. Box 460
Fort Duchesne, UT 84026

Gil Hunt
Technical Services Manager
Utah Division of Oil, Gas, and Mining
1594 West North Temple - Suite 1220
Salt Lake City, UT 84114-5801

Kirk Fleetwood, PE
BLM - Vernal District
170 South 500 East
Vernal, UT 84078

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-3513
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Water Injection Well		7. UNIT or CA AGREEMENT NAME: ANTELOPE CREEK
2. NAME OF OPERATOR: PETROGLYPH OPERATING CO		8. WELL NAME and NUMBER: UTE TRIBAL 18-03
3. ADDRESS OF OPERATOR: 960 Broadway Avenue, Ste 500 , Boise, ID, 83703		9. API NUMBER: 43013315280000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0614 FNL 1983 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 18 Township: 05.0S Range: 03.0W Meridian: U		9. FIELD and POOL or WILDCAT: ANTELOPE CREEK
		COUNTY: DUCHESNE
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/11/2014	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 4/11/2014 Petroglyph Operating rigged up a coiled tubing unit on the well referenced above to acidize the well and improve the well's injection rates. The targeted treatment interval was 4,580'-5,568'. We ran in hole through the injection tubing, established an injection rate and slowly pulled back as we spotted acid over the referenced interval.

We spotted 1,554 Gal of 15% Hcl, ran back in to the bottom of the interval and repeated spotting 1,008 Gal of Chlorine Dioxide, and ran back in spotting in 1,554 Gal of 15% Hcl. The treatment was then flushed out into the formation with 3,633 Gallons of fresh water and the well was returned to injection.

**Accepted by the
Utah Division of
Oil, Gas and Mining**
FOR RECORD ONLY
May 29, 2014

NAME (PLEASE PRINT) Rodrigo Jurado	PHONE NUMBER 435 722-5302	TITLE Regulatory & Compliance Spc
SIGNATURE N/A	DATE 5/27/2014	