

UTAH OIL AND GAS CONSERVATION COMMISSION

REMARKS: WELL LOG _____ ELECTRIC LOGS _____ FILE WATER SANDS _____ LOCATION INSPECTE _____ SUB. REPORT/abd. _____

971203 Equitable to Inland eff. 9-30-97: 980810 LA'D eff 7-27-98:

DATE FILED JUNE 25, 1996

LAND: FEE & PATENTED _____ STATE LEASE NO. _____ PUBLIC LEASE NO. U-65210 _____ INDIAN _____

DRILLING APPROVED: JULY 16, 1996

SPUDDED IN:

COMPLETED: 7-27-98 LA'D PUT TO PRODUCING:

INITIAL PRODUCTION:

GRAVITY A.P.I.

GOR:

PRODUCING ZONES:

TOTAL DEPTH:

WELL ELEVATION:

DATE ABANDONED: 7-27-98 LA'D

FIELD: MONUMENT BUTTE

UNIT:

COUNTY: DUCHESNE

WELL NO. MONUMENT FEDERAL 12-11-9-17Y API NO. 43-013-31679

LOCATION 1996 FNL FT. FROM (N) (S) LINE. 673 FWL FT. FROM (E) (W) LINE. SW NW 1/4 - 1/4 SEC. 11

TWP.	RGE.	SEC.	OPERATOR	TWP.	RGE.	SEC.	OPERATOR
9S	17E	11	Inland Prod. Co.				
			EQUITABLE RESOURCES				

9S 17E 11 EQUITABLE RESOURCES

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

5. LEASE DESIGNATION AND SERIAL NO.
U-65210

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
DRILL DEEPEN PLUG BACK

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
n/a

7. UNIT AGREEMENT NAME
n/a

8. FARM OR LEASE NAME
Monument Federal

9. WELL NO.
#12-11-9-17Y

10. FIELD AND POOL, OR WILDCAT
Monument Butte/Green River

11. SEC., T., R., M., OR BLE.
AND SURVEY OR AREA
11, T9S, R17E

b. TYPE OF WELL
OIL WELL GAS WELL OTHER
SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
Equitable Resources Energy Company

3. ADDRESS OF OPERATOR
1601 Lewis Avenue; Billings, MT 59102

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
At surface
SW NW Section 11, T9S, R17E 1996' FNL, 673' FWL
At proposed prod. zone 608 209

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
From Myton, UT approximately 10 mi SW

12. COUNTY OR PARISH 13. STATE
Duchesne UTAH

15. DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

16. NO. OF ACRES IN LEASE
1240

17. NO. OF ACRES ASSIGNED
TO THIS WELL
40 acres

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

19. PROPOSED DEPTH
5600'

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5,077' GL

22. APPROX. DATE WORK WILL START*
June 1, 1996


23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
See attached Drilling Program/Casing Design				

Operator intends to drill this well in accordance with the attached EXHIBITS. A listing of EXHIBITS is also attached.

SELF CERTIFICATION: I hereby certify that I am authorized, by proper lease interest owner, to conduct these operations associated with the application. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Equitable Resources Energy Company as principal and Safeco Insurance Company of America as surety under BLM Bond No. MT 0576 (Nationwide Oil & Gas Bond #5547188) who will be responsible for compliance with all of the terms and conditions of that portion of the lease associated with this application.

ORIGINAL: Bureau of Land Management (Vernal, UT)
COPY; Utah Division of Oil, Gas and Mining (Salt Lake City, UT)



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed non-productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Bobbie Schuman TITLE Regulatory and Environmental Specialist DATE April 17, 1996
Bobbie Schuman

(This space for Federal or State office use)


PERMIT NO. 43-013-31679 APPROVAL DATE

APPROVED BY [Signature] TITLE Petroleum Engineer DATE 7/16/96
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side

T9S, R17E, S.L.B.&M.

EQUITABLE RESOURCES ENERGY CO.



WELL LOCATION, MONUMENT FEDERAL #12-11-9-17Y, LOCATED AS SHOWN IN THE SW 1/4 NW 1/4 OF SECTION 11, T9S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

STACY W. STEWART
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 18937
 STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING

38 WEST 100 NORTH - VERNAL, UTAH 84078
(801) 781-2501

SCALE: 1" = 1000'	SURVEYED BY: S.S. D.S.
DATE: 2-29-96	WEATHER: WINDY & COLD
NOTES:	FILE #

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (PARIETTE DRAW SW)

EXHIBITS

- A PROPOSED DRILLING PROGRAM
- B PROPOSED SURFACE USE PROGRAM
- C GEOLOGIC PROGNOSIS
- D DRILLING PROGRAM/CASING DESIGN/WELLBORE DIAGRAM
- E HAZMAT DECLARATION
- F EXISTING & PLANNED ACCESS ROADS (MAPS A & B)
- G WELLSITE LAYOUT
- H BOPE SCHEMATIC
- I EXISTING ROADS (MAP C)
- J PROPOSED PRODUCTION FACILITY DIAGRAM
- K SURVEY PLAT
- L LAYOUT/CUT & FILL DIAGRAM

6/19/95

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 06/25/96

API NO. ASSIGNED: 43-013-31679

WELL NAME: MONUMENT FEDERAL 12-11-9-17Y
OPERATOR: EQUITABLE RESOURCES CORP (N9890)

PROPOSED LOCATION:
SWNW 11 - T09S - R17E
SURFACE: 1996-FNL-0673-FWL
BOTTOM: 1996-FNL-0673-FWL
DUCHESNE COUNTY
MONUMENT BUTTE FIELD (105)

LEASE TYPE: FED
LEASE NUMBER: U - 65210

PROPOSED PRODUCING FORMATION: GRRV

INSPECT LOCATION BY: / /		
TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

Plat
 Bond: Federal State Fee
(Number 5647188)
 Potash (Y/N)
 Oil shale (Y/N)
 Water permit
(Number JOB SHIELDS)
 RDCC Review (Y/N)
(Date: _____)


LOCATION AND SITING:

___ R649-2-3. Unit: _____
 R649-3-2. General.
___ R649-3-3. Exception.
___ Drilling Unit.
___ Board Cause no: _____
___ Date: _____

COMMENTS: _____

STIPULATIONS: _____

EQUITABLE RESOURCES CORP DEVELOPMENT DRILLING SEC. 5 & 11, T9S, R1E, DUCHESNE, COUNTY UAC R649-3-2



PREPARED:
DATE: 25-JUNE-96

CONFIDENTIAL

AS OPERATOR, WE HEREBY REQUEST THAT THE STATUS OF THIS WELL BE HELD TIGHT FOR THE MAXIMUM PERIOD ALLOWED BY FEDERAL AND STATE REGULATIONS.

Equitable Resources Energy Company,
Balcron Oil Division
1601 Lewis Avenue
Billings, MT 59102
(406) 259-7860

PROPOSED DRILLING PROGRAM

EQUITABLE RESOURCES ENERGY COMPANY

Monument Federal #12-11-9-17Y

SW NW Section 11, T9S, R17E

Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162-3.1 (d):

1. ESTIMATED IMPORTANT GEOLOGICAL MARKERS:

See Geologic Prognosis (EXHIBIT "C")

2. ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS OR WATER:

See Geologic Prognosis (EXHIBIT "C")

3. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

a. EXHIBIT "H" is a schematic of the BOP equipment and choke manifold. A 2M system will be used. The BOPE will be installed after setting 8-5/8" casing at 260'. The blind rams and pipe rams will be tested to 1500 psi. Pipe rams will be operationally checked each 24-hour period and blind rams each time pipe is pulled out of the hole.

b. The BOPE will be tested to 1500 psi when initially installed, whenever any seal subject to test pressure is broken, and following related repairs. The pipe and blind rams will be activated at least weekly and on every trip the pipe and blind rams will be activated.

c. An accumulator of sufficient capacity to open the hydraulically-controlled choke valve lines (if so equipped), close all rams, and retain a minimum of 200 psi above precharge on the closing manifold without the use of the closing unit pumps will be installed during the drilling of this well.

d. An upper kelly cock will be used during the drilling of this well.

e. Visual mud monitoring equipment will be used to detect volume changes indicating loss or gain in circulating fluid volume.

f. Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control.

4. PROPOSED CASING AND CEMENTING PROGRAM:

a. Surface casing will be set in the Uinta formation to approximately 260' and cemented to surface.

b. All potentially productive hydrocarbon zones will be isolated.

c. Casing designs are based on factors of burst: 1.00, collapse: 1.125, and joint strength: 1.8.

d. All casing strings will be pressure tested to 0.22 psi/ft. of casing string length or 1500 psi whichever is greater (not to exceed 70% of yield).

E. For details of casing, cement program, drilling fluid program, and proposed mud program, see the following attachment:

Drilling Program/Casing Design (EXHIBIT "D")

5. HAZARDOUS PRESSURES, TEMPERATURES, FLUIDS/GASSES EXPECTED:

a. Expected bottom hole temperature is 125 degrees F. Expected bottom hole pressure is 1500 psi.

b. No abnormal pressures or temperatures have been noted or reported in wells drilled to the Green River formation in this area.

c. No dangerous levels of hydrogen sulfide, hazardous fluids, or gasses have been found, reported, or known to exist at the depth to be drilled in this well, in this area.

6. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

a. The drilling operations for this well will begin as soon after APD approval as possible.

b. These drilling operations should be completed within 12 days after spudding the well depending on weather and hole conditions.

- c. If the well is productive, a sundry notice and plat showing exact installed facilities will be submitted.
- d. If this well is non-productive, a sundry notice will be filed with the BLM District Office within 30 days following completion of the well for abandonment.

7. OTHER

- a. Operator requests a variance to regulations requiring a straight run blooie line.
- b. Operator requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line.

B

Multi-Point Surface Use and Operations Plan

EQUITABLE RESOURCES ENERGY COMPANY
MONUMENT FEDERAL #12-11-9-17Y
SW NW SECTION 11, T9S, R17E
DUCHESNE COUNTY, UTAH

1. Existing Roads: Refer to Maps "A" & "B" (shown in RED)

- A. The proposed well site is staked and four reference stakes are present. 200' & 250' East and 150' & 200' North.
- B. The Monument Federal #12-11-9-17 is located 10 miles Southwest of Myton Utah in the SW1/4 NW1/4 Section 11, T9S, R17E, SLB&M, Duchesne County, Utah. To reach the 12-11-9-17Y, proceed West from Myton, Utah along U.S. Highway 40 for 1.6 miles to the junction of this highway and Sand Wash road; Proceed South along the Sand Wash road approximately 13.4 miles location which is on the North side of the existing road.
- C. Access roads - refer to Maps "A" and "B".
- D. Access roads within a one-mile radius - refer to map "B".
- E. The existing roads will be maintained in the same or better condition as existed prior to the commencement of operations and said maintenance will continue until final abandonment and reclamation of the well location.

2. Planned Access Roads: Refer to Map "B"

No new road construction will be required for access to the proposed well location.

- A. Width - maximum 30-foot overall right-of-way with an 18-foot road running surface, crowned & ditched and/or sloped and dipped.

- B. Construction standard - the access road will be constructed so as to conform to the standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. (1989)

The road will be constructed to meet the standards of the anticipated traffic flow and all-weather requirements. Construction will include ditching, draining, crowning, and capping or sloping and dipping the roadbed as necessary to provide a well constructed and safe road. Prior to construction/upgrading, the roadway shall be cleared of any snow cover and allowed to dry completely. Traveling off of the thirty (30) foot right-of-way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossing shall be designed so they will not cause siltation or the accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts.

Upgrading shall not be allowed during muddy conditions.

Should mud holes develop, they shall be filled in and detours around them avoided.

- C. Maximum grade - Less than 8%
- D. Turnouts - no turnouts will be required on this access road.
- E. Drainage design - the access road will be crowned and ditched or sloped and dipped, and water turnouts installed as necessary to provide for proper drainage along the access road route.
- F. Culverts, cuts and fills - none.
- G. Surface materials - all construction materials will be native material taken from onsite.
- H. Gates, cattleguards or fence cuts - none required.
- I. Road maintenance - during both the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and will be maintained in accordance with the original construction standards. All drainage ditches and culverts

will be kept clear and free-flowing, and will also be maintained in accordance with the original construction standards. The access road right-of-way will be kept free of trash during operations.

J. The proposed access road has been centerline flagged.

K. If a right-of-way is required please consider this APD the application for said right-of-way.

3. Location of Existing Wells Within a One-Mile Radius:

Please Refer to Map "C"

- A. Water wells - none known.
- B. Abandoned wells - see Map "C"
- C. Temporarily abandoned wells - none known.
- D. Disposal wells - none known.
- E. Drilling wells - none known.
- F. Producing wells - see Map "C".
- G. Shut-in wells - none known.
- H. Injection wells - none known.
- I. Monitoring wells - none known.

4. Location of Existing and/or Proposed Facilities Owned by Equitable Resources Energy Company Within a One-Mile Radius:

A. Existing

- 1. Tank batteries - see Map "C".
- 2. Production facilities - see Map "C".
- 3. Oil gathering lines - none.
- 4. Gas gathering lines - see Map "C".

B. New Facilities Contemplated

- 1. All production facilities will be located on the disturbed portion of the well pad and at a minimum of twenty-five (25) feet from the toe of the backslope or toe of the fill slope.
- 2. The production facilities will consist primarily of a pumping unit, Two tanks and an emergency pit. A diagram showing the proposed production facility layout is included in this APD.
- 3. Production facilities will be accommodated on the existing well pad. Construction materials required for installation of the production facilities will be obtained from the site; any additional materials required will be purchased from a local supplier having

a permitted (private) source of materials within the area.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

4. All permanent (onsite for six months or longer) above the ground structures constructed or installed including pumping units) will be painted Desert Brown. All production facilities will be painted within six (6) months of installation. Facilities required to comply with Occupational Health and Safety Act Rules and Regulations will be excluded from this painting requirement.
- C. The production (emergency) pit will be 12'x12' and will be fenced. Said fence will be maintained in good condition.
- D. During drilling and subsequent operations, all equipment and vehicles will be confined to the access road right-of-way and any additional areas as specified in the approved Application for Permit to Drill.
- E. Reclamation of disturbed areas no longer needed for operation will accomplished by grading, leveling and seeding as recommended by the Bureau of Land Management.

For Pipeline:

- F. Any proposed pipelines will be submitted to the authorized officer Via Sundry Notice for approval of subsequent operations.
- G. Equitable Resources Energy Company shall be responsible for road maintenance from the beginning to completion of operations.

5. Location and Type of Water Supply

- A. Water to be used for the drilling of these wells will be hauled by truck over the roads described in item #1 and item #2, from a well owned by Owen Dale Anderson of Vernal Utah or from a spring owned by Joe Shields of Myton Utah. Source will be determined by sundry notice closer to the

beginning of drilling operations.

B. No water well will be drilled on this location.

6. Source of Construction Materials

A. No construction materials are needed for drilling operations. In the event of production, the small amount of gravel needed for facilities will be hauled in by truck from a local gravel pit over existing access roads to the area. No special access other than for drilling operations and pipeline construction is needed.

B. All access roads crossing Federal land are described under item #2, and shown on Map #A.

All construction material for these location sites and access roads shall be borrowed material accumulated during the construction of the location sites and access roads. No additional construction material from other sources is anticipated at this time, if in the future it is required the appropriate actions will be taken to acquire it from private sources.

C. All surface disturbance area is on B.L.M. lands.

D. There are no trees on this location.

7. Methods of Handling Waste Materials:

A. Cuttings - the cuttings will be deposited in the reserve pit.

B. Drilling fluids - including salts and chemicals will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within one hundred twenty (120) days after termination of drilling and completion activities.

In the event adverse weather conditions prevent removal of the fluids from the reserve pit within this time period, an extension may be granted by the Authorized Officer upon receipt of a written request from Equitable Resources Energy Company.

The reserve pit will be constructed so as not to leak, break, or allow discharge. The reserve pit will be lined with a 12 mil plastic reinforced liner.

C. Produced fluids - liquid hydrocarbons produced during completion operations will be placed in test tanks on the location. Produced waste water will be confined to a lined pit (reserve pit) or storage tank for a period not to exceed ninety (90) days after initial production. During the ninety (90) day period, in accordance with Onshore Order #7, an application for approval of a permanent disposal method and location, along with the required water analysis, shall be submitted for the Authorized Officer's approval. Failure to file an application within the time frame allowed will be considered an incidence of noncompliance.

Any spills of oil, gas, salt water or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

D. Sewage - self-contained, chemical toilets will be provided for human waste disposal. Upon completion of operations, or as needed, the toilet holding tanks will be pumped and the contents thereof disposed of in the nearest, approved, sewage disposal facility.

E. Garbage and other waste material - garbage, trash and other waste materials will be collected in a portable, self-contained and fully-enclosed trash cage during drilling and completion operations. Upon completion of operations (or as needed) the accumulated trash will be disposed of at an authorized sanitary landfill. No trash will be burned on location or placed in the reserve pit.

F. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No adverse materials will be left on the location. Any open pits will be fenced during the drilling operation and the fencing will be maintained until such time as the pits are backfilled.

G. The reserve and/or production pit will be constructed on the existing location and will not be located in natural drainages where a flood hazard exists or surface runoff will destroy or damage the pit walls. All pits will be constructed so as not to leak, break, or allow the discharge of liquids therefrom.

8. Ancillary Facilities:

None anticipated.

9. Wellsite Layout:

- A. Plat #1 shows the drill site layout as staked. Cross sections have been drafted to visualize the planned cuts and fills across the location. An average minimum of six (6) inches of topsoil will be stripped from the location (including areas of cut, fill, and/or subsoil storage) and stockpiled for future reclamation of the well site. Refer to Figure #1 for the location of the topsoil and subsoil stockpiles. The reserve pit will be on the South side of location. Access will be from the South near corner #6. Corner #6 will be rounded to avoid excess cut. Corner #2 will be rounded to avoid excess fill.
- B. Plat #2 is a diagram showing the rig layout. No permanent living facilities are planned. There may be as many as three (3) trailers on location during drilling operation.
- C. A completion rig will be moved onto location for completion operations after drilling operations have been completed and the drilling rig has been moved off location.
- D. A diagram showing the proposed production facility layout is included in this APD.
- E. The reserve pit will be constructed so as to be capable of holding 12,000 bbls. of fluid.

The reserve pit will be lined with a 12 mil plastic liner, it will be torn and perforated after the pit dries and before backfilling of the reserve pit.

- F. Prior to the commencement of drilling operations, the reserve pit will be fenced on three (3) sides using 39-inch net wire with one strand of barbed wire on top of the net wire. The net wire will be no more than two inches above the ground. the barbed wire will be three inches above the net wire. total height of the fence will be at least 42-inches.
 - 1. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
 - 2. Standard steel, wood, or pipe posts shall be used between the corner braces. The maximum distance between any two (2) posts shall be no greater than sixteen (16) feet.
 - 3. All wire shall be stretched, by using a stretching

device, before it is attached to the corner posts.

The fourth side of the reserve pit will be fenced immediately upon removal of the drilling rig and the fencing will be maintained until the pit is backfilled.

- G. Any hydrocarbons on the pit will be removed from the pit as soon as possible after completion operations are completed.

10. Plans for Reclamation of the Surface:

The B.L.M. will be contacted prior to commencement of any reclamation operations.

A. Production

1. Immediately upon well completion, the well location and surrounding area(s) will be cleared of all debris, materials, trash and junk not required for production.
2. Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.
3. The plastic pit liner shall be torn and perforated before backfilling of the reserve pit.
4. Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed.

Other waste and spoil materials will be disposed of immediately upon completion of drilling and workover activities.

5. The reserve pit and that portion of the location and access road not needed for production facilities/operations will be reclaimed within one hundred twenty (120) days from the date of well completion, weather permitting.
6. If the well is a producer, Equitable Resources Energy Company will, upgrade and maintain access roads as necessary to prevent soil erosion, and accommodate year round traffic. Reshape areas unnecessary to operations, distribute topsoil, disk and seed all disturbed areas outside the work area according to the recommended seed mixture. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

If the well is abandoned/dry hole, Equitable Resources Energy Company will, restore the access road and location to approximately the original contours. During reclamation of the site, push the fill material into cuts and up over the backslope. Leave no depressions that will trap water or form ponds. Distribute topsoil evenly over the location, and seed according to the above seed mixture. The access road and location shall be ripped or disked prior to seeding. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

Seedbed will be prepared by disking, following the natural contours. Seed will be drilled on contours at a depth no greater than one-half inch (1/2"). In areas that cannot be drilled, seed will be broadcast at double the seeding rate and harrowed into soil. Certified seed will be used whenever available.

Fall seeding will be completed after September 15 and prior to prolonged ground frost. Spring seeding, to be effective, will be completed after the frost has left the ground and prior to May 15th.

7. Upon completion of backfilling, leveling and recontouring, the stockpiled topsoil will be evenly spread over the reclaimed area(s). Prior to reseeding, all disturbed surfaces will be scarified and left with a rough surface. No depressions will be left that would trap water and form ponds. All disturbed surfaces will be reseeded with the seed mixture stipulated by the B.L.M.

Seed will be drilled on the contour to a approximate depth of one-half (1/2) inch. All seeding will be conducted after September 15 and prior to ground frost. Spring seeding will be done after the frost leaves the ground and no later than May 15. If the seeding is unsuccessful, Equitable Resources may be required to make subsequent seedings.

B. Dry Hole/Abandoned Location

1. On lands administered by the Bureau of Land Management, abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include:

(c) ensuring revegetation of the disturbed areas to the specifications of the Bureau of Land Management at

the time of abandonment.

2. All disturbed surfaces will be recontoured to the approximate natural contours and reseeded according to BLM specifications. Reclamation of the well pad and access road will be performed as soon as practical after final abandonment and reseeded operations will be performed in the fall or spring following completion of reclamation operations.

11. Surface Ownership:

The well site and proposed access road are situated on surface lands administered by

Bureau of Land Management
Vernal District Office
Vernal, Utah

12. Other Information:

- A. Topographic and geologic features of the area (reference Topographic Map #A) are:

The proposed drill site is located in the Monument Butte oil field, which lies in a large basin formed by the Uinta Mountains to the North and the Bookcliff Mountains to the South. The site is located approximately 15 miles Northwest of the Green River, which is the major drainage for this area, and approximately 13 miles Southwest of Myton Utah.

This basin floor is interlaced with numerous canyons and ridges formed by the non-perennial streams of the area. The sides of these canyons are steep and ledges formed in sandstone, conglomerate deposits and shale are common in this area.

The geologic structures that are visible in the area are of the Uinta formation (Eocene Epoch) tertiary period and the cobblestone and younger alluvial deposits from the Quaternary period.

The soils in the semi-arid area of the Williams Fork Formation (Upper Cretaceous) and Wasatch Formation (Eocene) consist of light brownish gray clay (OL) to sand soil (SM-ML) type with poorly graded gravels.

Outcrops of sandstone ledges, conglomerate deposits and shale are common in this area.

The topsoils in the area range from a sandy clay (SM-ML) type soil to a clayey (OL) soil.

The majority of the numerous washes and draws in the area are of a non-perennial nature flowing during the early spring run-off and heavy rain storms of long duration which are rare as the normal annual rainfall in the area is only 8".

The flora of the area includes sagebrush, mountain mahogany, serviceberry, rabbit brush, greasewood, four-wing saltbush, Gambel scrub oak, willow, tamarack, shadscale, Spanish bayonet, indian rice grass, cheatgrass, wheatgrass, curly grass, crested wheatgrass, sweet clover, gum weed, foxtail, mustard, Canadian thistle, Russian thistle, Kochia, sunflowers and cacti.

The fauna of the area includes cattle, horses, elk, deer, coyotes, rabbits, rodents, lizards, bull snakes, rattle snakes, water snakes and horned toads. Birds of the area are ground sparrows, bluejays, bluebirds, magpies, ravens, raptors, morning doves, swallows, nighthawks, hummingbirds, and chukar.

- B. The surface ownership is Federal. The surface use is grazing and petroleum production.
- C.
 1. The closest live water is the Green River which is approximately 15 miles Southwest of the proposed site.
 2. There are no occupied dwellings in the immediate area
 3. An archaeological report will be forwarded upon completion.
 4. There are no reported restrictions or reservations noted on the oil and gas lease.
 5. A silt catchment dam will not be required for this location.

13. Lessee's or Operator's Representative:

Equitable Resources Energy Company
1601 Lewis Avenue
P.O. Box 21017
Billings, Montana 59104
(8:00 a.m. to 5:00 p.m.)
(406)259-7860
FAX: (406)245-1361

Dave McCoskery,

Home (406)248-3864

Dale Griffin,

Home (303)824-3323

14. certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that any statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Balcron Oil, a division of Equitable Resources Energy Company, and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

6-24-96

Date

Bobbie Schuman /mmc

Bobbie Schuman
Coordinator of Environmental
and Regulatory Affairs
Equitable Resources Energy Co.



Well Prognosis

Well Name Monument Federal #12-11-9-17Y				Control Well			
Location SW/NW Section 11-T9S-R17E (1996 FNL, 660 FWL)				Operator EREC			
County/State Duchesne County, Utah				Well Name Federal 11-11-9-17Y			
Field Monument Butte		Well Type Dev.		Location SW/NW Section 11-T9S-R17E			
GL (Ung)	5077	EST. KB	5086	Total Depth	5600		
				KB 5087			

Formation	Prognosis		Sample Top		Control Well Datum	High/Low		
	Depth	Datum	Depth	Datum		Prog	Control	Deviation
UINTA	surface							
GREEN RIVER	1319	3767			3717			
HORSEBENCH SS	2156	2930			2880			
2ND GARDEN GULCH	3735	1351			1301			
Y-3 (PAY)	4071	1015			965			
Y-4 (PAY)	4199	887			837			
YELLOW MARKER	4346	740			690			
Y-6 (PAY)	4415	671			621			
DOUGLAS CREEK	4508	578			528			
R-5 (PAY)	4571	515			465			
2ND DOUGLAS CREEK	4750	336			286			
GREEN MARKER	4890	196			146			
BLACK SHALE FACIES	5223	-137			-187			
CARBONATE MARKER	5330	-244			-294			
B-2 (PAY)	5430	-344			-394			
TD	5600							

Samples

50' FROM 1200' TO 3800'

20' FROM 3800' TO TD

5' THROUGH EXPECTED PAY

5' THROUGH DRILLING BREAKS

DST,s

DST #1 NONE

DST #2

DST #3

DST #4

Wellsite Geologist

Name: _____

From: _____ To: _____

Address: _____

Phone # _____ wk.

_____ hm.

Fax # _____

Logs

DLL FROM SURF CSNG TO TD

LDT/CNL FROM 3800' TO TD

Cores

Core #1 _____

Core #2 _____

Core #3 _____

Core #4 _____

Comments:

Mud Logger

Company: _____

From: 1200 _____ To: TD _____

Type: _____

Logger: _____

Phone # _____

Fax # _____

Report To: 1st Name: DAVE BICKERSTAFF Phone # (406)259-7860 wk. (406)245-2261 hm.

2nd Name: KEVEN REINSCHMIDT Phone # (406)259-7860 wk. (406)248-7026 hm.

Prepared By: DAVE BICKERSTAFF Phone # _____ wk. _____ hm.



**EQUITABLE RESOURCES
ENERGY COMPANY
WESTERN REGION**

DRILLING PROGRAM

WELL NAME: Monument Federal #12-11-9-17Y

DATE: 5-21-96

PROSPECT/FIELD: Monument Butte

LOCATION: SW/NE Section 11 Twn.9S Rge.17E

COUNTY: Duchesne

STATE: Utah

TOTAL DEPTH: 5600'

HOLE SIZE INTERVAL

12 1/4"	Surface to 260'
7 7/8"	260' to 5600'

CASING	INTERVAL		CASING		
	STRING TYPE	FROM	TO	SIZE	WEIGHT
Surface Casing	0'	260'	8 5/8"	24	J55
Production Casing	0'	5600'	5 1/2"	15.50	K55

CEMENT PROGRAM

Surface Casing 150 sacks class "G" with 2% CaCl and 1/4 lb/sack Flocele.
(Cement will be circulated to surface.)

Production Casing 250 sacks Thrifty Lite and 400 sacks 50-50 Poz.
(Actual cement volumes will be calculated from caliper log with cement top at 2000')

PRELIMINARY DRILLING FLUID PROGRAM

TYPE	FROM	TO	WEIGHT	PLAS.	YIELD
				VIS	POINT
Air and Air Mist	0'	260'	N.A.	N.A.	N.A.
Air/Air Mist/KCl wtr	260'	T.D.	8.7-8.9	N.A.	N.A.

COMMENTS

1.) No cores or tests are planned for this well.

EQUITABLE RESOURCES ENERGY COMPANY

Operator: EREC	Well Name: Monument Fed. 12-11
Project ID:	Location: Duchesne, Utah

Design Parameters:

Mud weight (8.90 ppg) : 0.462 psi/ft
 Shut in surface pressure : 2537 psi
 Internal gradient (burst) : 0.009 psi/ft
 Annular gradient (burst) : 0.000 psi/ft
 Tensile load is determined using air weight
 Service rating is "Sweet"

Design Factors:

Collapse : 1.125
 Burst : 1.00
 8 Round : 1.80 (J)
 Buttress : 1.60 (J)
 Other : 1.50 (J)
 Body Yield : 1.50 (B)

Length (feet)	Size (in.)	Weight (lb/ft)	Grade	Joint	Depth (feet)	Drift (in.)	Cost
1	5,600	5.500	15.50	J-55	ST&C	5,600	4.825

	Collapse Load (psi)	Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Tension Load (kips)	Strgth (kips)	S.F.
1.	2589	4040	1.560	2589	4810	1.86	86.80	202	2.33 J

Prepared by : *McCoskery, Billings, Montana*

Date : 05-21-1996

Remarks :

Minimum segment length for the 5,600 foot well is 1,500 feet.

SICP is based on the ideal gas law, a gas gravity of 0.10, and a mean gas temperature of 115°F (Surface 74°F , BHT 152°F & temp. gradient 1.400°/100 ft.)

String type: Production

The mud gradient and bottom hole pressures (for burst) are 0.462 psi/ft and 2,589 psi, respectively.

NOTE : The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - collapse (with evacuated casing), 1.0 - (uniaxial) burst, 1.8 - API 8rd tension, 1.6 - buttress tension, 1.5 - body yield tension, and 1.6 - EUE 8rd tension. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser.
 Costs for this design are based on a 1987 pricing model. (Version 1.07)

EXHIBIT E


- A. Hazardous chemicals 10,000 pounds of which will most likely be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:

We anticipate that none of the hazardous chemicals in quantities of 10,000 pounds or more will be associated with these operations.

- B. Extremely hazardous substances threshold quantities (per Howard Cleavinger 11/30/93) of which will be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:

We anticipate that none of the extremely hazardous substances in threshold quantities per 40 CFR 355 will be associated with these operations.

12/1/93
Revised 12/7/93
/rs




Proposed Location of the
MONUMENT FEDERAL #12-11-9-17Y

EQUITABLE RESOURCES CO.

***MONUMENT FEDERAL #12-11-9-17Y
 SEC. 11, T9S, R17E, S.L.B.&M.
 TOPO "A"***



Tri State
Land Surveying, Inc.
 (801) 781-2501
 38 WEST 100 NORTH VERNAL, UTAH 84078



Proposed Location:
MONUMENT FEDERAL #12-11-9-17Y

PROPOSED ACCESS
 ROAD ± 80'

± 1.9 Mi.

EQUITABLE RESOURCES CO.

MONUMENT FEDERAL #12-11-9-17Y
 SEC. 11, T9S, R17E, S.L.B.&M.
 TOPO "B"




SCALE: 1" = 2000'

Tri State
Land Surveying, Inc.
 (801) 781-2501

38 WEST 100 NORTH VERNAL, UTAH 84078

TYPICAL RIG LAYOUT

MONUMENT FEDERAL #12-11-9-17Y



Tri State
Land Surveying, Inc.
(801) 781-2501
38 WEST 100 NORTH, VERNAL, UTAH 84078

UNION DRILLING RIG #17

Hex Kelly -

ROTATING HEAD

ADJ. CHOKE

AIR BOWL

7" FLOWLINE

#3000
BLIND RAM-PIPE RAM


3" GATE VALVE


3" GATE VALVE

3" CHOKE LINE

ADJ. CHOKE

#3000 STACK





EQUITABLE RESOURCES CO.

MONUMENT FEDERAL #12-11-9-17Y
 SEC. 11, T9S, R17E, S.L.B.&M.
 TOPO "C"



Tri State
 Land Surveying, Inc.
 (801) 781-2501
 38 WEST 100 NORTH VERNAL, UTAH 84078

PROPOSED PRODUCTION FACILITY DIAGRAM

EXHIBIT "J"

VALVE DESCRIPTION		
	DURING PROD.	DURING SALES
VALVE #1	CLOSED	OPEN
VALVE #2	OPEN	CLOSED
VALVE #3	CLOSED	OPEN
VALVE #4	OPEN	CLOSED
VALVE #5	CLOSED	CLOSED
VALVE #6	CLOSED	CLOSED
VALVE #7	CLOSED	OPEN

DIKE




DIAGRAM NOT TO SCALE






EQUITABLE RESOURCES ENERGY COMPANY

BALCRON OIL DIVISION

1601 Lewis Avenue
Billings, MT 59104-2
(406) 259-7860

EQUITABLE RESOURCES ENERGY CO.

MONUMENT FEDERAL #12-11-9-17Y
SEC. 11, T9S, R17E, S.L.B.&M.



REFERENCE POINTS

150' NORTH	= 5073.1'
200' NORTH	= 5076.7'
200' EAST	= 5076.1'
250' EAST	= 5076.3'

APPROXIMATE YARDAGES

CUT	= 2,460 Cu. Yds.
FILL	= 2,450 Cu. Yds.
PIT	= 1,770 Cu. Yds.
6" TOPSOIL	= 910 Cu. Yds.

SURVEYED BY:	S.S.
DRAWN BY:	J.R.S.
DATE:	2-29-96
SCALE:	1" = 50'
FILE:	

Tri State
Land Surveying, Inc.
(801) 781-2501
38 WEST 100 NORTH VERNAL, UTAH 84078

**CULTURAL RESOURCE EVALUATION
OF 11 PROPOSED MONUMENT FEDERAL WELL LOCATIONS
IN THE WELLS DRAW, CASTLE PEAK DRAW,
PLEASANT VALLEY, & PARIETTE BENCH LOCALITIES
OF DUCHESNE COUNTY, UTAH**

Report Prepared for **Equitable Resources Energy Company**

Dept. of Interior Permit No.: UT-96-54937
AERC Project 1527 (BLCR-96-2)

Utah State Project No.: UT-96-AF-217b

Principal Investigator
F. Richard Hauck, Ph.D.

Author of the Report
F. Richard Hauck



**ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH
CORPORATION (AERC)**

181 North 200 West, Suite 5
Bountiful, Utah 84011-0853

May 10, 1996

ABSTRACT

An intensive cultural resource evaluation has been conducted for Equitable Resources Energy Company of 11 proposed Monument Federal well locations situated on federally administered lands in the Wells Draw, Castle Peak Draw, Pleasant Valley, and Pariette Bench localities of Duchesne County, Utah. This evaluation includes the Monument Federal Units 42-6-9-16Y, 43-6-9-16Y, 11-22-9-16Y, 12-11-9-17Y, 41-18-9-16Y, 14-22-8-17, 24-17-9-16, 44-17-9-16, 22-20-9-16, 42-20-9-16, and 31-5-9-17. This study involved a total of ca. 134.7 acres; 110 acres are associated with the ten acre parcels examined around each of the 11 well locations and 24.7 and acres are associated with the 2.07 miles of access routes associated with eight of the 11 well locations. These investigations were conducted by F.R. Hauck and by Glade Hadden on May 1 and 7, 1996; these archaeologists were assisted by James Merrell of Vernal, Utah.

No previously recorded significant or National Register eligible cultural resources will be adversely affected by the proposed 11 well locations and associated access routes.

No newly identified historic or prehistoric cultural resource loci were identified and recorded during the inventory.

No isolated artifacts were noted during the evaluations.

AERC recommends project clearance based on adherence to the stipulations noted in the final section of this report.

TABLE OF CONTENTS

	page
Abstract	ii
Table of Contents	iii
List of Maps of the Project Area	iv
General Information	1
Project Location	1
Environmental Description	9
Previous Research in the Locality	10
File Search	10
Prehistory and History of the Project Area	10
Site Potential in the Project Development Zone	10
Field Evaluations	11
Methodology	11
Site Significance Criteria	12
Results of the Inventory	12
Conclusion and Recommendations	13
References	14

LIST OF MAPS

	page
MAP 1: General Project Locality in Duchesne County, Utah.	2
MAP 2: Cultural Resource Survey of Proposed Well Locations in the Wells Draw Locality of Duchesne County, Utah	3
MAP 3: Cultural Resource Survey of Proposed Well Locations in the Wells Draw Locality of Duchesne County, Utah	4
MAP 4: Cultural Resource Survey of Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah	5
MAP 5: Cultural Resource Survey of Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah	6
MAP 6: Cultural Resource Survey of Proposed Well Locations in the Pleasant Valley Locality of Duchesne County, Utah	7
MAP 7: Cultural Resource Survey of Proposed Well Locations in the Pariette Bench Locality of Duchesne County, Utah	8

GENERAL INFORMATION

On May 1 and 7, 1996, AERC archaeologists F. Richard Hauck and Glade Hadden, assisted by James Merrell, conducted intensive cultural resource evaluations of 11 proposed Monument Federal well locations in the Wells Draw, Castle Peak Draw, Pleasant Valley and Pariette Bench localities of Duchesne County, Utah (see Map 1). The purpose of this report is to detail the results of these evaluations, which include the Monument Federal Units 42-6-9-16Y, 43-6-9-16Y, 11-22-9-16Y, 12-11-9-17Y, 41-18-9-16Y, 14-22-8-17, 24-17-9-16, 44-17-9-16, 22-20-9-16, 42-20-9-16, & 31-5-9-17 (see Maps 2 through 7) and access routes associated with eight of the 11 well sites. Some 134.7 acres were examined which include 110 acres associated with the 11 ten acre well pad parcels and 24.7 acres associated with the 2.07 miles of 100 foot-wide access corridor. All proposed pipelines are situated on federal lands administered by the Vernal District of the Bureau of Land Management, Diamond Mountain Resource Area, Vernal, Utah.

The purpose of the field study and this report is to identify and document cultural site presence and assess National Register potential significance relative to established criteria (cf., Title 36 CFR 60.6). The proposed development of these well locations and access corridors requires an archaeological evaluation in compliance with U.C.A. 9-8-404, the Federal Antiquities Act of 1906, the Reservoir Salvage Act of 1960-as amended by P.L. 93-291, Section 106 of the National Historic Preservation Act of 1966-as amended, the National Environmental Policy Act of 1969, the Federal Land Policy and Management Act of 1979, the Archaeological Resources Protection Act of 1979, the Native American Religious Freedom Act of 1978, the Historic Preservation Act of 1980, and Executive Order 11593.

In addition to documenting cultural identity and significance, mitigation recommendations relative to the preservation of cultural data and materials can be directed to the Bureau of Land Management, Vernal District Office and to the State Antiquities Section.

Project Location

The project location is in the Wells Draw, Castle Peak Draw, Pleasant Valley, and Pariette Bench localities of Duchesne County, Utah. These 11 wells are situated on the Myton SW, Myton SE, and Pariette Draw SW, 7.5 minute topographic quads. The proposed Monument Federal Wells are in the following sections:


Unit 42-6-9-16Y (see Map 2) is in the southeast quarter of the northeast quarter of Section 6, Township 9 South, Range 16 East, Salt Lake B. & M. Its .3 mile-long access links to an existing two-track to the south of the location;

Unit 43-6-9-16Y (see Map 2) is in the northeast quarter of the southeast quarter of Section 6, Township 9 South, Range 16 East, Salt Lake B. & M.

**MAP 1: GENERAL PROJECT LOCALITY
IN
DUCHESNE COUNTY
UTAH**



**PROJECT: BLCR - 96 - 2
SCALE: see below
QUAD: see below
DATE: May 10, 1996**



UTAH GEOLOGICAL AND MINERAL SURVEY
MAP 43 1977
PHYSIOGRAPHIC SUBDIVISIONS OF UTAH
BY W.L. STOKES




**TOWNSHIP: MULTIPLE
RANGE: MULTIPLE
MERIDIAN: SALT LAKE & UINTAH B. & M.**

**MAP 2: CULTURAL RESOURCE SURVEY
OF PROPOSED WELL LOCATIONS IN
THE WELLS DRAW
LOCALITY OF DUCHESNE COUNTY,
UTAH**



PROJECT: BLCR - 96- 2
SCALE: 1: 24,000
QUAD: Myton SW, Utah
DATE: May 10, 1996



TOWNSHIP: 9 South
RANGE: 16 East
MERIDIAN: Salt Lake B. & M.


LEGEND

- Well Location
- Access Route
- Survey Area
- Pipeline Corridor

**MAP 3: CULTURAL RESOURCE SURVEY
OF PROPOSED WELL LOCATIONS IN
THE WELLS DRAW
LOCALITY OF DUCHESNE COUNTY,
UTAH**



PROJECT: BLCR - 96- 2
SCALE: 1: 24,000
QUAD: Myton SW, Utah
DATE: May 10, 1996



TOWNSHIP: 9 South
RANGE: 16 East
MERIDIAN: Salt Lake B. & M.

LEGEND

Well Location ▲

Access Route - - -


Survey Area □

Pipeline Corridor ↔

**MAP 4: CULTURAL RESOURCE SURVEY
OF PROPOSED WELL LOCATIONS IN
CASTLE PEAK DRAW
LOCALITY OF DUCHESNE COUNTY,
UTAH**



PROJECT: BLCR - 96 - 2
SCALE: 1: 24,000
QUAD: Myton SE, Utah
DATE: May 10, 1996



TOWNSHIP: 9 South
RANGE: 16 East
MERIDIAN: Salt Lake B. & M.

LEGEND



Well Location ▲
Access Route - - -

Survey Area □
Pipeline Corridor ↔

**MAP 5: CULTURAL RESOURCE SURVEY
 OF PROPOSED WELL LOCATIONS IN
 CASTLE PEAK DRAW
 LOCALITY OF DUCHESNE COUNTY,
 UTAH**



PROJECT: BLCR - 96- 2
SCALE: 1: 24,000
QUAD: Myton SE, Utah
DATE: May 10, 1996



TOWNSHIP: 9 South
RANGE: 17 East
MERIDIAN: Salt Lake B. & M.

LEGEND

Well Location ▲

Access Route - - - - -


Survey Area □

Pipeline Corridor ↔


**MAP 6: CULTURAL RESOURCE SURVEY
OF PROPOSED WELL LOCATIONS IN
THE PLEASANT VALLEY
LOCALITY OF DUCHESNE COUNTY,
UTAH**



PROJECT: BLCR - 96- 2
SCALE: 1: 24,000
QUAD: Pariette Draw SW, Utah
DATE: May 10, 1996



UNIT 14-22-8-17



TOWNSHIP: 8 South
RANGE: 17 East
MERIDIAN: Salt Lake B. & M.

LEGEND

Well Location ▲



Access Route - - -

Survey Area □

Pipeline Corridor ↔

**MAP 7: CULTURAL RESOURCE SURVEY
OF PROPOSED WELL LOCATIONS IN
THE PARIETTE BENCH
LOCALITY OF DUCHESNE COUNTY,
UTAH**

PROJECT: BLCR - 96- 2
SCALE: 1: 24,000
QUAD: Pariette Draw SW, Utah
DATE: May 10, 1996



TOWNSHIP: 9 South
RANGE: 17 East
MERIDIAN: Salt Lake B. & M.

LEGEND

Well Location ▲

Access Route - - -

Survey Area □

Pipeline Corridor ↔

Unit 41-18-9-16Y (see Map 3) is in the northeast quarter of the northeast quarter of Section 18, Township 9 South, Range 16 East, Salt Lake B. & M.

Unit 24-17-9-16 (see Map 3) is in the southeast quarter of the southwest quarter of Section 17, Township 9 South, Range 16 East, Salt Lake B. & M. Its .33 mile-long access route links with the county road to the southwest of the location.

Unit 44-17-9-16 (see Map 3) is in the southeast quarter of the southeast quarter of Section 17, Township 9 South, Range 16 East, Salt Lake B. & M. Its .3 mile-long access route links with an existing well location and road to the southwest of the location.

Unit 22-20-9-16 (see Map 3) is in the southeast quarter of the northwest quarter of Section 20, Township 9 South, Range 16 East, Salt Lake B. & M. Its .1 mile-long access route links with an existing road to the southeast of the location.

Unit 42-20-9-16 (see Map 3) is in the southeast quarter of the northeast quarter of Section 20, Township 9 South, Range 16 East, Salt Lake B. & M. Its .23 mile-long access route links with an existing well location to the northwest of the location.

Unit 11-22-9-16Y (see Map 4) is in the northwest quarter of the northwest quarter of Section 22, Township 9 South, Range 16 East, Salt Lake B. & M. Its .38 mile-long access route links with an existing road to the west of the location.

Unit 31-5-9-17 (see Map 5) is in the northwest quarter of the northeast quarter of Section 5, Township 9 South, Range 17 East, Salt Lake B. & M. Its .33 mile-long access route links with an existing well to the west of the location.

Unit 14-22-8-17 (see Map 6) is in the southwest quarter of the southwest quarter of Section 22, Township 8 South, Range 17 East, Salt Lake B. & M. Its .1 mile-long access route links with the county road to the west of the location after passing through a pasture on private land.

Unit 12-11-9-17Y (see Map 7) is in the southwest quarter of the northwest quarter of Section 11, Township 9 South, Range 17 East, Salt Lake B. & M.

Environmental Description

The project area is within the 5100 to 6100 foot elevation zone above sea level. Open rangeland terrain and eroded Eocene lakebed surfaces are associated with the project area.

The vegetation in the project area includes *Chrysothamnus* spp., *Artemisia* spp., *Sarcobatus vermiculatus*, *Ephedra viridis*, *Cercocarpus* spp., *Atriplex canescens*, and a variety of grasses.

The geological associations within the project area consist of fluvial lake deposits which correlate with the Uinta Formation which is of Tertiary age.

PREVIOUS RESEARCH IN THE LOCALITY

File Search

A records search of the site files and maps at the Antiquities Section of the State Historic Preservation Office in Salt Lake City was conducted on May 6, 1996. A similar search was conducted in the Vernal District Office of the BLM on April 24, 1996. The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed developments.

A variety of known cultural sites are situated in the Monument Buttes / Castle Peak Draw locality. Many of these prehistoric resources were identified and recorded by AERC during the Mapco River Bend survey (Hauck and Norman 1980). Other sites have been located and recorded by AERC and other archaeologists and consultants during oil and gas exploration inventories (cf., Fike and Phillips 1984, Hauck and Weder 1989, Hauck and Hadden 1993, 1994, 1995).

Prehistory and History of the Cultural Region

Currently available information indicates that the Northern Colorado Plateau Cultural Region has been occupied by a variety of cultures beginning perhaps as early as 10,000 B.C. These cultures, as identified by their material remains, demonstrate a cultural developmental process that begins with the earliest identified Paleoindian peoples (10,000 -- 7,000 B.C.) and extends through the Archaic (ca. 7,000 B.C. -- A.D. 300), and Formative (ca. A.D. 400 -- 1100) Stages, and the Late Prehistoric-Protohistoric periods (ca. A.D. 1200 -- 1850) to conclude in the Historic-Modern period which was initiated with the incursion of the Euro-American trappers, explorers, and settlers. Basically, each cultural stage -- with the possible exception of the Late Prehistoric hunting and gathering Shoshonean bands -- features a more complex life-way and social order than occurred during the earlier stage of development (Hauck 1991:53). For a more comprehensive treatment of the prehistory and history of this region see Archaeological Evaluations in the Northern Colorado Plateau Cultural Area (Hauck 1991).

Site Potential in the Project Development Zone

Previous archaeological evaluations in the general project area have resulted in the identification and recording of a variety of cultural resource sites having eligibility for potential nomination to the National Register of Historic Places (NRHP). The majority of these sites are lithic scatters containing cobble reduction materials. Many of these quarry sites are of the "Tap and

Test" variety, and extend for tens or hundreds of meters. Open occupations are also frequently being identified in this locality. Sites associated with the open rangeland generally appear to have been occupied during the Middle Plains Archaic Stage with occasional indications of Paleoindian activity based on the recovery of isolated Plano style projectile points. The north-south drainage canyons appear to contain the majority of Late Prehistoric (Numa) sites probably because those canyon floors were transportation corridors and convenient pastures for the Ute horse herds. Evidence of Formative Stage occupation, i.e., Fremont, is rarely observed in the rangeland environment but is common within the Green River and White River canyons and their primary tributary canyons.

Site density in certain portions of the region appears to range from one to four sites per section. These densities increase in the canyon bottoms due to Ute rock art loci. Recent evaluations indicate that the site densities may reach 8 to 12 sites per section in certain localities on the upper benches which were apparently favored for hunting, lithic resource procurement, and camping. Prehistoric sites on the rangeland benches appear to be associated with water courses and aeolian deposits.

FIELD EVALUATIONS

Methodology

Intensive evaluations consisted of the archaeologists walking a series of 15 to 20 meter-wide transects within the ten acre parcel associated with each well pad zone and along a 100 foot-wide corridor centered on the flagged centerline for each of the associated access routes as shown on Maps 2 through 6. Thus, ca. 134.7 acres was inventoried relative to these proposed well locations of which 110 includes the ten acre parcels and ca. 24.7 acres includes the 2.07 miles of various access corridor.

Observation of cultural materials results in intensive examinations to determine the nature of the resource (isolate or activity locus). The analysis of each specific cultural site results in its subsequently being sketched, photographed, and appropriately recorded on standard IMACS forms.

In certain instances, the cultural sites are then evaluated for depth potential utilizing AERC's portable Ground Penetrating Radar (GPR) computerized system (SIR-2 manufactured by Geophysical Survey Systems, Inc. [GSSI] of North Salem, New Hampshire). GPR was not used during this project.

Cultural sites are then evaluated for significance utilizing the standards described below and mitigation recommendations are considered as a means of preserving significant resources which may be situated within the development zone.

Site Significance Criteria

Prehistoric and historic cultural sites which can be considered as eligible for nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

- a. That are associated with events that have made a significant contribution to the broad patterns of our history; or*
- b. that are associated with the lives of persons significant in our past; or*
- c. that embody the distinctive characteristics of a type, period, or method of construction ... ; or*
- d. that have yielded, or may be likely to yield, information important in prehistory or history.*

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National Register if it should advance our current state of knowledge relating to chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.

Results of the Inventory

No newly identified prehistoric cultural resource activity loci were observed and recorded during the archaeological evaluations of the proposed plant site and the three pipeline complexes.

No previously recorded cultural resource loci will be adversely effected by the proposed development of these 11 well locations.


No diagnostic isolated artifacts were observed and recorded during the evaluations.

CONCLUSION AND RECOMMENDATIONS

No known cultural resources will be adversely impacted during the development and operation of the various Monument Federal Units 42-6-9-16Y, 43-6-9-16Y, 11-22-9-16Y, 12-11-9-17Y, 41-18-9-16Y, 14-22-8-17, 24-17-9-16, 44-17-9-16, 22-20-9-16, 42-20-9-16, & 31-5-9-17.

AERC recommends that a cultural resource clearance be granted to Equitable Resources Energy Company relative to the development of these proposed wells and associated access routes based upon adherence to the following stipulations:

1. all vehicular traffic, personnel movement, construction and restoration operations should be confined to the well pad zones, flagged areas, and corridors examined as referenced in this report, and to the existing roadways;
2. all personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area; and
3. the authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.



F. Richard Hauck, Ph.D.
President and Principal
Investigator

REFERENCES

Fike, Richard E. and H. Blaine Phillips II

1984 *A Nineteenth Century Ute Burial from Northeast Utah*. Cultural Resource Series No. 16, Bureau of Land Management, Salt Lake City.

Hauck, F. Richard

1981 Cultural Resource Inventory of Nine Proposed Well Locations and Access Roads in the Coyote Basin Locality of Uintah County, Utah, and in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Diamond Shamrock, DS-81-2, Archeological-Environmental Research Corporation, Bountiful.

1982 Cultural Resource Inventory of Five Proposed Well Locations and Access Roads in the Eightmile Flat and Castle Peak Localities of Uintah and Duchesne Counties, Utah. Report Prepared for Diamond Shamrock, DS-82-5, Archaeological-Environmental Research Corporation, Bountiful.

1984a "Excavation" (in) *A Nineteenth Century Ute Burial from Northeast Utah*. Cultural Resource Series No. 16, Bureau of Land Management, Salt Lake City.

1984b Cultural Resource Evaluations of Seven Proposed Well Locations Situated in the Castle Peak Draw Locality of Uintah County, Utah. Report Prepared for Overthrust Oil and Royalty Company, OORC-84-1, Archaeological-Environmental Research Corporation, Bountiful.

1991 Archaeological Evaluations on the Northern Colorado Plateau Cultural Area, AERC Paper No. 45, Archeological-Environmental Research Corporation, Bountiful.

1992a Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-2, Archeological-Environmental Research Corporation, Bountiful.

1992b Addendum to Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-4, Archeological-Environmental Research Corporation, Bountiful.

- 1992c Cultural Resource Evaluations of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-5, Archeological-Environmental Research Corporation, Bountiful.
- 1992d Cultural Resource Evaluation of a Proposed Water Pipeline Corridor in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-6, Archeological-Environmental Research Corporation, Bountiful.
- 1992e Cultural Resource Evaluation of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-8, Archeological-Environmental Research Corporation, cf., Bountiful.
- 1993a Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-1, Archeological-Environmental Research Corporation, Bountiful.
- 1993b Addendum to Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-2, Archeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of a Pipeline Corridor Situated in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-3, Archeological-Environmental Research Corporation, Bountiful.
- 1996a Cultural Resource Evaluation of Four Proposed Well Locations and Access Routes in the Castle Peak Draw Locality -- Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-95-8A, Archeological-Environmental Research Corporation, Bountiful.
- 1996b Cultural Resource Evaluation of 13 Proposed Well Locations and Access Routes in the Castle Peak Draw Locality of Uintah and Duchesne Counties, Utah. Report prepared for Balcron Oil Company, BLCR-95-8B, Archeological-Environmental Research Corporation, Bountiful.
- 1996c Cultural Resource Evaluation of Two Proposed Well Locations and Access Routes in the Wells Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-96-1, Archeological-Environmental Research Corporation, Bountiful.

1996d Cultural Resource Evaluation of Three Proposed Pipeline Corridor Complexes in the Castle Peak Draw - Pariette Bench Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-96-3, Archeological-Environmental Research Corporation, Bountiful.

Hauck, F. Richard and Glade Hadden

1993a Cultural Resource Evaluation of Seven Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-4, Archaeological-Environmental Research Corporation, Bountiful.

1993b Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-5, Archaeological-Environmental Research Corporation, Bountiful.

1993c Cultural Resource Evaluation of Eight Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-9, Archaeological-Environmental Research Corporation, Bountiful.

1993d Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-10, Archaeological-Environmental Research Corporation, Bountiful.

1993e Cultural Resource Evaluation of Seven Proposed Wells in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-11, Archaeological-Environmental Research Corporation, Bountiful.

1994a Cultural Resource Evaluation of Eight Proposed Wells in the Pleasant Valley Locality of Uintah County, Utah. Report prepared for Balcron Oil Company, BLCR-94-3 Archaeological-Environmental Research Corporation, Bountiful.

1994b Cultural Resource Evaluation of Proposed Water Injection Line Lateral Segments in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-94-4, Archaeological-Environmental Research Corporation, Bountiful.

- 1994c Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Pariette Draw - Castle Peak Draw - Eight Mile Flat Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-94-9, Archaeological-Environmental Research Corporation, Bountiful.
- 1994d Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Castle Peak Draw and Eight Mile Flat Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-94-10, Archaeological-Environmental Research Corporation, Bountiful.
- 1994e Cultural Resource Evaluation of Two Proposed Balcron Monument State Well Locations and Access Routes in the Castle Peak Draw Locality of Uintah County, Utah. Report prepared for Balcron Oil Company, BLCR-94-10b, Archaeological-Environmental Research Corporation, Bountiful.
- 1994f Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-94-11, Archaeological-Environmental Research Corporation, Bountiful.
- 1995a Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-95-1 & 2, Archaeological-Environmental Research Corporation, Bountiful.
- 1995b Cultural Resource Evaluation of a Series of Proposed Water Return Pipeline Routes in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-95-7, Archaeological-Environmental Research Corporation, Bountiful.

Hauck, F.R. and G. Norman

- 1980 Final Report on the Mapco River Bend Cultural Mitigation Study. AERC Paper No. 18, of the Archeological-Environmental Research Corporation, Bountiful.

Hauck, F.R. and Dennis Weder

- 1989 Pariette Overlook -- A Paleo-Indian Quarry Site in the Pariette Draw Locality of Uintah County, Utah. AERC Paper No. 42, of the Archaeological-Environmental Research Corporation, Bountiful.

Stokes, W.L.

- 1977 Physiographic Subdivisions of Utah. Map 43, Utah Geological and Mineral Survey, Salt Lake City.

Report Acceptable Yes ___ No ___

Mitigation Acceptable Yes ___ No ___
Comments: _____

Summary Report of
Inspection for Cultural Resources

WELL LOCATIONS IN THE WELLS DRAW,
CASTLE PEAK DRAW, PLEASANT VALLEY, &
PARIETTE BENCH LOCALITY IN DUCHESNE CO.

1. Report Title Equitable Resources Energy Company

2. Development Company _____

3. Report Date 0 5 10 1 9 9 6 UT-96-54937
A E R C

4. Antiquities Permit No. _____
BLCR - 96 - 2 Duchesne

5. Responsible Institution County _____

6. Fieldwork

Location: TWN .0.8.S. . RNG .1.7.E. . Section.22
TWN .0.9.S. . RNG .1.6.E. . Section 06, 17, 18, 20, 22,
TWN .0.9.S. . RNG .1.7.E. . Section 05, 11

7. Resource Area .SM.

8. Description of Examination Procedures: The archeologist Glade Hadden and assistant James Merrell intensively examined the proposed well locations and associated access & access corridors by walking 10 to 15 meter-wide transects in the ten acre parcels and within the 100 foot-wide corridors on either side of the flagged center-line.

9. Linear Miles Surveyed . 2.07 10. Inventory Type I
and/or Definable Acres Surveyed R = Reconnaissance
and/or Legally Undefinable Acres Surveyed . 1.34.7 I = Intensive
S = Statistical Sample

11. Description of Findings: No archaeological sites were identified and recorded during this survey. 12. Number Sites Found .0. (No sites = 0)
13. Collection: .N.
(Y = Yes, N = No)

14. Actual/Potential National Register Properties Affected: The National Register of Historic Places (NRHP) has been consulted and no registered properties will be affected by the proposed development.

15. Literature Search, Location/ Date: Utah SHPO 5-6-96 Vernal BLM 4-24-96

16. Conclusion/ Recommendations:

AERC recommends that a cultural resource clearance be granted to Equitable Resources Energy Company for these proposed developments based on the following stipulations: (see reverse)

1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the flagged areas, well pads and corridors examined as referenced in this report, and to the existing roadways and/or evaluated access routes.

2. A l l p e r s o n n e l s h o u l d ^{refrain from} ~~be~~ disturbing any significant cultural resources in the area.

3. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.

17. Signature of Administrator & Field Supervisor

Administrator:



Field
Supervisor:

EQUITABLE RESOURCES CO.

BALCRON OIL

MONUMENT FEDERAL #12-11-9-17Y

SW/NW SECTION 11, T9S, R17E, SLB&M

Duchesne County, Utah

PALEONTOLOGY REPORT

WELLPAD LOCATION AND ACCESS ROAD

BY

ALDEN H. HAMBLIN
PALEONTOLOGIST
235 EAST MAIN
VERNAL, UTAH 84078

MAY 8, 1996

RESULTS OF PALEONTOLOGY SURVEY AT EQUITABLE RESOURCES CO. MONUMENT FEDERAL #12-11-9-17Y, SW/NW Section 11, T9S, R17E, S.L.B.&M, Duchesne Co., Utah.

Description of Geology and Topography-

This well location is 10 miles south and 4 miles east of Myton, Utah. The wellpad sits between Pariette Bench road on the south and a gully on the north. Location slopes north and the surface is covered with angular rock fragments of rusty brown limestone. Layers of mudstone, sandstone, and limestone occur on the north side of the gully.

All rock outcrops in the area are of the Upper Eocene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains and plant impressions.

Paleontological material found -

There is turtle shell eroding out in several places in the layers of mudstone north of the gully (and wellpad), but these will not be effected by wellpad construction.

Recommendations-

There is always some potential for encountering significant fossils when working in the Uinta Formation. If important looking fossil material is found during construction, a paleontologist should be called to evaluate it.

No other recommendations are being made for paleontology at this location.


Allen H. Hamblin
Paleontologist

Date May 9, 1996

United States
Department of the Interior
Bureau of Land Management

Paleontological Locality Form

1. Permit #/Permittee: BLM - UT-S-95-004 ALDEN H. HAMBLIN
2. Repository/Acn.#: UTAH FIELD HOUSE OF NATURAL HISTORY
3. Locality #: 42DC249V [] Plant [X] Vertebrate [] Invertebrate [] Other
4. Formation (and subdivision, if known): Uinta Formation, lower Member
5. Age: Late Eocene
6. County: Duchesne
7. BLM District: VERNAL
8. Resource Area: Diamond Mt.
9. Map name: Pariette Draw SW, Utah
10. Map source: U.S.G.S. 7 1/2 min. Quad.
11. Map scale: 1:24,000
12. Map edition: 1964
13. Latitude (deg., min., sec., direction): _____
14. Longitude (deg., min., sec., direction): _____
or: UTM Grid Zone: (A) 12 T 587031 mE 4433358 mN
15. Survey (Section, Township & Range): SW,NW,SW,NW, Sec. 11, T9S, R17E, SLBM
16. Taxa observed/collected: There is turtle shell eroding out in several places in the layers of mudstone north of the gully (and wellpad), but these will not be effected by wellpad construction.
17. Discoverer(s)/Collector(s): Alden H. Hamblin
18. Date(s): April 30, 1996
19. Remarks: This fossil site was found during the paleontology survey of Equatable Resources Balcron Federal #12-11-9-17Y.



EQUITABLE RESOURCES CO.

MONUMENT FEDERAL #12-11-9-17Y
 SEC. 11, T9S, R17E, S.L.B.&M.
 TOPO "B"



SCALE: 1" = 2000'

Tri State
 Land Surveying, Inc.
 (801) 781-2501
 38 WEST 100 NORTH VERNAL, UTAH 84078



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

July 16, 1996

Equitable Resources Energy Co.
1601 Lewis Avenue
Billings, Montana 59102

Re: Monument Federal 12-11-9-17Y Well, 1996' FNL, 673' FWL,
SW NW, Sec. 11, T. 9 S., R. 17 E., Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-31679.

Sincerely,

A handwritten signature in black ink, appearing to read 'R. J. Firth'.

R. J. Firth
Associate Director

lwp

Enclosures

cc: Duchesne County Assessor
Bureau of Land Management, Vernal District Office



Operator: Equitable Resources Energy
Well Name & Number: Monument Federal 12-11-9-17Y
API Number: 43-013-31679
Lease: U-65210
Location: SW NW Sec. 11 T. 9 S. R. 17 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5336.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews at (801)538-5334 or Mike Hebertson at (801)538-5333.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

5. LEASE DESIGNATION AND SERIAL NO.
U-65210

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
n/a

7. UNIT AGREEMENT NAME
n/a

8. FARM OR LEASE NAME

Monument Federal

9. WELL NO.
#12-11-9-17Y

10. FIELD AND POOL, OR WILDCAT

Monument Butte/Green River

11. SEC., T., R., M., OR B.L.K.
AND SURVEY OR AREA

11, T9S, R17E

12. COUNTY OR PARISH | 13. STATE

Duchesne | UTAH

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
DRILL DEEPEN PLUG BACK

b. TYPE OF WELL
OIL WELL GAS WELL OTHER
SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
Equitable Resources Energy Company

3. ADDRESS OF OPERATOR
1601 Lewis Avenue; Billings, MT 59102

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
At surface
SW NW Section 11, T9S, R17E
At proposed prod. zone

RECEIVED
MAY 19 1996
1996 FNL 873' FMA
DIV. OF OIL, GAS & MINING

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
From Myton, UT approximately 10 Mi SW

16. DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drig. unit line, if any)

18. NO. OF ACRES IN LEASE
1240

17. NO. OF ACRES ASSIGNED
TO THIS WELL
40 acres.

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

19. PROPOSED DEPTH
5600'

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5,077' GL

22. APPROX. DATE WORK WILL START*
June 1, 1996

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
See attached Drilling Program/Casing Design				REC JUN 26 1996

Operator intends to drill this well in accordance with the attached EXHIBITS. A listing of EXHIBITS is also attached.

SELF CERTIFICATION: I hereby certify that I am authorized, by proper lease interest owner, to conduct these operations associated with the application. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Equitable Resources Energy Company as principal and Safeco Insurance Company of America as surety under BLM Bond No. MT 0576 (Nationwide Oil & Gas Bond #5547188) who will be responsible for compliance with all of the terms and conditions of that portion of the lease associated with this application.

ORIGINAL: Bureau of Land Management (Vernal, UT)
COPY; Utah Division of Oil, Gas and Mining (Salt Lake City, UT)

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Bobbie Schuman TITLE Regulatory and Environmental Specialist DATE April 17, 1996
Bobbie Schuman

(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____
Assistant Field Manager
APPROVED BY [Signature] TITLE Mineral Resources DATE JUL 18 1996
CONDITIONS OF APPROVAL, IF ANY:

TERMS OF APPROVAL/CONDITIONS OF APPROVAL ATTACHED

UT 080-6M-156

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Equitable Resources Energy Company

Well Name & Number: Equitable Monument Federal 12-11-9-17Y

API Number: 43-013-31679

Lease Number: U - 65210

Location: SWSW Sec. 11 T. 9S R. 17E

NOTIFICATION REQUIREMENTS

- | | | |
|---------------------------------|---|---|
| Location Construction | - | at least forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion | - | prior to moving on the drilling rig. |
| Spud Notice | - | at least twenty-four (24) hours prior to spudding the well. |
| Casing String and Cementing | - | at least twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and Related Equipment Tests | - | at least twenty-four (24) hours prior to initiating pressure tests. |
| First Production Notice | - | within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days. |

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted on initial meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal Field Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2. Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Ed Forsman (801) 789-7077
Petroleum Engineer

Wayne P. Bankert (801) 789-4170
Petroleum Engineer

Jerry Kenczka (801) 789-1190
Petroleum Engineer

BLM FAX Machine (801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL**

Other Additional Information:

The operator will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered lands it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or hazardous chemicals.

MOUNTAIN PLOVERS

No surface disturbing activities, construction, or drilling operations including the initial completion activities are to occur on the well, access road, or location from March 15 through August 15. This restriction is to protect the nesting Mountain Plovers located in the surrounding area. The restriction does not apply to maintenance and operation of existing wells and facilities. Waivers, exceptions, or modifications to this restriction may be specifically approved in writing by the authorized officer of the Bureau of Land Management if either the resource values change or the lessee/operator demonstrates that adverse impacts can be mitigated.

An example of an exception: could be to contact the authorized officer of the BLM to coordinate additional surveys for mountain plover & burrowing owl. The notification will be required a minimum of 14 days prior to surface disturbance to allow time to conduct a wildlife survey. If an active nest or chicks are found, the proposed activity will be delayed until the chicks are out of downy plumage or the brood vacates the area.

The following additional conditions apply:

Since the location is also in or near potential raptor habitat,
A high quality muffler shall be used on the engine powering the well. This will limit the noise originating at the well site.

OPERATOR CHANGE WORKSHEET

Attach all documentation received by the division regarding this change.
Initial each listed item when completed. Write N/A if item is not applicable.

Routing	
1-MEC	6-VEC
2-GLH	7-KAS
3-DTS	8-SI
4-VLD	9-FILE
5-JRB	

- Change of Operator (well sold) Designation of Agent
 Designation of Operator Operator Name Change Only

The operator of the well(s) listed below has changed, effective: 9-30-97

TO: (new operator)	<u>INLAND PRODUCTION COMPANY</u>	FROM: (old operator)	<u>EQUITABLE RESOURCES COMPANY</u>
(address)	<u>PO BOX 1446</u>	(address)	<u>PO BOX 577</u>
	<u>ROOSEVELT UT 84066</u>		<u>LAUREL MT 59044</u>
			<u>C/O CRAZY MTN O&G</u>
Phone:	<u>(801)722-5103</u>	Phone:	<u>(406)628-4164</u>
Account no.	<u>N5160</u>	Account no.	<u>N9890</u>

WELL(S) attach additional page if needed:

Name: **SEE ATTACHED**	API: <u>43-013-311671</u>	Entity: _____	S _____	T _____	R _____	Lease: _____
Name: _____	API: _____	Entity: _____	S _____	T _____	R _____	Lease: _____
Name: _____	API: _____	Entity: _____	S _____	T _____	R _____	Lease: _____
Name: _____	API: _____	Entity: _____	S _____	T _____	R _____	Lease: _____
Name: _____	API: _____	Entity: _____	S _____	T _____	R _____	Lease: _____
Name: _____	API: _____	Entity: _____	S _____	T _____	R _____	Lease: _____
Name: _____	API: _____	Entity: _____	S _____	T _____	R _____	Lease: _____

OPERATOR CHANGE DOCUMENTATION

- Jec 1. (r649-8-10) Sundry or other legal documentation has been received from the FORMER operator (attach to this form). *(Rec'd 12-10-97)*
- Jec 2. (r649-8-10) Sundry or other legal documentation has been received from the NEW operator (Attach to this form). *(Rec'd 10-20-97)*
- N/A 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is the company registered with the state? (yes/no) ____ If yes, show company file number: _____
- Jec 4. FOR INDIAN AND FEDERAL WELLS ONLY. The BLM has been contacted regarding this change. Make note of BLM status in comments section of this form. BLM approval of Federal and Indian well operator changes should ordinarily take place prior to the division's approval, and before the completion of steps 5 through 9 below.
- Jec 5. Changes have been entered in the Oil and Gas Information System (3270) for each well listed above. *(12-2-97)*
- Jec 6. Cardex file has been updated for each well listed above. *(12-3-97)*
- Jec 7. Well file labels have been updated for each well listed above. *(12-3-97)*
- Jec 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to Trust Lands, Sovereign Lands, UGS, Tax Commission, etc. *(12-3-97)*
- Jec 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- J
ec 1. (r649-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no If entity assignments were changed, attach copies of Form 6, Entity Action Form.
- N/A 2. Trust Lands, Sovereign Lands, Tax Commission, etc., have been notified through normal procedures of entity changes.

BOND VERIFICATION - (FEE WELLS ONLY)

- N/A
ec 1. (r649-3-1) The NEW operator of any fee lease well listed above has furnished a proper bond.
- 2. A copy of this form has been placed in the new and former operator's bond files.
- 3. The FORMER operator has requested a release of liability from their bond (yes/no) , as of today's date . If yes, division response was made to this request by letter dated .

LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY

- N/A
DT3 1. Copies of documents have been sent on to at Trust Lands for changes involving State leases, in order to remind that agency of their responsibility to review for proper bonding.
- N/A
12/5/97 2. (r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by letter dated 19 , of their responsibility to notify all interest owners of this change.

FILMING

- VB 1. All attachments to this form have been microfilmed. Today's date: 8.17.98.

FILING

- 1. Copies of all attachments to this form have been filed in each well file.
- 2. The original of this form, and the original attachments are now being filed in the Operator Change file.

COMMENTS

971202 Blm/Vernal Aprv. Nov. 10, 13 & 20, 1997.




Crazy Mountain Oil & Gas Services
P.O. Box 577
Laurel, MT 59044
(406) 628-4164
(406) 628-4165

TO: Lisha
St of Utah.

FROM: Molly Conrad
Crazy Mountain Oil & Gas Services
(406) 628-4164

Pages Attached - Including Cover Sheet 2.

NOTE: Here is the letter you requested.
Call if you need anything
further.



**EQUITABLE RESOURCES
ENERGY COMPANY**
WESTERN REGION

(406) 259-7860 Telephone
(406) 245-1361 Fax

December 10, 1997

Lisha
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

Dear Lisha:

RE: Equitable Sale of Utah Properties

Effective September 30, 1997, Equitable Resources Energy Company sold all of its Utah properties to Inland Production Company.

Please feel free to contact me if you require additional information.

Sincerely,

Molly Conrad
Agent for Equitable Resources
Energy Company

/mc

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

Equitable Resources Energy Company

3. Address and Telephone No.

1601 Lewis Avenue, Billings, MT 59102 (406) 259-7860'

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SW NW Section 11, T9S, R17E
1996' FNL & 673' FWL

5. Lease Designation and Serial No.

U-65210

6. If Indian, Allottee or Tribe Name

n/a

7. If Unit or CA, Agreement Designation

n/a

8. Well Name and No.

Monument Fed. #12-119-17X

9. API Well No.

43-013-31679

10. Field and Pool, or Exploratory Area

M. Butte/Green River

11. County or Parish, State

Duchesne County, UT

CONFIDENTIAL

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other <u>APD Extension</u>
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)


13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Operator requests that this APD be extended for a period of one year.

CONFIDENTIAL

Orig: Bureau of Land Management, Vernal District Office

Copy: State of Utah, Division of Oil, Gas, & Mining



14. I hereby certify that the foregoing is true and correct

Signed Molly Leonard

Title Agent for Equitable Resources Energy Company

Date 7-18-97

(This space for Federal or State office use)

Approved by _____

Title _____

Date _____

Conditions of approval, if any:

original approval date: 7/16/96 Approval extended to: 7/16/98

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.

U-65210

6. If Indian, Allottee or Tribe Name

n/a

7. If Unit or CA, Agreement Designation

n/a

8. Well Name and No.

Monument Fed. #12-119-17Y

9. API Well No.

43-013-31079

10. Field and Pool, or Exploratory Area

M. Butte/Green River

11. County or Parish, State

Duchesne County, UT

SUBMIT IN TRIPLICATE

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

Equitable Resources Energy Company

3. Address and Telephone No.

1601 Lewis Avenue, Billings, MT 59102 (406) 259-7860

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SW NW Section 11, T9S, R17E
1996' FNL & 673' FWL

CONFIDENTIAL

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other <u>APD Extension</u>
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Operator requests that this APD be extended for a period of one year.

7/18/97

Orig: Bureau of Land Management, Vernal District Office
Copy: State of Utah, Division of Oil, Gas, & Mining

VERNAL DIST.
ENG. <u>WAP 8/12/97</u>
GEOL. _____
E.S. _____
PWT. _____
A.M. _____

RECEIVED
JUL 30 1997

RECEIVED
SEP 15 1997
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed Molly Leonard Title Agent for Equitable Resources Energy Company Date 7-18-97

(This space for Federal or State office use)
Approved [Signature] Title Assistant Field Manager Mineral Resources Date AUG 14 1997
Conditions of approval, if any:

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

DOG M
07-87-6004

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well RECEIVED
 Oil Well Gas Well Other

2. Name of Operator OCT 13 1997
 Inland Production Company

3. Address and Telephone No.
 475 - 17th Street, Suite 1500, Denver, CO 80202 (303) 292-0900

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
 See Attached Exhibit

5. Lease Designation and Serial No.
See Attached

6. If Indian, Allottee or Tribe Name
See Attached

7. If Unit or CA, Agreement Designation
See Attached

8. Well Name and No.
See Attached

9. API Well No.
See Attached

10. Field and Pool, or Exploratory Area
See Attached

11. County or Parish, State
See Attached

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other <u>Change of Operator</u>
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Effective September 30, 1997, Inland Production Company will take over operations of the wells on the attached list. The previous operator was:
 Equitable Resources Energy Company
 1601 Lewis Avenue
 Billings, MT 59102

Effective September 30, 1997, Inland Production Company is responsible under the terms and conditions of the leases for operations conducted on the leased lands or a portion thereof under BLM Bond No. UT0056 issued by The Hartford Insurance Group.

RECEIVED
OCT 10 1997

14. I hereby certify that the foregoing is true and correct

Signed

Chris A. Potter

CHRIS A. POTTER, ATTORNEY-IN-FACT

Title

Date

9/30/97

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

RECEIVED
OCT 10 1997



October 7, 1997

Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078



RE: Change of Operator
Duchesne & Vernal Counties, Utah

Dear Mr. Forsman:

Please find attached Sundry Notices and Reports on Wells for Change of Operator, previously operated by Equitable Resources Energy Company for approval.


If you should have questions regarding this matter, please do not hesitate to contact me at the number listed below.

Sincerely,

INLAND PRODUCTION COMPANY

Patsy Barreau
Patsy Barreau

/pb
encs.



Revised 9/17/97		09/30/97		EREC APD LIST (APPROVED and PENDING)					ST = State						UNIT OR WELL	
WELL NAME	FIELD	QTR/QTR	SEC	TWP	RANGE	COUNTY	ST	APD STATUS	ZONE	FED. OR STATE LEASE NO.	API NUMBER	FOOTAGES	BLM OFFICE	FILE NO.		
Monument Federal #11-10-9-17Y	Monument Butte	NW NW	10	9S	17E	Duchesne	UT	PND	Green River	U-65210	4301331534	409' FNL, 475' FWL	Vernal			
Monument Federal #11-17-9-16Y	Monument Butte	NW NW	17	9S	17E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31779	575' FNL, 640' FWL	Vernal			
Monument Federal #12-7-9-16Y	Monument Butte	SW NW	7	9S	16E	Duchesne	UT	APRVD	Green River	UT-74390	43-013-31777	1980' FNL, 660' FWL	Vernal			
Monument Federal #12-11-9-17Y	Monument Butte	SW NW	11	9S	17E	Duchesne	UT	APRVD	Green River	U-65210	43-013-31679	1996' FNL, 673' FWL	Vernal			
Monument Federal #14-22-8-17	Monument Butte	SW SW	22	8S	17E	Duchesne	UT	APRVD	Green River	U-67845	43-013-31643	532' FSL, 495' FWL	Vernal			
Monument Federal #14-25-8-17	Monument Butte	SW SW	25	8S	17E	Uintah	UT	APRVD	Green River	UTU-74870	43-047-32765	660' FSL, 660' FWL	Vernal		Humpback	
Monument Federal #21-6-9-16Y	Monument Butte	NE NW	6	9S	16E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31816	663' FNL, 1728' FWL	Vernal			
Monument Federal #21-18-9-16Y	Monument Butte	NE NW	18	9S	16E	Duchesne	UT	PND	Green River	UTU-74390	4301331817	859' FNL, 1660' FWL	Vernal			
Monument Federal #21-22-9-16Y	Monument Butte	NE NW	22	9S	16E	Duchesne	UT	APRVD	Green River	UTU-64379	43-013-31727	911' FNL, 2030' FWL	Vernal			
Monument Federal #22-6-9-16Y	Monument Butte	SE NW	6	9S	16E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31719	2011' FNL, 1869' FWL	Vernal			
Monument Federal #22-7-9-16Y	Monument Butte	SE NW	7	9S	16E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31776	2036' FNL, 2070' FWL	Vernal			
Monument Federal #23-6-9-16Y	Monument Butte	NE SW	6	9S	16E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31812	1938' FSL, 1756' FWL	Vernal			
Monument Federal #23-31-8-16Y	Monument Butte	NE SW	31	8S	16E	Duchesne	UT	APRVD	Green River	UTU-74389	43-013-31810	1980' FSL, 1826' FWL	Vernal			
Monument Federal #24-6-9-16Y	Monument Butte	SE SW	6	9S	16E	Duchesne	UT	PND	Green River	UTU-74390	4301331811	717' FSL, 2118' FWL	Vernal			
Monument Federal #24-7-9-16Y	Monument Butte	SE SW	7	9S	16E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31775	517' FSL, 1952' FWL	Vernal			
Monument Federal #24-31-8-16Y	Monument Butte	SE SW	31	8S	16E	Duchesne	UT	APRVD	Green River	U-49950	43-013-31780	682' FSL, 1832' FWL	Vernal			
Monument Federal #31-10-9-17Y	Monument Butte	NW NE	10	9S	17E	Duchesne	UT	PND	Green River	U-65210	4301331591	660' FNL, 1980' FEL	Vernal			
Monument Federal #32-5-9-17	Monument Butte	SW NE	5	9S	17E	Duchesne	UT	PND	Green River	UTU-74808	4301331818	1833' FNL, 1913' FEL	Vernal			
Monument Federal #32-7-9-16Y	Monument Butte	SW NE	7	9S	16E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31778	2048' FNL, 1769' FEL	Vernal			
Monument Federal #32-18-9-16Y	Monument Butte	SW NE	18	9S	16E	Duchesne	UT	PND	Green River	UTU-74390	4301331805	1996' FNL, 1910' FEL	Vernal			
Monument Federal #32-20-9-18Y	8 Mile Flat	SW NE	20	9S	18E	Uintah	UT	APRVD	Green River	U-64917	43-047-32725	1980' FNL, 1980' FEL	Vernal			
Monument Federal #33-5-9-17	Monument Butte	NW SE	5	9S	17E	Duchesne	UT	PND	Green River	UTU-74808	4301331819	1754' FSL, 2031' FEL	Vernal			
Monument Federal #33-7-9-16Y	Monument Butte	NW SE	7	9S	16E	Duchesne	UT	APRVD	Green River	UTU-74390	43-013-31773	2131' FSL, 1910' FEL	Vernal			
Monument Federal #33-31-8-16Y	Monument Butte	NE SE	31	8S	16E	Duchesne	UT	APRVD	Green River	UTU-74389	43-013-31772	1957' FSL, 1810' FEL	Vernal			
Monument Federal #34-6-9-16Y	Monument Butte	SW SE	34	9S	16E	Duchesne	UT	PND	Green River	UTU-74390	4301331774	660' FSL, 1980' FEL	Vernal			
Monument Federal #34-7-9-16Y	Monument Butte	SW SE	7	9S	16E	Duchesne	UT	PND	Green River	UTU-74390	4301331803	701' FSL, 2075' FEL	Vernal			
Monument Federal #34-31-8-18Y	Monument Butte	SWSE	34	8S	18E	Uintah	UT	PND	Green River	UTU-74404	4304732845	636' FSL, 2160' FEL	Vernal			
Monument Federal #41-22-8-17	Monument Butte	NE NE	22	8S	17E	Duchesne	UT	APRVD	Green River	UTU-76240	43-013-31827	703' FNL, 759' FEL	Vernal (Private stc)			
Monument Federal #41-25-8-17	Monument Butte	NE NE	25	8S	17E	Uintah	UT	APRVD	Green River	U-67845	43-047-32766	800' FNL, 860' FEL	Vernal		Humpback	
Monument Federal #41-35-9-18Y	Monument Butte	NE NE	35	9S	18E	Uintah	UT	APRVD	Green River	U-68618	43-047-32727	500' FNL, 660' FEL	Vernal			
Monument Federal #42-22-8-17	Monument Butte	SE NE	22	8S	17E	Duchesne	UT	APRVD	Green River	UTU-76240	43-013-31826	1930' FNL, 803' FEL	Vernal (Private stc)			
Monument Federal #42-25-8-17	Monument Butte	NE NE	25	8S	17E	Uintah	UT	APRVD	Green River	U-67845	43-047-32767	1930' FNL, 803' FEL	Vernal			
Monument Federal #43-22-8-17	Monument Butte	NE SE	22	8S	17E	Duchesne	UT	APRVD	Green River	UTU-67845	43-013-31813	2174' FSL, 557' FEL	Vernal			
Monument Federal #43-31-8-16Y	Monument Butte	NE SE	31	8S	16E	Duchesne	UT	APRVD	Green River	UTU-74389	43-013-31815	1980' FSL, 660' FEL	Vernal			
Monument Federal #43-31-8-18Y	Monument Butte	NE SE	31	8S	18E	Uintah	UT	PND	Green River	UTU-74404	4304732844	1764' FSL, 623' FEL	Vernal			
Monument Federal #43-25-8-17	Monument Butte	NE SE	25	8S	17E	Uintah	UT	APRVD	Green River	U-67845	43-047-32768	1973' FSL, 719' FEL	Vernal			
Monument Federal #44-7-9-16Y	Monument Butte	SE SE	7	9S	16E	Duchesne	UT	PND	Green River	UTU-74390	4301331804	660' FSL, 660' FEL	Vernal		Beluga	
Monument Federal #44-31-8-18Y	Monument Butte	SE SE	31	8S	18E	Uintah	UT	PND	Green River	U-65969	4304732729	915' FSL, 759' FEL	Vernal			
Monument State #41-2-9-17CD	Monument Butte	NE NE	2	9S	17E	Uintah	UT	APRVD	Green River	State #ML-45555	43-047-32843	662' FNL, 660' FEL	Vernal		Castle Draw	
Monument State #42-2-9-17CD	Monument Butte	SE NE	2	9S	17E	Uintah	UT	APRVD	Green River	State #ML-45555	42-047-32842	1985' FNL, 660' FEL	Vernal		Castle Draw	



United States Department of the Interior


BUREAU OF LAND MANAGEMENT

Vernal District Office
170 South 500 East
Vernal, Utah 84078-2799

Phone: (801) 781-4400
Fax: (801) 781-4410

IN REPLY REFER TO:
3162.3
UT08438

November 13, 1997



Inland Production Company
475 17th Street, Suite 1500
Denver, CO 80202

43-013-31679
Re: Well No. Mon. Fed. 12-11-9-17Y
SWNW, Sec. 11, T9S, R17E
Lease U-65210
Uintah County, Utah

Dear Sir:

This correspondence is in regard to the self-certification statement submitted requesting a change in operator for the referenced well. After a review by this office, the change in operator request is approved. Effective immediately, Inland Production Company is responsible for all operations performed on the referenced well. All liability will now fall under your bond, BLM Bond No. UT0056, for all operations conducted on the referenced well on the leased land.

If you have any other questions concerning this matter, please contact Margie Herrmann or Pat Sutton of this office at (435) 781-4400.

Sincerely,

Howard B. Cleavinger II
Assistant Field Manager,
Minerals Resources

cc: Division of Oil, Gas & Mining
Equitable Resources Energy Company
ABO Petro Corp
Myco Industries Inc
Yates Drilling Co.
Yates Petro Corp



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Vernal Field Office

170 South 500 East

Vernal, Utah 84078-2799

<http://www.blm.gov/utah/vernal>

Phone: (435) 781-4400

Fax: (435) 781-4410

IN REPLY REFER TO:


3160

UT08300

Inland Production Company
Attn: Cheryl Cameron
P O Box 790233
Vernal UT 84079

July 21, 1998

DOBm
'LA'
DATE



Re: Notification of Expiration *43-013-31699*
Well No. Monument Fed. 12-11-9-17Y
SWNW, Section 11, T9S, R17E
Lease No. U-65210
Uintah County, Utah

Dear Cheryl:

The Application for Permit to Drill the above-referenced well was approved on July 18, 1996. Inland Production Company requested an extension of the original APD approval for an additional year. The request was reviewed and the extension approved until July 18, 1998. According to our records, no known activity has transpired at the approved location. In view of the foregoing, this office is notifying you the approval of the referenced application has expired. If you intend to drill at this location at a future date, a new Application for Permit to Drill must be submitted.

This office requires a letter confirming that no surface disturbance has been made for this drill site. Any surface disturbance associated with the approved location of this well is to be rehabilitated. A schedule for this rehabilitation must be submitted to this office. Your cooperation in this matter is appreciated.

Sincerely,

Margie Herrmann
Legal Instruments Examiner

cc: State Div. OG&M