


Petroglyph Operating Co., Inc.
P.O. Box 1839
Hutchinson, KS 67504-1839

June 5, 1997

Utah Division of Oil, Gas, & Mining
1594 West North Temple
Box 145801
Salt Lake City, UT 84114-5801



RE: APPLICATION FOR PERMIT TO DRILL
UTE TRIBAL #07-10
NW/SE SEC. 7, T5S, R3W
DUCHESNE COUNTY, UTAH
LEASE NO. BIA 14-20-H62-3506
UTE TRIBAL LANDS

Enclosed please find a copy of the Application for Permit to Drill and associated attachments for the referenced well.

Please address further communication regarding this matter (including approval) to:

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Phone # (801) 789-4120
Fax # (801) 789-1420

Sincerely,

A handwritten signature in cursive script, appearing to read "Ed Trotter".

Ed Trotter

Agent

Petroglyph Operating Co., Inc.

Attachments

/EHT/dmt

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
 DRILL DEEPEN

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 PETROGLYPH OPERATING COMPANY, INC.

3. ADDRESS AND TELEPHONE NO.
 P.O. BOX 607, ROOSEVELT, UTAH 84066

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)
 At surface 1786' FSL & 1687' FEL NW/SE
 At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 18.2 MILES SOUTHWEST OF MYTON, UTAH

10. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)
 1687'

16. NO. OF ACRES IN LEASE
 640

17. NO. OF ACRES ASSIGNED TO THIS WELL
 .80

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.
 5986'

19. PROPOSED DEPTH
 5986'

20. ROTARY OR CABLE TOOLS
 ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
 6010.9' GRADED GROUND

22. APPROX. DATE WORK WILL START*
 JUNE 1997

5. LEASE DESIGNATION AND SERIAL NO.
 14-20-H62-3506

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
 UTE INDIAN TRIBE

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME, WELL NO.
 UTE TRIBAL

9. API WELL NO.
 #07-10

10. FIELD AND POOL, OR WILDCAT
 ANTELOPE CREEK

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
 SEC. 7, T5S, R3W

12. COUNTY OR PARISH
 DUCHESNE

13. STATE
 UTAH

CONFIDENTIAL


PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4	8 5/8	24.0#	250'	135 sx class "G" + 2% CaCl ₂ + 1/4 #/sx celloflake.
7 7/8	5 1/2	15.5#	5986'	50/50 POZMIX + 2% GEL + 10% SALT TO 400' ABOVE ALL ZONES OF INTEREST (+ 10% EXCESS). LIGHT CEMENT (11 PPG+) + LCM TO 200' ABOVE OIL SHALE OR FRESH WATER INTERVALS (+ 5% EXCESS).

CONFIDENTIAL

PETROGLYPH OPERATING COMPANY, INC. WILL BE THE DESIGNATED OPERATOR OF THE SUBJECT WELL UNDER BOND #4556.

pc: Utah Division of Oil, Gas, and Mining
 Bureau of Indian Affairs, Fort Duchesne, Utah
 Ute Tribe, Fort Duchesne, Utah



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED [Signature] TITLE AGENT FOR PETROGLYPH DATE 6-10-97

(This space for Federal or State office use)

PERMIT NO. 43-013-31901 APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY [Signature] TITLE Petroleum Engineer DATE 7/2/97

*See Instructions On Reverse Side


T5S, R3W, U.S.B.&M.

PETROGLYPH OPERATING CO., INC.

Well Location, UTE TRIBAL #07-10, located is shown in the NW 1/4 SE 1/4 of Section 7, T5S, R3W, U.S.B.&M. Duchesne County, Utah.


R
4
W

S89°54'E - 79.82 (G.L.O.)



BASIS OF ELEVATION

BRASS CAP SET IN CONCRETE BY SUNRISE ENGINEERING LOCATED IN THE SE 1/4 OF SECTION 8, T5S, R3W, U.S.B.&M. SAID ELEVATION IS MARKED AS BEING 6191.3 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

NO. 161319
ROBERT L. KAY
REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(801) 789-1017

Corner Established by Bearing Tree Information. (Not Set on Ground)

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.
- △ = Section Corner Re-established by Bearing Tree Information. (Not Set on Ground)

SCALE 1" = 1000'	DATE SURVEYED: 05-27-97	DATE DRAWN: 05-31-97
PARTY D.A. K.H. C.B.T.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE PETROGLYPH OPERATING CO., INC.	

EIGHT POINT PLAN

UTE TRIBAL #07-10
NW/SE, SEC. 7, T5S R3W
DUCHESNE COUNTY, UTAH

1. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

FORMATIONS	DEPTH	SUBSEA
Mahogany Shale	2771	3261
"X" Marker	4382	1650
Douglas Creek	4521	1511
"B" Limestone	4912	1120
B/Castle Peak Limestone	5459	573
Basal Carbonate Limestone	5876	156
Total Depth	5986	46

Anticipated BHP 2000 psi

2. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS FORMATIONS:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>	<u>Subsea</u>
Oil/Gas	Douglas Creek	4521	1511
Oil/Gas	B/Castle Peak	5459	573
Other mineral zones	N/A		

3. PRESSURE CONTROL EQUIPMENT : BOP Schematic Diagram attached.

4. CASING PROGRAM :

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>MINIMUM SAFETY FACTOR</u>		
						<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
12 1/4	0' - 250'	250'	8 5/8	24.0 #	J-55	1370 PSI	2950 PSI	263,000#
7 7/8	0'-5986'	5986'	5 1/2	15.5 #	M-50	3650 PSI	4550 PSI	186,000#

All casing will be new or inspected.

EIGHT POINT PLAN

UTE TRIBAL #07-10
NW/SE, SEC. 7, T5S R3W
DUCHESNE COUNTY, UTAH

5. MUD PROGRAM

<u>INTERVAL</u>	<u>MUD TYPE</u>
0' - 250'	Air
250' - 4000'	Air/Mist & Aerated Water
4000' - TD	Air/3% KCL water or KCL substitute
TD	Gel/polyacrylamide polymer w/5-10% LCM

Sufficient mud inventory will be maintained on location during drilling to handle any adverse conditions that may arise.

6. VARIANCE REQUESTS:

- A. Petroglyph Operating Co., Inc. requests a variance to regulations requiring a straight run blooie line.
- B. Petroglyph Operating Co., Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line.

7. EVALUATION PROGRAM:

Logs: Mud Logging	T.D. to base of surface csg.
Compensated Density-Compensated Neutron Log	T.D. to base of surface csg.
Dual Laterolog - Micro-SFL	T.D. to base of surface csg.
Numar (Magnetic Resonance Imaging Log)	@ Geologists discretion

Cores: None Programmed
DST: None Programmed

Completion: To be submitted at a later date.

8. ABNORMAL CONDITIONS:

None anticipated.

EIGHT POINT PLAN

UTE TRIBAL #07-10
NW/SE, SEC. 7, T5S R3W
DUCHESNE COUNTY, UTAH

9. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

10. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

2000 PSIG DIAGRAM

BOTH RAMS ARE 2000 PSIG RATED.
CASING FLANGE IS 9" 2000 PSIG RATED.
BOPE 9" 2000 PSIG

TESTING PROCEDURE:

1. BOPE 's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind rams will be tested to rated working pressure, 2000 psig
3. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
4. All lines subject to well pressure will be pressure tested to the same pressure as blind & pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 2000 psig BOPE specifications.



CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Petroglyph Operating Co., Inc.
Well Name & Number: Ute Tribal #07-10
Lease Number: BIA 14-20-H62-3506
Location: 1786' FSL & 1687' FEL NW/SE, Sec. 7, T5S R3W
U.S.B.&M., Duchesne County, Utah
Surface Ownership: Ute Indian Tribe

NOTIFICATION REQUIREMENTS

- Location Construction - forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and related Equipment Tests - twenty-four (24) hours prior to running casing and tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice To Drill and Surface Use Program.

THIRTEEN POINT SURFACE USE PROGRAM

1. EXISTING ROADS

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing road.
- B. The proposed well site is located approximately 18.2 miles southwest of Myton, Utah - See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. PLANNED ACCESS ROAD

- A. The access road will be approximately 0.2 miles in length. See attached TOPO Map "B".
- B. The access road has a 30 foot ROW w/18 foot running surface.
- C. Maximum grade on access road will be 8%
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges or major cuts & fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards or fences will be required or encountered.

New or reconstructed roads will be centerlined - flagged at time of location staking.

All travel will be confined to existing access road Right-of-Way. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service Publication: Surface Operating Standards For Oil & Gas Exploration and Development, (1989).

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, drainage, graveling, crowning, and capping the

roadbed as necessary to provide a well-constructed safe road.

Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot Right-of- Way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, Petroglyph Operating Co., Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

3. LOCATION OF EXISTING WELLS WITHIN A ONE MILE RADIUS OF PROPOSED WELL LOCATION

- A. Water wells - 1*
- B. Abandoned wells - None
- C. Temporarily abandoned wells - None.
- D. Disposal wells - None.
- E. Drilling wells - None.
- F. Producing wells - 15*
- G. Shut in wells - 3*
- H. Injection wells - 1*

(*See attached TOPO map "C" for location)

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

A. ON WELL PAD

- 1. Tank batteries - None
- 2. Production facilities-To be submitted later
- 3. Oil gathering lines - None

4. Gas gathering lines-None
5. Injection lines - None
6. Disposal lines - None
7. Surface pits - None

B. OFF WELL PAD

1. Proposed location of attendant off pad flowlines shall be flagged prior to archaeological clearance.
2. A 4 1/2" OD steel above ground production pipeline will be laid approximately 200' from proposed location to a point in the NW/SE of Section 7, T5S, R3W, where it will tie into Petroglyph Operating Co., Inc.'s existing pipeline. Proposed pipeline crosses Ute Tribe lands, thus a Right-of-Way grant will be required. See attached TOPO Map D showing pipeline route.
3. Proposed pipeline will be a 4 1/2" OD steel, welded line laid on the surface.
4. Protective measures and devices for livestock and wildlife will be taken and/or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

The production facilities will be placed on the Northwest side of the location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities required will be painted within 6 months of installation. Facilities required to comply with O.S.H.A.

(Occupational Safety and Health Act) will be excluded.
The required paint color is Desert Brown.

5. LOCATION & TYPE OF WATER SUPPLY

- A. Water supply will be from Target Trucking's Roosevelt Brine Storage and/or Target's water source in SE 1/4, Sec. 1, T 4S, R 5W Duchesne County, Utah (State water right #43-10152). All water will come from a non-depletable source.
- B. Water will be hauled by Target Trucking.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIAL

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of location.
- B. All construction material will come from Ute Tribal Land.
- C. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at an approved waste disposal facility.
- 4. Produced waste water will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. During the 90 day period, an application for approval of a permanent disposal method and location, together with the required water analysis, will be submitted for the AO's approval.

5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on drilling rig to avoid leakage of oil to pit.

B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in reserve pit or be removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to reserve pit will be avoided by flaring them off in flare pit at time of recovery.

Burning of trash will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BIA administered land:

All reserve pits will be lined with either native clay, commercial bentonite or plastic sufficient to prevent seepage. (If a plastic nylon reinforced liner is used, it shall be torn and perforated after the pit dries and before backfilling of the reserve pit).

A 12 mill liner shall be installed in the reserve pit.

To protect the environment:

If the reserve pit is lined the operator will provide the BIA with a chemical analysis of the fluids in that pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements described by part II, Standards of Quality for Waters of the State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.

To protect the environment (without a chemical analysis) reserve pits will be constructed so as not to leak, break, or allow discharge of liquids.

Storage tanks will be used if drill sites are located on tribal

irrigable land, flood plains, or on lands under crop production. After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. ANCILLARY FACILITIES

- A. No airstrips or camps are planned for this well.

9. WELL SITE LAYOUT

- A. Refer to attached well site plat for related topography cuts and fills & cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation parking areas, and access road.

The reserve pit will be located on the Southeast side of the location. The flare pit will be located downwind of the prevailing wind direction on the Southeast side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence. The stockpiled topsoil will be stored on the Northwest end.

Access to the well pad will be from the South.

N/A Diversion ditch(es) shall be constructed on the _____ side of the location (above/below) the cut slope, draining to the _____

N/A Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____

N/A The drainage(s) shall be diverted around the sides of the well pad location.

N/A The reserve pit and/or pad locations shall be constructed long and narrow for topographic reasons _____

X Corners No. 2, 4, 6, & 8 will be rounded off to minimize excavation.

FENCING REQUIREMENTS

All pits will be fenced according to the following minimum standards:

- A. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16'.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BIA or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguards (shall/ shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BIA, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to

satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RESTORATION OF SURFACE

A. PRODUCING LOCATION

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 120 days from the date of well completion (weather permitting). Before any dirt work takes place, the reserve pit will be completely dry and all cans, barrels, pipe, fluid, and hydrocarbons, will be removed.

Contact appropriate surface management agency for required seed mixture.

B. DRY HOLE/ABANDONED LOCATION

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and BIA will attach the appropriate surface rehabilitation conditions of approval.

ON BIA Administered lands:

Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) reestablishing irrigation systems where applicable, (b) reestablishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and, (c) ensuring revegetation of the disturbed areas to the specifications of the Ute Indian Tribe or the BIA at the time of abandonment.

11. SURFACE OWNERSHIP

Access road: Ute Indian Tribe

Location: Ute Indian Tribe

12. OTHER INFORMATION

- A. Petroglyph Operating Co., Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the AO. Within five working days the AO will inform the operator as to:
- whether the materials appear eligible for the National Register of historic Places;

the mitigation measures the operator will likely have to undertake before the site can be used.

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, Petroglyph Operating Co., Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BIA,

or the appropriate County Extension Office. On BIA administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Tribal Lands after the conclusion of drilling operations or at any other time without BIA authorization. However, if BIA authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

On BIA administered land:

Operator's employees, including subcontractors, will not gather firewood along roads constructed by operators. If wood cutting is required, a permit will be obtained from the Forestry Department of the BIA pursuant to 25 CFR 169.13 "Assessed Damages Incident to Right-of-Way authorization". All operators, subcontractors, vendors, and their employees or agents may not disturb saleable timber (including firewood) without a duly granted wood permit from the BIA Forester.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved right-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

All roads constructed by operators on the Uintah and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) that the land is owned by the Ute Indian Tribe, (b) the name of the operator, (c) that firearms are prohibited to all non-Ute Tribal members (d) that permits must be obtained from the BIA before cutting firewood or other timber products, and (e) only authorized personnel permitted. All well site locations on the Uintah and Ouray Indian Reservation will have an appropriate sign indicating the name of the operator,

the lease serial number, the well name and number, the survey description of the well (either footage or the quarter-quarter section, the section, township, and range).

Additional Surface Stipulations

N/A No construction or drilling activities shall be conducted between

_____ and _____ because of _____

N/A No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.

N/A No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.

N/A There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).

N/A No cottonwood trees will be removed or damaged.

N/A Pond will be constructed according to BLM specifications approximately _____ ft. _____ of the location, as flagged on onsite.

LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION

PERMITTING

Ed Trotter
1620 West 750 North
Vernal UT 84078
Telephone # (801)789-4120
Fax # (801) 789-1420

OPERATIONS

Vince Guinn
P.O. Box 607
Roosevelt, UT 84066
(801) 722-2531
Fax # (801) 722-9145

All lease/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approval plan of operations, and any applicable Notice to Lessees. Petroglyph Operating Co., Inc. is fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

A copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The BIA Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in the Plan are to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Petroglyph Operating Co., Inc. and its contractors and sub-contractors in conformity with this Plan and the terms and conditions under which it is approved.

6-10-97


Date

Paul L. J. [Signature]

PETROGLYPH OPERATING CO., INC.

LOCATION LAYOUT FOR

UTE TRIBAL #07-10
SECTION 7, T5S, R3W, U.S.B.&M.
1786' FSL 1687' FEL



Proposed Access Road


SCALE: 1" = 50'
DATE: 5-31-97
Drawn By: C.B.T.

NOTE:

Flare Pit is to be located a min. of 100' from the Well Head.

FLARE PIT

Approx. Top of Cut Slope



NOTE:
Pit Capacity W/2' of Freeboard is ±4,600 Bbls.

Elev. Ungraded Ground at Location Stake = 6022.4'

Elev. Graded Ground at Location Stake = 6010.9'


UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (801) 789-1017

PETROGLYPH OPERATING CO., INC.


TYPICAL CROSS SECTIONS FOR

UTE TRIBAL #07-10
SECTION 7, T5S, R3W, U.S.B.&M.
1786' FSL 1687' FEL

DATE: 5-31-97
Drawn By: C.B.T.



1" = 20'
X-Section
Scale
1" = 50'




APPROXIMATE YARDAGES

(12") Topsoil Stripping	=	1,910 Cu. Yds.
Remaining Location	=	18,270 Cu. Yds.
TOTAL CUT	=	20,180 CU.YDS.
FILL	=	16,690 CU.YDS.
EXCESS MATERIAL AFTER 5% COMPACTION	=	2,610 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	2,610 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	0 Cu. Yds.

NOTE:
Topsoil should not be Stripped Below Finished Grade on Substructure Area.

UINTAH ENGINEERING & LAND SURVEYING
86 So. 200 East * Vernal, Utah 84078 * (801) 789-1017



LEGEND:

○ PROPOSED LOCATION



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (801) 789-1017 * FAX (801) 789-1018
 Email: uels@easilink.com




PETROGLYPH OPERATING CO., INC.

UTE TRIBAL #07-10
 SECTION 7, T5S, R3W, U.S.B.&M.
 1786' FSL 1687' FEL

TOPOGRAPHIC 5 31 97
MAP MONTH DAY YEAR
 SCALE: 1 : 100,000 | DRAWN BY: D.COX | REVISED: 00-00-00



T5S



**PROPOSED LOCATION:
UTE TRIBAL #07-10**

R
4
W
R
3
W

LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- ⬮ SHUT IN WELLS
- ⊗ WATER WELLS
- ⬮ ABANDONED WELLS
- ⬮ TEMPORARILY ABANDONED



PETROGLYPH OPERATING CO., INC.


**UTE TRIBAL #07-10
SECTION 7, T5S, R3W, U.S.B.&M.
1786' FSL 1687' FEL**



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(801) 789-1017 * FAX (801) 789-1018
Email: uels@easilink.com

TOPOGRAPHIC MAP
5 31 97
MONTH DAY YEAR
SCALE: 1" = 2000' DRAWN BY: D.COX REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 200' +/-

LEGEND:

-  EXISTING PIPELINE
-  PROPOSED PIPELINE
-  PROPOSED ACCESS



PETROGLYPH OPERATING CO., INC.

UTE TRIBAL #07-10
SECTION 7, T5S, R3W, U.S.B.&M.
1786' FSL 1687' FEL

U E L S
Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (801) 789-1017 * FAX (801) 789-1018
 Email: uels@easilink.com

TOPOGRAPHIC **5 31 97**
MAP MONTH DAY YEAR
 SCALE: 1" = 1000' DRAWN BY: D.COX REVISED: 00-00-00 **D**
 TOPO

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 06/20/97

API NO. ASSIGNED: 43-013-31901

WELL NAME: UTE TRIBAL 07-10
OPERATOR: PETROGLYPH OPERATING (N3800)

PROPOSED LOCATION:
NWSE 07 - T05S - R03W
SURFACE: 1786-FSL-1687-FEL
BOTTOM: 1786-FSL-1687-FEL
DUCHESNE COUNTY
ANTELOPE CREEK FIELD (060)

INSPECT LOCATION BY: / /		
TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: IND
LEASE NUMBER: 14-20-H62-3506

PROPOSED PRODUCING FORMATION: GRRV

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Federal State Fee
(Number 4556)
- Potash (Y/N)
- Oil shale (Y/N)
- Water permit
(Number 44 10152)
- RDCC Review (Y/N)
(Date: _____)

LOCATION AND SITING:

- R649-2-3. Unit: _____
- R649-3-2. General.
- R649-3-3. Exception.
- Drilling Unit.
Board Cause no: _____
Date: _____

COMMENTS: Exc. loc. ok


STIPULATIONS: _____

OPERATOR: PETROGLYPH OPERATING (N3800)

FIELD: ANTELOPE CREEK (060)

SEC, TWP, RNG: 7, T5S, R3W

COUNTY: DUCHESNE UAC: R649-3-2



PREPARED:
DATE: 23-JUNE-97

State of Utah
Division of Oil, Gas & Mining
1594 West North Temple
Box 145801
Salt Lake City, UT 84114-5801

July 1, 1997

RE: Application for Exception Well Location
Proposed Ute Tribal #07-10
Township 5 South, Range 3 West
Section 7: NW/4 SE/4
Duchesne County, Utah

Gentlemen;

Petroglyph Operating Company, Inc. (Petroglyph) respectfully requests administrative approval per R-649-3-3 to drill the Ute Tribal #07-10 a 5986' Green River test, at a location 1786' FSL & 1687' FEL, NW/4 SE/4, Section 7, Township 5 South Range 3 West, Duchesne County, Utah.

The aforementioned footage is not a location at which a well could be drilled in compliance with the spacing order of this lease, which established 40 acre drilling units.


Enclosed is a topographic map which depicts the surface contour in the area of the subject location. Petroglyph believes the proposed exceptionally spaced location to be the preferred location from a construction standpoint. Also this location is preferred by the Bureau of Indian Affairs Resource Department and the Ute Indian Tribe, Energy and Minerals Department who regulate activities on this land.

Petroglyph Operating Company Inc. holds 100% of the operating rights underlying the subject drilling unit as well as drilling units to the north, south, east and west.

Petroglyph respectfully requests the Division of Oil, Gas and Mining Administratively grant this application for the exceptional well location at its earliest opportunity.

Please direct further correspondence and approval to myself at P.O. Box 1910, Vernal, Utah 84078, or phone me at 801-789-4120.

Sincerely,



Petroglyph Operating Company Inc.
Ed Trotter, Agent


T5S, R3W, U.S.B.&M.

PETROGLYPH OPERATING CO., INC.


Well Location, UTE TRIBAL #07-10, located is shown in the NW 1/4 SE 1/4 of Section 7, T5S, R3W, U.S.B.&M. Duchesne County, Utah.

BASIS OF ELEVATION

BRASS CAP SET IN CONCRETE BY SUNRISE ENGINEERING LOCATED IN THE SE 1/4 OF SECTION 8, T5S, R3W, U.S.B.&M. SAID ELEVATION IS MARKED AS BEING 6191.3 FEET.




CERTIFICATE
THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.




UNTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (801) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 05-27-97	DATE DRAWN: 05-31-97
PARTY D.A. K.H. C.B.T.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE PETROGLYPH OPERATING CO. INC.	



- LEGEND:**
- └─┘ = 90° SYMBOL
 - = PROPOSED WELL HEAD.
 - ▲ = SECTION CORNERS LOCATED.
 - △ = Section Corner Re-established by Bearing Tree Information. (Not Set on Ground)
- Corner Established by Bearing Tree Information. (Not Set on Ground)



LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING ROAD
- DRILLING WELL LOCATION

PETROGLYPH OPERATING CO., INC.

UTE TRIBAL #07-10
SECTION 7, T5S, R3W, U.S.B.&M.
1786' FSL 1687' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (801) 789-1017 * FAX (801) 789-1018
 Email: uels@enslink.com



TOPOGRAPHIC **5** **31** **97**
MAP **MONTH** **DAY** **YEAR**
 SCALE: 1" = 2000' DRAWN BY: D.COX REVISED: 00-00-00





State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

July 2, 1997

Petroglyph Operating Company, Inc.
P.O. Box 607
Roosevelt, Utah 84066

Re: Ute Tribal 07-10 Well, 1786' FSL, 1687' FEL, NW SE, Sec. 7,
T. 5 S., R. 3 W., Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-31901.

Sincerely,

A handwritten signature in cursive script that reads "Lowell P. Braxton".

Lowell P. Braxton
Deputy Director

lwp

Enclosures

cc: Duchesne County Assessor
Bureau of Land Management, Vernal District Office

Operator: Petroglyph Operating Company, Inc.
Well Name & Number: Ute Tribal 07-10
API Number: 43-013-31901
Lease: 14-20-H62-3506
Location: NW SE Sec. 7 T. 5 S. R. 3 W.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5336.

Notify the Division prior to commencing operations to plug and abandon the well. Contact John R. Baza (801)538-5334 or Mike Hebertson at (801) 538-5333.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
 DRILL DEEPEN

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 PETROGLYPH OPERATING COMPANY, INC.

3. ADDRESS AND TELEPHONE NO.
 P.O. BOX 607, ROOSEVELT, UTAH 84066

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)
 At surface 1786' FSL & 1687' FEL NW/SE
 At proposed prod. zone

5. LEASE DESIGNATION AND SERIAL NO.
 14-20-H62-3506

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
 UTE INDIAN TRIBE

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME, WELL NO.
 UTE TRIBAL

9. AN WELL NO.
 #07-10

10. FIELD AND POOL, OR WILDCAT
 ANTELOPE CREEK

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
 SEC. 7, T5S, R3W

12. COUNTY OR PARISH 13. STATE
 DUCHESNE UTAH

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 18.2 MILES SOUTHWEST OF MYTON, UTAH

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)
 1687'

16. NO. OF ACRES IN LEASE
 640

17. NO. OF ACRES ASSIGNED TO THIS WELL
 .80

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.
 5986'

19. PROPOSED DEPTH
 5986'

20. ROTARY OR CABLE TOOLS
 ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
 6010.9' GRADED GROUND

22. APPROX. DATE WORK WILL START*
 JUNE 1997

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4	8 5/8	24.0#	250'	135 sx class "G" + 2% CaCl ₂ + 1/4 #/sx celloflake.
7 7/8	5 1/2	15.5#	5986'	

50/50 POZMIX + 2% GEL + 10% SALT TO 400' ABOVE ALL ZONES OF INTEREST (+ 10% EXCESS). LIGHT CEMENT (11 PPG+) + LCM TO 200' ABOVE OIL SHALE OR FRESH WATER INTERVALS (+ 5% EXCESS).

RECEIVED
 JUL 07 1997
 DIV. OF OIL, GAS & MINING

PETROGLYPH OPERATING COMPANY, INC. WILL BE THE DESIGNATED OPERATOR OF THE SUBJECT WELL UNDER BOND #4556.

pc: Utah Division of Oil, Gas, and Mining
 Bureau of Indian Affairs, Fort Duchesne, Utah
 Ute Tribe, Fort Duchesne, Utah

RECEIVED
 JUN 17 1997

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

SIGNED [Signature] TITLE AGENT FOR PETROGLYPH DATE 6-10-97

(This space for Federal or State office use)

PERMIT NO. **NOTICE OF APPROVAL** APPROVAL DATE _____ CONDITIONS OF APPROVAL ATTACHED TO OPERATOR'S COPY

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY [Signature] TITLE ACTING Assistant Field Manager Mineral Resources DATE JUN 30 1997

U-080-7m-288

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Petroglyph Operating Company

Well Name & Number: Ute Tribal 07-10

API Number: 43-013-31901

Lease Number: 14-20-H62-3506

Location: NWSE Sec. 07 T. 5S R. 3W

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative by the operator to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report **ALL** water shows and water-bearing sands to Tim Ingwell of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a **2M** system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

If conductor pipe is set it will be cemented to surface. If drive pipe is used it will be pulled prior to cementing surface casing.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected via the cementing program. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

The Gamma Ray and Induction Logs need to be pulled from TD to the Surface Shoe.

A cement bond log (CBL) will be run from the production casing shoe to **Top Of Cement** and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. One copy of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours **prior** to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.), and shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted following initial installation and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approval or notification is necessary, please contact one of the following individuals:

Wayne Bankert (801) 789-4170
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

Jerry Kenczka (801) 789-1190
Petroleum Engineer

BLM FAX Machine (801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

SURFACE CONDITIONS OF APPROVAL

The Surface Use Conditions of Approval all come from the Bureau of Indian Affairs Concurrence Memorandum and Site Specific Environmental Analysis.

The Ute Tribe Energy and Mineral Department is to be notified 48 hours prior to construction. A Tribal Technician is to monitor construction.

Fifty (75) foot wide Rights-Of-Way (ROWs) corridor shall be granted for the following:

Access roads which shall have constructed travel width limited to 30 feet, except as granted for sharp curves or intersections.

Surface pipelines shall be limited to 13 feet of the ROW. The pipeline will be constructed to lay on the soil surface, and the ROW for the pipeline will not be bladed or cleared of vegetation.

Where pipelines are constructed parallel to roads they may be welded on the road and then lifted from the road onto the ROW. Where pipelines cross country between stations, they shall be welded in place at wellsites or on roads and then pulled into place with suitable equipment. Traffic will be restricted along these areas so that the pipeline ROW will not be used as an access road.

Buried pipelines shall be buried a minimum of 3 feet below the soil surface within an area of disturbance limited to 15 feet wide, and construction will be monitored by a Tribal Technician.

Buried pipelines adjacent to access roads shall be buried within 1.5 feet from the outside edge of the barrow ditch. Any additional buried pipelines shall be parallel to the outer side of the first buried pipeline and shall be constructed as close to the first pipeline as safety requirements allow.

After construction of the buried pipeline is completed the disturbed area of the right-of-way shall be contoured to blend into the natural landscape and it shall be reseeded with desirable vegetation as recommended by the BIA. Between September 15 and November 1 of the year following pipeline construction all disturbed areas shall be reseeded with perennial vegetation according to BIA, or Ute Tribe specifications.

Petroglyph will assure the Ute Tribe that any/all contractors and subcontractors have acquired a Tribal Business License and have access permits prior to construction.

All vehicular traffic, personnel movement, construction, and restoration activities shall be confined to the areas examined, as referenced in report, and to the existing roadways and/or evaluated access routes.

All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.

The Ute Tribe Energy & Mineral Department shall be consulted if cultural remains from subsurface deposits are exposed or identified during construction.

Before the site is abandoned, the company will be required to restore the well site and ROWs to near their original state. The disturbed areas will be reseeded with desirable perennial vegetation.

Noxious weeds will be controlled on the well site and rights-of-way. If noxious weeds spread from the project area onto adjoining land, the company will also be responsible for their control.

Reserve pits will be lined with impervious synthetic liners. Prior to backfilling the reserve pit all fluids will be pumped from the pit into trucks and hauled to approved disposal sites. When the reserve pits are backfilled the cuttings and mud, etc. left in them to be buried will be buried a minimum of three feet below the surface of the soil.

A closed production system will be used. Production fluids will be contained in leak proof tanks. All production fluids will be disposed of at approved disposal sites. The indiscriminate dumping of production fluids on roads, wellsites or other areas will not be allowed.

Firewood shall be stockpiled at convenient locations near the wellsite and along the access road.

Upon completion of the project approved under this Application for Permit to Drill and Right-of-way, the Ute Tribe Energy & Minerals Resources Department will be notified by Petroglyph Operating Company so that a Tribal Technician can verify Affidavit of Completion's.



United States Department of the Interior
 BUREAU OF INDIAN AFFAIRS
 UINTAH AND OURAY AGENCY
 Fort Duchesne, Utah 84026
 (801) 722-2406 Ext.

RECEIVED
 JUN 26 1997

IN REPLY REFER TO:
 Minerals and Mining

MINERAL ACCESS AGREEMENT ON INDIAN OWNED LANDS

WELL PAD, ACCESS ROAD AND 75' WIDE PIPELINE CORRIDOR FOR Well No. UT #07-10

The purpose of this agreement is to regulate the surface development of Indian Lands which have been leased for oil and gas development. An approved agreement must be obtained prior to the commencement of any surface disturbing activity and will be in effect for the term of the lease and the agreed upon contractual provisions referenced therein, in not revoked under the terms in item 4 of this agreement.

1. The authorized officer for the Bureau of Indian Affairs, in conjunction with the Indian Surface owner and Tribe hereby grants permission to:
PETROGLYPH OPERATING CO., INC.
P.O. BOX 607
ROOSEVELT, UT 84066

To improve and/or construct and maintain a development corridor which may contain an access road, pipelines, powerlines, communication lines and well pads on the following trust land (reference lease number and legal description):

LEASE NO. 14-20-H62-3506 SE/4 SECTION 7, T5S, R3W, U.S.B. & M

2. In consideration of the approval of this agreement, the above company agrees to adhere to all lease provisions, A.P.D. stipulations and regulations of the Secretary of the Interior now or hereafter in force relative to such leases.
3. The Company herewith submits an estimated surface damage fee in the amount of 1 AS PER TERMS OF COOP. P.O.D. for _____ acres Pending Agency appraisal and the Affidavit of Completion.
4. This agreement will remain in effect unless revoked upon 30 days written notice by the Superintendent or the appropriate official, depending upon circumstances.
5. The permittee will submit a certified survey map of the proposed access road and/or well pad with this permit. The map must adhere to all specifications and requirements of the Branch of Minerals and Mining, Uintah and Ouray Agency, Bureau of Indian Affairs. Upon completion of construction, an Affidavit of Completion will be submitted by the company to certify that the construction completed was in accordance to the specifications certified to on the survey map accompanying this agreement.
6. The Company agrees to furnish a bond in the amount of \$ _____, or to utilize said company's existing Nationwide Oil and Gas Bond No. BO 4556 to guarantee performance of this permit.
7. The Company agrees to contact immediately the Bureau of Indian Affairs (BIA) and the Bureau of Land Management (BLM), if cultural resources discovered during construction or any time during the course of daily operations.

8. ADDITIONAL STIPULATIONS:

Signed on this 25th day of June, 1997.

WITNESS:

Stephanie Appel

[Signature]
 AUTHORIZED AGENT

PETROGLYPH OPERATING CO., INC.
 COMPANY NAME

P.O. BOX 607
 ADDRESS

ROOSEVELT, UT 84066
 CITY/STATE ZIP CODE

APPROVED:

[Signature]
 Superintendent

7/26/97

Date

[Signature]

memorandum

DATE:

6/26/97

REPLY TO
ATTN OF:

SUBJECT:

Superintendent, Uintah & Ouray Agency

TO: Concurrence Letter for PETROGLYPH OPERATING COMPANY
 Ute Tribal 07-09, NESE, SEC. 7 Ute Tribal 07-10, NWSE, Sec. 7
 Ute Tribal 07-11, NESW, SEC. 7 Ute Tribal 07-13, SWSW, Sec. 7
ALL IN TOWNSHIP 5 SOUTH RANGE 4 WEST, USB&M

RECEIVED

JUN 26 1997

Bureau of Land Management, Vernal District Office
ATTENTION: Minerals and Mining Division


We recommend approval of the Application for Permit to Drill on the subject well.

Based on available information received on JUNE 25, 1997, we cleared the proposed location in the following areas of environmental impact.

YES NO Listed threatened or endangered species
 YES NO Critical wildlife habitat
 YES NO Archaeological or cultural resources
 YES NO Air quality aspects (to be used only if
 project is in or adjacent to a Class I area

REMARKS: The Ute Tribe Energy & Minerals Department is recommending the following criteria to be adhered during all phases of construction activities.

1. The Ute Tribe Energy and Minerals Department is to be notified 48 hours prior to construction, as a Tribal Technician is to monitor construction.
2. A 75 foot corridor rights-of-way shall be granted with the following:
 - a. Buried pipelines shall be buried a minimum of 3 feet below soil surface.
 - b. Access roads shall be limited to 30 feet, except as granted for sharp turns
 - c. Surface pipelines shall be limited to 13 feet wide.
 - d. Buried pipelines shall be limited to 15 feet wide and construction will be monitored by Tribal Technician.
3. Pipelines adjacent to access roads shall be buried within 1.5 feet from the outside edge of the barrow ditch. Additional pipelines shall be parallel to each other, as safety requirements will allow.
4. Petroglyph Operating Corporation will assure the Ute Tribe that any/all contractors and any sub-contractors has acquired a Tribal Business License and have access permits prior to construction.
5. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the area examined, as referenced in report, and to the existing roadways and/or evaluated access routes.
6. All mitigative stipulations contained in the Bureau of Indian Affairs site specific Environmental Analysis (EA) will be strictly adhered.
7. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.



OPTIONAL FORM NO. 10
 GSA
 (REV. 1-94)
 5010-118

8. The personnel from the Ute Tribe Energy & Minerals Department should be consulted, should cultural remains from subsurface deposits be exposed or identified during construction work.

9. Upon completion of Application for Right-of-way, the Ute Tribe Energy and Minerals Department will be notified by Barrett Resources Corporation, so that a Tribal Technician can verify Affidavits of Completion's.

Attachments: Environmental Analysis- UT, . 07-09, 07-10, 07-11, 07-13

SITE SPECIFIC
ENVIRONMENTAL ANALYSIS

RECEIVED
JUN 26 1997

1.0 PROPOSED ACTION

Petroglyph Operating Co., Inc. is proposing to drill oil well #07-10, and construct pipelines, and an access road.

2.0 ALTERNATIVE ACTIONS

- A. ALTERNATIVE CONSIDERED: The proposed action is the preferred alternative.
- B. NO ACTION: Under the no action alternative the proposed action would not be implemented.
- C. OTHER: NA

3.0 PERMITTEE/LOCATION

- A. Permittee- Petroglyph Operating Co., Inc.
- B. Date 6-5-97
- C. Well number- 07-10
- D. Right-of-way- Access road R\W approx. 0.3 mile.
Pipeline R\W approx. 200 feet.
- E. Site location- NWSE, Section 7, T5S, R3W, USB&M.

4.0 SITE SPECIFIC SURVEY

A. SITE DESCRIPTION

- 1. Elevation (feet) 6022
- 2. Annual precipitation (inches)- 12-14
- 3. Topography- rolling hills
- 4. Soil- The soil texture is (0 to 6") gravelly loam with moderate permeability.

B. VEGETATION

- 1. Habitat type is upland pinion juniper.
- 2. Percent Ground Cover- estimated to be 40%.
- 3. Vegetation consists of approximately 10% grasses, 30% shrubs, 10% forbs, 36% trees. The main variety of grasses are squirrel tail, Indian ricegrass, poa, needle & thread, bluebunch wheat, galleta, and blue grama. Forbs are astragalus, mustard, lambs quarter, globemallow, buck wheat, flox, daisy, Indian paint brush, & annuals. Shrubs consist of black sagebrush, fring sage, bud sage, pigmy sage, prickly pear, winterfat, shadscale, snakeweed, mahogany, greasewood, rabbit brush. Trees, pinion pine, and Utah Juniper.

4. Observed Threatened & Endangered species: None.
5. Potential For Threatened & Endangered species: Slight
7. Observed Noxious Weeds: None

8. AFFECTED ENVIRONMENTAL

1. There are no surface damages as a result of the initial survey.

4.1 WILDLIFE

A. POTENTIAL SITE UTILIZATION

1. Big Game-The area is used throughout the year by mule deer, elk, and antelope. (elk & mule deer use this area most during winter months.)
2. Small Game-The area is used by cottontail rabbit.
3. Raptor- Various species of raptors use this area for habitat. Raptors which are observed using the area are Golden eagles, Redtail hawk, & Kestrel. Ferruginous hawk hunt in the area and there is an active nest located approximately 2.25 miles south east of this site in Section 20, T5S, R3W, USB&M.
5. Non-Game Wildlife- Animal species which have been observed using this area are black tail jack rabbit, coyote, fox, badger, and various species of reptiles, and song birds.
6. Threatened & Endangered Species: No T&E species are reported using the area of this project.

4.2 PRESENT SITE USE

A. USAGE

	<u>acres</u>
Rangeland	2.86
Irrigable land	0
Woodland	0
Non-Irrigable land	2.86
Commercial timber	0
Floodplain	0
Wetland	0
Riparian	0
Other:	0

4.3 CULTURAL RESOURCES

A. CULTURAL SURVEY

Cultural Resource Surveys were performed by James A. Truesdale, an Independent Archaeologist.

5.0 ENVIRONMENTAL IMPACTS

A. SURFACE ALTERATIONS

	<u>acres</u>
1. Access road	1.09
2. Well site	1.43
3. Pipeline right-of-way	0.34
4. Corridor right-of-way	0.00
5. Total area disturbed	2.86

B. VEGETATION/LANDSCAPE

1. Production loss (AUM's)/year: 0.19
2. Permanent scar on landscape: Yes x No
3. Potential impacts to Threatened & Endangered species:
Yes No X

C. SOIL/RANGE/WATERSHED

There will be an increase in soil erosion from wind and water. There will not be any possible point source of water pollution.

The area is presently used as rangeland. In recent years the area has been permitted for livestock grazing, but at the present time no permits have been issued for the area. This project will reduce livestock grazing by approximately 0.19 AUM/year.

The area is not used as irrigated cropland and a water right has not been designated for the area.

D. WILDLIFE/THREATENED & ENDANGERED SPECIES

There will be an insignificant reduction of wildlife habitat and grazing for livestock. There will also be an increase in wildlife disturbance and poaching resulting from the additional traffic and people using the area.

There are no known impacts to Threatened or Endangered species but is important habitat for the Ferruginous hawk. The area is important winter range for big game.

Ferruginous Hawks use this area for nesting and hunting. There is an nest in Section 20.

6.0 MITIGATION STIPULATIONS

A. VEGETATION/LANDSCAPE

1. Before the site is abandoned the company will be required to restore the well site and right-of-ways to near their original state. The disturbed area will be reseeded with desirable perennial vegetation.
2. Noxious weeds will be controlled on the well site and rights-of-way. If noxious weeds spread from the project area onto adjoining land, the company will also be responsible for their control.

B. SOILS/RANGE/WATERSHEDS

1. Soil erosion will be mitigated by reseeding all disturbed areas.

2. SURFACE PIPELINES

Surface pipelines will be constructed to lay on the soil surface, and the right-of-way will not be bladed or cleared of vegetation.

Where surface pipelines do not parallel roads but cross country between stations, they shall be welded in place at wellsites or on access roads and then pulled between stations with a suitable piece of equipment. Traffic will be restricted along these areas so that the pipeline right-of-way will not be used as an access road.

3. BURIED PIPELINES

Buried pipelines shall be buried a minimum of 3.0 feet below the soil surface. After construction of the pipeline is completed the disturbed area of the right-of-way shall be contoured to blend into the natural landscape, and it shall be reseeded with desirable vegetation.

Between September 15 and November 1 of the year following pipeline construction all disturbed areas shall be reseeded with perennial vegetation according to BIA, or Ute Tribe specifications.

4. CORRIDOR RIGHT-OF-WAY

A 75 foot wide corridor pipeline right-of-way will be used for, surface pipelines, buried pipelines.

5. ACCESS ROADS

Although the access road rights-of-way is 30 feet, the constructed travel width of the access road shall be limited to 22 feet, except it may be wider where sharp curves, or intersections are required.

6. DRILLING SYSTEM

An open drilling system will be used. Reserve pits will be lined with impervious synthetic liners. Prior to backfilling the reserve pit all fluids will be pumped from the pit into trucks and hauled to approved disposal sites. When the reserve pits are backfilled the surplus oil and mud, etc will be buried a minimum of 3.0 feet below the surface of the soil.

7. PRODUCTION SYSTEM

A closed production system will be used. Production fluids will be contained in leak proof tanks. All production fluids will be disposed of at approved disposal sites. The indiscriminate dumping of production fluids on roads, wellsites or other areas will not be allowed.

8. FIREWOOD

Firewood shall be stockpiled at convenient locations near the wellsite and along the access road.

C. WILDLIFE/VEGETATION/THREATENED & ENDANGERED SPECIES

Because the wellsite is located more than 1/2 mile from a Ferruginous hawk nest this wellsite may be constructed and drilled at any time throughout the year.

D. CULTURAL RESOURCES

Cultural resource surveys were performed by James A. Truesdale. The consultant recommends clearance of the project as it is presently staked.

E. UTE TRIBAL REGULATIONS

(1). Prior to commencing surveys or construction on the U&O Indian Reservation the operator, and any of its sub-contractors, shall acquire access permits and business permits from the Ute Indian Tribe.

(2). Prior to the commencement of construction, the operator shall notify the Ute Tribal Department of Energy and Minerals of the date construction shall begin.

7.0 UNAVOIDABLE ADVERSE IMPACTS

A. SURFACE ALTERATIONS

None of the adverse impacts listed in 5.0 above can be avoided in a practical manner except those which are mitigated in item 6.0 above and those specified in BLM's 13 point

surface use plan.

B. RELATIONSHIP BETWEEN SHORT-TERM USE OF THE ENVIRONMENT VS LONG TERM PRODUCTIVITY.

1. Short Term: (Estimated 20 years) A total loss of production on the land and the associated environmental impacts will continue to influence the surrounding area for the productive life of the well.
2. Long Term: Standard policies provide for rehabilitation of wellsite and rights-of-ways. After the land is rehabilitated, it is not expected to return to its original productive capability. Normally, there will be a permanent scar left on the landscape.

C. IRREVERSIBLE AND IRRETRIEVABLE COMMITMENT

Oil and Gas are non-renewable resources, once they have been removed they can never be replaced.

8.0 CUMULATIVE IMPACTS

A. FULL DEVELOPMENT

Each additional well drilled for development increases the soil erosion potential, reduces wildlife habitat and grazing, increases potential soil and geologic pollution resulting from salt loading, reduces the soil's potential to recover, and increases the potential of water pollution from produced waters and hydro-carbons. Therefore, strict conformance with the mitigation measures and recommendations in this document is emphasized to minimize the adverse environmental impacts.

9.0 NEPA COMPLIANCE

A. RESEARCH/DOCUMENTATION

Based on available information, 6-5-97, the proposed location in the following areas of environmental impacts has been cleared:

<u>X</u>	Yes	_____	No	Listed Threatened & Endangered species
<u>X</u>	Yes	_____	No	Critical wildlife habitat
<u>X</u>	Yes	_____	No	Historical and cultural resources

10.0 REMARKS

A. SURFACE PROTECTION/REHABILITATION

All essential surface protection and rehabilitation requirements are specified above.

11.0 RECOMMENDATIONS

A. APPROVAL/DISAPPROVAL

We recommend approval of the proposed action as outlined in item 1.0 above.

6-5-97

Date

Dale A. Hanberg
Representative - BIA Land
Operations, Uintah and Ouray
Agency

12.0 DECLARATION

A. APPROVAL

It has been determined that the proposed action is not a federal action significantly affecting the quality of the environment as it would require the preparation of an environmental impact statement in accordance with Section 102 (2) (c) of the National Environmental Policy Act of 1969 (42 USC 4331) (2) (C).

6/5/97

Date

Allen P. Lloyd
Acting Superintendent,
Uintah and Ouray Agency

14.0 CONSULTATION

A. REPRESENTATIVES/ORGANIZATION

Dale Hanberg- BIA
Ed Trotter-Petroglyphs
Lonnie Nephi-UTEM
Greg Darlington-BLM

B:\EAPet07.10

CONFIDENTIAL

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: PETROGLYPH OPERATING

Well Name: UTE TRIBAL 07-10

Api No. 43-013-31901

Section: 7 Township: 5S Range: 3W County: DUCHESNE

Drilling Contractor UNION

Rig # 16

SPUDDED:

Date 7/15/97

Time _____

How ROTARY

Drilling will commence _____

Reported by DEANNA


Telephone # _____

Date: 7/17/97 Signed: JLT

✓

October 15, 1997

Vicky Dyson
State of Utah
Division of Oil, Gas & Mining
1594 W. North Temple, Ste.1210
Salt Lake City, UT 84114



CONFIDENTIAL

Ms. Dyson:

Enclosed please find the logs listed below for the wells located in Duchesne County, Utah.

<u>Well Name</u>	<u>Log</u>
Ute Tribal 19-06	CNL & AIT
Ute Tribal 16-07	CNL & AIT
Ute Tribal 19-05	CNL & AIT
Ute Tribal 18-11	CNL & AIT
Ute Tribal 15-12	CNL & AIT
Ute Tribal 16-03	CNL & AIT
Ute Tribal 14-05	CNL & AIT
Ute Tribal 19-09	CNL & AIT
Ute Tribal 16-08	CNL & AIT
Ute Tribal 19-04	CNL & AIT
Ute Tribal 07-10	CNL & AIT
Ute Tribal 19-03	CNL & AIT
Ute Tribal 30-10	CNL & AIT
Ute Tribal 30-11	CNL & AIT

43 013 31901 T055 R03W 07

If you need further information, please do not hesitate to call me at 316-665-8500.

Sincerely,

Judy Gates
Petroleum Geology Technician

COMPLETION REPORT

CONFIDENTIAL

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Lease: Ute Tribal 07-10

KB 6021

API #: 43-013-31901

Property: 50183

Location: 7 - 5 S - 3 W

AFE/EPE Number:

County, St.: Duchesne UT

Activity Date Daily Cost Activity Description

9/12/97 \$20,850.00

Open well. SICP @ 0 psi. Spot in rods on trailer. Flush tbg w/35 bbls K water @ 180 degrees F. RIH w/pump & rods. Seat & space out pump. Fill tbg w/water & test to 500 psi. Long stroke pump w/good action. RD service rig & equipment. TWTR @ 1796 bbls. FINAL.

FLUID RECOVERY

ZONE BLF:	838
ZONE BLFR:	78
ZONE BLFTR:	760
ZONE % REC:	9.3%
WELL BLF:	2636
WELL BLFR:	840
WELL BLFTR:	1796
WELL % REC:	31.9%

9/11/97 \$4,500.00

Open well. SICP @ 0 psi. Finish RIH w/tbg & clean out to PBTD @ 6170'. POOH. RIH w/5 1/2" BVBP & set @ 2000'. Pressure up on csg to 1000 psi. RU HES & establish inj rate @ 2 bpm @ 750 psi. Down 5 1/2" X 7 7/8 OH. Cement granulate & 1% EX-1 @ 12.1 ppg & 220 ft 3/sx. Squeezed off @ 1000 psi. Shut in annulus @ surface. RD HES. Bleed off 5 1/2" csg & release BVBP. POOH w/BVBP. RIH w/BHA & 2 7/8" prod. tbg. ND BOP's & frac head. NU prod. head & set B2 tac w/+/- 10,000# tension. SWIFN.

FLUID RECOVERY

ZONE BLF:	838
ZONE BLFR:	220
ZONE BLFTR:	618
ZONE % REC:	26.3%
WELL BLF:	2636
WELL BLFR:	840
WELL BLFTR:	1796
WELL % REC:	31.9%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

9/10/97	\$2,050.00	
---------	------------	--

Open well. W/C62, B10 & B6 Zones open. SITP @ 0 psi. SICP @ 0 psi. RIH w/ret head & tag sand @ 5260'. Clean out to BVBP @ 5400'. POOH to 4820' & RU to swab. Made 17 runs. IFL @ surface. Had trace of oil on run #3 & increased to 50% on last run. FFL @ 2500'. TWR @ 142 bbls. TOR @ 26 bbls. RIH & circulate on BVBP. Release of POOH. RIH w/75 jnts 2 7/8" tbg for clean out run to PBD @ 6170'. SWIFN.

FLUID RECOVERY

ZONE BLF:	838
ZONE BLFR:	220
ZONE BLFTR:	618
ZONE % REC:	26.3%
WELL BLF:	2636
WELL BLFR:	840
WELL BLFTR:	1796
WELL % REC:	31.9%

9/9/97	\$2,150.00	
--------	------------	--

Open well. SICP @ 0 psi. SITP @ 0 psi. RIH & tag sand @ 4040'. Cleanout to RBP @ 4100'. Release RBP & POOH. RIH w/rethead & tag sand @ 4100'. Cleanout to RBP @ 4120'. Release & POOH. RIH w/rethead & tag sand @ 4199'. Cleanout to RBP @ 4400'. Release RBP & POOH. REH w/rethead for BVBP & 20 jnts 2 7/8" tbg & SWIFN. NOTE: Displaced +/- 30 bbls w/tbg.

FLUID RECOVERY

ZONE BLF:	838
ZONE BLFR:	78
ZONE BLFTR:	760
ZONE % REC:	9.3%
WELL BLF:	2636
WELL BLFR:	698
WELL BLFTR:	1938
WELL % REC:	26.5%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

9/8/97	\$44,641.00	PERFORATIONS:
		6178-6183 Green River H (01) 4 SPF 20 shots
		6147-6153 Green River H (03) 4 SPF 24 shots
		5728-5734 Green River E (05) 4 SPF 24 shots
		5250-5256 Green River D (7.21) 4 SPF 24 shots
		5080-5094 Green River D (07) 4 SPF 56 shots
		4705-4709 Green River C (06.2) 4 SPF 16 shots
		4299-4305 Green River B (10) 4 SPF 24 shots
		4275-4278 Green River B (10) 4 SPF 12 shots
		4052-4058 Green River B (06) 4 SPF 24 shots
		4032-4040 Green River B (06) 4 SPF 32 shots

Open well W/C6.2 zone brkdw. SCIP @ 0 psi. RU HES & Frac C6.2 zone. ISIP @ 1964 psi. RU Schlumberger & RIH w/RBP & perfguns. Set RBP @ 4450' & test to 3000 psi. Perforate B10 zone. Breakdown w/Kwater @ 3000 psi. RU HES & Frac B10 zone. ISIP @ 2952 psi. Lubricate in well w/RBP & perfguns. Set RBP @ 4120'. RBP would not test. Set 2nd RBP @ 4100' & test to 3000 psi. Perforate B6 zone. RU HES & frac B6 zone. ISIP @ 2062 psi. Flow well to tank @ 5 min, shut in @ +/- 60 BPH to 0 psi. Flowed 48 bbls in 50 min to 0 psi. RIH w/rethead & 150 jnts & circ well clean & SWIFN.

STIMULATION TREATMENT:

C6.2

FLUID:

Fluid Task	Fluid Type	Amount	Unit
frac fluid	Boragel 30	5802	gal

PROPPANT:

Type	Total Lbs:	Ramp Range
20/40 sand	29500	1-10

PRESSURE/RATE:

Maximum:	2387 psi	21.4 BPM
Average:	2150 psi	20.4 BPM

SI PRESSURE:

	TP	CP
5 Min:		1856
10 Min:		1812
15 Min:		1760

STIMULATION TREATMENT:

B10

FLUID:

Fluid Task	Fluid Type	Amount	Unit
frac fluid	Boragel 30	10189	gal

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date Daily Cost Activity Description

PROPPANT:	Type	Total Lbs:	Ramp Range
	20/40 sand	63200	1-10

PRESSURE/RATE:			
Maximum:	3230 psi		36 BPM
Average:	2450 psi		33.5 BPM

SI PRESSURE:		TP	CP
	5 Min:		2650
	10 Min:		2458
	15 Min:		2295

STIMULATION TREATMENT:			B6
------------------------	--	--	----

FLUID:			
Fluid Task	Fluid Type	Amount	Unit
frac fluid	Boragel 30	6415	gal

PROPPANT:	Type	Total Lbs:	Ramp Range
	20/40 sand	41200	1-10

PRESSURE/RATE:			
Maximum:	2220 psi		26.4 BPM
Average:	2000 psi		25.7 BPM

SI PRESSURE:		TP	CP
	5 Min:		1786

FLUID RECOVERY

ZONE BLF:			838
ZONE BLFR:			48
ZONE BLFTR:			790
ZONE % REC:			5.7%
WELL BLF:			2636
WELL BLFR:			668
WELL BLFTR:			1968
WELL % REC:			25.3%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

9/5/97	\$3,250.00	PERFORATIONS: 6178-6183 Green River H (01) 4 SPF 20 shots 6147-6153 Green River H (03) 4 SPF 24 shots 5728-5734 Green River E (05) 4 SPF 24 shots 5250-5256 Green River D (7.21) 4 SPF 24 shots 5080-5094 Green River D (07) 4 SPF 56 shots 4705-4709 Green River C (06.2) 4 SPF 16 shots
--------	------------	---

Open well - W/D7 zone. Fraced & flowed to pit 4-0 0 psi yesterday. This a.m. SCIP @ 25 psi & SITP @ 25 psi. RU & swab well. Made 5 runs. IFL @ surface. Trace of oil on run #1 & increased to 100% on final run. TWR @ 80 bbls. TOR @ 17 bbls. FFL @ 400'. Well flowed for 1 hr after run #5 & recovered 10 bbls 100% oil. RIH w/2 jnt & clean out to BVBP. Release & POOH to 4800' & reset. Test to 4000 psi. POOH to 4720' & spot 6 bbls 15% HCL @ C6.2 interval & POOH. RU Schlumberger & perforate C6.2 zone. RD wireline. Brkdwn C6.2 perfs @ 1100 psi & pump HCL asay w/Kwater @ 4 BPM @ 800 psi. Overdisplace w/15 bbls Kwater. SWIFN.

STIMULATION TREATMENT:

C6.2

FLUID:

Fluid Task	Fluid Type	Amount	Unit
acid	15% HCL	6	bbls

FLUID RECOVERY

ZONE BLF:	480
ZONE BLFR:	112
ZONE BLFTR:	368
ZONE % REC:	23.3%
WELL BLF:	1798
WELL BLFR:	620
WELL BLFTR:	1178
WELL % REC:	34.5%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

9/4/97	\$23,887.00	
--------	-------------	--

Open well - W/D7.0 zone. Perforated & brkdw last p.m. This a.m. SICO @ psi. RU HES & frac D7.0 zone. ISIP @ 2814 psi. Flow next to trnk @ 5 min @ +/- 60 BPH to 0 psi. Flowed +/- 71 bbls. RIH w/rethead & tag sand @ 5090'. Cleanout to BVBP @ 5150' POOH & w/EOT @ 5090. RU to swab well. Had good oil & gas show while circulating. SWIFN.

STIMULATION TREATMENT:

D7

FLUID:

Fluid Task	Fluid Type	Amount	Unit
frac fluid	Boragel 30	15578	gal

PROPPANT:

Type	Total Lbs:	Ramp Range
20/40 sand	77700	1-10

PRESSURE/RATE:

Maximum:	3460 psi	32 BPM
Average:	2250 psi	31.4 BPM

SI PRESSURE:

	TP	CP
5 Min:		2166

FLUID RECOVERY

ZONE BLF:	480
ZONE BLFR:	91
ZONE BLFTR:	389
ZONE % REC:	19.0%
WELL BLF:	1798
WELL BLFR:	549
WELL BLFTR:	1249
WELL % REC:	30.5%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

9/3/97	\$3,481.00	PERFORATIONS: 6178-6183 Green River H (01) 4 SPF 20 shots 6147-6153 Green River H (03) 4 SPF 24 shots 5728-5734 Green River E (05) 4 SPF 24 shots 5250-5256 Green River D (7.21) 4 SPF 24 shots 5080-5094 Green River D (07) 4 SPF 56 shots
--------	------------	---

Open well w/D72.1 zone. Swabbed to 1% oil and 2600' last p.m. This a.m. SICP @ 300 psi. SITP @ 250 psi. Flowed to tank for 1/2 hr & recovered 13 bbls. RU & swab well. Made 6 runs. IFL @ 800'. Run #1 90% oil then went down to 5% on run #5 & increased to 85% on run #6. FFL @ 2600'. TWR @ 60 bbls, TOR @ 35 bbls. RD swab & RIH w/4 jnts 2 7/8" tbg. Release BVBP & POOH to 5150' & spot 6 bbls 15% HCL @ D7. Interval & POOH w/rethead. RU Schlumberger & perforate D7 zone. RU Schlumberger. Brkdwn perms @ 1800 psi. Pump HCL away @ 4 bpm @ 1200 psi. Overdisplace w/15 bbls Kwater.

FLUID:

STIMULATION TREATMENT:

Fluid Task	Fluid Type	D7 Amount	Unit
acid	15% HCL	6	bbls

FLUID RECOVERY

ZONE BLF:	345
ZONE BLFR:	223
ZONE BLFTR:	122
ZONE % REC:	64.6%
WELL BLF:	1318
WELL BLFR:	454
WELL BLFTR:	864
WELL % REC:	34.4%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.
Well: Ute Tribal 07-10
County, St.: Duchesne UT

Elevation: GL 6011
 KB 6021

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

9/2/97	\$23,038.00	PERFORATIONS:
		6178-6183 Green River H (01) 4 SPF 20 shots
		6147-6153 Green River H (03) 4 SPF 24 shots
		5728-5734 Green River E (05) 4 SPF 24 shots
		5250-5256 Green River D (7.21) 4 SPF 24 shots
		WELLBORE:
		6194 RTD
		6081 LTD
		6170 PBTD
		6188 CSA

Open well. SICP @ 0 psi. SITP @ 0 psi. Spot 6 bbl 15% HCL @ D72.1. Interval & POOH w/tbg. R.U. Schlumberger & perforate D72.1 zone. RU HES & breakdown @ ± 3400 psi. Inj rate @ 15 bpm @ 4000 psi. Pump step down test and redesign fracture treatment. Pump sand slug due to step down test shown near wellbore restriction & cont. (Frac see detail report) Flow well to tank @ 5 min at 60 BPH. Flowed ± 30 bbls to 0 psi. RIH w/rethead cleaning out frac fluid & sand to packed sand @ 5160'. Clean out to BOBP @ 5400' & POOH w 4 jnts. RU to swab well. made 8 runs. IFL @ surface MOC @ 1%. TWR @ 133 bbls. FFL @ 2600'. SWIFN.

STIMULATION TREATMENT:

D7.21

FLUID:

Fluid Task	Fluid Type	Amount	Unit
frac fluid	Boragel 30	9213	gal

PROPPANT:

Type	Total Lbs:	Ramp Range
20/40 sand	45000	
sand (unspecified)	6100	6

PRESSURE/RATE:

Maximum:	4665 psi	18 BPM
Average:	4450 psi	13 BPM

SI PRESSURE:

	TP	CP
5 Min:		3685

FLUID RECOVERY

ZONE BLF:	345
ZONE BLFR:	163
ZONE BLFTR:	182

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

ZONE % REC:	47.2%
WELL BLF:	1318
WELL BLFR:	394
WELL BLFTR:	924
WELL % REC:	29.9%

STIMULATION TREATMENT:

D7.21

FLUID:

Fluid Task	Fluid Type	Amount	Unit
prepad fluid	15% HCL	6	bbls

8/29/97 \$2,050.00

Open well. W/ zone open & H3 & H1 isolate w/plugs. SITP @ 0 ps. SICP @ 0 psi. RIH w/4 jnt & tag sand @ 5300'. Clean out to RBP @ 5850. Release RBP & POOH. RIH w/rethead for BVBP & tag sand @ 6050'. Clean out to BOBP @ 6115'. Release BVBP & RIH to tag @ 6165'. Set BVBP & POOH to 6018' w/EOT. RU & swab well. Made 7 runs. IFL @ surface. Trace of oil on run #1 and increased to 35% on final run. FEL @ 1800'. TWR @ 140 bbls. RIH to BOBP @ 6115'. Circ. clean & release. POOH to 5398' & set BOBP. Test to 4000 psi. POOH to 5270' & prep to spot HCL on Tuesday 9/2/97. SWIF long weekend.

FLUID RECOVERY

ZONE BLF:	973
ZONE BLFR:	231
ZONE BLFTR:	742
ZONE % REC:	23.7%
WELL BLF:	973
WELL BLFR:	231
WELL BLFTR:	742
WELL % REC:	23.7%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

8/28/97	\$32,676.00	PERFORATIONS: 6147-6153 Green River H (03) 4 SPF 24 shots 6078-6083 Green River H (01) 4 SPF 20 shots 5728-5734 Green River E (05) 4 SPF 24 shots 5250-5256 Green River D (07.21) 4 SPF 24 shots 5080-5094 Green River D (07) 4 SPF 56 shots 4705-4709 Green River C (06.2) 4 SPF 16 shots 4299-4305 Green River B (10) 4 SPF 24 shots 4275-4278 Green River B (10) 4 SPF 12 shots 4052-4058 Green River B (06) 4 SPF 24 shots 4032-4040 Green River B (06) 4 SPF 32 shots
---------	-------------	--

WELLBORE:

6194	RTD
6081	LTD
6143	PBTD
6188	CSA

Open well. W/RBP set above H3 zone. SICP @ 0 psi. W/EOT @ 6100'. Spot 6 bbls 15% HCL @ HI zone & POOH w/rethead. RU Schlumberger. R.U. HES & attempt to brkdw. No break. R.U. Schlumberger & spot HCL w/dump bailer. Brkdw @ 3000 psi. R.U. HES. ISIP @ 4028 psi. R.U. Schlumberger & lubricate W well w/RBP & perfgun. Set RBP @ 5850' & test to 3000 psi. Gun did not shoot. POOH & repair gun. RIH & perforate E5 zone. Brkdw perfs @ 2400 psi. RU HES & frac E5 zone. Well screened out w/ +/- 3500 gal left in flush, +/- 30,000# in formation, & 12,300# in csg. No ISIP due to screenout. Flow E5 zone to T2Wk @ +/- 60 bph. Flowed +/- 2 min & recovered +/- 2 bbls. RIH w/rethead & 100 jnts tbg. Circulate clean. RIH w/58 jnts & circulate out sand. RIH w/2 jnts & tag sand @ 5300'. POOH w/4 jnts. SWIFN.

STIMULATION TREATMENT:

H01

FLUID:

Fluid Task	Fluid Type	Amount	Unit
frac fluid	Boragel 30	6834	gal

PROPPANT:

Type	Total Lbs:	Ramp Range
20/40 sand	28700	1-10

SI PRESSURE:

	TP	CP
5 Min:		2845
10 Min:		2615
15 Min:		2474

STIMULATION TREATMENT:

E05

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

FLUID:

Fluid Task	Fluid Type	Amount	Unit
frac fluid	Boragel 30	5600	gal

PROPPANT:	Type	Total Lbs:	Ramp Range
	20/40 sand	42300	1-10

PRESSURE/RATE:

Maximum:	4470 psi		28.4 BPM
Average:	2900 psi		25.9 BPM

8/27/97 \$4,043.00

Open well. W/H3 zone frac'ed & shut in yestrday due to fishin hole. SICP @ 2000 psi. Bleed well to tank at +/- 1/46 pm to 0 psi. Flowed 5 1/2 hours for TWR @ 74 bbls. PU 4 1/8" overshot w/2 5/16 grapple. Bumper sub of J2rs. REH on 197 jnts. 2 7/8" Tbj of tag fish at 6125' circ. onto fish of POOH w/all of fish. Lay down fishing tools. PU BVBP of RIH to 6115'. Set BVBP of test to 4500 psi. Lay down 1 jnt and prep to spot HCL in A.M. @ 6100'. SWIFN.

FLUID:

FLUID RECOVERY

ZONE BLF:	462
ZONE BLFR:	89
ZONE BLFTR:	373
ZONE % REC:	19.3%
WELL BLF:	462
WELL BLFR:	89
WELL BLFTR:	373
WELL % REC:	19.3%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

8/26/97	\$19,310.00	PERFORATIONS:
		6147-6153 Green River H (03) 4 SPF 24 shots
		WELLBORE:
		6194 RTD
		6081 LTD
		6143 PBTD
		6188 CSA

Open well. SICP @ 0 psi w/ EOT @ 6165'. POOH w/ 4 3/4" bit and scraper. RU Schlumberger and perforate H3 zone. RU HES and breakdown H3 perms @ 3000 psi. Frac H3 zone with a fracture gradient of .88. Lubricate into well w/ RBP and Perfgun after equalizing psi to lubricator and starting in well. Line parted dropping RBP and gun in well. RIH to 3000' w/weight. Did not tag. RU Schlumberger and Halliburton. SWIFN to prevent sand returns into casing.

STIMULATION TREATMENT:	H 03		
FLUID:			
Fluid Task	Fluid Type	Amount	Unit
frac fluid	Borgel 30	7317	gal
PROPPANT:	Type	Total Lbs:	Ramp Range
	20/40 sand	41900	1-10

PRESSURE/RATE:	
Maximum:	3420 psi 21.36 BPM
Average:	2750 psi 20.5 BPM

SI PRESSURE:	TP	CP
	ISIP:	2692
	5 Min:	2450
	10 Min:	2415
	15 Min:	2369

FLUID RECOVERY	
ZONE BLF:	462
ZONE BLFR:	0
ZONE BLFTR:	462
ZONE % REC:	.%
WELL BLF:	0
WELL % REC:	.%

COMPLETION REPORT

10/9/97

Petroglyph Operating Co., Inc.

Operator: Petroglyph Operating Company, Inc.

Elevation: GL 6011

Well: Ute Tribal 07-10

KB 6021

County, St.: Duchesne UT

Activity Date	Daily Cost	Activity Description
---------------	------------	----------------------

STIMULATION TREATMENT:

STIMULATION TREATMENT:

H03

FLUID:

Fluid Task	Fluid Type	Amount	Unit
------------	------------	--------	------

acid	15% HCL	6	bbls
------	---------	---	------

FLUID RECOVERY

ZONE BLF:	462
-----------	-----

ZONE BLFR:	0
------------	---

ZONE BLFTR:	462
-------------	-----

ZONE % REC:	%
-------------	---

WELL BLF:	462
-----------	-----

8/25/97	\$3,830.00	WELLBORE:
---------	------------	-----------

6194	RTD
------	-----

6081	LTD
------	-----

6143	PBTD
------	------

6188	CSA
------	-----

MIRU. DUCO Well Service Rig. NU Frac head and BOP's. PU taley and RIH w/ 4 3/4" bit and 2 7/8" tubing. Tag cement @ 6143. RU swivel and drive out plug. Float collar and cement to 6170' (27'). Circulate well. Clean and test casing to 4500 psi. Pull up 5' from TD and prep to spot HCL in A.M. SWIFN.

Cumulative Cost: \$189,756.00

Days Since Start: 19

FORM 7

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

REPORT OF WATER ENCOUNTERED DURING DRILLING

1. Well name and number: LITE TRIBAL 07-10
 API number: 43-013-31901
2. Well Location: QQ MUSE Section 07 Township 5S Range 3W County Duchesne
3. Well operator: PETROGLYPH Operating Company, Inc.
 Address: P.O. Box 607
Roosevelt, UT 84066 Phone: 801-722-2531
4. Drilling contractor: Union Drilling
 Address: P.O. Drawer 40
Buckhannon WV 26201 Phone: 304-472-4610
5. Water encountered (attach additional pages as needed):

DEPTH		VOLUME (FLOW RATE OR HEAD)	QUALITY (FRESH OR SALTY)
FROM	TO		
0	307 465	DRY DAMP 465	NO Flow w/out sp Pump
465	1146	1 GAL PER MIN 1146	FRESH

6. Formation tops: _____

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I hereby certify that this report is true and complete to the best of my knowledge. Date: 7-25-97
 Name & Signature: L. Jeanne K. Bell Title: Operations Coordinator

SUBMIT IN DUPLICATE
(See other instructions on
reverse side)

Form approved.
Budget Bureau No. 1004-0137
(Expires August 31, 1985)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

5. LEASE DESIGNATION AND SERIAL NO.
14-20-H62-3506

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Ute Indian Tribe

7. UNIT AGREEMENT NAME
14-20-H62-4650

8. FARM OR LEASE NAME

9. WELL NO.
Ute Tribal 07-10

10. FIELD AND POOL, OR WILDCAT
Antelope Creek

11. SEC., T., R., M., OR BLOCK AND
SURVEY OR AREA
NWSE Sec. 7-T5S-R3W

12. County or Parish
Duchesne

13. State
Utah

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1.a. TYPE OF WELL: Oil Well Gas Well Dry Other

b. TYPE OF COMPLETION: New Well Workover Deepen Plug Back Diff. Reserv. Other

2. NAME OF OPERATOR
Petroglyph Operating Company, Inc.

3. ADDRESS OF OPERATOR
P.O. Box 607, Roosevelt, UT 84066 (801) 722-2531

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface 1786' FSL 1687' FEL

At top prod. interval reported below

At total depth 6194' RTD

CONFIDENTIAL
PERIOD
EXPIRED
ON 10-12-98

CONFIDENTIAL

14. PERMIT NO.
43-013-31901

DATE ISSUED
7/2/97

15. DATE SPUDDED 7/15/97

16. DATE T.D. REACHED 7/23/97

17. DATE COMPLETED (Ready to prod.)
9/12/97

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*
6011' GL

19. ELEV. CASINGHEAD
6011

20. TOTAL DEPTH, MD & TVD
6194' RTD

21. PLUG BACK T.D., MD & TVD
6170'

22. IF MULTIPLE COMPL., HOW MANY*
8

23. INTERVALS
DRILLED BY

ROTARY TOOLS

CABLE TOOLS

24. PRODUCING INTERVAL(S) OF THIS COMPLETION -- TOP, BOTTOM, NAME (MD AND TVD)*

Green River

26. TYPE ELECTRIC AND OTHER LOGS RUN
CNL, AIT 10-21-97

25. WAS DIRECTIONAL SURVEY MADE

27. WAS WELL CORED

CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8-5/8"	24#	263'	12-1/4"	163 sxs Type 5	
5-1/2"	15-5#	6188'	7-7/8"	225 sxs Highfill	
				390 sxs Thixotropic	

LINER RECORD

TUBING RECORD

SIZE	TOP	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8"	5930'	

31. PERFORATION RECORD (Interval, size and number)

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

H3 6147-53' (24 holes)	B10 4299-4305' (24 holes)
H1 6078-83' (20 holes)	B10 4275-78' (12 holes)
E5 5728-34' (24 holes)	B6 4052-58' (24 holes)
D72.1 5250-56' (24 holes)	B6 4032-40' (32 holes)
D7 5080-94' (56 holes)	
C6.2 4705-09' (16 holes)	

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
6147-53'	7317 Boragel, 41900# 20/40 prop
6078-83'	6834 gal Boragel, 28700# 20/40 prop
5728-34'	5600 gal Boragel, 30000# 20/40 prop
5250-56'	9213 gal Boragel, 45000# 20/40 prop
5080-94'	15578 gal Boragel, 77700# 20/40 prop (cont'd)

33. PRODUCTION

DATE FIRST PRODUCTION	PRODUCTION METHOD (Flowing, gas lift, pumping - size and type of pump)	WELL STATUS (Producing or shut-in)					
9/26/97	2 1/2" x 1-3/4" x 16' 40 ring RHAC pump	producing					
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL - BBL.	GAS - MCF.	WATER - BBL.	GAS-OIL RATIO
9/30/97	24			465	125	8	
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24 HR. RATE	OIL - BBL.	GAS - MCF.	WATER - BBL.	OIL GRAVITY - API (CORR.)	
	1405						

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

TEST WITNESSED BY
Dave Schreiner

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

Signed

Deana Bell


Title Operations Coordinator

Date

11-25-97

* (See Instructions and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly or willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



CONFIDENTIAL

WELL COMPLETION 07-10

(continued)

32.

4705-09'		5802 gal Boragel, 29500# 20/40 prop
4299-4305' &	4275-78'	10189 gal Boragel, 63200# 20/40 prop
4052-58' &	4032-40'	6415 gal Boragel, 41200# 20/40 prop

CONFIDENTIAL

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

38. GEOLOGIC MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
B Marker	3871		CONFIDENTIAL			
X Marker	4367					
Y Marker	4400					
Douglas Creek	4510					
B Limestone	4885					
Castle Peak	5458					
Basal Carbonate	5863					

STATE OF UTAH
 DIVISION OF OIL, GAS AND MINING
 ENTITY ACTION FORM - FORM 6

OPERATOR Petroglyph Operating Co. Inc.
 ADDRESS P.O. Box 607
Roosevelt, UT 84066

OPERATOR ACCT. N. N3800

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	12259	43-013-31901	Ute Tribal 07-10	MUSE	7	SS	3W	Duchesne	7-15-97	
WELL 1 COMMENTS: Battery w/ Ute Tribal 07-09 Entity added 11-12-97. fee											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

- ACTION CODES (See instructions on back of form)
- A - Establish new entity for new well (single well only)
 - B - Add new well to existing entity (group or unit well)
 - C - Re-assign well from one existing entity to another existing entity
 - D - Re-assign well from one existing entity to a new entity
 - E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.
 (3/89)

Wesley Bell
 Signature
Operations Coordinator 11-12-97
 Title Date
 Phone No. 801 722-2531

002

HUTCHINSON

11/12/87 15:22 FAX 8017229145

11/12/97 16:35 316 665 8577 PETROGLYPH UT-DOG 002/004

PETROGLYPH



P.O. Box 1839
Hutchinson, KS 67504-1839
Phone: (316) 665-8500
Fax: (316) 665-8577

This facsimile contains privileged and confidential information intended only for the use of the individual or entity named below. If the reader of the facsimile is not the intended recipient or the employee or agent responsible for delivering it to the intended recipient, you are hereby on notice that you are in possession of confidential and privileged information. Any dissemination, distribution or copying of this facsimile is strictly prohibited. If you have received this facsimile in error, please immediately notify the sender by telephone (collect) and return the original to the sender at the above address via the U.S. Postal Service.

To: Lisha Cordova From: Learna Bell

Company: _____ Company: Petroglyph

Fax: _____ Pages: 5 (including cover)

Phone: _____ Date: 11/12/97

Re: _____ CC: _____

Urgent For Review Please Comment Please Complete _____

● Comments:

Please deliver to Lisha - ASAP (Thank you)
Lisha - please call me at 316-665-8500
w/ Entity #'s.
Thanks a bunch,
Learna

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
1420H623506

6. If Indian, Allottee or Tribe Name
UTE INDIAN TRIBE

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

7. If Unit or CA/Agreement, Name and/or No.
1420H624650

1. Type of Well
 Oil Well Gas Well Other

8. Well Name and No.
UTE TRIBAL 07-10

2. Name of Operator
PETROGLYPH OPERATING COMPANY, Contact: MICHEAL SAFFORD
E-Mail: msafford@petrogllyphenergy.com

9. API Well No.
43-013-31901

3a. Address
P.O. BOX 607
ROOSEVELT, UT 84066

3b. Phone No. (include area code)
Ph: 435.722.2531
Fx: 435.722.9145

10. Field and Pool, or Exploratory
ANTELOPE CREEK

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 7 T5S R3W Mer NWSE 1786FSL 1687FEL

11. County or Parish, and State
DUCHESNE COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> WRK
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The above referenced well had a rig on it reperforating and acidizing, to improve production on 3/21/2001. The well was restored to production on 3/26/2001.

Zones reperforated:
4273-81, 4296-4309, 5072-80, 5094-5104
Zones Acidized:
5072-5104 treated with 1600 gallons 15% HCL and additives
4705-4709 treated with 400 gallons 15% HCL and additives
4273-4309 treated with 1400 gallons 15% HCL and additives
4032-4058 treated with 600 gallons 15% HCL and additives

SEARCHED
SERIALIZED
INDEXED
FILED
JUN 27 2001
BLM - DENVER

14. I hereby certify that the foregoing is true and correct.
Electronic Submission #5314 verified by the BLM Well Information System For PETROGLYPH OPERATING COMPANY,, sent to the Vernal

Name (Printed/Typed) MICHEAL SAFFORD Title COORDINATOR

Signature _____ Date 06/27/2001

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

AUG-26-2002 MON 12:35 PM OIL, GAS & MINING

FAX NO. 801 359 3940

P. 02

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Petroglyph Operating Co.
Address: P.O. Box 607
Roosevelt, UT. 84066

Operator Account Number: N3800

Phone Number: 435-722-2531

Well 1

API Number	Well Name	QQ	Sec	Twp	Rng	County
43-013-31901	Ute Tribal 07-10	NW SE	7	55	3W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date	
C	12259	09392	7-15-1997		Sept-2004	
Comments: <u>GRV</u> <u>10/12/04 ER</u>						

Well 2

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date	
Comments: 						

Well 3

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date	
Comments: 						

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Callie Duncan
Name (Please Print)
Callie Duncan
Signature
Production Asst. 10-11-04
Title Date

(5/2000)

RECEIVED

OCT 12 2004

DIV. OF OIL, GAS & MINING