

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5a. Lease Serial No. 20G0006154	
6. If Indian, Allottee or Tribe Name UTE	
7. If Unit or CA Agreement, Name and No. NA	
8. Lease Name and Well No. Ute Tribal 15-25-4-3	
9. API Well No. 4301334268	
10. Field and Pool, or Exploratory <del>Undesignated</del> South Myton Bend	11. Sec., T. R. M. or Blk. and Survey or Area Sec. 25, T4S R3W
12. County or Parish Duchesne	13. State UT
14. Distance in miles and direction from nearest town or post office* Approximately 10.4 miles southwest of Myton, UT	15. Distance from proposed* location to nearest property or lease line, ft. Approx. NA' f/lease, NA' f/unit (Also to nearest drig. unit line, if any)
16. No. of acres in lease NA	17. Spacing Unit dedicated to this well 40 Acres
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 1259'	19. Proposed Depth 6,505'
20. BLM/BIA Bond No. on file RLB00100473	21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5592' GL
22. Approximate date work will start* 3rd Qtr. 2009	23. Estimated duration (7) days from SPUD to rig release

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the BLM.

25. Signature 	Name (Printed/Typed) Mandie Crozier	Date 4/21/09
Title Regulatory Specialist		
Approved by Signature 	Name (Printed/Typed) BRADLEY G. HILL	Date 05-14-09
Title Office	ENVIRONMENTAL MANAGER	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

RECEIVED

APR 27 2009

DIV. OF OIL, GAS & MINING

Federal Approval of this  
Action is Necessary




# T4S, R3W, U.S.B.&M.

## NEWFIELD PRODUCTION COMPANY

WELL LOCATION, WELL 15-25-4-3,  
 LOCATED AS SHOWN IN THE SW 1/4 SE  
 1/4 (LOT 1) OF SECTION 25, T4S, R3W,  
 U.S.B.&M. DUCHESNE COUNTY, UTAH.

◆ = SECTION CORNERS LOCATED

THIS IS TO CERTIFY THAT THE ABOVE PLAN WAS  
 PREPARED FROM FIELD NOTES AND SURVEYS  
 MADE BY ME OR UNDER MY SUPERVISION AND THAT  
 THE SAME ARE TRUE AND CORRECT TO THE BEST  
 OF MY KNOWLEDGE AND BELIEF.



BASIS OF ELEV;  
 U.S.G.S. 7-1/2 min QUAD (MYTON SW)

**WELL 15-25-4-3**  
 (Surface Location) NAD 83  
 LATITUDE = 40° 06' 04.27"  
 LONGITUDE = 110° 10' 08.96"

<b>TRI STATE LAND SURVEYING &amp; CONSULTING</b> 180 NORTH VERNAL AVE. - VERNAL, UTAH 84078 (435) 781-2501	
DATE SURVEYED: 01-16-09	SURVEYED BY: C.M.
DATE DRAWN: 01-19-09	DRAWN BY: F.T.M.
REVISED:	SCALE: 1" = 1000'

NEWFIELD PRODUCTION COMPANY  
UTE TRIBAL 15-25-4-3  
SW/SE SECTION 25, T4S, R3W  
DUCHESNE COUNTY, UTAH

ONSHORE ORDER NO. 1

**DRILLING PROGRAM**

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta                    0' – 1675'  
Green River            1675'  
Wasatch                6505'  
Base of Moderately Saline Ground Water @ 5250'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation 1675' – 6505' - Oil

4. **PROPOSED CASING PROGRAM**

Please refer to the Ute Tribe Green River Development Program Standard Operating Practices (SOP).

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

Please refer to the Ute Tribe Green River Development Program Standard Operating Practices (SOP). See Exhibit "C".

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

Please refer to the Ute Tribe Green River Development Program Standard Operating Practices (SOP).

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Please refer to the Ute Tribe Green River Development Program Standard Operating Practices (SOP).

8. **TESTING, LOGGING AND CORING PROGRAMS:**

Please refer to the Ute Tribe Green River Development Program Standard Operating Practices (SOP).

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated

bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient

**10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

Please refer to the Ute Tribe Green River Development Program Standard Operating Practices (SOP).

**NEWFIELD PRODUCTION COMPANY  
UTE TRIBAL 15-25-4-3  
SW/SE SECTION 25, T4S, R3W  
DUCHESNE COUNTY, UTAH**

**ONSHORE ORDER NO. 1**

**MULTI-POINT SURFACE USE & OPERATIONS PLAN**

**1. EXISTING ROADS**

See attached Topographic Map "A"

To reach Newfield Production Company well location site Ute Tribal 15-25-4-3 located in the SW 1/4 SE 1/4 Section 25, T4S, R3W, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed southwesterly - 6.4 miles  $\pm$  to its junction with an existing road to the southwest; proceed southwesterly - 1.9 miles  $\pm$  to its junction with an existing road to the northeast; proceed northeasterly - 0.3 miles  $\pm$  to its junction with the beginning of the proposed access road; proceed along the proposed access road - 1520'  $\pm$  to the proposed well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

**2. PLANNED ACCESS ROAD**

Approximately 1520' of access road is proposed for the proposed well. See attached **Topographic Map "B"**.

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

**3. LOCATION OF EXISTING WELLS**

Refer to Exhibit "B".

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent surface equipment will be painted Carlsbad. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck for drilling purposes from the following water sources:

Johnson Water District  
Water Right : 43-7478

Neil Moon Pond  
Water Right: 43-11787

Maurice Harvey Pond  
Water Right: 47-1358

Newfield Collector Well  
Water Right: 41-3530 (A30414DV, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), State of Utah approved surface disposal facilities, or Federally approved surface disposal facilities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

**Fencing Requirements**

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – Todd and Camille Moon. See attached Surface Use Agreement.

12. **OTHER ADDITIONAL INFORMATION**

Newfield Production Company requests 1520' of disturbed area be granted to allow for construction of the planned access road. **Refer to Topographic Map "B"**. A permanent width of 30' and a running surface of 18' is proposed for the planned access road. The construction phase of the planned access road will last approximately (5) days. The planned access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%. There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road. There are no fences encountered along this proposed road. There will be no new gates or cattle guards required. All construction material for this access road will be borrowed material accumulated during construction of the access road.

Newfield Production Company requests 1520' of disturbed area be granted for construction of the proposed gas lines. It is proposed that the disturbed area will temporarily be 50' wide to allow for construction of a 6" gas gathering line, and a 3" poly fuel gas line, with a permanent width of 30' upon completion of the proposed gas lines. The construction phase of the proposed gas lines will last approximately (5) days. Both proposed lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."**

Newfield Production Company requests 1520' of disturbed area be granted to allow for construction of the proposed water lines. It is proposed that the disturbed area will temporarily be 50' wide to allow for construction of a buried 3" steel water injection line and a buried 3" poly water return line and 30' wide upon completion of the proposed water lines. Both proposed lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** In the event that the proposed well is converted to a water injection well, a separate injection permit will be applied for through the proper agencies.

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

**Additional Surface Stipulations**

All lease and/or unit operations will be conducted in such a manner that full compliance is made

with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

### **Hazardous Material Declaration**

Newfield Production Company guarantees that during the drilling and completion of the Ute Tribal 15-25-4-3, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Ute Tribal 15-25-4-3, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office as well as the Ute Tribe Energy and Mineral Department shall be notified upon site completion prior to moving on the drilling rig.

### **13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

#### Representative

Name: Dave Allred  
Address: Newfield Production Company  
Route 3, Box 3630  
Myton, UT 84052  
Telephone: (435) 646-3721

#### Certification

Please be advised that Newfield Production Company is considered to be the operator of well #15-25-4-3, SW/SE Section 25, T4S, R3W, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #RLB00100473.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

4/21/09  
Date

  
Mandie Crozier  
Regulatory Specialist  
Newfield Production Company

**MEMORANDUM  
of  
EASEMENT, RIGHT-OF-WAY  
and  
SURFACE USE AGREEMENT**

This Easement, Right-of-Way and Surface Use Agreement ("Agreement") is entered into this 1st day of February, 2008 by and between **Todd and Camille Moon, whose address is Route 3 Box 3622, Myton, Utah 84052** ("Surface Owner," whether one or more) and Newfield Production Company, a Texas corporation ("NEWFIELD"), with offices at 1401 17<sup>th</sup> Street, Suite #1000, Denver, Colorado 80202, covering certain lands, (the "Lands") situated in Duchesne County, Utah described as follows:

Township 4 South, Range 3 West  
Section 25: All  
Duchesne County, Utah

being, 622 acres more or less,

and associated road and pipeline routes beginning at each of the wellsites and traversing the lands as shall be agreed upon prior to the construction of same.

For and in consideration of the sum of ten dollars (\$10.00), and other valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the undersigned hereby agree to the terms and provisions set forth as follows:

1. Compensation for Well; Release of All Claims

NEWFIELD shall pay to Surface Owner the sum as set forth in and according to the terms of that certain Letter Agreement for Easement, Right-of Way and Surface Use by and between Surface Owner and NEWFIELD, dated February 01, 2008, as full payment and satisfaction for any and all detriment, depreciation, injury or damage of any nature to the Lands or growing crops thereon that may occur as a result of NEWFIELD's drilling or completion operations or its continuing activities for the production or transportation of oil, gas, or other hydrocarbons or products associated with the foregoing including, but not limited to, surface use, access, pipelines, gathering lines, pipeline interconnections, and any and all other reasonable or customary uses of land related to said operations or activities.

2. Grant of Right of Way and Easement

Surface Owner hereby grants, bargains, leases, assigns, and conveys to NEWFIELD an easement and right-of-way for the purpose of construction, using and maintaining access roads, locations for surface equipment and subsurface gathering lines for each well drilled upon the Lands, pipelines, and pipeline interconnections for two years from date of this agreement and so long thereafter as NEWFIELD's oil and gas leases remain in effect.

This Agreement shall be binding upon the respective heirs, executors, administrators, successors, and assigns of the undersigned.

These Parties hereto have executed this document effective as of the day first above written.

TODD AND CAMILLE MOON

NEWFIELD PRODUCTION COMPANY

By: Todd Moon  
Todd Moon, private surface owner


By: \_\_\_\_\_  
Gary D. Packer, President

By: Camille Moon  
Camille Moon, private surface owner

STATE OF UTAH )  
 )ss  
COUNTY OF Duchesne )

This instrument was acknowledged before me this 6<sup>th</sup> day of Feb, 2008 by **Todd and Camille Moon, private surface owners.**

Witness my hand and official seal.



David Allred  
Notary Public

My commission expires July 5, 2011

STATE OF COLORADO )  
 )ss  
COUNTY OF Denver )

This instrument was acknowledged before me this \_\_\_\_\_, 2008 by **Gary D. Packer, as President of Newfield Production Company, a Texas corporation, on behalf of the corporation.**

Witness my hand and official seal.



\_\_\_\_\_  
Notary Public

My commission expires \_\_\_\_\_

# NEWFIELD PRODUCTION COMPANY

WELL 15-25-4-3

Section 25, T4S, R3W, U.S.B.&M.



*Note:*  
Flare pit is to be located a minimum of 80' from well head.

REFERENCE POINTS





220' NORTHEAST	= 5590.8'
270' NORTHEAST	= 5591.5'
170' SOUTHEAST	= 5582.1'
220' SOUTHEAST	= 5572.7'

SURVEYED BY: C.M.	DATE SURVEYED: 01-16-09
DRAWN BY: F.T.M.	DATE DRAWN: 01-26-09
SCALE: 1" = 50'	REVISED:

**Tri State**  
Land Surveying, Inc.  
(435) 781-2501  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

# NEWFIELD PRODUCTION COMPANY

## CROSS SECTIONS WELL 15-25-4-3



ESTIMATED EARTHWORK QUANTITIES  
(No Shrink or swell adjustments have been used)  
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	3,340	3,340	Topsoil is not included in Pad Cut	0
PIT	640	0		640
TOTALS	3,980	3,340	1,100	640

NOTE:  
UNLESS OTHERWISE  
NOTED ALL CUT/FILL  
SLOPES ARE AT 1.5:1


SURVEYED BY: C.M.	DATE SURVEYED: 01-16-09
DRAWN BY: F.T.M.	DATE DRAWN: 01-26-09
SCALE: 1" = 50'	REVISED:

**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

# NEWFIELD PRODUCTION COMPANY

## TYPICAL RIG LAYOUT

### WELL 15-25-4-3



SURVEYED BY: C.M.	DATE SURVEYED: 01-16-09
DRAWN BY: F.T.M.	DATE DRAWN: 01-26-09
SCALE: 1" = 50'	REVISED:

**Tri State**  
 Land Surveying, Inc. (435) 781-2501  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078


# Newfield Production Company Proposed Site Facility Diagram

Ute Tribal 15-25-4-3

SW/SE Sec. 25, T4S, R3W

Duchesne County, Utah

EDA# 2OG0006154



## Legend

Emulsion Line	.....
Load Rack	- - - - -
Water Line	- . - . - .
Gas Sales	- - - - -
Oil Line	—————

### Production Phase:

- 1) Valves 1, 3, and 4 sealed closed
- 2) Valves 2, 5, and 6 sealed open

### Sales Phase:


- 1) Valves 1, 2, 4, 5, and 6 sealed closed
- 2) Valve 3 open

### Draining Phase:

- 1) Valves 1 and 6 open

Diked Section





**Proposed Location  
Well 15-25**

See Topo "B"

±0.3 mi.

±0.8 mi.

±1.1 mi.

±4.7 mi.

±1.7 mi.

±1.4 mi.

**NEWFIELD**  
Exploration Company

**Well 15-25-4-3**  
**SEC. 25, T4S, R3W, U.S.B.&M.**




**Tri-State**  
Land Surveying Inc.  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1:100,000  
DRAWN BY: JAS  
DATE: 02-04-2009

**Legend**

- Existing Road
- Proposed Access

TOPOGRAPHIC MAP  
**"A"**



**NEWFIELD**  
Exploration Company

**Well 15-25-4-3**  
**SEC. 25, T4S, R3W, U.S.B.&M.**




**Tri-State**  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'  
DRAWN BY: JAS  
DATE: 02-04-2009

**Legend**

- Existing Road
- Proposed Access

TOPOGRAPHIC MAP  
**"B"**



 **NEWFIELD**  
Exploration Company

**Well 15-25-4-3**  
**SEC. 25, T4S, R3W, U.S.B.&M.**




*Tri-State*  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'  
DRAWN BY: JAS  
DATE: 02-04-2009

**Legend**

-  Roads
-  Proposed Gas Line
-  Proposed Water Line


**TOPOGRAPHIC MAP**  
**"C"**



- Newfield Wells**
- Location
  - Surface Spud
  - Drilling
  - Waiting on Completion
  - Producing Oil Well
  - Producing Gas Well
  - Water Injection Well
  - Dry Hole
  - Temporarily Abandoned
  - Plugged & Abandoned
  - Shut In
  - Water Source Well
  - Water Disposal Well
  - Injection Stations
- Unit Outlines**
- 

**NEWFIELD**  
 ROCKY MOUNTAINS  
 Exhibit A  
 Dechenre & Urtah Contrace

100' 17th Street Suite 2008  
 Denver, Colorado 80202  
 Phone: (303) 853-0122




**NEWFIELD**  
Exploration Company

**Well 15-25-4-3**  
**SEC. 25, T4S, R3W, U.S.B.&M.**




**Tri-State**  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave., Vernal, Utah 84078


SCALE: 1" = 2,000'  
DRAWN BY: JAS  
DATE: 02-04-2009

**Legend**

- Location
- One-Mile Radius

**Exhibit "B"**

**2-M SYSTEM**  
Blowout Prevention Equipment Systems



**EXHIBIT C**

**WORKSHEET  
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 04/27/2009

API NO. ASSIGNED: 43-013-34268

WELL NAME: UTE TRIBAL 15-25-4-3  
 OPERATOR: NEWFIELD PRODUCTION ( N2695 )  
 CONTACT: MANDIE CROZIER

PHONE NUMBER: 435-646-3721

PROPOSED LOCATION:  
 SWSE 25 040S 030W  
 SURFACE: 0826 FSL 2191 FEL  
 BOTTOM: 0826 FSL 2191 FEL  
 COUNTY: DUCHESNE  
 LATITUDE: 40.10283 LONGITUDE: -110.16844  
 UTM SURF EASTINGS: 570877 NORTHINGS: 4439291  
 FIELD NAME: SOUTH MYTON BENCH ( 117 )

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 2 - Indian  
 LEASE NUMBER: 20G0006154  
 SURFACE OWNER: 4 - Fee

PROPOSED FORMATION: GRRV  
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

Plat

Bond: Fed[] Ind[2] Sta[] Fee[]  
 (No. RLB00100473 )

Potash (Y/N)

Oil Shale 190-5 (B) or 190-3 or 190-13

Water Permit  
 (No. 43-7478 )

RDCC Review (Y/N)  
 (Date: \_\_\_\_\_ )

Fee Surf Agreement  (Y/N)

Intent to Commingle (Y/N)

LOCATION AND SITING:

         R649-2-3.

Unit: \_\_\_\_\_

R649-3-2. General  
 Siting: 460 From Qtr/Qtr & 920' Between Wells

         R649-3-3. Exception

         Drilling Unit

Board Cause No: \_\_\_\_\_

Eff Date: \_\_\_\_\_

Siting: \_\_\_\_\_

         R649-3-11. Directional Drill

COMMENTS: Sup, Separate File  
Needs Permit (04-21-09)

STIPULATIONS: 1- Federal Approval  
2- Spaling Strip  
3- STATEMENT OF BASIS

API Number: 4301334268

Well Name: UTE TRIBAL 15-25-4-3



Township 04.0 S Range 03.0 W Section 25

Meridian: UBM

Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:  
Map Produced by Diana Mason

<b>Units</b>	<b>Wells Query Events</b>
STATUS	✕ <all other values>
ACTIVE	GIS_STAT_TYPE
EXPLORATORY	<Null>
GAS STORAGE	◆ APD
NF PP OIL	◆ DRL
NF SECONDARY	◆ GI
PI OIL	◆ GS
PP GAS	✕ LA
PP GEOTHERML	✕ NEW
PP OIL	✕ OPS
SECONDARY	○ PA
TERMINATED	✕ PGW
<b>Fields</b>	● POW
STATUS	⊙ RET
ACTIVE	✕ SGW
COMBINED	● SOW
Sections	○ TA
	○ TW
	✕ WD
	○ WI
	● WS



# Application for Permit to Drill

## Statement of Basis

5/12/2009

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
1455	43-013-34268-00-00		OW	P	No
<b>Operator</b>	NEWFIELD PRODUCTION COMPANY	<b>Surface Owner-APD</b>			
<b>Well Name</b>	UTE TRIBAL 15-25-4-3	<b>Unit</b>			
<b>Field</b>	UNDESIGNATED	<b>Type of Work</b>			
<b>Location</b>	SWSE 25 4S 3W U 826 FSL 2191 FEL	GPS Coord (UTM) 570877E 4439291N			

### Geologic Statement of Basis

The mineral lease for the proposed well is owned by the Ute Tribe. The BLM will be the agency responsible for evaluating and approving the proposed drilling casing and cement programs.

Brad Hill

5/12/2009

**APD Evaluator**

**Date / Time**

### Surface Statement of Basis

The general location is approximately 11 road miles southwest of Myton, UT in the upper portion of the Pleasant Valley Drainage. Wells Draw is approximately 4 miles to the east and the Ute Tribal Indian Reservation Boundary less than 1 mile to the south. Broad flats with rolling hills characterize the area. Flats are often intersected by drainages with gentle to moderate side slopes. Flats at lower elevations to the northeast are frequently used for agriculture. No seeps, springs or streams are known to exist in the immediate area. An occasional pond for livestock watering occurs. Pleasant Valley Wash drains into the Pariette Draw drainage of Duchesne County. The lower reaches of both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 18 miles down drainage from the area. Access is by State and County and existing or proposed oilfield development roads to within 1,210 feet of the site. From this point new construction will be required.

The proposed Ute Tribal 15-25-4-3 oil well site is in upper Pleasant Valley. The pad is laid out longitudinally along the south slope of a moderately gentle ridge in rolling topography. A significant wash to the south has been avoided by moving the location to the northwest corner of the normal drilling window. No drainages intersect the site and no diversions will be needed. The selected site appears to be a suitable location for constructing a pad, drilling and operating a well.

Mr. Todd Moon owns the surface of the location and was invited to the pre-site by phone. He said he did not see a need to attend. On previous pre-sites in this general area, Mr. Moon requested that needle and thread grass and globe mallow be included in the seed mix that will be used to re-vegetate the site. A signed landowner agreement exists. The minerals are owned by the United States Government and held in trust for the Ute Indian Tribe. James Hereford of the BIM was invited to the pre-site but did not attend.

Floyd Bartlett

4/21/2009

**Onsite Evaluator**

**Date / Time**

### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

# ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY  
Well Name UTE TRIBAL 15-25-4-3  
API Number 43-013-34268-0 APD No 1455 Field/Unit UNDESIGNATED  
Location: 1/4,1/4 SWSE Sec 25 Tw 4S Rng 3W 826 FSL 2191 FEL  
GPS Coord (UTM) 570880 4439296 Surface Owner

## Participants

Floyd Bartlett and Mark Reinholt (DOGGM), Tim Eaton (Newfield).

## Regional/Local Setting & Topography

The general location is approximately 11 road miles southwest of Myton, UT in the upper portion of the Pleasant Valley Drainage. Wells Draw is approximately 4 miles to the east and the Ute Tribal Indian Reservation Boundary less than 1 mile to the south. Broad flats with rolling hills characterize the area. Flats are often intersected by drainages with gentle to moderate side slopes. Flats at lower elevations to the northeast are frequently used for agriculture. No seeps, springs or streams are known to exist in the immediate area. An occasional pond for livestock watering occurs. Pleasant Valley Wash drains into the Pariette Draw drainage of Duchesne County. The lower reaches of both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 18 miles down drainage from the area. Access is by State and County and existing or proposed oilfield development roads to within 1,210 feet of the site. From this point new construction will be required.

The proposed Ute Tribal 15-25-4-3 oil well site is in upper Pleasant Valley. The pad is laid out longitudinally along the south slope of a moderately gentle ridge in rolling topography. A significant wash to the south has been avoided by moving the location to the northwest corner of the normal drilling window. No drainages intersect the site and no diversions will be needed. The selected site appears to be a suitable location for constructing a pad, drilling and operating a well.

Mr. Todd Moon owns the surface of the location and was invited to the pre-site by phone He said he did not see a need to attend.

## Surface Use Plan

### Current Surface Use

Grazing  
Agricultural  
Recreational

### New Road

Miles	Well Pad	Src Const Material	Surface Formation
0.24	Width 199 Length 300	Onsite	UNTA

Ancillary Facilities N

## Waste Management Plan Adequate?

## Environmental Parameters

Affected Floodplains and/or Wetland N

### Flora / Fauna

A fair desert shrub type consisting of horsebrush, cheatgrass, halogeton, Indian ricegrass, globe mallow, shadscale, curly mesquite, broom snakeweed, and spring annuals.

Cattle, deer, prairie dogs, small mammals and birds.

**Soil Type and Characteristics**

Deep Sandy loam.

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

**Drainage Diversion Required** N

**Berm Required?** Y

**Erosion Sedimentation Control Required?** N

**Paleo Survey Run?** N    **Paleo Potential Observed?**    **Cultural Survey Run?** N    **Cultural Resources?**

**Reserve Pit**

**Site-Specific Factors**

**Site Ranking**

<b>Distance to Groundwater (feet)</b>	100 to 200	5
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>	300 to 1320	10
<b>Native Soil Type</b>	Mod permeability	10
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>	<10	0
<b>Affected Populations</b>	<10	0
<b>Presence Nearby Utility Conduits</b>	Not Present	0

**Final Score** 30    1    **Sensitivity Level**

**Characteristics / Requirements**

A reserve pit 40' x 80' x 8' deep will be located in an area of cut on the northwest side of the location. A pit liner is required. Newfield commonly uses a 16-mil liner.

**Closed Loop Mud Required?** Y    **Liner Required?** Y    **Liner Thickness** 16    **Pit Underlayment Required?** Y

**Other Observations / Comments**

Floyd Bartlett  
**Evaluator**

4/21/2009  
**Date / Time**



JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

May 14, 2009

Newfield Production Company  
Rt. #3, Box 3630  
Myton, UT 84052

Re: Ute Tribal 15-25-4-3 Well, 826' FSL, 2191' FEL, SW SE, Sec. 25, T. 4 South, R. 3 West,  
Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-34268.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Duchesne County Assessor  
Bureau of Land Management, Vernal Office



Operator: Newfield Production Company

Well Name & Number Ute Tribal 15-25-4-3

API Number: 43-013-34268

Lease: 2OG0006154

Location: SW SE                      Sec. 25                      T. 4 South                      R. 3 West

### Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281    (801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 20G0006154
6a. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name UTE
2. Name of Operator Newfield Production Company		7. If Unit or CA Agreement, Name and No. NA
3a. Address Route #3 Box 3630, Myton UT 84052		8. Lease Name and Well No. Ute Tribal 15-25-4-3
3b. Phone No. (include area code) (435) 646-3721		9. API Well No. 43 013 34268
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SW/SE 826' FSL 2191' FEL At proposed prod. zone Lot #1		10. Field and Pool, or Exploratory Undesignated
14. Distance in miles and direction from nearest town or post office* Approximately 10.4 miles southwest of Myton, UT		11. Sec., T. R. M. or Blk. and Survey or Area Sec. 25, T4S R3W
15. Distance from proposed* location to nearest property or lease line, ft. Approx. NA' f/lse, NA' f/unit (Also to nearest drig. unit line, if any)	16. No. of acres in lease NA	17. Spacing Unit dedicated to this well 40 Acres
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 1259'	19. Proposed Depth 6,505'	20. BLM/BIA Bond No. on file RLB00100473
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5592' GL	22. Approximate date work will start* 3rd Qtr. 2009	23. Estimated duration (7) days from SPUD to rig release
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the BLM.

25. Signature <i>Mandie Crozier</i>	Name (Printed/Typed) Mandie Crozier	Date 4/21/09
Title Regulatory Specialist		
Approved by (Signature) <i>Jerry Kevork</i>	Name (Printed/Typed) Jerry Kevork	Date JUN 24 2009
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached. **CONDITIONS OF APPROVAL ATTACHED**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

NOS

IAFMSS#09RRH0061A

RECEIVED NOTICE OF APPROVAL  
RECEIVED

APR 24 2009

JUL 01 2009

UDOGM

BLM/VERNAL, UTAH DIV. OF OIL, GAS & MINING



**UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE**

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

<b>Company:</b>	<b>Newfield Production Company</b>	<b>Location:</b>	<b>SWSE (Lot #1), Sec. 25, T4S, R3W</b>
<b>Well No:</b>	<b>Ute Tribal 15-25-4-3</b>	<b>Lease No:</b>	<b>2OG0006154</b>
<b>API No:</b>	<b>43-013-34268</b>	<b>Agreement:</b>	<b>N/A</b>

<b>Title</b>	<b>Name</b>	<b>Office Phone Number</b>	<b>Cell Phone Number</b>
Petroleum Engineer:	Matt Baker	(435) 781-4490	(435) 828-4470
Petroleum Engineer:	Michael Lee	(435) 781-4432	(435) 828-7875
Petroleum Engineer:	Ryan Angus	(435) 781-4430	(435) 828-7368
Supervisory Petroleum Technician:	Jamie Sparger	(435) 781-4502	(435) 828-3913
Supervisory NRS:	Karl Wright	(435) 781-4484	
NRS/Enviro Scientist:	Christine Cimiluca	(435) 781-4475	
NRS/Enviro Scientist:	Dan Emmett	(435) 781-3414	(435) 828-4029
NRS/Enviro Scientist:	Anna Figueroa	(435) 781-3407	(435) 828-3548
NRS/Enviro Scientist:	Lori Ford	(435) 781-4406	
NRS/Enviro Scientist:	David Gordon	(435) 781-4424	
NRS/Enviro Scientist:	James Hereford	(435) 781-3412	(435) 828-3546
NRS/Enviro Scientist:	Chuck Macdonald	(435) 781-4441	(435) 828-7481
NRS/Enviro Scientist:	Nathan Packer	(435) 781-3405	(435) 828-3545
NRS/Enviro Scientist:	Paul Percival	(435) 781-4493	(435) 828-7381
NRS/Enviro Scientist:	Verlyn Pindell	(435) 781-3402	(435) 828-3547
NRS/Enviro Scientist:	Holly Villa	(435) 781-4404	(435) 828-3544

**Fax: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Construction Activity	- The Ute Tribe Energy & Minerals Dept. shall be notified in writing 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion	- Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)***

- NONE

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

- Newfield Production Co. shall adhere to all referenced requirements in the SOP (version: Ute Tribal Green River Development Program) along with all Oil and Gas rules and requirements listed in the Code of Federal Regulations and all Federal Onshore Oil and Gas Orders.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth

(from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to [UT\\_VN\\_Welllogs@BLM.gov](mailto:UT_VN_Welllogs@BLM.gov). This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

## OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location (¼¼, Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or

data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross Rig #  
29 \_\_\_\_\_ Submitted By Jay Burton Phone Number  
435-823-6013

Well Name/Number Ute Tribal 15-25-4-3W  
Qtr/Qtr SW/SE Section 25 Township 4S Range 3W  
Lease Serial Number  
20G0006154  
API Number 43-013-34268

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 12/23/09 12:00 AM  PM

Casing – Please report time casing run starts, not cementing times.

- Surface Casing
- Intermediate Casing
- Production Casing
- Liner
- Other

Date/Time 12/24/09 9:00 AM  PM

BOPE

- Initial BOPE test at surface casing point
- BOPE test at intermediate casing point
- 30 day BOPE test
- Other

Date/Time \_\_\_\_\_ AM  PM

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**  
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUBMIT IN TRIPLICATE - Other Instructions on page 2**

1. Type of Well  
 Oil Well  Gas Well  Other

2. Name of Operator  
NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630  
Myton, UT 84052

3b. Phone (include area code)  
435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SWSE Section 25 T4S R3W

5. Lease Serial No.  
MON BUTTE EDA 20G0005609

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or

8. Well Name and No.  
UTE TRIBAL 15-25-4-3

9. API Well No.  
4301334268

10. Field and Pool, or Exploratory Area  
MONUMENT BUTTE

11. County or Parish, State  
DUCHESNE, UT

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off	
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity	
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____	
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Spud Notice _____	
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	_____	

13. Describe Proposed or Completed Operation: (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 12/23/09 MIRU Ross #29. Spud well @ 12:00pm. Drill 360' of 121/4" hole with air mist. TIH w/7 jt's 85/8" j-55 24# csgn. set @ 363.66KB On 12/29/09 cement with 180 sks of class "G" w/ 2% CaCL2 + 1/4# sk Cello-Flake mixed @15.8 ppg>1.17 cf/sk yeild. Returned 4 bbls cement to pit. Woc.

I hereby certify that the foregoing is true and correct (Printed/ Typed) Jav Burton	Title Drilling Foreman
Signature <i>Jav E. Burton</i>	Date 12/29/2009

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by .....	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on page 2)

**RECEIVED**

**JAN 20 2010**

**DIV. OF OIL, GAS & MINING**





STATE OF UTAH  
 DIVISION OF OIL, GAS AND MINING  
 ENTITY ACTION FORM -FORM 6

OPERATOR: NEWFIELD PRODUCTION COMPANY  
 ADDRESS: RT. 3 BOX 3630  
MYTON, UT 84052

OPERATOR ACCT. NO. N2695

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	17400 ✓	4301334119	JONAH T-1-9-16	NESE	1	9S	16E	DUCHESNE	1/7/2010	1/28/10
WELL 1 COMMENTS: <i>GRRV</i> <i>BHL = SESE</i>											
A	99999	17463	4301334269	UTE TRIBAL 14-25-4-3	SESW	25	4S	3W	DUCHESNE	1/13/2010	1/28/10
WELL 1 COMMENTS: <i>GRRV</i>											
B	99999	17400 ✓	4301334094	MON BT NE B-25-8-16	SESE	24 25	8S	16E	DUCHESNE	1/2/2010	1/28/10
WELL 1 COMMENTS: <i>GRRV</i> <i>BHL = Sec 25 NENE</i>											
A	99999	17464	4301350152	UTE TRIBAL 10-23-4-3	NWSE	23	4S	3W	DUCHESNE	1/11/2010	1/28/10
WELL 1 COMMENTS: <i>GRRV</i>											
A	99999	17465	50003 <del>4301350004</del>	MOON 2-29-4-2	SENW	29	4S	2W	DUCHESNE	1/11/2010	1/28/10
WELL 5 COMMENTS: <i>GRRV</i>											
A	99999	17466	4301334268	UTE TRIBAL 15-25-4-3	SWSE	25	4S	3W	DUCHESNE	12/23/2009	1/28/10
WELL 5 COMMENTS: <i>GRRV</i>											

**CONFIDENTIAL**

- ACTION CODES (See instructions on back of form)
- A - 1 new entity for new well (single well only)
  - B - well to existing entity (group or unit well)
  - C - from one existing entity to another existing entity
  - D - well from one existing entity to a new entity
  - E - other (explain in comments section)

RECEIVED  
 JAN 19 2010

*[Signature]*  
 Signature  
 Production Clerk

Jentri Park

01/13/10  
 Date

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:  
UTE TRIBE EDA 20G0006154

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

1. TYPE OF WELL: OIL WELL  GAS WELL  OTHER

8. WELL NAME and NUMBER:  
UTE TRIBAL 15-25-4-3

2. NAME OF OPERATOR:  
NEWFIELD PRODUCTION COMPANY

9. API NUMBER:  
4301334268

3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 PHONE NUMBER 435.646.3721

10. FIELD AND POOL, OR WILDCAT:  
MONUMENT BUTTE

4. LOCATION OF WELL:  
FOOTAGES AT SURFACE: COUNTY: DUCHESNE  
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWSE, 25, T4S, R3W STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 02/06/2010	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
The above subject well was completed on 02-06-10, attached is a daily completion status report.

NAME (PLEASE PRINT) Lucy Chavez-Naupoto

TITLE Administrative Assistant

SIGNATURE 

DATE 02/09/2010

(This space for State use only)

**RECEIVED**

**FEB 11 2010**

**DIV. OF OIL, GAS & MINING**

## Daily Activity Report

Format For Sundry

**UTE TRIBAL 15-25-4-3**

**12/1/2009 To 4/28/2010**

**1/28/2010 Day: 1**

**Completion**

Rigless on 1/28/2010 - CBL/Perforate 1st stage. - RU frac head & Cameron BOP's. RU Hot Oiler truck test casing, frac head w/ valves & BOP's to 4500 psi. RU Perforators LLC. WLT w/ mast. Run CBL under pressure. WLTD @ 6464' & cement top @ 114'. RIH & perforate CP5 sds @ 6292-96' w/ 3-1/8" Port Guns (11 gram, .36"EH, 120°, 16.82"pen) w/ 3 spf for total of 12 shots. SIFN w/ 155 bbls EWTR.

**Daily Cost:** \$0

**Cumulative Cost:** \$11,078

**2/2/2010 Day: 2**

**Completion**

Rigless on 2/2/2010 - Frac well. Flow well back. - Stage #1: RU BJ Services "Ram Head" frac flange. Open well w/ 16 psi on casing. Perfs broke down @ 3505 psi back to psi 3389 w/ 4 bbls @ 3 bpm. ISIP was 2501 w/ .83FG. 1 min was 2444. 4 min was 2410. Pump 6 bbls of 15% HCL acid. Pump 30 gals of Techni Hib chemical @ 4% by volume. Frac w/ 14,488#'s of sand in 337 bbls of Lightning 17 frac fluid. Treated @ ave pressure of 3562 w/ ave rate of 17 bpm w/ 6 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 2743 w/ .87FG. 5 min was 2330. 10 min was 2255. 15 min was 2205. Leave pressure on well. 492 Bbls EWTR. - Stage #2: RU PSI WLT, crane & lubricator. RIH w/ 4-3/4" Weatherford (6K) composite flow through frac plug & 2', 3', 2', 2', 2' perf guns. Set plug @ 6220'. Perforate CP3 sds @ 6117-6119', 6108-6111', CP2 sds @ 6045-47', 6035-37', CP.5 sds @ 5961-63' w/ 3-1/8" Slick Guns (16 gram. .34"EH, 120°, 21"pen) w/ 3 spf for total of 33 shots (mis fired on guns). Open well w/ 1766 psi on casing. Perfs broke down @ 2081 psi back to psi 2043 w/ 4 bbls @ 3 bpm. Pressure to low to rec'd ISIP. Pump 30 gals of Techni Hib chemical @ 4% by volume. Frac w/ 85,733#'s of sand in 689 bbls of Lightning 17 frac fluid. Treated @ ave pressure of 2895 w/ ave rate of 39 bpm w/ 8 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 2365 w/ .83FG. 5 min was 2175. 10 min was 2123. 15 min was 2077. Leave pressure on well. 1181 Bbls EWTR. - Stage #3: RU WLT. RIH w/ frac plug & 2', 4' perf guns. Set plug @ 5235'. Perforate D2 sds @ 5135-37', 5128-32' w/ 3 spf for total of 18 shots. Open well w/ 1820 psi on casing. Perfs broke down @ 1890 psi back to psi 1847 w/ 2 bbls @ 3 bpm. Pressure to low to rec'd ISIP. Pump 30 gals of Techni Hib chemical @ 4% by volume. Frac w/ 17,357#'s of sand in 293 bbls of Lightning 17 frac fluid. Treated @ ave pressure of 2770 w/ ave rate of 30 bpm w/ 6 ppg of sand. ISIP was 1927 w/ .81FG. 5 min was 1796. 10 min was 1770. 15 min was 1752. 1476 Bbls EWTR. RD BJ & WLT. Flow well back. Well flowed for 3 hours & died w/ 450 bbls rec'd. SIFN w/ 1026 bbls EWTR.

**Daily Cost:** \$0

**Cumulative Cost:** \$62,622

**2/3/2010 Day: 3**

**Completion**

NC #2 on 2/3/2010 - MIRUSU NC #2. PU tbg to drill out plugs - Hot oiler had thawed BOP. Check csg pressure. 100 PSI. Open well to pit. ND BOP. Break out frac head. MU wellhead flange. NU BOP. RU workflow. MU Weatherford 4 3/4" chomp bit, bit sub, & PSN. TIH picking up tbg. Shut down to make repairs to tbg tongs. Continue PU tbg. Shut down to make repairs to NC #2. Continue PU tbg. PU 166 jts tbg. Tag sand @ 5150'. 85' of sand. RU power swivel & rig pump lines. SDFN

**Daily Cost:** \$0

**Cumulative Cost:** \$74,226

**2/4/2010 Day: 4**

**Completion**

NC #2 on 2/4/2010 - Drill out plugs. Clean out to btm. Swab well - Hot oiler had thawed well. Check pressure. CSG 250 psi. TBG 200 psi. Open well to pit. Showed trace of yellow paraffin while bleeding off pressure. Tag up on sand. Catch circulation. Clean out to CBP @ 5179'. Drill out plug. Continue pick up tbg to tag CBP @ 6136'. Drill out plug. Continue to pick up tbg to tag sand @ 6391'. Clean out to sand to WLPBTD @ 6464'. Attempt to clean out to PBTD @ 6525'. Did not make hole. Pull up off btm. Circulate clean. RU swab equipment. RIH w/ swab. IFL @ surface. Make 15 swab runs to recover 150 bbls fluid. FFL @ 1400'. Final sample had trace of oil & sand. SDFN

**Daily Cost:** \$0

**Cumulative Cost:** \$79,585

**2/5/2010 Day: 5**

**Completion**

NC #2 on 2/5/2010 - Tag btm. Circulate well bore. Round trip tbg. - Check well pressure. CSG 250 psi. TBG 250 psi. Open well to pit to bleed off pressure. MU wash stand. RIH w/ tbg to tag sand. No sand. Circulate well bore clean. TOOH w/ tbg. LD bit & bit sub. MU btm hole assembly. Make repairs to NC #2. TIH w/ tbg detail @ follows. NC, 2 jts 2 7/8" J-55 tbg, PSN, 1 jt, TAC, & 201 jts. Get in hole w/ tbg. RD workfloor. ND BOP. Set TAC. MU B-1 adapter flange. Land tbg on wellhead flange w/ 18000# tension. NU wellhead. X-over to rod equipment. SDFN

**Daily Cost:** \$0

**Cumulative Cost:** \$117,905

**2/6/2010 Day: 6**

**Completion**

NC #2 on 2/6/2010 - PU rod string. PWOP - Open well. PU & prime new Central Hydraulic 2 1/2" x 1 3/4" x 21' x 24' RHAC pump. TIH picking up rod detail as follows. 6 - 1 1/2" wt bars, 20 - 3/4" guided rods, 125 - 3/4" plain rods, & 104 - 7/8" guided rods. PU new 1 1/2" x 26' polished rod. RU pumping unit. Fill & test tbg to 200 psi w/1 bw. Stroke test pump to 800 psi w/ unit. RDMOSU NC #2. PWOP @ 3:00 PM W/ 84" SL @ 5 SPM FINAL REPORT! EST WTR TO RECOVER 1063 BBLs **Finalized**

**Daily Cost:** \$0

**Cumulative Cost:** \$157,050

**Pertinent Files: Go to File List**

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0137  
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

a. Type of Well  Oil Well  Gas Well  Dry  Other  
 b. Type of Completion:  New Well  Work Over  Deepen  Plug Back  Diff. Resvr.,  
 Other: \_\_\_\_\_

5. Lease Serial No.  
EDA 20G0006154

6. If Indian, Allottee or Tribe Name  
UTE TRIBE  
7. Unit or CA Agreement Name and No.

2. Name of Operator  
NEWFIELD EXPLORATION COMPANY

8. Lease Name and Well No.  
UTE TRIBAL 15-25-4-3

3. Address  
1401 17TH ST. SUITE 1000 DENVER, CO 80202

3a. Phone No. (include area code)  
(435)646-3721

9. AFI Well No.  
43-013-34268

4. Location of Well (Report location clearly and in accordance with Federal requirements)\*

At surface 826' FSL & 2191' FEL (SW/SE) SEC. 25, T4S, R3W

10. Field and Pool or Exploratory  
MONUMENT BUTTE

11. Sec., T., R., M., on Block and  
Survey or Area  
SEC. 25, T4S, R3W

At top prod. interval reported below

12. County or Parish  
DUCHESNE  
13. State  
UT

At total depth 6580'

14. Date Spudded  
12/23/2009

15. Date T.D. Reached  
01/19/2010

16. Date Completed 02/06/2010  
 D & A  Ready to Prod.

17. Elevations (DF, RKB, RT, GL)\*  
5592' GL 5604' KB

18. Total Depth: MD 6580'  
TVD

19. Plug Back T.D.: MD 6525'  
TVD

20. Depth Bridge Plug Set: MD  
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)  
DUAL IND GRD, SP, COMP. DENSITY, COMP. NEUTRON, GR, CALIPER, CMT BOND

22. Was well cored?  No  Yes (Submit analysis)  
Was DST run?  No  Yes (Submit report)  
Directional Survey?  No  Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24#	0	364'		180 CLASS G			
7-7/8"	5-1/2" J-55	15.5#	0	6570'		300 PRIMLITE		114'	
						400 50/50 POZ			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT@ 6441'	TA @ 6343'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) GREEN RIVER			See Below			
B)						
C)						
D)						

26. Perforation Record

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
See Below	See Below

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
2-6-10	2-18-10	24	→	56	0	103			2-1/2" x 1-3/4" x 21' x 24' RHAC Pump
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

RECEIVED  
FEB 22 2010

\*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

USED FOR FUEL

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MRK GARDEN GULCH 1	3959' 4193'
				GARDEN GULCH 2 POINT 3	4318' 4614'
				X MRKR Y MRKR	4868' 4899'
				DOUGALS CREEK MRK BI CARBONATE MRK	5020' 5287'
				B LIMESTON MRK LBLKSH	5426' 5742'
				CPLS BSCARB	5930' 6356'
				WASATCH	6489'

32. Additional remarks (include plugging procedure):

Stage 1: Green River Formation (CP5) 6292-6296', .36" 3/12 Frac w/ 14488#s of 20/40 sand in 90 bbls of Lightning 17 fluid

Stage 2: Green River Formation (CP.5, CP2, & CP3) 5961-63', 6035-47', 6108-19', .34" 3/33 Frac w/ 85733#s of 20/40 sand in 363 bbls of Lightning 17 fluid

Stage 3: Green River Formation (D2) 5128-37' .34" 3/18 Frac w/ 17357#s of 20/40 sand in 101 bbls of Lightning 17 fluid


33. Indicate which items have been attached by placing a check in the appropriate boxes:

- Electrical/Mechanical Logs (1 full set req'd.)     
  Geologic Report     
  DST Report     
  Directional Survey  
 Sundry Notice for plugging and cement verification     
  Core Analysis     
 Other: Drilling Daily Activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)\*

Name (please print) Lucy Chavez-Naupoto

Title Administrative Assistant

Signature 

Date 02/19/2010

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Daily Activity Report**

Format For Sundry

**UTE TRIBAL 15-25-4-3****11/1/2009 To 3/28/2010****UTE TRIBAL 15-25-4-3****Waiting on Cement****Date:** 12/26/2009

Ross #29 at 363. Days Since Spud - KB.Cemented with BJ on 12/29/09 with 180sks of Class G+2% Calcium Chloride. 4bbls returned to pit. - Ross Rig # 29 Spud on 12/23/09. Drilled 360' of 12.25" hole. Ran 8jts of 8 5/8" casing set @ 363.66' - State and BLM notified by e-mail.

**Daily Cost:** \$0**Cumulative Cost:** \$64,764**UTE TRIBAL 15-25-4-3****Waiting on Cement****Date:** 1/12/2010

NDSI #3 at 363. 1 Days Since Spud - PU & RIH with BHA / Tag cmt @ 320' Drill 7 7/8" hole with fresh water to a depth of 363' - Work on frozen air & water lines - Finish RU - RU Quick test & Test upper kelly, safety valve, blind & pipe rams & choke to 2000 psi/ Csg. To 1500 - On 1/11/10 RD & move rig #3 from Ute Tribal 15-23-4-3 to Ute Tribal 15-25-4-3/ Set Equipment

**Daily Cost:** \$0**Cumulative Cost:** \$102,489**UTE TRIBAL 15-25-4-3****Drill 7 7/8" hole with fresh water****Date:** 1/13/2010

NDSI #3 at 1575. 2 Days Since Spud - Work on charge pump - Drill 7 7/8" hole with fresh water to a depth of 1575' - Survey @ 1441' 2.75° - Drill 7 7/8" hole with fresh water to a depth of 1521' - Survey @ 907' 1.25° - Drill 7 7/8" hole with fresh water to a depth of 987' - Survey @ 658' 2.25° - Rig service/ Function test BOP's & Crown-O-Matic - Drill 7 7/8" hole with fresh water to a depth of 735' - Install drive bushings & rotating head rubber - Drill 7 7/8" hole with fresh water to a depth of 703'

**Daily Cost:** \$0**Cumulative Cost:** \$140,605**UTE TRIBAL 15-25-4-3****Drill 7 7/8" hole with fresh water****Date:** 1/14/2010

NDSI #3 at 1884. 3 Days Since Spud - Drill 7 7/8" hole with fresh water to a depth of 1884' - Wait on orders - TOOH for directional tools/ LD2 DC's, 2IBS's,& MM - PU directional tools & TIH/ Directional tools not working - TOOH & LD directional tools - Wait on new directional tools - Drill 7 7/8" hole with fresh water to a depth of 1740' - Survey @ 1663' 3° - Rig service / Function test BOP's & Crown-O-Matic - Kelly up & Wash 30' to bottom - Work on rotar seal pump - PU new directional tools & TIH

**Daily Cost:** \$0**Cumulative Cost:** \$199,736**UTE TRIBAL 15-25-4-3****Drill 7 7/8" hole with fresh water****Date:** 1/15/2010

NDSI #3 at 3600. 4 Days Since Spud - Rig service/ Function test BOP's & Crown-O-Matic /Flow 5 gal/min. - Drill 7 7/8" hole with fresh water to a depth of 3600' - Drill 7 7/8" hole with fresh water to a depth of 2608'

**Daily Cost:** \$0

**Cumulative Cost:** \$216,641

**UTE TRIBAL 15-25-4-3**

**Drill 7 7/8" hole with fresh water**

**Date:** 1/16/2010

NDSI #3 at 4800. 5 Days Since Spud - Drill 7 7/8" hole with fresh water to a depth of 4057' - Rig service / Function test BOP's & Crown-O-Matic - Drill 7 7/8" hole with fresh water to a depth of 4800'

**Daily Cost:** \$0

**Cumulative Cost:** \$232,946

**UTE TRIBAL 15-25-4-3**

**Drill 7 7/8" hole with fresh water**

**Date:** 1/17/2010

NDSI #3 at 5860. 6 Days Since Spud - Drill 7 7/8" hole with fresh water to a depth of 5155' - Rig service & Function test BOP's & Crown-O-Matic/ No flow - Drill 7 7/8" hole with fresh water to a depth of 5860'

**Daily Cost:** \$0

**Cumulative Cost:** \$249,051

**UTE TRIBAL 15-25-4-3**

**PU & RIH with kill strin**

**Date:** 1/18/2010

NDSI #3 at 6580. 7 Days Since Spud - RU Halliburton to log/ Well started kicking/ RD Halliburton - LDDP & BHA - Pump 10# brine from 4500' to surface - LDDP to 4500' - PU DP & RIH for kill string - Drill 7 7/8" hole with fresh water to a depth of 6580' TD - Rig service / Function test BOP's & Crown-O-Matic/ 0 flow - Drill 7 7/8" hole with fresh water to a depth of 6321' - Circ for logs

**Daily Cost:** \$0

**Cumulative Cost:** \$297,384

**UTE TRIBAL 15-25-4-3**

**Rigging down**

**Date:** 1/19/2010

NDSI #3 at 6580. 9 Days Since Spud - RU BJ & cement with 300 sks PLII+3% KCL+5#CSE+0.5#CF+2#KOL+.5SMS+FP+SF/ 11 ppg /3.43 yield/ Followed - by 400 sks 50:50:2+3%KCL+0.5%EC-1+.25#CF+.05#SF+.3SMS+FP-6L/14.4 ppg/1.24 yield/50bbbls to pit - ND BOP's & Set Csg. Slips with 115,000# tension - Clean mud tanks - Release rig @ 1:00 PM 1/19/10 - PU drill pipe to 3000'/Mud up - Circ & cond mud / WT up to 11 ppg - Pump pill & TOOH / Std back - RU Halliburton/Log running triple combo TD to 2000'/ GR, SP, Resistivity- Laterolog, Neutron porosit - Density porosity+ PE-Logging speed of 30'/min/ Loggers TD 6592' - TIH with DP to 3000'/ Install rotating head rubber - Circ out gas/ pump pill - LDDP - Change to casing rams & test to 2000 psi - RU QT & run 176 jts of 5.5" J55 15.5# Csg/ Tag @ 6562' /Land @ 6569.58 - RU BJ & cement with 300 sks PLII+3% KCL+5#CSE+0.5#CF+2#KOL+.5SMS+FP+SF/ 11 ppg /3.43 yield/ Followed - by 400 sks 50:50:2+3%KCL+0.5%EC-1+.25#CF+.05#SF+.3SMS+FP-6L/14.4 ppg/1.24 yield/50bbbls to pit - ND BOP's & Set Csg. Slips with 115,000# tension - Clean mud tanks - Release rig @ 1:00 PM 1/19/10 - RU QT & run 176 jts of 5.5" J55 15.5# Csg/ Tag @ 6562' /Land @ 6569.58 - Change to casing rams & test to 2000 psi - LDDP - Circ out gas/ pump pill - TIH with DP to 3000'/ Install rotating head rubber - Density porosity+ PE-Logging speed of 30'/min/ Loggers TD 6592' - RU Halliburton/Log running triple combo TD to 2000'/ GR, SP, Resistivity- Laterolog, Neutron porosit - Pump pill & TOOH / Std back - PU drill pipe to 3000'/Mud up - Circ & cond mud / WT up to 11 ppg **Finalized**

**Daily Cost:** \$0

**Cumulative Cost:** \$441,364