

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL				1. WELL NAME and NUMBER South Monument Butte State N-2-9-16		
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				3. FIELD OR WILDCAT MONUMENT BUTTE		
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO				5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)		
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY				7. OPERATOR PHONE 435 646-4825		
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052				9. OPERATOR E-MAIL mcrozier@newfield.com		
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) ML-21839		11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>		12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>		
13. NAME OF SURFACE OWNER (if box 12 = 'fee')				14. SURFACE OWNER PHONE (if box 12 = 'fee')		
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')				16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')		18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>		19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	1989 FSL 1981 FWL	NESW	2	9.0 S	16.0 E	S
Top of Uppermost Producing Zone	2399 FSL 1486 FWL	NESW	2	9.0 S	16.0 E	S
At Total Depth	2635 FNL 1204 FWL	SWNW	2	9.0 S	16.0 E	S
21. COUNTY DUCHESNE		22. DISTANCE TO NEAREST LEASE LINE (Feet) 1204		23. NUMBER OF ACRES IN DRILLING UNIT 20		
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1443		26. PROPOSED DEPTH MD: 6407 TVD: 6407		
27. ELEVATION - GROUND LEVEL 5519		28. BOND NUMBER B001834		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 43-7478		

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP

NAME Mandie Crozier	TITLE Regulatory Tech	PHONE 435 646-4825
SIGNATURE	DATE 08/18/2009	EMAIL mcrozier@newfield.com
API NUMBER ASSIGNED 43013501170000	APPROVAL  Permit Manager	

Proposed Hole, Casing, and Cement

String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	5.5	0	6407		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	6407	15.5			



Proposed Hole, Casing, and Cement

String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	8.625	0	1100		
Pipe	Grade	Length	Weight			
	Grade J-55 ST&C	1100	24.0			


T9S, R16E, S.L.B.&M.

NEWFIELD PRODUCTION COMPANY

WELL LOCATION, SOUTH MONUMENT BUTTE N-2-9-16, LOCATED AS SHOWN IN THE NE 1/4 SW 1/4 OF SECTION 2, T9S, R16E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
 (435) 781-2501

DATE SURVEYED: 06-23-09	SURVEYED BY: T.H.
DATE DRAWN: 06-26-09	DRAWN BY: F.T.M.
REVISED:	SCALE: 1" = 1000'

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are base on LOCATION: an N.G.S. OPUS Correction. LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

SOUTH MONUMENT BUTTE N-2-9-16
 (Surface Location) NAD 83
 LATITUDE = 40° 03' 29.09"
 LONGITUDE = 110° 05' 20.36"

NEWFIELD PRODUCTION COMPANY
SOUTH MONUMENT BUTTE STATE N-2-9-16
AT SURFACE: NE/SW SECTION 2, T9S, R16E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0 – 1560'
Green River	1560'
Wasatch	6407'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation 1560' – 6407' – Oil

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 1,100'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM**

a. **Casing Design: So. Monument Butte State N-2-9-16**

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	1,100'	24.0	J-55	STC	2,950	1,370	244,000
						4.78	3.91	9.24
Prod casing 5-1/2"	0'	6,407'	15.5	J-55	LTC	4,810	4,040	217,000
						2.36	1.98	2.19

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. **Cementing Design: So. Monument Butte State N-2-9-16**

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	1,100'	Class G w/ 2% CaCl	504	30%	15.8	1.17
			590			
Prod casing Lead	4,407'	Prem Lite II w/ 10% gel + 3% KCl	305	30%	11.0	3.26
			993			
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363	30%	14.3	1.24
			451			

- *Actual volume pumped will be 15% over the caliper log
- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
 - Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

Waiting On Cement: A minimum of four (4) hours shall elapse prior to attempting any pressure testing of the BOP equipment which would subject the surface casing cement to pressure, and a minimum of six (6) hours shall elapse before drilling out of the wiper plug, cement, or shoe is begun. WOC time shall be recorded in the Driller's Log. Compressive Strength shall be a minimum of 500 psi prior to drilling out.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if

the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

The production casing cementing program shall be conducted as approved to protect and/or isolate all usable water zones, potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals.

As a minimum, usable water zones shall be isolated and/or protected by having a cement top for the production casing at least 200 feet above the base of the usable water. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

Top plugs shall be used to reduce contamination of cement by displacement fluid. A bottom plug or other acceptable technique, such as a suitable preflush fluid, inner string cement method, etc., shall be utilized to help isolate the cement from contamination by the mud being displaced ahead of the cement slurry.

All casing strings below the conductor shall be pressure tested to 0.22 psi per foot of casing string length or to 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield. If pressure declines more than 10% in 30 minutes, corrective action shall be taken.

Setting of each string of casing showing the size, grade, weight of casing set, depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of the cementing tools used, casing test method and results, and the date of the work done. Spud date will be shown on the first reports submitted.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 1100 feet will be drilled with an air/mist system. From about 1100 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite.

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 1100' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the first quarter of 2010, and take approximately seven (7) days from spud to rig release.

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C





Project: USGS Myton SW (UT)
 Site: SECTION 2 9S 16E
 Well: N-2-9-16*
 Wellbore: Wellbore #1
 Design: Design #1



Azimuths to True North
 Magnetic North: 11.56°

Magnetic Field
 Strength: 52492.8snT
 Dip Angle: 65.86°
 Date: 7/15/2009
 Model: IGRF200510

KOP @ 1200'
 DOGLEG RATE 1.5 DEG/100
 TARGET RADIUS IS 75'



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
N-2-9-16 TGT	6298.0	657.6	-793.5	Circle (Radius: 75.0)

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	1200.0	0.00	0.00	1200.0	0.0	0.0	0.00	0.00	0.0	
3	2027.5	12.41	309.65	2021.0	57.0	-68.7	1.50	309.65	89.3	
4	6406.8	12.41	309.65	6298.0	657.6	-793.5	0.00	0.00	1030.6	N-2-9-16 TGT

NEWFIELD



NEWFIELD EXPLORATION

USGS Myton SW (UT)

SECTION 2 9S 16E

N-2-9-16*

Wellbore #1

Plan: Design #1

Standard Planning Report

15 February, 2010



HATHAWAYBURNHAM

Planning Report

Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well N-2-9-16*
Company:	NEWFIELD EXPLORATION	TVD Reference:	N-2-9-16 @ 5531.0ft (EST KB)
Project:	USGS Myton SW (UT)	MD Reference:	N-2-9-16 @ 5531.0ft (EST KB)
Site:	SECTION 2 9S 16E	North Reference:	True
Well:	N-2-9-16*	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		Using geodetic scale factor

Site	SECTION 2 9S 16E, SEC 2 9S 16E				
Site Position:		Northing:	7,193,600.00ft	Latitude:	40° 3' 34.952 N
From:	Map	Easting:	2,036,100.00ft	Longitude:	110° 5' 10.480 W
Position Uncertainty:	0.0 ft	Slot Radius:	"	Grid Convergence:	0.91 °

Well	N-2-9-16*, SHL LAT: 40 03 29.09, LONG: -110 05 20.36					
Well Position	+N/-S	-593.2 ft	Northing:	7,192,994.76 ft	Latitude:	40° 3' 29.090 N
	+E/-W	-768.2 ft	Easting:	2,035,341.30 ft	Longitude:	110° 5' 20.360 W
Position Uncertainty		0.0 ft	Wellhead Elevation:	5,531.0 ft	Ground Level:	5,519.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	7/15/2009	11.56	65.86	52,493

Design	Design #1				
Audit Notes:					
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0	
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	6,298.0	0.0	0.0	309.65	

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,027.5	12.41	309.65	2,021.0	57.0	-68.7	1.50	1.50	0.00	309.65	
6,406.8	12.41	309.65	6,298.0	657.6	-793.5	0.00	0.00	0.00	0.00	N-2-9-16 TGT



HATHAWAYBURNHAM

Planning Report

Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well N-2-9-16*
Company:	NEWFIELD EXPLORATION	TVD Reference:	N-2-9-16 @ 5531.0ft (EST KB)
Project:	USGS Myton SW (UT)	MD Reference:	N-2-9-16 @ 5531.0ft (EST KB)
Site:	SECTION 2 9S 16E	North Reference:	True
Well:	N-2-9-16*	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	1.50	309.65	1,300.0	0.8	-1.0	1.3	1.50	1.50	0.00
1,400.0	3.00	309.65	1,399.9	3.3	-4.0	5.2	1.50	1.50	0.00
1,500.0	4.50	309.65	1,499.7	7.5	-9.1	11.8	1.50	1.50	0.00
1,600.0	6.00	309.65	1,599.3	13.3	-16.1	20.9	1.50	1.50	0.00
1,700.0	7.50	309.65	1,698.6	20.8	-25.2	32.7	1.50	1.50	0.00
1,800.0	9.00	309.65	1,797.5	30.0	-36.2	47.0	1.50	1.50	0.00
1,900.0	10.50	309.65	1,896.1	40.8	-49.2	64.0	1.50	1.50	0.00
2,000.0	12.00	309.65	1,994.2	53.3	-64.3	83.5	1.50	1.50	0.00
2,027.5	12.41	309.65	2,021.0	57.0	-68.7	89.3	1.50	1.50	0.00
2,100.0	12.41	309.65	2,091.8	66.9	-80.7	104.9	0.00	0.00	0.00
2,200.0	12.41	309.65	2,189.5	80.6	-97.3	126.4	0.00	0.00	0.00
2,300.0	12.41	309.65	2,287.2	94.3	-113.8	147.9	0.00	0.00	0.00
2,400.0	12.41	309.65	2,384.8	108.1	-130.4	169.4	0.00	0.00	0.00
2,500.0	12.41	309.65	2,482.5	121.8	-146.9	190.8	0.00	0.00	0.00
2,600.0	12.41	309.65	2,580.2	135.5	-163.5	212.3	0.00	0.00	0.00
2,700.0	12.41	309.65	2,677.8	149.2	-180.0	233.8	0.00	0.00	0.00
2,800.0	12.41	309.65	2,775.5	162.9	-196.6	255.3	0.00	0.00	0.00
2,900.0	12.41	309.65	2,873.1	176.6	-213.1	276.8	0.00	0.00	0.00
3,000.0	12.41	309.65	2,970.8	190.4	-229.7	298.3	0.00	0.00	0.00
3,100.0	12.41	309.65	3,068.5	204.1	-246.2	319.8	0.00	0.00	0.00
3,200.0	12.41	309.65	3,166.1	217.8	-262.8	341.3	0.00	0.00	0.00
3,300.0	12.41	309.65	3,263.8	231.5	-279.3	362.8	0.00	0.00	0.00
3,400.0	12.41	309.65	3,361.5	245.2	-295.9	384.3	0.00	0.00	0.00
3,500.0	12.41	309.65	3,459.1	258.9	-312.4	405.8	0.00	0.00	0.00
3,600.0	12.41	309.65	3,556.8	272.6	-329.0	427.3	0.00	0.00	0.00
3,700.0	12.41	309.65	3,654.4	286.4	-345.5	448.8	0.00	0.00	0.00
3,800.0	12.41	309.65	3,752.1	300.1	-362.1	470.3	0.00	0.00	0.00
3,900.0	12.41	309.65	3,849.8	313.8	-378.6	491.8	0.00	0.00	0.00
4,000.0	12.41	309.65	3,947.4	327.5	-395.2	513.3	0.00	0.00	0.00
4,100.0	12.41	309.65	4,045.1	341.2	-411.7	534.8	0.00	0.00	0.00
4,200.0	12.41	309.65	4,142.8	354.9	-428.3	556.3	0.00	0.00	0.00
4,300.0	12.41	309.65	4,240.4	368.7	-444.8	577.8	0.00	0.00	0.00
4,400.0	12.41	309.65	4,338.1	382.4	-461.4	599.2	0.00	0.00	0.00
4,500.0	12.41	309.65	4,435.7	396.1	-477.9	620.7	0.00	0.00	0.00
4,600.0	12.41	309.65	4,533.4	409.8	-494.5	642.2	0.00	0.00	0.00
4,700.0	12.41	309.65	4,631.1	423.5	-511.0	663.7	0.00	0.00	0.00
4,800.0	12.41	309.65	4,728.7	437.2	-527.6	685.2	0.00	0.00	0.00
4,900.0	12.41	309.65	4,826.4	451.0	-544.1	706.7	0.00	0.00	0.00
5,000.0	12.41	309.65	4,924.1	464.7	-560.7	728.2	0.00	0.00	0.00
5,100.0	12.41	309.65	5,021.7	478.4	-577.2	749.7	0.00	0.00	0.00
5,200.0	12.41	309.65	5,119.4	492.1	-593.8	771.2	0.00	0.00	0.00



HATHAWAYBURNHAM

Planning Report


Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well N-2-9-16*
Company:	NEWFIELD EXPLORATION	TVD Reference:	N-2-9-16 @ 5531.0ft (EST KB)
Project:	USGS Myton SW (UT)	MD Reference:	N-2-9-16 @ 5531.0ft (EST KB)
Site:	SECTION 2 9S 16E	North Reference:	True
Well:	N-2-9-16*	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,300.0	12.41	309.65	5,217.1	505.8	-610.3	792.7	0.00	0.00	0.00
5,400.0	12.41	309.65	5,314.7	519.5	-626.9	814.2	0.00	0.00	0.00
5,500.0	12.41	309.65	5,412.4	533.2	-643.4	835.7	0.00	0.00	0.00
5,600.0	12.41	309.65	5,510.0	547.0	-660.0	857.2	0.00	0.00	0.00
5,700.0	12.41	309.65	5,607.7	560.7	-676.5	878.7	0.00	0.00	0.00
5,800.0	12.41	309.65	5,705.4	574.4	-693.1	900.2	0.00	0.00	0.00
5,900.0	12.41	309.65	5,803.0	588.1	-709.6	921.7	0.00	0.00	0.00
6,000.0	12.41	309.65	5,900.7	601.8	-726.2	943.2	0.00	0.00	0.00
6,100.0	12.41	309.65	5,998.4	615.5	-742.7	964.7	0.00	0.00	0.00
6,200.0	12.41	309.65	6,096.0	629.3	-759.3	986.1	0.00	0.00	0.00
6,300.0	12.41	309.65	6,193.7	643.0	-775.8	1,007.6	0.00	0.00	0.00
6,406.8	12.41	309.65	6,298.0	657.6	-793.5	1,030.6	0.00	0.00	0.00

Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
N-2-9-16 TGT - hit/miss target - Shape	0.00	0.00	6,298.0	657.6	-793.5	7,193,639.73	2,034,537.59	40° 3' 35.588 N	110° 5' 30.565 W
- plan hits target									
- Circle (radius 75.0)									



**South Monument Butte N-2 (Proposed Well)
South Monument Butte 11-2 (Existing Well)**

See Topo "B"

NEWFIELD
Exploration Company

**South Monument Butte N-2-9-16 (Proposed Well)
South Monument Butte 11-2-9-16 (Existing Well)
Pad Location NESW SEC. 2, T9S, R16E, S.L.B.&M.**




*Tri-State
Land Surveying Inc.*
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

**SCALE: 1 = 100,000
DRAWN BY: JAS
DATE: 06-30-2009**

Legend

Existing Road

**TOPOGRAPHIC MAP
"A"**



South Monument Butte N-2 (Proposed Well)
South Monument Butte 11-2 (Existing Well)



NEWFIELD
Exploration Company

South Monument Butte N-2-9-16 (Proposed Well)
South Monument Butte 11-2-9-16 (Existing Well)
 Pad Location NESW SEC. 2, T9S, R16E, S.L.B.&M.





Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
 DRAWN BY: JAS
 DATE: 06-30-2009

Legend

 Existing Road

TOPOGRAPHIC MAP
"B"



South Monument Butte N-2 (Proposed Well)
South Monument Butte 11-2 (Existing Well)

Existing Gas Pipeline

Existing Waterline

NEWFIELD
Exploration Company

South Monument Butte N-2-9-16 (Proposed Well)
South Monument Butte 11-2-9-16 (Existing Well)
 Pad Location NESW SEC. 2, T9S, R16E, S.L.B.&M.




Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: JAS
DATE: 06-30-2009

Legend

— Roads

TOPOGRAPHIC MAP
"C"




- Newfield Wells**
- Location
 - Surface Spud
 - Drilling
 - Waiting on Completion
 - Producing Oil Well
 - Producing Gas Well
 - Water Injection Well
 - Dry Hole
 - Temporarily Abandoned
 - Plugged & Abandoned
 - Shut In
 - Water Source Well
 - Water Disposal Well
 - Injection Stations
- Unit Outlines**
-

NEWFIELD
ROCKY MOUNTAINS

Exhibit A
Duckhorn & Ullrich Counselors

©2011 17th Street Suite 2000
Denver, Colorado 80202
Phone (303) 953-0102

Issued 9/2011




NEWFIELD
Exploration Company

South Monument Butte N-2-9-16 (Proposed Well)
South Monument Butte 11-2-9-16 (Existing Well)
 Pad Location NESW SEC. 2, T9S, R16E, S.L.B.&M.




Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: JAS
DATE: 06-30-2009

Legend

- Pad Location
- Bottom Hole Location
- One-Mile Radius

Exhibit "B"

NEWFIELD PRODUCTION COMPANY
SOUTH MONUMENT BUTTE STATE N-2-9-16
AT SURFACE: NE/SW SECTION 2, T9S, R16E
DUCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. EXISTING ROADS

See attached **Topographic Map "A"**

To reach Newfield Production Company well location site South Monument Butte State N-2-9-16 located in the NE ¼ SW ¼ Section 2, T9S, R16E, S.L.B. & M., Duchesne County, Utah:

Proceed in a southwesterly direction out of Myton, Utah along Highway 40 approximately 1.4 ± miles to the junction of this highway and Utah State Highway 53; proceed southeasterly approximately 6.2 miles ± to its junction with an existing road to the southwest; proceed southwesterly approximately 2.9 miles ± to its junction with an existing road to the south; proceed southeasterly approximately 2.4 miles ± to its junction with an existing road to the west; proceed southwesterly approximately 0.5 miles ± to its junction with an existing road to the northwest; proceed northwesterly approximately 0.4 miles ± to its junction with an existing road to the north; proceed northerly approximately 0.2 miles ± to the existing 11-2-9-16 well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled off of the existing 11-2-9-16 well pad. See attached **Topographic Map "B"**.

There will be no new gates or cattle guards required.

3. LOCATION OF EXISTING WELLS

Refer to **EXHIBIT B**.

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

The proposed well will be drilled directionally off of the existing 11-2-9-16 well pad. There will be a pumping unit and a short flow line added to the existing tank battery for the proposed N-2-9-16.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted Carlsbad Canyon. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck for drilling purposes from the following water sources:

Johnson Water District
Water Right: 43-7478

Neil Moon Pond
Water Right: 43-11787

Maurice Harvey Pond
Water Right: 47-1358

Newfield Collector Well
Water Right: 41-3530 (A30414DV, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

The proposed South Monument Butte State N-2-9-16 will be drilled off of the existing 11-2-9-16 well pad. No additional surface disturbance will be required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. **ANCILLARY FACILITIES:**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) **Producing Location**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) **Dry Hole Abandoned Location**

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** State of Utah

12. **OTHER ADDITIONAL INFORMATION:**

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the South Monument Butte State N-2-9-16, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the South Monument Butte State N-2-9-16 Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Ten Point Well Program &
Thirteen Point Well Program
Page 8 of 8

Name: Tim Eaton
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #N-2-9-16, NE/SW Section 2, T9S, R16E, LEASE #ML-21839, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Bond #B001834.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

8/18/09
Date


Mandie Crozier
Regulatory Specialist
Newfield Production Company


NEWFIELD PRODUCTION COMPANY

WELL PAD INTERFERENCE PLAT

MONUMENT BUTTE N-2-9-16 (Proposed Well)

MONUMENT BUTTE 11-2-9-16 (Existing Well)

Pad Location: *NESW Section 2, T9S, R16E, S.L.B.&M.*



TOP HOLE FOOTAGES
 N-2-9-16 (PROPOSED)
 1989' FSL & 1981' FWL

BOTTOM HOLE FOOTAGES
 N-2-9-16 (PROPOSED)
 2635' FNL & 1204' FWL

Note:
 Bearings are based on
 GLO Information.

<i>RELATIVE COORDINATES</i>		
<i>From top hole to bottom hole</i>		
WELL	NORTH	EAST
N-2-9-16	658'	-793'

<i>LATITUDE & LONGITUDE</i>		
<i>Surface position of Wells (NAD 83)</i>		
WELL	LATITUDE	LONGITUDE
N-2-9-16	40° 03' 29.09"	110° 05' 20.53"
11-2-9-16	40° 03' 28.93"	110° 05' 20.53"

SURVEYED BY: T.H.	DATE SURVEYED: 06-23-09
DRAWN BY: F.T.M.	DATE DRAWN: 06-29-09
SCALE: 1" = 50'	REVISED:

Tri State
 Land Surveying, Inc.


(435) 781-2501
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD PRODUCTION COMPANY

SOUTH MONUMENT BUTTE N-2-9-16 (Proposed Well)

SOUTH MONUMENT BUTTE 11-2-9-16 (Existing Well)

Pad Location: NESW Section 2, T9S, R16E, S.L.B.&M.



Note:
Flare pit is to be located at least 80' from well head.

SURVEYED BY: T.H.	DATE SURVEYED: 06-19-09
DRAWN BY: F.T.M.	DATE DRAWN: 06-24-09
SCALE: 1" = 50'	REVISED:

(435) 781-2501





Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD PRODUCTION COMPANY

CROSS SECTIONS

SOUTH MONUMENT BUTTE N-2-9-16 (Proposed Well)
SOUTH MONUMENT BUTTE 11-2-9-16 (Existing Well)



NOTE:
UNLESS OTHERWISE NOTED
CUT SLOPES ARE AT 1:1
FILL SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	290	0	Topsoil is not included in Pad Cut	290
PIT	640	0		640
TOTALS	930	0	140	930


SURVEYED BY: T.H.	DATE SURVEYED: 06-19-09	
DRAWN BY: F.T.M.	DATE DRAWN: 06-24-09	
SCALE: 1" = 50'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD PRODUCTION COMPANY

TYPICAL RIG LAYOUT

SOUTH MONUMENT BUTTE N-2-9-16 (Proposed Well)
 SOUTH MONUMENT BUTTE 11-2-9-16 (Existing Well)



Note:
 Flare pit is to be located at least 80' from well head.

SURVEYED BY: T.H.	DATE SURVEYED: 06-19-09
DRAWN BY: F.T.M.	DATE DRAWN: 06-24-09
SCALE: 1" = 50'	REVISED:

Tri State (435) 781-2501
 Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

Newfield Production Company Proposed Site Facility Diagram


So. Monument Butte State N-2-9-16

From the 11-2-9-16 Location

NE/SW Sec. 2, T9S, R16E

Duchesne County, Utah

ML-21839



Site Security Plan is held at the Pleasant Valley Office, Duchesne County, Utah

Production Phase:

- 1) Valves 1, 3, and 4 sealed closed
- 2) Valves 2, 5, and 6 sealed open

Sales Phase:


- 1) Valves 1, 2, 4, 5, and 6 sealed closed
- 2) Valve 3 open

Draining Phase:

- 1) Valves 1 and 6 open

Legend


Emulsion Line
Load Rack	-----
Water Line	- . - . - .
Gas Sales	- . - . - . - .
Oil Line	—————



API Number: 4301350117
Well Name: South Monument Butte State N-2-9-16
Township 09.0 S Range 16.0 E Section 2
Meridian: SLBM
Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:
 Map Produced by Diana Mason

- Sections Wells Query Events
- <all other values>
- GIS_STAT_TYPE
- <Null>
- APD
- DRL
- GI
- GS
- LA
- NEW
- OPS
- PA
- PGW
- POW
- RET
- SGW
- SOW
- TA
- TW
- WD
- WI
- WS



From: Jim Davis
To: Bonner, Ed; Mason, Diana
Date: 8/31/2009 9:01 AM
Subject: SITLA well approvals (Newfield 16)

CC: Garrison, LaVonne
The following wells have been approved by SITLA including arch and paleo clearance.

Monument Butte East State A-36-8-16 [API #4301350105],

Monument Butte East State J-36-8-16 [API #4301350106],

Monument Butte East State B-36-8-16 [API #4301350107],

Monument Butte East State C-36-8-16 [API #4301350108],

Monument Butte East State G-36-8-16 [API #4301350109],

Monument Butte East State M-36-8-16 [API #4301350110],

Monument Butte East State H-36-8-16 [API #4301350111],

Monument Butte State Q-36-8-16 [API #4301350113],

Monument Butte East State R-36-8-16 [API #4301350114],

Monument Butte State G-2-9-16 [API #4301350115],

South Monument Butte State M-2-9-16 [API #4301350116],

South Monument Butte State N-2-9-16 [API #4301350117],

South Monument Butte State P-2-9-16 [API #4301350118],

South Monument Butte State X-2-9-16 [API #4301350119],

South Monument Butte State V-2-9-16 [API #4301350120],

South Monument Butte State W-2-9-16 [API #4301350121]

These wells are still waiting for approvals of one kind or another:

Monument Butte East Federal V-35-8-16, Host well 2-2-9-16, no new disturbance (State surface, Federal mineral)
Monument Butte East Federal W-35-8-16, Host well 2-2-9-16, no new disturbance (State surface, Federal mineral)
Monument Butte East State K-36-8-16 [API #4301350112], Host well 9-36-8-16, new disturbance

-Jim

Jim Davis
Utah Trust Lands Administration
jimdavis1@utah.gov
Phone: (801) 538-5156

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

August 28, 2009

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2009 Plan of Development South Monument Butte Unit,
Duchesne County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2009 within the South Monument Butte Unit, Duchesne County, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ Green River)		
43-013-50117	S Monument Butte	N-2-9-16 Sec 02 T09S R16E 1989 FSL 1981 FWL BHL Sec 02 T09S R16E 2635 FNL 1204 FWL
43-013-50118	S Monument Butte	P-2-9-16 Sec 02 T09S R16E 0704 FSL 0607 FWL BHL Sec 02 T09S R16E 1393 FSL 0040 FWL
43-013-50119	S Monument Butte	X-2-9-16 Sec 02 T09S R16E 0724 FSL 0613 FWL BHL Sec 02 T09S R16E 0040 FSL 1317 FWL
43-013-50120	S Monument Butte	V-2-9-16 Sec 02 T09S R16E 0775 FSL 2005 FEL BHL Sec 02 T09S R16E 0040 FSL 1393 FEL
43-013-50121	S Monument Butte	W-2-9-16 Sec 02 T09S R16E 0765 FSL 2024 FEL BHL Sec 02 T09S R16E 0040 FSL 2597 FEL

The approval of these wells should be deferred until the approval of the Greater Monument Butte Unit.

/s/ Michael L. Coulthard

bcc: File – South Monument Butte Unit
Division of Oil Gas and Mining
Central Files

Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:8-28-09



December 2, 2009

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
South Monument Butte State N-2-9-16
Greater Monument Butte (Green River) Unit
ML-21839
Surface Hole: T9S-R16E Section 2: NESW
1989' FSL 1981' FWL

At Target: T9S-R16E Section 2: SWNW
2635' FNL 1204' FWL

1911

Duchesne County, Utah

Dear Ms. Mason;

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 8/18/09, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield Certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4197 or by email at sgillespie@newfield.com. Your consideration in this matter is greatly appreciated.

Sincerely,
Newfield Production Company

A handwritten signature in blue ink that reads "Shane Gillespie".

Shane Gillespie
Land Associate

RECEIVED

DEC 07 2009

DIV. OF OIL, GAS & MINING

Well Name	NEWFIELD PRODUCTION COMPANY South Monument Butte State N-2-9		
String	Surf	Prod	
Casing Size(")	8.625	5.500	
Setting Depth (TVD)	1100	6407	
Previous Shoe Setting Depth (TVD)	0	1100	
Max Mud Weight (ppg)	8.3	8.6	
BOPE Proposed (psi)	500	2000	
Casing Internal Yield (psi)	2950	4810	
Operators Max Anticipated Pressure (psi)	2755	8.3	

Calculations	Surf String	8.625	"
Max BHP (psi)	$.052 * \text{Setting Depth} * \text{MW} =$	475	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 * \text{Setting Depth}) =$	343	YES Air drill
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 * \text{Setting Depth}) =$	233	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 * (\text{Setting Depth} - \text{Previous Shoe Depth}) =$	233	NO OK
Required Casing/BOPE Test Pressure=		1100	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	Prod String	5.500	"
Max BHP (psi)	$.052 * \text{Setting Depth} * \text{MW} =$	2865	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 * \text{Setting Depth}) =$	2096	NO
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 * \text{Setting Depth}) =$	1455	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 * (\text{Setting Depth} - \text{Previous Shoe Depth}) =$	1697	NO Reasonable
Required Casing/BOPE Test Pressure=		2000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		1100	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	$.052 * \text{Setting Depth} * \text{MW} =$		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 * \text{Setting Depth}) =$		NO
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 * \text{Setting Depth}) =$		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 * (\text{Setting Depth} - \text{Previous Shoe Depth}) =$		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	$.052 * \text{Setting Depth} * \text{MW} =$		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 * \text{Setting Depth}) =$		NO
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 * \text{Setting Depth}) =$		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 * (\text{Setting Depth} - \text{Previous Shoe Depth}) =$		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

43013501170000 South Monument Butte State N-2-9-16

Casing Schematic



Well name:	43013501170000 South Monument Butte State N-2-9-16		
Operator:	NEWFIELD PRODUCTION COMPANY		
String type:	Surface	Project ID:	43-013-50117
Location:	DUCHESNE COUNTY		

Design parameters:

Collapse

Mud weight: 8.330 ppg
 Design is based on evacuated pipe.

Burst

Max anticipated surface pressure: 968 psi
 Internal gradient: 0.120 psi/ft
 Calculated BHP: 1,100 psi

 No backup mud specified.

Minimum design factors:

Collapse:

Design factor: 1.125

Burst:

Design factor: 1.00

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.70 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.50 (B)

Tension is based on air weight.
 Neutral point: 962 ft

Environment:

H2S considered? No
 Surface temperature: 74 °F
 Bottom hole temperature: 89 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 100 ft

 Cement top: 228 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 6,298 ft
 Next mud weight: 8.600 ppg
 Next setting BHP: 2,814 psi
 Fracture mud wt: 19,250 ppg
 Fracture depth: 1,100 ft
 Injection pressure: 1,100 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1100	8.625	24.00	J-55	ST&C	1100	1100	7.972	5662
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	476	1370	2.878	1100	2950	2.68	26.4	244	9.24 J

Prepared by: Helen Sadik-Macdonald
 Div of Oil, Gas & Mining

Phone: 801-538-5357
 FAX: 801-359-3940

Date: March 1, 2010
 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1100 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013501170000 South Monument Butte State N-2-9-16		
Operator:	NEWFIELD PRODUCTION COMPANY		
String type:	Production	Project ID:	43-013-50117
Location:	DUCHESNE COUNTY		

Design parameters:

Collapse

Mud weight: 8.600 ppg
 Design is based on evacuated pipe.

Burst

Max anticipated surface pressure: 1,428 psi
 Internal gradient: 0.220 psi/ft
 Calculated BHP: 2,814 psi

No backup mud specified.

Minimum design factors:

Collapse:

Design factor: 1.125

Burst:

Design factor: 1.00

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.80 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.60 (B)

Tension is based on air weight.
 Neutral point: 5,568 ft

Environment:

H2S considered? No
 Surface temperature: 74 °F
 Bottom hole temperature: 162 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 100 ft
 Cement top: 637 ft

Directional Info - Build & Hold

Kick-off point: 1200 ft
 Departure at shoe: 1031 ft
 Maximum dogleg: 1.5 °/100ft
 Inclination at shoe: 12.42 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	6407	5.5	15.50	J-55	LT&C	6298	6407	4.825	22623
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	2814	4040	1.436	2814	4810	1.71	97.6	217	2.22 J

Prepared by: Helen Sadik-Macdonald
 Div of Oil, Gas & Mining

Phone: 801 538-5357
 FAX: 801-359-3940

Date: March 1, 2010
 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6298 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name South Monument Butte State N-2-9-16
API Number 43013501170000 **APD No** 1911 **Field/Unit** MONUMENT BUTTE
Location: 1/4,1/4 NESW **Sec 2 Tw** 9.0S **Rng** 16.0E 1989 FSL 1981 FWL
GPS Coord (UTM) 577759 4434396 **Surface Owner**

Participants

Floyd Bartlett (DOGM), Tim Eaton (Newfield).

Regional/Local Setting & Topography

The proposed South Monument Butte State M-2-9-16 and the South Monument Butte State N-2-9-16 are proposed oil wells to be directionally drilled from the existing pad of the Monument Butte State 11-2-9-16 water flood injection well. No changes are planned to the existing pad. The reserve pit will be re-dug near the original location in the southeast side of the pad. The wells are on 20-acre spacing.

A field review of the site and the existing pad showed no concerns and should be suitable for drilling and operating the proposed additional wells.

SITLA owns both the surface and the minerals.

Surface Use Plan

Current Surface Use
Existing Well Pad

New Road Miles	Well Pad	Src Const Material	Surface Formation
	Width Length		
0			

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands

Flora / Fauna
Existing Well Pad

Soil Type and Characteristics

Erosion Issues

Sedimentation Issues

Site Stability Issues

Drainage Diverson Required?

Berm Required?

Erosion Sedimentation Control Required?

Paleo Survey Run? Paleo Potential Observed? Cultural Survey Run? Cultural Resources?

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet)	100 to 200	5	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)		20	
Native Soil Type	Mod permeability	10	
Fluid Type	Fresh Water	5	
Drill Cuttings	Normal Rock	0	
Annual Precipitation (inches)		0	
Affected Populations			
Presence Nearby Utility Conduits	Not Present	0	
	Final Score	40	1 Sensitivity Level

Characteristics / Requirements

A reserve pit will be re-dug near the original location. Its dimensions are 80' x 40' x 8' deep. A 10-foot wide bench is provided around the outside. A 16-mil liner with an appropriate sub-liner is required.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y

Other Observations / Comments

Floyd Bartlett
Evaluator

8/24/2009
Date / Time

Application for Permit to Drill Statement of Basis

3/8/2010

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
1911	43013501170000	LOCKED	OW	S	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD		
Well Name	South Monument Butte State N-2-9-16		Unit	GMBU (GRRV)	
Field	MONUMENT BUTTE		Type of Work	DRILL	
Location	NESW 2 9S 16E S 1989 FSL 1981 FWL GPS Coord (UTM) 577755E 4434384N				

Geologic Statement of Basis

Newfield proposes to set 300' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 1,100'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 2. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a major source of useable ground water. However, ground water in the Uinta Formation should be of sufficient quality and quantity for isolated domestic and agricultural use and should be protected. Surface casing should be extended to cover the base of the moderately saline ground water.

Brad Hill
APD Evaluator

9/1/2009
Date / Time

Surface Statement of Basis

The proposed South Monument Butte State M-2-9-16 and the South Monument Butte State N-2-9-16 are proposed oil wells to be directionally drilled from the existing pad of the Monument Butte State 11-2-9-16 water flood injection well. No changes are planned to the existing pad. The reserve pit will be re-dug near the original location in the southeast side of the pad. The wells are on 20-acre spacing.

A field review of the site and the existing pad showed no concerns and should be suitable for drilling and operating the proposed additional wells.

SITLA owns both the surface and the minerals. They were invited to the pre-site visit but did not attend.

The Utah Division of Wildlife Resources was also invited and did not attend.

Floyd Bartlett
Onsite Evaluator

8/24/2009
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 8/18/2009

API NO. ASSIGNED: 43013501170000

WELL NAME: South Monument Butte State N-2-9-16

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: NESW 2 090S 160E

Permit Tech Review:

SURFACE: 1989 FSL 1981 FWL

Engineering Review:

BOTTOM: 2635 FNL 1204 FWL

Geology Review:

COUNTY: DUCHESNE

LATITUDE: 40.05801

LONGITUDE: -110.08835

UTM SURF EASTINGS: 577755.00

NORTHINGS: 4434384.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 3 - State

LEASE NUMBER: ML-21839

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 3 - State

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- PLAT
- Bond: STATE/FEE - B001834
- Potash
- Oil Shale 190-5
- Oil Shale 190-3
- Oil Shale 190-13
- Water Permit: 43-7478
- RDCC Review:
- Fee Surface Agreement
- Intent to Commingle


Commingle Approved

LOCATION AND SITING:

- R649-2-3.
- Unit: GMBU (GRRV)
- R649-3-2. General
- R649-3-3. Exception
- Drilling Unit
- Board Cause No: Cause 213-11
- Effective Date: 11/30/2009
- Siting: 460' fr unit boundary
- R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill
15 - Directional - dmason
25 - Surface Casing - ddoucet
27 - Other - bhill



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: South Monument Butte State N-2-9-16
API Well Number: 43013501170000
Lease Number: ML-21839
Surface Owner: STATE
Approval Date: 3/9/2010

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan – contact Dustin Doucet
- Significant plug back of the well – contact Dustin Doucet
- Plug and abandonment of the well – contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program – contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well – contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):


- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:



Gil Hunt
Associate Director, Oil & Gas

Spud
BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross Rig #26
Submitted By Mitch Benson Phone Number 823-5885
Well Name/Number South Monument Butte^{STB} N-2-9-16
Qtr/Qtr NE/SW Section 2 Township 9S Range 16E
Lease Serial Number ML-21839
API Number 43-013-50117

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 3/13/10 9:00 AM PM

Casing – Please report time casing run starts, not cementing times.

- Surface Casing
- Intermediate Casing
- Production Casing
- Liner
- Other

Date/Time 3/14/10 9:00 AM PM

BOPE

- Initial BOPE test at surface casing point
- BOPE test at intermediate casing point
- 30 day BOPE test
- Other

Date/Time _____ AM PM

Remarks _____

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM -FORM 6


OPERATOR: NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630
MYTON, UT 84052

OPERATOR ACCT. NO. N2695

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	17550	4304750817	HANCOCK 1-26-4-1	NENE	26	4S	1W	UINTAH	3/16/2010	3/22/10
WELL 1 COMMENTS: GRRV											
B	99999	17400	✓ 4301350117 4304750117	S MON BUTTE N-2-9-16	NESW	2	9S	16E	DUCHESNE	3/13/2010	3/22/10
GRRV BHL = SWNW											
B	99999	17400	✓ 4301350116	S MON BUTTE M-2-9-16	NESW	2	9S	16E	DUCHESNE	3/16/2010	3/22/10
GRRV BHL = SENW											
B	99999	17400	✓ 4301334144 4304734144	SUNDANCE FEDERAL P-11-9-17	SWSW	11	9S	17E	Duchesne UINTAH	3/16/2010	3/22/10
GRRV BHL = SWSW											
A	99999		4301334269	UTE TRIBAL 14-25-4-3	SESW	25 24	4S	3W	DUCHESNE	3/11/2010	
WELL 5 COMMENTS: Duplicate - original processed 1/28/10											
A	99999	17551	4301334210	UTE TRIBAL 4-30-4-2	NWNW	30	4S	2W	DUCHESNE	3/12/2010	3/22/10
WELL 5 COMMENTS: GRRV											

ACTION CODES (See instructions on back of form)
A - new entity for new well (single well only)
B - well to existing entity (group or unit well)
C - from one existing entity to another existing entity
D - well from one existing entity to a new entity
E - other (explain in comments section)

RECEIVED
MAR 22 2010

Signature: 
Jentri Park
Production Clerk
03/09/10
Date

NOTE: Use COMMENT section to explain why each Action Code was selected.

STATE OF UTAH
 DEPARTMENT OF NATURAL RESOURCES
 DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
 UTAH STATE ML-21839

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
 GMBU

8. WELL NAME and NUMBER:
 SO MON BUTTE N-2-9-16

9. API NUMBER:
 4301350117

10. FIELD AND POOL, OR WILDCAT:
 MONUMENT BUTTE

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, recenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR:
 NEWFIELD PRODUCTION COMPANY

3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 PHONE NUMBER 435.646.3721

4. LOCATION OF WELL:
 FOOTAGES AT SURFACE: COUNTY: DUCHESNE
 STATE: UT
 OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: , 2, T9S, R16E

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 03/16/2010	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Spud Notice
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 On 3/13/10 MIRU Ross # 26. Spud well @ 9:00 AM. Drill 1135' of 12 1/4" hole with air mist. TIH W/ 26 Jt's 8 5/8" J-55 24# casing. Set @ 1133.24' KB. On 3/16/10 cement with 558 sks of class "G" w/ 2% CaCL2 + 1/4# per sk Cello Flake mixed @ 15.8 ppg with 1.17 cf/sk yield. Returned 30 bbls cement to pit. WOC.

NAME (PLEASE PRINT) Mitch Benson TITLE Drilling Foreman

SIGNATURE *Mitch Benson* DATE 03/16/2010

(This space for State use only)

RECEIVED
MAR 29 2010
 DIV. OF OIL, GAS & MINING

STATE OF UTAH
 DEPARTMENT OF NATURAL RESOURCES
 DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
 UTAH STATE ML-21839

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
 GMBU

1. TYPE OF WELL: OIL WELL GAS WELL OTHER

8. WELL NAME and NUMBER:
 SO MON BUTTE N-2-9-16

2. NAME OF OPERATOR:
 NEWFIELD PRODUCTION COMPANY

9. API NUMBER:
 4301350117

3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 PHONE NUMBER 435.646.3721

10. FIELD AND POOL, OR WILDCAT:
 GREATER MB UNIT


4. LOCATION OF WELL:
 FOOTAGES AT SURFACE:
 1989 FSL 1991 FWL
 OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: , 2, T9S, R16E NESW

COUNTY: DUCHESNE
 STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 05/11/2010	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 The above subject well was completed on 05-11-10, attached is a daily completion status report.

NAME (PLEASE PRINT) Lucy Chavez-Naupoto TITLE Administrative Assistant
 SIGNATURE  DATE 05/13/2010

(This space for State use only)

RECEIVED
MAY 18 2010
 DIV. OF OIL, GAS & MINING

Daily Activity Report

Format For Sundry

SO MON BUTTE N-2-9-16

3/1/2010 To 7/30/2010

4/8/2010 Day: 1

Completion

Rigless on 4/8/2010 - Run CSG CBL & Perforate 1 st stage - Install 5m frac head. NU 6" 5K Cameron BOP. RU hot oil truck & pressure test casing, blind rams, frac head, & casing valves to 4500 psi w/ 2 bw. RU The Perforators LLC WLT w/ mast & run CBL under pressure. WLTD @ 6276' w/ cement top @ 98'. Perforate stage #1, CP 5 sds (6136'-44') w/ 3 1/8" Port plug guns (11 gram .36" EH 16.82" pen) w/ spf for a total of 24 shots. RD The Peforators LLC WLT.

Daily Cost: \$0

Cumulative Cost: \$12,222

4/13/2010 Day: 2

Completion

Rigless on 4/13/2010 - Frac well. Flow well to pit for immediate flowback. Well flowed for 12 hrs & turned to oil. SWIFN. 1168 BWTR. - RU BJ Services. Frac CP5 sds as shown in stimulation report. 569 BWTR. - RU The Perforators wireline. Set CBP & perf GB6 sds as shown in perforation report. RU BJ Services. Frac GB6 sds as shown in stimulation report. RD BJ & wireline. Open well to pit for immediate flowback at approx. 3 bpm. Well flowed for 12 hrs & turned to oil. Recovered 1700 bbls. SWIFN. 1168 BWTR. - RU The Perforators wireline. Set CBP & perf D1 sds as shown in perforation report. RU BJ Services. Frac D1 sds as shown in stimulation report. 2592 BWTR. - RU The Perforators wireline. Set CBP & perf C sds as shown in perforation report. RU BJ Services. Frac C sds as shown in stimulation report. 2316 BWTR. - RU The Perforators wireline. Set CBP & perf C sds as shown in perforation report. RU BJ Services. Frac C sds as shown in stimulation report. 2316 BWTR. - RU The Perforators wireline. Set CBP & perf B2/B1 sds as shown in perforation report. RU BJ Services. Frac B2/B1 sds as shown in stimulation report. 2022 BWTR. - RU The Perforators wireline. Set CBP & perf A3 sds as shown in perforation report. RU BJ Services. Frac A3 sds as shown in stimulation report. 1392 BWTR. - RU The Perforators wireline. Set solid composite plug & tighten csg. Valve to stop leak. Perf CP1 sds as shown in perforation report. RU BJ Services. Frac CP1 sds as shown in stimulation report. 981 BWTR.

Daily Cost: \$0

Cumulative Cost: \$128,034

4/15/2010 Day: 3

Completion

WWS #1 on 4/15/2010 - MIRU Western #1. ND Cameron BOP. NU Schaeffer BOP. SWIFN. - RU The Perforators wireline. Set kill plug @ 4320'. Bleed off well. MIRU Western #1. ND Cameron BOP & 5m frac head. NU 3m production head & Schaeffer BOP. SWIFN. 1168 BWTR.

Daily Cost: \$0

Cumulative Cost: \$139,366

4/16/2010 Day: 4

Completion

WWS #1 on 4/16/2010 - RIH w/ tbg. DU CBPs. - RIH w/ 4 3/4" chomp bit, bit sub & new 2 7/8" tbg. from pipe racks (tallying & drifting). Tag CBP @ 4320'. RU powerswivel & pump. DU CBP in 45 min. Cont. RIH w/ tbg. Tag CBP @ 4500'. DU CBP in 37 min. Cont. RIH w/ tbg. Tag CBP @ 5020'. DU CBP in 28 min. Circulate well clean. SWIFN. 1048 BWTR.

Daily Cost: \$0

Cumulative Cost: \$178,290

4/17/2010 Day: 5

Completion

WWS #1 on 4/17/2010 - DU CBPs. C/O to PBD @ 6332'. Flow well. Recoverd total of 380 bbls water today. SWIFN. 668 BWTR. - Csg. @ 1550 psi, tbg. @ 1550 psi. Bleed off well. Circulate well. Cont. RIH w/ tbg. Tag CBP @ 5160'. DU CBP in 30 min. Cont. RIH w/ tbg. Tag CBP @ 5330'. DU CBP in 23 min. Cont. RIH w/ tbg. Tag fill @ 5535'. C/O to CBP @ 5550'. DU CBP in 15 min. Cont. RIH w/ tbg. Tag fill @ 5714'. C/O to CBP @ 5940'. DU CBP in 22 min. Cont. RIH w/ tbg. Tag fill @ 6217'. C/O to PBD @ 6332'. Circulate well clean. RD powerswivel. Pull up to 6280'. Flow tbg. to tank for 1 hr. Recovered 80 bbls. Recovered total of 380 bbls water today. SWIFN. 668 BWTR.

Daily Cost: \$0

Cumulative Cost: \$184,965

4/19/2010 Day: 6

Completion

WWS #1 on 4/19/2010 - Attempt to kill well. - Csg. @ 1250 psi, tbg. @ 1000 psi. Bleed off well. Circulate well to kill well. POOH w/ 80 jts tbg. Well started to flow. Attempt to kill well. RIH w/ 80 jts 2 7/8" tbg. Circulate well to kill well w/ no success. SWIFN. 600 BWTR.

Daily Cost: \$0

Cumulative Cost: \$193,490

4/20/2010 Day: 7

Completion

WWS #1 on 4/20/2010 - Attempt to kill well w/ no success. - 1200 psi on well. Attempt to kill well w/ 10# brine w/ no success. RU well to flow. RD.

Daily Cost: \$0

Cumulative Cost: \$197,008

5/8/2010 Day: 8

Completion

WWS #5 on 5/8/2010 - Attempt to kill well. - MIRU Western #5. Csg. @ 700 psi, tbg. @ 120 psi. Attempt to kill well w/ 340 bbls 10# brine w/ no success. SWIFN.

Daily Cost: \$0

Cumulative Cost: \$205,261

5/10/2010 Day: 9

Completion

WWS #5 on 5/10/2010 - Round trip tbg. ND BOP. Set TAC @ 6103' w/ 18,000# tension. NU wellhead. RIH w/ partial rod string. - Csg. @ 450 psi, tbg. @ 500 psi. Kill well w/ 180 bbls 10# brine. RIH w/ tbg. Tag fill @ 6329'. Circulate well w/ 250 bbls 10# brine. POOH w/ tbg. LD BHA. RIH w/ 2 7/8" notched collar, 2 jts 2 7/8" tbg., PSN, 1 jt 2 7/8" tbg., 5 1/2" TAC & 194 jts 2 7/8" tbg. ND BOP. Set TAC @ 6103' w/ 18,000# tension. NU wellhead. X-over for rods. Flush tbg. w/ 60 bbls water. RIH w/ Central Hydraulic 2 1/2" x 1 3/4" x 20' x 24' RHAC rod pump, 4- 1 1/2" weight bars, 160- 7/8" & 1 1/2" x 30' polished rod pkg. SWIFN.

Daily Cost: \$0

Cumulative Cost: \$210,724

5/11/2010 Day: 10

Completion

WWS #5 on 5/11/2010 - - Cont. RIH w/ rods. Seat pump. Stroke test to 800 psi. Good pump action. RU pumping unit. Hang off rods. **Finalized**

Daily Cost: \$0

Cumulative Cost: \$246,980

Pertinent Files: Go to File List

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
ML-21839

1a. Type of Well Oil Well Gas Well Dry Other
b. Type of Completion: New Well Work Over Deepen Plug Back Diff. Resrv.,
Other: _____

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.
GMBU

2. Name of Operator
NEWFIELD EXPLORATION COMPANY

8. Lease Name and Well No.
SO MONUMENT BUTTE STATE N-2-9-16

3. Address
1401 17TH ST. SUITE 1000 DENVER, CO 80202

3a. Phone No. (include area code)
(435)646-3721

9. API Well No.
43-013-50117

4. Location of Well (Report location clearly and in accordance with Federal requirements)*
At surface 1989' FSL & 1981' FWL (NE/SW) SEC. 2, T9S, R16E (ML-21839)
At top prod. interval reported below 2513' FSL & 1335' FWL (NE/SW) SEC. 2, T9S, R16E (ML-21839)
At total depth 2430' FNL & 969' FWL (SW/NW) SEC. 2, T9S, R16E (ML-21839)

10. Field and Pool or Exploratory
MONUMENT BUTTE

11. Sec., T., R., M., on Block and
Survey or Area
SEC. 2, T9S, R16E

12. County or Parish
DUCHESNE

13. State
UT

14. Date Spudded
03/13/2010

15. Date T.D. Reached
03/27/2010

16. Date Completed 05/10/2010
 D & A Ready to Prod.

17. Elevations (DF, RKB, RT, GL)*
5519' GL 5531' KB

18. Total Depth: MD 6378'
TVD 6187'

19. Plug Back T.D.: MD 6332'
TVD 6142'

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
DUAL IND GRD, SP, COMP. DENSITY, COMP. NEUTRON, GR, CALIPER, CMT BOND

22. Was well cored? No Yes (Submit analysis)
Was DST run? No Yes (Submit report)
Directional Survey? No Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24#	0	1133'		558 CLASS G			
7-7/8"	5-1/2" J-55	15.5#	0	6378'		250 PRIMLITE		98'	
						425 50/50 POZ			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT@ 6203'	TA @ 6104'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Green River			6136-6144' CP5	.36"	3	24
B) Green River			5842-5852' CP1	.36"	3	30
C) Green River			5470-5490' A3	.36"	3	27
D) Green River			5200-5276' B1 B2	.36"	3	33

26. Perforation Record 4440

Depth Interval	Amount and Type of Material
6136-6144'	Frac w/ 24779#'s 20/40 sand in 216 bbls of Lightning 17 fluid.
5842-5852'	Frac w/ 35124#'s 20/40 sand in 234 bbls of Lightning 17 fluid.
5470-5490'	Frac w/ 38249#'s 20/40 sand in 246 bbls of Lightning 17 fluid.
5200-5276'	Frac w/ 72726#'s 20/40 sand in 466 bbls of Lightning 17 fluid.

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
4-15-10	4-30-10	24	→	167	0	141			2-1/2" x 1-3/4" x 20' x 24' RHAC Pump
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

RECEIVED

JUN 14 2010

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

USED FOR FUEL

30. Summary of Porous Zones (Include Aquifers):
 Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers
 GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MRK GARDEN GULCH 1	3857' 4075'
				GARDEN GULCH 2 POINT 3	4197' 4465'
				X MRKR Y MRKR	4729' 4767'
				DOUGALS CREEK MRK BI CARBONATE MRK	4898' 5150'
				B LIMESTON MRK CASTLE PEAK	5289' 5782'
				BASAL CARBONATE	6233'


32. Additional remarks (include plugging procedure):

Stage 5: Green River Formation (C) 5112-5122', .36" 3/24 Frac w/ 15086#'s of 20/40 sand in 135 bbls of Lightning 17 fluid
 Stage 6: Green River Formation (D1) 4942-4952', .36" 3/30 Frac w/ 19788#'s of 20/40 sand in 169 bbls of Lightning 17 fluid
 Stage 7: Green River Formation (GB6) 4448-4454', .36" 3/18 Frac w/ 15201#'s of 20/40 sand in 136 bbls of Lightning 17 fluid

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- Electrical/Mechanical Logs (1 full set req'd.)
 Geologic Report
 DST Report
 Directional Survey
 Sundry Notice for plugging and cement verification
 Core Analysis
 Other: Drilling Daily Activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Lucy Chavez-Naupoto Title Administrative Assistant
 Signature  Date 06/04/2010

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

NEWFIELD



NEWFIELD EXPLORATION

USGS Myton SW (UT)

SECTION 2 9S 16E

N-2-9-16

Wellbore #1

Survey: Survey #1

Standard Survey Report

13 April, 2010



HATHAWAYBURNHAM

Survey Report

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 2 9S 16E
 Well: N-2-9-16
 Wellbore: Wellbore #1
 Design: Wellbore #1

Local Co-ordinate Reference: Well N-2-9-16
 TVD Reference: N-2-9-16 @ 5531.0ft (EST KB)
 MD Reference: N-2-9-16 @ 5531.0ft (EST KB)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone	Using geodetic scale factor	

Site	SECTION 2 9S 16E, SEC 2 9S 16E				
Site Position:		Northing:	7,193,600.00ft	Latitude:	40° 3' 34.952 N
From:	Map	Easting:	2,036,100.00ft	Longitude:	110° 5' 10.480 W
Position Uncertainty:	0.0 ft	Slot Radius:	"	Grid Convergence:	0.91 °

Well	N-2-9-16, SHL LAT: 40 03 29.09, LONG: -110 05 20.36					
Well Position	+N/-S	0.0 ft	Northing:	7,192,994.76 ft	Latitude:	40° 3' 29.090 N
	+E/-W	0.0 ft	Easting:	2,035,341.30 ft	Longitude:	110° 5' 20.360 W
Position Uncertainty		0.0 ft	Wellhead Elevation:	ft	Ground Level:	0.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	7/15/2009	11.56	65.86	52,493

Design	Wellbore #1				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.0	0.0	0.0	309.65	

Survey Program	Date 4/13/2010				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
1,172.0	6,378.0	Survey #1 (Wellbore #1)	MWD	MWD - Standard	

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
1,172.0	0.11	15.42	1,172.0	1.1	0.3	0.5	0.01	0.01	0.00
1,217.0	0.26	38.37	1,217.0	1.2	0.4	0.5	0.37	0.33	51.00
1,263.0	0.81	332.66	1,263.0	1.6	0.3	0.8	1.61	1.20	-142.85
1,308.0	1.65	307.93	1,308.0	2.3	-0.4	1.7	2.17	1.87	-54.96
1,353.0	2.31	304.79	1,353.0	3.2	-1.6	3.3	1.49	1.47	-6.98
1,399.0	3.23	305.96	1,398.9	4.5	-3.4	5.5	2.00	2.00	2.54
1,444.0	3.60	308.21	1,443.8	6.1	-5.6	8.2	0.87	0.82	5.00
1,489.0	4.17	306.63	1,488.7	7.9	-8.0	11.2	1.29	1.27	-3.51
1,534.0	4.97	303.18	1,533.6	10.0	-10.9	14.8	1.88	1.78	-7.67
1,580.0	5.84	308.19	1,579.4	12.5	-14.4	19.1	2.15	1.89	10.89
1,625.0	6.86	310.87	1,624.1	15.7	-18.3	24.1	2.36	2.27	5.96
1,670.0	7.14	309.53	1,668.8	19.2	-22.5	29.6	0.72	0.62	-2.98



HATHAWAYBURNHAM

Survey Report

Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 2 9S 16E
Well: N-2-9-16
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well N-2-9-16
TVD Reference: N-2-9-16 @ 5531.0ft (EST KB)
MD Reference: N-2-9-16 @ 5531.0ft (EST KB)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
1,716.0	7.87	306.30	1,714.4	22.9	-27.2	35.6	1.83	1.59	-7.02
1,761.0	8.79	306.26	1,758.9	26.8	-32.5	42.1	2.04	2.04	-0.09
1,806.0	9.05	307.51	1,803.3	31.0	-38.0	49.0	0.72	0.58	2.78
1,851.0	9.62	306.37	1,847.8	35.3	-43.9	56.3	1.33	1.27	-2.53
1,897.0	10.02	305.86	1,893.1	40.0	-50.2	64.2	0.89	0.87	-1.11
1,942.0	10.48	305.44	1,937.4	44.6	-56.7	72.2	1.04	1.02	-0.93
1,987.0	10.84	306.83	1,981.6	49.5	-63.4	80.5	0.98	0.80	3.09
2,033.0	11.32	306.81	2,026.7	54.8	-70.5	89.3	1.04	1.04	-0.04
2,078.0	11.60	306.70	2,070.8	60.2	-77.7	98.2	0.62	0.62	-0.24
2,123.0	11.90	311.60	2,114.9	66.0	-84.8	107.4	2.31	0.67	10.89
2,169.0	12.70	315.00	2,159.8	72.7	-91.9	117.2	2.35	1.74	7.39
2,214.0	13.30	313.60	2,203.7	79.8	-99.2	127.2	1.51	1.33	-3.11
2,259.0	13.50	309.20	2,247.5	86.7	-107.0	137.7	2.31	0.44	-9.78
2,304.0	14.20	310.20	2,291.1	93.5	-115.3	148.4	1.64	1.56	2.22
2,350.0	14.40	308.10	2,335.7	100.7	-124.1	159.8	1.21	0.43	-4.57
2,395.0	14.50	307.80	2,379.3	107.6	-132.9	171.0	0.28	0.22	-0.67
2,440.0	14.20	309.10	2,422.9	114.5	-141.7	182.2	0.98	-0.67	2.89
2,486.0	14.50	309.20	2,467.5	121.7	-150.5	193.6	0.65	0.65	0.22
2,531.0	15.50	309.30	2,510.9	129.1	-159.5	205.2	2.22	2.22	0.22
2,576.0	15.70	309.50	2,554.3	136.8	-168.9	217.3	0.46	0.44	0.44
2,622.0	16.00	310.00	2,598.5	144.8	-178.5	229.9	0.72	0.65	1.09
2,667.0	16.80	312.50	2,641.7	153.2	-188.1	242.6	2.37	1.78	5.56
2,757.0	19.20	312.80	2,727.3	172.1	-208.5	270.3	2.67	2.67	0.33
2,848.0	21.90	313.80	2,812.5	194.0	-231.8	302.2	2.99	2.97	1.10
2,939.0	23.80	314.80	2,896.3	218.7	-257.0	337.4	2.13	2.09	1.10
3,029.0	25.60	314.60	2,978.1	245.1	-283.8	374.9	2.00	2.00	-0.22
3,120.0	24.70	309.90	3,060.5	271.1	-312.4	413.5	2.41	-0.99	-5.16
3,211.0	23.30	306.40	3,143.6	294.0	-341.4	450.5	2.19	-1.54	-3.85
3,301.0	21.80	303.00	3,226.7	313.7	-369.8	484.9	2.21	-1.67	-3.78
3,392.0	21.70	304.30	3,311.3	332.3	-397.8	518.4	0.54	-0.11	1.43
3,483.0	20.30	302.90	3,396.2	350.4	-425.0	550.8	1.63	-1.54	-1.54
3,573.0	19.50	304.10	3,480.8	367.3	-450.5	581.3	1.00	-0.89	1.33
3,664.0	18.40	307.50	3,566.9	384.6	-474.5	610.7	1.71	-1.21	3.74
3,754.0	17.40	307.60	3,652.5	401.4	-496.4	638.4	1.11	-1.11	0.11
3,845.0	15.80	308.08	3,739.7	417.4	-517.0	664.4	1.76	-1.76	0.53
3,936.0	14.77	309.05	3,827.5	432.3	-535.7	688.4	1.17	-1.13	1.07
4,026.0	15.67	309.20	3,914.4	447.2	-554.1	712.0	1.00	1.00	0.17
4,117.0	15.89	308.85	4,001.9	462.8	-573.3	736.7	0.26	0.24	-0.38
4,207.0	16.17	313.24	4,088.4	479.1	-592.0	761.6	1.38	0.31	4.88
4,298.0	15.21	308.50	4,176.1	495.2	-610.6	786.1	1.76	-1.05	-5.21
4,389.0	14.19	308.08	4,264.1	509.5	-628.7	809.2	1.13	-1.12	-0.46
4,479.0	14.63	310.94	4,351.2	523.8	-646.0	831.6	0.93	0.49	3.18
4,570.0	14.40	314.10	4,439.3	539.2	-662.8	854.4	0.91	-0.25	3.47
4,660.0	13.60	311.70	4,526.7	554.0	-678.7	876.1	1.10	-0.89	-2.67
4,751.0	15.10	309.70	4,614.8	568.7	-695.8	898.7	1.74	1.65	-2.20
4,841.0	15.36	311.84	4,701.7	584.1	-713.7	922.3	0.69	0.29	2.38
4,932.0	15.00	313.60	4,789.5	600.3	-731.3	946.1	0.64	-0.40	1.93
5,022.0	15.60	309.50	4,876.3	616.0	-749.0	969.8	1.37	0.67	-4.56
5,113.0	15.60	305.60	4,964.0	630.9	-768.4	994.2	1.15	0.00	-4.29
5,204.0	14.20	305.20	5,051.9	644.5	-787.5	1,017.6	1.54	-1.54	-0.44
5,294.0	15.60	311.10	5,138.9	658.8	-805.6	1,040.7	2.29	1.56	6.56
5,385.0	15.80	306.70	5,226.5	674.3	-824.8	1,065.3	1.33	0.22	-4.84
5,475.0	15.80	309.90	5,313.1	689.5	-844.0	1,089.8	0.97	0.00	3.56
5,566.0	14.70	315.30	5,400.9	705.6	-861.6	1,113.7	1.97	-1.21	5.93



HATHAWAYBURNHAM

Survey Report

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 2 9S 16E
 Well: N-2-9-16
 Wellbore: Wellbore #1
 Design: Wellbore #1

Local Co-ordinate Reference: Well N-2-9-16
 TVD Reference: N-2-9-16 @ 5531.0ft (EST KB)
 MD Reference: N-2-9-16 @ 5531.0ft (EST KB)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,657.0	13.40	314.70	5,489.2	721.2	-877.2	1,135.7	1.44	-1.43	-0.66
5,747.0	14.10	314.90	5,576.6	736.3	-892.4	1,157.0	0.78	0.78	0.22
5,838.0	13.80	315.70	5,664.9	751.9	-907.9	1,178.8	0.39	-0.33	0.88
5,929.0	15.20	316.10	5,753.0	768.3	-923.7	1,201.4	1.54	1.54	0.44
6,019.0	15.20	313.00	5,839.8	784.8	-940.5	1,224.9	0.90	0.00	-3.44
6,110.0	15.14	310.12	5,927.7	800.6	-958.3	1,248.7	0.83	-0.07	-3.16
6,201.0	16.08	308.48	6,015.3	816.1	-977.3	1,273.2	1.14	1.03	-1.80
6,291.0	13.84	306.76	6,102.3	830.3	-995.7	1,296.4	2.54	-2.49	-1.91
6,328.0	12.50	303.33	6,138.3	835.2	-1,002.6	1,304.8	4.19	-3.62	-9.27
6,378.0	12.50	303.33	6,187.1	841.1	-1,011.6	1,315.6	0.00	0.00	0.00

Checked By: _____ Approved By: _____ Date: _____





Project: USGS Myton SW (UT)
Site: SECTION 2 9S 16E
Well: N-2-9-16
Wellbore: Wellbore #1
SURVEY: Wellbore #1

FINAL SURVEY REPORT



Azimuths to True North
Magnetic North: 11.56°

Magnetic Field
Strength: 52492.8snT
Dip Angle: 65.86°
Date: 7/15/2009
Model: IGRF200510



Survey: Survey #1 (N-2-9-16/Wellbore #1)
Date: 10:40, April 13 2010
THIS SURVEY IS SUPPORTED BY ACTUAL FIELD DATA.

Daily Activity Report

Format For Sundry

SO MON BUTTE N-2-9-16**1/1/2010 To 5/30/2010****SO MON BUTTE N-2-9-16****Waiting on Cement****Date:** 3/16/2010

Ross #26 at 1135. Days Since Spud - On 3/13/10 Ross Rig #26 spud SMB N-2-9-16, drilled 1135' of 12 1/4" hole, and ran 26 jts 8 5/8" - Returned 30 bbls to pit. - 8 5/8" casing w/ 558 sks Class "G" + 2% CaCl₂ + 0.25#/sk Cello Flake at 15.8 ppg w/ 1.17 yield. - casing (guide shoe, shoe jt, baffle plate, 25 jt) set @ 1133.2' KB. On 3/16/10 BJ Services cemented

Daily Cost: \$0**Cumulative Cost:** \$82,144**SO MON BUTTE N-2-9-16****Waiting on Cement****Date:** 3/22/2010

Capstar #328 at 1135. 0 Days Since Spud - Rig down prepare to move to the SMB N-2-9-16

Daily Cost: \$0**Cumulative Cost:** \$82,494**SO MON BUTTE N-2-9-16****Drill 7 7/8" hole with fresh water****Date:** 3/24/2010

Capstar #328 at 2128. 1 Days Since Spud - No H₂S or flow reported in last 24 hours - Pick up bit,m.m,BHA scribe directional tools and trip in the hole. - Test,kelly,safety valve,rams,choke to 2000#,Hydrill to 1500# for 10 min.Casing 1500# for 30 minutes - Move rig , Set equipment, Nipple up, Accept rig @ 17:00 3-23-10 - Drill 7 7/8" hole F/1080' to 2128' w/ 15K WOB,TRPM-180,GPM-400.,Avg ROP-140 ft/hr

Daily Cost: \$0**Cumulative Cost:** \$131,600**SO MON BUTTE N-2-9-16****Drill 7 7/8" hole with fresh water****Date:** 3/25/2010

Capstar #328 at 4575. 2 Days Since Spud - Rig serv - Drill 7/8" hole f/3080' to 4575' WOB= 18/20 RPMS= 184 GPM= 409 ROP= 87.9' Pr hr - Drill 7/8" hole f/3080' to 4575' WOB= 18/20 RPMS= 184 GPM= 409 ROP= 87.9' Pr hr - No H₂S in the last 24 hrs - Drill 7/8" hole f/ 2173' to 3080 WOB= 18/20 RPMS= 184 GPM= 409 ROP= 139.5' Pr hr

Daily Cost: \$0**Cumulative Cost:** \$154,091**SO MON BUTTE N-2-9-16****Drill 7 7/8" hole with fresh water****Date:** 3/26/2010

Capstar #328 at 6075. 3 Days Since Spud - Drill 7/8" hole f/5118' to 6075' WOB 18/20 RPMS 184, GPM=409 ROP= 58' Pr hr - Drill 7/8" hole f/4575' to 5118' WOB 18/20 RPMS 184, GPM=409 ROP= 77.5' Pr hr - Rig serv - No H₂S in the last 24 hrs

Daily Cost: \$0**Cumulative Cost:** \$173,370**SO MON BUTTE N-2-9-16****Wait on Completion****Date:** 3/27/2010

Capstar #328 at 6378. 4 Days Since Spud - pump pill - Circ for lay down -

.05#SF+.3SMS+FP-6L Displ w/ 151 bbls - Drill 77/8" hole f/ 6075' to 6378' WOB= 18/20
RPMS= 184 GPM= 409 ROP= 86.5' Pr hr - LDDP & BHA - Hold safety mty & RU Phoenix
Survey Inc & Log w/Dual Guard Gamma Ray & Compensated Density - Compensated Neutron
Gamma Ray loggers depth= 6364' - RU & get ready to run casing - Run 146 jts of 5.5 15.5#
J55 LT&C Shoe @ 6378.41' Float collar @ 6331.52' 1jt will be transferd to - the next well
South Monumont Butte State M-2-9-16 - Circ for cmt job - RU BJ & cement 250 sks of lead
Mixed @ 11 ppg & 3.53 yeild PLII+3%KCl+5#CSE+0.5%EC-1+.25#CF+2# -
KCL+.5SMS+FP+SF & 425 sks Tail mixed @ 14.4 ppg & 1.24 yeild 50:50:2+3%KCL+0.5%EC-
1+.25#CF+

Daily Cost: \$0

Cumulative Cost: \$281,705

SO MON BUTTE N-2-9-16

Wait on Completion

Date: 3/28/2010

Capstar #328 at 6378. 5 Days Since Spud - Clean mud tanks - ND BOP's & set casing slips
with 78,000# tension - Release rig 328 at 1130 AM 3/27/10 **Finalized**

Daily Cost: \$0

Cumulative Cost: \$312,435

Pertinent Files: Go to File List



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

November 28, 2016

CERTIFIED MAIL NO.: 7015 0640 0003 5276 0440

Mr. Kirby Carroll
Newfield Production Company
1001 17th Street, STE 2000
Denver, CO 80202

43 013 50117
S Mon Butte St N-2-9-16
2 9S 16E

Subject: Extended Shut-in and Temporary Abandoned Well Requirements for Fee or State Leases

Dear Mr. Carroll:

As of August 2016, Newfield has thirty-two (32) State and Fee Lease Wells (see attachment A) that are currently in non-compliance with the requirements for extended shut-in or temporarily abandoned (SI/TA) status.

Wells SI/TA beyond twelve (12) consecutive months requires filing a Sundry Notice (R649-3-36-1). Wells with five (5) years non-activity or non-productivity shall be plugged, unless the Division grants approval for extended shut-in time upon a showing of good cause by the operator (649-3-36-1.3.3). For extended SI/TA consideration the operator shall provide the Utah Division of Oil, Gas and Mining with the following:

1. Reasons for SI/TA of the well (R649-3-36-1.1).
2. The length of time the well is expected to be SI/TA (R649-3-36-1.2), and
3. An explanation and supporting data if necessary, for showing the well has integrity, meaning that the casing, cement, equipment condition, static fluid level, pressure, existence or absence of Underground Sources of Drinking Water and other factors do not make the well a risk to public health and safety or the environment (R649-3-36-1.3).

Please note that the Divisions preferred method for showing well integrity is by MIT.



Page 2
Newfield Production Company
November 28, 2016

Submitting the information suggested below may help show well integrity and may help qualify your well for extended SI/TA. **Note: As of July 1, 2003, wells in violation of the SI/TA rule R649-3-36 may be subject to full cost bonding (R649-3-1-4.2, 4.3).**

1. Wellbore diagram, and
2. Copy of recent casing pressure test, and
3. Current pressures on the wellbore (tubing pressure, casing pressure, and casing/casing annuli pressure) showing wellbore has integrity, and
4. Fluid level in the wellbore, and
5. An explanation of how the submitted information proves integrity.

All Submittals should be sent via ePermit

If the required information is not received within 30 days of the date of this notice, further actions may be initiated. If you have any questions concerning this matter, please contact me at (801) 538-5281.

Sincerely,



Dustin K. Doucet
Petroleum Engineer

DKD/DD/js

cc: Compliance File
Well File
LaVonne Garrison, SITLA

N:\O&G Reviewed Docs\ChronFile\PetroleumEngineer\SITLA

ATTACHMENT A

	Well Name	API	LEASE	Years.Months Inactive
1	GMBU 2-16-9-18H	43-047-52013	ML-48378	4.4
2	Gulf State 36-13	43-047-31345	ML-22057	9.2
3	Moon 3-20-4-2	43-013-50007	Fee	3.5
4	S Mon Butte ST P-2-9-16	43-013-50118	ML-21839	3.6
5	State 3-16-9-18	43-047-35813	ML-48378	3.5
6	Wells Draw ST 7-36	43-013-30934	ML-21835	3.4
7	Prewitt 10-24	43-013-31865	Fee	3.2
8	W Draw ST N-32-8-16	43-013-34146	ML-45555	2.4
9	Wells Draw 2-32-8-16	43-013-32220	ML-21836	2.3
10	GMBU N-2-9-15	43-013-50910	ML-43538	2.2
11	GMBU M-2-9-15	43-013-50909	ML-43538	2.1
12	Moon 1-29-4-2	43-013-50006	Fee	2.0
13	Moon 1-20-4-2	43-013-50008	Fee	2.0
14	State 1-36-8-15	43-013-34234	ML-21835	2.5
15	Ashley ST 6-2-9-15	43-013-32584	ML-43538	1.10
16	Allen Trust 2-24	43-013-31944	Fee	1.9
17	Lamb 4-34-4-1E	43-047-40272	Fee	1.5
18	Wells Draw 4-32-8-16	43-013-32222	ML-21836	1.8
19	Greater Mon Butte T-36-8-16	43-013-50211	ML-22061	1.8
20	Williams #14-8-4-2	43-013-50617	Fee	1.8
21	Hancock 11-21-4-1	43-013-33242	Fee	1.5
22	Malnar 9-19-4-1	43-013-33913	Fee	1.2
23	Hancock 16-20-4-1	43-013-33914	Fee	1.0
24	State 12-36-8-15	43-013-34224	ML-21835	2.1
25	State 4-36-8-15	43-013-34231	ML-21835	1.4
26	Roberts 4-19-4-1	43-013-50072	Fee	1.1
27	Mon Butte East K-36-8-16	43-013-50112	ML-22061	1.1
→ 28	S Mon Butte ST N-2-9-16	43-013-50117	ML-21839	1.4
29	Wilcken 16-23-4-2	43-013-50304	Fee	1.0
30	Hancock 12-7-4-1W	43-013-50422	Fee	1.3
31	State 1-16-9-18	43-047-35811	ML-48378	1.6
32	Lamb 1-34-4-1E	43-047-40275	Fee	1.1