

| STATE OF UTAH<br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS AND MINING   |                  |                |  |                 | FORM 3<br>AMENDED REPORT <input type="checkbox"/>   |                 |
|---|------------------|----------------|--|-----------------|---|-----------------|
| <b>APPLICATION FOR PERMIT TO DRILL</b>  |                  |                |  |                 | <b>1. WELL NAME and NUMBER</b><br>Ute Tribal 5-22-4-3W  |                 |
| <b>2. TYPE OF WORK</b><br>DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/> |                  |                |  |                 | <b>3. FIELD OR WILDCAT</b><br>WILDCAT   |                 |
| <b>4. TYPE OF WELL</b><br>Oil Well Coalbed Methane Well: NO   |                  |                |  |                 | <b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b>  |                 |
| <b>6. NAME OF OPERATOR</b><br>NEWFIELD PRODUCTION COMPANY   |                  |                |  |                 | <b>7. OPERATOR PHONE</b><br>435 646-4825  |                 |
| <b>8. ADDRESS OF OPERATOR</b><br>Rt 3 Box 3630 , Myton, UT, 84052   |                  |                |  |                 | <b>9. OPERATOR E-MAIL</b><br>mcrozier@newfield.com  |                 |
| <b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b><br>1420H626154  |                  |                | <b>11. MINERAL OWNERSHIP</b><br>FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>    |                 | <b>12. SURFACE OWNERSHIP</b><br>FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/> |                 |
| <b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b><br>Todd and Camille Moon   |                  |                |  |                 | <b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>  |                 |
| <b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b><br>Route 3 Box 3622, ,  |                  |                |  |                 | <b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>   |                 |
| <b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>   |                  |                | <b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b><br>YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/> |                 | <b>19. SLANT</b><br>VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>                               |                 |
| <b>20. LOCATION OF WELL</b>   | <b>FOOTAGES</b>  | <b>QTR-QTR</b> | <b>SECTION</b>   | <b>TOWNSHIP</b> | <b>RANGE</b>  | <b>MERIDIAN</b> |
| <b>LOCATION AT SURFACE</b>  | 2098 FNL 821 FWL | SWNW           | 22   | 4.0 S           | 3.0 W   | U               |
| <b>Top of Uppermost Producing Zone</b>  | 2098 FNL 821 FWL | SWNW           | 22   | 4.0 S           | 3.0 W   | U               |
| <b>At Total Depth</b>   | 2098 FNL 821 FWL | SWNW           | 22   | 4.0 S           | 3.0 W   | U               |
| <b>21. COUNTY</b><br>DUCHESNE   |                  |                | <b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b><br>821  |                 | <b>23. NUMBER OF ACRES IN DRILLING UNIT</b><br>40   |                 |
|   |                  |                | <b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b><br>1193   |                 | <b>26. PROPOSED DEPTH</b><br>MD: 7010 TVD: 7010   |                 |
| <b>27. ELEVATION - GROUND LEVEL</b><br>5574   |                  |                | <b>28. BOND NUMBER</b><br>RLB0010462   |                 | <b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b><br>437478  |                 |
| <b>ATTACHMENTS</b>  |                  |                |  |                 |   |                 |
| <b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>   |                  |                |  |                 |   |                 |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER  |                  |                | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN   |                 |   |                 |
| <input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)   |                  |                | <input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER   |                 |   |                 |
| <input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)   |                  |                | <input checked="" type="checkbox"/> TOPOGRAPHICAL MAP  |                 |   |                 |
| <b>NAME</b> Mandie Crozier  |                  |                | <b>TITLE</b> Regulatory Tech   |                 | <b>PHONE</b> 435 646-4825   |                 |
| <b>SIGNATURE</b>  |                  |                | <b>DATE</b> 10/28/2010   |                 | <b>EMAIL</b> mcrozier@newfield.com  |                 |
| <b>API NUMBER ASSIGNED</b><br>43013504540000  |                  |                | <b>APPROVAL</b>  |                 | <br>Permit Manager   |                 |

| <b>Proposed Hole, Casing, and Cement</b> |                  |                    |                 |                    |  |  |
|--|------------------|--------------------|-----------------|--------------------|--|--|
| <b>String</b>                            | <b>Hole Size</b> | <b>Casing Size</b> | <b>Top (MD)</b> | <b>Bottom (MD)</b> |  |  |
| Prod                                     | 7.875            | 5.5                | 0               | 7010               |  |  |
| <b>Pipe</b>                              | <b>Grade</b>     | <b>Length</b>      | <b>Weight</b>   |                    |  |  |
|  | Grade J-55 LT&C  | 7010               | 15.5            |                    |  |  |
|  |                  |                    |                 |                    |  |  |

| <b>Proposed Hole, Casing, and Cement</b> |                  |                    |                 |                    |  |  |
|--|------------------|--------------------|-----------------|--------------------|--|--|
| <b>String</b>                            | <b>Hole Size</b> | <b>Casing Size</b> | <b>Top (MD)</b> | <b>Bottom (MD)</b> |  |  |
| Surf                                     | 12.25            | 8.625              | 0               | 300                |  |  |
| <b>Pipe</b>                              | <b>Grade</b>     | <b>Length</b>      | <b>Weight</b>   |                    |  |  |
|  | Grade J-55 ST&C  | 300                | 24.0            |                    |  |  |
|  |                  |                    |                 |                    |  |  |

NEWFIELD PRODUCTION COMPANY  
UTE TRIBAL 5-22-4-3W  
SW/NW SECTION 22, T4S, R3W  
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

|                    |               |
|--------------------|---------------|
| Uinta              | 0' – 1,745'   |
| Green River        | 1,745'        |
| Wasatch            | 6,735'        |
| <b>Proposed TD</b> | <b>7,010'</b> |

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1,745' – 6,735'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

|  |   |
|--|---|
| Location & Sampled Interval                        | Date Sampled                                  |
| Flow Rate  | Temperature                                   |
| Hardness   | pH  |
| Water Classification (State of Utah)               | Dissolved Calcium (Ca) (mg/l)                 |
| Dissolved Iron (Fe) (ug/l)                         | Dissolved Sodium (Na) (mg/l)                  |
| Dissolved Magnesium (Mg) (mg/l)                    | Dissolved Carbonate (CO <sub>3</sub> ) (mg/l) |
| Dissolved Bicarbonate (NaHCO <sub>3</sub> ) (mg/l) | Dissolved Chloride (Cl) (mg/l)                |
| Dissolved Sulfate (SO <sub>4</sub> ) (mg/l)        | Dissolved Total Solids (TDS) (mg/l)           |

4. **PROPOSED CASING PROGRAM**

a. **Casing Design: Ute Tribal 5-22-4-3W**

| Size                     | Interval |        | Weight | Grade | Coupling | Design Factors |          |         |
|--------------------------|----------|--------|--------|-------|----------|----------------|----------|---------|
|                          | Top      | Bottom |        |       |          | Burst          | Collapse | Tension |
| Surface casing<br>8-5/8" | 0'       | 300'   | 24.0   | J-55  | STC      | 2,950          | 1,370    | 244,000 |
|                          |          |        |        |       |          | 17.53          | 14.35    | 33.89   |
| Prod casing<br>5-1/2"    | 0'       | 7,010' | 15.5   | J-55  | LTC      | 4,810          | 4,040    | 217,000 |
|                          |          |        |        |       |          | 2.16           | 1.81     | 2.00    |

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg  
 Pore pressure at surface casing shoe = 8.33 ppg  
 Pore pressure at prod casing shoe = 8.33 ppg  
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. **Cementing Design: Ute Tribal 5-22-4-3W**

| Job                 | Fill   | Description                      | Sacks           | OH Excess* | Weight (ppg) | Yield (ft <sup>3</sup> /sk) |
|---------------------|--------|----------------------------------|-----------------|------------|--------------|-----------------------------|
|                     |        |                                  | ft <sup>3</sup> |            |              |                             |
| Surface casing      | 300'   | Class G w/ 2% CaCl               | 138             | 30%        | 15.8         | 1.17                        |
|                     |        |                                  | 161             |            |              |                             |
| Prod casing<br>Lead | 5,010' | Prem Lite II w/ 10% gel + 3% KCl | 346<br>1129     | 30%        | 11.0         | 3.26                        |
| Prod casing<br>Tail | 2,000' | 50/50 Poz w/ 2% gel + 3% KCl     | 363<br>451      | 30%        | 14.3         | 1.24                        |

- \*Actual volume pumped will be 15% over the caliper log
- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
  - Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:  
The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system, and individual components shall be operable as designed. Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ±350 feet will be drilled with an air/mist system. The air rig is equipped with a 6 ½" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ±350 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBDT to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated

bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**



It is anticipated that the drilling operations will commence the first quarter of 2011, and take approximately seven (7) days from spud to rig release.

# T4S, R3W, U.S.B.&M.

WEST - 80.30 (G.L.O.)

## NEWFIELD EXPLORATION COMPANY

WELL LOCATION, 5-22-4-3W, LOCATED AS SHOWN IN THE SW 1/4 NW 1/4 OF SECTION 22, T4S, R3W, U.S.B.&M. DUCHESNE COUNTY, UTAH.




**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. 189377



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are base on LOCATION: an N.G.S. OPUS Correction. LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'


**5-22-4-3W**  
 (Surface Location) NAD 83  
 LATITUDE = 40° 07' 18.79"  
 LONGITUDE = 110° 12' 56.41"

### TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078  
 (435) 781-2501

|                            |                   |
|----------------------------|-------------------|
| DATE SURVEYED:<br>09-13-10 | SURVEYED BY: D.G. |
| DATE DRAWN:<br>09-15-10    | DRAWN BY: M.W.    |
| REVISED:                   | SCALE: 1" = 1000' |

# Access Road Map



**Tri State**  
**Land Surveying, Inc.**  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501  
 F: (435) 781-2518



## NEWFIELD EXPLORATION COMPANY


5-22-4-3W  
 SEC. 22, T4S, R3W, U.S.B.&M.  
 Duchesne County, UT.

DRAWN BY: C.H.M.  
 DATE: 10-11-2010  
 SCALE: 1:100,000

## TOPOGRAPHIC MAP

SHEET  
**A**

**Access Road Map**



**Legend**

- Existing Road
- Proposed Reroute
- Proposed Road

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

**Tri State  
Land Surveying, Inc.**  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501  
F: (435) 781-2518



**NEWFIELD EXPLORATION COMPANY**


**5-22-4-3W**  
**SEC. 22, T4S, R3W, U.S.B.&M.**  
**Duchesne County, UT.**

|           |             |
|-----------|-------------|
| DRAWN BY: | C.H.M.      |
| DATE:     | 10-11-2010  |
| SCALE:    | 1" = 2,000' |

**TOPOGRAPHIC MAP**

SHEET  
**B**

**Proposed Pipeline Map**



**Legend**

- Existing Road
- Proposed Reroute
- Proposed Waterline
- Proposed Gas Pipeline
- Proposed Flowline

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

**Tri State Land Surveying, Inc.**  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
 P: (435) 781-2501  
 F: (435) 781-2518




**NEWFIELD EXPLORATION COMPANY**

**5-22-4-3W**  
**SEC. 22, T4S, R3W, U.S.B.&M.**  
**Duchesne County, UT.**


|           |             |
|-----------|-------------|
| DRAWN BY: | C.H.M.      |
| DATE:     | 10-11-2010  |
| SCALE:    | 1" = 2,000' |

**TOPOGRAPHIC MAP**

SHEET  
**C**



### Exhibit "B" Map



**Proposed Location**  
5-22-4-3W

**Legend**

-  1 Mile Radius
-  Proposed Location



**Tri State**  
**Land Surveying, Inc.**  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501  
F: (435) 781-2518



### NEWFIELD EXPLORATION COMPANY

**5-22-4-3W**  
**SEC. 22, T4S, R3W, U.S.B.&M.**  
**Duchesne County, UT.**

|           |             |
|-----------|-------------|
| DRAWN BY: | C.H.M.      |
| DATE:     | 10-11-2010  |
| SCALE:    | 1" = 2,000' |

**TOPOGRAPHIC MAP**

SHEET  
**D**



STATE OF UTAH )  
 )ss  
COUNTY OF Duchesne )


File # 42148220 R. 00596 F. 0504

This instrument was acknowledged before me this 11<sup>th</sup> day of February, 2010 by **Todd and Camille Moon, private surface owners.**

Witness my hand and official seal.

My commission expires 9/8/2013

[Signature]  
Notary Public




STATE OF COLORADO )  
 )ss  
COUNTY OF Denver )

This instrument was acknowledged before me this March 5, 2010 by **Daniel W. Shewmake, Vice President-Development** a Texas corporation, on behalf of the corporation.

Witness my hand and official seal.

My commission expires \_\_\_\_\_

[Signature]  
Notary Public



**MEMORANDUM  
of  
EASEMENT, RIGHT-OF-WAY  
and  
SURFACE USE AGREEMENT**

This Easement, Right-of-Way and Surface Use Agreement ("Agreement") is entered into this 17<sup>th</sup> day of March, 2010 by and between **Ken and Nancy Moon, whose address is HC 64 box 102, Duchesne, Utah 84021**, ("Surface Owner," whether one or more) and Newfield Production Company, a Texas corporation ("NEWFIELD"), with offices at 1001 Seventeenth Street, Suite 2000, Denver, Colorado 80202, covering certain lands, (the "Lands") situated in Duchesne County, Utah described as follows:

**Township 4 South, Range 3 West**

**Section 15: E/2**

**Section 22: E/2**

**Township 4 South, Range 2 West**

**Section 7: S $\frac{1}{2}$ N $\frac{1}{4}$ ; S $\frac{1}{2}$**

Duchesne County, Utah

For and in consideration of the sum of ten dollars (\$10.00), and other valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the undersigned hereby agree to the terms and provisions set forth as follows:

1. **Compensation for Well; Release of All Claims**

NEWFIELD shall pay to Surface Owner the sum as set forth in and according to the terms of that certain Letter Agreement for Easement, Right-of Way and Surface Use by and between Surface Owner and NEWFIELD, dated March 17, 2010 as full payment and satisfaction for any and all detriment, depreciation, injury or damage of any nature to the Lands or growing crops thereon that may occur as a result of NEWFIELD's drilling or completion operations or its continuing activities for the production or transportation of oil, gas, or other hydrocarbons or products associated with the foregoing including, but not limited to, surface use, access, pipelines, gathering lines, pipeline interconnections, and any and all other reasonable or customary uses of land related to said operations or activities.

2. **Grant of Right of Way and Easement**

Surface Owner hereby grants, bargains, leases, assigns, and conveys to NEWFIELD an easement and right-of-way for the purpose of construction, using and maintaining access roads, locations for surface equipment and subsurface gathering lines for each well drilled upon the Lands, pipelines, and pipeline interconnections for two years from date of this agreement and so long thereafter as NEWFIELD's oil and gas leases remain in effect.

This Agreement shall be binding upon the respective heirs, executors, administrators, successors, and assigns of the undersigned.

These Parties hereto have executed this document effective as of the day first above written.

KEN AND NANCY MOON

NEWFIELD PRODUCTION COMPANY

By: *Ken Moon*  
Ken Moon, private surface owner

By: \_\_\_\_\_  
Dan Shewmake,  
Vice President-Development


By: *Nancy Moon*  
Nancy Moon, private surface owner

STATE OF UTAH )  
 )  
COUNTY OF Duchesne )<sup>ss</sup>

This instrument was acknowledged before me this 24<sup>th</sup> day of March, 2010 by Ken and Nancy Moon, private surface owners.

Witness my hand and official seal.

My commission expires 9/8/2013

*[Signature]*  
Notary Public  


STATE OF COLORADO )  
 )  
COUNTY OF Denver )<sup>ss</sup>

This instrument was acknowledged before me this \_\_\_\_\_, 2010 by Dan Shewmake, Vice President-Development a Texas corporation, on behalf of the corporation.

Witness my hand and official seal.

\_\_\_\_\_  
Notary Public

My commission expires \_\_\_\_\_

**NEWFIELD PRODUCTION COMPANY  
UTE TRIBAL 5-22-4-3W  
SW/NW SECTION 22, T4S, R3W  
DUCHESNE COUNTY, UTAH**

**ONSHORE ORDER NO. 1**

**MULTI-POINT SURFACE USE & OPERATIONS PLAN**

**I. EXISTING ROADS**

See attached Topographic Map "A"

To reach Newfield Production Company well location site Ute Tribal 5-22-4-3W located in the SW 1/4 NW 1/4 Section 22, T4S, R3W, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed in a southwesterly direction approximately 6.4 miles to it's junction with an existing road to the southwest; proceed in a southwesterly direction approximately 2.7 miles to it's junction with an existing road to the northwest; proceed in a northwesterly direction approximately 1.5 miles to it's junction with an existing road to the northeast; proceed northeasterly approximately 0.8 miles to it's junction with an existing road to the northwest; proceed northwesterly approximately 0.3 miles to it's junction with the beginning of the proposed access road to the north; proceed northwesterly along the proposed access road approximately 3,645' to the proposed well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

**2. PLANNED ACCESS ROAD**

Approximately 3,645' of access road is proposed for the proposed well. See attached **Topographic Map "B"**.

The proposed access road will be an 20' crown road (10' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. **LOCATION OF EXISTING WELLS**

Refer to Exhibit "B".

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District  
Water Right : 43-10136

Maurice Harvey Pond  
Water Right: 47-1358

Neil Moon Pond  
Water Right: 43-11787

Newfield Collector Well  
Water Right: 41-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be

be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

**Fencing Requirements**

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

- b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – Todd and Camille Moon.  
See attached Memorandums of Surface Use Agreement and Easement ROW..

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological and Paleontological Reports will be forthcoming.

Newfield Production Company requests 3,645' of planned access road to be granted. **Refer to Topographic Map "B"**. Newfield Production Company requests 1,263' of surface gas line to be granted. Newfield Production Company requests 1,256' of buried water line to be granted.

It is proposed that the disturbed area will be 60' wide to allow for construction of the proposed access road, a 10" or smaller gas gathering line, a 4" poly fuel gas line, a buried 10" steel water injection line, a buried 3" poly water return line, and a and a 14" surface flow line. The planned access road will consist of a 20' permanent running surface (10' either side of the centerline) crowned and ditched in order to handle any run-off from any precipitation events that are prevalent to this area. The maximum grade will be less than 8%. There will be no culverts required along this access road. There will be turnouts as needed along this road to allow for increases in potential traffic issues. There are no fences encountered along this proposed road. There will be no new gates or cattle guards required. All construction material for this access road will be borrowed material accumulated during construction of the access road.

Both the proposed surface gas and buried water lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** The proposed water pipelines will be buried in a 4-5' deep trench constructed with a trencher or backhoe for the length of the proposal. The equipment will run on the surface and not be flat bladed to minimize surface impacts to precious topsoil in these High Desert environments. If possible, all proposed surface gas pipelines will be installed on the same side of the road as existing gas lines. The construction phase of the planned access road, proposed gas lines and proposed water lines will last approximately (5) days.

In the event that the proposed well is converted to a water injection well, a Sundry Notice 3160-5 form will be applied for through the Bureau of Land Management field office:

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

**Surface Flow Line**

Newfield requests 1,263' of surface flow line be granted. The Surface Flow Line will consist of up to a 14" bundled pipe consisting of 2-2" poly glycol lines and 1-3" production line. For all new

wells, Newfield. **Refer to Topographic Map "D"** for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures:

Clearing and Grading: No clearing or grading of the ROW will be required. The centerline of the proposed route will be staked prior to installation. Flow lines shall be placed as close to existing roads as possible without interfering with normal road travel or road maintenance activities. Due to the proximity of existing facilities, no temporary use or construction/storage areas are anticipated. If necessary, temporary use or construction/storage areas will be identified on a topographic map included in the approved permit.

Installation: The proposed flow lines will be installed 4-6" above the ground. For portions along existing two-track and primary access roads, lengths of pipe will be strung out in the borrow ditch, welded together, and rolled or dragged into place with heavy equipment. For pipelines that are installed cross-country (not along existing or proposed roads), travel along the lines will be infrequent and for maintenance needs only. No installation activities will be performed during periods when the soil is too wet to adequately support installation equipment. If such equipment creates ruts in excess of three (3) inches deep, the soil will be deemed too wet to adequately support the equipment.

Termination and Final Reclamation: After abandonment of the associated production facilities, the flow lines will be cut and removed, and any incidental surface disturbance reclaimed. Reclamation procedures will follow those outlined in the Ute Tribe Green River Development Program Standard Operating Practices (SOP).

#### **Water Disposal**

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

#### **Additional Surface Stipulations**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

#### **Hazardous Material Declaration**

Newfield Production Company guarantees that during the drilling and completion of the Ute Tribal 5-22-4-3W, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Ute Tribal 5-22-4-3W, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office as well as the Ute Tribe Energy and Mineral Department shall be notified upon site completion prior to moving on the drilling rig.

13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

Representative

Name: Tim Eaton  
Address: Newfield Production Company  
Route 3, Box 3630  
Myton, UT 84052  
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #5-22-4-3W, SW/NW Section 22, T4S, R3W, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage for this well is covered by the Bureau of Indian Affairs Bond #RLB0010462.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

10/28/10  
Date

  
Mandie Crozier  
Regulatory Specialist  
Newfield Production Company

# 2-M SYSTEM

Blowout Prevention Equipment Systems





EXHIBIT C

**API Number: 4301350454**  
**Well Name: Ute Tribal 5-22-4-3W**  
**Township 04.0 S Range 03.0 W Section 22**  
**Meridian: UBM**  
 Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:  
 Map Produced by Diana Mason



**Units**


- ACTIVE
- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

**Fields**

- Sections
- Township
- Bottom Hole Location - AGRC

**Wells Query**

- <call other values>
- APD - Approved Permit
- DRL - Spudded (Drilling Commenced)
- GIW - Gas Injection
- GS - Gas Storage
- LA - Location Abandoned
- LOC - New Location
- OPS - Operation Suspended
- PA - Plugged Abandoned
- PGW - Producing Gas Well
- POW - Producing Oil Well
- RET - Returned APD
- SGW - Shut-in Gas Well
- SOW - Shut-in Oil Well
- TA - Temp. Abandoned
- TW - Test Well
- WDW - Water Disposal
- WW - Water Injection Well
- WSW - Water Supply Well



# ON-SITE PREDRILL EVALUATION Utah Division of Oil, Gas and Mining

|                          |                             |                      |                       |                   |             |
|--------------------------|-----------------------------|----------------------|-----------------------|-------------------|-------------|
| <b>Operator</b>          | NEWFIELD PRODUCTION COMPANY |                      |                       |                   |             |
| <b>Well Name</b>         | Ute Tribal 5-22-4-3W        |                      |                       |                   |             |
| <b>API Number</b>        | 43013504540000              | <b>APD No</b>        | 3104                  | <b>Field/Unit</b> | WILDCAT     |
| <b>Location: 1/4,1/4</b> | SWNW                        | <b>Sec</b>           | 22                    | <b>Tw</b>         | 4.0S        |
|                          |                             | <b>Rng</b>           | 3.0W                  | 2098              | FNL 821 FWL |
| <b>GPS Coord (UTM)</b>   | 566896 4441378              | <b>Surface Owner</b> | Todd and Camille Moon |                   |             |

**Participants**

Floyd Bartlett (DOGM), Tim Eaton (Newfield Permitting), Christina Cimiluca, Suzanne Grayson and Janna Simonsen (BLM), and Corie Miller (Tri-State Land Surveying).

**Regional/Local Setting & Topography**

The proposed location is approximately 13.6 road miles southwest of Myton, UT in the South Myton Bench area. The drainages are sub drainage of Pleasant Valley Canal and Wash that drain into the Pariette Draw drainage of Duchesne County. The lower reaches of both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 20 plus miles downstream from the location. Broad flats with those in lower Pleasant Valley frequently used for agriculture, characterize the area. Flats are intersected by drainages with gentle to moderate side slopes. Access is by State and County and planned or existing oil field development roads. Approximately 1,259 feet of new construction across Moon’s private land will be required to reach the location.

The proposed site for the Ute Tribal 5-22-4-3 oil well is in upper Pleasant Valley in lightly rolling topography with a gentle slope to the northwest. The pad is laid out in a east to west direction of a flat with a slight north slope. The slope leads to a draw which runs to the northwest. To the south the flat continues. Maximum cut is 5.3 feet at Pit Corner B and maximum fill is 3.5 feet at Location Corner 2. No drainages intersect the location and no diversions are needed. No springs, streams or seeps are known to exist in the immediate area. The selected site appears to be a good location for constructing a pad, drilling and operating a well.

Mr. Todd Moon and his wife Camille own the surface of the location.

**Surface Use Plan**

**Current Surface Use**  
Grazing  
Wildlfe Habitat

|                       |                             |                           |                          |
|-----------------------|-----------------------------|---------------------------|--------------------------|
| <b>New Road Miles</b> | <b>Well Pad</b>             | <b>Src Const Material</b> | <b>Surface Formation</b> |
| 0.23                  | <b>Width 204 Length 305</b> | Onsite                    | UNTA                     |

**Ancillary Facilities** N

**Waste Management Plan Adequate?**

**Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

**Flora / Fauna**

A desert shrub type vegetation covers the area. Principal plants consist of horsebrush, big sagebrush, broom snakeweed, prickly pear, curly mesquite grass, cheatgrass, halogeton, Indian ricegrass, globe mallow, buckwheat, aster, shadscale,

Cattle, deer, prairie dogs, small mammals and birds.

**Soil Type and Characteristics**

Deep sandy loam with some gravel.

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

**Drainage Diverson Required?** N

**Berm Required?** Y

**Erosion Sedimentation Control Required?** N

**Paleo Survey Run?**    **Paleo Potental Observed?** N    **Cultural Survey Run?** Y    **Cultural Resources?**

**Reserve Pit**

**Site-Specific Factors**

**Site Ranking**

|  |                    |    |                     |
|--|--------------------|----|---------------------|
| <b>Distance to Groundwater (feet)</b>    | 100 to 200         | 5  |                     |
| <b>Distance to Surface Water (feet)</b>  | >1000              | 0  |                     |
| <b>Dist. Nearest Municipal Well (ft)</b> | >5280              | 0  |                     |
| <b>Distance to Other Wells (feet)</b>    | 300 to 1320        | 10 |                     |
| <b>Native Soil Type</b>                  | Mod permeability   | 10 |                     |
| <b>Fluid Type</b>                        | Fresh Water        | 5  |                     |
| <b>Drill Cuttings</b>                    | Normal Rock        | 0  |                     |
| <b>Annual Precipitation (inches)</b>     |                    | 0  |                     |
| <b>Affected Populations</b>              |                    |    |                     |
| <b>Presence Nearby Utility Conduits</b>  | Not Present        | 0  |                     |
|  | <b>Final Score</b> | 30 | 1 Sensitivity Level |

**Characteristics / Requirements**

A reserve pit 40' x 80' x 8' deep will be located in an area of cut on the southeast side of the location. A 16-mil pit liner is required

**Closed Loop Mud Required?** N    **Liner Required?** Y    **Liner Thickness** 16    **Pit Underlayment Required?** Y

**Other Observations / Comments**

Floyd Bartlett  
**Evaluator**

11/15/2010  
**Date / Time**

# Application for Permit to Drill

## Statement of Basis

11/18/2010

### Utah Division of Oil, Gas and Mining

Page 1

|                  |   |               |                          |                       |            |
|------------------|---|---------------|--------------------------|-----------------------|------------|
| <b>APD No</b>    | <b>API WellNo</b>   | <b>Status</b> | <b>Well Type</b>         | <b>Surf Owner</b>     | <b>CBM</b> |
| 3104             | 43013504540000  | LOCKED        | OW                       | P                     | No         |
| <b>Operator</b>  | NEWFIELD PRODUCTION COMPANY                                       |               | <b>Surface Owner-APD</b> | Todd and Camille Moon |            |
| <b>Well Name</b> | Ute Tribal 5-22-4-3W  |               | <b>Unit</b>              |                       |            |
| <b>Field</b>     | WILDCAT   |               | <b>Type of Work</b>      | DRILL                 |            |
| <b>Location</b>  | SWNW 22 4S 3W U 2098 FNL 821 FWL GPS Coord (UTM) 566898E 4441365N |               |                          |                       |            |

#### Geologic Statement of Basis

The mineral rights for the proposed well are owned by the Ute Tribe. The BLM will be the agency responsible for evaluating and approving the drilling, casing and cement programs.

Brad Hill  
APD Evaluator

11/17/2010  
Date / Time

#### Surface Statement of Basis

The proposed location is approximately 13.6 road miles southwest of Myton, UT in the South Myton Bench area. The drainages are sub drainage of Pleasant Valley Canal and Wash that drain into the Pariette Draw drainage of Duchesne County. The lower reaches of both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 20 plus miles downstream from the location. Broad flats with those in lower Pleasant Valley frequently used for agriculture, characterize the area. Flats are intersected by drainages with gentle to moderate side slopes. Access is by State and County and planned or existing oil field development roads. Approximately 1,259 feet of new construction across Moon's private land will be required to reach the location.

The proposed site for the Ute Tribal 5-22-4-3 oil well is in upper Pleasant Valley in lightly rolling topography with a gentle slope to the northwest. The pad is laid out in a east to west direction of a flat with a slight north slope. The slope leads to a draw which runs to the northwest. To the south the flat continues. Maximum cut is 5.3 feet at Pit Corner B and maximum fill is 3.5 feet at Location Corner 2. No drainages intersect the location and no diversions are needed. No springs, streams or seeps are known to exist in the immediate area. The selected site appears to be a good location for constructing a pad, drilling and operating a well.

Mr. Todd Moon and his wife Camille own the surface of the location. Mr. Moon was contacted by telephone by the BLM and invited to the pre-site visit. He said he would not attend. The minerals are owned by the United States Government and held in trust for the Ute Indian Tribe. Ms. Christina Cimuluca, Ms. Suzanne Grayson and Ms. Janna Simonsen of the BLM all attended the preside visit. They had no concerns regarding the selected area. A signed landowner agreement exists.

Floyd Bartlett  
Onsite Evaluator

11/15/2010  
Date / Time

#### Conditions of Approval / Application for Permit to Drill

| Category | Condition   |
|----------|---|
| Pits     | A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit. |
| Surface  | The well site shall be bermed to prevent fluids from leaving the pad.   |
| Surface  | The reserve pit shall be fenced upon completion of drilling operations.   |

**WORKSHEET  
APPLICATION FOR PERMIT TO DRILL**

---

---

**APD RECEIVED:** 10/28/2010

**API NO. ASSIGNED:** 43013504540000

**WELL NAME:** Ute Tribal 5-22-4-3W

**OPERATOR:** NEWFIELD PRODUCTION COMPANY (N2695)

**PHONE NUMBER:** 435 646-4825

**CONTACT:** Mandie Crozier

**PROPOSED LOCATION:** SWNW 22 040S 030W

**Permit Tech Review:**

**SURFACE:** 2098 FNL 0821 FWL

**Engineering Review:**

**BOTTOM:** 2098 FNL 0821 FWL

**Geology Review:**

**COUNTY:** DUCHESNE

**LATITUDE:** 40.12184

**LONGITUDE:** -110.21491

**UTM SURF EASTINGS:** 566898.00

**NORTHINGS:** 4441365.00

**FIELD NAME:** WILDCAT

**LEASE TYPE:** 2 - Indian

**LEASE NUMBER:** 1420H626154

**PROPOSED PRODUCING FORMATION(S):** GREEN RIVER

**SURFACE OWNER:** 4 - Fee

**COALBED METHANE:** NO

---

**RECEIVED AND/OR REVIEWED:**

- PLAT
- Bond: INDIAN - RLBO010462
- Potash
- Oil Shale 190-5
- Oil Shale 190-3
- Oil Shale 190-13
- Water Permit: 437478
- RDCC Review: 2010-11-17 00:00:00.0
- Fee Surface Agreement
- Intent to Commingle

**Commingling Approved**

**LOCATION AND SITING:**

- R649-2-3.
  - Unit:**
  - R649-3-2. General
  - R649-3-3. Exception
  - Drilling Unit
  - Board Cause No:** R649-3-2
  - Effective Date:**
  - Siting:**
  - R649-3-11. Directional Drill
- 

**Comments:** Presite Completed

**Stipulations:** 4 - Federal Approval - dmason  
5 - Statement of Basis - bhll  
21 - RDCC - dmason  
23 - Spacing - dmason



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

### Permit To Drill

\*\*\*\*\*

**Well Name:** Ute Tribal 5-22-4-3W  
**API Well Number:** 43013504540000  
**Lease Number:** 1420H626154  
**Surface Owner:** FEE (PRIVATE)  
**Approval Date:** 11/18/2010

**Issued to:**

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

**Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-2. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

**Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

**General:**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**Conditions of Approval:**

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

The Application for Permit to Drill has been forwarded to the Resource Development Coordinating Committee for review of this action. The operator will be required to comply with any applicable recommendations resulting from this review. (See attached)

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "John Rogers", written over a faint, illegible stamp or background.

For John Rogers  
Associate Director, Oil & Gas

RECEIVED  
MAR 11 2011

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

|  |  |   |
|--|--|---|
| 1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER   |  | 5. Lease Serial No.<br>14-20-H62-6380                             |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone |  | 6. If Indian, Allottee or Tribe Name<br>UTE                       |
| 2. Name of Operator<br>Newfield Production Company   |  | 7. If Unit or CA Agreement, Name and No.<br>NA                    |
| 3a. Address<br>Route #3 Box 3630, Myton UT 84052   |  | 8. Lease Name and Well No.<br>Ute Tribal 5-22-4-3W                |
| 3b. Phone No. (include area code)<br>(435) 646-3721  |  | 9. API Well No.<br>43-013-50454                                   |
| 4. Location of Well (Report location clearly and in accordance with any State requirements. *)<br>At surface: SW/NW 2098' FNL 821' FWL<br>At proposed prod. zone   |  | 10. Field and Pool, or Exploratory<br>Undesignated                |
| 14. Distance in miles and direction from nearest town or post office*<br>Approximately 13.4 miles southwest of Myton, UT   |  | 11. Sec., T. R. M. or Blk. and Survey or Area<br>Sec. 22, T4S R3W |
| 15. Distance from proposed* location to nearest property or lease line, ft. Approx. 821' f/lse, NA' f/unit (Also to nearest drig. unit line, if any)   | 16. No. of acres in lease<br>NA                        | 12. County or Parish<br>Duchesne                                  |
| 17. Spacing Unit dedicated to this well<br>40 Acres  | 13. State<br>UT  |   |
| 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 1193'   | 19. Proposed Depth<br>7,010'                           | 20. BLM/BIA Bond No. on file<br>RLB0010462                        |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.)<br>5574' GL  | 22. Approximate date work will start*<br>3rd Qtr. 2011 | 23. Estimated duration<br>(7) days from SPUD to rig release       |
| 24. Attachments  |  |   |

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

|   |  |                     |
|---|--|---------------------|
| 25. Signature<br><i>Mandie Crozier</i>                        | Name (Printed/Typed)<br>Mandie Crozier | Date<br>3/10/11     |
| Title<br>Regulatory Specialist                                |  |                     |
| Approved by (Signature)<br><i>Jerry Kenczka</i>               | Name (Printed/Typed)<br>Jerry Kenczka  | Date<br>MAR 21 2011 |
| Title<br>Assistant Field Manager<br>Lands & Mineral Resources |  |                     |
| Office<br>VERNAL FIELD OFFICE                                 |  |                     |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18, U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

RECEIVED

*NBS 10/28/10*  
*AFMS# 11550523A*

UDOGM

APR 04 2011  
DIV. OF OIL, GAS & MINING

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED



UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

|          |                             |            |                        |
|----------|-----------------------------|------------|------------------------|
| Company: | Newfield Production Company | Location:  | SWNW, Sec. 22, T4S R3W |
| Well No: | Ute Tribal 5-22-4-3W        | Lease No:  | 14-20-H62-6380         |
| API No:  | 43-013-50454                | Agreement: | N/A                    |

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

|   |  |
|---|--|
| Construction Activity<br>(Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)   | - The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.                                      |
| Construction Completion<br>(Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist) | - Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig. |
| Spud Notice<br>(Notify BLM Petroleum Engineer)  | - Twenty-Four (24) hours prior to spudding the well.   |
| Casing String & Cementing<br>(Notify BLM Supv. Petroleum Tech.)                                       | - Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <a href="mailto:ut_vn_opreport@blm.gov">ut_vn_opreport@blm.gov</a> .   |
| BOP & Related Equipment Tests<br>(Notify BLM Supv. Petroleum Tech.)                                   | - Twenty-Four (24) hours prior to initiating pressure tests.   |
| First Production Notice<br>(Notify BLM Petroleum Engineer)  | - Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.   |

***SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)***

- A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be installed and maintained in the reserve pit.
- Any deviation from submitted APD's and ROW applications the operator will notify the BLM in writing and will receive written authorization of any such change with appropriate authorization.
- All operator employees and/or authorized personnel (sub-contractors) in the field will have approved applicable APD's and ROW permits/authorizations on their person(s) during all phases of construction.
- All vehicular traffic, personnel movement, construction/restoration operations should be confined to the area examined and approved, and to the existing roadways and/or evaluated access routes.
- All permanent surface equipment (meaning on site for six months or longer) will be painted Covert Green to match the surrounding landscape color unless otherwise authorized. This would include all facilities except those required to comply with Occupational Safety and Health Act (OSHA) regulations.
- Reclamation will be completed in accordance with the recontouring and reseeding procedures outlined in the Newfield Exploration Company Castle Peak and Eight Mile Flat Reclamation Plan on file with the Vernal Field Office of the BLM, unless otherwise specified by the private surface owner.

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

- The operator shall comply with all applicable requirements in the SOP (version: "Ute Tribe Green River Development Program", April 17, 2008). The operator shall also comply with applicable laws and regulations; with the lease terms, Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the authorized officer.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth

(from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT\_VN\_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

#### **OPERATING REQUIREMENT REMINDERS:**

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at [www.ONRR.gov](http://www.ONRR.gov).
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location ( $\frac{1}{4}$  $\frac{1}{4}$ , Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and

Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent

Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

| STATE OF UTAH<br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING   |  | FORM 9  |
|--|--|---|
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b>   |  | <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>1420H626154 |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.   |  | <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>                  |
|  |  | <b>7. UNIT or CA AGREEMENT NAME:</b>                          |
| <b>1. TYPE OF WELL</b><br>Oil Well   | <b>8. WELL NAME and NUMBER:</b><br>UTE TRIBAL 5-22-4-3W  |   |
| <b>2. NAME OF OPERATOR:</b><br>NEWFIELD PRODUCTION COMPANY   | <b>9. API NUMBER:</b><br>43013504540000  |   |
| <b>3. ADDRESS OF OPERATOR:</b><br>Rt 3 Box 3630 , Myton, UT, 84052   | <b>PHONE NUMBER:</b><br>435 646-4825 Ext   | <b>9. FIELD and POOL or WILDCAT:</b><br>WILDCAT               |
| <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>2098 FNL 0821 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 22 Township: 04.0S Range: 03.0W Meridian: U  | <b>COUNTY:</b><br>DUCHESNE   |   |
|  |  | <b>STATE:</b><br>UTAH   |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA  |  |   |
| <b>TYPE OF SUBMISSION</b>  | <b>TYPE OF ACTION</b>  |   |
| <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b><br>Approximate date work will start:<br>11/18/2011<br><br><input type="checkbox"/> <b>SUBSEQUENT REPORT</b><br>Date of Work Completion:<br><br><input type="checkbox"/> <b>SPUD REPORT</b><br>Date of Spud:<br><br><input type="checkbox"/> <b>DRILLING REPORT</b><br>Report Date: | <input type="checkbox"/> ACIDIZE<br><input type="checkbox"/> CHANGE TO PREVIOUS PLANS<br><input type="checkbox"/> CHANGE WELL STATUS<br><input type="checkbox"/> DEEPEN<br><input type="checkbox"/> OPERATOR CHANGE<br><input type="checkbox"/> PRODUCTION START OR RESUME<br><input type="checkbox"/> REPERFORATE CURRENT FORMATION<br><input type="checkbox"/> TUBING REPAIR<br><input type="checkbox"/> WATER SHUTOFF<br><input type="checkbox"/> WILDCAT WELL DETERMINATION<br><input type="checkbox"/> ALTER CASING<br><input type="checkbox"/> CHANGE TUBING<br><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS<br><input type="checkbox"/> FRACTURE TREAT<br><input type="checkbox"/> PLUG AND ABANDON<br><input type="checkbox"/> RECLAMATION OF WELL SITE<br><input type="checkbox"/> SIDETRACK TO REPAIR WELL<br><input type="checkbox"/> VENT OR FLARE<br><input type="checkbox"/> SI TA STATUS EXTENSION<br><input type="checkbox"/> OTHER |   |
|  | <input type="checkbox"/> CASING REPAIR<br><input type="checkbox"/> CHANGE WELL NAME<br><input type="checkbox"/> CONVERT WELL TYPE<br><input type="checkbox"/> NEW CONSTRUCTION<br><input type="checkbox"/> PLUG BACK<br><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION<br><input type="checkbox"/> TEMPORARY ABANDON<br><input type="checkbox"/> WATER DISPOSAL<br><input checked="" type="checkbox"/> APD EXTENSION<br>OTHER: <input style="width: 100px;" type="text"/>   |   |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.   |  |   |
| Newfield proposes to extend the Application for Permit to Drill this well.   |  |   |
| <p style="color: red; font-weight: bold;">Approved by the<br/>Utah Division of<br/>Oil, Gas and Mining</p> <p style="color: red; font-weight: bold;">Date: <u>11/23/2011</u></p> <p style="color: red; font-weight: bold;">By: <u></u></p>                |  |   |
| <b>NAME (PLEASE PRINT)</b><br>Mandie Crozier   | <b>PHONE NUMBER</b><br>435 646-4825  | <b>TITLE</b><br>Regulatory Tech                               |
| <b>SIGNATURE</b><br>N/A  | <b>DATE</b><br>11/9/2011   |   |



**The Utah Division of Oil, Gas, and Mining**

- State of Utah  
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Request for Permit Extension Validation Well Number 43013504540000**

**API:** 43013504540000

**Well Name:** UTE TRIBAL 5-22-4-3W

**Location:** 2098 FNL 0821 FWL QTR SWNW SEC 22 TWNP 040S RNG 030W MER U

**Company Permit Issued to:** NEWFIELD PRODUCTION COMPANY

**Date Original Permit Issued:** 11/18/2010

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated?  Yes  No
  
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?  Yes  No
  
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?  Yes  No
  
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location?  Yes  No
  
- Has the approved source of water for drilling changed?  Yes  No
  
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?  Yes  No
  
- Is bonding still in place, which covers this proposed well?  Yes  No

**Signature:** Mandie Crozier

**Date:** 11/9/2011

**Title:** Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

|  |   |
|--|---|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  | <b>FORM 9</b>   |
| <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>1420H626154  |   |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b>   |   |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. |   |
| <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>   | <b>7. UNIT or CA AGREEMENT NAME:</b>  |
| <b>1. TYPE OF WELL</b><br>Oil Well   | <b>8. WELL NAME and NUMBER:</b><br>UTE TRIBAL 5-22-4-3W   |
| <b>2. NAME OF OPERATOR:</b><br>NEWFIELD PRODUCTION COMPANY   | <b>9. API NUMBER:</b><br>43013504540000   |
| <b>3. ADDRESS OF OPERATOR:</b><br>Rt 3 Box 3630 , Myton, UT, 84052   | <b>PHONE NUMBER:</b><br>435 646-4825 Ext  |
| <b>9. FIELD and POOL or WILDCAT:</b><br>SOUTH MYTON BENCH  | <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>2098 FNL 0821 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 22 Township: 04.0S Range: 03.0W Meridian: U |
| <b>COUNTY:</b><br>DUCHESNE   | <b>STATE:</b><br>UTAH   |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION   | TYPE OF ACTION   |   |  |
|--|--|---|--|
| <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b><br>Approximate date work will start:<br>11/18/2012 | <input type="checkbox"/> ACIDIZE                       | <input type="checkbox"/> ALTER CASING                   | <input type="checkbox"/> CASING REPAIR                   |
| <input type="checkbox"/> <b>SUBSEQUENT REPORT</b><br>Date of Work Completion:                                  | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS      | <input type="checkbox"/> CHANGE TUBING                  | <input type="checkbox"/> CHANGE WELL NAME                |
| <input type="checkbox"/> <b>SPUD REPORT</b><br>Date of Spud:   | <input type="checkbox"/> CHANGE WELL STATUS            | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE               |
| <input type="checkbox"/> <b>DRILLING REPORT</b><br>Report Date:  | <input type="checkbox"/> DEEPEN                        | <input type="checkbox"/> FRACTURE TREAT                 | <input type="checkbox"/> NEW CONSTRUCTION                |
|  | <input type="checkbox"/> OPERATOR CHANGE               | <input type="checkbox"/> PLUG AND ABANDON               | <input type="checkbox"/> PLUG BACK                       |
|  | <input type="checkbox"/> PRODUCTION START OR RESUME    | <input type="checkbox"/> RECLAMATION OF WELL SITE       | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  |
|  | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL       | <input type="checkbox"/> TEMPORARY ABANDON               |
|  | <input type="checkbox"/> TUBING REPAIR                 | <input type="checkbox"/> VENT OR FLARE                  | <input type="checkbox"/> WATER DISPOSAL                  |
|  | <input type="checkbox"/> WATER SHUTOFF                 | <input type="checkbox"/> SI TA STATUS EXTENSION         | <input checked="" type="checkbox"/> <b>APD EXTENSION</b> |
|  | <input type="checkbox"/> WILDCAT WELL DETERMINATION    | <input type="checkbox"/> OTHER                          | OTHER: <input style="width: 100px;" type="text"/>        |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to extend the Application for Permit to Drill for one year.

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Date:** November 13, 2012

**By:** 

|  |                                     |                                 |
|--|-------------------------------------|---------------------------------|
| <b>NAME (PLEASE PRINT)</b><br>Mandie Crozier | <b>PHONE NUMBER</b><br>435 646-4825 | <b>TITLE</b><br>Regulatory Tech |
| <b>SIGNATURE</b><br>N/A                      | <b>DATE</b><br>11/8/2012            |                                 |



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Request for Permit Extension Validation Well Number 43013504540000**

API: 43013504540000

Well Name: UTE TRIBAL 5-22-4-3W

Location: 2098 FNL 0821 FWL QTR SWNW SEC 22 TWNP 040S RNG 030W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/18/2010

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated?  Yes  No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?  Yes  No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?  Yes  No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location?  Yes  No
- Has the approved source of water for drilling changed?  Yes  No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?  Yes  No
- Is bonding still in place, which covers this proposed well?  Yes  No

Signature: Mandie Crozier

Date: 11/8/2012

Title: Regulatory Tech Representing: NEWFIELD PRODUCTION COMPANY

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

RECEIVED

FEB 20 2013

FORM APPROVED  
OMB NO. 1004-0135  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*

BLM

5. Lease Serial No.  
1420H626380

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.  
NA

8. Well Name and No.  
UTE TRIBAL 5-22-4-3W

9. API Well No.  
43-013-50454

10. Field and Pool, or Exploratory  
UNDESIGNATED

11. County or Parish, and State  
DUCHESNE COUNTY, UT

**SUBMIT IN TRIPLICATE - Other instructions on reverse side.**

1. Type of Well  
 Oil Well  Gas Well  Other

2. Name of Operator  
NEWFIELD PRODUCTION  
Contact: MANDIE H CROZIER  
E-Mail: mcrozier@newfield.com

3a. Address  
ROUTE 3 BOX 3630  
MYTON, UT 84052

3b. Phone No. (include area code)  
Ph: 435-646-4825

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
Sec 22 T4S R3W Mer UBM SWNW 2098FNL 821FWL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION                                   | TYPE OF ACTION                                |   |  |   |
|--|---|---|--|---|
| <input checked="" type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize              | <input type="checkbox"/> Deepen           | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off   |
| <input type="checkbox"/> Subsequent Report           | <input type="checkbox"/> Alter Casing         | <input type="checkbox"/> Fracture Treat   | <input type="checkbox"/> Reclamation               | <input type="checkbox"/> Well Integrity   |
| <input type="checkbox"/> Final Abandonment Notice    | <input type="checkbox"/> Casing Repair        | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete                | <input checked="" type="checkbox"/> Other |
|  | <input type="checkbox"/> Change Plans         | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon       | Change to Original A PD                   |
|  | <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back        | <input type="checkbox"/> Water Disposal            |   |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Newfield requests to extend the Application for Permit to Drill this well for two more years.

MAY 09 2013

CONDITIONS OF APPROVAL ATTACHED

VERNAL FIELD OFFICE

ENG. RJH 4/22/13

GEOLOGIST \_\_\_\_\_

E.S. \_\_\_\_\_

PETROLEUM \_\_\_\_\_

RECLAMATION \_\_\_\_\_

14. I hereby certify that the foregoing is true and correct.

**Electronic Submission #199535 verified by the BLM Well Information System  
For NEWFIELD PRODUCTION, sent to the Vernal  
Committed to AFMSS for processing by BOBBI SCHROEDER on 03/14/2013 ()**

Name (Printed/Typed) MANDIE H CROZIER Title REGULATORY ANALYST

Signature (Electronic Submission) Date 02/20/2013

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By [Signature] Assistant Field Manager  
Title Lands & Mineral Resources Date **APR 22 2013**

Office **VERNAL FIELD OFFICE**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UDOGM

\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\*

12R 15172925

# CONDITIONS OF APPROVAL

## Newfield Exploration Company

### Notice of Intent APD Extension

**Lease:** 1420H626380  
**Well:** Ute Tribal 5-22-4-3W  
**Location:** SWNW Sec 22-T4S-R3W

An extension for the referenced APD is granted with the following conditions:

---

1. The extension and APD shall expire on 03/21/2015.
2. No other extension shall be granted.

If you have any other questions concerning this matter, please contact Robin L Hansen of this office at (435) 781-2777

|  |   |
|--|---|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  | <b>FORM 9</b>   |
| <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>1420H626154  |   |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b>   |   |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. |   |
| <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>   | <b>7. UNIT or CA AGREEMENT NAME:</b>  |
| <b>1. TYPE OF WELL</b><br>Oil Well   | <b>8. WELL NAME and NUMBER:</b><br>UTE TRIBAL 5-22-4-3W   |
| <b>2. NAME OF OPERATOR:</b><br>NEWFIELD PRODUCTION COMPANY   | <b>9. API NUMBER:</b><br>43013504540000   |
| <b>3. ADDRESS OF OPERATOR:</b><br>Rt 3 Box 3630 , Myton, UT, 84052   | <b>PHONE NUMBER:</b><br>435 646-4825 Ext  |
| <b>9. FIELD and POOL or WILDCAT:</b><br>SOUTH MYTON BENCH  | <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>2098 FNL 0821 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 22 Township: 04.0S Range: 03.0W Meridian: U |
| <b>COUNTY:</b><br>DUCHESNE   | <b>STATE:</b><br>UTAH   |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION   | TYPE OF ACTION   |   |  |
|--|--|---|--|
| <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b><br>Approximate date work will start:<br>11/18/2013 | <input type="checkbox"/> ACIDIZE                       | <input type="checkbox"/> ALTER CASING                   | <input type="checkbox"/> CASING REPAIR                   |
| <input type="checkbox"/> <b>SUBSEQUENT REPORT</b><br>Date of Work Completion:                                  | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS      | <input type="checkbox"/> CHANGE TUBING                  | <input type="checkbox"/> CHANGE WELL NAME                |
| <input type="checkbox"/> <b>SPUD REPORT</b><br>Date of Spud:   | <input type="checkbox"/> CHANGE WELL STATUS            | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE               |
| <input type="checkbox"/> <b>DRILLING REPORT</b><br>Report Date:  | <input type="checkbox"/> DEEPEN                        | <input type="checkbox"/> FRACTURE TREAT                 | <input type="checkbox"/> NEW CONSTRUCTION                |
|  | <input type="checkbox"/> OPERATOR CHANGE               | <input type="checkbox"/> PLUG AND ABANDON               | <input type="checkbox"/> PLUG BACK                       |
|  | <input type="checkbox"/> PRODUCTION START OR RESUME    | <input type="checkbox"/> RECLAMATION OF WELL SITE       | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  |
|  | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL       | <input type="checkbox"/> TEMPORARY ABANDON               |
|  | <input type="checkbox"/> TUBING REPAIR                 | <input type="checkbox"/> VENT OR FLARE                  | <input type="checkbox"/> WATER DISPOSAL                  |
|  | <input type="checkbox"/> WATER SHUTOFF                 | <input type="checkbox"/> SI TA STATUS EXTENSION         | <input checked="" type="checkbox"/> <b>APD EXTENSION</b> |
|  | <input type="checkbox"/> WILDCAT WELL DETERMINATION    | <input type="checkbox"/> OTHER                          | OTHER: <input style="width: 100px;" type="text"/>        |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to extend the Application for Permit to Drill this well.

**Approved by the Utah Division of Oil, Gas and Mining**

**Date:** November 18, 2013

**By:**

|  |                                     |                                 |
|--|-------------------------------------|---------------------------------|
| <b>NAME (PLEASE PRINT)</b><br>Mandie Crozier | <b>PHONE NUMBER</b><br>435 646-4825 | <b>TITLE</b><br>Regulatory Tech |
| <b>SIGNATURE</b><br>N/A                      | <b>DATE</b><br>11/12/2013           |                                 |



**The Utah Division of Oil, Gas, and Mining**

- State of Utah  
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Request for Permit Extension Validation Well Number 43013504540000**

API: 43013504540000

Well Name: UTE TRIBAL 5-22-4-3W

Location: 2098 FNL 0821 FWL QTR SWNW SEC 22 TWNP 040S RNG 030W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/18/2010

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated?  Yes  No
  
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?  Yes  No
  
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?  Yes  No
  
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location?  Yes  No
  
- Has the approved source of water for drilling changed?  Yes  No
  
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?  Yes  No
  
- Is bonding still in place, which covers this proposed well?  Yes  No

Signature: Mandie Crozier

Date: 11/12/2013

Title: Regulatory Tech Representing: NEWFIELD PRODUCTION COMPANY

|   |               |
|---|---------------|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING | <b>FORM 9</b> |
| <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>1420H626154                               |               |
| <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>  |               |
| <b>7. UNIT or CA AGREEMENT NAME:</b>  |               |
| <b>8. WELL NAME and NUMBER:</b><br>UTE TRIBAL 5-22-4-3W                                     |               |
| <b>9. API NUMBER:</b><br>43013504540000   |               |
| <b>9. FIELD and POOL or WILDCAT:</b><br>SOUTH MYTON BENCH                                   |               |
| <b>COUNTY:</b><br>DUCHESNE  |               |
| <b>STATE:</b><br>UTAH   |               |

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

|   |  |
|---|--|
| <b>1. TYPE OF WELL</b><br>Oil Well  |  |
| <b>2. NAME OF OPERATOR:</b><br>NEWFIELD PRODUCTION COMPANY  |  |
| <b>3. ADDRESS OF OPERATOR:</b><br>Rt 3 Box 3630 , Myton, UT, 84052  | <b>PHONE NUMBER:</b><br>435 646-4825 Ext |
| <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>2098 FNL 0821 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 22 Township: 04.0S Range: 03.0W Meridian: U |  |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION   | TYPE OF ACTION   |   |   |
|--|--|---|---|
| <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b><br>Approximate date work will start:<br>11/18/2014 | <input type="checkbox"/> ACIDIZE                       | <input type="checkbox"/> ALTER CASING                   | <input type="checkbox"/> CASING REPAIR  |
| <input type="checkbox"/> <b>SUBSEQUENT REPORT</b><br>Date of Work Completion:                                  | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS      | <input type="checkbox"/> CHANGE TUBING                  | <input type="checkbox"/> CHANGE WELL NAME   |
| <input type="checkbox"/> <b>SPUD REPORT</b><br>Date of Spud:   | <input type="checkbox"/> CHANGE WELL STATUS            | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE  |
| <input type="checkbox"/> <b>DRILLING REPORT</b><br>Report Date:  | <input type="checkbox"/> DEEPEN                        | <input type="checkbox"/> FRACTURE TREAT                 | <input type="checkbox"/> NEW CONSTRUCTION   |
|  | <input type="checkbox"/> OPERATOR CHANGE               | <input type="checkbox"/> PLUG AND ABANDON               | <input type="checkbox"/> PLUG BACK  |
|  | <input type="checkbox"/> PRODUCTION START OR RESUME    | <input type="checkbox"/> RECLAMATION OF WELL SITE       | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION   |
|  | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL       | <input type="checkbox"/> TEMPORARY ABANDON  |
|  | <input type="checkbox"/> TUBING REPAIR                 | <input type="checkbox"/> VENT OR FLARE                  | <input type="checkbox"/> WATER DISPOSAL   |
|  | <input type="checkbox"/> WATER SHUTOFF                 | <input type="checkbox"/> SI TA STATUS EXTENSION         | <input checked="" type="checkbox"/> <b>APD EXTENSION</b><br>OTHER: <input style="width: 100px;" type="text"/> |
|  | <input type="checkbox"/> WILDCAT WELL DETERMINATION    | <input type="checkbox"/> OTHER                          |   |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to extend the Application for Permit to Drill this well.

**Approved by the**  
**November 10, 2014**  
**Oil, Gas and Mining**

**Date:** \_\_\_\_\_  
**By:**

|  |                                     |                                 |
|--|-------------------------------------|---------------------------------|
| <b>NAME (PLEASE PRINT)</b><br>Mandie Crozier | <b>PHONE NUMBER</b><br>435 646-4825 | <b>TITLE</b><br>Regulatory Tech |
| <b>SIGNATURE</b><br>N/A                      | <b>DATE</b><br>11/5/2014            |                                 |



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Request for Permit Extension Validation Well Number 43013504540000**

API: 43013504540000

Well Name: UTE TRIBAL 5-22-4-3W

Location: 2098 FNL 0821 FWL QTR SWNW SEC 22 TWNP 040S RNG 030W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/18/2010

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated?  Yes  No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?  Yes  No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?  Yes  No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location?  Yes  No
- Has the approved source of water for drilling changed?  Yes  No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?  Yes  No
- Is bonding still in place, which covers this proposed well?  Yes  No

Signature: Mandie Crozier

Date: 11/5/2014

Title: Regulatory Tech Representing: NEWFIELD PRODUCTION COMPANY



# United States Department of the Interior



## BUREAU OF LAND MANAGEMENT

Green River District  
Vernal Field Office  
170 South 500 East  
Vernal, UT 84078

<http://www.blm.gov/ut/st/en/fo/vernal.html>

JUN 03 2015

IN REPLY REFER TO:  
3160 (UTG011)

Mandie Crozier  
Newfield Production Company  
Route 3, Box 3630  
Myton, UT 84052

RECEIVED

JUN 05 2015

DIV. OF OIL, GAS & MINING

Dear Mandie:

The referenced Applications for Permit to Drill (APD) have expired. According to our records, no known activity has transpired at the approved location. In view of the foregoing, this office is notifying you that the approval of the referenced applications has expired. If you intend to drill at these locations in the future, a new Application for Permit to Drill must be submitted.

43-

|     | Lease          | Well                        | Aliquot | Sec., T., R.     | Date Rec'd | Date Exp'd |
|-----|----------------|-----------------------------|---------|------------------|------------|------------|
| 013 | UTU-096550     | GMBU 8A-14-9-16 50879       | NESE    | Sec. 14-T9S-R16E | 7/12/2011  | 12/14/2013 |
| 013 | UTU-15855      | GMBU D-25-9-16 52510        | SESW    | Sec. 24-T9S-R16E | 10/25/2013 | 3/25/2015  |
| 013 | 14-20-H62-6068 | Daisy 13-23-14-3-3WH 51502  | NWNW    | Sec. 26-T3S-R3W  | 6/5/2012   | 1/6/2015   |
| 013 | 14-20-H62-6154 | Ute Tribal 3-22-4-3W 50453  | NENW    | Sec. 22-T4S-R3W  | 11/1/2010  | 3/21/2015  |
| 013 | 14-20-H62-6154 | Ute Tribal 5-22-4-3W 50454  | SWNW    | Sec. 22-T4S-R3W  | 11/1/2010  | 3/21/2015  |
| 013 | 14-20-H62-6222 | Forest 1-2-4-3WH 51398      | Lot 1   | Sec. 2-T4S-R3W   | 6/11/2012  | 10/1/2014  |
| 047 | 14-20-H62-6277 | Ute Tribal 4-11-4-1E 51292  | NWNW    | Sec. 11-T4S-R1E  | 10/1/2010  | 2/3/2015   |
| 047 | 14-20-H62-6277 | Ute Tribal 6-11-4-1E 51293  | NWNW    | Sec. 11-T4S-R1E  | 10/2/2010  | 2/3/2015   |
| 047 | 14-20-H62-6277 | Ute Tribal 12-11-4-1E 51312 | NWSW    | Sec. 11-T4S-R1E  | 10/14/2010 | 2/3/2015   |
| 047 | 14-20-H62-6387 | Ute Tribal 8-10-4-1E 51314  | SENE    | Sec. 10-T4S-R1E  | 10/14/2010 | 2/3/2015   |
| 047 | 14-20-H62-6404 | Ute Tribal 12-7-4-2W 50413  | Lot 3   | Sec. 7-T4S-R2W   | 8/2/2010   | 1/27/2015  |
| 013 | 14-20-H62-6424 | Ute Tribal 13-7-4-1W 50434  | SESW    | Sec. 7-T4S-R1W   | 10/6/2010  | 2/22/2015  |
| 013 | 14-20-H62-6424 | Ute Tribal 14-7-4-1W 50410  | SESW    | Sec. 7-T4S-R1W   | 8/2/2010   | 1/27/2015  |

This office requires a letter confirming that no surface disturbance has been made for these drill sites. Any surface disturbance associated with the approved location of these wells is to be rehabilitated. A schedule for this rehabilitation must be submitted to this office. Your cooperation in this matter is appreciated.

If you have any questions regarding this matter, please contact Robin R. Hansen at (435) 781-3428.

Sincerely,

/s/ Jerry Kenczka

Jerry Kenczka  
Assistant Field Manager  
Lands & Mineral Resources

cc: UDOGM

bcc: Well File  
I&E Asst.



GARY R. HERBERT  
Governor

SPENCER J. COX  
Lieutenant Governor

# State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

November 12, 2015

Mandie Crozier  
Newfield Production Company  
Rt 3 Box 3630  
Myton, UT 84052

Re: APDs Rescinded for Newfield Production Company,  
Duchesne and Uintah County


Dear Ms. Crozier:

Enclosed find the list of APDs that you asked to be rescinded. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded effective November 10, 2015

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

  
Diana Mason  
Environmental Scientist

cc: Well File  
Bureau of Land Management, Vernal



43-047-51292 UTE TRIBAL 4-11-4-1E  
43-047-51293 UTE TRIBAL 6-11-4-1E  
43-047-51312 UTE TRIBAL 12-11-4-1E  
43-047-51314 UTE TRIBAL 8-10-4-1E  
43-047-54781 UTE TRIBAL 8-24-4-1E  
43-013-50453 UTE TRIBAL 3-22-4-3W  
43-013-50454 UTE TRIBAL 5-22-4-3W