

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER 7-4D-45 BTR				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT ALTAMONT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR BILL BARRETT CORP						7. OPERATOR PHONE 303 312-8164				
8. ADDRESS OF OPERATOR 1099 18th Street Ste 2300, Denver, CO, 80202						9. OPERATOR E-MAIL BHilgers@billbarrettcorp.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) 1420H626281			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') Uintah and Ouray			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		2338 FNL 2002 FEL		SWNE	4	4.0 S	5.0 W	U		
Top of Uppermost Producing Zone		1979 FNL 1980 FEL		SWNE	4	4.0 S	5.0 W	U		
At Total Depth		1979 FNL 1979 FEL		SWNE	4	4.0 S	5.0 W	U		
21. COUNTY DUCHESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 1979			23. NUMBER OF ACRES IN DRILLING UNIT 640				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 2541			26. PROPOSED DEPTH MD: 9735 TVD: 9714				
27. ELEVATION - GROUND LEVEL 5794			28. BOND NUMBER LPM8874725			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Duchesne City Culinary Water Dock				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Cond	26	16	0 - 80	65.0	Unknown	8.8	Unknown	0	0.0	0.0
Surf	14.75	10.75	0 - 2500	45.5	J-55 ST&C	8.8	Halliburton Light , Type Unknown	630	3.16	11.0
							Halliburton Premium , Type Unknown	360	1.36	14.8
Prod	9.875	5.5	0 - 9735	17.0	P-110 LT&C	9.7	Unknown	1070	2.31	11.0
							Unknown	1270	1.42	13.5
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Venessa Langmacher			TITLE Senior Permit Analyst			PHONE 303 312-8172				
SIGNATURE			DATE 07/12/2011			EMAIL vlangmacher@billbarrettcorp.com				
API NUMBER ASSIGNED 43013508840000			APPROVAL			 Permit Manager				

DRILLING PLAN

BILL BARRETT CORPORATION

7-4D-45 BTR Well Pad

SW NE, 2338' FNL and 2002' FEL, Section 4, T4S, R5W, USB&M (surface hole)

SW NE, 1979' FNL and 1979' FEL, Section 4, T4S, R5W, USB&M (bottom hole)

Duchesne County, UT

1 - 2. Estimated Tops of Geological Markers and Formations Expected to Contain Water, Oil and Gas and Other Minerals

<u>Formation</u>	<u>Depth – MD</u>	<u>Depth – TVD</u>
Lower Green River*	5,178'	5,164'
Douglas Creek	6,070'	6,049'
Black Shale	6,985'	6,964'
Castle Peak	7,125'	7,104'
Uteland Butte	7,435'	7,414'
Wasatch*	7,670'	7,649'
TD	9,735'	9,714'

*PROSPECTIVE PAY

Members of the Wasatch and the Lower Green River are primary objectives for oil/gas.

The Base of Useable Water = 5,600'

3. BOP and Pressure Containment Data

<u>Depth Intervals</u>	<u>BOP Equipment</u>
0 – 2,500'	No pressure control required
2,500' – TD	11" 5000# Ram Type BOP 11" 5000# Annular BOP
- Drilling spool to accommodate choke and kill lines;	
- Ancillary equipment and choke manifold rated at 5,000 psi. All BOP and BOPE tests will be in accordance with the requirements of onshore Order No. 2;	
- The BLM and the State of Utah Division of Oil, Gas and Mining will be notified 24 hours in advance of all BOP pressure tests.	
- BOP hand wheels may be underneath the sub-structure of the rig if the drilling rig used is set up To operate most efficiently in this manner.	

4. Casing Program

<u>Hole Size</u>	<u>SETTING DEPTH</u>		<u>Casing Size</u>	<u>Casing Weight</u>	<u>Casing Grade</u>	<u>Thread</u>	<u>Condition</u>
	<u>(FROM)</u>	<u>(TO)</u>					
26"	Surface	80'	16"	65#			
14 3/4"	Surface	2,500'	10-3/4"	45.5#	J or K 55	BT&C	New
9-7/8" & 8-3/4"	Surface	TD	5 1/2"	17#	P-110	LT&C	New

NOTE: If necessary due to lost circulation, BBC would like to request the option to set 7-5/8", 33.70# P-110 LT&C to a depth of 6000', then drill a 6-1/2" hole to TD and run 5-1/2" casing as a 2000' liner (200' liner lap).

Bill Barrett Corporation
 Drilling Program
 #7-4D-45 BTR
 Duchesne County, Utah

5. **Cementing Program**

<u>Casing</u>	<u>Cement</u>
16" Conductor Casing	Grout
14-3/4" hole for 10-3/4" Surface Casing	<p><i>Lead</i> with approximately 630 sx Halliburton Light Premium with additives mixed at 11.0 ppg (yield = 3.16 ft³/sx) circulated to surface with 75% excess. Planned top of lead cement at surface.</p> <p><i>Tail</i> with approximately 360 sx Halliburton Premium cement with additives mixed at 14.8 ppg (yield = 1.36 ft³/sx). Calculated hole volume with 75% excess. Planned top of tail cement at 2,000'.</p>
9-7/8 hole for 5 1/2" Production Casing May reduce hole size to 8-3/4" at 6000' if minimal hole problems.	<p><i>Lead</i> with approximately 1070 sx Tuned Light cement with additives mixed at 11.0 ppg (yield = 2.31 ft³/sx). Planned top of lead cement at 2,000'</p> <p><i>Tail</i> with approximately 1270 sx Halliburton Econocem cement with additives mixed at 13.5 ppg (yield = 1.42 ft³/sx). Planned top of tail cement at 6,485'.</p>
<p>NOTE: If 7-5/8" casing is necessary, cement with Lead with approximately 700 sx Tuned Light cement with additives mixed at 11.0 ppg (yield = 2.31 ft³/sx). Tail with approximately 240 sx Halliburton Econocem cement with additives mixed at 13.5 ppg (yield = 1.42 ft³/sx). Planned TOC surface. We will perform a FIT to 10.2 ppg after drilling 20' of new hole.</p> <p>The 5-1/2" liner would be cemented with 300 sx of Class G 50/50 Poz w/ 2% gel (14.2 ppg) with additives from TD to 200' above TOL.</p>	

6. **Mud Program**

<u>Interval</u>	<u>Weight</u>	<u>Viscosity</u>	<u>Fluid Loss (API filtrate)</u>	<u>Remarks</u>
0' – 80'	8.3 – 8.8	26 – 36	NC	Freshwater Spud Mud Fluid System
80' – 2,500'	8.3 – 8.8	26 – 36	NC	Freshwater Spud Mud Fluid System
2,500' – TD	8.6 – 9.7	42 – 52	20 cc or less	DAP Polymer Fluid System
<p>Note: Sufficient mud materials to maintain mud properties, control lost circulation and to contain "kicks" will be available at wellsite. BBC may require minor amounts of diesel to be added to its fluid system in order to reduce torque and drag.</p>				

Bill Barrett Corporation
 Drilling Program
 #7-4D-45 BTR
 Duchesne County, Utah

7. Testing, Logging and Core Programs

Cores	None anticipated
Testing	None anticipated; drill stem tests may be run on shows of interest;
Sampling	30' to 50' samples; surface casing to TD. Preserve samples all show intervals;
Surveys	MWD as needed to land wellbore;
Logging	DIL-GR-SP, FDC-CNL-GR-CALIPER-Pe-Microlog, Sonic-GR (all TD to surface). FMI & Sonic Scanner to be run at geologist's discretion.
NOTE: If BBC pursues the "Alternate" program, a suite of the above logs will be run on both the intermediate and production hole sections.	

8. Anticipated Abnormal Pressures or Temperatures

No abnormal pressures or temperatures or other hazards are anticipated.

Maximum anticipated bottom hole pressure equals approximately 4900 psi* and maximum anticipated surface pressure equals approximately 2763 psi** (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

*Max Mud Wt x 0.052 x TD = A (bottom hole pressure)

**Maximum surface pressure = A - (0.22 x TD)

9. Auxiliary Equipment

- a) Upper kelly cock; lower Kelly cock will be installed while drilling
- b) Inside BOP or stab-in valve (available on rig floor)
- c) Safety valve(s) and subs to fit all string connections in use
- d) Mud monitoring will be visually observed

10. Location and Type of Water Supply

Water for the drilling and completion will be trucked from the Duchesne City Culinary Water Dock located in Sec. 1, T4S, R5W.

11. Drilling Schedule

Location Construction: January 2012
 Spud: January 2012
 Duration: 15 days drilling time
 45 days completion time

PRESSURE CONTROL EQUIPMENT – Schematic Attached

A. Type: Eleven (11) Inch Double Gate Hydraulic BOP with Eleven (11) Inch Annular Preventer. The blow out preventer will be equipped as follows:

1. One (1) blind ram (above).
2. One (1) pipe ram (below).
3. Drilling spool with two (2) side outlets (choke side 3-inch minimum, kill side 2-inch minimum).
4. 3-inch diameter choke line.
5. Two (2) choke line valves (3-inch minimum).
6. Kill line (2-inch minimum).
7. Two (2) chokes with one (1) remotely controlled from the rig floor.
8. Two (2) kill line valves, and a check valve (2-inch minimum).
9. Upper and lower kelly cock valves with handles available.
10. Safety valve(s) & subs to fit all drill string connections in use.
11. Inside BOP or float sub available.
12. Pressure gauge on choke manifold.
13. Fill-up line above the uppermost preventer.

B. Pressure Rating: 5,000 psi

C. Testing Procedure:

Annular Preventer

At a minimum, the Annular Preventer will be pressure tested to 50% of the rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition, the Annular Preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be

maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

D. Choke Manifold Equipment:

All choke lines will be straight lines unless turns use tee blocks or are targeted with running tees, and will be anchored to prevent whip and vibration.

E. Accumulator:

The accumulator will have sufficient capacity to open the hydraulically-controlled choke line valve (if so equipped), close all rams plus the annular preventer, and retain a minimum of 200 psi above precharge on the closing manifold without the use of closing unit pumps. The fluid reservoir capacity will be double the usable fluid volume of the accumulator system capacity and the fluid level of the reservoir will be maintained at the manufacturer's recommendations.

The BOP system will have two (2) independent power sources to close the preventers. Nitrogen bottles (3 minimum) will be one (1) of these independent power sources and will maintain a charge equal to the manufacturer's specifications.

The accumulator precharge pressure test will be conducted prior to connecting the closing unit to the BOP stack and at least once every six (6) months thereafter. The accumulator pressure will be corrected if the measured precharge pressure is found to be above or below the maximum or minimum limits specified in the *Onshore Oil & Gas Order Number 2*.

A manual locking device (i.e. hand wheels) or automatic locking device will be installed on all systems of 2M or greater. A valve will be installed in the closing line as close as possible to the annular preventer to act as a locking device. This valve will be maintained in the open position and will be closed only when the power source for the accumulator is inoperative.

Remote controls shall be readily accessible to the driller. Remote controls for all 3M or greater systems will be capable of closing all preventers. Remote controls for 5M or greater systems will be capable of both opening and closing all preventers. Master controls will be at the accumulator and will be capable of opening and closing all preventers and the choke line valve (if so equipped).

F. Miscellaneous Information:

The Blow-Out Preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*. The hydraulic BOP closing unit will be located at least twenty-five (25) feet from the well head but readily accessible to the driller. Exact locations and configurations of the hydraulic BOP closing unit will depend upon the particular rig contracted to drill this hole.

A flare line will be installed after the choke manifold, extending 125 feet (minimum) from the center of the drill hole to a separate flare pit.



Bill Barrett Corporation

LAKE CANYON & BLACK TAIL RIDGE CEMENT VOLUMES

AS OF: 2/18/2011

Well Name: 7-4D-45 BTR

Surface Hole Data:

Total Depth:	2,500'
Top of Cement:	0'
OD of Hole:	14.750"
OD of Casing:	10.750"

Calculated Data:

Lead Volume:	1947.1	ft ³
Lead Fill:	2,000'	
Tail Volume:	486.8	ft ³
Tail Fill:	500'	

Cement Data:

Lead Yield:	3.16	ft ³ /sk
% Excess:	75%	
Top of Lead:	0'	

Calculated # of Sacks:

# SK's Lead:	630
--------------	-----

Tail Yield:	1.36	ft ³ /sk
% Excess:	75%	
Top of Tail:	2,000'	

# SK's Tail:	360
--------------	-----

Production Hole Data:

Total Depth:	9,735'
Top of Cement:	2,000'
Top of Tail:	6,485'
OD of Hole:	9.875"
OD of Casing:	5.500"

Calculated Data:

Lead Volume:	2468.1	ft ³
Lead Fill:	4,485'	
Tail Volume:	1788.7	ft ³
Tail Fill:	3,250'	

Cement Data:

Lead Yield:	2.31	ft ³ /sk
Tail Yield:	1.42	ft ³ /sk
% Excess:	50%	

Calculated # of Sacks:

# SK's Lead:	1070
# SK's Tail:	1270

7-4D-45 BTR Proposed Cementing Program


<u>Job Recommendation</u>	<u>Surface Casing</u>
Lead Cement - (2000' - 0')	
Halliburton Light Premium	Fluid Weight: 11.0 lbm/gal
5.0 lbm/sk Silicalite Compacted	Slurry Yield: 3.16 ft ³ /sk
0.25 lbm/sk Kwik Seal	Total Mixing Fluid: 19.48 Gal/sk
0.125 lbm/sk Poly-E-Flake	Top of Fluid: 0'
2.0% Bentonite	Calculated Fill: 2,000'
	Volume: 346.77 bbl
	Proposed Sacks: 630 sks
Tail Cement - (TD - 2000')	
Premium Cement	Fluid Weight: 14.8 lbm/gal
2.0% Calcium Chloride	Slurry Yield: 1.36 ft ³ /sk
	Total Mixing Fluid: 6.37 Gal/sk
	Top of Fluid: 2,000'
	Calculated Fill: 500'
	Volume: 86.69 bbl
	Proposed Sacks: 360 sks

<u>Job Recommendation</u>	<u>Production Casing</u>
Lead Cement - (6485' - 2000')	
Tuned Light™ System	Fluid Weight: 11.0 lbm/gal
	Slurry Yield: 2.31 ft ³ /sk
	Total Mixing Fluid: 10.65 Gal/sk
	Top of Fluid: 2,000'
	Calculated Fill: 4,485'
	Volume: 439.56 bbl
	Proposed Sacks: 1070 sks
Tail Cement - (9735' - 6485')	
Econocem™ System	Fluid Weight: 13.5 lbm/gal
0.125 lbm/sk Poly-E-Flake	Slurry Yield: 1.42 ft ³ /sk
1.0 lbm/sk Granulite TR 1/4	Total Mixing Fluid: 6.61 Gal/sk
	Top of Fluid: 6,485'
	Calculated Fill: 3,250'
	Volume: 318.55 bbl
	Proposed Sacks: 1270 sks

T4S, R5W, U.S.B.&M.

BILL BARRETT CORPORATION

Well location, #7-4D-45 BTR, located as shown in the SW 1/4 NE 1/4 of Section 4, T4S, R5W, U.S.B.&M., Duchesne County, Utah.



S89°53'45"W - 2636.61' (Meas.)

S89°53'47"W - 2635.59' (Meas.)

T3S

T4S

1983 Brass Cap, 1.4' High, Pile of Stones, Steel Post

Lot 1

1979'

2338'

Legal Window

Bottom Hole

1979'

2002'

N00°13'54"W - 5310.43' (Meas.)

1979 Alum. Cap, 1.8' High, Set Marked Stone, Steel Post

Lot 2

Lot 3

1983 Brass Cap, 1.8' High, Pile of Stones

Lot 4

1983 Alum. Cap, 1.0' High, Set of Stones, Steel Post

Set. Marked Stone

N00°13'51"W - 2612.93' (Meas.)

N00°13'4"E - 2655.40' (Meas.)

N89°38'51"W - 5284.44' (Meas.)

#7-4D-45 BTR


Elev. Ungraded Ground = 5794'

4

BASIS OF ELEVATION

BENCH MARK (M67) LOCATED IN THE SW 1/4 OF SECTION 9, T5S, R4W, U.S.B.&M., TAKEN FROM THE DUCHESNE SE, QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 6097 FEET.

LINE	DIRECTION	LENGTH
L1	N03°33'16"E	359.83'



CERTIFICATE


THIS IS TO CERTIFY THAT THE ABOVE POINT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY CLOSE SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ROBERT K. KAY
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING	
85 SOUTH 200 EAST - VERNAL, UTAH 84078 (435) 789-1017	
SCALE 1" = 1000'	DATE SURVEYED: 11-19-10
PARTY T.A. C.N. K.G.	DATE DRAWN: 12-02-10
WEATHER COOL	REFERENCES G.L.O. PLAT
	FILE BILL BARRETT CORPORATION

LEGEND:

- = 90° SYMBOL
 - = PROPOSED WELL HEAD.
 - ▲ = SECTION CORNERS LOCATED.
 - △ = SECTION CORNERS RE-ESTABLISHED.
(Not Set on Ground.)
- BASIS OF BEARINGS IS A G.P.S. OBSERVATION.
- | NAD 83 (TARGET BOTTOM HOLE) | NAD 83 (SURFACE LOCATION) |
|--|--|
| LATITUDE = 40°09'50.14" (40.163928) | LATITUDE = 40°09'46.59" (40.162942) |
| LONGITUDE = 110°27'10.47" (110.452908) | LONGITUDE = 110°27'10.75" (110.452986) |
| NAD 27 (TARGET BOTTOM HOLE) | NAD 27 (SURFACE LOCATION) |
| LATITUDE = 40°09'50.29" (40.163969) | LATITUDE = 40°09'46.74" (40.162983) |
| LONGITUDE = 110°27'07.91" (110.452197) | LONGITUDE = 110°27'08.19" (110.452275) |



LEGEND:

 PROPOSED LOCATION



BILL BARRETT CORPORATION

#7-4D-45 BTR
SECTION 4, T4S, R5W, U.S.B.&M.
2338' FNL 2002' FEL




Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

12 15 10
 MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: Z.L. REVISED: 00-00-00





LEGEND:

-  EXISTING ROAD
-  PROPOSED ACCESS ROAD
-  18" CMP REQUIRED
-  LOW WATER CROSSING

BILL BARRETT CORPORATION


#7-4D-45 BTR
 SECTION 4, T4S, R5W, U.S.B.&M.
 2338' FNL 2002' FEL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC 12 15 10
MAP MONTH DAY YEAR
 SCALE: 1" = 2000' DRAWN BY: Z.L. REVISED: 06-22-11





APPROXIMATE TOTAL PIPELINE DISTANCE = 339' +/-

LEGEND:

-  PROPOSED ACCESS ROAD
-  EXISTING PIPELINE
-  EXISTING POWER LINE
-  PROPOSED PIPELINE

BILL BARRETT CORPORATION

#7-4D-45 BTR
SECTION 4, T4S, R5W, U.S.B.&M.
2338' FNL 2002' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
MAP

12	15	10
MONTH	DAY	YEAR

SCALE: 1" = 1000' DRAWN BY: Z.L. REVISED: 00-00-00





APPROXIMATE TOTAL POWER LINE DISTANCE = 346' +/-

LEGEND:

-  PROPOSED ACCESS ROAD
-  EXISTING POWER LINE
-  PROPOSED POWER LINE

BILL BARRETT CORPORATION

#7-4D-45 BTR
 SECTION 4, T4S, R5W, U.S.B.&M.
 2338' FNL 2002' FEL

U&L S Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP 12 15 10
 MONTH DAY YEAR
 SCALE: 1" = 1000' DRAWN BY: Z.L. REVISED: 00-00-00 **D TOPO**

Project: Duchesne County, UT (NAD 1927)

Site: Sec. 4-T4S-R5W

Well: #7-4D-45 BTR

Wellbore: Plan A Rev 0

Plan: Plan A Rev 0 Proposal

Bill Barrett Corp

HALLIBURTON

Sperry Drilling

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N-S	+E-W	DLeg	TFace	VSec
1	0.00	0.000	0.000	0.00	-0.01	0.00	0.00	0.00	0.00
2	2600.00	0.000	0.000	2600.00	-0.01	0.00	0.00	0.00	0.00
3	3034.30	0.000	0.000	3034.30	-0.01	0.00	0.00	0.00	0.00
4	3384.30	7.000	3.473	3383.43	21.31	1.29	2.00	3.47	21.35
5	5928.33	7.000	3.473	5908.49	330.78	20.08	0.00	0.00	331.39
6	6394.99	0.000	0.000	6374.00	359.19	21.80	1.50	180.00	359.86
7	6494.99	0.000	0.000	6474.00	359.19	21.80	0.00	0.00	359.86
8	9734.99	0.000	0.000	9714.00	359.19	21.80	0.00	0.00	359.86

WELL DETAILS: #7-4D-45 BTR



Ground Level:	5793.00	Latitude	40° 9' 46.739 N	Longitude	110° 27' 8.190 W
Northing	668127.03	Easting	2292810.91		

WELLBORE TARGET DETAILS

Name	TVD	+N-S	+E-W	Latitude	Longitude	Shape
#7-4D-45 BTR_SHL	0.00	0.00	0.00	40° 9' 46.739 N	110° 27' 8.190 W	
#7-4D-45 BTR_ZONE Tgt	6474.00	359.19	21.80	40° 9' 50.288 N	110° 27' 7.909 W	Rectangle L200.00 W200.00
#7-4D-45 BTR_BHL Tgt	9714.00	359.19	21.80	40° 9' 50.288 N	110° 27' 7.909 W	Point

FORMATION TOP DETAILS

TVDPath	MDPath	Formation
3059.00	3059.00	GREEN_RIVER
5164.00	5178.24	TGR3
6049.00	6069.60	DOUGLAS_CRK
6474.00	6494.99	3PT_MKR
6964.00	6984.99	BLACK_SHALE_FACIES
7104.00	7124.99	CASTLE_PEAK
7414.00	7434.99	UTELAND_BUTTE
7474.00	7494.99	CR_1
7649.00	7669.99	WASATCH
7799.00	7819.99	CR_2
8044.00	8064.99	CR_3
8374.00	8394.99	CR_4
8659.00	8679.99	CR_4A
8784.00	8804.99	CR_5
8954.00	8974.99	CR_6
9214.00	9234.99	CR_7
9714.00	9734.99	TD



ANNOTATIONS

TVD	MD	Annotation
0.00	0.00	RKB 16' EL=5809 (Patterson 506)
3034.30	3034.30	Kickoff at 3034.30 ft
3199.91	3200.00	Build Rate = 2.00°/100 ft
3383.43	3384.30	End Build at 3384.30 ft
4590.07	4600.00	Hold INC at 7.000°
5908.50	5928.33	Begin Drop at 5928.33 ft
6179.09	6200.00	Drop Rate = 1.50°/100 ft
6374.00	6394.99	End Drop at 6394.99ft
9714.00	9734.99	Total Depth = 9734.99 ft

PROJECT DETAILS: Duchesne County, UT (NAD 1927)

Geodetic System: US State Plane 1927 (Exact solution)
 Datum: NAD 1927 (NADCON CONUS)
 Ellipsoid: Clarke 1866
 Zone: Utah Central 4302
 System Datum: Mean Sea Level

Plan A Rev 0 Proposal (#7-4D-45 BTR)

Created By: Jerry Popp Date: 06/17/2011
 Checked: _____ Date: _____
 Reviewed: _____ Date: _____
 Approved: _____ Date: _____

Plan Report for #7-4D-45 BTR - Plan A Rev 0 Proposal

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
0.00	0.000	0.000	0.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
RKB 16' EL=5809 (Patterson 506)										
100.00	0.000	0.000	100.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.000	0.000	200.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.000	0.000	300.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.000	0.000	400.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.000	0.000	500.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.000	0.000	600.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.000	0.000	700.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.000	0.000	800.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.000	0.000	900.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.000	0.000	1,000.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.000	0.000	1,100.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.000	0.000	1,200.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.000	0.000	1,300.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.000	0.000	1,400.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.000	0.000	1,500.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.000	0.000	1,600.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.000	0.000	1,700.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.000	0.000	1,800.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.000	0.000	1,900.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.000	0.000	2,000.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.000	0.000	2,100.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.000	0.000	2,200.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.000	0.000	2,300.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.000	0.000	2,400.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.000	0.000	2,500.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
10 3/4" Casing Pt.										
2,600.00	0.000	0.000	2,600.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.000	0.000	2,700.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.000	0.000	2,800.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.000	0.000	2,900.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.000	0.000	3,000.00	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
3,034.30	0.000	0.000	3,034.30	-0.01	0.00	0.00	0.00	0.00	0.00	0.00
Kickoff at 3034.30 ft										
3,059.00	0.494	3.473	3,059.00	0.10	0.01	0.11	2.00	2.00	0.00	3.47
GREEN_RIVER										
3,100.00	1.314	3.473	3,099.99	0.74	0.05	0.75	2.00	2.00	0.00	0.00
3,200.00	3.314	3.473	3,199.91	4.77	0.29	4.79	2.00	2.00	0.00	0.00
Build Rate = 2.00°/100 ft										
3,300.00	5.314	3.473	3,299.62	12.28	0.75	12.31	2.00	2.00	0.00	0.00
3,384.30	7.000	3.473	3,383.43	21.31	1.29	21.35	2.00	2.00	0.00	0.00
End Build at 3384.30 ft										
3,400.00	7.000	3.473	3,399.01	23.22	1.41	23.27	0.00	0.00	0.00	0.00
3,500.00	7.000	3.473	3,498.27	35.38	2.15	35.45	0.00	0.00	0.00	0.00
3,600.00	7.000	3.473	3,597.52	47.54	2.89	47.64	0.00	0.00	0.00	0.00
3,700.00	7.000	3.473	3,696.78	59.71	3.62	59.83	0.00	0.00	0.00	0.00
3,800.00	7.000	3.473	3,796.03	71.87	4.36	72.01	0.00	0.00	0.00	0.00
3,900.00	7.000	3.473	3,895.29	84.04	5.10	84.20	0.00	0.00	0.00	0.00
4,000.00	7.000	3.473	3,994.54	96.20	5.84	96.39	0.00	0.00	0.00	0.00
4,100.00	7.000	3.473	4,093.80	108.37	6.58	108.58	0.00	0.00	0.00	0.00
4,200.00	7.000	3.473	4,193.05	120.53	7.32	120.76	0.00	0.00	0.00	0.00
4,300.00	7.000	3.473	4,292.30	132.70	8.05	132.95	0.00	0.00	0.00	0.00
4,400.00	7.000	3.473	4,391.56	144.86	8.79	145.14	0.00	0.00	0.00	0.00
4,500.00	7.000	3.473	4,490.81	157.03	9.53	157.32	0.00	0.00	0.00	0.00
4,600.00	7.000	3.473	4,590.07	169.19	10.27	169.51	0.00	0.00	0.00	0.00
Hold INC at 7.000°										

Plan Report for #7-4D-45 BTR - Plan A Rev 0 Proposal

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Tooface Azimuth (°)
4,700.00	7.000	3.473	4,689.32	181.35	11.01	181.70	0.00	0.00	0.00	0.00
4,800.00	7.000	3.473	4,788.58	193.52	11.75	193.88	0.00	0.00	0.00	0.00
4,900.00	7.000	3.473	4,887.83	205.68	12.48	206.07	0.00	0.00	0.00	0.00
5,000.00	7.000	3.473	4,987.09	217.85	13.22	218.26	0.00	0.00	0.00	0.00
5,100.00	7.000	3.473	5,086.34	230.01	13.96	230.44	0.00	0.00	0.00	0.00
5,178.24	7.000	3.473	5,164.00	239.53	14.54	239.98	0.00	0.00	0.00	0.00
TGR3										
5,200.00	7.000	3.473	5,185.60	242.18	14.70	242.63	0.00	0.00	0.00	0.00
5,300.00	7.000	3.473	5,284.85	254.34	15.44	254.82	0.00	0.00	0.00	0.00
5,400.00	7.000	3.473	5,384.11	266.51	16.18	267.01	0.00	0.00	0.00	0.00
5,500.00	7.000	3.473	5,483.36	278.67	16.91	279.19	0.00	0.00	0.00	0.00
5,600.00	7.000	3.473	5,582.61	290.84	17.65	291.38	0.00	0.00	0.00	0.00
5,700.00	7.000	3.473	5,681.87	303.00	18.39	303.57	0.00	0.00	0.00	0.00
5,800.00	7.000	3.473	5,781.12	315.16	19.13	315.75	0.00	0.00	0.00	0.00
5,900.00	7.000	3.473	5,880.38	327.33	19.87	327.94	0.00	0.00	0.00	0.00
5,928.33	7.000	3.473	5,908.50	330.78	20.08	331.39	0.00	0.00	0.00	0.00
Begin Drop at 5928.33 ft										
6,000.00	5.925	3.473	5,979.71	338.83	20.56	339.46	1.50	-1.50	0.00	180.00
6,069.60	4.881	3.473	6,049.00	345.37	20.96	346.01	1.50	-1.50	0.00	180.00
DOUGLAS_CRK										
6,100.00	4.425	3.473	6,079.30	347.83	21.11	348.48	1.50	-1.50	0.00	-180.00
6,200.00	2.925	3.473	6,179.09	354.23	21.50	354.89	1.50	-1.50	0.00	-180.00
Drop Rate = 1.50°/100 ft										
6,300.00	1.425	3.473	6,279.02	358.02	21.73	358.68	1.50	-1.50	0.00	180.00
6,394.99	0.000	0.000	6,374.00	359.19	21.80	359.86	1.50	-1.50	-3.66	-180.00
End Drop at 6394.99ft										
6,400.00	0.000	0.000	6,379.01	359.19	21.80	359.86	0.00	0.00	0.00	180.00
6,494.99	0.000	0.000	6,474.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
3PT_MKR - #7-4D-45 BTR_ZONE Tgt										
6,500.00	0.000	0.000	6,479.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
6,600.00	0.000	0.000	6,579.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
6,700.00	0.000	0.000	6,679.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
6,800.00	0.000	0.000	6,779.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
6,900.00	0.000	0.000	6,879.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
6,984.99	0.000	0.000	6,964.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
BLACK_SHALE_FACIES										
7,000.00	0.000	0.000	6,979.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,100.00	0.000	0.000	7,079.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,124.99	0.000	0.000	7,104.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CASTLE_PEAK										
7,200.00	0.000	0.000	7,179.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,300.00	0.000	0.000	7,279.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,400.00	0.000	0.000	7,379.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,434.99	0.000	0.000	7,414.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
UTELAND_BUTTE										
7,494.99	0.000	0.000	7,474.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CR_1										
7,500.00	0.000	0.000	7,479.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,600.00	0.000	0.000	7,579.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,669.99	0.000	0.000	7,649.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
WASATCH										
7,700.00	0.000	0.000	7,679.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,800.00	0.000	0.000	7,779.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
7,819.99	0.000	0.000	7,799.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CR_2										
7,900.00	0.000	0.000	7,879.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,000.00	0.000	0.000	7,979.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,064.99	0.000	0.000	8,044.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00

Plan Report for #7-4D-45 BTR - Plan A Rev 0 Proposal

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
CR_3										
8,100.00	0.000	0.000	8,079.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,200.00	0.000	0.000	8,179.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,300.00	0.000	0.000	8,279.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,394.99	0.000	0.000	8,374.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CR_4										
8,400.00	0.000	0.000	8,379.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,500.00	0.000	0.000	8,479.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,600.00	0.000	0.000	8,579.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,679.99	0.000	0.000	8,659.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CR_4A										
8,700.00	0.000	0.000	8,679.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,800.00	0.000	0.000	8,779.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,804.99	0.000	0.000	8,784.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CR_5										
8,900.00	0.000	0.000	8,879.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
8,974.99	0.000	0.000	8,954.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CR_6										
9,000.00	0.000	0.000	8,979.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,100.00	0.000	0.000	9,079.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,200.00	0.000	0.000	9,179.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,234.99	0.000	0.000	9,214.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
CR_7										
9,300.00	0.000	0.000	9,279.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,400.00	0.000	0.000	9,379.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,500.00	0.000	0.000	9,479.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,600.00	0.000	0.000	9,579.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,700.00	0.000	0.000	9,679.01	359.19	21.80	359.86	0.00	0.00	0.00	0.00
9,734.99	0.000	0.000	9,714.00	359.19	21.80	359.86	0.00	0.00	0.00	0.00
Total Depth = 9734.99 ft - #7-4D-45 BTR_BHL Tgt										

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
0.00	0.00	-0.01	0.00	RKB 16' EL=5809 (Patterson 506)
3,034.30	3,034.30	-0.01	0.00	Kickoff at 3034.30 ft
3,200.00	3,199.91	4.77	0.29	Build Rate = 2.00°/100 ft
3,384.30	3,383.43	21.31	1.29	End Build at 3384.30 ft
4,600.00	4,590.07	169.19	10.27	Hold INC at 7.000°
5,928.33	5,908.50	330.78	20.08	Begin Drop at 5928.33 ft
6,200.00	6,179.09	354.23	21.50	Drop Rate = 1.50°/100 ft
6,394.99	6,374.00	359.19	21.80	End Drop at 6394.99ft
9,734.99	9,714.00	359.19	21.80	Total Depth = 9734.99 ft

Vertical Section Information

Angle Type	Target	Azimuth (°)	Origin Type	Origin		Start TVD (ft)
				+N/-S (ft)	+E/-W (ft)	
Target	#7-4D-45 BTR_BHL Tgt	3.473	Slot	-0.01	0.00	0.00

Survey tool program

From (ft)	To (ft)	Survey/Plan	Survey Tool
0.00	9,734.99	Plan A Rev 0 Proposal	MWD

Plan Report for #7-4D-45 BTR - Plan A Rev 0 Proposal**Casing Details**

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")
2,500.00	2,500.00	10 3/4" Casing Pt.	10-3/4	12-1/4

Formation Details

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
3,059.00	3,059.00	GREEN_RIVER			
5,178.24	5,164.00	TGR3			
6,069.60	6,049.00	DOUGLAS_CRK			
6,494.99	6,474.00	3PT_MKR			
6,984.99	6,964.00	BLACK_SHALE_FACIES			
7,124.99	7,104.00	CASTLE_PEAK			
7,434.99	7,414.00	UTELAND_BUTTE			
7,494.99	7,474.00	CR_1			
7,669.99	7,649.00	WASATCH			
7,819.99	7,799.00	CR_2			
8,064.99	8,044.00	CR_3			
8,394.99	8,374.00	CR_4			
8,679.99	8,659.00	CR_4A			
8,804.99	8,784.00	CR_5			
8,974.99	8,954.00	CR_6			
9,234.99	9,214.00	CR_7			
9,734.99	9,714.00	TD			

Targets associated with this wellbore

Target Name	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Shape
#7-4D-45 BTR_BHL Tgt	9,714.00	359.19	21.80	Point
#7-4D-45 BTR_SHL	0.00	0.00	0.00	Point
#7-4D-45 BTR_ZONE Tgt	6,474.00	359.19	21.80	Rectangle

North Reference Sheet for Sec. 4-T4S-R5W - #7-4D-45 BTR - Plan A Rev 0

All data is in US Feet unless otherwise stated. Directions and Coordinates are relative to True North Reference.

Vertical Depths are relative to RKB 16' @ 5809.00ft (Patterson 506). Northing and Easting are relative to #7-4D-45 BTR

Coordinate System is US State Plane 1927 (Exact solution), Utah Central 4302 using datum NAD 1927 (NADCON CONUS), ellipsoid Clarke 1866

Projection method is Lambert Conformal Conic (2 parallel)

Central Meridian is -111.50°, Longitude Origin:0° 0' 0.000 E°, Latitude Origin:40° 39' 0.000 N°

False Easting: 2,000,000.00ft, False Northing: 0.00ft, Scale Reduction: 0.99991517

Grid Coordinates of Well: 668,127.03 ft N, 2,292,810.91 ft E


Geographical Coordinates of Well: 40° 09' 46.74" N, 110° 27' 08.19" W

Grid Convergence at Surface is: 0.67°

Based upon Minimum Curvature type calculations, at a Measured Depth of 9,734.99ft

the Bottom Hole Displacement is 359.86ft in the Direction of 3.47° (True).

Magnetic Convergence at surface is: -10.82° (16 September 2011, , BGGM2011)



SURFACE USE PLAN

BILL BARRETT CORPORATION

7-4D-45 BTR Well Pad

SW NE, 2338' FNL and 2002' FEL, Section 4, T4S, R5W, USB&M (surface hole)

SW NE, 1979' FNL and 1979' FEL, Section 4, T4S, R5W, USB&M (bottom hole)

Duchesne County, Utah

The onsite inspection for this pad occurred on June 10, 2011. Site specific conditions or changes as a result of that onsite are indicated below. Plat changes requested are reflected within this APD.

- a) Paint color will be beetle green
- b) Reclamation plan diagram included with facilities location
- c) See Map B for additional low water crossings/culverts
- d) Access will not utilize the un-improved UDOT approach, but the 8-10 approach instead

The excavation contractor would be provided with an approved copy of the surface use plan of operations before initiating construction.

1. Existing Roads:

- a. The proposed well site is located approximately 3.8 miles west of Duchesne, Utah. Maps and directions reflecting the route to the proposed well site are included (see Topographic maps A and B).
- b. The existing State Highway 40 would be utilized for 2.2 miles to the existing BBC maintained 8-10-45 BTR well site access road that would be utilized for 0.6 miles to an existing El Paso P&A well access road that would be utilized for an additional 0.6 miles and provides access to the planned new access road.
- c. Project roads would require routine year-round maintenance to provide year-round access. Maintenance would include inspections, reduction of ruts and holes, maintenance to keep water off the road, replacement of surfacing materials, and clearing of sediment blocking ditches and culverts. Should snow removal become necessary, roads would be cleared with a motor grader and snow would be stored along the down gradient side to prohibit runoff onto the road. Aggregate would be used as necessary to maintain a solid running surface and minimize dust generation.
- d. Vehicle operators would obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions. Travel would be limited to the existing access roads and proposed access road.
- e. The use of roads under State and Duchesne County Road Department maintenance are necessary to access the project area with no improvements proposed. No encroachment or pipeline crossing permit are required

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

- f. All existing roads would be maintained and kept in good repair during all phases of operation.

2. Planned Access Road:

- a. Approximately 2,207 feet of new access road trending northwest is planned from the existing P&A El Paso well access road (see Topographic Map B).
- b. The planned access road would be constructed to a 30-foot ROW width with an 18-foot travel surface. See section 12.d. below for disturbance estimates.
- c. New road construction and improvements of existing roads would typically require the use of motor graders, crawler tractors, 10-yard end dump trucks, and water trucks. The standard methodology for building new roads involves the use of a crawler tractor or track hoe to windrow the vegetation to one side of the road corridor, remove topsoil to the opposing side of the corridor, and rough-in the roadway. This is followed by a grader or bulldozer to establish barrow ditches and crown the road surface. Where culverts are required, a track hoe or backhoe would trench the road and install the culverts. Some hand labor would be required when installing and armoring culverts. Road base or gravel in some instances would be necessary and would be hauled in and a grader used to smooth the running surface.
- d. The proposed road would be constructed to facilitate drainage, control erosion and minimize visual impacts by following natural contours where practical. No unnecessary side-casting of material would occur on steep slopes.
- e. A maximum grade of 10% would be maintained throughout the project with minimum cuts and fills, as necessary, to access the well.
- f. Excess rock from construction of the pad may be used for surfacing of the access road if necessary. Any additional aggregate necessary would be obtained from private or State of Utah lands in conformance with applicable regulations. Aggregate would be of sufficient size, type, and amount to allow all weather access and alleviate dust.
- g. Where topsoil removal is necessary, it would be windrowed (i.e. stockpiled/accumulated along the edge of the ROW and in a low row/pile parallel with the ROW) and re-spread over the disturbed area after construction and backfilling are completed. Vegetation removed from the disturbed area would also be re-spread to provide protection, nutrient recycling, and a seed source for reclamation.
- h. Turnouts are not proposed.

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

- i. One 18 inch culvert where the access road enters the pad area and three low-water crossings are anticipated as shown on Map B. Adequate drainage structures, where necessary, would be incorporated into the remainder of the road to prevent soil erosion and accommodate all-weather traffic.
 - j. No gates or cattle guards are anticipated at this time.
 - k. Surface disturbance and vehicular travel would be limited to the approved location access road. Adequate signs would be posted, as necessary, to warn the public of project related traffic.
 - l. All access roads and surface disturbing activities would conform to the appropriate standard, **no higher than necessary**, to accommodate their intended function adequately as outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition – Revised 2007.
 - m. The operator would be responsible for all maintenance needs of the new access road.
3. Location of Existing Wells (see One-Mile Radius Map):
- a. Following is a list of wells with surface hole locations within a one-mile radius of the proposed pad:
 - i. water wells none
 - ii. injection wells none
 - iii. disposal wells none
 - iv. drilling wells none
 - v. temp shut-in wells none
 - vi. producing wells three
 - vii. abandoned wells three

4. Location of Production Facilities

- a. Surface facilities would consist of a wellhead, separator, gas meter, (1) 500 gal methanol tank, (1) 500 glycol tank, (3) 500 bbl oil tanks, (1) 500 bbl water tank, (1) 500 bbl test tank, (1) 1000 gal propane tank, a pumping unit or Roto-flex unit or gas lift unit with a natural gas fired motor, solar panels, solar chemical and methanol pumps and one trace pump. See attached proposed facility diagram.
- b. Most wells would be fitted with a pump jack or Roto-flex unit or gas lift to assist liquid production if liquid volumes and/or low formation pressures require it. Plunger lift systems do not require any outside source of energy. The prime mover for pump jacks or Roto-flex units would be small (75 horsepower or less), natural gas-fired internal combustion engines. If a gas lift is installed, it would

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

be set on a 10 ft x 15 ft pad and the prime mover would be a natural gas-fired internal combustion engine rated at 200 horsepower or less or an electric compressor of similar horsepower powered by a generator.

- c. The tank battery would be surrounded by a secondary containment berm of sufficient capacity to contain 1.1 times the entire capacity of the largest single tank and sufficient freeboard to contain precipitation. All loading lines and valves would be placed inside the berm surrounding the tank battery or would utilize catchment basins to contain spills. All liquid hydrocarbon production and measurement shall conform to the provisions of 43 CFR 3162.7-2 and Onshore Oil and Gas Order No. 4 for the measurement of oil.
- d. Gas meter run(s) would be constructed and located on lease within 500 feet of the wellheads. Meter runs would be housed and/or fenced. As practicably feasible, meters would be equipped with remote telemetry monitoring systems. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.
- e. A combustor may be installed at this location for control of associated condensate tank emissions. A combustor ranges from 24 inches to 48 inches wide and is approximately 27 ft tall. Combustor placement would be on existing disturbance.
- f. Approximately 339 feet of pipeline corridor (see Topographic Map C) containing up to three lines (one gas pipeline up to 8 inch in diameter, one water line up to 4 inch in diameter and one residue line up to 4 inch in diameter) is proposed trending east to the existing El Paso pipeline corridor. Pipelines would be constructed of steel, polyethylene or fiberglass and would connect to the existing pipeline servicing nearby BBC and El Paso wells. The pipeline crosses entirely Ute Tribe surface.
- g. The new segment of gas pipeline would be surface laid within a 30 foot wide pipeline corridor adjacent to the proposed access road. See 12.d below for disturbance estimates.
- h. Construction of the ROW would temporarily utilize the 30 foot disturbed width for the road for a total disturbed width of 60 foot for the road and pipeline corridors. The use of the proposed well site and access roads would facilitate the staging of the pipeline construction.
- i. Pipeline construction methods and practices would be planned and conducted by BBC with the objective of enhancing reclamation and fostering the re-establishment of the native plant community.
- j. All permanent above-ground structures would be painted a flat, non-reflective color, such as Beetle Green, to match the standard environmental colors. All facilities would be painted the designated color at the time of installation.

Bill Barrett Corporation
 Surface Use Plan
 7-4D-45 BTR
 Duchesne County, UT

Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.

- k. Site security guidelines identified in 43 CFR 3162.7-5 and Onshore Oil and Gas Order No. 3 would be adhered to. Any modifications to proposed facilities would be reflected in the site security diagram submitted.
- l. The site would require periodic maintenance to ensure that drainages are kept open and free of debris, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.

5. Location and Type of Water Supply:

- a. Water for the drilling and completion would be trucked from any of the following locations:

Water Right No. and Application or Change No.	Applicant	Allocation	Date	Point of Diversion	Source
43-180	Duchesne City Water Service District	5 cfs	8/13/2004	Knight Diversion Dam	Duchesne River
43-1202, Change a13837	Myton City	5.49 cfr and 3967 acre feet	3/21/1986	Knight Diversion Dam	Duchesne River
43-10444, Appln A57477	Duchesne County Upper Country Water	2 cfs	1994	Ditch at Source	Cow Canyon Spring
43-10446, Appln F57432	Duchesne County Upper Country Water	1.58 cfs	1994	Ditch at Source	Cow Canyon Spring
43-1273, Appln A17462	J.J.N.P. Company	7 cfs	1946	Strawberry River	Strawberry River
43-1273, Appln t36590	J.J.N.P. Company	4 cfs	6/03/2010	Strawberry River	Strawberry River

- b. No new water well is proposed with this application.
- c. Should additional water sources be pursued they would be properly permitted through the State of Utah – Division of Water Rights.
- d. Water use would vary in accordance with the formations to be drilled but would be up to approximately 5.41 acre feet for drilling and completion operations.

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

6. Source of Construction Material:

- a. The use of materials would conform to 43 CFR 3610.2-3.
- b. No construction materials would be removed from the lease or EDA area.
- c. If any additional gravel is required, it would be obtained from a local supplier having a permitted source of materials within the general area.

7. Methods of Handling Waste Disposal:

- a. All wastes associated with this application would be contained and disposed of utilizing approved facilities.
- b. The reserve pit would be constructed so as not to leak, break or allow any discharge.
- c. The reserve would be lined with 12 mil (minimum) thickness polyethylene nylon reinforced liner material. The liner(s) would overlay straw, dirt and/or bentonite if rock is encountered during excavation. The liner would overlap the pit walls and be covered with dirt and/or rocks to hold them in place. No trash, scrap pipe, or other materials that could puncture the liner would be discarded in the pit. A minimum of two feet of free board would be maintained between the maximum fluid level and the top of the reserve pit at all times.
- d. To deter livestock from entering the pit, the three sides exterior to the location would be fenced before drilling starts. Following the conclusion of drilling and completion activities, the fourth side would also be fenced.
- e. Drill cuttings would be contained in the pit and buried on-site for a period not to exceed six months, weather permitting
- f. Produced fluids from the well other than water would be decanted into steel test tank(s) until such time as construction of production facilities is completed. Any oil that may be accumulated would be transferred to a permanent production tank. Produced water may be used in further drilling and completion activities, evaporated in the pit, or would be hauled to one of the state-approved disposal facilities below:

Disposal Facilities
1. RNI Industries, Inc. – Pleasant Valley Disposal Pits, Sec. 25, 26, 35 & 36, T4S-R3W
2. Pro Water LLC – Blue Bench 13-1 Disposal Well (43-013-30971) NENE, Sec. 13, T3S-R5W
3. RN Industries, Inc. – Bluebell Disposal Ponds, Sec. 2, 4 & 9, T2S-R2W
4. Water Disposal, Inc. – Harmston 1-32-A1 Disposal Well (43-013-30224), UTR #00707, Sec. 32, T1S-R1W

Bill Barrett Corporation
 Surface Use Plan
 7-4D-45 BTR
 Duchesne County, UT

Disposal Facilities
5. Unified Water Pits – Sec. 31, T2S-R4W
6. Iowa Tank Line Pits – 8500 BLM Fence Road, Pleasant Valley

- g. Any salts and/or chemicals, which are an integral part of the drilling system, would be disposed of in the same manner as the drilling fluid.
- h. Any spills of oil, condensate, produced or frac water, drilling fluids, or other potentially deleterious substances would be recovered and either returned to its origin or disposed of at an approved disposal site, most likely in Duchesne, Utah.
- i. Chemicals on the EPA’s Consolidated List of Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA) may be used or stored in quantities over reportable quantities. In the course of drilling, BBC could potentially store and use diesel fuel, sand (silica), hydrochloric acid, and CO₂ gas, all described as hazardous substances in 40 CFR Part 302, Section 302.4, in quantities exceeding 10,000 pounds. In addition, natural gas condensate and crude oil and methanol may be stored or used in reportable quantities. Small quantities of retail products (paint/spray paints, solvents {e.g., WD-40}, and lubrication oil) containing non-reportable volumes of hazardous substances may be stored and used on site at any time. No extremely hazardous substances, as defined in 40 CFR 355, would be used, produced, stored, transported or disposed of in association with the drilling, testing or completion of the wells.
- j. Portable toilets and trash containers would be located onsite during drilling and completion operations. A commercial supplier would install and maintain portable toilets and equipment and would be responsible for removing sanitary waste. Sanitary waste facilities (i.e. toilet holding tanks) would be regularly pumped and their contents disposed of at approved sewage disposal facilities in Duchesne, and/or Uintah Counties, in accordance with applicable rules and regulations regarding sewage treatment and disposal. Accumulated trash and nonflammable waste materials would be hauled to an approved landfill once a week or as often as necessary. All debris and waste materials not contained in the trash containers would be cleaned up, removed from the construction ROW, well pad, or worker housing location, and disposed of at an approved landfill. Trash would be cleaned up everyday.
- k. Sanitary waste equipment and trash bins would be removed from the Project Area upon completion of access road or pipeline construction; following drilling and completion operations at an individual well pad; when worker housing is no longer needed; or as required.
- l. A flare pit may be constructed a minimum of 110 feet from the wellhead(s) and may be used during completion work. In the event a flare pit proves to be unworkable, a temporary flare stack or open top tank would be installed. BBC would flow back as much fluid and gas as possible into pressurized vessels,

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

separating the fluids from the gas. In some instances, due to the completion fluids utilized within the Project Area, it is not feasible to direct the flow stream from the wellbore through pressurized vessels. In such instances BBC proposes to direct the flow to the open top tanks until flow through the pressurized vessels is feasible. At which point the fluid would either be returned to the reserve pit or placed into a tank(s). The gas would be directed to the flare pit, flare stack (each with a constant source of ignition), or may be directed into the sales pipeline.

- m. Hydrocarbons would be removed from the reserve pit would as soon as practical. In the event immediate removal is not practical, the reserve pit would be flagged overhead or covered with wire or plastic mesh to protect migrating birds.

8. Ancillary Facilities:

- a. Garbage containers and portable toilets would be located on the well pad.
- b. On well pads where active drilling and completion is occurring, temporary housing would be provided on location for the well pad supervisor, geologist, tool pusher, and others that are required to be on location at all times. The well pad could include up to five single wide mobile homes or fifth wheel campers/trailers.
- c. A surface powerline corridor 346 feet in length is proposed for installation by third-party installer within a 150 foot wide powerline corridor adjacent to the proposed access road. See 12.d below for disturbance estimates.

9. Well Site Layout:

- a. The well would be properly identified in accordance with 43 CFR 3162.6.
- b. The pad layout, cross section diagrams and rig layout are enclosed (see Figures 1 and 2).
- c. The pad and road designs are consistent with industry specifications.
- d. The pad has been staked at its maximum size of 400 feet x 285 feet with an inboard reserve pit size of 200 feet x 100 feet x 8 feet deep. See section 12.d below for disturbance estimates.
- e. Within the approved well pad location, a crawler tractor would strip whatever topsoil is present and stockpile it along the edge of the well pad for use during reclamation. Vegetation would be distributed along the sides of the well pad.
- f. Fill from pit excavation would be stockpiled along the edge of the pit and the adjacent edge of the well pad.
- g. Use of erosion control measures, including proper grading to minimize slopes, diversion terraces and ditches, mulching, terracing, riprap, fiber matting,

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

temporary sediment traps, and broad-based drainage dips or low water crossings would be employed by BBC as necessary and appropriate to minimize erosion and surface runoff during well pad construction and operation. Cut and fill slopes would be constructed such that stability would be maintained for the life of the activity.

- h. All cut and fill slopes would be such that stability can be maintained for the life of the activity.
- i. Diversion ditches would be constructed, if necessary, around the well site to prevent surface waters from entering the well site area.
- j. Water application may be implemented if necessary to minimize the amount of fugitive dust.
- k. All surface disturbing activities would be supervised by a qualified, responsible company representative who is aware of the terms and conditions of the APD and specifications in the approved plans.

10. Plan for Restoration of the Surface:

- a. A site specific reclamation plan would be submitted, if requested, within 90 days of location construction to the surface managing agency.
- b. Site reclamation would be accomplished for portions of the well pad not required for the continued operation of the well on this pad within six months of completion, weather permitting.
- c. The operator would control noxious weeds along access road use authorizations and well site by spraying or mechanical removal, according to the Utah Noxious Weed Act and as set forth in the approved surface damage agreements.
- d. Rat and mouse holes would be filled and compacted from bottom to top immediately upon release of the drilling rig from location. Upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1. The reserve pit would be allowed to dry prior to the commencement of backfilling work. No attempts would be made to backfill the reserve pit until it is free of standing water. Once dry, the liner would be torn and perforated before backfilling.
- e. The reserve pit and that portion of the location not needed for production facilities/operations would be recontoured to the approximate natural contours. Areas not used for production purposes would be backfilled and blended into the surrounding terrain, reseeded and erosion control measures installed. Mulching, erosion control measures and fertilization may be required to achieve acceptable stabilization. Back slopes and fore slopes would be reduced as practical and scarified with the contour.

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

The reserved topsoil would be evenly distributed over the slopes and scarified along the contour. Slopes would be seeded with the Ute Tribe specified seed mix.

- f. Topsoil salvaged from the drill site and stored for more than one year would be placed at the location indicated on the well site layout drawing and graded to a depth optimum to maintain topsoil viability, seeded with the Ute Tribe prescribed seed mixture and covered with mulch for protection from wind and water erosion and to discourage the invasion of weeds.

11. Surface and Mineral Ownership:

- a. Surface ownership – Ute Indian Tribe - 988 South 7500 East; Ft. Duchesne, Utah 84026; 435-725-4982.
- b. Mineral ownership – Ute Indian Tribe - 988 South 7500 East; Ft. Duchesne, Utah 84026; 435-725-4982.

12. Other Information:

- a. Montgomery Archeological Consultants has conducted a Class III archeological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by Montgomery as MOAC Report No. 10-256 dated 5-24-2011.
- b. BBC would require that their personnel, contractors, and subcontractors to comply with Federal regulations intended to protect archeological and cultural resources.
- c. Project personnel and contractors would be educated on and subject to the following requirements:
 - No dogs or firearms within the Project Area.
 - No littering within the Project Area.
 - Smoking within the Project Area would only be allowed in off-operator active locations or in specifically designated smoking areas. All cigarette butts would be placed in appropriate containers and not thrown on the ground or out windows of vehicles; personnel and contractors would abide by all fire restriction orders.
 - Campfires or uncontained fires of any kind would be prohibited.
 - Portable generators used in the Project Area would have spark arrestors.

Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

d. Disturbance estimates:

Approximate Acreage Disturbances

Well Pad		3.461	acres
Access	2207 feet	1.520	acres
*Pipeline			acres
Powerline	346 feet	1.192	acres
	Total	6.17	acres

*Pipeline Disturbance is included within the Powerline

- e. Access will not utilize the existing UDOT right-of-way fence opening as a short-cut to the pad area.


Bill Barrett Corporation
Surface Use Plan
7-4D-45 BTR
Duchesne County, UT

OPERATOR CERTIFICATION

Certification:

I hereby certify that I, or someone under my direction supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein would be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application and that bond coverage is provided under Bill Barrett Corporations federal nationwide bond. These statements are subject to the provisions of 18 U.S.C. 1001 for the filings of false statements.


Executed this 12th day of July 2011
Name: Venessa Langmacher
Position Title: Senior Permit Analyst
Address: 1099 18th Street, Suite 2300, Denver, CO 80202
Telephone: 303-312-8172
E-mail: vlangmacher@billbarrettcorp.com
Field Representative Kary Eldredge / Bill Barrett Corporation
Address: 1820 W. Highway 40, Roosevelt, UT 84066
Telephone: 435-725-3515 (office); 435-724-6789 (mobile)
E-mail: keldredge@billbarrettcorp.com



Venessa Langmacher, Senior Permit Analyst

BILL BARRETT CORPORATION

TYPICAL 5,000 p.s.i. BLOWOUT PREVENTER





July 12, 2011

Ms. Diana Mason – Petroleum Technician
State of Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, Utah 84114-5801

Re: Directional Drilling R649-3-11
Blacktail Ridge Area #7-4D-45 BTR Well
Surface: 2,338' FNL & 2,002' FEL, SWNE, 4-T4S-R5W, USM
Bottom Hole: 1,979' FNL & 1,979' FEL, SWNE, 4-T4S-R5W, USM
Duchesne County, Utah

Dear Ms. Mason,

Pursuant to the filing of Bill Barrett Corporation's ("BBC") Application for Permit to Drill the above referenced well, we hereby submit this letter in accordance with Oil & Gas Conservation Rules R649-2, R649-3, R649-10 and R649-11, pertaining to the Location and Siting of Wells.

- The proposed location is within our Blacktail Ridge Area.
- BBC is permitting this well as a directional well in order to minimize surface disturbance. By locating the well at the surface location and directionally drilling from this location, BBC will be able to utilize the existing road and pipelines in the area.
- The well will be drilled under an Exploration and Development Agreement between the Ute Indian Tribe and Ute Distribution Corporation. Ute Energy, LLC owns a right to participate in this well.
- BBC certifies that it is the working interest owner of all lands within 460 feet of the proposed well location, and together with Ute Energy, LLC, we own 100% of the working interest in these lands.

Based on the information provided, BBC requests that the permit be granted pursuant to R649-3-11. Should you have any questions or need further information, please contact me at 303-312-8544.

Sincerely,

A handwritten signature in blue ink that reads "Venus Langmackey" with a small "for" written below it.

David Watts
Landman

1099 18TH STREET
SUITE 2300
DENVER, CO 80202
P 303.293.9100
F 303.291.0420


BILL BARRETT CORPORATION

FIGURE #1

LOCATION LAYOUT FOR

#7-4D-45 BTR
SECTION 4, T4S, R5W, U.S.B.&M.

2338' FNL 2002' FEL



SCALE: 1" = 60'
DATE: 12-02-10
DRAWN BY: K.G.



NOTE:
Flare Pit is to be located a min. of 100' from the Well Head.

CONSTRUCT DIVERSION DITCH

CONSTRUCT DIVERSION DITCH

Elev. Ungraded Ground At Loc. Stake = 5794.5'
FINISHED GRADE ELEV. AT LOC. STAKE = 5792.9

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



RESERVE PITS (8' Deep)
Total Pit Capacity W/2' of Freeboard = 16,830 Bbbs.±
Total Pit Volume = 4,920 Cu. Yds

Reserve Pit Backfill & Spoils Stockpile

Install 18" CMP

Proposed Access Road

Sta. 1+00

N03°33'16"E - 359.83'
(To Bottom Hole)

Sta. 0+00

Sta. 2+00

Sta. 4+00

El. 802.6'

El. 797.4'

El. 794.5'

El. 797.5'

El. 795.4'

El. 794.9'

El. 792.8'

El. 786.5'

El. 782.5'

El. 782.3'

Approx. Top of Cut Slope

Approx. Toe of Fill Slope

Round Corners as Needed

Topsail Stockpile

Existing Fence

Prevailing Winds

BILL BARRETT CORPORATION


TYPICAL CROSS SECTIONS FOR

#7-4D-45 BTR






SECTION 4, T4S, R5W, U.S.B.&M.

2338' FNL 2002' FEL

FIGURE #2



DATE: 12-02-10
DRAWN BY: K.G.



APPROXIMATE ACREAGES

WELL SITE DISTURBANCE	= ± 3.461 ACRES
ACCESS ROAD DISTURBANCE	= ± 1.520 ACRES
PIPELINE DISTURBANCE	= ± 0.234 ACRES
TOTAL	= ± 5.215 ACRES

NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.


*** NOTE:**

FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

(12") Topsoil Stripping	= 5,080 Cu. Yds.
Remaining Location	= 15,860 Cu. Yds.
TOTAL CUT	= 20,940 CU.YDS.
FILL	= 13,400 CU.YDS.


EXCESS MATERIAL	= 7,540 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 7,540 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 0 Cu. Yds.



API Number: 4301350884
Well Name: 7-4D-45 BTR
Township T0.4 . Range R0.5 . Section 04
Meridian: UBM
Operator: BILL BARRETT CORP

Map Prepared:
 Map Produced by Diana Mason

Units	Wells Query
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LA - Location Abandoned
PI OIL	LDC - New Location
PP GAS	OPS - Operation Suspended
PP GEOTHERML	PA - Plugged Abandoned
PP OIL	PGW - Producing Gas Well
SECONDARY	POW - Producing Oil Well
TERMINATED	RET - Returned APD
UNKNOWN	SGW - Shut-in Gas Well
ABANDONED	SGW - Shut-in Oil Well
ACTIVE	TA - Temp. Abandoned
COMBINED	TW - Test Well
INACTIVE	WDW - Water Disposal
STORAGE	WW - Water Injection Well
TERMINATED	WSW - Water Supply Well
Sections	
Township	
Bottom Hole Location - AGRC	



WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 7/12/2011

API NO. ASSIGNED: 43013508840000

WELL NAME: 7-4D-45 BTR

OPERATOR: BILL BARRETT CORP (N2165)

PHONE NUMBER: 303 312-8172

CONTACT: Venessa Langmacher

PROPOSED LOCATION: SWNE 04 040S 050W

Permit Tech Review:

SURFACE: 2338 FNL 2002 FEL

Engineering Review:

BOTTOM: 1979 FNL 1979 FEL

Geology Review:

COUNTY: DUCHESNE

LATITUDE: 40.16291

LONGITUDE: -110.45231

UTM SURF EASTINGS: 546640.00

NORTHINGS: 4445772.00

FIELD NAME: ALTAMONT

LEASE TYPE: 2 - Indian

LEASE NUMBER: 1420H626281

PROPOSED PRODUCING FORMATION(S): GREEN RIVER-WASATCH

SURFACE OWNER: 2 - Indian

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- PLAT**
- Bond:** INDIAN - LPM8874725
- Potash**
- Oil Shale 190-5**
- Oil Shale 190-3**
- Oil Shale 190-13**
- Water Permit:** Duchesne City Culinary Water Dock
- RDCC Review:**
- Fee Surface Agreement**
- Intent to Commingle**

Commingle Approved

LOCATION AND SITING:

- R649-2-3.**
- Unit:**
- R649-3-2. General**
- R649-3-3. Exception**
- Drilling Unit**
- Board Cause No:** Cause 139-85
- Effective Date:** 3/11/2010
- Siting:** 4 Prod LGRRV-WSTC Wells in Drl Units
- R649-3-11. Directional Drill**

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason
15 - Directional - dmason



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: 7-4D-45 BTR
API Well Number: 43013508840000
Lease Number: 1420H626281
Surface Owner: INDIAN
Approval Date: 7/28/2011

Issued to:

BILL BARRETT CORP, 1099 18th Street Ste 2300, Denver, CO 80202

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-85. The expected producing formation or pool is the GREEN RIVER-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a faint, illegible stamp or background.

For John Rogers
Associate Director, Oil & Gas

RECEIVED

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

JUL 13 2011

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 1420H626281
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name UINTAH AND OURAY
2. Name of Operator BILL BARRETT CORPORATION		7. If Unit or CA Agreement, Name and No.
3a. Address 1099 18TH STREET SUITE 2300 DENVER, CO 80202		8. Lease Name and Well No. 7-4D-45 BTR
3b. Phone No. (include area code) Ph: 303-312-8172 Fx: 303-291-0420		9. API Well No. 43-013-50884
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SWNE 2338FNL 2002FEL 40.162942 N Lat, 110.452986 W Lon At proposed prod. zone SWNE 1979FNL 1979FEL 40.163928 N Lat, 110.452908 W Lon		10. Field and Pool, or Exploratory UNDESIGNATED
14. Distance in miles and direction from nearest town or post office* 3.8 MILES WEST OF DUCHESNE, UT		11. Sec., T., R., M., or Blk. and Survey or Area Sec 4 T4S R5W Mer UBM
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1979' (BOTTOM HOLE)	16. No. of Acres in Lease 639.20	12. County or Parish DUCHESNE
17. Spacing Unit dedicated to this well 640.00	13. State UT	18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 2541'
19. Proposed Depth 9735 MD 9714 TVD	20. BLM/BIA Bond No. on file WYB000040 / LP M8874725	21. Elevations (Show whether DF, KB, RT, GL, etc.) 5794 GL
22. Approximate date work will start 01/01/2012	23. Estimated duration 60 DAYS (D&C)	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) VENESSA LANGMACHER Ph: 303-312-8172	Date 07/12/2011
Title SENIOR PERMIT ANALYST		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date JAN 17 2012
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

Additional Operator Remarks (see next page)

JAN 27 2012

Electronic Submission #112760 verified by the BLM Well Information System
For BILL BARRETT CORPORATION, sent to the Vernal
Committed to AFMSS for processing by LESLIE ROBINSON on 07/14/2011 (11LBR0028AE)

DIV OF OIL, GAS & MINING

NOTICE OF APPROVAL

UDOGM

** BLM REVISED **

11LBR0028AE




UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Bill Barrett Corporation
Well No: 7-4D-45 BTR
API No: 43-013-50884

Location: SWNE, Sec. 4, T4S, R5W
Lease No: 14-20-H62-6281
Agreement: N/A

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Construction Activity (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig.
Spud Notice (Notify BLM Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm_ut_vn_opreport@blm.gov .
BOP & Related Equipment Tests (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify BLM Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

Additional Stipulations:

- Production Equipment will be painted Beetle Green to help blend into the surrounding vegetation.
- See Exhibit One of the approved EA U&O-FY12-Q1-037 for additional mitigation measures that must be followed for each of the proposed well locations.

General Conditions of Approval:

- A 30' foot corridor right-of-way shall be approved. Upon completion of each pipeline in corridor, they shall be identified and filed with the Ute Tribe.
- The Ute Tribe Energy & Minerals Department is to be notified, in writing 48 hours prior to construction of pipelines.
- Construction Notice shall be given to the department on the Ute Tribe workdays, which are Monday through Thursday. The Company understands that they may be responsible for costs incurred by the Ute Tribe after hours.
- The Company shall inform contractors to maintain construction of pipelines within the approved ROW's.
- The Company shall assure the Ute Tribe that "ALL CONTRACTORS, INCLUDING SUB-CONTRACTORS, LEASING CONTRACTORS, AND ETC." have acquired a current and valid Ute Tribal Business License and have "Access Permits" prior to construction, and will have these permits in all vehicles at all times.
- You are hereby notified that working under the "umbrella" of a company does not allow you to be in the field, and can be subject to those fines of the Ute Tribe Severance Tax Ordinance.
- Any deviation of submitted APD's and ROW applications the Companies will notify the Ute Tribe and BIA in writing and will receive written authorization of any such change with appropriate authorization.
- Bill Barrett Corporation will implement a "Safety and Emergency Plan." The Company's safety director will ensure its compliance.
- All Company employees and/or authorized personnel (sub-contractors) in the field will have approved applicable APD's, COA's, and/or ROW permits/authorizations on their person(s) during all phases of construction.
- All vehicular traffic, personnel movement, construction/restoration operations shall be confined to the area examined and approved, and to the existing roadways and/or evaluated access routes.
- The personnel from the Ute Tribe Energy & Minerals Department shall be notified should cultural remains from subsurface deposits be exposed or identified during construction. All construction will cease.

- Upon completion of Application for Corridor Right-Way, the company will notify the Ute Tribe Energy & Minerals Department, so that a Tribal Technician can verify Affidavit of Completion.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- Production casing cement shall be brought up and into the surface casing. The minimum cement top is 200 ft. above the surface casing shoe.
- Contingency, for casing production (partial) liner installation, casing liner is to be installed and tested to the standards of Onshore Orders #2. The operator specified casing liner lap overlap interval length is 200 ft.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.

- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: 1420H626281
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: 7-4D-45 BTR
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43013508840000
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext
9. FIELD and POOL or WILDCAT: ALTAMONT	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2338 FNL 2002 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 04.0S Range: 05.0W Meridian: U	COUNTY: DUCHESNE STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/1/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Based on our experience the last 18 months in 4S-5W in the BTR area, BBC would like to get away from running 10-3/4" surface casing and replace it with 9-5/8" like the rest of the BTR field. We have not needed to run intermediate in the last 18 months anywhere in BTR. We would still have the option to run the 7" if necessary. We would drill 8-3/4" production hole to TD. At this time, we are requesting to change the 10-3/4" surface casing to 9-5/8" (12-1/4" hole size, 36#, J or K55, BT&C) surface casing on this well. Surface casing will be run from surface to 2800'. The cement program will stay the same with the exception of 360 sx for lead and 210 sx for tail.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: May 09, 2012

By: *Derek Quist*

NAME (PLEASE PRINT) Venessa Langmacher	PHONE NUMBER 303 312-8172	TITLE Senior Permit Analyst
SIGNATURE N/A	DATE 4/20/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 1420H626281
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: BILL BARRETT CORP		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202		8. WELL NAME and NUMBER: 7-4D-45 BTR
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2338 FNL 2002 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 04.0S Range: 05.0W Meridian: U		9. API NUMBER: 43013508840000
PHONE NUMBER: 303 312-8164 Ext		9. FIELD and POOL or WILDCAT: ALTAMONT
COUNTY: DUCHESNE		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 6/4/2012	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. This well was spud by Triple A Drilling on 6/4/2012 at 4:30 pm.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 15, 2012		
NAME (PLEASE PRINT) Venessa Langmacher	PHONE NUMBER 303 312-8172	TITLE Senior Permit Analyst
SIGNATURE N/A	DATE 6/12/2012	

BLM - Vernal Field Office - Notification Form

Operator Bill Barrett Corporation Rig Name/# Triple A Drilling
 Submitted By Venessa Langmach Phone Number 303-312-8172
 Well Name/Number 7-4D-45 BTR
 Qtr/Qtr SWNE Section 4 Township 4S Range 5W
 Lease Serial Number 1420H626281
 API Number 4301350884

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 06/02/2012 8:00 AM PM

Casing – Please report time casing run starts, not cementing times.

- Surface Casing
 Intermediate Casing
 Production Casing
 Liner
 Other

RECEIVED

MAY 31 2012

DIV. OF OIL, GAS & MINING

Date/Time _____ AM PM

BOPE

- Initial BOPE test at surface casing point
 BOPE test at intermediate casing point
 30 day BOPE test
 Other

Date/Time _____ AM PM

Remarks _____

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Bill Barrett Corporation Operator Account Number: N 2165
 Address: 1099 18th Street, Suite 2300
city Denver
state CO zip 80202 Phone Number: (303) 312-8172

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301351053	10-22-22 South Altamont		NWSE	22	2S	2W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	18560	6/8/2012			6/13/2012	
Comments: Spudding Operation was conducted by Triple A Drilling @ 8:00 am. GR-WS							CONFIDENTIAL

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301350900	8-6-45 BTR		SENE	6	4S	5W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	18561	6/1/2012			6/13/2012	
Comments: Spudding Operation was conducted by Triple A Drilling @ 8:00 am. GR-WS							—

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301350884	7-4D-45 BTR		SWNE	4	4S	5W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	18562	6/4/2012			6/13/2012	
Comments: Spudding Operation was conducted by Triple A Drilling @ 4:30 pm. GR-WS							—

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Venessa Langmacher

Name (Please Print)

Venessa Langmacher

Signature

Sr Permit Analyst

Title

6/12/2012

Date

RECEIVED

JUN 13 2012

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 1420H626281
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: 7-4D-45 BTR	
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43013508840000	
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2338 FNL 2002 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 04.0S Range: 05.0W Meridian: U		COUNTY: DUCHESNE
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 6/30/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Well spud this month; no other June 2012 monthly drilling activity to report.		
		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY July 03, 2012
NAME (PLEASE PRINT) Megan Finnegan	PHONE NUMBER 303 299-9949	TITLE Permit Analyst
SIGNATURE N/A	DATE 7/3/2012	

BLM - Vernal Field Office - Notification Form

Operator Bill Barrett Corp Rig Name/# Nabors M22
Submitted By Jeremy Mejorado Phone Number 303-353-5350

Well Name/Number 7-4D-45 BTR
Qtr/Qtr Section 4 Township 4S Range 5W
Lease Serial Number 14207626281
API Number 43-013-50884

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time AM PM

Casing – Please report time casing run starts, not cementing times.

- Surface Casing
- Intermediate Casing
- Production Casing
- Liner
- Other

Date/Time 7/3/12 - 4:00 AM PM

BOPE

- Initial BOPE test at surface casing point
- BOPE test at intermediate casing point
- 30 day BOPE test
- Other

Date/Time AM PM

RECEIVED
JUL 03 2012
DIV. OF OIL, GAS & MINING

Remarks WE WILL BE CEMENTING AROUND 8:00 PM 7/3/12
PLEASE CALL WITH ANY QUESTIONS OR
CONCERNS

TOYS ROSW SEC 04

From: Naborsm22 <naborsm22@bbcontractors.com>
To: "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "dennisingram@utah.gov" ...
CC: Tracey Fallang <tfallang@billbarrettcorp.com>, Venessa Langmacher <vlang...>
Date: 7/3/2012 7:07 PM
Subject: NABORS M-22 BOP TESTING 24 HR NOTICE

Good evening;

This is a rough 24 hr. notice for Nabors M-22 bop testing procedures on the 7-4D-45 BTR, API# 43-013-50884...

If there are any questions, comments, and/or concerns please call 303-353-5350...

Thanks.

Bill Barrett Corp.
Nabors M-22
303-353-5350

RECEIVED

JUL 04 2012

DIV. OF OIL, GAS & MINING

RECEIVED

JUL 04 2012

DIV. OF OIL, GAS & MINING

TOYS ROSW S-04

From: Naborsm22 <naborsm22@bbccontractors.com>
To: "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "dennisingram@utah.gov" ...
CC: Tracey Fallang <tfallang@billbarrettcorp.com>, Venessa Langmacher <vlang...>
Date: 7/15/2012 7:17 PM
Subject: NABORS M-22, 24 HR NOTICES

GOOD EVENING; THIS IS A 24 HR NOTICE FOR CSG. RUN, AND A ROUGH 30 HR NOTICE FOR CEMENTING PROCEDURES ON WELL # ~~7-4D-45 BTR~~ API#43-013-50884.

IF THERE ARE ANY QUESTIONS, COMMENTS, AND/OR CONCERNS CONTACT 303-353-5350

BILL BARRETT CORP.
NABORS M-22
303-353-5350

RECEIVED
JUL 15 2012

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
5. LEASE DESIGNATION AND SERIAL NUMBER: 1420H626281	
SUNDRY NOTICES AND REPORTS ON WELLS	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE	
7. UNIT or CA AGREEMENT NAME:	
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: 7-4D-45 BTR
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43013508840000
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext
9. FIELD and POOL or WILDCAT: ALTAMONT	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2338 FNL 2002 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 04.0S Range: 05.0W Meridian: U	
COUNTY: DUCHESNE	
STATE: UTAH	

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 7/31/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

July 2012 monthly drilling activity report is attached.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY
 August 08, 2012**

NAME (PLEASE PRINT) Megan Finnegan	PHONE NUMBER 303 299-9949	TITLE Permit Analyst
SIGNATURE N/A	DATE 8/2/2012	

**7-4D-45 BTR 7/1/2012 06:00 - 7/2/2012 06:00**

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	2.00	08:00	8	REPAIR RIG	WORK ON TOP DRIVE ELECTRICAL
08:00	7.00	15:00	2	DRILL ACTUAL	W/ 730 GPM 65 RPM & 12K WT ON BIT
15:00	2.50	17:30	8	REPAIR RIG	TROUBLE SHOOT TOP DRIVE ELECTRICAL - WAIT ON ELECTRICIAN
17:30	4.50	22:00	5	COND MUD & CIRC	MUD UP & WIEGHT UP TO KILL WATER FLOW
22:00	3.50	01:30	8	REPAIR RIG	WORK ON TOP DRIVE ELECTRICAL
01:30	4.50	06:00	2	DRILL ACTUAL	W/ 730 GPM 65 RPM & 12K WT ON BIT

7-4D-45 BTR 7/2/2012 06:00 - 7/3/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	11.50	17:30	2	DRILL ACTUAL	W/ 730 GPM 65 RPM & 14K WT ON BIT
17:30	0.50	18:00	7	LUBRICATE RIG	RIG SERVICE
18:00	10.00	04:00	2	DRILL ACTUAL	W/ 730 GPM 65 RPM & 15K WT ON BIT
04:00	0.50	04:30	7	LUBRICATE RIG	RIG SERVICE
04:30	1.50	06:00	2	DRILL ACTUAL	W/ 730 GPM 65 RPM & 15K WT ON BIT

7-4D-45 BTR 7/3/2012 06:00 - 7/4/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	0.50	06:30	5	COND MUD & CIRC	CIRC. & COND. MUD FOR TRIP OUT
06:30	2.00	08:30	6	TRIPS	TRIP OUT OF HOLE
08:30	1.50	10:00	20	DIRECTIONAL WORK	CHANGE OUT DIRECTIONAL MWD TOOL
10:00	2.00	12:00	6	TRIPS	TRIP IN THE HOLE, NO FILL ON BTM...
12:00	13.50	01:30	2	DRILL ACTUAL	BIT WT= 15K - 20K RPM= 50 SPM=180
01:30	0.50	02:00	5	COND MUD & CIRC	CIRC. & COND. MUD
02:00	2.50	04:30	6	TRIPS	TRIP FOR MUD MTR ISSUES
04:30	1.50	06:00	20	DIRECTIONAL WORK	CHANGE OUT MOTORS AND RESCRIBE TOOL

7-4D-45 BTR 7/4/2012 06:00 - 7/5/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	20	DIRECTIONAL WORK	CHANGE OUT MUD MOTORS
07:00	1.50	08:30	6	TRIPS	T.I.H. AND NO FILL
08:30	8.00	16:30	2	DRILL ACTUAL	BIT WT= 20K - 25K RPM= 55 STK'S= 180
16:30	0.50	17:00	5	COND MUD & CIRC	CIRC. & COND. MUD FOR TRIP OUT...
17:00	2.00	19:00	6	TRIPS	TRIP FOR MOTOR AND BIT...
19:00	2.00	21:00	20	DIRECTIONAL WORK	CHANGE OUT BIT AND MOTOR
21:00	1.50	22:30	6	TRIPS	T.I.H, NO FILL ON BTM
22:30	7.50	06:00	2	DRILL ACTUAL	BIT WT= 35K RPM= 50 SPM= 180

7-4D-45 BTR 7/5/2012 06:00 - 7/6/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

**Time Log**

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	8.50	14:30	2	DRILL ACTUAL	BIT WT= 45K RPM= 50 SPM= 160
14:30	1.00	15:30	5	COND MUD & CIRC	CIRC. & COND. MUD AND RAISE MUD WT UP DUE TO GAS SHOW...
15:30	2.00	17:30	6	TRIPS	TRIP OUT OF HOLE, FOUND TOP REAMER HAS BEEN WASHED OUT...
17:30	4.00	21:30	20	DIRECTIONAL WORK	L/D REAMERS, MUD MTR, AND BIT... P/U NEW BIT, MTR, AND REAMERS... CHANGE OUT INTERCONNECT ON MWD TOOL...
21:30	1.50	23:00	6	TRIPS	TRIP IN HOLE
23:00	6.50	05:30	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 50 SPM= 180
05:30	0.50	06:00	5	COND MUD & CIRC	CIRC. & COND. MUD FOR TRIP OUT...

7-4D-45 BTR 7/6/2012 06:00 - 7/7/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	5	COND MUD & CIRC	CIRC MUD, FOR TRIP OUT...
07:00	1.50	08:30	6	TRIPS	T.O.H...
08:30	2.50	11:00	20	DIRECTIONAL WORK	L/D 8" TOOL'S, DC'S, BIT AND MOTOR...
11:00	4.50	15:30	12	RUN CASING & CEMENT	RAN 64 JT'S OF 9 5/8'S , 36# , J-55, TO A DEPTH OF 2800'
15:30	0.50	16:00	5	COND MUD & CIRC	CIRC. CSG. WITH RIG PUMP
16:00	4.00	20:00	12	RUN CASING & CEMENT	R/U AND CMT WITH HALLIBURTON... PUMP 460 SX'S/259 BBL'S OF LEAD CMT @ 11.0#... PUMP 230 SX'S/55 BBL'S OF TAIL CMT @ 14.8#... DISPLACEMENT 212.9 BBL'S OF DISPLACEMENT WATER...
20:00	2.00	22:00	21	OPEN	WAIT ON CMT
22:00	1.00	23:00	12	RUN CASING & CEMENT	1" TOP JOB, CMT TOP JOB... PUMP 80 BBL'S...
23:00	2.00	01:00	21	OPEN	WAIT ON CMT...
01:00	2.00	03:00	22	OPEN	WELD ON WELL HEAD WITH BADLANDERZ WELDERS...
03:00	3.00	06:00	14	NIPPLE UP B.O.P	NIPPLE UP BOP'S...

7-4D-45 BTR 7/7/2012 06:00 - 7/8/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	21	OPEN	PSI TESTING WELL HEAD, TO 1200 PSI, NO LEAKS
07:00	4.00	11:00	14	NIPPLE UP B.O.P	NIPPLE UP BOP'S, KILL VALVE, HCR VALVE, AND CHOKE LINE...
11:00	6.50	17:30	15	TEST B.O.P	TEST BOPS, AND ALL VALVES AND RAMS TO 5K...
17:30	2.00	19:30	22	OPEN	HERO VALVE GOT DROPPED ON TESTERS PSI LINE AND PUNCTURED HOSE, WAITNING ON REPLACEMENT HOSE TO COME FROM VERNAL...
19:30	1.00	20:30	15	TEST B.O.P	FINISH TEST BOP'S WITH B&C QUICK TEST
20:30	2.00	22:30	20	DIRECTIONAL WORK	P/U BIT, MTR AND ALL 6" DIRECTIONAL TOOL'S
22:30	1.50	00:00	6	TRIPS	TRIP IN HOLE
00:00	1.00	01:00	23	OPEN	DRLG FLOAT EQUIP... DRLG CMT @ 2730... DRLG FLOAT @ 2757... DRLG SHOE @ 2800...
01:00	0.50	01:30	21	OPEN	HELD EMW TEST, HELD SERVICE PSI @ 225 FOR 20 MINUTES, EQUIVILANT MUD WT= 10.5
01:30	4.50	06:00	2	DRILL ACTUAL	BIT WT= 8 K RPM= 55 SPM=140

7-4D-45 BTR 7/8/2012 06:00 - 7/9/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion



Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	11.00	17:00	2	DRILL ACTUAL	BIT WT= 15K RPM= 55 SPM= 140	
17:00	0.50	17:30	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE...	
17:30	6.50	00:00	2	DRILL ACTUAL	BIT WT= 15K RPM= 55 SPM= 140	
00:00	0.50	00:30	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE	
00:30	2.00	02:30	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 55 SPM= 120	
02:30	2.00	04:30	5	COND MUD & CIRC	100% LOSSES, REBUILD VOLUME AND RAISE LCM% TO 20%	
04:30	1.50	06:00	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 45 SPM=80	

7-4D-45 BTR 7/9/2012 06:00 - 7/10/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	23.00	05:00	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 55 SPM= 100	
05:00	0.50	05:30	7	LUBRICATE RIG	SERVICE TOP DRIVE AND RIG	
05:30	0.50	06:00	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 55 SPM= 120	

7-4D-45 BTR 7/10/2012 06:00 - 7/11/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	11.50	17:30	2	DRILL ACTUAL	BIT WT= 15 K RPM= 55 SPM= 120	
17:30	0.50	18:00	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE, AND PUMPS	
18:00	11.50	05:30	2	DRILL ACTUAL	BIT WT= 15K RPM= 50 SPM= 120	
05:30	0.50	06:00	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE	

7-4D-45 BTR 7/11/2012 06:00 - 7/12/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	11.50	17:30	2	DRILL ACTUAL	BIT WT= 15K RPM= 55 SPM= 120	
17:30	0.50	18:00	7	LUBRICATE RIG	SERVICE TOP DRIVE & RIG...	
18:00	10.50	04:30	2	DRILL ACTUAL	BIT WT= 15K RPM= 55 SPM= 120	
04:30	0.50	05:00	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE	
05:00	1.00	06:00	2	DRILL ACTUAL	BIT WT= 15K RPM=55 SPM=120	

7-4D-45 BTR 7/12/2012 06:00 - 7/13/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status COMPLETION	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	---------------------------	-------------------------------	---

**Time Log**

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	11.50	17:30	2	DRILL ACTUAL	BIT WT= 15K RPM= 55 SPM= 120
17:30	0.50	18:00	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE
18:00	9.50	03:30	2	DRILL ACTUAL	BIT WT= 15K RPM= 55 SPM= 120
03:30	0.50	04:00	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE
04:00	2.00	06:00	2	DRILL ACTUAL	BIT WT= 15K RPM=55 SPM=120

7-4D-45 BTR 7/13/2012 06:00 - 7/14/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	7.50	13:30	2	DRILL ACTUAL	BIT WT= 18K RPM= 55 SPM=120
13:30	1.00	14:30	5	COND MUD & CIRC	CIRC. & COND MUD, PUMP SWEEP & DRY JOB
14:30	5.00	19:30	6	TRIPS	T.O.H FOR BIT AND MOTOR
19:30	1.00	20:30	20	DIRECTIONAL WORK	CHANGE OUT BITS AND MOTOR,
20:30	4.00	00:30	6	TRIPS	T.I.H., NO FILL ON BTM
00:30	3.50	04:00	5	COND MUD & CIRC	BUILD VOLUME
04:00	2.00	06:00	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 55 SPM=100

7-4D-45 BTR 7/14/2012 06:00 - 7/15/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	10.00	16:00	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 55 SPM= 100
16:00	0.50	16:30	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE
16:30	11.50	04:00	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 55 SPM= 100
04:00	0.50	04:30	7	LUBRICATE RIG	SERVICE RIG
04:30	1.50	06:00	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM=55 SPM= 120

7-4D-45 BTR 7/15/2012 06:00 - 7/16/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	11.50	17:30	2	DRILL ACTUAL	BIT WT= 12K - 15K RPM= 55 SPM= 100
17:30	0.50	18:00	7	LUBRICATE RIG	SERVICE RIG AND TOP DRIVE
18:00	7.50	01:30	2	DRILL ACTUAL	BIT WT= 15K RPM=55 SPM=140
01:30	1.00	02:30	5	COND MUD & CIRC	CIRC. AND COND. MUD, PUMP SWEEP AND DRY JOB FOR TRIP
02:30	3.50	06:00	6	TRIPS	T.O.H. FOR LOGS

7-4D-45 BTR 7/16/2012 06:00 - 7/17/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

**Time Log**

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	3.00	09:00	6	TRIPS	TRIP OUT FOR LOGS
09:00	1.50	10:30	20	DIRECTIONAL WORK	L/D ALL DIRECTIONAL TOOL'S, MUD MOTOR, AND BIT...
10:30	6.50	17:00	11	WIRELINE LOGS	R/U HALLIBURTON WIRELINE, LOG WELL, AND R/D THE SAME... LOGGERS DEPTH= 8978.0
17:00	1.50	18:30	6	TRIPS	TRIP IN BHA...
18:30	1.00	19:30	9	CUT OFF DRILL LINE	SLIP AND CUT DRLG LINE, 14 WRAPS
19:30	5.50	01:00	6	TRIPS	TRIP INTO BTM
01:00	2.00	03:00	5	COND MUD & CIRC	CIRC. AND RAISE MUD WT
03:00	3.00	06:00	6	TRIPS	L/D D.P.,

7-4D-45 BTR 7/17/2012 06:00 - 7/18/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	6.50	12:30	6	TRIPS	L/D DRILL PIPE & BHA
12:30	0.50	13:00	21	OPEN	PULL WEAR BUSHING
13:00	5.00	18:00	12	RUN CASING & CEMENT	R/U CSG CREW & RUN CSG TO 4400'
18:00	4.00	22:00	5	COND MUD & CIRC	CIRC & BUILD VOLUME (LOST RETURNS @ 4400') LOWER MW TO 9.5
22:00	7.00	05:00	12	RUN CASING & CEMENT	FINISH RUNNING CSG - RUN A TOTAL OF 204 JOINTS 5.5" 17# P-110 CSG WITH 3 MARKER JOINTS & 72 CENTRILIZERS - CSG SET @ 8909'
05:00	1.00	06:00	5	COND MUD & CIRC	CIRC - TRY TO WASH TO BOTTOM - UNABLE TO WASH TO BOTTOM LAY DOWN ONE JOINT

7-4D-45 BTR 7/18/2012 06:00 - 7/19/2012 00:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	2.50	08:30	5	COND MUD & CIRC	CIRC & COND MUD FOR CEMENT
08:30	4.50	13:00	12	RUN CASING & CEMENT	R/U CEMENTERS TEST LINES @ 5000 PSI - PUMP 10 BBLS WATER SPACER, 40 BBLS SUPER FLUSH, 10 BBLS WATER SPACER, 293.7 BBLS 710 SKS 11.0# 2.33 YIELD LEAD CEMENT MIXED @ 10.66 GAL/SK, 137.8 BBLS 545 SKS 13.5# 1.42 YIELD TAIL CEMENT MIXED @ 6.61 GAL/SK, SHUT DOWN WASH LINES DROP PLUG & DISPLACE WITH 201.5 BBLS CLAY-WEB WATER, BUMP PLUG FCP 1580 PSI PRESSURE UP 500 PSI OVER 2100 PSI HELD FOR 2 MIN RELEASE PRESSURE FLOATS HELD - LOST RETURNS 195 BBLS INTO DISPLACEMENT - 0 BBLS CEMENT TO SURFACE - R/D CEMENTERS
13:00	1.00	14:00	14	NIPPLE DOWN B.O.P	NIPPLE DOWN B.O.P.
14:00	0.50	14:30	21	OPEN	SET SLIPS @ 175K - CUT OFF CSG
14:30	1.50	16:00	14	NIPPLE DOWN B.O.P	FINISH NIPPLE DOWN
16:00	8.00	00:00	21	OPEN	CLEAN MUD TANKS WHILE RIGGING DOWN - RIG RELEASED @ 0:00 HRS 7/19/12

7-4D-45 BTR 7/20/2012 00:00 - 7/21/2012 00:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
00:00	24.00	00:00	LOCL	Lock Wellhead & Secure	Blade and cleaned location for completion activities.

7-4D-45 BTR 7/21/2012 00:00 - 7/22/2012 00:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
00:00	24.00	00:00	LOCL	Lock Wellhead & Secure	Clean cellar ring and prep for well head.

7-4D-45 BTR 7/22/2012 00:00 - 7/23/2012 00:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion



Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
00:00	24.00	00:00	LOCL	Lock Wellhead & Secure	Cameron Arrvied on location. Safety Meeting, Check pressures on surface Csg & 5.5" casing. 0 psi on both side. Removed 11' x 5k night cap. Dressed 5.5" casing top. Installed 11" x 7 1/16" x 5k B-section. Pressure tested hanger seals to 5k. Good test. Installed 7 1/16" night cap. Secured Well head.	

7-4D-45 BTR 7/23/2012 06:00 - 7/24/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	1.00	07:00	GOP	General Operations	WSI And Secured.	
07:00	1.25	08:15	SRIG	Rig Up/Down	MIRU SLB W/L Crew And Equipment. Hold Safety Meeting. Rig Up Gauge Ring And Logging Tool.	
08:15	5.75	14:00	LOGG	Logging	P/U Junk Basket/Gauge Ring. RIH, Tagged Up At 8,844', Drilling Report Shows FC At 8,818', 0' Of Fill. POOH, P/U CBL Tool, Rih To PBTD, 8,844', Correlating To HES Spectral Density/ Dual Spaced Neutron Dated 07-16-2012. Run Repeat Section From 8,844' - 8,640', Log Up Hole. Showed Good Bond From TD To 4330', 4330' - 2050' Good/Poor. TOC 2050'. Ran With Pressure. Found Short Joints At 8,358' - 8,380', 7,466' - 7,489' And 5,156' - 5,178'. Pooh, RD Equipment, MOL.	
14:00	16.00	06:00	LOCL	Lock Wellhead & Secure	WSI And Secured	

7-4D-45 BTR 7/25/2012 00:00 - 7/26/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
00:00	24.00	00:00	FRAC	Frac. Job	SPOTTING FRAC TANKS.	

7-4D-45 BTR 7/26/2012 06:00 - 7/27/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	24.00	06:00	FRAC	Frac. Job	SPOTTING FRAC TANKS.	
06:00		06:00				

7-4D-45 BTR 7/27/2012 06:00 - 7/28/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	24.00	06:00	FRAC	Frac. Job	43) 600 BBLs FRAC TANKS SPOTTED ON LOC. 20% FILLED W/ PROD 2% AND FRESH 2%. FACILITIES UNDER CONSTRUCTION	

7-4D-45 BTR 7/28/2012 06:00 - 7/29/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00		06:00			FILLING FRAC TANKS. 50% FILLED. BATTERY UNDER CONSTRUCTION	

7-4D-45 BTR 7/29/2012 06:00 - 7/30/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	COMPLETION	8,972.0	Drilling & Completion

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00		06:00			FILLING FRAC TANKS. 75% FILLED. BATTERY UNDER CONSTRUCTION	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5.LEASE DESIGNATION AND SERIAL NUMBER: 1420H626281
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE 7.UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: 7-4D-45 BTR
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43013508840000
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext
9. FIELD and POOL or WILDCAT: ALTAMONT	4. LOCATION OF WELL FOOTAGES AT SURFACE: 2338 FNL 2002 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 04.0S Range: 05.0W Meridian: U
	COUNTY: DUCHESNE STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/13/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This well had first gas sales on 8/9/2012 and first oil sales on 8/13/2012.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY

August 14, 2012

NAME (PLEASE PRINT) Venessa Langmacher	PHONE NUMBER 303 312-8172	TITLE Senior Permit Analyst
SIGNATURE N/A	DATE 8/14/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5.LEASE DESIGNATION AND SERIAL NUMBER: 1420H626281
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE 7.UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: 7-4D-45 BTR
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43013508840000
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext
9. FIELD and POOL or WILDCAT: ALTAMONT	4. LOCATION OF WELL FOOTAGES AT SURFACE: 2338 FNL 2002 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 04.0S Range: 05.0W Meridian: U
	COUNTY: DUCHESNE STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 8/31/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

August 2012 monthly drilling activity report is attached.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 September 05, 2012

NAME (PLEASE PRINT) Megan Finnegan	PHONE NUMBER 303 299-9949	TITLE Permit Analyst
SIGNATURE N/A	DATE 9/4/2012	

**7-4D-45 BTR 8/1/2012 06:00 - 8/2/2012 06:00**

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	24.00	06:00	GOP	General Operations	Production Crew Insulating Facilities Nipple Up Frac Mandrel, Test Seals Nipple Up Frac Tree. Test Casing. Rig Up FlowBack To Frac Tree, Test FlowBack Iron. Run Fill Line To 1 2% KCL Tank.

7-4D-45 BTR 8/4/2012 06:00 - 8/5/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	24.00	06:00	GOP	General Operations	Heat 2% KCL Tanks In Frac Line To 80 degrees

7-4D-45 BTR 8/5/2012 06:00 - 8/6/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	LOCL	Lock Wellhead & Secure	WSI And Secured. 0 Psi. On Well.
07:00	1.50	08:30	SRIG	Rig Up/Down	SLB WireLine Arrive On Location. Hold Safety Meeting. Rig Up Equipment. Pick Up Lubricator, Arm Gun, Rig Up To Well.
08:30	1.00	09:30	PFRT	Perforating	RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 8,358 - 8,380'. Drop Down To Depth, Perforate Stage 1 CR-4A/CR-4 Zone, 8,604 - 8,824'. 51 Holes. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.
09:30	3.50	13:00	SRIG	Rig Up/Down	HES On Location At 10:00 Hrs. Rig Up Equipment
13:00	17.00	06:00	LOCL	Lock Wellhead & Secure	WSI And Secured. SDFD.

7-4D-45 BTR 8/6/2012 06:00 - 8/7/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	0.01	06:00	LOCL	Lock Wellhead & Secure	HES Crew On Location At 0500 Hrs., Prime Chemical And Fluid Pumps, Pressure Test To 9000 Psi., Ran QC On Fluid, Looks Good.
06:00	0.24	06:15	SMTG	Safety Meeting	Safety Meeting. Talk About Smoking Area, PPE, Escape And Mustering Areas, Communication, And Red Zone.
06:15	1.50	07:45	FRAC	Frac. Job	Frac Stage 1. Fluid System: Hybor G 16 Open Well, 1,181 Psi. ICP. BrokeDown At 9.3 Bpm And 3,823 Psi.. Pump 3900 Gals. 15% HCL And 102 Bio Balls, Attempt BallOut. Let Balls Fall. Get Stabilized Injection Of 68.8 Bpm And 4,222 Psi., Get ISIP, 2,820 Psi.. 0.76 Psi./Ft. F.G.. 41/51 Holes. Con't With SlickWater Pad, 50,015 Gals.. Stage Into X-Link Pad, On Perfs., 72.0 Bpm At 4,369 Psi., 12,551 Gals. Stage Into 2# 20/40 CRC, On Perfs., 71.4 Bpm At 4,017 Psi., 9,531 Gals. Stage Into 3# 20/40 CRC, On Perfs., 71.6 Bpm At 3,827 Psi., 20,476 Gals. Stage Into 3.5# 20/40 CRC, On Perfs., 71.7 Bpm At 3,772 Psi., 10,540 Gals. Stage Into 4# 20/40 CRC, On Perfs., 71.4 Bpm At 3,793 Psi., 11,234 Gals. Stage Into Flush, Flush 15 Bbls. Over Bottom Perf.. Get ISDP, 2,970 Psi.. 0.78 Psi./Ft. F.G.. WSI And Secured. Total 20/40 CRC - 155,300# Total Clean - 154,190 Gals.. (3,300 Bbls..) 66,510 Gals. 2% KCL(1,584 Bbls.) 68,715 Gals. Produced Water(1,636 Bbls.) BWTR - 3,420 Bbls. Max. Rate - 73.4 Bpm Avg. Rate - 71.6 Bpm Max. Psi. - 4,390 Psi. Avg. Psi. - 3,953 Psi.
07:45	0.25	08:00	CTUW	W/L Operation	Well Turned Over To WireLine. Pick Up Gun String And CBP Plug Assembly. Equalize To Well Pressure.



Time Log					
Start Time	Dur (hr)	End Time	Code	Category	Com
08:00	1.34	09:20	PFRT	Perforating	RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 8,358 - 8,380'. Drop Down, Set CBP At 8,590', 2700 Psi. On Well. Pull Up And Perforate Stage 2 CR-4 Zone, 8,319 - 8,575'. 45 Holes. 2600 Psi. On Well. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.
09:20	0.17	09:30	GOP	General Operations	Well Turned Over To HES. Pressure Test To 8500#. Equalize, Open To Well.
09:30	1.33	10:50	FRAC	Frac. Job	Frac Stage 2. Fluid System: Hybor G 16 Open Well, 2,380 Psi. ICP. BrokeDown At 10.1 Bpm And 3,299 Psi.. Pump 3900 Gals. 15% HCL And 90 Bio Balls, Attempt BallOut. Let Balls Fall. Get Stabilized Injection Of 70.2 Bpm And 4,148 Psi., Get ISIP, 2,693 Psi.. 0.76 Psi./Ft. F.G.. 45/45 Holes. Con't With SlickWater Pad, 48,139 Gals.. Stage Into X-Link Pad, On Perfs., 70.3 Bpm At 4,285 Psi., 12,112 Gals. Stage Into 2# 20/40 CRC, On Perfs., 70.9 Bpm At 4,007 Psi., 9,362 Gals. Stage Into 3# 20/40 CRC, On Perfs., 71.0 Bpm At 3,887 Psi., 19,433 Gals. Stage Into 3.5# 20/40 CRC, On Perfs., 71.0 Bpm At 4,197 Psi., 18,167 Gals. Stage Into Flush, Flush 15 Bbls. Over Bottom Perf.. Get ISDP, 3,321 Psi.. 0.83 Psi./Ft. F.G.. WSI And Secured. Total 20/40 CRC - 134,800# Total Clean - 129,459 Gals.. (3,082 Bbls..) 61,239 Gals. 2% KCL(1,458 Bbls.) 66,510 Gals. Produced Water(1,584 Bbls.) BWTR - 3,221 Bbls. Max. Rate - 73.0 Bpm Avg. Rate - 70.9 Bpm Max. Psi. - 4,731 Psi. Avg. Psi. - 4,120 Psi.
10:50	0.25	11:05	CTUW	W/L Operation	Well Turned Over To WireLine. Pick Up Gun String And CBP Plug Assembly. Equalize To Well Pressure.
11:05	1.25	12:20	PFRT	Perforating	RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 7,466 - 7,489'. Drop Down, Set CBP At 8,295', 2700 Psi. On Well. Pull Up And Perforate Stage 3 CR-3/CR-2 Zone, 7,988 - 8,275'. 45 Holes. 2650 Psi. On Well. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.
12:20	0.08	12:25	GOP	General Operations	Well Turned Over To HES. Pressure Test To 8500#. Equalize, Open To Well.
12:25	1.42	13:50	FRAC	Frac. Job	Frac Stage 3. Fluid System: Hybor G 16 Open Well, 2,432 Psi. ICP. BrokeDown At 10.2 Bpm And 3,246 Psi.. Pump 3900 Gals. 15% HCL And 90 Bio Balls, Attempt BallOut. Let Balls Fall. Get Stabilized Injection Of 70.2 Bpm And 4,151 Psi., Get ISIP, 2,619 Psi.. 0.76 Psi./Ft. F.G.. 45/45 Holes. Con't With SlickWater Pad, 51,574 Gals.. Stage Into X-Link Pad, On Perfs., 69.3 Bpm At 4,268 Psi., 12,350 Gals. Stage Into 2# 20/40 White, On Perfs., 70.0 Bpm At 3,925 Psi., 9,043 Gals. Stage Into 3# 20/40 White, On Perfs., 70.3 Bpm At 3,660 Psi., 23,735 Gals. Stage Into 3.5# 20/40 White, On Perfs., 70.2 Bpm At 3,720 Psi., 10,046 Gals. Stage Into 4# 20/40 White, On Perfs., 70.3 Bpm At 3,441 Psi., 9,602 Gals. Stage Into Flush, Flush 15 Bbls. Over Bottom Perf.. Get ISDP, 2,800 Psi.. 0.78 Psi./Ft. F.G.. WSI And Secured. Total 20/40 White - 159,900# Total Clean - 139,180 Gals.. (3,314 Bbls..) 66,920 Gals. 2% KCL(1,593 Bbls.) 70,242 Gals. Produced Water(1,672 Bbls.) BWTR - 3,486 Bbls. Max. Rate - 73.2 Bpm Avg. Rate - 70.2 Bpm Max. Psi. - 4,340 Psi. Avg. Psi. - 3,881 Psi.
13:50	0.25	14:05	CTUW	W/L Operation	Well Turned Over To WireLine. Pick Up Gun String And CBP Plug Assembly. Equalize To Well Pressure.
14:05	1.17	15:15	PFRT	Perforating	RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 7,466 - 7,489'. Drop Down, Set CBP At 7,958', 2500 Psi. On Well. Pull Up And Perforate Stage 4 CR-2/Wasatch Zone, 7,725 - 7,944'. 45 Holes. 2450 Psi. On Well. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.
15:15	0.17	15:25	GOP	General Operations	Well Turned Over To HES. Pressure Test To 8500#. Equalize, Open To Well.



Time Log					
Start Time	Dur (hr)	End Time	Code	Category	Com
15:25	1.41	16:50	FRAC	Frac. Job	Frac Stage 4. Fluid System: Hybor G 16 Open Well, 2,350 Psi. ICP. BrokeDown At 9.7 Bpm And 2,868 Psi.. Pump 3900 Gals. 15% HCL And 90 Bio Balls, Attempt BallOut. Let Balls Fall. Get Stabilized Injection Of 70.3 Bpm And 3,684 Psi., Get ISIP, 2,240 Psi.. 0.73 Psi./Ft. F.G.. 38/45 Holes. Con't With SlickWater Pad, 51,623 Gals.. Stage Into X-Link Pad, On Perfs., 70.6 Bpm At 3,815 Psi., 13,035 Gals. Stage Into 2# 20/40 White, On Perfs., 70.2 Bpm At 3,508 Psi., 8,741 Gals. Stage Into 3# 20/40 White, On Perfs., 70.4 Bpm At 3,262 Psi.,24,742 Gals. Stage Into 3.5# 20/40 White, On Perfs., 70.5 Bpm At 3,187 Psi.,9,761 Gals. Stage Into 4# 20/40 White, On Perfs., 70.4 Bpm At 3,225 Psi., 9,947 Gals. Stage Into Flush, Flush 15 Bbls. Over Bottom Perf.. Get ISDP, 2,350 Psi.. 0.74 Psi./Ft. F.G.. WSI And Secured. Total 20/40 White - 159,800# Total Clean - 138,701 Gals.. (3,302 Bbls..) 68,243 Gals. 2% KCL(1,625 Bbls.) 68,559 Gals. Produced Water(1,632 Bbls.) BWTR - 3,469 Bbls. Max. Rate - 70.7 Bpm Avg. Rate - 70.4 Bpm Max. Psi. - 3,851 Psi. Avg. Psi. - 3,406 Psi.
16:50	0.25	17:05	CTUW	W/L Operation	Well Turned Over To WireLine. Pick Up Gun String And CBP Plug Assembly. Equalize To Well Pressure.
17:05	1.17	18:15	PFRT	Perforating	RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 7,466 - 7,489'. Drop Down, Set CBP At 7,715', 2100 Psi. On Well. Pull Up And Perforate Stage 5 CR-1/UteLand Butte Zone, 7,474 - 7,695'. 45 Holes. 2000 Psi. On Well. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.
18:15	0.75	19:00	SRIG	Rig Up/Down	ShutDown And Secure Equipment
19:00	11.00	06:00	LOCL	Lock Wellhead & Secure	WSI And Secured. SDFD.

7-4D-45 BTR 8/7/2012 06:00 - 8/8/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log					
Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	0.50	06:30	LOCL	Lock Wellhead & Secure	HES Crew On Location At 0600 Hrs., Prime Chemical And Fluid Pumps, Pressure Test To 9000 Psi., Ran QC On Fluid, Looks Good.
06:30	0.34	06:50	SMTG	Safety Meeting	Safety Meeting. Talk About Smoking Area, PPE, Escape And Mustering Areas, Communication, And Red Zone.
06:50	1.34	08:10	FRAC	Frac. Job	Frac Stage 5. Fluid System: Hybor G 16 Open Well, 1,975 Psi. ICP. BrokeDown At 9.3 Bpm And 2,967 Psi.. Pump 3900 Gals. 15% HCL And 90 Bio Balls, Attempt BallOut. Let Balls Fall. Get Stabilized Injection Of 70.8 Bpm And 3,560 Psi., Get ISIP, 2,162 Psi.. 0.73 Psi./Ft. F.G.. 39/45 Holes. Con't With SlickWater Pad, 48,355 Gals.. Stage Into .75# 100 Mesh, On Perfs., 71.1 Bpm At 3,535 Psi., 15,726 Gals. Stage Into 1# 20/40 White, On Perfs., 71.3 Bpm At 3,490 Psi., 9,359 Gals. Stage Into 2# 20/40 White, On Perfs., 71.2 Bpm At 3,311 Psi., 8,974 Gals. Stage Into 3# 20/40 White, On Perfs., 71.2 Bpm At 3,131 Psi.,19,501 Gals. Stage Into 3.5# 20/40 White, On Perfs., 71.1 Bpm At 3,075 Psi.,9,351 Gals. Stage Into 4# 20/40 White, On Perfs., 71.2 Bpm At 3,060 Psi., 8,903 Gals. Stage Into Flush, Flush 15 Bbls. Over Bottom Perf.. Get ISDP, 2,475 Psi.. 0.77 Psi./Ft. F.G.. WSI And Secured. Total 100 Mesh - 15,500# Total 20/40 White - 148,500# Total Clean - 139,863 Gals.. (3,330 Bbls..) 73,823 Gals. 2% KCL(1,758 Bbls.) 64,087 Gals. Produced Water(1,526 Bbls.) BWTR - 3,509 Bbls. Max. Rate - 71.8 Bpm Avg. Rate - 71.2 Bpm Max. Psi. - 3,622 Psi. Avg. Psi. - 3,293 Psi.
08:10	0.16	08:20	CTUW	W/L Operation	Well Turned Over To WireLine. Pick Up Gun String And CBP Plug Assembly. Equalize To Well Pressure.



Time Log					
Start Time	Dur (hr)	End Time	Code	Category	Com
08:20	1.17	09:30	PFRT	Perforating	RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 5,156 - 5,178'. Drop Down, Set CBP At 7,460', 2100 Psi. On Well. Pull Up And Perforate Stage 6 Castle Peak Zone, 7,303 - 7,446'. 42 Holes. 2050 Psi. On Well. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.
09:30	0.17	09:40	GOP	General Operations	Well Turned Over To HES. Pressure Test To 8500#. Equalize, Open To Well.
09:40	1.41	11:05	FRAC	Frac. Job	Frac Stage 6. Fluid System: Hybor G 16 Open Well, 1,890 Psi. ICP. BrokeDown At 9.5 Bpm And 2,992 Psi.. Pump 3900 Gals. 15% HCL And 84 Bio Balls, Attempt BallOut. Let Balls Fall. Get Stabilized Injection Of 71.1 Bpm And 3,534 Psi., Get ISIP, 1,844 Psi.. 0.69 Psi./Ft. F.G.. 33/42 Holes. Con't With SlickWater Pad, 51,729 Gals.. Stage Into .75# 100 Mesh, On Perfs., 71.3 Bpm At 3,487 Psi., 17,639 Gals. Stage Into 1# 20/40 White, On Perfs., 71.3 Bpm At 3,390 Psi., 11,643 Gals. Stage Into 2# 20/40 White, On Perfs., 71.2 Bpm At 3,206 Psi., 11,660 Gals. Stage Into 3# 20/40 White, On Perfs., 71.0 Bpm At 3,226 Psi.,19,839 Gals. Stage Into 3.5# 20/40 White, On Perfs., 71.1 Bpm At 3,391 Psi.,9,251 Gals. Stage Into 4# 20/40 White, On Perfs., 70.8 Bpm At 3,772 Psi., 3,788 Gals. Stage Into Flush, Flush 15 Bbls. Over Bottom Perf.. Get ISDP, 1,908 Psi.. 0.70 Psi./Ft. F.G.. WSI And Secured. Total 100 Mesh - 13,100# Total 20/40 White - 136,400# Total Clean - 146,266 Gals.. (3,483 Bbls..) 75,801 Gals. 2% KCL(1,805 Bbls.) 68,555 Gals. Produced Water(1,632 Bbls.) BWTR - 3,646 Bbls. Max. Rate - 71.4 Bpm Avg. Rate - 71.2 Bpm Max. Psi. - 3,376 Psi. Avg. Psi. - 3,371 Psi.
11:05	0.17	11:15	CTUW	W/L Operation	Well Turned Over To WireLine. Pick Up Gun String And CBP Plug Assembly. Equalize To Well Pressure.
11:15	1.17	12:25	PFRT	Perforating	RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 5,156 - 5,178'. Drop Down, Set CBP At 7,290', 1550 Psi. On Well. Pull Up And Perforate Stage 7 Castle Peak/Black Shale Zone, 6,994 - 7,278'. 45 Holes. 1500 Psi. On Well. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.
12:25	0.33	12:45	GOP	General Operations	Well Turned Over To HES. Pressure Test To 8500#. Equalize, Open To Well.
12:45	1.50	14:15	FRAC	Frac. Job	Frac Stage 6. Fluid System: Hybor G 16 Open Well, 1,350 Psi. ICP. BrokeDown At 10.1 Bpm And 1,522 Psi.. Pump 3900 Gals. 15% HCL And 90 Bio Balls, Attempt BallOut. Let Balls Fall. Get Stabilized Injection Of 71.0 Bpm And 2,913 Psi., Get ISIP, 1,690 Psi.. 0.68 Psi./Ft. F.G.. 45/45 Holes. Con't With SlickWater Pad, 48,193 Gals.. Stage Into .75# 100 Mesh, On Perfs., 71.5 Bpm At 2,981 Psi., 17,996 Gals. Stage Into 1# 20/40 White, On Perfs., 67.2 Bpm At 2,804 Psi., 8,870 Gals. Stage Into 2# 20/40 White, On Perfs., 71.2 Bpm At 2,745 Psi., 11,077 Gals. Stage Into 3# 20/40 White, On Perfs., 71.2 Bpm At 2,608 Psi.,23,058 Gals. Stage Into 3.5# 20/40 White, On Perfs., 71.2 Bpm At 2,513 Psi.,9,199 Gals. Stage Into 4# 20/40 White, On Perfs., 71.2 Bpm At 2,462 Psi., 12,774 Gals. Stage Into Flush, Flush 15 Bbls. Over Bottom Perf.. Get ISDP, 1,970 Psi.. 0.72 Psi./Ft. F.G.. WSI And Secured. Total 100 Mesh - 13,000# Total 20/40 White - 181,000# Total Clean - 151,362 Gals.. (3,604 Bbls..) 85,137 Gals. 2% KCL(2,027 Bbls.) 64,295 Gals. Produced Water(1,531 Bbls.) BWTR - 3,509 Bbls. Max. Rate - 71.6 Bpm Avg. Rate - 71.2 Bpm Max. Psi. - 3,013 Psi. Avg. Psi. - 2,693 Psi.
14:15	0.50	14:45	CTUW	W/L Operation	Well Turned Over To WireLine. Pick Up CBP Plug Assembly. Equalize To Well Pressure.
14:45	1.00	15:45	PFRT	Perforating	RIH With CBP Plug Assembly. Correlating To HES Spectral Density/Dual Spaced Neutron Dated 07/16/2012 And SLB CBL/CCL Dated 07/23/2012. Found And Correlated To Marker Joint At 5,156 - 5,178'. Drop Down, Set CBP At 6,930', 1850 Psi. On Well. POOH. LayDown Tools. WSI And Secured.
15:45	2.25	18:00	SRIG	Rig Up/Down	RigDown SLB And HES, MOL.

**Time Log**

Start Time	Dur (hr)	End Time	Code	Category	Com
18:00	12.00	06:00	LOCL	Lock Wellhead & Secure	WSI And Secured. Batch Wwater And Move Frac Tanks Off Location.

7-4D-45 BTR 8/8/2012 06:00 - 8/9/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	PRODUCING	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	CTRL	Crew Travel	Crew travel, safety meeting & jsa
07:00	1.00	08:00	SRIG	Rig Up/Down	MIR & RU
08:00	1.50	09:30	BOPI	Install BOP's	ND Frac tree, NU BOP'S, RU floor & equipment, spot in cat walk & pipe racks, load 1 float tbg on racks & tally top row
09:30	3.00	12:30	RUTB	Run Tubing	Make up 4 3/4 tri-cone, POBS, 1 jt 2 7/8 L-80, XN NIPPLE & RIH while waiting for 2nd float of tbg
12:30	1.50	14:00	RUTB	Run Tubing	Load tbg on pipe racks, RIH tallying to tag kill plug @ 6938'
14:00	3.00	17:00	DOPG	Drill Out Plugs	Rig up swivel & load tbg, drill out kill plug @ 6938', 1000 psi on csg, RIH tag10' fill & drill plug @ 7297', 1050 psi, RIH tag 15' fill & drill plug @ 7465', 1050 psi, RIH to 7521'
17:00	1.00	18:00	GOP	General Operations	Circ. well clean, secure & SWIFN, SICP 1100

7-4D-45 BTR 8/9/2012 06:00 - 8/10/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	PRODUCING	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	CTRL	Crew Travel	Crew travel, safety meeting & jsa, SICP 1200
07:00	5.00	12:00	DOPG	Drill Out Plugs	Open up csg & RIH F/ 7521', tag 7700', c/o & d/o cbp @ 7725', cfp 1000 tag 7927', c/o & d/o cbp @ 7969', cfp 950 tag 8265', c/o & d/o cbp @ 8304', cfp 900 tag 8580', c/o & d/o cbp @ 8598', cfp 950 tag f/c @ 8854' d/o to 8918'
12:00	1.00	13:00	GOP	General Operations	Circ. well clean, finish clean up @ 900 psi on csg
13:00	1.50	14:30	PULT	Pull Tubing	Rig down swivel, lay down 61 jts 2 7/8 L-80 tbg, land tbg w/ 213 jts total L-80 eue tbg in well @ 6975'
14:30	0.50	15:00	BOPR	Remove BOP's	Rig down floor & equipment, ND BOP'S
15:00	1.00	16:00	SRIG	Rig Up/Down	Rig down rig & move away from well
16:00	2.00	18:00	IWHD	Install Wellhead	NU well head & A&J plumb in well head, try to pump off bit, can not pump bit off @ 5k
18:00	1.00	19:00	SRIG	Rig Up/Down	Spot in & RU Rig
19:00	2.00	21:00	inactive	inactive	Wait on cutters wireline
21:00	2.50	23:30	WLWK	Wireline	RU cutters wireline, rih w/ 2 1/8 cutter & tag up @ 6994' wireline depth, equalize tbg & cut @ 6992', cut but didn't drop, try tagging harder but won't drop, POOH & make up new cutter, RIH tag same depth @ 6994, pick up to 6990' & cut, still won't drop, POOH w/ wireline & rig down cutters wireline, sdfn, turn well to flowback
23:30	6.50	06:00	FBCK	Flowback Well	Flow back well

7-4D-45 BTR 8/24/2012 06:00 - 8/25/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	PRODUCING	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	CTRL	Crew Travel	
07:00	6.00	13:00	SWAB	Swab Well Down	swabbing
13:00	1.00	14:00	CTRL	Crew Travel	

7-4D-45 BTR 8/25/2012 06:00 - 8/26/2012 06:00

API/UWI	State/Province	County	Field Name	Well Status	Total Depth (ftKB)	Primary Job Type
43013508840000	UT	Duchesne	Black Tail Ridge	PRODUCING	8,972.0	Drilling & Completion

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	CTRL	Crew Travel	
07:00	5.00	12:00	SWAB	Swab Well Down	



7-4D-45 BTR 8/29/2012 06:00 - 8/30/2012 06:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log					
Start Time	Dur (hr)	End Time	Code	Category	Com
06:00		06:00			SPOT AND RUSU. WAIT ON BOP. PMP KILL AND ND WH. NU BOP. RU FLOOR AND TBG EQUIP. POOH W/ TBG-- 212-JTS, XN, 1 JT, POBS. RIH W/ PROD TBG AS FOLLOWS-- BP, 3 JTS, DESANDER, 4' TBG SUB, PSN, 1-JTS, TAC, 40-JTS SWIFN W/ CSG TO SALES.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: 1420H626281
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: 7-4D-45 BTR	
2. NAME OF OPERATOR: BILL BARRETT CORP	9. API NUMBER: 43013508840000	
3. ADDRESS OF OPERATOR: 1099 18th Street Ste 2300 , Denver, CO, 80202	PHONE NUMBER: 303 312-8164 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2338 FNL 2002 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 04.0S Range: 05.0W Meridian: U		COUNTY: DUCHESNE
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 9/30/2012	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER
		<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
September 2012 monthly drilling activity report is attached.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 02, 2012		
NAME (PLEASE PRINT) Megan Finnegan	PHONE NUMBER 303 299-9949	TITLE Permit Analyst
SIGNATURE N/A	DATE 10/2/2012	

**7-4D-45 BTR 9/7/2012 06:00 - 9/8/2012 00:00**

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
06:00	1.00	07:00	CTRL	Crew Travel	CREW TRAVEL. HOLD SAFETY MEETING.
07:00	2.50	09:30	PULT	Pull Tubing	POOH W/ 1/4 SET TAC. REPLACE W/ NEW 1/4 TURN TAC.
09:30	2.50	12:00	RUTB	Run Tubing	RIH W/ TAC & 264 JTS TBG.
12:00	3.00	15:00	GOP	General Operations	ATTEMPT TO SET TAC. NO LUCK. FLUSH CSG W/ 80 BBL'S. ATTEMPT TO SET TAC. NO LUCK.
15:00	2.50	17:30	PULT	Pull Tubing	POOH W/ TAC. SDFN. OPEN CSG TO SALES.
17:30	12.50	06:00	LOCL	Lock Wellhead & Secure	WELL SECURED. CREW TRAVEL.

7-4D-45 BTR 9/8/2012 00:00 - 9/9/2012 00:00

API/UWI 43013508840000	State/Province UT	County Duchesne	Field Name Black Tail Ridge	Well Status PRODUCING	Total Depth (ftKB) 8,972.0	Primary Job Type Drilling & Completion
---------------------------	----------------------	--------------------	--------------------------------	--------------------------	-------------------------------	---

Time Log

Start Time	Dur (hr)	End Time	Code	Category	Com
00:00	1.00	01:00	CTRL	Crew Travel	CREW TRAVEL. HOLD SAFETY MEETING.
01:00	2.50	03:30	RUTB	Run Tubing	RIH W/ 244 JTS, TAC, 1 JT, S/N, 4' PUP, DESANDER, 3 JTS & BULL PLUG.
03:30	2.00	05:30	GOP	General Operations	SET TAC @ 8009'. 20K TENSION. R/D FLOOR. N/D BOP. R/U ROD EQUIPMENT. R/U D&M. FLUSH TBG W/ 50 BBL'S.
05:30	8.00	13:30	RURP	Run Rods & Pump	P/U ROD PUMP & PRIME. RIH W/ PUMP P/U RODS. 36- 1". 123- 3/4". 92- 7/8". 66- 1". 8' PONY 2' PONY POLISH ROD. SPACE OUT PUMP. TEST TO 800 PSI.
13:30	1.00	14:30	SRIG	Rig Up/Down	R/D RIG & EQUIPMENT. SDFN
14:30	9.50	00:00	CTRL	Crew Travel	CREW TRAVEL.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
1420H626281

1a. Type of Well Oil Well Gas Well Dry Other
 b. Type of Completion New Well Work Over Deepen Plug Back Diff. Resvr.
 Other _____

6. If Indian, Allottee or Tribe Name
 7. Unit or CA Agreement Name and No.

2. Name of Operator **BILL BARRETT CORPORATION** Contact: **MEGAN FINNEGAN**
 E-Mail: **mfinnegan@billbarrettcorp.com**

8. Lease Name and Well No.
7-4D-45 BTR

3. Address **1099 18TH STREET SUITE 2300 DENVER, CO 80202** 3a. Phone No. (include area code)
 Ph: **303-299-9949**

9. API Well No.
43-013-50884

4. Location of Well (Report location clearly and in accordance with Federal requirements)*
 At surface **SWNE 2336FNL 2002FEL**
 At top prod interval reported below **SWNE 2000FNL 2003FEL**
 At total depth **SWNE 2026FNL 2004FEL**

10. Field and Pool, or Exploratory
ALTAMONT
 11. Sec., T., R., M., or Block and Survey or Area **Sec 4 T4S R5W Mer UBM**
 12. County or Parish **DUCHESNE** 13. State **UT**

14. Date Spudded **06/04/2012** 15. Date T.D. Reached **07/16/2012** 16. Date Completed
 D & A Ready to Prod. **08/09/2012**

17. Elevations (DF, KB, RT, GL)*
5794 GL

18. Total Depth: MD **8972** TVD **8952** 19. Plug Back T.D.: MD **8818** TVD **8798.7** 20. Depth Bridge Plug Set: MD **8818** TVD **8798.7**

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
CBL TRIPLE COMBO MUD

22. Was well cored? No Yes (Submit analysis)
 Was DST run? No Yes (Submit analysis)
 Directional Survey? No Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
26.000	16.000 COND	65.0	0	80	80			0	
12.250	9.625 J-55	36.0	0	2800	2800	690	144	0	
8.750	5.500 P-110	17.0	0	8972	8909	1255	432	2160	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.875		8009						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) GREEN RIVER	6994	7695	6994 TO 7695	0.440	132	OPEN
B) WASATCH	7725	8824	7725 TO 8824	0.440	186	OPEN
C)						
D)						

26. Perforation Record

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
6994 TO 7695	GREEN RIVER: SEE TREATMENT STAGES 5 - 7
7725 TO 8824	WASATCH: SEE TREATMENT STAGES 1 - 4

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
08/09/2012	08/14/2012	24	→	276.0	374.0	906.0			FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
22/64	550	1500.0	→	276	374	906	1355	POW	

RECEIVED

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

SEP 20 2012
DIV. OF OIL, GAS & MINING

28b. Production - Interval C									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			▶						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			▶						

28c. Production - Interval D									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			▶						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			▶						

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):
 Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers


Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GREEN RIVER	3045
				MAHOGANY	3758
				DOUGLAS CREEK	6096
				BLACK SHALE	6989
				CASTLE PEAK	7153
				UTELAND BUTTE	7467
				WASATCH	7709
				TD	8972

32. Additional remarks (include plugging procedure):
 Conductor was cemented with grout. TOC was calculated by CBL. CBL mailed due to file size. First gas sales was on 8/9/2012. First oil sales was on 8/13/2012. Attached is Treatment Data.

33. Circle enclosed attachments:
- | | | | |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis | 7 Other: | |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #151190 Verified by the BLM Well Information System.
 For BILL BARRETT CORPORATION, sent to the Vernal**

Name (please print) MEGAN FINNEGAN Title PERMIT ANALYST
 Signature  (Electronic Submission) Date 09/20/2012

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

7-4D-45 BTR Report Continued*

44. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. (cont.)				
AMOUNT AND TYPE OF MATERIAL				
<u>Stage</u>	<u>Bbls Slurry</u>	<u>lbs Common White 100 Mesh Sand</u>	<u>lbs 20/40 White Sand</u>	<u>lbs CRC Sand</u>
1	3,434		51,698	
2	3,180		46,912	
3	3,486		144,880	15,020
4	3,477		53,191	
5	3,508		47,185	
6	3,645	13,100	126,000	
7	3,813		52,204	

*Depth intervals for frac information same as perforation record intervals.



Bill Barrett Corporation

Bill Barrett Corp. (II)

Duchesne Co., UT (NAD27)

Sec.4-T4S-R5W

#7-4D-45 BTR


Wellbore #1

Survey: Survey #1

Standard Survey Report

18 July, 2012






WELL DETAILS: #7-4D-45 BTR							
+N/-S	+E/-W	Northing	Easting	Ground Level:	5793.01	Latitude	Longitude
0.00	0.00	668127.04	2292810.91			40° 9' 46.74 N	110° 27' 8.19 W
Slot							

WELLBORE TARGET DETAILS (MAP CO-ORDINATES AND LAT/LONG)							
Name	TVD	+N/-S	+E/-W	Latitude	Longitude	Shape	
#7-4D-45 BTR Tgt	6473.01	359.16	21.80	40° 9' 50.29 N	110° 27' 7.91 W	Rectangle (Sides: L200.00 W200.00)	

PROJECT DETAILS: Duchesne Co., UT (NAD27)
Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: Utah Central 4302
System Datum: Mean Sea Level

REFERENCE INFORMATION
Co-ordinate (N/E) Reference: Well #7-4D-45 BTR, True North
Vertical (TVD) Reference: WELL @ 5815.01ft
Section (VS) Reference: Slot - (0.00N, 0.00E)
Measured Depth Reference: WELL @ 5815.01ft
Calculation Method: Minimum Curvature

ANNOTATIONS											
TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation			
679.93	680.00	1.800	22.80	5.62	-0.28	5.59	8.59	As of July 02			
1243.85	1244.00	0.400	55.00	13.72	0.74	13.74	17.42	As of July 03			
2286.76	2287.00	1.600	166.00	6.85	1.67	6.94	29.65	As of July 05			
4287.15	4294.00	8.800	7.90	116.33	-5.21	115.81	160.29	As of July 09			
4942.17	4954.00	6.200	359.80	195.89	7.14	195.96	241.03	As of July 10			
5695.65	5713.00	5.300	354.70	284.94	18.24	285.52	330.99	As of July 11			
6261.91	6281.00	4.000	343.90	328.95	14.91	329.25	375.30	As of July 12			
7116.46	7136.00	1.800	267.40	336.82	-3.16	336.01	401.16	As of July 13			
8822.06	8842.00	1.800	198.50	313.98	-1.77	313.30	435.56	Last Sharewell Survey			
8896.03	8916.00	1.800	186.50	311.72	-2.27	311.02	437.88	Projection To Bit			



Company:	Bill Barrett Corp. (II)	Local Co-ordinate Reference:	Well #7-4D-45 BTR
Project:	Duchesne Co., UT (NAD27)	TVD Reference:	WELL @ 5815.01ft
Site:	Sec.4-T4S-R5W	MD Reference:	WELL @ 5815.01ft
Well:	#7-4D-45 BTR	North Reference:	True
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Wellbore #1	Database:	CompassVM

Project	Duchesne Co., UT (NAD27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		

Site	Sec.4-T4S-R5W				
Site Position:		Northing:	668,127.05 usft	Latitude:	40° 9' 46.74 N
From:	Lat/Long	Easting:	2,292,810.91 usft	Longitude:	110° 27' 8.19 W
Position Uncertainty:	0.00 ft	Slot Radius:	1.10 ft	Grid Convergence:	0.67 °

Well	#7-4D-45 BTR					
Well Position	+N/-S	0.00 ft	Northing:	668,127.04 usft	Latitude:	40° 9' 46.74 N
	+E/-W	0.00 ft	Easting:	2,292,810.91 usft	Longitude:	110° 27' 8.19 W
Position Uncertainty		0.00 ft	Wellhead Elevation:	ft	Ground Level:	5,793.01 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	06/20/12	11.36	65.79	52,177

Design	Wellbore #1				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	3.47	

Survey Program	Date	07/18/12			
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
151.00	8,916.00	Survey #1 (Wellbore #1)	MWD	MWD - Standard	

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
0.00	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
151.00	0.500	271.00	151.00	0.01	-0.66	-0.03	0.33	0.33	0.00	
217.00	0.400	285.90	217.00	0.08	-1.17	0.01	0.23	-0.15	22.58	
310.00	0.400	119.20	310.00	0.01	-1.20	-0.06	0.85	0.00	-179.25	
403.00	0.600	306.00	402.99	0.14	-1.31	0.06	1.07	0.22	-186.24	
496.00	1.100	24.00	495.99	1.24	-1.34	1.16	1.22	0.54	83.87	
588.00	1.400	3.50	587.96	3.17	-0.91	3.11	0.58	0.33	-22.28	
680.00	1.800	22.80	679.93	5.62	-0.28	5.59	0.72	0.43	20.98	
As of July 02										
772.00	1.100	355.90	771.90	7.84	0.21	7.83	1.04	-0.76	-29.24	
864.00	1.000	3.10	863.88	9.52	0.19	9.51	0.18	-0.11	7.83	

Company:	Bill Barrett Corp. (II)	Local Co-ordinate Reference:	Well #7-4D-45 BTR
Project:	Duchesne Co., UT (NAD27)	TVD Reference:	WELL @ 5815.01ft
Site:	Sec.4-T4S-R5W	MD Reference:	WELL @ 5815.01ft
Well:	#7-4D-45 BTR	North Reference:	True
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Wellbore #1	Database:	CompassVM

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
959.00	1.100	337.70	958.87	11.19	-0.11	11.16	0.50	0.11	-26.74
1,054.00	0.400	10.30	1,053.86	12.36	-0.39	12.31	0.83	-0.74	34.32
1,149.00	0.700	43.50	1,148.86	13.11	0.07	13.09	0.45	0.32	34.95
1,244.00	0.400	55.00	1,243.85	13.72	0.74	13.74	0.33	-0.32	12.11
As of July 03									
1,339.00	0.400	343.50	1,338.85	14.23	0.91	14.25	0.49	0.00	-75.26
1,434.00	0.600	332.10	1,433.85	14.98	0.59	14.99	0.23	0.21	-12.00
1,529.00	0.200	315.50	1,528.84	15.54	0.24	15.53	0.43	-0.42	-17.47
1,624.00	0.500	162.20	1,623.84	15.26	0.25	15.25	0.72	0.32	-161.37
1,719.00	0.700	239.30	1,718.84	14.57	-0.12	14.54	0.80	0.21	81.16
1,814.00	0.000	254.90	1,813.84	14.28	-0.62	14.21	0.74	-0.74	0.00
1,909.00	0.500	181.70	1,908.84	13.86	-0.63	13.80	0.53	0.53	0.00
2,003.00	1.000	174.90	2,002.83	12.64	-0.57	12.58	0.54	0.53	-7.23
2,098.00	1.100	148.90	2,097.81	11.03	-0.03	11.01	0.51	0.11	-27.37
2,193.00	1.400	156.80	2,192.79	9.18	0.90	9.22	0.36	0.32	8.32
2,287.00	1.600	166.00	2,286.76	6.85	1.67	6.94	0.33	0.21	9.79
As of July 05									
2,399.00	1.000	164.90	2,398.73	4.39	2.30	4.52	0.54	-0.54	-0.98
2,492.00	1.500	124.80	2,491.71	2.91	3.51	3.12	1.05	0.54	-43.12
2,587.00	0.800	107.20	2,586.69	2.01	5.17	2.32	0.82	-0.74	-18.53
2,687.00	1.100	116.80	2,686.67	1.37	6.69	1.77	0.34	0.30	9.60
2,764.00	0.900	116.20	2,763.66	0.77	7.89	1.25	0.26	-0.26	-0.78
2,878.00	0.400	170.70	2,877.66	-0.02	8.76	0.51	0.65	-0.44	47.81
2,973.00	1.700	5.50	2,972.64	1.06	8.95	1.60	2.20	1.37	-173.89
3,068.00	1.500	8.20	3,067.61	3.69	9.26	4.24	0.22	-0.21	2.84
3,162.00	1.200	307.00	3,161.58	5.50	8.65	6.01	1.49	-0.32	-65.11
3,256.00	1.800	336.60	3,255.55	7.45	7.28	7.87	1.02	0.64	31.49
3,351.00	3.600	353.80	3,350.45	11.78	6.36	12.15	2.06	1.89	18.11
3,445.00	4.200	349.70	3,444.23	18.10	5.43	18.40	0.70	0.64	-4.36
3,540.00	4.700	4.10	3,538.94	25.41	5.09	25.67	1.28	0.53	15.16
3,635.00	5.800	10.40	3,633.54	34.01	6.23	34.33	1.31	1.16	6.63
3,730.00	6.200	349.70	3,728.04	43.78	6.18	44.08	2.30	0.42	-21.79
3,823.00	8.000	346.00	3,820.32	55.00	3.72	55.13	2.00	1.94	-3.98
3,917.00	8.100	345.10	3,913.39	67.75	0.43	67.65	0.17	0.11	-0.96
4,011.00	6.800	347.50	4,006.60	79.58	-2.48	79.29	1.42	-1.38	2.55
4,106.00	7.700	352.20	4,100.84	91.38	-4.56	90.94	1.13	0.95	4.95
4,200.00	7.100	356.10	4,194.05	103.41	-5.81	102.87	0.83	-0.64	4.15
4,294.00	8.800	7.90	4,287.15	116.33	-5.21	115.81	2.50	1.81	12.55
As of July 09									
4,388.00	7.100	7.80	4,380.25	129.21	-3.44	128.77	1.81	-1.81	-0.11
4,482.00	7.600	15.80	4,473.48	140.95	-0.96	140.63	1.21	0.53	8.51
4,576.00	7.400	6.10	4,566.68	152.95	1.38	152.75	1.36	-0.21	-10.32
4,670.00	6.400	10.10	4,660.00	164.13	2.94	164.01	1.18	-1.06	4.26

Company:	Bill Barrett Corp. (II)	Local Co-ordinate Reference:	Well #7-4D-45 BTR
Project:	Duchesne Co., UT (NAD27)	TVD Reference:	WELL @ 5815.01ft
Site:	Sec.4-T4S-R5W	MD Reference:	WELL @ 5815.01ft
Well:	#7-4D-45 BTR	North Reference:	True
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Wellbore #1	Database:	CompassVM

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
4,765.00	6.300	13.00	4,754.41	174.42	5.04	174.40	0.35	-0.11	3.05	
4,859.00	6.900	4.80	4,847.79	185.07	6.68	185.14	1.19	0.64	-8.72	
4,954.00	6.200	359.80	4,942.17	195.89	7.14	195.96	0.95	-0.74	-5.26	
As of July 10										
5,049.00	6.900	4.30	5,036.55	206.71	7.55	206.79	0.91	0.74	4.74	
5,144.00	7.400	9.50	5,130.81	218.43	8.98	218.58	0.86	0.53	5.47	
5,239.00	8.500	6.90	5,224.90	231.44	10.84	231.67	1.22	1.16	-2.74	
5,334.00	8.200	8.90	5,318.89	245.10	12.73	245.42	0.44	-0.32	2.11	
5,429.00	7.500	11.90	5,413.00	257.86	15.05	258.30	0.85	-0.74	3.16	
5,524.00	5.700	7.70	5,507.37	268.60	16.97	269.14	1.96	-1.89	-4.42	
5,618.00	4.500	8.20	5,601.00	276.88	18.12	277.47	1.28	-1.28	0.53	
5,713.00	5.300	354.70	5,695.65	284.94	18.24	285.52	1.47	0.84	-14.21	
As of July 11										
5,807.00	3.900	355.00	5,789.35	292.45	17.56	292.97	1.49	-1.49	0.32	
5,901.00	4.500	354.70	5,883.09	299.30	16.94	299.78	0.64	0.64	-0.32	
5,996.00	5.300	4.30	5,977.75	307.39	16.93	307.85	1.20	0.84	10.11	
6,091.00	3.900	351.70	6,072.44	314.96	16.79	315.40	1.81	-1.47	-13.26	
6,186.00	4.600	356.30	6,167.18	321.96	16.08	322.34	0.82	0.74	4.84	
6,281.00	4.000	343.90	6,261.91	328.95	14.91	329.25	1.16	-0.63	-13.05	
As of July 12										
6,376.00	2.900	335.60	6,356.74	334.32	13.00	334.49	1.27	-1.16	-8.74	
6,471.00	2.000	321.50	6,451.65	337.80	10.98	337.85	1.13	-0.95	-14.84	
6,566.00	1.000	264.00	6,546.62	339.01	9.12	338.95	1.78	-1.05	-60.53	
6,661.00	1.400	279.40	6,641.60	339.12	7.15	338.93	0.54	0.42	16.21	
6,756.00	2.000	263.10	6,736.56	339.11	4.36	338.75	0.81	0.63	-17.16	
6,851.00	1.100	249.90	6,831.53	338.60	1.86	338.09	1.01	-0.95	-13.89	
6,946.00	0.700	181.40	6,926.52	337.70	0.99	337.14	1.12	-0.42	-72.11	
7,041.00	1.600	265.00	7,021.50	337.01	-0.35	336.37	1.76	0.95	88.00	
7,136.00	1.800	267.40	7,116.46	336.82	-3.16	336.01	0.22	0.21	2.53	
As of July 13										
7,231.00	0.600	286.50	7,211.44	336.90	-5.13	335.97	1.31	-1.26	20.11	
7,326.00	0.900	132.00	7,306.43	336.54	-5.05	335.62	1.54	0.32	-162.63	
7,421.00	1.800	168.20	7,401.41	334.58	-4.19	333.71	1.26	0.95	38.11	
7,516.00	2.200	177.70	7,496.35	331.30	-3.81	330.46	0.55	0.42	10.00	
7,611.00	1.100	208.10	7,591.31	328.67	-4.17	327.81	1.44	-1.16	32.00	
7,705.00	2.100	217.60	7,685.27	326.51	-5.64	325.57	1.10	1.06	10.11	
7,800.00	1.500	195.20	7,780.23	323.93	-7.03	322.91	0.96	-0.63	-23.58	
7,895.00	0.900	224.70	7,875.21	322.20	-7.88	321.13	0.89	-0.63	31.05	
7,990.00	0.400	207.20	7,970.20	321.37	-8.56	320.27	0.56	-0.53	-18.42	
8,085.00	0.600	39.60	8,065.20	321.46	-8.39	320.37	1.05	0.21	-176.42	
8,180.00	0.500	82.40	8,160.19	321.90	-7.66	320.85	0.43	-0.11	45.05	
8,274.00	1.500	121.20	8,254.18	321.32	-6.21	320.35	1.23	1.06	41.28	
8,369.00	1.400	102.90	8,349.15	320.41	-4.01	319.58	0.50	-0.11	-19.26	
8,464.00	1.600	130.20	8,444.12	319.30	-1.87	318.60	0.77	0.21	28.74	

Company:	Bill Barrett Corp. (II)	Local Co-ordinate Reference:	Well #7-4D-45 BTR
Project:	Duchesne Co., UT (NAD27)	TVD Reference:	WELL @ 5815.01ft
Site:	Sec.4-T4S-R5W	MD Reference:	WELL @ 5815.01ft
Well:	#7-4D-45 BTR	North Reference:	True
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Wellbore #1	Database:	CompassVM

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
8,559.00	1.000	183.20	8,539.10	317.62	-0.90	316.98	1.35	-0.63	55.79	
8,654.00	0.100	172.80	8,634.09	316.71	-0.94	316.07	0.95	-0.95	-10.95	
8,749.00	0.800	196.70	8,729.09	315.99	-1.12	315.34	0.75	0.74	25.16	
8,842.00	1.800	198.50	8,822.06	313.98	-1.77	313.30	1.08	1.08	1.94	
Last Sharewell Survey										
8,916.00	1.800	186.50	8,896.03	311.72	-2.27	311.02	0.51	0.00	-16.22	
Projection To Bit										

Survey Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment	
		+N/-S (ft)	+E/-W (ft)		
680.00	679.93	5.62	-0.28	As of July 02	
1,244.00	1,243.85	13.72	0.74	As of July 03	
2,287.00	2,286.76	6.85	1.67	As of July 05	
4,294.00	4,287.15	116.33	-5.21	As of July 09	
4,954.00	4,942.17	195.89	7.14	As of July 10	
5,713.00	5,695.65	284.94	18.24	As of July 11	
6,281.00	6,261.91	328.95	14.91	As of July 12	
7,136.00	7,116.46	336.82	-3.16	As of July 13	
8,842.00	8,822.06	313.98	-1.77	Last Sharewell Survey	
8,916.00	8,896.03	311.72	-2.27	Projection To Bit	

Checked By: _____ Approved By: _____ Date: _____

Division of Oil, Gas and Mining
 Operator Change/Name Change Worksheet-for State use only

Effective Date: 11/1/2016

FORMER OPERATOR:	NEW OPERATOR:
Bill Barrett Corporation 1099 18th Street, Suite 2300 Denver, CO 80202	Rig II, LLC 1582 West 2600 South Woods Cross, UT 84087
CA Number(s):	Unit(s):

WELL INFORMATION:

Well Name	Sec	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
See Attached List									

OPERATOR CHANGES DOCUMENTATION:

- Sundry or legal documentation was received from the **FORMER** operator on: 10/21/2016
- Sundry or legal documentation was received from the **NEW** operator on: 10/21/2016
- New operator Division of Corporations Business Number: 8256968-0160

REVIEW:

- Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: N/A
- Receipt of Acceptance of Drilling Procedures for APD on: 10/21/2016
- Reports current for Production/Disposition & Sundries: 11/2/2016
- OPS/SI/TA well(s) reviewed for full cost bonding: 11/3/2016
- UIC5 on all disposal/injection/storage well(s) approved on: 11/3/2016
- Surface Facility(s) included in operator change: None
- Inspections of PA state/fee well sites complete on (only upon operators request): 11/3/2016

NEW OPERATOR BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000712
- Indian well(s) covered by Bond Number: LPM 922467
- State/fee well(s) covered by Bond Number(s): 9219529

DATA ENTRY:

- Well(s) update in the **OGIS** on: 11/7/2016
- Entity Number(s) updated in **OGIS** on: 11/7/2016
- Unit(s) operator number update in **OGIS** on: N/A
- Surface Facilities update in **OGIS** on: N/A
- State/Fee well(s) attached to bond(s) in **RBDMS** on: 11/7/2016
- Surface Facilities update in **RBDMS** on: N/A

COMMENTS:

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral	Surface	Type	Status
SWD 9-36 BTR	9	030S	060W	4301350646	18077	Indian	Fee	WD	A
16-6D-46 BTR SWD	6	040S	060W	4301350781	18327	Indian	Fee	WD	A
6-32-36 BTR SWD	32	030S	060W	4301350921	18329	Indian	Fee	WD	A
LC TRIBAL 8-26D-47	26	040S	070W	4301334024		Indian	Indian	OW	APD
16-21D-37 BTR	21	030S	070W	4301350758		Indian	Fee	OW	APD
14-11D-37 BTR	11	030S	070W	4301350862		Indian	Fee	OW	APD
7-17D-46 BTR	17	040S	060W	4301350883		Indian	Indian	OW	APD
14-12D-37 BTR	12	030S	070W	4301350894		Indian	Fee	OW	APD
1-18D-36 BTR	18	030S	060W	4301350922		Indian	Fee	OW	APD
13-2D-45 BTR	2	040S	050W	4301350931		Indian	Indian	OW	APD
5H-16-46 BTR	16	040S	060W	4301350992		Indian	Indian	OW	APD
9H-17-45 BTR	17	040S	050W	4301351098		Indian	Indian	OW	APD
13H-8-46 BTR UB	8	040S	060W	4301351124		Indian	Indian	OW	APD
8H-9-46 BTR	9	040S	060W	4301351140		Indian	Indian	OW	APD
LC TRIBAL 7-31D-37	31	030S	070W	4301351147		Indian	Fee	OW	APD
14-16D-45 BTR	16	040S	050W	4301351178		Indian	Indian	OW	APD
16-19D-37 BTR	19	030S	070W	4301351179		Indian	Fee	OW	APD
6-2D-45 BTR	2	040S	050W	4301351234		Indian	Indian	OW	APD
2-2D-45 BTR	2	040S	050W	4301351235		Indian	Indian	OW	APD
10-26-35 BTR	26	030S	050W	4301351248		Indian	Fee	OW	APD
LC TRIBAL 1H-33-46	33	040S	060W	4301351257		Indian	Fee	OW	APD
LC TRIBAL 9-25D-46	25	040S	060W	4301351276		Indian	Indian	OW	APD
LC TRIBAL 8H-30-45	30	040S	050W	4301351277		Indian	Indian	OW	APD
LC TRIBAL 16H-30-45	30	040S	050W	4301351279		Indian	Indian	OW	APD
LC TRIBAL 13-30D-45	30	040S	050W	4301351282		Indian	Indian	OW	APD
LC TRIBAL 16H-36-46	36	040S	060W	4301351291		Indian	Indian	OW	APD
LC TRIBAL 13H-30-46	30	040S	060W	4301351321		Indian	Indian	OW	APD
LC TRIBAL 13H-31-46	31	040S	060W	4301351326		Indian	Indian	OW	APD
LC TRIBAL 16-31D-46	31	040S	060W	4301351328		Indian	Indian	OW	APD
LC TRIBAL 5H-26-47	26	040S	070W	4301351337		Indian	Indian	OW	APD
LC TRIBAL 5H-19-45	20	040S	050W	4301351349		Indian	Indian	OW	APD
LC TRIBAL 16-36D-47	36	040S	070W	4301351363		Indian	Indian	OW	APD
15-4D-47 BTR	4	040S	070W	4301351377		Indian	Fee	OW	APD
16-23D-46 LC TRIBAL	23	040S	060W	4301351396		Indian	Fee	OW	APD
15-2D-36 BTR	2	030S	060W	4301351419		Indian	Fee	OW	APD
16-23D-37 BTR	23	030S	070W	4301351420		Indian	Fee	OW	APD
11-9D-47 BTR	9	040S	070W	4301351422		Indian	Fee	OW	APD
15-13D-47 BTR	13	040S	070W	4301351424		Indian	Indian	OW	APD
LC TRIBAL 15-19D-46	19	040S	060W	4301351426		Indian	Indian	OW	APD
16-13D-45 BTR	13	040S	050W	4301351428		Indian	Indian	OW	APD

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

14-12D-45 BTR	12	040S	050W	4301351444		Indian	Indian	OW	APD
16-14D-45 BTR	14	040S	050W	4301351445		Indian	Indian	OW	APD
5-13D-45 BTR	13	040S	050W	4301351446		Indian	Indian	OW	APD
LC TRIBAL 16-26D-46	26	040S	060W	4301351450		Indian	State	OW	APD
LC TRIBAL 16-34D-46	34	040S	060W	4301351451		Indian	State	OW	APD
16-12D-45 BTR	12	040S	050W	4301351452		Indian	Indian	OW	APD
8-12D-45 BTR	12	040S	050W	4301351453		Indian	Indian	OW	APD
LC TRIBAL 1-35D-46	35	040S	060W	4301351454		Indian	Fee	OW	APD
16-25D-37 BTR	25	030S	070W	4301351455		Indian	Fee	OW	APD
LC TRIBAL 13H-29-46	28	040S	060W	4301351462		Indian	Fee	OW	APD
LC TRIBAL 14-30D-37	30	030S	070W	4301351494		Indian	Fee	OW	APD
7-13D-45 BTR	13	040S	050W	4301351497		Indian	Indian	OW	APD
LC TRIBAL 4H-35-46	35	040S	060W	4301351515		Indian	Fee	OW	APD
LC TRIBAL 13H-19-46	19	040S	060W	4301351543		Indian	Indian	OW	APD
16-26D-37 BTR	26	030S	070W	4301351598		Indian	Fee	OW	APD
LC TRIBAL 16-31D-37	31	030S	070W	4301351610		Indian	Fee	OW	APD
5-4-35 BTR	4	030S	050W	4301351613		Indian	Fee	OW	APD
LC TRIBAL 16-31D-47	31	040S	070W	4301351616		Indian	Indian	OW	APD
LC TRIBAL 13H-31-47	31	040S	070W	4301351617		Indian	Indian	OW	APD
LC TRIBAL 13-32D-47	32	040S	070W	4301351619		Indian	Indian	OW	APD
LC TRIBAL 16H-32-47	32	040S	070W	4301351620		Indian	Indian	OW	APD
LC TRIBAL 1-32D-47	32	040S	070W	4301351624		Indian	Indian	OW	APD
LC TRIBAL 4H-32-47	32	040S	070W	4301351625		Indian	Indian	OW	APD
LC TRIBAL 13-28D-47	28	040S	070W	4301351627		Indian	Indian	OW	APD
LC TRIBAL 13H-29-47	28	040S	070W	4301351628		Indian	Indian	OW	APD
LC TRIBAL 16H-28-47	28	040S	070W	4301351629		Indian	Indian	OW	APD
LC TRIBAL 1-28D-47	28	040S	070W	4301351639		Indian	Indian	OW	APD
LC TRIBAL 1H-27-47	28	040S	070W	4301351640		Indian	Indian	OW	APD
LC TRIBAL 4H-28-47	28	040S	070W	4301351641		Indian	Indian	OW	APD
LC TRIBAL 7-25D-58	25	050S	080W	4301351643		Indian	Indian	OW	APD
LC TRIBAL 6-25D-58	25	050S	080W	4301351644		Indian	Indian	OW	APD
LC TRIBAL 13H-24-58	24	050S	080W	4301351645		Indian	Indian	OW	APD
LC TRIBAL 16-24D-58	24	050S	080W	4301351646		Indian	Indian	OW	APD
LC Tribal 8-23D-46	23	040S	060W	4301351654		Indian	Fee	OW	APD
LC Tribal 16-35D-45	35	040S	050W	4301351656		Indian	Fee	OW	APD
LC Tribal 13H-35-45	35	040S	050W	4301351657		Indian	Fee	OW	APD
LC Tribal 16-36D-45	36	040S	050W	4301351658		Indian	Fee	OW	APD
LC Tribal 13H-36-45	36	040S	050W	4301351659		Indian	Fee	OW	APD
LC Tribal 5-36D-45	36	040S	050W	4301351661		Indian	Fee	OW	APD
LC Tribal 8-26D-46	26	040S	060W	4301351663		Indian	Fee	OW	APD
3-29D-36 BTR	29	030S	060W	4301351665		Indian	Fee	OW	APD

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

LC Tribal 5-35D-45	35	040S	050W	4301351666	Indian	Fee	OW	APD
LC Tribal 5-24D-46	24	040S	060W	4301351668	Indian	Indian	OW	APD
LC TRIBAL 6-12D-58	12	050S	080W	4301351696	Indian	Indian	OW	APD
LC TRIBAL 8-12D-58	12	050S	080W	4301351697	Indian	Indian	OW	APD
LC TRIBAL 16H-22-47	21	040S	070W	4301351700	Indian	Indian	OW	APD
5-25D-37 BTR	25	030S	070W	4301351803	Indian	Fee	OW	APD
8-3D-36 BTR	3	030S	060W	4301351804	Indian	Fee	OW	APD
14-26D-37 BTR	26	030S	070W	4301351805	Indian	Fee	OW	APD
9-4-35 BTR	4	030S	050W	4301351806	Indian	Fee	OW	APD
11-4D-35 BTR	4	030S	050W	4301351807	Indian	Fee	OW	APD
16-27D-37 BTR	27	030S	070W	4301351808	Indian	Fee	OW	APD
14-27D-37 BTR	27	030S	070W	4301351809	Indian	Fee	OW	APD
14-16D-46 BTR	16	040S	060W	4301351812	Indian	Indian	OW	APD
LC Tribal 16-35D-48	35	040S	080W	4301351847	Indian	Indian	OW	APD
LC Tribal 13H-35-48	35	040S	080W	4301351848	Indian	Indian	OW	APD
LC Tribal 13-2D-58	11	050S	080W	4301351850	Indian	Indian	OW	APD
5-13D-36 BTR	13	030S	060W	4301351862	Indian	Fee	OW	APD
5-8D-36 BTR	8	030S	060W	4301351871	Indian	Fee	OW	APD
16-1D-36 BTR	1	030S	060W	4301351872	Indian	Fee	OW	APD
8-18D-46 BTR	18	040S	060W	4301351897	Indian	Fee	OW	APD
LC Tribal 5-36D-46	36	040S	060W	4301351905	Indian	Indian	OW	APD
LC Tribal 5-26D-45	26	040S	050W	4301351907	Indian	Indian	OW	APD
14-13D-45 BTR	13	040S	050W	4301351974	Indian	Indian	OW	APD
14-34D-46 DLB	34	040S	060W	4301351975	Indian	Fee	OW	APD
LC Tribal 5-21D-45	21	040S	050W	4301352001	Indian	Indian	OW	APD
LC Tribal 8-22D-45	22	040S	050W	4301352002	Indian	Indian	OW	APD
LC Tribal 8-25D-45	25	040S	050W	4301352007	Indian	Indian	OW	APD
LC Tribal 16-25D-45	25	040S	050W	4301352008	Indian	Indian	OW	APD
LC Tribal 16-22D-45	22	040S	050W	4301352009	Indian	Indian	OW	APD
LC Tribal 16-26D-45	26	040S	050W	4301352010	Indian	Indian	OW	APD
LC Tribal 14-31D-37	31	030S	070W	4301352016	Indian	Fee	OW	APD
5-12D-45 BTR	12	040S	050W	4301352030	Indian	Indian	OW	APD
LC Tribal 9-20D-45	20	040S	050W	4301352031	Indian	Indian	OW	APD
LC Tribal 13-35D-47	35	040S	070W	4301352055	Indian	Indian	OW	APD
LC Tribal 1-23D-47	23	040S	070W	4301352057	Indian	Indian	OW	APD
9-17D-46 BTR	17	040S	060W	4301352059	Indian	Indian	OW	APD
11-18D-46 BTR	18	040S	060W	4301352060	Indian	Indian	OW	APD
9-10D-47 BTR	10	040S	070W	4301352092	Indian	Fee	OW	APD
LC Tribal 1-17D-47	17	040S	070W	4301352096	Indian	Fee	OW	APD
7-35D-37 BTR	35	030S	070W	4301352115	Indian	Fee	OW	APD
14-25D-37 BTR	25	030S	070W	4301352116	Indian	Fee	OW	APD

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

LC Tribal 5-25-46	25	040S	060W	4301352126	Indian	Indian	OW	APD
8-33D-35 BTR	33	030S	050W	4301352161	Indian	Fee	OW	APD
5-4D-36 BTR	4	030S	060W	4301352175	Indian	Fee	OW	APD
7-4D-36 BTR	4	030S	060W	4301352176	Indian	Fee	OW	APD
LC Tribal 4-36D-47	36	040S	070W	4301352186	Indian	Indian	OW	APD
LC Tribal 4-22D-46	22	040S	060W	4301352944	Indian	Indian	OW	APD
LC Tribal 16-22D-46	22	040S	060W	4301352945	Indian	Indian	OW	APD
LC Tribal 11-19D-46	19	040S	060W	4301352946	Indian	Indian	OW	APD
LC Tribal 7-20D-45	20	040S	050W	4301352947	Indian	Indian	OW	APD
15-11D-35 BTR	11	030S	050W	4301353056	Indian	Fee	OW	APD
13-11D-35 BTR	11	030S	050W	4301353057	Indian	Fee	OW	APD
BTR 16-36D-37	36	030S	070W	4301353059	Indian	Fee	OW	APD
4-29D-35 BTR	30	030S	050W	4301353060	Indian	Fee	OW	APD
1-30D-35 BTR	30	030S	050W	4301353061	Fee	Fee	OW	APD
LC TRIBAL 3-23D-46	23	040S	060W	4301353066	Indian	State	OW	APD
LC Tribal 14-23D-46	23	040S	060W	4301353067	Indian	State	OW	APD
LC Tribal 13-25D-46	25	040S	060W	4301353068	Indian	Indian	OW	APD
LC Tribal 14-26D-46	26	040S	060W	4301353069	Indian	State	OW	APD
LC Tribal 5-26D-46	26	040S	060W	4301353070	Indian	State	OW	APD
LC Tribal 11-35D-45	35	040S	050W	4301353071	Indian	State	OW	APD
LC Tribal 7-35D-45	35	040S	050W	4301353072	Indian	State	OW	APD
LC Tribal 3-35D-45	35	040S	050W	4301353075	Indian	State	OW	APD
LC Tribal 14-36D-45	36	040S	050W	4301353076	Indian	State	OW	APD
LC Tribal 13-36D-45	36	040S	050W	4301353077	Indian	State	OW	APD
LC Tribal 10-36D-45	36	040S	050W	4301353078	Indian	State	OW	APD
LC Tribal 8-36D-45	36	040S	050W	4301353079	Indian	State	OW	APD
LC Tribal 6-36D-45	36	040S	050W	4301353080	Indian	State	OW	APD
LC Tribal 1-34D-46	34	040S	060W	4301353081	Indian	State	OW	APD
LC Tribal 9-27D-46	27	040S	060W	4301353082	Indian	State	OW	APD
LC Tribal 13-35D-45	35	040S	050W	4301353083	Indian	State	OW	APD
LC Tribal 8-35D-45	35	040S	050W	4301353084	Indian	State	OW	APD
LC Tribal 15-35D-45	35	040S	050W	4301353085	Indian	State	OW	APD
LC Tribal 12-25D-45	25	040S	050W	4301353122	Indian	Indian	OW	APD
LC Tribal 14-25D-45	25	040S	050W	4301353123	Indian	Indian	OW	APD
LC Tribal 10-25D-45	25	040S	050W	4301353124	Indian	Indian	OW	APD
LC Tribal 11-26-45	26	040S	050W	4301353125	Indian	Indian	OW	APD
LC Tribal 13-26D-45	26	040S	050W	4301353126	Indian	Indian	OW	APD
LC Tribal 7-31D-46	31	040S	060W	4301353127	Indian	Indian	OW	APD
LC Tribal 7-19D-45	19	040S	050W	4301353128	Indian	Indian	OW	APD
LC Tribal 5-19D-45	19	040S	050W	4301353130	Indian	Indian	OW	APD
LC Tribal 7-25D-46	25	040S	060W	4301353132	Indian	Indian	OW	APD

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

LC Tribal 7-24D-46	24	040S	060W	4301353134		Indian	Indian	OW	APD
LC Tribal 14-31D-46	31	040S	060W	4301353135		Indian	Indian	OW	APD
LC Tribal 14-30D-46	30	040S	060W	4301353136		Indian	Indian	OW	APD
13-4-35 BTR SWD	4	030S	050W	4301353293		Fee	Fee	OW	APD
LC FEE 14-26D-47	26	040S	070W	4301353294		Fee	Indian	OW	APD
LC Fee 5-25D-47	25	040S	070W	4301353295		Fee	Indian	OW	APD
7-35-46 LC SWD	35	040S	060W	4301353296		Fee	Fee	OW	APD
LC Fee 1H-33-47	32	040S	070W	4301353309		Fee	Indian	OW	APD
LC FEE 14-2D-58	2	050S	080W	4301353312		Fee	Indian	OW	APD
LC FEE 13H-21-47	21	040S	070W	4301353313		Fee	Indian	OW	APD
LC Fee 16-21D-47	21	040S	070W	4301353326		Fee	Indian	OW	APD
16-7D-46 BTR	7	040S	060W	4301353328		Fee	Indian	OW	APD
LC Fee 15-26D-47	26	040S	070W	4301353331		Fee	Indian	OW	APD
LC Fee 4-24D-47	23	040S	070W	4301353332		Fee	Indian	OW	APD
LC Fee 5-34D-47	34	040S	070W	4301353333		Fee	Indian	OW	APD
LC Fee 5-35D-47	35	040S	070W	4301353334		Fee	Indian	OW	APD
13-34D-47 LC Fee	34	040S	070W	4301353337		Fee	Indian	OW	APD
14-35D-35 BTR	35	030S	050W	4301352120		Fee	Fee	OW	DRL
6-17D-46 BTR	17	040S	060W	4301351078		Indian	Indian	OW	OPS
5-34D-35 BTR	34	030S	050W	4301351187		Indian	Fee	OW	OPS
5-10D-45 BTR	10	040S	050W	4301351221		Indian	Indian	OW	OPS
5-3D-45 BTR	3	040S	050W	4301351810		Indian	Indian	OW	OPS
9-34D-35 BTR	34	030S	050W	4301352117		Fee	Fee	OW	OPS
5-35D-35 BTR	35	030S	050W	4301352118		Fee	Fee	OW	OPS
1-2D-46 BTR	2	040S	060W	4301353086		Indian	Fee	OW	OPS
7-21-46 DLB	21	040S	060W	4301333567	16526	Indian	Indian	OW	P
LC TRIBAL 1H-27-46	27	040S	060W	4301333568	18175	Indian	Fee	GW	P
7-29-46 DLB	29	040S	060W	4301333584	17603	Indian	Fee	GW	P
LC TRIBAL 12H-28-46	28	040S	060W	4301333631	18132	Indian	Indian	GW	P
LC TRIBAL 13H-21-46	21	040S	060W	4301333632	18107	Indian	Indian	GW	P
12-36-36 BTR	36	030S	060W	4301333638	16336	Indian	Fee	GW	P
5-5-46 BTR	5	040S	060W	4301333639	16542	Indian	Fee	OW	P
5-23-36 BTR	23	030S	060W	4301333642	16675	Indian	Fee	GW	P
14-29-36 BTR	29	030S	060W	4301333643	16725	Indian	Fee	OW	P
14-30-36 BTR	30	030S	060W	4301333644	16701	Indian	Fee	GW	P
7-20-46 DLB	20	040S	060W	4301333657	16584	Indian	Indian	OW	P
LC TRIBAL 5-21D-46	21	040S	060W	4301333658	18887	Indian	Indian	OW	P
5-20-46 DLB	20	040S	060W	4301333659	18750	Indian	Indian	GW	P
LC TRIBAL 13H-20-46	20	040S	060W	4301333678	17979	Indian	Indian	GW	P
14-7-46 BTR	7	040S	060W	4301333806	16890	Indian	Indian	GW	P
7-8-45 BTR	8	040S	050W	4301333820	16974	Indian	Indian	OW	P

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

1-5-45 BTR	5	040S	050W	4301333868	16931	Indian	Indian	OW	P
5-16-36 BTR	16	030S	060W	4301333970	17195	Indian	Fee	OW	P
5-29-36 BTR	29	030S	060W	4301333972	17557	Indian	Fee	OW	P
4-30-36 BTR	30	030S	060W	4301333973	17249	Indian	Fee	OW	P
7-19-46 DLB	19	040S	060W	4301334004	19018	Indian	Indian	OW	P
5-25-36 BTR	25	030S	060W	4301334021	17126	Fee	Fee	OW	P
5-4-45 BTR	4	040S	050W	4301334089	17507	Indian	Indian	OW	P
13-2-46 BTR	2	040S	060W	4301334090	18618	Indian	Indian	OW	P
2-3-45 BTR	3	040S	050W	4301334099	17932	Indian	Indian	OW	P
7-6-45 BTR	6	040S	050W	4301334100	17653	Indian	Indian	OW	P
1-9-45 BTR	9	040S	050W	4301334101	17910	Indian	Indian	OW	P
8-10-45 BTR	10	040S	050W	4301334102	17530	Indian	Indian	OW	P
7-17-45 BTR	17	040S	050W	4301334104	17933	Indian	Indian	OW	P
16-7-45 BTR	7	040S	050W	4301334111	17665	Indian	Indian	OW	P
15-18-45 BTR	18	040S	050W	4301334112	17832	Indian	Indian	OW	P
6-12-46 BTR	12	040S	060W	4301334114	17964	Indian	Indian	OW	P
5-13-46 BTR	13	040S	060W	4301334115	17833	Indian	Indian	OW	P
16-26-36 BTR	26	030S	060W	4301334132	18028	Indian	Fee	OW	P
1-23-36 BTR	23	030S	060W	4301334136	17722	Indian	Fee	OW	P
15-10-36 BTR	10	030S	060W	4301334277	17419	Indian	Fee	OW	P
14-5-46 BTR	5	040S	060W	4301350307	17624	Fee	Fee	OW	P
14X-22-46 DLB	22	040S	060W	4301350351	17604	Indian	Indian	OW	P
16-13-36 BTR	13	030S	060W	4301350372	17853	Indian	Fee	OW	P
5-33-46 DLB	33	040S	060W	4301350397	17765	Indian	Fee	OW	P
5-34-46 DLB	34	040S	060W	4301350415	17801	Indian	State	GW	P
LC FEE 12H-32-46	32	040S	060W	4301350431	18003	Fee	Fee	OW	P
1-13D-47 BTR	13	040S	070W	4301350445	18205	Indian	Fee	OW	P
16-8D-45 BTR	8	040S	050W	4301350466	18799	Indian	Indian	OW	P
7-13D-46 BTR	13	040S	060W	4301350470	18076	Indian	Indian	OW	P
14-8D-45 BTR	8	040S	050W	4301350567	18207	Indian	Indian	OW	P
14-5D-45 BTR	5	040S	050W	4301350568	18108	Indian	Indian	OW	P
16-31D-36 BTR	31	030S	060W	4301350573	18004	Indian	Fee	OW	P
5-7D-46 BTR	7	040S	060W	4301350574	18176	Indian	Indian	OW	P
LC TRIBAL 13H-33-46	34	040S	060W	4301350575	18223	Indian	State	OW	P
5-8-45 BTR	8	040S	050W	4301350607	18279	Indian	Indian	OW	P
16-6D-45 BTR	6	040S	050W	4301350610	18177	Indian	Indian	OW	P
5-18D-45 BTR	18	040S	050W	4301350611	18300	Indian	Indian	OW	P
7-26-37 BTR	26	030S	070W	4301350641	18131	Indian	Fee	OW	P
3-11D-36 BTR	11	030S	060W	4301350642	18299	Indian	Fee	OW	P
16-1D-46 BTR	1	040S	060W	4301350675	18525	Indian	Indian	OW	P
14-3-45 BTR	3	040S	050W	4301350676	18363	Indian	Indian	OW	P

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

4-17D-45 BTR	17	040S	050W	4301350687	18517	Indian	Indian	OW	P
5-6D-45 BTR	6	040S	050W	4301350688	18726	Indian	Indian	OW	P
7-7D-45 BTR	7	040S	050W	4301350689	18380	Indian	Indian	OW	P
14-10D-45 BTR	10	040S	050W	4301350754	18447	Indian	Indian	OW	P
14-9D-45 BTR	9	040S	050W	4301350755	18379	Indian	Indian	OW	P
13-16D-36 BTR	16	030S	060W	4301350757	18206	Indian	State	OW	P
5-9D-36 BTR	9	030S	060W	4301350843	18381	Indian	Fee	OW	P
16-5D-46 BTR	5	040S	060W	4301350844	18280	Fee	Fee	OW	P
5-27D-37 BTR	27	030S	070W	4301350847	18526	Indian	Fee	OW	P
7-4D-45 BTR	4	040S	050W	4301350884	18562	Indian	Indian	OW	P
2-16D-45 BTR	16	040S	050W	4301350899	18619	Indian	Indian	OW	P
16-10D-45 BTR	10	040S	050W	4301350902	18725	Indian	Indian	OW	P
5-2D-36 BTR	2	030S	060W	4301350913	18886	Indian	Fee	OW	P
13H-27-36 BTR	27	030S	060W	4301350918	18445	Indian	State	OW	P
8-16D-46 BTR	16	040S	060W	4301350953	19027	Indian	Indian	OW	P
16-16D-46 BTR	16	040S	060W	4301350956	19028	Indian	Indian	OW	P
16-9D-45 BTR	9	040S	050W	4301350962	18662	Indian	Indian	OW	P
14-31D-36 BTR	31	030S	060W	4301350973	18524	Indian	Fee	OW	P
5-10D-36 BTR	10	030S	060W	4301350978	18989	Indian	Fee	OW	P
1-32D-36 BTR	32	030S	060W	4301350979	18648	Indian	Fee	OW	P
16-12D-36 BTR	12	030S	060W	4301350980	18748	Indian	Fee	OW	P
2-18D-45 BTR	18	040S	050W	4301350991	18776	Indian	Indian	OW	P
3-1-46 BTR	1	040S	060W	4301351017	18777	Indian	Fee	OW	P
10-5-45 BTR	5	040S	050W	4301351062	18724	Indian	Indian	OW	P
12-4D-45 BTR	4	040S	050W	4301351063	18813	Indian	Indian	OW	P
1-10D-45 BTR	10	040S	050W	4301351064	18966	Indian	Indian	OW	P
16-2D-46 BTR	2	040S	060W	4301351079	18830	Indian	Indian	OW	P
9H-4-45 BTR	4	040S	050W	4301351092	18814	Indian	Indian	OW	P
12-17-45 BTR	17	040S	050W	4301351097	18984	Indian	Indian	OW	P
5-9D-46 BTR	9	040S	060W	4301351109	19313	Indian	Fee	OW	P
14-9D-36 BTR	9	030S	060W	4301351144	19004	Indian	Fee	OW	P
5-31D-36 BTR	31	030S	060W	4301351146	18691	Indian	Fee	OW	P
4-9D-45 BTR	9	040S	050W	4301351157	18883	Indian	Indian	OW	P
8-12D-46 BTR	12	040S	060W	4301351159	18911	Indian	Indian	OW	P
LC TRIBAL 16-23D-47	23	040S	070W	4301351180	18617	Indian	Indian	OW	P
14-7D-45 BTR	7	040S	050W	4301351222	18949	Indian	Indian	OW	P
5-16D-45 BTR	16	040S	050W	4301351223	18987	Indian	Indian	OW	P
4-5D-45 BTR	5	040S	050W	4301351242	18882	Indian	Indian	OW	P
LC TRIBAL 16H-19-45	19	040S	050W	4301351278	18627	Indian	Indian	OW	P
LC TRIBAL 13-19D-45	19	040S	050W	4301351280	18628	Indian	Indian	OW	P
LC TRIBAL 5-30D-45	30	040S	050W	4301351281	19448	Indian	Indian	OW	P

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

LC TRIBAL 15-24D-46	24	040S	060W	4301351283	18626	Indian	Indian	OW	P
LC TRIBAL 13H-24-46	19	040S	050W	4301351289	18629	Indian	Indian	OW	P
7-16-47 BTR	16	040S	070W	4301351296	18950	Indian	Fee	OW	P
14-18D-45 BTR	18	040S	050W	4301351313	19005	Indian	Indian	OW	P
LC TRIBAL 16-30D-46	30	040S	060W	4301351320	19006	Indian	Indian	OW	P
LC TRIBAL 5-20D-45	20	040S	050W	4301351331	19449	Indian	Indian	OW	P
11-8D-46 BTR	8	040S	060W	4301351336	19314	Indian	Indian	OW	P
5-7D-45 BTR	7	040S	050W	4301351350	18951	Indian	Indian	OW	P
7-5-35 BTR	5	030S	050W	4301351599	19078	Indian	Fee	OW	P
13-5D-35 BTR	5	030S	050W	4301351600	18996	Indian	Fee	OW	P
11-5D-35 BTR	5	030S	050W	4301351601	19061	Fee	Fee	OW	P
15-5D-35 BTR	5	030S	050W	4301351602	19062	Fee	Fee	OW	P
9-5D-35 BTR	5	030S	050W	4301351609	19029	Indian	Fee	OW	P
3-5D-35 BTR	5	030S	050W	4301351638	19079	Indian	Fee	OW	P
7-8-46 BTR	8	040S	060W	4301351702	19315	Indian	Indian	OW	P
7-30-46 DLB	30	040S	060W	4301351703	18997	Fee	Indian	OW	P
3-13D-46 BTR	13	040S	060W	4301351718	18881	Indian	Indian	OW	P
2-13D-46 BTR	13	040S	060W	4301351719	18885	Indian	Indian	OW	P
12-12D-46 BTR	12	040S	060W	4301351720	18867	Indian	Indian	OW	P
10-12D-46 BTR	12	040S	060W	4301351721	18856	Indian	Indian	OW	P
11-11D-47 BTR	11	040S	070W	4301352091	19633	Fee	Fee	OW	P
7-12D-47 BTR	12	040S	070W	4301352094	19600	Indian	Fee	OW	P
5-12D-47 BTR	12	040S	070W	4301352095	19634	Indian	Fee	OW	P
14-33D-35 BTR	33	030S	050W	4301352162	19450	Indian	Fee	OW	P
16-33D-35 BTR	33	030S	050W	4301352163	19451	Indian	Fee	OW	P
14-22-46 DLB	22	040S	060W	4301333660	17604	Indian	Indian	D	PA
13H-31-36 BTR	31	030S	060W	4301350465	18485	Indian	Fee	OW	PA
16X-23D-36 BTR	23	030S	060W	4301350623	18007	Indian	State	OW	PA
8-6-45 BTR	6	040S	050W	4301350900	18561	Indian	Indian	OW	PA
13-13-36 BTR	13	030S	060W	4301350919	18364	Indian	Fee	OW	PA
7-28-46 DLB	28	040S	060W	4301333569	16460	Indian	Indian	OW	S
5-21-36 BTR	21	030S	060W	4301333641	16674	Indian	Fee	GW	S
13-26-36 BTR	26	030S	060W	4301333980	17569	Indian	Fee	OW	S
14-1-46 BTR	1	040S	060W	4301334113	18516	Indian	Indian	OW	S
16-21-36 BTR	21	030S	060W	4301334130	17721	Indian	Fee	OW	S
14-21-36 BTR	21	030S	060W	4301334131	18006	Indian	Fee	OW	S
7-16-36 BTR	16	030S	060W	4301334133	17834	Indian	Fee	OW	S
1-30-36 BTR	30	030S	060W	4301334134	17905	Indian	Fee	OW	S
16-30-36 BTR	30	030S	060W	4301334135	18005	Indian	Fee	OW	S
3-23-36 BTR	23	030S	060W	4301334137	17860	Indian	Fee	OW	S
16-16-36 BTR	16	030S	060W	4301334138	17666	Indian	Fee	OW	S

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

4-26-36 BTR	26	030S	060W	4301334139	17620	Fee	Fee	OW	S
9-11-36 BTR	11	030S	060W	4301334276	17451	Indian	Fee	OW	S
3-36-36 BTR	36	030S	060W	4301350398	17955	Indian	Fee	OW	S
7-10-36 BTR	10	030S	060W	4301350437	18052	Indian	Fee	OW	S
16-12D-46 BTR	12	040S	060W	4301350467	18051	Indian	Indian	OW	S
13H-13-46 BTR	13	040S	060W	4301350468	18208	Indian	Indian	OW	S
13-12-46 BTR	12	040S	060W	4301350469	18233	Indian	Indian	OW	S
14-8D-36 BTR	8	030S	060W	4301350612	18163	Indian	Fee	OW	S
14-7D-36 BTR	7	030S	060W	4301350613	18330	Indian	Fee	OW	S
16-9-36 BTR	9	030S	060W	4301350645	18078	Indian	Fee	OW	S
7-27-37 BTR	27	030S	070W	4301350647	18090	Indian	Fee	OW	S
16-12D-37 BTR	12	030S	070W	4301350785	18446	Indian	Fee	OW	S
14-21D-37 BTR	21	030S	070W	4301350859	18548	Indian	Fee	OW	S
10-18D-36 BTR	18	030S	060W	4301350915	18884	Indian	Fee	OW	S
5-27D-36	27	030S	060W	4301350917	18482	Indian	State	OW	S
10-36D-36 BTR	36	030S	060W	4301351005	18523	Indian	Fee	OW	S
14-6D-45 BTR	6	040S	050W	4301351158	18967	Indian	Indian	OW	S
5H-1-46 BTR UTELAND BUTTE	6	040S	050W	4301351215	18728	Indian	Indian	OW	S
5H-1-46 BTR WASATCH	6	040S	050W	4301351216	18727	Indian	Indian	OW	S
1-25D-36 BTR	25	030S	060W	4301351294	18798	Indian	Fee	OW	S
5-5D-35 BTR	5	030S	050W	4301351605	19055	Indian	Fee	OW	S
16-23-36 BTR	23	030S	060W	4301333971	17182	Indian	Fee	OW	TA
LC TRIBAL 14-23D-47	23	040S	070W	4301334022	18616	Indian	Indian	OW	TA
5-32D-36 BTR	32	030S	060W	4301350756	18328	Indian	Fee	OW	TA



October 20, 2016

Re: Bill Barrett Corporation Transfer to New Operator

Dear Ms. Medina:

Attached please find the change of operation Form 9, Form 5's and Request to Transfer APD form changing the operator from Bill Barrett Corporation to RIG II, LLC, effective 11/1/2016. Badlands Energy – Utah, LLC will be a sub-operator.

New Operator Contact information:

RIG II, LLC
1582 West 2600 South
Woods Cross, Utah 84087-0298
Telephone:(801) 683-4245
Fax:(801) 298-9889

Upon reviewing the attached, please contact myself with any questions at 303-312-8115.

Sincerely,

Bill Barrett Corporation

A handwritten signature in cursive script that reads 'Brady Riley'.

Brady Riley
Permit Analyst

RECEIVED
OCT 21 2016
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: (see attached well list)
2. NAME OF OPERATOR: RIG II, LLC <u>N14055</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 1582 West 2600 South CITY Wood Cross STATE UT ZIP 84087		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (801) 683-4245		8. WELL NAME and NUMBER: (see attached well list)
4. LOCATION OF WELL FOOTAGES AT SURFACE: (see attached well list) COUNTY:		9. API NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit In Duplicate) Approximate date work will start: <u>11/1/2016</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

RIG II, LLC IS SUBMITTING THIS SUNDRY AS NOTIFICATION THAT THE WELLS LISTED ON THE ATTACHED LIST HAVE BEEN SOLD TO RIG II, LLC BY BILL BARRETT CORPORATION EFFECTIVE 11/1/2016. PLEASE REFER ALL FUTURE CORRESPONDENCE TO THE ADDRESS BELOW.

RIG II, LLC
1582 West 2600 South
Woods Cross, Utah 84087-0298
801-683-4245
(STATE/FEE BOND # 9219529/ BLM BOND # UTB000712/ BIA BOND # LPM9224670)

BILL BARRETT CORPORATION N21165
Duana Zavala NAME (PLEASE PRINT)
Duana Zavala SIGNATURE
Senior Vice President -
EH&S, Government and Regulatory Affairs

RIG II, LLC
Jesse McSwain NAME (PLEASE PRINT)
Jesse McSwain SIGNATURE
Manager

NAME (PLEASE PRINT) Jesse McSwain TITLE Manager
SIGNATURE Jesse McSwain DATE 10/20/16

(This space for State use only)

APPROVED

NOV 07 2016

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Request to Transfer Application or Permit to Drill


(This form should accompany a Sundry Notice, Form 9, requesting APD transfer)

Well name:	(See attached list)
API number:	
Location:	Qtr-Qtr: Section: Township: Range:
Company that filed original application:	Bill Barrett Corporation
Date original permit was issued:	
Company that permit was issued to:	Bill Barrett Corporation

Check one	Desired Action:
<input type="checkbox"/>	Transfer pending (unapproved) Application for Permit to Drill to new operator
	The undersigned as owner with legal rights to drill on the property, hereby verifies that the information as submitted in the pending Application for Permit to Drill, remains valid and does not require revision. The new owner of the application accepts and agrees to the information and procedures as stated in the application.
<input checked="" type="checkbox"/>	Transfer approved Application for Permit to Drill to new operator
	The undersigned as owner with legal rights to drill on the property as permitted, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.	Yes	No
If located on private land, has the ownership changed?	✓	
If so, has the surface agreement been updated?		✓
Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?		✓
Have there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?		✓
Have there been any changes to the access route including ownership or right-of-way, which could affect the proposed location?		✓
Has the approved source of water for drilling changed?		✓
Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?		✓
Is bonding still in place, which covers this proposed well? Bond No. <small>9219529-UDOGM / UTB000712-BLM / LPM9224670-BIA</small>	✓	

Any desired or necessary changes to either a pending or approved Application for Permit to Drill that is being transferred, should be filed on a Sundry Notice, Form 9, or amended Application for Permit to Drill, Form 3, as appropriate, with necessary supporting information as required.

Name (please print) Jesse McSwain Title Manager
 Signature  Date 10/20/16
 Representing (company name) RIG II, LLC

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING


UIC FORM 5

TRANSFER OF AUTHORITY TO INJECT


Well Name and Number 6-32-36 BTR SWD	API Number 4301350921
Location of Well Footage : 1628 FNL 1553 FWL County : DUCHENSE QQ, Section, Township, Range: SENW 32 3S 6W State : UTAH	Field or Unit Name CEDAR RIM Lease Designation and Number 2OG0005608

EFFECTIVE DATE OF TRANSFER: 11/1/2016


CURRENT OPERATOR

Company: BILL BARRETT CORPORATION	Name: Duane Zavadil
Address: 1099 18th Street Ste 2300	Signature: 
city DENVER state CO zip 80202	Title: Senior Vice President - EH&S, Government and Regulatory Affairs
Phone: (303) 293-9100	Date: 10/20/16
Comments:	

NEW OPERATOR

Company: RIG II, LLC	Name: Jesse McSwain
Address: 1582 West 2600 South	Signature: 
city Wood Cross state UT zip 84087	Title: Manager
Phone: (801) 683-4245	Date: 10/20/16
Comments:	

(This space for State use only)

Transfer approved by: 
Title: UIC Geologist

Approval Date: 11/3/16

Comments:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING


UIC FORM 5

TRANSFER OF AUTHORITY TO INJECT


Well Name and Number 16-6D-46 BTR SWD	API Number 4301350781
Location of Well Footage : 0200 FSL 0099 FEL County : DUCHESNE QQ, Section, Township, Range: SESE 6 4S 6W State : UTAH	Field or Unit Name ALTAMONT Lease Designation and Number 2OG0005608

EFFECTIVE DATE OF TRANSFER: 11/1/2016

CURRENT OPERATOR

Company: <u>BILL BARRETT CORPORATION</u>	Name: <u>Duane Zavadil</u>
Address: <u>1099 18th Street Ste 2300</u>	Signature: <u></u>
city <u>DENVER</u> state <u>CO</u> zip <u>80202</u>	Title: <u>Senior Vice President -</u>
Phone: <u>(303) 293-9100</u>	Date: <u>10/20/16</u>
Comments:	

NEW OPERATOR

Company: <u>RIG II, LLC</u>	Name: <u>Jesse McSwain</u>
Address: <u>1582 West 2600 South</u>	Signature: <u></u>
city <u>Wood Cross</u> state <u>UT</u> zip <u>84087</u>	Title: <u>Manager</u>
Phone: <u>(801) 683-4245</u>	Date: <u>10/20/16</u>
Comments:	

(This space for State use only)

Transfer approved by: 
Title: VIC

Approval Date: 11/3/16

Comments:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING


UIC FORM 5

TRANSFER OF AUTHORITY TO INJECT


Well Name and Number SWD 9-36 BTR	API Number 4301350646
Location of Well Footage : 0539 FSL 0704 FEL County : DUCHESNE	Field or Unit Name CEDAR RIM
	Lease Designation and Number 2OG0005608
QQ, Section, Township, Range: SESE 9 3S 6W	State : UTAH

EFFECTIVE DATE OF TRANSFER: 11/1/2016

CURRENT OPERATOR

Company: <u>BILL BARRETT CORPORATION</u>	Name: <u>Duane Zavadil</u>
Address: <u>1099 18th Street Ste 2300</u>	Signature: 
city <u>DENVER</u> state <u>CO</u> zip <u>80202</u>	Title: <u>Senior Vice President - EH&S, Government and Regulatory Affairs</u>
Phone: <u>(303) 293-9100</u>	Date: <u>10/20/16</u>
Comments:	

NEW OPERATOR

Company: <u>RIG II, LLC</u>	Name: <u>Jesse McSwain</u>
Address: <u>1582 West 2600 South</u>	Signature: 
city <u>Wood Cross</u> state <u>UT</u> zip <u>84087</u>	Title: <u>Manager</u>
Phone: <u>(801) 683-4245</u>	Date: <u>10/20/16</u>
Comments:	

(This space for State use only)

Transfer approved by: _____ Approval Date: _____

Title: _____

Comments:

This well was approved by USEPA.
EPA approval will be required.