



Texaco Exploration and Production Inc

3300 N Butler
Farmington NM 87401

Feb. 8, 1996

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

RE: **Application for Permit to Drill (APD)**
Utah Federal 'D' No. 35-14, Surf Loc: 1249' FNL, 360' FWL, Unit D
Sec. 35-T17S-R7E
Emery County, Utah

Gentlemen:

Texaco Exploration and Production Inc. is seeking approval from the BLM to drill an exploratory well to test the Ferron formation. Texaco requests confidential status of this well and all information pertaining to it.

Texaco requests an exception to "Standard Location" due to adverse topography.

Your attention to this matter is greatly appreciated. If you have any questions concerning this matter please contact me at 505-325-4397, ext. 20.

Sincerely,

Ted A. Tipton
Operating Unit Manager
RSD/s, Attachments

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

FORM APPROVED
Budget Bureau No. 1004-0136
Expires: December 31, 1991

SUBMIT IN TRIPLICATE

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. Type of Work DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/>		5. Lease Designation and Serial No. UTU-74823	
1b. Type of Well OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER COAL-BED METHANE		6. If Indian, Alottee or Tribe Name	
2. Name of Operator TEXACO EXPLORATION & PRODUCTION, INC.		7. If Unit or CA, Agreement Designation	
3. Address and Telephone No. 3300 N. Butler Ave., Suite Farmington NM 87401 325-4397		8. Well Name and Number UTAH FEDERAL 'D'	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At Surface Unit Letter D : 1249 Feet From The NORTH Line and 360 Feet From The WEST Line At proposed prod. zone 40 110		9. API Well No. 35-14	
14. Distance in Miles and Direction from Nearest Town or Post Office* APP. 8.5 MI. NORTHWEST OF CASTLE DALE, UT		10. Field and Pool, Exploratory Area WILDCAT	
15. Distance From Proposed* Location to Nearest Property or Lease Line, Ft. (also to nearest drlg. unit line, if any) 1249'		11. SEC., T., R., M., or BLK. and Survey or Area Sec. 35 , Township T17S , Range R7E	
16. No. of Acres in Lease 2277.95		12. County or Parish EMERY	
17. No. of Acres Assigned To This Well 160 AC.		13. State UT	
18. Distance From Proposed Location* to Nearest Well, Drilling, Completed or Applied For, On This Lease, Ft. APP. 3640'		14. Proposed Depth 4175'	
19. Rotary or Cable Tools ROTARY		20. Rotary or Cable Tools ROTARY	
21. Elevations (Show whether DF, RT, GR, etc.) <input type="checkbox"/> KB <input type="checkbox"/> DF 6934 <input type="checkbox"/> GR		22. Approx. Date Work Will Start* 5/1/96	

23. PROPOSED CASING AND CEMENT PROGRAM				
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
11"	8-5/8"	24#	300'	230 SX
7-7/8"	5-1/2"	17#	4175'	365 SX (APPROX.)

TEXACO EXPLORATION & PRODUCTION, INC. PROPOSES TO DRILL A WELL TO A DEPTH OF 4175' TO TEST THE FERRON SAND AND ASSOCIATED COALS FOR PRODUCTIVE QUANTITIES OF NATURAL GAS. IF THE WELL IS UNPRODUCTIVE, IT WILL BE PLUGGED AND ABANDONED AS PER BLM AND STATE OF UTAH REQUIREMENTS.

PLEASE BE ADVISED THAT TEXACO EXPLORATION & PRODUCTION, INC. HAS BEEN AUTHORIZED BY PROPER LEASE INTEREST OWNERS TO CONDUCT OPERATIONS ON THE ABOVE MENTIONED LOCATION. TEXACO EXPLORATION & PRODUCTION, INC. AGREES TO BE RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR OPERATIONS CONDUCTED UPON THE LEASE LANDS.

BOND COVERAGE FOR THIS WELL IS PROVIDED BY BOND NO. CO-0058 (NATIONWIDE BOND). THE PRINCIPAL IS TEXACO EXPLORATION & PRODUCTION, INC. VIA SURETY CONSENT AS PROVIDED FOR IN 43 CFR-3104.2.

CONFIDENTIAL-TIGHT HOLE

In Above Space Describe Proposed Program: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured true verticle depths. Give blowout preventer program, if any.

24. I hereby certify that the foregoing is true and correct

SIGNATURE *Ted A. Tipton* TITLE Operating Unit Manager DATE 2/7/96

TYPE OR PRINT NAME Ted A. Tipton

(This space for Federal or State office use)

PERMIT NO. 43-015-30286 APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

APPROVED *J. Matthews* TITLE Petroleum Engineer DATE 7/15/96

CONDITIONS OF APPROVAL, IF ANY: _____



T17S, R7E, S.L.B.&M.

TEXACO EXPLR. & PROD., INC.

Well location, UTAH FEDERAL "D" #35-14, located as shown in the NW 1/4 NW 1/4 of Section 35, T17S, R7E, S.L.B.&M. Emery County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT THE NORTHWEST CORNER OF SECTION 2, T18S, R7E, S.L.B.&M. TAKEN FROM THE RED POINT QUADRANGLE, Utah, EMERY COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 6687 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RE: 161319
FORBES E. KAY
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (801) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 1-15-96	DATE DRAWN: 1-19-96
PARTY J.T.K. B.B. D.J.S.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE TEXACO EXPLR. & PROD., INC.	


R
7
E

Proposed Location:
UTAH FEDERAL "D" #35-14

T17S
T18S

PROPOSED ACCESS
ROAD 0.5 MI. +/-

HUNTINGTON 16.2 MI. +/-



UELS

TOPOGRAPHIC
MAP "B"

DATE: 1-22-96
Drawn by: C.B.T.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (801) 789-1017



TEXACO EXPLR. & PROD., INC.


UTAH FEDERAL "D" #35-14
SECTION 35, T17S, R7E, S.L.B.&M.
1249' FNL 360' FWL

SCALE: 1" = 2000'


TEXACO EXPLR. & PROD., INC.

LOCATION LAYOUT FOR

UTAH FEDERAL "D" #35-14
SECTION 35, T17S, R7E, S.L.B.&M.
1249' FNL 360' FWL



SCALE: "1 = 50'
DATE: 1-19-96
DRAWN BY: D.J.S.




Elev. Ungraded Ground at Location Stake = 6933.8'
Elev. Graded Ground at Location Stake = 6929.1'


TEXACO EXPLR. & PROD., INC.

TYPICAL CROSS SECTIONS FOR

UTAH FEDERAL "D" #35-14
SECTION 35, T17S, R7E, S.L.B.&M.
1249' FNL 360' FWL



1" = 20'
X-Section Scale
1" = 50'
DATE: 1-19-96
DRAWN BY: D.J.S.



APPROXIMATE YARDAGES

CUT		
(6") Topsoil Stripping	=	650 Cu. Yds.
Remaining Location	=	5,170 Cu. Yds.
TOTAL CUT	=	5,820 CU.YDS.
FILL	=	4,590 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	=	990 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	990 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East Vernal, Utah (801) 789-1017

THIRTEEN POINT SURFACE USE PLAN

OPERATOR: TEXACO EXPLORATION & PRODUCTION, INC.
LEASE NAME: UTAH FEDERAL 'D' #35-14
LEASE NUMBER: UTU-74823
LOCATION: 1249' FNL - 360' FWL, SECTION 35, T17S/R7E SLPM, EMERY CO.,UTAH

1. EXISTING ROADS.

- A. THE PROPOSED WELL SITE IS LOCATED APPROXIMATELY 8.5 MILES NORTHWEST OF CASTLE DALE, UTAH.
- B. DIRECTIONS TO THE LOCATION FROM CASTLE DALE, UTAH ARE AS FOLLOWS:

FROM CASTLE DALE, PROCEED WEST ON HIGHWAY #10 TO INTERSECTION WITH HIGHWAY # 57, TURN RIGHT ON #57. TRAVEL 6.0 MI. TO INTERSECTION WITH "COAL HAUL ROAD". TURN RIGHT(NORTH) ON PAVED "COAL HAUL ROAD". PROCEED NORTH APPROX. 2.9 MILE TO ACCESS ROAD. TURN RIGHT ONTO ACCESS ROAD TO LOCATION. PROCEED NORTH APPROX. 1/2 MI.
- C. THIS WELL WILL REQUIRE APPROX. 2600' OF NEW ACCESS ROAD.
- D. NO IMPROVEMENT WILL BE NECESSARY ON EXISTING ACCESS ROAD.
- E. ALL EXISTING ROADS WILL BE MAINTAINED AND KEPT IN GOOD REPAIR DURING ALL DRILLING AND COMPLETION OPERATIONS ASSOCIATED WITH THIS WELL.
- F. EXISTING ROADS AND THE EXISTING ACCESS ROAD UNDER THE JURISDICTION OF ANY SURFACE MANAGING AGENCY SHALL BE MAINTAINED IN ACCORDANCE WITH THE STANDARDS OF THE S.M.A.

2. PLANNED ACCESS ROAD.

- A. APPROXIMATELY 2600' OF NEW ACCESS ROAD IS REQUIRED FOR THE SUBJECT WELL. CURRENTLY, THERE IS A JEEP TRAIL THAT WILL BE UPGRADED TO ACCESS STANDARDS. THE ROAD WILL BE FLATBLADED WITH A RUNNING SURFACE OF APPROXIMATELY 25 FT.. IF NECESSARY, APPROPRIATE WATER CONTROL CULVERTS WILL BE INSTALLED TO CONTROL EROSION. CONSTRUCTION WILL NOT CHANGE EXISTING DRAINAGE.
- B. THE ROAD WILL BE UPGRADED AND MAINTAINED AS REQUIRED BY THE S.M.A.
- C. MAXIMUM GRADE WILL BE 8%.
- D. TURNOUTS WILL BE CONSTRUCTED AS REQUIRED BY THE S.M.A.
- E. LOW WATER CROSSINGS WILL BE INSTALLED ALONG THE ACCESS WHERE NEEDED.
- F. SURFACING MATERIAL WILL BE DEPENDENT UPON S.M.A. REQUIREMENTS.
- G. GATES & CATTLEGUARDS WILL BE INSTALLED AS NECESSARY.
- H. SURFACE DISTURBANCE AND VEHICULAR TRAVEL WILL BE LIMITED TO THE APPROVED LOCATION AND APPROVED ACCESS ROUTE. ANY ADDITIONAL AREA NEEDED WILL BE APPROVED IN ADVANCE.

3. **LOCATION OF EXISTING WELLS WITHIN A 1-MILE RADIUS OF THE PROPOSED LOCATION.**

- A. WATER WELLS - NONE
- B. INJECTION WELLS - NONE
- C. PRODUCING WELLS - ONE TEXACO COAL-BED METHANE WELL, ALONG WITH FOUR OTHER (TO-BE-PERMITTED) WELLS ARE LOCATED WITHIN A MILE OF THE PROPOSED WELL LOCATION.
- D. DRILLING WELLS - NONE

4. **LOCATION OF TANK BATTERIES AND PRODUCTION FACILITIES.**

- A. ALL PERMANENT STRUCTURES (ONSITE FOR SIX MONTHS OR LONGER) CONSTRUCTED OR INSTALLED (INCLUDING OIL WELL PUMP JACKS) WILL BE PAINTED A NEUTRAL COLOR TO BLEND WITH THE SURROUNDING ENVIRONMENT. FACILITIES REQUIRED TO COMPLY WITH THE OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA) WILL BE EXCLUDED.
- B. IF STORAGE FACILITIES/TANK BATTERIES ARE CONSTRUCTED ON THIS LEASE, THE FACILITY /BATTERY OR THE WELLPAD SHALL BE SURROUNDED BY A CONTAINMENT DIKE OF SUFFICIENT CAPACITY TO CONTAIN AT A MINIMUM, THE ENTIRE CONTENT OF THE LARGEST TANK WITHIN THE FACILITY/BATTERY, UNLESS MORE STRINGENT PROTECTIVE REQUIREMENTS ARE DEEMED NECESSARY BY THE AUTHORIZED OFFICER.
- C. ALL LOADING LINES WILL BE PLACED INSIDE THE BERM SURROUNDING THE TANK BATTERY.
- D. GAS MEASUREMENT DEVICES WILL BE LOCATED IN ACCORDANCE WITH THE APPROPRIATE REGULATORY BODY.
- E. ALL METER/MEASUREMENT FACILITIES WILL CONFORM WITH ONSHORE OIL AND GAS ORDER NO. 4 FOR LIQUID HYDROCARBONS AND ONSHORE OIL AND GAS ORDER NO. 5 FOR NATURAL GAS MEASUREMENT.
- F. ANY NECESSARY PITS WILL BE PROPERLY FENCED TO PREVENT ANY WILDLIFE ENTRY.
- G. ALL SITE SECURITY GUIDELINES IDENTIFIED IN 43 CFR 3162.7 REGULATIONS WILL BE ADHERED TO.
- H. ALL OFF-LEASE STORAGE, OFF-LEASE MEASUREMENT, OR COMMINGLING ON-LEASE OR OFF-LEASE WILL HAVE PRIOR WRITTEN APPROVAL FROM THE AUTHORIZED OFFICER.
- I. ALL ACCESS ROADS WILL BE MAINTAINED AS NECESSARY TO PREVENT EROSION AND ACCOMMODATE YEAR-ROUND TRAFFIC.
- J. THE ROAD WILL BE MAINTAINED IN A SAFE USEABLE CONDITION.
- K. WATER PRODUCED DURING THE TEST PHASE OF THIS WELL WILL BE STORED IN STORAGE TANKS ON LOCATION AND HAULED TO AN APPROVED DISPOSAL SITE. IF THE PROJECT SEEMS VIABLE BASED ON TEST RESULTS, A CONNECTION WILL BE MADE TO THE EXISTING GATHERING SYSTEM.

5. **LOCATION AND TYPE OF WATER SUPPLY.**

- A. ALL WATER NEEDED FOR DRILLING PURPOSES WILL BE OBTAINED FROM ORANGEVILLE MUNICIPAL WATER SYSTEM.

- B. WATER WILL BE HAULED TO LOCATION OVER THE ROADS MARKED ON MAPS ATTACHED.
- C. NO WATER WELL IS TO BE DRILLED ON THIS LEASE, WITHOUT PROPER APPROVAL OF DIVISION OF WATER RIGHTS IN PRICE, UTAH.
- D. ALL APPROPRIATE PERMITS WILL BE FILED WITH THE DIVISION OF WATER RIGHTS IN PRICE, UTAH.

6. **SOURCE OF CONSTRUCTION MATERIALS.**

- A. SURFACE AND SUBSOIL MATERIALS IN THE IMMEDIATE AREA WILL BE UTILIZED.
- B. ANY GRAVEL USED WILL BE OBTAINED FROM A COMMERCIAL SOURCE.
- C. THE USE OF MATERIALS UNDER BLM JURISDICTION WILL CONFORM WITH 43 CFR 3610.2.3.
- D. NO CONSTRUCTION MATERIALS WILL BE REQUIRED TO BE REMOVED FROM FEDERAL LAND AND ALL CONSTRUCTION ITEMS WILL BE PURCHASED FROM A THIRD PARTY.

7. **METHODS OF HANDLING WASTE DISPOSAL.**

- A. SINCE THE PROPOSED WELL WILL BE AIR-DRILLED, ONLY A SMALL RESERVE PIT WILL BE NECESSARY. THE RESERVE PIT WILL BE CONSTRUCTED SO AS NOT TO LEAK, BREAK, OR ALLOW DISCHARGE. THE RESERVE PIT WILL BE LINED IF DETERMINED NECESSARY AT THE TIME OF CONSTRUCTION.
- B. IF THE PIT IS LINED, A PLASTIC NYLON REINFORCED LINER WILL BE USED. IT WILL BE A MINIMUM OF 12 MIL THICKNESS WITH SUFFICIENT BEDDING (EITHER STRAW OR DIRT) TO COVER ANY ROCKS. THE LINER WILL OVERLAP THE PIT WALLS AND BE COVERED WITH DIRT AND/OR ROCKS TO HOLD IT IN PLACE. NO TRASH, SCRAP PIPE, ETC., THAT COULD PUNCTURE THE LINER WILL BE DISPOSED OF IN THE PIT.
- C. ALL TRASH WILL BE CONTAINED IN A TRASH CAGE AND ITS CONTENTS REMOVED AT THE END OF DRILLING OPERATIONS AND HAULED TO AN APPROVED DISPOSAL SITE.
- D. AFTER FIRST PRODUCTION, PRODUCED WATER WILL BE CONFINED TO A STORAGE TANK FOR A PERIOD NOT TO EXCEED NINETY (90) DAYS. DURING THE 90-DAY PERIOD, IN ACCORDANCE WITH ONSHORE ORDER NO. 7, AN APPLICATION FOR APPROVAL OF A PERMANENT DISPOSAL METHOD AND LOCATION, ALONG WITH THE REQUIRED WATER ANALYSIS, WILL BE SUBMITTED FOR THE AO'S APPROVAL.
- E. DRILL CUTTINGS ARE TO BE CONTAINED AND BURIED IN THE RESERVE PIT.
- F. ANY SALTS AND/OR CHEMICALS WHICH ARE AN INTEGRAL PART OF THE DRILLING SYSTEM, WILL BE DISPOSED OF IN THE SAME MANNER AS THE DRILLING FLUID.
- G. SEWAGE WILL BE PLACED IN A PORTABLE CHEMICAL TOILET OR HOLDING TANK AND DISPOSED OF IN ACCORDANCE WITH STATE AND COUNTY REGULATIONS.
- H. THE PRODUCED FLUIDS WILL BE PRODUCED INTO A TEST TANK UNTIL SUCH TIME AS CONSTRUCTION OF PRODUCTION FACILITIES IS COMPLETED. ANY SPILLS OF OIL, GAS, SALT WATER OR OTHER PRODUCED FLUIDS WILL BE CLEANED UP.

8. **ANCILLARY FACILITIES.**

- A. THERE ARE NO AIRSTRIPS, CAMPS, OR OTHER FACILITIES PLANNED DURING THE DRILLING OF THE PROPOSED WELL.

9. **WELL SITE LAYOUT.**

- A. THE RESERVE PIT WILL BE LOCATED ON THE NORTH SIDE OF THE LOCATION.
- B. THE STOCKPILED TOPSOIL (FIRST SIX INCHES) WILL BE STORED ALONG THE SOUTH SIDE OF THE WELLPAD AS SHOWN ON THE RIG LAYOUT.
- C. SEE LOCATION LAYOUT FOR ORIENTATION OF RIG, CROSS SECTION OF DRILL PAD AND CUTS AND FILLS.
- D. THE LOCATION OF MUD TANKS, RESERVE PIT, TRASH CAGE, PIPE RACKS, LIVING FACILITIES AND SOIL STOCKPILES ARE SHOWN ON THE LOCATION LAYOUT.
- E. ALL PITS WILL BE FENCED TO PREVENT WILDLIFE ENTRY.
- F. THE RESERVE PIT FENCING WILL BE ON THREE SIDES DURING OPERATIONS AND ON THE FOURTH SIDE WHEN THE RIG MOVES OFF LOCATION. PITS WILL BE FENCED AND MAINTAINED UNTIL CLEANUP.

10. **PLANS FOR RESTORATION OF SURFACE.**

PRODUCING LOCATION

- A. IMMEDIATELY UPON WELL COMPLETION, THE LOCATION AND SURROUNDING AREA WILL BE CLEARED OF ALL UNUSED TUBING, EQUIPMENT, DEBRIS, MATERIALS, TRASH AND JUNK NOT REQUIRED FOR PRODUCTION.
- B. IMMEDIATELY UPON WELL COMPLETION, ANY HYDROCARBONS ON THE PIT SHALL BE REMOVED IN ACCORDANCE WITH 43 CFR 3162.7-1.
- C. IF A PLASTIC NYLON REINFORCED LINER IS USED, IT SHALL BE TORN AND PERFORATED BEFORE BACKFILLING OF THE RESERVE PIT.
- D. ONCE THE RESERVE PIT IS DRY, THE RESERVE PIT AND THAT PORTION OF THE LOCATION NOT NEEDED FOR PRODUCTION FACILITIES/OPERATIONS WILL BE RECONTOURED TO THE APPROXIMATE NATURAL CONTOURS.
- E. THE LOCATION WILL BE RECLAIMED AND RESEEDDED AS REQUESTED BY THE BLM.

DRY HOLE

- F. AT SUCH TIME AS THE WELL IS PLUGGED AND ABANDONED, THE OPERATOR SHALL SUBMIT A SUBSEQUENT REPORT OF ABANDONMENT AND WILL RECLAIM LANDS AS PER GUIDELINES PURSUANT TO AO.

11. **SURFACE OWNERSHIP.**

- A. ACCESS ROADS - ALL EXISTING IMPROVED ROADS ARE COUNTY MAINTAINED AND ENCROACHMENT IS BEING APPLIED FOR.
- B. WELLPAD - THE WELLPAD IS LOCATED ON LANDS MANAGED BY THE BUREAU OF LAND MANAGEMENT.

12. **OTHER INFORMATION.**

- A. A CLASS III ARCHAEOLOGY SURVEY WILL BE CONDUCTED BY AN APPROVED ARCHAEOLOGICAL CONSULTANT. THIS SURVEY WILL BE CONDUCTED AT THE TIME OF ON-SITE INSPECTION BY THE BLM. A COPY OF THE REPORT WILL BE SUPPLIED TO THE BLM DISTRICT ARCHAEOLOGIST, PRICE, UTAH.
- B. THE OPERATOR IS RESPONSIBLE FOR INFORMING ALL PERSONS IN THE AREAS WHO ARE ASSOCIATED WITH THIS PROJECT, THAT THEY WILL BE SUBJECT TO PROSECUTION FOR KNOWINGLY DISTURBING HISTORIC OR ARCHAEOLOGICAL SITES, OR FOR COLLECTING ARTIFACTS. IF HISTORIC OR ARCHAEOLOGICAL MATERIALS ARE UNCOVERED DURING CONSTRUCTION, THE OPERATOR IS TO IMMEDIATELY STOP WORK THAT MIGHT FURTHER DISTURB SUCH MATERIALS, AND CONTACT THE AUTHORIZED OFFICER (AO). WITHIN FIVE WORKING DAYS, THE AO WILL INFORM THE OPERATOR AS TO:
- WHETHER THE MATERIALS APPEAR ELIGIBLE FOR THE NATIONAL REGISTER OF HISTORIC PLACES;
 - THE MITIGATION MEASURES THE OPERATOR WILL LIKELY HAVE TO UNDERTAKE BEFORE THE SITE CAN BE USED (ASSUMING IN SITU PRESERVATION IS NOT NECESSARY); AND
 - A TIME FRAME FOR THE AO TO COMPLETE AND EXPEDITE REVIEW UNDER 36 CFR 800.11 TO CONFORM, THROUGH THE STATE HISTORIC PRESERVATION OFFICER, THAT THE FINDINGS OF THE AO ARE CORRECT AND THAT MITIGATION IS APPROPRIATE. IF THE OPERATOR WISHES, AT ANY TIME, TO RELOCATE ACTIVITIES TO AVOID THE EXPENSE OF MITIGATION AND/OR THE DELAYS ASSOCIATED WITH THIS PROCESS, THE AO WILL ASSUME RESPONSIBILITY FOR WHATEVER RECORDATION AND STABILIZATION OF THE EXPOSED MATERIALS MAY BE REQUIRED. OTHERWISE, THE OPERATOR WILL BE RESPONSIBLE FOR MITIGATION COSTS. THE AO WILL PROVIDE TECHNICAL AND PROCEDURAL GUIDELINES FOR THE CONDUCT OF MITIGATION. UPON VERIFICATION FROM THE AO THAT REQUIRED MITIGATION HAS BEEN COMPLETED, THE OPERATOR WILL THEN BE ALLOWED TO RESUME CONSTRUCTION.
- C. ALL LEASE AND/OR UNIT OPERATIONS WILL BE CONDUCTED IN SUCH A MANNER THAT FULL COMPLIANCE IS MADE WITH ALL APPLICABLE LAWS, REGULATIONS, ONSHORE OIL AND GAS ORDERS, THE APPROVED PLAN OF OPERATIONS, AND ANY APPLICABLE NOTICE TO LESSEES. THE OPERATOR IS FULLY RESPONSIBLE FOR THE ACTIONS OF HIS SUBCONTRACTORS. A COPY OF THESE CONDITIONS WILL BE FURNISHED TO THE REPRESENTATIVE TO INSURE COMPLIANCE.
- D. A COMPLETE COPY OF THE APPROVED APD SHALL BE ON LOCATION DURING CONSTRUCTION OF THE LOCATION AND DRILLING ACTIVITIES.
- E. THERE WILL BE NO DEVIATION FROM THE PROPOSED DRILLING AND/OR WORKOVER PROGRAM WITHOUT PRIOR APPROVAL FROM THE AO. SAFE DRILLING AND OPERATING PRACTICES MUST BE OBSERVED. ALL WELLS, WHETHER DRILLING, PRODUCING, SUSPENDED, OR ABANDONED WILL BE IDENTIFIED IN ACCORDANCE WITH 43 CFR 3162.H.
- F. "SUNDRY NOTICE AND REPORT ON WELLS" (FORM 3160-5) WILL BE FILED FOR APPROVAL FOR ALL CHANGES OF PLANS AND OTHER OPERATIONS IN ACCORDANCE WITH 43 CFR 3162.3-2.
- G. THIS PERMIT WILL BE VALID FOR A PERIOD OF ONE YEAR FROM THE DATE OF APPROVAL. AN EXTENSION PERIOD MAY BE GRANTED, IF REQUESTED, PRIOR TO THE EXPIRATION OF THE ORIGINAL APPROVAL PERIOD.
- H. THE OPERATOR OR HIS CONTRACTOR SHALL CONTACT THE BLM OFFICES AT (801)637-4584, 48 HOURS PRIOR TO CONSTRUCTION ACTIVITIES.
- I. IF THE WELL PROVES ECONOMIC, A GAS FLOWLINE AND WATER GATHERING LINE WILL BE INSTALLED ON LEASE.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION.**

PERMIT MATTERS
TEXACO E. & P., INC.
TED A. TIPTON
3300 N. BUTLER AVE.
FARMINGTON, NM 87401
(505) 325-4397

DRILLING AND COMPLETION MATTERS
TEXACO E. & P., INC.
P.O. BOX 46510
DENVER, CO 80201-6510
(303) 793-4000 MAIN NUMBER
(303) 793-4936 - (W) STEVE GODFREY
(303) 347-0737 - (H)


CERTIFICATION

I HEREBY CERTIFY THAT I, OR PERSONS UNDER MY DIRECT SUPERVISION, HAVE INSPECTED THE PROPOSED DRILLSITE AND ACCESS ROUTE; THAT I AM FAMILIAR WITH THE CONDITIONS WHICH PRESENTLY EXIST; THAT THE STATEMENTS MADE IN THIS PLAN ARE, TO THE BEST OF MY KNOWLEDGE, TRUE AND CORRECT; AND, THAT THE WORK ASSOCIATED WITH THE OPERATIONS PROPOSED HEREIN WILL BE PERFORMED BY TEXACO EXPLORATION & PRODUCTION, INC. AND ITS CONTRACTORS AND SUBCONTRACTORS IN CONFORMITY WITH THE PLAN AND THE TERMS AND CONDITIONS UNDER WHICH IT IS APPROVED.

THIS STATEMENT IS SUBJECT TO THE PROVISIONS OF 18.U.S.C. 1001 FOR THE FILING OF A FALSE STATEMENT.

2/15/96

DATE:



TED A. TIPTON
OPERATIONS UNIT MANAGER
TEXACO E. & P., INC.

DRILLING PROGRAM

OPERATOR: TEXACO EXPLORATION & PRODUCTION, INC.
LEASE NAME: UTAH FEDERAL 'D' #35-14
LEASE NUMBER: UTU-74823
LOCATION: 1249' FNL - 360' FWL, SECTION 35, T17S/R7E SLPM, EMERY CO.,UTAH

1. **ESTIMATED TOPS OF GEOLOGIC MARKERS.**

THE ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS ARE AS FOLLOWS:

<u>FORMATION</u>	<u>DEPTH</u>	<u>SUBSEA</u>
BLUE GATE	100	+6845
FERRON	3825	+3120
T.D.	4175	+2770

2. **ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS, WATER, OR OTHER MINERAL BEARING ZONES.**

<u>SUBSTANCE</u>	<u>FORMATION</u>	<u>DEPTH</u>
WATER,GAS	FERRON COALS	3825
GAS	FERRON SANDSTONES	3825
OIL	N/A	
OTHER MINERALS	N/A	

ALL FRESH WATER AND PROSPECTIVELY VALUABLE MINERALS ENCOUNTERED DURING DRILLING, WILL BE RECORDED BY DEPTH AND ADEQUATELY PROTECTED. ALL OIL AND GAS SHOWS WILL BE TESTED TO DETERMINE COMMERCIAL POTENTIAL.

ALL WATER SHOWS AND WATER-BEARING SANDS WILL BE REPORTED TO THE BLM IN MOAB, UTAH. COPIES OF STATE OF UTAH FORM OGC-8-X ARE ACCEPTABLE. IF NOTICEABLE WATER FLOWS ARE DETECTED, SAMPLES WILL BE SUBMITTED TO THE BLM ALONG WITH ANY WATER ANALYSIS CONDUCTED.

3. **BOP EQUIPMENT.**

TEXACO'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL EQUIPMENT ARE AS FOLLOWS:

RAM TYPE: 11" HYDRAULIC DOUBLE, 2000 PSI W.P.

RAM TYPE PREVENTERS AND ASSOCIATED EQUIPMENT SHALL BE TESTED TO APPROVED STACK WORKING PRESSURE IF ISOLATED BY TEST PLUG OR TO 70 PERCENT OF INTERNAL YIELD PRESSURE OF CASING. PRESSURE SHALL BE MAINTAINED FOR AT LEAST 10 MINUTES OR UNTIL REQUIREMENTS OF TEST ARE MET, WHICHEVER IS LONGER. IF A TEST PLUG IS UTILIZED, NO BLEED-OFF PRESSURE IS ACCEPTABLE. FOR A TEST NOT UTILIZING A TEST PLUG, IF A DECLINE IN PRESSURE OF MORE THAN 10 PERCENT IN 30 MINUTES OCCURS, THE TEST SHALL BE CONSIDERED TO HAVE FAILED. VALVE ON CASING HEAD BELOW TEST PLUG SHALL BE OPEN DURING TEST OF BOP STACK.

ANNULAR TYPE PREVENTERS (IF USED) SHALL BE TESTED TO 50 PERCENT OF RATED WORKING PRESSURE. PRESSURE SHALL BE MAINTAINED AT LEAST 10 MINUTES OR UNTIL PROVISIONS OF TEST ARE MET, WHICHEVER IS LONGER.

AS A MINIMUM, THE ABOVE TEST SHALL BE PERFORMED:

- A. WHEN INITIALLY INSTALLED;
- B. WHENEVER ANY SEAL SUBJECT TO TEST PRESSURE IS BROKEN

- C. FOLLOWING RELATED REPAIRS; AND
- D. AT 30 DAY INTERVALS

VALVES SHALL BE TESTED FROM WORKING PRESSURE SIDE DURING BOPE TESTS WITH ALL DOWNSTREAM VALVES OPEN.

WHEN TESTING THE KILL LINE VALVE(S), THE CHECK VALVE SHALL BE HELD OPEN OR THE BALL REMOVED.

ANNULAR PREVENTERS (IF USED) SHALL BE FUNCTIONALLY OPERATED AT LEAST WEEKLY.

PIPE AND BLIND RAMS SHALL BE ACTIVATED EACH TRIP, HOWEVER, THIS FUNCTION NEED NOT BE PERFORMED MORE THAN ONCE A DAY.

A BOPE PIT LEVEL DRILL SHALL BE CONDUCTED WEEKLY FOR EACH DRILLING CREW.

PRESSURE TESTS SHALL APPLY TO ALL RELATED WELL CONTROL EQUIPMENT.

ALL OF THE ABOVE DESCRIBED TESTS AND/OR DRILLS SHALL BE RECORDED IN THE DRILLING LOG. TEST CHARTS, WITH INDIVIDUAL TEST RESULTS IDENTIFIED, SHALL BE MAINTAINED ON LOCATION WHILE DRILLING AND SHALL BE MADE AVAILABLE TO A BLM REPRESENTATIVE UPON REQUEST. PRESSURE TESTS SHALL APPLY TO ALL RELATED WELL CONTROL EQUIPMENT.

BOP SYSTEMS SHALL BE CONSISTENT WITH API RP53. PRESSURE TESTS WILL BE CONDUCTED BEFORE DRILLING OUT FROM UNDER CASING STRINGS WHICH HAVE BEEN SET AND CEMENTED IN PLACE. BLOWOUT PREVENTER CONTROLS WILL BE INSTALLED PRIOR TO DRILLING THE SURFACE CASING PLUG AND WILL REMAIN IN USE UNTIL THE WELL IS COMPLETED OR ABANDONED. PREVENTERS WILL BE INSPECTED AND OPERATED AT LEAST DAILY TO ENSURE GOOD MECHANICAL WORKING ORDER, AND THIS INSPECTION WILL BE RECORDED ON THE DAILY DRILLING REPORT. PREVENTERS WILL BE PRESSURE TESTED BEFORE DRILLING CASING CEMENT PLUGS.

THE SAN RAFAEL RESOURCE AREA OFFICE SHALL BE NOTIFIED, AT LEAST 24 HOURS PRIOR TO INITIATING THE PRESSURE TEST, IN ORDER TO HAVE A BLM REPRESENTATIVE ON LOCATION DURING PRESSURE TESTING.

- A. THE SIZE AND RATING OF THE BOP STACK IS SHOWN ON THE ATTACHED DIAGRAM. ALTHOUGH A RIG HAS NOT BEEN CHOSEN TO DRILL THIS WELL, MOST OF THE EQUIPMENT FOR THIS DEPTH OF HOLE IN THE AREA USE A 11", 2000 PSI WORKING PRESSURE BLOWOUT PREVENTOR.
- B. A CHOKE LINE AND A KILL LINE ARE TO BE PROPERLY INSTALLED. THE KILL LINE IS NOT TO BE USED AS A FILL UP LINE.
- C. THE ACCUMULATOR SYSTEM SHALL HAVE A PRESSURE CAPACITY TO PROVIDE FOR REPEATED OPERATION OF HYDRAULIC PREVENTORS.
- D. DRILL STRING SAFETY VALVE(S), TO FIT ALL TOOLS IN THE DRILL STRING, ARE TO BE MAINTAINED ON THE RIG FLOOR WHILE DRILLING OPERATIONS ARE IN PROGRESS.

4. **CASING AND CEMENTING PROGRAMS.**

- A. THE SAN RAFAEL RESOURCE AREA OFFICE SHALL BE NOTIFIED AT LEAST 24 HOURS PRIOR TO THE RUNNING AND CEMENTING OF ALL CASING STRINGS, IN ORDER TO HAVE A BLM REPRESENTATIVE ON LOCATION WHILE RUNNING AND CEMENTING ALL CASING STRINGS.
- B. THE PROPOSED CASING AND CEMENTING PROGRAM SHALL BE CONDUCTED AS APPROVED TO PROTECT AND/OR ISOLATE ALL USABLE WATER ZONES, POTENTIALLY PRODUCTIVE ZONES, LOST CIRCULATION ZONES, ABNORMALLY PRESSURED ZONES, AND ANY PROSPECTIVELY VALUABLE DEPOSITS OF MINERALS. ANY ISOLATING MEDIUM OTHER THAN CEMENT SHALL RECEIVE APPROVAL PRIOR TO USE. THE CASING SETTING DEPTH SHALL BE CALCULATED TO

POSITION THE CASING SEAT OPPOSITE A COMPETENT FORMATION WHICH WILL CONTAIN THE MAXIMUM PRESSURE TO WHICH IT WILL BE EXPOSED DURING NORMAL DRILLING OPERATIONS. DETERMINATIONS OF CASING SETTINGS DEPTH SHALL BE BASED ON ALL RELEVANT FACTORS, INCLUDING; PRESENCE/ABSENCE OF HYDROCARBONS; FRACTURE GRADIENTS; USABLE WATER ZONES; FORMATION PRESSURES; LOST CIRCULATION ZONES; OTHER MINERALS; OR OTHER UNUSUAL CHARACTERISTICS. ALL INDICATIONS OF USABLE WATER SHALL BE REPORTED.

- C. CASING DESIGN SHALL ASSUME FORMATION PRESSURE GRADIENTS OF 0.44 TO 0.50 PSI PER FOOT FOR EXPLORATORY WELLS (LACKING BETTER DATA).
- D. CASING DESIGN SHALL ASSUME FRACTURE GRADIENTS FROM 0.70 TO 1.00 PSI PER FOOT FOR EXPLORATORY WELLS (LACKING BETTER DATA).
- E. CASING COLLARS SHALL HAVE A MINIMUM CLEARANCE OF 0.422 INCHES OF ALL SIDES IN THE HOLE/CASING ANNULUS, WITH RECOGNITION THAT VARIANCES CAN BE GRANTED FOR JUSTIFIED EXCEPTIONS.
- F. ALL WAITING ON CEMENT TIMES SHALL BE ADEQUATE TO ACHIEVE A MINIMUM OF 500 PSI COMPRESSIVE STRENGTH AT THE CASING SHOE PRIOR TO DRILLING OUT.
- G. ALL CASING EXCEPT THE CONDUCTOR CASING, SHALL BE NEW OR RECONDITIONED AND TESTED, USING CASING THAT MEETS OR EXCEEDS API STANDARDS FOR NEW CASING.
- H. THE SURFACE CASING SHALL BE CEMENTED BACK TO SURFACE EITHER DURING THE PRIMARY CEMENTING JOB OR BY REMEDIAL CEMENTING.
- I. ALL INDICATIONS OF USABLE WATER SHALL BE REPORTED TO THE AUTHORIZED OFFICER PRIOR TO RUNNING THE NEXT STRING OF CASING OR BEFORE PLUGGING ORDERS ARE REQUESTED, WHICHEVER OCCURS FIRST.
- J. THE SURFACE CASING SHALL HAVE CENTRALIZERS ON THE BOTTOM THREE JOINTS OF CASING (A MINIMUM OF ONE CENTRALIZER PER JOINT, STARTING WITH THE SHOE JOINT), THEN EVERY FOURTH JOINT OF CASING UP TO THE BOTTOM OF THE CELLAR.
- K. TOP PLUGS SHALL BE USED TO REDUCE CONTAMINATION OF CEMENT BY DISPLACEMENT FLUID. A BOTTOM PLUG OR OTHER ACCEPTABLE TECHNIQUE, SUCH AS A SUITABLE PREFLUSH FLUID, INNER STRING CEMENT METHOD, ETC. SHALL BE UTILIZED TO HELP ISOLATE THE CEMENT FROM CONTAMINATION BY THE MUD FLUID BEING DISPLACED AHEAD OF THE CEMENT SLURRY.
- L. ALL CASING STRINGS BELOW THE CONDUCTOR SHALL BE PRESSURE TESTED TO 0.22 PSI PER FOOT OF CASING STRING LENGTH OR 1500 PSI, WHICHEVER IS GREATER, BUT NOT TO EXCEED 70 PERCENT OF THE MINIMUM INTERNAL YIELD. IF PRESSURE DECLINES MORE THAN 10 PERCENT IN 30 MINUTES, CORRECTIVE ACTION SHALL BE TAKEN.

M. THE PROPOSED CASING PROGRAM WILL BE AS FOLLOWS:

<u>PURPOSE</u>	<u>DEPTH</u>	<u>HOLE SIZE</u>	<u>O.D.</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>TYPE</u>	<u>NEW</u>	<u>OR USED</u>
SURFACE	0-300'	11"	8-5/8"	24#	K-55	ST&C	NEW	
PRODUCTION	0-4175'	7-7/8"	5-1/2"	17#	N-80	LT&C	NEW	

N. CASING DESIGN SUBJECT TO REVISION BASED ON GEOLOGIC CONDITIONS ENCOUNTERED.

O. THE CEMENT PROGRAM WILL BE AS FOLLOWS:

<u>SURFACE</u>	<u>TYPE AND AMOUNT</u>
0-300'	CEMENT TO SURFACE WITH 230 SX CLASS 'G' CEMENT WITH 2% CaCl, AND 1/4#/SK CELLOPHANE FLAKES. 15.8 PPG, 1.15 CU FT./SK
<u>PRODUCTION</u>	<u>TYPE AND AMOUNT</u>
0-4175' LEAD (2875'-SURFACE)	190 SX CLASS 'G' CEMENT WITH 12% D-20(GEL), 10% D-44(SALT), 1% D-79 (EXTENDER), WITH 5# / SX D-42 (KOLITE), 0.2% D-46 (ANTIFOAMER)
TAIL (4175' - 2875')	175 SX RFC 10-1 BLEND CEMENT

P. THE SAN RAFAEL RESOURCE AREA OFFICE SHOULD BE NOTIFIED, WITH SUFFICIENT LEAD TIME, IN ORDER TO HAVE A BLM REPRESENTATIVE ON LOCATION WHILE RUNNING AND CEMENTING ALL CASING STRINGS.

Q. AFTER CEMENTING, BUT BEFORE COMMENCING ANY TEST, THE CASING STRING SHALL STAND CEMENTED UNTIL THE CEMENT HAS REACHED A COMPRESSIVE STRENGTH OF AT LEAST 500 PSI AT THE SHOE. WOC TIME SHALL BE RECORDED IN THE DRILLER'S LOG.

R. THE FOLLOWING REPORTS SHALL BE FILED WITH THE DISTRICT MANAGER WITHIN 30 DAYS AFTER THE WORK IS COMPLETED.

1. PROGRESS REPORTS, FORM 3160-5 (FORMERLY 9-331) "SUNDRY NOTICES AND REPORTS ON WELLS", MUST INCLUDE COMPLETE INFORMATION CONCERNING:
 - A. SETTING OF EACH STRING OF CASING, SHOWING THE SIZE, GRADE, WEIGHT OF CASING SET, HOLE SIZE, SETTING DEPTH, AMOUNTS AND TYPES OF CEMENT USED, WHETHER CEMENT CIRCULATED OR THE TOP OF THE CEMENT BEHIND THE CASING, DEPTH OF CEMENTING TOOLS USED, CASING TEST METHOD AND RESULTS, AND THE DATE WORK WAS DONE. SHOW THE SPUD DATE ON THE FIRST REPORT SUBMITTED.

S. AUXILIARY EQUIPMENT TO BE USED IS AS FOLLOWS:

1. KELLY COCK
2. NO BIT FLOAT IS DEEMED NECESSARY.
3. A SUB WITH A FULL OPENING VALVE.

5. **MUD PROGRAM**

A. THE PROPOSED CIRCULATING MEDIUMS TO BE EMPLOYED IN DRILLING ARE AS FOLLOWS:

<u>INTERVAL</u>	<u>MUD TYPES</u>	<u>MUD WEIGHT</u>	<u>VISC.</u>	<u>F/L</u>	<u>PH</u>
0-4175'	AIR	--	--	--	--

B. THE RIG IS NOT EQUIPPED WITH AN AUTO-IGNITOR OR DEBUSTER EQUIPMENT.

- C. HAZARDOUS SUBSTANCES SPECIFICALLY LISTED BY THE E.P.A. AS A HAZARDOUS WASTE OR DEMONSTRATING A CHARACTERISTIC OF A HAZARDOUS WASTE WILL NOT BE USED IN DRILLING, TESTING OR COMPLETION OPERATIONS. DUE TO POTENTIAL CONTAMINATION OF USABLE QUALITY WATER AQUIFERS, CHROMATES ARE BANNED FROM FEDERAL LEASES.

6. **EVALUATION PROGRAM.**

THE ANTICIPATED TYPE AND AMOUNT OF TESTING, LOGGING AND CORING ARE AS FOLLOWS:

- A. NO DRILL STEM TESTS (DST) ARE ANTICIPATED, HOWEVER, IF DST'S ARE RUN, THE FOLLOWING REQUIREMENTS WILL BE ADHERED TO:

INITIAL OPENING OF DST TOOLS SHALL BE RESTRICTED TO DAYLIGHT HOURS, UNLESS SPECIFIC APPROVAL TO START DURING OTHER HOURS IS OBTAINED FROM THE AUTHORIZED OFFICER. HOWEVER, DST'S MAY BE ALLOWED TO CONTINUE AT NIGHT IF THE TEST WAS INITIATED DURING DAYLIGHT HOURS AND THE RATE OF FLOW IS STABILIZED AND IF ADEQUATE LIGHTING IS AVAILABLE (I.E. LIGHTING WHICH IS ADEQUATE FOR VISIBILITY AND VAPOR-PROOF FOR SAFE OPERATIONS). PACKERS CAN BE RELEASED, BUT TRIPPING SHALL NOT BEGIN BEFORE DAYLIGHT, UNLESS PRIOR APPROVAL IS OBTAINED FROM THE AUTHORIZED OFFICER. CLOSED CHAMBER DST'S MAY BE ACCOMPLISHED DAY OR NIGHT.

A DST THAT FLOWS TO THE SURFACE WITH EVIDENCE OF HYDROCARBONS SHALL BE EITHER REVERSED OUT OF THE TESTING STRING UNDER CONTROLLED SURFACE CONDITIONS. THIS WOULD INVOLVE PROVIDING SOME MEANS FOR REVERSE CIRCULATION.

SEPARATION EQUIPMENT REQUIRED FOR THE ANTICIPATED RECOVERY SHALL BE PROPERLY INSTALLED BEFORE A TEST STARTS.

ALL ENGINES WITHIN 100 FEET OF THE WELLBORE THAT ARE REQUIRED TO "RUN" DURING THE TEST SHALL HAVE SPARK ARRESTERS OR WATER COOLED EXHAUSTS.

- B. THE LOGGING PROGRAM WILL CONSIST OF A GR-LDT-CNL FROM 3000'-4175'. A HIGH RESOLUTION COAL LOG WILL BE RUN FROM 3100'-4175'. A GR-SFL-DIL LOG WILL BE RUN FROM 300'-4175'.
- C. NO CORES ARE PLANNED IN THE WELL.
- D. WHETHER THE WELL IS COMPLETED AS A DRY HOLE OR AS A PRODUCER, "WELL COMPLETION AND RECOMPLETION REPORT AND LOG" (FORM 3160-4) WILL BE SUBMITTED NOT LATER THAN 30 DAYS AFTER COMPLETION OF THE WELL OR AFTER COMPLETION OF OPERATIONS PERFORMED, IN ACCORDANCE WITH 43 CFR 3164. TWO COPIES OF ALL LOGS, CORE DESCRIPTIONS, CORE ANALYSES, WELL-TEST DATA, GEOLOGIC SUMMARIES, SAMPLE DESCRIPTION, AND ALL OTHER SURVEYS OR DATA OBTAINED AND COMPILED DURING THE DRILLING, WORKOVER, AND/OR COMPLETION OPERATIONS, WILL BE FILED WITH FORM 3160-4. SAMPLES (CUTTINGS, FLUIDS, AND/OR GASES) WILL BE SUBMITTED WHEN REQUESTED BY THE AUTHORIZED OFFICER (AO).
- E. THE ANTICIPATED COMPLETION PROGRAM IS AS FOLLOWS:
- SET 5-1/2" PRODUCTION CASING. PERFORATE AND FRACTURE TREAT FERRON FORMATION. FLOW TEST.

7. **ABNORMAL PRESSURES AND H₂S GAS.**


- A. NO ABNORMAL CONDITIONS ARE ANTICIPATED; FORMATION IS SLIGHTLY OVER-PRESSURED. THE ESTIMATED BOTTOM-HOLE PRESSURE IS 1545 PSI. NO ABNORMAL TEMPERATURES ARE ANTICIPATED.
- B. NO HYDROGEN SULFIDE GAS IS ANTICIPATED.

8. NOTIFICATION REQUIREMENTS AND OTHER INFORMATION.

- A. SHOULD THE WELL BE SUCCESSFULLY COMPLETED FOR PRODUCTION, THE AO WILL BE NOTIFIED WHEN THE WELL IS PLACED IN A PRODUCING STATUS. SUCH NOTIFICATION WILL BE SENT BY TELEGRAM OR OTHER WRITTEN COMMUNICATIONS, NOT LATER THAN 5 DAYS FOLLOWING THE DATE ON WHICH THE WELL IS PLACED ON PRODUCTION.
- B. PRODUCTION DATA SHALL BE REPORTED TO THE MMS PURSUANT TO 30 CFR 216.5 USING FORM MMS/3160.
- C. THE DATE ON WHICH PRODUCTION IS COMMENCED OR RESUMED WILL BE CONSTRUED FOR OIL WELLS AS THE DATE ON WHICH LIQUID HYDROCARBONS ARE FIRST SOLD OR SHIPPED FROM A TEMPORARY STORAGE FACILITY, SUCH AS A TEST TANK, AND FOR WHICH A RUN TICKET IS REQUIRED TO BE GENERATED OR, THE DATE ON WHICH LIQUID HYDROCARBONS ARE FIRST PRODUCED INTO A PERMANENT STORAGE FACILITY, WHICHEVER FIRST OCCURS; AND FOR GAS WELLS AS THE DATE ON WHICH ASSOCIATED LIQUID HYDROCARBONS ARE FIRST SOLD OR SHIPPED FROM A TEMPORARY STORAGE FACILITY, SUCH AS A TEST TANK, AND FOR WHICH A RUN TICKET IS REQUIRED TO BE GENERATED OR THE DATE ON WHICH GAS IS FIRST MEASURED THROUGH PERMANENT METERING FACILITIES, WHICHEVER FIRST OCCURS.
- D. PURSUANT TO NTL-4A, LESSEES OR OPERATORS ARE AUTHORIZED TO VENT/FLARE GAS DURING INITIAL WELL EVALUATION TEST, NOT EXCEEDING A PERIOD OF 30 DAYS OR THE PRODUCTION OF 50 MMCF OF GAS, WHICHEVER OCCURS FIRST. AN APPLICATION MUST BE FILED WITH THE DISTRICT ENGINEER AND APPROVAL RECEIVED, FOR ANY VENTING/FLARING OF GAS BEYOND THE INITIAL 30 DAY OR AUTHORIZED TEST PERIOD.
- E. GAS PRODUCED FROM THIS WELL MAY NOT BE VENTED OR FLARED BEYOND AN INITIAL AUTHORIZED TEST PERIOD OF 30 DAYS OR 50 MMCF FOLLOWING ITS COMPLETION, WHICHEVER OCCURS FIRST, WITHOUT THE PRIOR WRITTEN APPROVAL OF THE AUTHORIZED OFFICER. SHOULD GAS BE VENTED OR FLARED WITHOUT APPROVAL BEYOND THE AUTHORIZED TEST PERIOD, THE OPERATOR MAY BE DIRECTED TO SHUT-IN THE WELL UNTIL THE GAS CAN BE CAPTURED OR THE OPERATOR SHALL BE REQUIRED TO COMPENSATE THE LESSOR FOR THAT PORTION OF THE GAS VENTED OR FLARED WITHOUT APPROVAL WHICH IS DETERMINED TO HAVE BEEN AVOIDABLY LOST.
- F. A SCHEMATIC FACILITIES DIAGRAM AS REQUIRED BY CFR 3162.7-2, 3162.7-3 AND 3162.7-4 SHALL BE SUBMITTED TO THE APPROPRIATE DISTRICT OFFICE WITHIN 30 DAYS OF INSTALLATION OR FIRST PRODUCTION, WHICHEVER OCCURS FIRST. ALL SITE SECURITY REGULATIONS AS SPECIFIED IN 43 CFR 3162.7 AND ONSHORE ORDER NO. 3 SHALL BE ADHERED TO. ALL PRODUCT LINES ENTERING AND LEAVING HYDROCARBON STORAGE TANKS WILL BE EFFECTIVELY SEALED IN ACCORDANCE WITH 43 CFR 3162.7-4.
- G. SECTION 102(B)(3) OF THE FEDERAL OIL AND GAS ROYALTY MANAGEMENT ACT OF 1982, AS IMPLEMENTED BY THE APPLICABLE PROVISIONS OF THE OPERATING REGULATIONS AT TITLE 43 CFR 3162.4-1(C), REQUIRES THAT "NOT LATER THAN THE 5TH BUSINESS DAY AFTER ANY WELL BEGINS PRODUCTION ON WHICH ROYALTY IS DUE ANYWHERE ON A LEASE SITE OR ALLOCATED TO A LEASE SITE, OR RESUMES PRODUCTION IN THE CASE OF A WELL WHICH HAS BEEN OFF PRODUCTION FOR MORE THAN 90 DAYS, THE OPERATOR SHALL NOTIFY THE AUTHORIZED OFFICER BY LETTER OR SUNDRY NOTICE, FORM 3160-5, OR ORALLY TO BE FOLLOWED BY A LETTER OR SUNDRY NOTICE, OF THE DATE ON WHICH SUCH PRODUCTION HAS BEGUN OR RESUMED."
- H. DRILLING WILL COMMENCE AS SOON AS POSSIBLE, UPON APPROVAL OF THIS APPLICATION.
- I. IT IS ANTICIPATED THAT THE DRILLING OF THIS WELL WILL TAKE APPROXIMATELY 8 DAYS.
- J. NO LOCATION WILL BE CONSTRUCTED OR MOVED, NO WELL WILL BE PLUGGED WITHOUT PRIOR APPROVAL OF THE AO. IF OPERATIONS ARE TO BE SUSPENDED, PRIOR APPROVAL OF THE AO WILL BE OBTAINED AND NOTIFICATION GIVEN BEFORE RESUMPTION OF OPERATIONS.

- K. **IMMEDIATE REPORT:** SPILLS, BLOWOUTS, FIRES, LEAKS, ACCIDENTS, OR ANY OTHER UNUSUAL OCCURRENCES SHALL BE PROMPTLY REPORTED IN ACCORDANCE WITH THE REQUIREMENTS OF NTL-3A OR ITS REVISION.
- L. IF A REPLACEMENT RIG IS USED FOR COMPLETION OPERATIONS, ALL CONDITIONS OF THIS APPROVED PLAN ARE APPLICABLE DURING ALL OPERATIONS CONDUCTED WITH THE REPLACEMENT RIG.
- M. PURSUANT TO ONSHORE ORDER NO. 7, WITH THE APPROVAL OF THE DISTRICT ENGINEER, PRODUCED WATER MAY BE TEMPORARILY DISPOSED OF INTO UNLINED PITS FOR A PERIOD OF UP TO 90 DAYS. DURING THE PERIOD SO AUTHORIZED, AN APPLICATION FOR APPROVAL OF THE PERMANENT DISPOSAL METHOD, ALONG WITH THE REQUIRED WATER ANALYSIS AND OTHER INFORMATION, MUST BE SUBMITTED TO THE DISTRICT ENGINEER.
- N. NO WELL ABANDONMENT OPERATIONS WILL BE COMMENCED WITHOUT THE PRIOR APPROVAL OF THE AO. IN THE CASE OF NEWLY DRILLED DRY HOLES OR FAILURES, AND IN EMERGENCY SITUATIONS, ORAL APPROVAL WILL BE OBTAINED FROM THE AO. A "SUBSEQUENT REPORT OF ABANDONMENT" FORM 3160-5, WILL BE FILED WITH THE AO WITHIN 30 DAYS FOLLOWING COMPLETION OF THE WELL FOR ABANDONMENT. THIS REPORT WILL INDICATE WHERE PLUGS WERE PLACED AND THE CURRENT STATUS OF SURFACE RESTORATION. FINAL ABANDONMENT WILL NOT BE APPROVED UNTIL THE SURFACE RECLAMATION WORK REQUIRED BY THE APPROVED APD OR APPROVED ABANDONMENT NOTICE HAS BEEN COMPLETED TO THE SATISFACTION OF THE AO OR HIS REPRESENTATIVE, OR THE APPROPRIATE SURFACE MANAGING AGENCY.

TYPICAL 2000 p.s.i.
BLOWOUT PREVENTER SCHEMATIC
FOR AIR DRILLING



DRILLING CONTROL

MATERIAL LIST*

- A Texaco Wellhead.
- B 2000# W.P. Dual ram type preventer, hydraulic operated with 1" steel, 2000# W.P. control lines (where sub-structure height is adequate, 2 - 2000# W.P. single ram type preventers may be utilized).
- C Rotating head with extended Bore Line (optional fill up outlet).
- 1, 3, 4 2" minimum 2000# W.P. flanged full opening steel gate valve, or Halliburton Lo Torc Plug valve.
- 2 2" minimum 2000# W.P. back pressure valve.
- 5, 6, 9 2" minimum 2000# W.P. flanged full opening steel gate valve, or Halliburton Lo Torc Plug valve.
- 12 2" minimum schedule 80, Grade "B", seamless line pipe.
- 13 2" minimum x 2" minimum 2000# W.P. flanged cross.
- 10, 11 2" minimum 2000# W.P. adjustable choke bodies.
- 14 Cameron Mud Gauge or equivalent (location optional in choke line).
- 15 2" minimum 2000# W.P. flanged or threaded full opening steel gate valve, or Halliburton Lo Torc Plug valve.

*(OR EQUIVALENT)

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 03/04/96

API NO. ASSIGNED: 43-015-30286

WELL NAME: UTAH FEDERAL D 35-14
 OPERATOR: TEXACO E & P INC (N5700)

PROPOSED LOCATION:
 NWNW 35 - T17S - R07E
 SURFACE: 1249-FNL-0360-FWL
 BOTTOM: 1249-FNL-0360-FWL
 EMERY COUNTY
 UNDESIGNATED FIELD ()

INSPECT LOCATION BY: / /		
TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: FED
 LEASE NUMBER: UTU-74823

PROPOSED PRODUCING FORMATION: FRSD

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Federal State Fee
 (Number CO-0058)
- Potash (Y/N)
- Oil shale (Y/N)
- Water permit
 (Number CITY OF ORANGEVILLE)
- RDCC Review (Y/N)
 (Date: _____)


LOCATION AND SITING:

- ___ R649-2-3. Unit: _____
- ___ R649-3-2. General.
- R649-3-3. Exception. *Need exception letter*
- ___ Drilling Unit.
- ___ Board Cause no: _____
- ___ Date: _____

COMMENTS: _____ 380.68 FNL _____
 _____ 109.72 FWL _____

STIPULATIONS: _____

TEXACO EXPL. & PROD.
DEVELOPMENT DRILLING
SEC. 34,35, T17S, R7E &
SEC. 3, T18S, R7E
EMERY COUNTY UAC R649-3-2 & R649-3-3



PREPARED:
DATE: 14-MAR-96



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

July 15, 1996

Texaco Exploration & Production, Inc.
3300 North Butler Avenue
Farmington, New Mexico 87401

Re: Utah Federal D 35-14 Well, 1249' FNL, 360' FWL, NW NW,
Sec. 35, T. 17 S., R. 7 E., Emery County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-015-30286.

Sincerely,

A handwritten signature in black ink, appearing to read "R. J. Firth".

R. J. Firth
Associate Director

lwp

Enclosures

cc: Emery County Assessor
Bureau of Land Management, Moab District Office



Operator: Texaco Exploration & Production, Inc.
Well Name & Number: Utah Federal D 35-14
API Number: 43-015-30286
Lease: UTU-74823
Location: NW NW Sec. 35 T. 17 S. R. 7 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5336.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews at (801)538-5334 or Mike Hebertson at (801)538-5333.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

SUBMIT IN TRIPLICATE

FORM APPROVED

Budget Bureau No. 1004-0136

Expires: December 31, 1991

96 FEB 20

5. Lease Designation and Serial No.
RANGE 22 UTU-74823

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. Type of Work **DRILL** **DEEPEN**
 1b. Type of Well **SINGLE ZONE**
 OIL WELL GAS WELL OTHER COAL-BED METHANE **MULTIPLE ZONE**

6. If Indian, Allottee or Tribe Name
7. If Unit or CA, Agreement Designation

2. Name of Operator **TEXACO EXPLORATION & PRODUCTION, INC.**

8. Well Name and Number
UTAH FEDERAL 'D'

3. Address and Telephone No.
3300 N. Butler Ave., Suite Farmington NM 87401 325-4397

35-14
9. API Well No.

4. Location of Well (Report location clearly and in accordance with any State requirements. *)
At Surface
Unit Letter **D** : **1249** Feet From The **NORTH** Line and **360** Feet From The **WEST** Line
At proposed prod. zone

10. Field and Pool, Exploratory Area
WILDCAT
11. SEC., T., R., M., or BLK. and Survey or Area
Sec. **35**, Township **T17S**, Range **R7E**

14. Distance In Miles and Direction from Nearest Town or Post Office*
APP. 8.5 MI. NORTHWEST OF CASTLE DALE, UT

12. County or Parish **EMERY** 13. State **UT**

15. Distance From Proposed* Location to Nearest Property or Lease Line, Ft. (also to nearest drlg. unit line, if any) **1249'**

16. No. of Acres in Lease **2277.95**

17. No. of Acres Assigned To This Well **160 AC.**

18. Distance From Proposed Location* to Nearest Well, Drilling, Completed or Applied For, On This Lease, Ft. **APP. 3640'**

19. Proposed Depth


20. Rotary or Cable Tools
ROTARY

21. Elevations (Show whether DF, RT, GR, etc.)
 KB DF GR

22. Approx. Date Work Will Start*
5/1/96

23. PROPOSED CASING AND CEMENT PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT



**FLARING OR VENTING OF
GAS IS SUBJECT TO NTL 4-A
Dated 1/1/80**

CONDITIONS OF APPROVAL ATTACHED

In Above Space Describe Proposed Program: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured true verticle depths. Give blowout preventer program, if any.

24. I hereby certify that the foregoing is true and correct

SIGNATURE *Ted A. Tipton* TITLE Operating Unit Manager DATE 2/7/96
 TYPE OR PRINT NAME Ted A. Tipton

(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____
 Application approval does not warrant or certify that the applicant holds legal or equitable title to those lands the subject of this application which would entitle the applicant to conduct operations thereon.
 APPROVED *Brad D. Palmer* Assistant Field Manager DATE JUL 10 1996
 CONDITIONS OF APPROVAL, IF ANY: _____ TITLE Resource Management DATE _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

DC/m



T17S, R7E, S.L.B.&M.

TEXACO EXPLR. & PROD., INC.

Well location, UTAH FEDERAL "D" #35-14, located as shown in the NW 1/4 NW 1/4 of Section 35, T17S, R7E, S.L.B.&M. Emery County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT THE NORTHWEST CORNER OF SECTION 2, T18S, R7E, S.L.B.&M. TAKEN FROM THE RED POINT QUADRANGLE, Utah, EMERY COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 6687 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert L. Key
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (801) 789-1017

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

SCALE 1" = 1000'	DATE SURVEYED: 1-15-96	DATE DRAWN: 1-19-96
PARTY J.T.K. B.B. D.J.S.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE TEXACO EXPLR. & PROD., INC.	

Texaco and Exploration and Production, Inc
Utah Federal 'D' 35-14
Lease U-74823
NW/NW, Section 35, T. 17 S., R. 7 E.
Emery County, Utah

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be advised that Texaco Exploration and Production, Inc is considered to be the operator of the above well and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for this well is provided by CO-0058 (Principal - Texaco Exploration and Production, Inc) via surety consent as provided for in 43 CFR § 3104.2.

This office will hold the aforementioned operator and bond liable until the provisions of 43 CFR § 3106.7-2 continuing responsibility are met.

This permit will be valid for a period of one year from the date of approval. After permit termination, a new application must be filed for approval.

All lease operations will be conducted in full compliance with applicable regulations (43 CFR § 3100), Onshore Oil and Gas Orders, lease terms, notices to lessees, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions and the approved plan will be made available to field representatives to insure compliance.

A. DRILLING PROGRAM

1. The proposed 2M BOP system is adequate. Installation, testing and operation of the system shall be in conformance with Onshore Oil and Gas Order No. 2.
2. The application did not indicate whether a rotating head would be used. As with all air drilling operations, use of a rotating head is mandatory. An auto-ignitor or debuster is required. A bit float is required. These and other air drilling requirements are found in Onshore Oil and Gas Order No. 2, part III,E,1 "Special Drilling Operations." All of the proposed drilling operations must meet or exceed these requirements.
3. Due to the potential for fresh water, the Emery Sandstone must be isolated.
4. Any fluid bearing zones or lost circulation zones encountered while drilling will be isolated behind casing and cement.
5. If a gas meter run is constructed, it will be located on lease within 500 feet of the wellhead. The gas flowline will be buried from the wellhead to the meter and will be buried downstream of the meter until it leaves the pad. Meter runs will be housed and/or fenced. The gas meter shall be calibrated prior to first sales and shall be calibrated quarterly thereafter. All gas production and measurement shall comply with the provisions of 43 CFR § 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.

CONDITIONS OF APPROVAL

1. Thirty (30) days prior to well abandonment, the operator shall contact the authorized officer to arrange a joint inspection of the well pad, access road and other related disturbance. This inspection will be held to agree to an acceptable well abandonment and rehabilitation plan. This plan shall include, but is not limited to, removal of facilities, recontouring, fertilizing, mulching topsoiling and reseeded. The authorized officer must approve the plan in writing prior to the operators commencement of any termination activities.
2. All activities will be limited during periods of crucial winter use (when animals are actually present, generally December 1 to April 15 annually). During this period, no surface-disturbing activity may take place which would remove forage and browse plants used by the mule deer or elk, require a continued human presence (over 12 hours duration) within the area, involve sudden load noises (such as detonation of surface charges, or sustained noise such as chain saw or diesel generator).
3. To minimize habitat loss of crucial and high priority mule deer range, Texaco E&P and the BLM would complete a 45-acre area habitat enhancement within the same herd unit. This area, identified in a prior environmental assessment (Re: EA UT-067-91-13, Grimes Vegetation Treatment, January 1992), is approximately one mile from the area of the proposed action. Procedures outlined within that document would be followed for the proposed enhancement.

C. REQUIRED APPROVALS, REPORTS AND NOTIFICATIONS

Required verbal notifications are summarized in Table 1, enclosed.

Building Location- Contact the BLM Natural Resource Protection Specialist at the Price BLM Field Office at least 48 hours prior to commencing construction of location.

Spud- The spud date will be reported to BLM 24 hours prior to spudding. Written notification in the form of a Sundry Notice (Form 3160-5) will be submitted to the Moab BLM Field Office within 24 hours after spudding, regardless of whether spud was made with a dry hole digger or big rig.

Daily Drilling Reports- Daily drilling reports shall detail the progress and status of the well and shall be submitted to the Moab BLM Field Office on a weekly basis.

Monthly Reports of Operations- In accordance with Onshore Oil and Gas Order No. 1, this well shall be reported on Minerals Management Service (MMS) Form 3160, "Monthly Report of Operations," starting the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with MMS.

Sundry Notices- There will be no deviation from the proposed drilling and/or workover program without prior approval. "Sundry Notices and Reports on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR § 3162.3-2. Safe drilling and operating practices must be observed.

Drilling Suspensions- Operations authorized by this permit shall not be suspended for more than 30 days without prior approval of the Moab BLM Field Office. All conditions of this approval shall be applicable during any operations conducted with a replacement rig.

Undesirable Events- Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be immediately reported to the BLM in accordance with requirements of NTL-3A.

Cultural Resources- If cultural resources are discovered during construction, work that might disturb the resources is to stop, and the BLM is to be notified.

First Production- Should the well be successfully completed for production, the Moab BLM Field Office will be notified when the well is placed in producing status. Such notification may be made by phone, but must be followed by a sundry notice or letter not later than five (5) business days following the date on which the well is placed into production.

A first production conference will be scheduled as soon as the productivity of the well is apparent. This conference should be coordinated through the Price BLM Field Office. The Price BLM Field Office shall be notified prior to the first sale.

Well Completion Report- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted to the Moab BLM Filed Office not later than thirty (30) days after completion of the well or after completion of operations being performed, in accordance with 43 CFR § 3162.4-1. Two copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and

all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. When requested, samples (cuttings and/or samples) will be submitted to the Moab BLM Field Office.

Venting/Flaring of Gas- Gas produced from this well may not be vented/flared beyond an initial, authorized test period of 30 days or 50 MMcf, whichever occurs first, without the prior, written approval of the BLM. Should gas be vented or flared without approval beyond the authorized test period, the well may be ordered shut-in until the gas can be captured or approval to continue the venting/flaring as uneconomic is granted. In such case, compensation to the lessor shall be required for that portion of the gas that is vented/flared without approval and which is determined to have been avoidably lost.

Produced Water- Produced waste water may be confined to an unlined pit for a period not to exceed 90 days after initial production. During the 90 day period, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted to the Moab BLM Field Office for approval pursuant to Onshore Oil and Gas Order No. 7.

Off-Lease Measurement, Storage, Commingling- Prior approval must be obtained from the Moab BLM Field Office for off-lease measurement, off-lease storage and/or commingling (either down-hole or at the surface).

Plugging and Abandonment- If the well is completed as a dry hole, plugging instructions must be obtained from the Moab BLM Field Office prior to initiating plugging operations.

A "Subsequent Report of Abandonment" (Form 3160-5) shall be filed with the Moab BLM Field Office within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR § 3162.6. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the BLM, or the appropriate surface managing agency.

TABLE 1. NOTIFICATIONS

Notify Mike Kaminski of the Price BLM Field Office in Price, Utah, at (801) 636-3640, or at home (801) 637-2518 for the following:

2 days prior to commencement of dirt work, construction and reclamation;

1 day prior to spudding;

50 feet prior to reaching each casing setting depth;

3 hours prior to testing BOPE

If the person at the above number cannot be reached, notify the Moab BLM Field Office at (801) 259-6111. If unsuccessful, contact one of the people listed below.

Well abandonment operations require 24 hour advance notice and prior approval. In the case of newly drilled dry holes, verbal approval can be obtained by calling the Moab Field Office at (801) 259-6111. If approval is needed after work hours, you may contact the following:

Eric Jones, Petroleum Engineer	Office:	(801) 259-2117
	Home:	(801) 259-2214
Gary Torres, Petroleum Engineer	Office:	(801) 587-2141
	Home:	(801) 587-2705

CONFIDENTIAL

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: TEXACO EXPLORATION & PRODUCTION CO.

Well Name: UTAH FEDERAL "D" 35-14

Api No. 43-015-30286

Section 35 Township 17S Range 7E County EMERY

Drilling Contractor NABORS

Rig #: 953

SPUDDED:

Date: 9/21/96

Time: _____

How: ROTARY

Drilling will commence: _____

Reported by: EDDIE WELDAN

Telephone #: 1-801-636-6816

Date: 9/23/96 Signed: JLT

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT --" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well: OIL WELL GAS WELL OTHER COAL-BED METHANE

2. Name of Operator
TEXACO EXPLORATION & PRODUCTION, INC.

3. Address and Telephone No. 3300 N. Butler Ave., Suite Farmington NM 87401 325-4397

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Unit Letter D : 1249 Feet From The NORTH Line and 360 Feet From The
WEST Line Section 35 Township T17S Range R7E

5. Lease Designation and Serial No.
UTU-74823

6. If Indian, Alottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and Number
UTAH FEDERAL 'D'
35-14

9. API Well No.
4301530286

10. Field and Pool, Exploratory Area
WILDCAT

11. County or Parish, State
EMERY, UT

12. Check Appropriate Box(s) To Indicate Nature of Notice, Report, or Other Data

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent <input checked="" type="checkbox"/> Subsequent Report <input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Abandonment <input type="checkbox"/> Recompletion <input type="checkbox"/> Plugging Back <input type="checkbox"/> Casing Repair <input type="checkbox"/> Attlering Casing <input checked="" type="checkbox"/> OTHER: <u>PERF & FRAC</u>
	<input type="checkbox"/> Change of Plans <input type="checkbox"/> New Construction <input type="checkbox"/> Non-Routine Fracturing <input type="checkbox"/> Water Shut-Off <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log Form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)


TEXACO E. & P., INC. HAS COMPLETED THE FOLLOWING ON THE SUBJECT WELL:

11/6/96 - RIG UP SERVICE RIG. RUN GR/CBL/CCL LOG. PBTD 4044'. TOP OF CEMENT 3350'. PERFORATE 3988' - 4004', 3968' - 3971' WITH 4" HEGGS, 4 SPF, 0.60" HOLES. PREP TO FRAC. FRAC WELL (3968' - 4004') WITH 18,000 GAL. GELLED WATER, 90,000 # 20/40 SAND. CLEAN OUT WELL FOR SECOND FRAC.

11/16/96 - PERFORATE 3865' - 3875', 3905' - 3925' WITH 4" HEGGS, 4 JSPF, 0.60" HOLES. FRAC WITH 31,765# 20/40 SAND. CLEAN UP WELL. SWAB LOAD WATER. RUN IN HOLE WITH TUBING.

WAIT ON PIPELINE CONNECTION.

CONFIDENTIAL



14. I hereby certify that the foregoing is true and correct

SIGNATURE Ted A. Tipton TITLE Operating Unit Manager DATE 12/10/96
TYPE OR PRINT NAME Ted A. Tipton

(This space for Federal or State office use)

APPROVED
CONDITIONS OF APPROVAL, IF ANY: _____ TITLE _____ DATE _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0137
Expires: December 31, 1991

SUBMIT ORIGINAL WITH 5 COPIES

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

5. Lease Designation and Serial No.

UTU-74823

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and Number
UTAH FEDERAL 'D'

35-14

9. API Well No.

4301530286

10. Field and Pool, Exploratory Area
WILDCAT

11. SEC., T., R., M., or BLK. and Survey or Area
Sec. 35, Township T17S, Range R7E

1a. Type of Well: OIL GAS DRY OTHER COAL-BED METHANE WELL
1b. Type of Completion: NEW WORK DEEPEN PLUG DIFF. OTHER WELL OVER RESVR.

2. Name of Operator
TEXACO EXPLORATION & PRODUCTION, INC.

3. Address and Telephone No.
3300 N. Butler Ave., Suite 1 Farmington NM 87401 325-4397

4. Location of Well (Report location clearly and in accordance with any State requirements. *)
At Surface
Unit Letter D : 1249 Feet From The NORTH Line and 380 Feet From The WEST Line
At proposed prod. zone

At Total Depth

CONFIDENTIAL

14. Permit No. Date Issued
12. County or Parish EMERY 13. State UT
15. Date Spudded 9/20/96 16. Date T.D. Reached 9/29/96 17. Date Compl. (Ready to Prod.) 11/30/96 18. Elevations (Show whether DF, RT, GR, etc.) 6934 19. Elev. Casinhead

20. Total Depth, MD & TVD 4108 21. Plug Back T.D., MD & TVD 4044' 22. If Multiple Compl., How Many* 23. Intervals Drilled By --> ROTARY Rotary Tools CableTools

24. Producing Interval(s), Of This Completion - Top, Bottom, Name (MD and TVD)*
FERRON 25. Was Directional Survey Made YES

26. Type Electric and Other Logs Run
GR/LDT/CNL, GR/SFL/DIL, HIGH RES. COAL LOG, GR/CBL/CCL 10-21-96
ARRAY INDUCTION/GR 27. Was Well Cored NO

28. CASING RECORD (Report all Strings set in well)

CASING SIZE & GRADE	WEIGHT LB./FT.	DEPTH SET	HOLE SIZE	CEMENT RECORD	AMOUNT PULLED
8-5/8"	24#	338'	12-1/4"	230 SX	
5-1/2"	17#	4107'	7-7/8"	380 SX	

29. LINER RECORD					30. TUBING RECORD		
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	SIZE	DEPTH SET	PACKER SET
					2-7/8"	3869'	

31. Perforation record (interval, size, and number)	32. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.
3865' - 3875' - 4 SPF, 0.60" HOLES	DEPTH INTERVAL AMOUNT AND KIND MATERIAL USED
3905' - 3925'	3868' - 3925' 31,765 # 20/40 SAND
3968' - 3971'	3968' - 4004' 18,000 GAL GEL, 90,000 # 20/40 SAND
3988' - 4004'	

CONFIDENTIAL

RECEIVED
DEC 16 1995
DIV. OF OIL, GAS & MINING
PRODUCTION

33. Date First Production Production Method (Flowing, gas lift, pumping - size and type pump) Well Status (Prod. or Shut-in) SHUT-IN

Date of Test Hours tested Choke Size Prod'n For Test Period Oil - Bbl. Gas - MCF Water - Bbl. Gas - Oil Ratio
Flow Tubing Press. Casing Pressure Calculated 24-Hour Rate Oil - Bbl. Gas - MCF Water - Bbl. Oil Gravity - API -(Corr.)

34. Disposition of Gas (Sold, used for fuel, vented, etc.) Test Witnessed By

35. List of Attachments

36. I hereby certify that the foregoing is true and correct.
SIGNATURE *JAG* TITLE Operating Unit Manager DATE 12/10/96
TYPE OR PRINT NAME Ted A. Tipton

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof, cored intervals; and all drill-stem, tests including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

38. GEOLOGIC MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
				FERRON	3844'	



TEXACO

FAX TRANSMITTAL COVER SHEET

NOTE: DO NOT USE BLUE OR RED INK OR PENCIL ON THIS FORM. THEY WILL NOT REPRODUCE.

DATE: 2/19/97 URGENT ROUTINE NO. OF PAGES C + 1

MESSAGE TO: Lisha Cordova

TELEPHONE NO. _____ FAX MACHINE NO. _____

DEPT./DIV./SUBS. _____

LOCATION _____ ROOM NO. _____

MESSAGE FROM: Tami Denetsu

TELEPHONE NO. 305 325 4397 x10 FAX MACHINE NO. _____

DEPT./DIV./SUBS. _____

LOCATION FARMINGTON OM ROOM NO. _____

SENDING DEPT. APPROVAL _____ TIME TRANSMITTED _____

RETURN ORIGINAL VIA INTER-OFFICE MAIL RETURN ORIGINAL CALL SENDER TO PICK UP

ADDITIONAL COMMENTS:

Call me if there are any questions

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR TEXACO E & P INC.
ADDRESS 3300 N BUTLER
FARMINGTON, NM 87401

OPERATOR ACCT. NO. N 5700

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION				SPUD DATE	EFFECTIVE DATE
					99	SC	TP	RG		
A	99999	12074	4301530282	UTAH FEDERAL D 34-12	SE/SE	34	17S	7E	EMERY	7/29/96
WELL 1 COMMENTS: <i>Entities added 2-19-97. Lec</i>										
A	99999	12075	4301530285	UTAH FEDERAL D 35-13	SW/SW	35	17S	7E	EMERY	7/30/96
WELL 2 COMMENTS:										
A	99999	12076	4301530286	UTAH FEDERAL D 35-14	NW/NW	35	17S	7E	EMERY	9/20/96
WELL 3 COMMENTS:										
A	99999	12077	4301530287	UTAH FEDERAL D 35-15	SW/SE	35	17S	7E	EMERY	8/11/96
WELL 4 COMMENTS:										
WELL 5 COMMENTS:										
WELL 6 COMMENTS:										

- ACTION CODES (See instructions on back of form)**
- A - Establish new entity for new well (single well only)
 - B - Add new well to existing entity (group or unit well)
 - C - Re-assign well from one existing entity to another existing entity
 - D - Re-assign well from one existing entity to a new entity
 - E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

[Signature]
Signature
Admin. Associate III
Title
2/19/97
Date
Phone No. (505) 325-4397

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well: OIL WELL GAS WELL OTHER COAL-BED METHANE

2. Name of Operator
TEXACO EXPLORATION & PRODUCTION, INC.

3. Address and Telephone No.
3300 N. Butler Ave, Ste100 Farmington NM 87401 325-4397

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Unit Letter **D** : **1249** Feet From The **NORTH** Line and **360** Feet From The
WEST Line Section **35** Township **T17S** Range **R7E**

5. Lease Designation and Serial No.
UTU-74823

6. If Indian, Alottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and Number
UTAH FEDERAL 'D'

35-14

9. API Well No.
4301530286

10. Field and Pool, Exploratory Area
WILDCAT

11. County or Parish, State
EMERY , UT

12. **Check Appropriate Box(s) To Indicate Nature of Notice, Report, or Other Data**

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> OTHER: <u>FRACTURE TREAT</u>
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water


(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log Form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

***** THIS SUNDRY REPORT IS FOR UTAH SEVERANCE TAX CALCULATION INFORMATION PURPOSES ONLY *****

TEXACO E. & P., INC. HAS FRACTURE TREATED THE SUBJECT WELL:

- 11/12/98 - 11/13/98 MIRU, TOOH W/ TBG, RODS AND PUMP, SET RBP @ 3949', RDMO
- 11/20/98 SAND FRAC W/ 500 GALS 15% HCL ACID, 114,870# 20/40 SAND
- 11/21/98 - 11/24/98 TAGGED FILL @ 3850, CLEANED OUT - TIH, RETRIEVED RBP, CLEANED OUT TO PBTD 4045', RIH W/ TBG & SEAT NIPPLE
- 11/25/98 RIH W/ RODS AND 2" PUMP, PLACED WELL ON TEST, RDMO
- 12/16/98 FINAL REPORT



14. I hereby certify that the foregoing is true and correct.

SIGNATURE Billy C. Bowen TITLE Eng. Assistant DATE 3/3/99

TYPE OR PRINT NAME Billy C. Bowen

(This space for Federal or State office use)

APPROVED _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY: _____

Well Name: Federal "D" 35-14
 Area/Property Number: 333-69090310
 API #: 4301530286
 Location: NW ¼, NW ¼, Sec. 35, T17S, R7E
 County & State: Emery County, Utah
 Job Number: 48-1051
 Commencement Date: 11/11/1998
 Contractor: Colorado Well Service
 Objective of Workover: refrac the upper coal & sand (3865' - 3925' gross)
 Producing Formation: Ferron Sand/Coal
 Current Perforations: 3865' - 75', 3905' - 25', 3968' - 71', 3988' - 4004'
 Production before workover: 29 mcfpd & 43 bwpd
 Production after workover: 115 mcfpd & 330 bwpd

11/12/98

PO TOOH w/ tbg
 Sum MIRUSU - TOOH laying down rods and pump - NDWH - NUBOP - SWIFN

11/13/98

PO SI - ready & waiting to frac
 Sum tally OOH w/ tbg - TIH w/ Guiberson RBP & tbg - set RBP @ 3949' - TOOH w/ tbg & retrieving head - SWI - RDMOSU

11/19/98

PO preparing to sand frac
 Sum SI - MIRU Dowell

4200	30492
3150	
9828	
15372	114870
21168	
30660	

11/20/98

PO continue TIH w/ tbg
 Sum RU Stinger tree saver - test lines to 6840 psi - treat 3865' - 75' & 3905' - 25' as follows: pump 500 gallons of 15% HCL - displace w/ 102 bbls WF 120, 5 bpm, 842 max psi, 500 avg psi - let acid soak 30 min. - run injection test, 5 bpm 420 psi for 3 min, 10 bpm 640 psi for 3 min, 5 bpm 570 psi for 3 min, 10 bpm 740 psi for 3 min, ISIP 489 psi, 5 min 197 psi, 10 min 27 psi, 12 min 23 psi - pump 215 bbls pad, 100 bbls w/ 1 ppg sand, 120 bbls pad, 75 bbls w/ 1 ppg sand, 117 bbls w/ 2 ppg sand, 122 bbls w/ 3 ppg sand, 126 bbls w/ 4 ppg sand, 146 bbls w/ 5 ppg sand, 121 bbls w/ 6 ppg sand, all stages w/ YF125LG fluid and 20-40 sand - displace w/ 95 bbls WF120 - avg rate 60 bpm, max rate 65.4 bpm, avg pressure 1825 psi, max pressure 1996 psi, ISIP 1551 psi, 5 min. 1208 psi, 10 min. 947 psi, 15 min. 755 psi, 20 min 613 psi, 25 min. 522 psi - SWI - (gell samples from caught during each stage broke with in 1 hr.) - RD tree saver - RD Dowell - MIRUSU - 0 psi on well - start in hole w/ retrieving head & 2 7/8" tbg - SWIFN

11/21/98

PO SI
 Sum continue TIH w/ retrieving head & 2 7/8" tbg - tag fill at 3850' - reverse circ. from 3850' to 3860', hole clean from 3860' to 3875', clean out from 3875' to 3945' - pull up hole to

3890' – RU swab – swab 7 hrs, made 15 runs, IFL 300', FFL 1100', recovered 130 bbls – getting sand back at first but cleaning up by end of day - SWIFN

11/22/98

PO SI

Sum SI

11/23/98

PO preparing to put on production

Sum SI

11/24/98

PO TIH w/ pump and rods

Sum 0 psi – IFL 1100' – made 1 swab run – no sand – RD swab – RIH w/ tbg & tag fill at 3923' (2' over bottom perf) – clean out to 3948' (lost 225 bbls wtr) – release RBP – TOO – TIH w/ notched/pinned collar, 1 jt, SN, and 2 7/8" tbg – tag fill at 4032' – clean out to 4045' (PBTD) – pull up hole to 4012' – ND BOP – NU well head - SWIFN

11/25/98

PO well pumping – 2" pump, 100" SL, 8.1 SPM, pm 12 hrs, 0 mcf, 213 bw, unable to get fluid level

Sum TIH w/ 2" insert pump and rods, picking up rods, & changing out 21 worn rod boxes – hang well on – RDMOSU

11/26/98 pm 24 hrs, 0 mcf, 292 bw.

11/27/98 pm 24 hrs, 0 mcf, 340 bw.

11/28/98 pm 14 hrs, 0 mcf, 190 bw, down 10 hrs Ajax down.

11/29/98 pm 2 hrs, 0 mcf, 20 bw, down 22 hrs Ajax down.

11/30/98 pm 24 hrs, 23 mcf, 276 bw, fluid level 2791' over pump.

12/1/98 pm 24 hrs, 31 mcf, 323 bw.

12/2/98 pm 24 hrs, 40 mcf, 278 bw, fluid level 2634' over pump.

12/3/98 pm 24 hrs, 47 mcf, 284 bw.

12/4/98 pm 24 hrs, 53 mcf, 302 bw.

12/5/98 pm 24 hrs, 65 mcf, 432 bw, increase to 10 SPM.

12/6/98 pm 24 hrs, 77 mcf, 466 bw.

12/7/98 pm 12 hrs, 75 mcf, 189 bw, fluid level 2166' over pump, ajax engine down 12 hrs, weather.

12/8/98 pm 18 hrs, 75 mcf, 295 bw, ajax engine down 6 hrs, repair fuel gas system.

12/9/98 pm 22 hrs, 92 mcf, 418 bw, down 2 hours to change to longest stroke length of 142"

12/10/98 pm 24 hrs, 101 mcf, 540 bw.

12/11/98 pm 24 hrs, 104 mcf, 493 bw, fluid level 1072' over pump. Central Compressor down and line pressure up to 125 psi.

12/12/98 pm 24 hrs, 113 mcf, 483 bw.

12/13/98 pm 24 hrs, 117 mcf, 539 bw.

12/14/98 pm 6 hrs, 102 mcf, 138 bw, down 18 hrs, fuel gas froze.

12/15/98 pm 17 hrs, 110 mcf, 390 bw, engine down 7 hrs, fluid level 229' over pump.

12/16/98 pm 24 hrs, 119 mcf, 332 bw.

FINAL REPORT

Estimate Detail

UTAH FED "D" #35-14 WATER WL

Estimate Number: 481051	Assigned FRS ID: 333000069090310		
Completion Status: 1	Financially Closed: 0000	IDC Closing Date: 0000	
Completion Date: 0000	Drilling Disposition: 00	Total Appropriated: 50750	

Estimate	ID	IDC Type	CAC	Qty	Amount	Vendor	Invoice	Yr	Mo	Reference	Pac	PI Level	Service Type
481051	333000069090310	060	000	0	340.00	NIELSON CONSTRUCTION INC	7832	98	12	1298020551100366	259001	064067	1003
Total IDC Type: 060					340.00	Transportation							
481051	333000069090310	064	000	0	5,901.60	COLORADO WELL SERVICE INC	0800655IN	98	12	1298020552200712	259001	064067	1002
Total IDC Type: 064					5,901.60	Contract Completion Unit							
481051	333000069090310	072	000	0	2,769.21	A 1 SERVICE	256458	98	12	1298020771400456	259001	064067	1003
Total IDC Type: 072					2,769.21	Rental Tools							
481051	333000069090310	075	000	0	1,645.00	DRAGON HOT OIL	4677	98	12	1298020552200730	259001	064067	1003
481051	333000069090310	075	000	0	185.50	NIELSON CONSTRUCTION INC	7976	99	01	0199020550700146	259001	064067	1003
Total IDC Type: 075					1,830.50	Water							
481051	333000069090310	082	000	0	344.50	NIELSON CONSTRUCTION INC	7976	99	01	0199020550700146	259001	064067	1003
Total IDC Type: 082					344.50	Disposal							
481051	333000069090310	000	107	0	3,203.50	COLORADO WELL SERVICE INC	0800610IN	98	12	1298020550900257	258035	064067	0000
481051	333000069090310	000	107	0	944.50	COLORADO WELL SERVICE INC	0800616IN	98	12	1298020550900263	258035	064067	0000
481051	333000069090310	000	107	0	4,074.24	STINGER WELLHEAD PROTECTI	12565	98	12	1298020550900289	258035	064067	0000
481051	333000069090310	000	107	0	800.80	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	537.66	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	238.00	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	308.00	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	85.43	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	49.85	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	144.00	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	4,146.76	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	873.44	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	712.35	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	1,752.00	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	3,455.86	DOWELL A DIV OF SCHLUMBER	9090251471	98	12	1298020551150091	258035	064067	0000

Estimate	ID	IDC Type	CAC	Qty	Amount	Vendor	Invoice	Yr Mo	Reference	Pac	PI Level	Service Type
481051	333000069090310	000	107	0	526.90	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	610.58	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	351.52	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	1,716.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	14,064.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	2,217.60	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	1,440.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	232.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	692.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	448.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	2,896.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	3,552.58	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	272.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	1,080.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	162.12	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	208.00	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	374.40	DOWELL A DIV OF SCHLUMBER	9090251471	98 12	1298020551150091	258035	064067	0000
481051	333000069090310	000	107	0	329.00	NIELSON CONSTRUCTION INC	7832	98 12	1298020551100366	258035	064067	0000
481051	333000069090310	000	107	0	132.50	NIELSON CONSTRUCTION INC	7832	98 12	1298020551100366	258035	064067	0000
481051	333000069090310	000	107	0	185.50	NIELSON CONSTRUCTION INC	7832	98 12	1298020551100366	258035	064067	0000
481051	333000069090310	000	107	0	150.00	NIELSON CONSTRUCTION INC	7832	98 12	1298020551100366	258035	064067	0000
481051	333000069090310	000	107	0	1,035.00	NIELSON CONSTRUCTION INC	7832	98 12	1298020551100366	258035	064067	0000
481051	333000069090310	000	107	0	668.43	WEATHERFORD ENTERRA U S	984500102226	98 12	1298020552850236	258035	064067	0000
481051	333000069090310	000	107	0	668.43	WEATHERFORD ENTERRA U S	984500102226	98 12	1298020552850236	258035	064067	0000
481051	333000069090310	000	107	0	37.14	WEATHERFORD ENTERRA U S	984500102226	98 12	1298020552850236	258035	064067	0000
481051	333000069090310	000	107	0	190.98	WEATHERFORD ENTERRA U S	984500102226	98 12	1298020552850236	258035	064067	0000

Total CAC: 107 0 55,567.07 INSTALLATION COSTS

Total ID: 333000069090310 0 66,752.88

Total Estimate: 481051 0 66,752.88

$Loc\ 340 + 1832 = 2172$
 $Rig\ 5901.6 + 3203.50 + 944.50 = 10049.60$
 $Rental\ 2769.21 + 1544.98 + 4074.24 = 8408.43$
 $Util\ Haul\ 1830.50 + 344.50 = 2175.00$
 $Frac\ 43947.85$

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

		5. LEASE DESIGNATION AND SERIAL NUMBER: See Attached List of Wells
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: BLM & State of Utah
		7. UNIT or CA AGREEMENT NAME: Orangeville & Huntington
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Operator Name Change</u>		8. WELL NAME and NUMBER: See Attached List of Wells
2. NAME OF OPERATOR: Chevron U.S.A. Inc.		9. API NUMBER:
3. ADDRESS OF OPERATOR: P.O. Box 36366 CITY Houston STATE TX ZIP 77236		10. FIELD AND POOL, OR WILDCAT:
PHONE NUMBER: (281) 561-3443		

4. LOCATION OF WELL
FOOTAGES AT SURFACE: See Attached List of Wells COUNTY: Emery
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: <u>Operator Name Change (Merger)</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
Effective May 1, 2002, Chevron U.S.A. Inc. is the new operator of the attached list of subject wells and leases that were previously operated by Texaco Exploration and Production Inc. The subject wells are located North of Orangeville and North of Huntington, Emery County, Utah. These Wells will be protected by the following surety bonds:

STATE OF UTAH Bond #: 103521627-0010 in the amount of \$80,000. (This bond will replace United Pacific Insurance Company bond number U89-75-80-0059. We respectfully request this bond be released and returned.)

BLM Nationwide Bond#: U89-75-81-0034 in the amount of \$300,000.

Key Contacts:
Ron Wirth - Operations Supervisor - 435 748-5395 x1
Texaco Exploration & Production Inc.

J. S. Purdy, Attorney-In-Fact

RECEIVED
MAY 06 2002
DIVISION OF
OIL, GAS AND MINING

NAME (PLEASE PRINT) <u>Allen S. Robinson</u>	TITLE <u>Attorney-In-Fact</u>
SIGNATURE 	DATE <u>April 30, 2002</u>

(This space for State use only)

Chevron U.S.A. Inc.
 Midcontinent Business Unit
 Ferron Operations
 Emery County, Utah

Name / Operatorship Change
 Texaco Exploration and Production Inc.
 to
 Chevron U.S.A. Inc.

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main	Fed or State
N5700	06	170S	080E	4301530292	UTAH FEDERAL M 6-25	1	S	GW	Federal
N5700	34	170S	070E	4301530282	UTAH FEDERAL D 34-12	1	P	GW	Federal
N5700	34	170S	070E	4301530389	USA 34-80	1	P	GW	Federal
N5700	34	170S	070E	4301530390	USA 34-82	1	P	GW	Federal
N5700	35	170S	070E	4301530285	UTAH FEDERAL D 35-13	1	P	GW	Federal
N5700	35	170S	070E	4301530286	UTAH FEDERAL D 35-14	1	P	GW	Federal
N5700	35	170S	070E	4301530287	UTAH FEDERAL D 35-15	1	P	GW	Federal
N5700	03	180S	070E	4301530383	USA 3-74	1	P	GW	Federal
N5700	03	180S	070E	4301530384	USA 3-75	1	P	GW	Federal
N5700	03	180S	070E	4301530448	FEDERAL P 3-92	1	DRL	GW	Federal
N5700	03	180S	070E	4301530449	FEDERAL P 3-93	1	DRL	GW	Federal
N5700	04	180S	070E	4301530280	UTAH FEDERAL Q 4-44	1	P	GW	Federal
N5700	08	180S	070E	4301530274	UTAH FEDERAL S 8-46	1	P	GW	Federal
N5700	10	180S	070E	4301530258	UTAH FEDERAL P 10-47	1	P	GW	Federal
N5700	10	180S	070E	4301530276	UTAH FEDERAL P 10-42	1	P	GW	Federal
N5700	10	180S	070E	4301530277	UTAH FEDERAL P 10-43	1	P	GW	Federal
N5700	11	180S	070E	4301530385	USA 11-70	1	APD	GW	Federal
N5700	11	180S	070E	4301530386	USA 11-71	1	APD	GW	Federal
N5700	11	180S	070E	4301530387	USA 11-72	1	P	GW	Federal
N5700	11	180S	070E	4301530388	USA 11-73	1	APD	GW	Federal
N5700	21	180S	070E	4301530450	FEDERAL T 21-94	1	APD	GW	Federal
N5700	22	180S	070E	4301530451	FEDERAL T 22-69	1	P	GW	Federal
N5700	22	180S	070E	4301530452	FEDERAL T 22-83	1	APD	GW	Federal
N5700	22	180S	070E	4301530453	FEDERAL T 22-91	1	APD	GW	Federal
N5700	23	180S	070E	4301530245	FEDERAL C23-8	1	P	GW	Federal
N5700	23	180S	070E	4301530447	FEDERAL C 23-84	1	APD	GW	Federal
N5700	26	180S	070E	4301530244	FEDERAL A26-2	1	P	GW	Federal
N5700	26	180S	070E	4301530246	FEDERAL A26-4	1	P	GW	Federal
N5700	26	180S	070E	4301530445	FEDERAL A 26-88	1	APD	GW	Federal
N5700	27	180S	070E	4301530440	FEDERAL T 27-85	1	APD	GW	Federal
N5700	27	180S	070E	4301530455	FEDERAL T 27-86	1	APD	GW	Federal
N5700	27	180S	070E	4301530456	FEDERAL T 27-87	1	P	GW	Federal

Not moved by JLT

6/6/03 need to move these

Chevron U.S.A. Inc.
Midcontinent Business Unit
Ferron Operations
Emery County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main	Fed or State
N5700	27	180S	070E	4301530457	FEDERAL T 27-90	1	APD	GW	Federal
N5700	34	180S	070E	4301530249	FEDERAL A34-7	1	P	GW	Federal
N5700	35	180S	070E	4301530247	FEDERAL A35-6	1	P	GW	Federal
N5700	35	180S	070E	4301530248	FEDERAL A35-5	1	P	GW	Federal
N5700	35	180S	070E	4301530446	FEDERAL A 35-89	1	DRL	GW	Federal
N5700	21	190S	070E	4301530243	FEDERAL B21-3	1	S	GW	Federal
N5700	06	200S	070E	4301530294	UTAH FEDERAL H 6-21	1	TA	GW	Federal

6/6/13
[Handwritten signature]

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH
2. CDW
3. FILE

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

05/01/2002

FROM: (Old Operator): TEXACO EXPLORATION & PRODUCTION, INC 11111 S. WILCREST Phone: (281) 561-4991 Account No. N5700	TO: (New Operator): CHEVRON U.S.A., INC. 11111 S. WILCREST HOUSTON, TX 77099 Phone: (281) 561-4991 Account No. N0210
--	---

CA No.

Unit:

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
UP&L FED 01-101	01	170S	070E	4301530511	13546	Federal	GW	P
UT FED KK 01-140	01	170S	070E	4301530507	13553	Federal	GW	P
UT FED KK 01-141	01	170S	070E	4301530559	13587	Federal	GW	P
USA 34-80	34	170S	070E	4301530389	12765	Federal	GW	P
USA 34-82	34	170S	070E	4301530390	12821	Federal	GW	P
UTAH FED D 34-12	34	170S	070E	4301530282	12074	Federal	GW	P
UTAH FED D 35-13	35	170S	070E	4301530285	12075	Federal	GW	P
UTAH FED D 35-14	35	170S	070E	4301530286	12076	Federal	GW	P
UTAH FED D 35-15	35	170S	070E	4301530287	12077	Federal	GW	P
FEDERAL P 3-92	03	180S	070E	4301530448	13209	Federal	GW	P
FEDERAL P 3-93	03	180S	070E	4301530449	13210	Federal	GW	P
USA 3-74	03	180S	070E	4301530383	12823	Federal	GW	P
USA 3-75	03	180S	070E	4301530384	12822	Federal	GW	P
UTAH FED Q 4-44	04	180S	070E	4301530280	12237	Federal	GW	S
UTAH FED S 8-46	08	180S	070E	4301530274	12239	Federal	GW	P
UTAH FED R 9-45	09	180S	070E	4301530275	12236	Federal	GW	P
UTAH FED P 10-42	10	180S	070E	4301530276	12195	Federal	GW	P
UTAH FED P 10-43	10	180S	070E	4301530277	12198	Federal	GW	P
UTAH FED P 10-47	10	180S	070E	4301530258	11843	Federal	GW	P
USA 11-72	11	180S	070E	4301530387	12824	Federal	GW	P
FEDERAL T 22-69	22	180S	070E	4301530451	12818	Federal	GW	P
FEDERAL C23-8	23	180S	070E	4301530245	11979	Federal	GW	P
FEDERAL A26-2	26	180S	070E	4301530244	11706	Federal	GW	P
FEDERAL A26-4	26	180S	070E	4301530246	11980	Federal	GW	P
FEDERAL T 27-87	27	180S	070E	4301530456	12817	Federal	GW	P
FEDERAL A34-7	34	180S	070E	4301530249	11982	Federal	GW	P
FEDERAL A 35-89	35	180S	070E	4301530446	12819	Federal	GW	P
FEDERAL A35-5	35	180S	070E	4301530248	11983	Federal	GW	P
FEDERAL A35-6	35	180S	070E	4301530247	11981	Federal	GW	P
FEDERAL B21-3	21	190S	070E	4301530243	11713	Federal	GW	TA
UTAH FED H 6-21	06	200S	070E	4301530294	12347	Federal	GW	TA
UTAH FED M 6-25	06	170S	080E	4301530292	12345	Federal	GW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 05/06/2002

2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 05/06/2002

3. The new company was checked on the Department of Commerce, Division of Corporations Database on: 07/15/2003

4. Is the new operator registered in the State of Utah: YES Business Number: 564408-0143

5. If **NO**, the operator was contacted on: _____

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: not given

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: n/a

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 07/15/2003

2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 07/15/2003

3. Bond information entered in RBDMS on: n/a

4. Fee wells attached to bond in RBDMS on: n/a

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: n/a

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: ES0022 *United Pacific (NR-5 rating)

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: n/a

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number n/a

2. The **FORMER** operator has requested a release of liability from their bond on: n/a

The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:



Talon Resources, Inc.

Service, Quality and Accuracy

P.O. Box 1230
195 North 100 West
Huntington, Utah 84528
Phone: 435-687-5310

Cell: 435-650-1886
Fax: 435-687-5311
Email: talon@etv.net

January 8, 2003

Mr. Eric Jones
Petroleum Engineer
Bureau of Land Management
82 East Dogwood
Moab, Utah 84532

**RE: Request for approval to utilize Electronic Flow Meters (EFM's);
Sundry Notices for Calibration Reschedule—Texaco E & P, Inc.**

Dear Mr. Jones:

On behalf of Texaco Exploration and Production, Inc. (Texaco), Talon Resources, Inc. respectfully submits this request to utilize Electronic Flow Meters (EFM's) within the Texaco Buzzard Bench and Huntington Canyon Fields comprising all of their operations in Emery County, Utah. Additionally, we have enclosed one original and two copies of the *Sundry Notices and Reports on Wells* for 21 federal wells that we are requesting a calibration reschedule from quarterly to semi-annually.

Thank you very much for your timely consideration of this request and enclosed sundries. Please feel free to contact myself, or Mr. Kern Behling of Texaco at 435-748-5395 if you have any questions or need additional information.

Sincerely,

Don Hamilton
Don Hamilton
Agent for Texaco

cc: Mr. Don Stephens, BLM—Price Field Office
Mrs. Carol Daniels, Division of Oil, Gas and Mining
Mr. Kern Behling, Texaco
Mr. Ian Kephart, Texaco
Texaco Well Files

RECEIVED

JAN 10 2003

DIV. OF OIL, GAS & MINING

FILE COPY

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT-" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

Oil Gas

2. Name of Operator

Texaco Exploration and Production, Inc.

3. Address and Telephone No.

P.O. Box 618, Orangeville, Utah 84537 435-748-5395

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1,249' FNL, 360' FWL
NW/4 NW/4, Section 35, T17S, R7E, SLB&M

5. Lease Designation and Serial No.

UTU-74823

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

N/A

8. Well Name and No.

Utah Federal "D" 35-14

9. API Well No.

43-015-30286

10. Field and Pool, or Exploratory Area

Buzzard Bench

11. County or Parish, State

Emery County, Utah

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Change of Name	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Calibration Reschedule	<input type="checkbox"/> Dispose Water

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Texaco E&P, Inc. requests that the calibration schedule of the Electronic Flow Meter (EFM) for the referenced well that makes less than 100 mcf per day be changed from quarterly to semi-annually.

The EFM is located at the well site and all associated measurement and calibration of the EFM will occur at the well site.

Accepted by the
Utah Division of
Oil, Gas and Mining

Date: 1/17/2003
By: *[Signature]*

Federal Approval Of This
Action Is Necessary

COPY SENT TO OPERATOR
Date: 1-21-03
Initials: CHD

RECEIVED

JAN 10 2003

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed *Don Hamilton* Don Hamilton Title Agent for Texaco E&P, Inc. Date January 8, 2003

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: Various Leases
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: XTO ENERGY INC. N2615		8. WELL NAME and NUMBER: See attached list
3. ADDRESS OF OPERATOR: 2700 Farmington Bldg K, Sul CITY Farmington STATE NM ZIP 87401	PHONE NUMBER: (505) 324-1090	9. API NUMBER: Multiple
4. LOCATION OF WELL FOOTAGES AT SURFACE: COUNTY: Emery QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		10. FIELD AND POOL, OR WILDCAT: Buzzard Bench

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective August 1, 2004, the operator changed from Chevron U.S.A. Inc. to XTO ENERGY INC. for all wells on the attached list.

BLM #579173

State and Fee Bond #104312762

Kenneth W. Jackson

Kenneth W. Jackson Regulatory Specialist ChevronTexaco for Chevron U.S.A. Inc. N0210

NAME (PLEASE PRINT) <u>James L. Death</u>	TITLE <u>Vice President - land</u>
SIGNATURE <u>James L. Death</u>	DATE <u>8/16/04</u>

(This space for State use only)

APPROVED 9/30/2004

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED

SEP 28 2004

DIV. OF OIL, GAS & MINING

API Well Number	Well Name	Well Type	County Name	Qtr/Qtr	Section	TwN-Rng
43-015-30242-00-00	L M LEMMON 10-1	Gas Well	EMERY	SESE	10	17S-8E
43-015-30243-00-00	FEDERAL B21-3	Gas Well	EMERY	NESW	21	19S-7E
43-015-30244-00-00	FEDERAL A26-2	Gas Well	EMERY	SESW	26	18S-7E
43-015-30245-00-00	FEDERAL C23-8	Gas Well	EMERY	NENW	23	18S-7E
43-015-30246-00-00	FEDERAL A26-4	Gas Well	EMERY	SWSE	26	18S-7E
43-015-30247-00-00	FEDERAL A35-6	Gas Well	EMERY	NWNW	35	18S-7E
43-015-30248-00-00	FEDERAL A35-5	Gas Well	EMERY	NWNE	35	18S-7E
43-015-30249-00-00	FEDERAL A34-7	Gas Well	EMERY	NENE	34	18S-7E
43-015-30258-00-00	UTAH FED P 10-47	Gas Well	EMERY	NWNW	10	18S-7E
43-015-30259-00-00	A L JENSEN 27-9	Gas Well	EMERY	SESE	27	21S-6E
43-015-30268-00-00	ST OF UT T 36-10	Gas Well	EMERY	SWNE	36	16S-7E
43-015-30270-00-00	ST OF UT U 2-11	Gas Well	EMERY	NWNW	2	18S-7E
43-015-30272-00-00	SWD 1	Water Disposal Well	EMERY	SWNW	24	18S-7E
43-015-30274-00-00	UTAH FED S 8-46	Gas Well	EMERY	SESW	8	18S-7E
43-015-30275-00-00	UTAH FED R 9-45	Gas Well	EMERY	NWNE	9	18S-7E
43-015-30276-00-00	UTAH FED P 10-42	Gas Well	EMERY	NWNE	10	18S-7E
43-015-30277-00-00	UTAH FED P 10-43	Gas Well	EMERY	NWSE	10	18S-7E
43-015-30280-00-00	UTAH FED Q 4-44	Gas Well	EMERY	SESE	4	18S-7E
43-015-30282-00-00	UTAH FED D 34-12	Gas Well	EMERY	SESE	34	17S-7E
43-015-30285-00-00	UTAH FED D 35-13	Gas Well	EMERY	SWSW	35	17S-7E
43-015-30286-00-00	UTAH FED D 35-14	Gas Well	EMERY	NWNW	35	17S-7E
43-015-30287-00-00	UTAH FED D 35-15	Gas Well	EMERY	SWSE	35	17S-7E
43-015-30292-00-00	UTAH FED M 6-25	Gas Well	EMERY	SENE	6	17S-8E
43-015-30294-00-00	UTAH FED H 6-21	Gas Well	EMERY	SESW	6	20S-7E
43-015-30303-00-00	SWD 3	Water Disposal Well	EMERY	SENE	11	18S-7E
43-015-30306-00-00	ST OF UT U 2-48	Gas Well	EMERY	NWNE	2	18S-7E
43-015-30308-00-00	ST OF UT U 2-50	Gas Well	EMERY	NESW	2	18S-7E
43-015-30309-00-00	ST OF UT U 2-49	Gas Well	EMERY	NWSE	2	18S-7E
43-015-30310-00-00	L & M CURTIS 10-58	Gas Well	EMERY	SWSW	10	18S-7E
43-015-30311-00-00	ST OF UT X 16-66	Gas Well	EMERY	SENE	16	18S-7E
43-015-30312-00-00	ST OF UT X 16-65	Gas Well	EMERY	NWNE	16	18S-7E
43-015-30313-00-00	U P & L 14-53	Gas Well	EMERY	SESE	14	18S-7E
43-015-30314-00-00	U P & L 14-55	Gas Well	EMERY	NWNW	14	18S-7E
43-015-30315-00-00	U P & L 23-51	Gas Well	EMERY	SENE	23	18S-7E
43-015-30316-00-00	U P & L 24-57	Gas Well	EMERY	NWNW	24	18S-7E
43-015-30318-00-00	D & A JONES 15-68	Gas Well	EMERY	NENW	15	18S-7E
43-015-30319-00-00	D&D CURTIS 14-54	Gas Well	EMERY	SENE	14	18S-7E
43-015-30320-00-00	P & K PEACOCK 8-62	Gas Well	EMERY	SWNE	8	18S-7E
43-015-30321-00-00	PEACOCK TRUST 9-60	Gas Well	EMERY	NWSW	9	18S-7E
43-015-30323-00-00	SWD 2	Water Disposal Well	EMERY	NWNW	14	18S-7E
43-015-30324-00-00	R G NORRIS 14-40	Gas Well	EMERY	NESW	14	18S-7E
43-015-30325-00-00	L & M CURTIS 15-67	Gas Well	EMERY	NENE	15	18S-7E
43-015-30326-00-00	PEACOCK TRUST 8-61	Gas Well	EMERY	NESE	8	18S-7E
43-015-30327-00-00	PEACOCK 7-64	Gas Well	EMERY	NENE	7	18S-7E
43-015-30328-00-00	PEACOCK TRUST 8-63	Gas Well	EMERY	SENE	8	18S-7E
43-015-30329-00-00	D & A JONES 9-59	Gas Well	EMERY	SESE	9	18S-7E
43-015-30381-00-00	UTAH STATE 1-76	Gas Well	EMERY	NWNW	1	18S-7E
43-015-30382-00-00	UTAH STATE 36-78	Gas Well	EMERY	SWSW	36	17S-7E
43-015-30383-00-00	USA 3-74	Gas Well	EMERY	SESE	3	18S-7E
43-015-30384-00-00	USA 3-75	Gas Well	EMERY	NENE	3	18S-7E
43-015-30385-00-00	USA 11-70	Gas Well	EMERY	SWSE	11	18S-7E
43-015-30386-00-00	USA 11-71	Gas Well	EMERY	SWNE	11	18S-7E
43-015-30387-00-00	USA 11-72	Gas Well	EMERY	NWNW	11	18S-7E
43-015-30388-00-00	USA 11-73	Gas Well	EMERY	NWSW	11	18S-7E
43-015-30389-00-00	USA 34-80	Gas Well	EMERY	SENE	34	17S-7E
43-015-30390-00-00	USA 34-82	Gas Well	EMERY	SESW	34	17S-7E
43-015-30393-00-00	ST OF UT EE 06-138	Gas Well	EMERY	NENW	6	17S-9E
43-015-30396-00-00	ST OF UT AA 07-106	Gas Well	EMERY	NWNE	7	17S-8E
43-015-30437-00-00	ST OF UT BB 09-119	Gas Well	EMERY	SESW	9	17S-8E
43-015-30438-00-00	ST OF UT CC 10-124	Gas Well	EMERY	SENE	10	17S-8E
43-015-30439-00-00	ST OF UT DD 31-98	Gas Well	EMERY	NWSW	31	17S-8E
43-015-30440-00-00	FEDERAL T 27-85	Gas Well	EMERY	SENE	27	18S-7E
43-015-30441-00-00	UP&L 06-102	Gas Well	EMERY	NENW	6	17S-8E
43-015-30442-00-00	UP&L 06-104	Gas Well	EMERY	NESE	6	17S-8E
43-015-30443-00-00	WM S IVIE ET AL 09-118	Gas Well	EMERY	SWNE	9	17S-8E

API Well Number	Well Name	Well Type	County Name	Qtr/Qtr	Section	Twn-Rng
43-015-30444-00-00	ST OF UT BB 09-120	Gas Well	EMERY	NESE	9	17S-8E
43-015-30445-00-00	FEDERAL A 26-88	Gas Well	EMERY	SWNW	26	18S-7E
43-015-30446-00-00	FEDERAL A 35-89	Gas Well	EMERY	NWSW	35	18S-7E
43-015-30447-00-00	FEDERAL C 23-84	Gas Well	EMERY	NESW	23	18S-7E
43-015-30448-00-00	FEDERAL P 3-92	Gas Well	EMERY	SESW	3	18S-7E
43-015-30449-00-00	FEDERAL P 3-93	Gas Well	EMERY	SWNW	3	18S-7E
43-015-30450-00-00	FEDERAL T 21-94	Gas Well	EMERY	NENE	21	18S-7E
43-015-30451-00-00	FEDERAL T 22-69	Gas Well	EMERY	NENE	22	18S-7E
43-015-30452-00-00	FEDERAL T 22-83	Gas Well	EMERY	SWSE	22	18S-7E
43-015-30453-00-00	FEDERAL T 22-91	Gas Well	EMERY	NENW	22	18S-7E
43-015-30454-00-00	ST OF UT CC 10-123	Gas Well	EMERY	NWNW	10	17S-8E
43-015-30455-00-00	FEDERAL T 27-86	Gas Well	EMERY	SENE	27	18S-7E
43-015-30456-00-00	FEDERAL T 27-87	Gas Well	EMERY	SESE	27	18S-7E
43-015-30457-00-00	FEDERAL T 27-90	Gas Well	EMERY	NWSW	27	18S-7E
43-015-30458-00-00	ST OF UT FF 10-125	Gas Well	EMERY	NESW	10	17S-8E
43-015-30459-00-00	ST OF UT FF 11-129	Gas Well	EMERY	NWNW	11	17S-8E
43-015-30462-00-00	ST OF UT FF 11-130	Gas Well	EMERY	NWSW	11	17S-8E
43-015-30478-00-00	GARDNER TRUST ET AL 16-121	Gas Well	EMERY	NENE	16	17S-8E
43-015-30479-00-00	ST OF UT BB 05-107	Gas Well	EMERY	SENE	5	17S-8E
43-015-30480-00-00	ST OF UT BB 05-108	Gas Well	EMERY	NWSW	5	17S-8E
43-015-30481-00-00	ST OF UT BB 05-109	Gas Well	EMERY	SENE	5	17S-8E
43-015-30482-00-00	ST OF UT BB 05-110	Gas Well	EMERY	SWSE	5	17S-8E
43-015-30483-00-00	UP&L 06-103	Gas Well	EMERY	NESW	6	17S-8E
43-015-30484-00-00	AMERICA WEST GROUP ET AL 15-126	Gas Well	EMERY	NENW	15	17S-8E
43-015-30485-00-00	W H LEONARD ET AL 15-127	Gas Well	EMERY	NENE	15	17S-8E
43-015-30486-00-00	ROWLEY 08-111	Gas Well	EMERY	SENE	8	17S-8E
43-015-30490-00-00	SWD 4	Water Disposal Well	EMERY	SENE	15	17S-8E
43-015-30495-00-00	SEELEY 08-112	Gas Well	EMERY	NENE	8	17S-8E
43-015-30496-00-00	ST OF UT BB 08-113	Gas Well	EMERY	NWSE	8	17S-8E
43-015-30497-00-00	ST OF UT AA 07-105	Gas Well	EMERY	SWNW	7	17S-8E
43-015-30498-00-00	ST OF UT 01-97	Gas Well	EMERY	SENE	1	18S-7E
43-015-30499-00-00	ST OF UT GG 03-122	Gas Well	EMERY	SWSW	3	17S-8E
43-015-30500-00-00	ST OF UT HH 03-133	Gas Well	EMERY	SWSE	3	17S-8E
43-015-30501-00-00	SEELEY FARMS 09-117	Gas Well	EMERY	NWNW	9	17S-8E
43-015-30502-00-00	ST OF UT GG 15-128	Gas Well	EMERY	NWSW	15	17S-8E
43-015-30503-00-00	ST OF UT BB 04-116	Gas Well	EMERY	SWSE	4	17S-8E
43-015-30504-00-00	ST OF UT GG 04-115	Gas Well	EMERY	NESW	4	17S-8E
43-015-30505-00-00	BURNSIDE 14-132	Gas Well	EMERY	NWNE	14	17S-8E
43-015-30506-00-00	ST OF UT T 36-100	Gas Well	EMERY	NESE	36	16S-7E
43-015-30507-00-00	UT FED KK 01-140	Gas Well	EMERY	SENE	1	17S-7E
43-015-30508-00-00	ST OF UT II 36-96	Gas Well	EMERY	NWSE	36	17S-7E
43-015-30509-00-00	ST OF UT II 36-95	Gas Well	EMERY	NWNE	36	17S-7E
43-015-30510-00-00	SWD 5	Water Disposal Well	EMERY	SESE	23	17S-8E
43-015-30511-00-00	UP&L FED 01-101	Gas Well	EMERY	SENE	1	17S-7E
43-015-30520-00-00	ST OF UT SS 22-165	Gas Well	EMERY	NENE	22	17S-8E
43-015-30521-00-00	ZIONS FED 35-135R (RIG SKID)	Gas Well	EMERY	NESW	35	16S-7E
43-015-30528-00-00	ST OF UT 14-170	Gas Well	EMERY	SWSE	14	17S-8E
43-015-30529-00-00	CONOVER 14-171	Gas Well	EMERY	NWSW	14	17S-8E
43-015-30530-00-00	ST OF UT 36-139	Gas Well	EMERY	NWSW	36	16S-7E
43-015-30533-00-00	ST OF UT FO 02-186	Gas Well	EMERY	NENW	2	17S-8E
43-015-30549-00-00	ST OF UT JJ 03-160	Gas Well	EMERY	NWNW	3	17S-8E
43-015-30550-00-00	ST OF UT 36-138	Gas Well	EMERY	SWNW	36	16S-7E
43-015-30551-00-00	UT FED P 12-153	Gas Well	EMERY	NWNW	12	18S-7E
43-015-30552-00-00	ST OF UT CC 03-161	Gas Well	EMERY	SENE	3	17S-8E
43-015-30553-00-00	ST OF UT FO 02-188	Gas Well	EMERY	NWSW	2	17S-8E
43-015-30554-00-00	ST OF UT BB 04-158	Gas Well	EMERY	NENW	4	17S-8E
43-015-30555-00-00	ST OF UT BB 04-159	Gas Well	EMERY	SWNE	4	17S-8E
43-015-30556-00-00	MALONE 14-131	Gas Well	EMERY	SWNW	14	17S-8E
43-015-30559-00-00	UT FED KK 01-141	Gas Well	EMERY	SESE	1	17S-7E
43-015-30560-00-00	ST OF UT FO 02-189	Gas Well	EMERY	SWNE	2	17S-8E
43-015-30561-00-00	ST OF UT GG 15-184	Gas Well	EMERY	NWSE	15	17S-8E
43-015-30562-00-00	STATE OF UTAH "LL" 31-20	Gas Well	EMERY	NWNW	31	17S-8E
43-015-30566-00-00	ST OF UT "KK" 32-145	Gas Well	EMERY	NESE	32	16S-8E
43-015-30567-00-00	ST OF UT "KK" 32-144	Gas Well	EMERY	SWSW	32	16S-8E
43-015-30568-00-00	ST OF UT "AA" 18-153	Gas Well	EMERY	SESW	18	17S-8E

API Well Number	Well Name	Well Type	County Name	Qtr/Qtr	Section	TwN-Rng
43-015-30569-00-00	ST OF UT "AA" 07-146	Gas Well	EMERY	NESW	7	17S-8E
43-015-30570-00-00	ST OF UT "AA" 18-154	Gas Well	EMERY	NESE	18	17S-8E
43-015-30571-00-00	ST OF UT "AA" 17-156	Gas Well	EMERY	SWSE	17	17S-8E
43-015-30572-00-00	ST OF UT "AA" 18-149	Gas Well	EMERY	SESW	18	17S-8E
43-015-30573-00-00	ST OF UT "MM" 20-192	Gas Well	EMERY	SESW	20	17S-8E
43-015-30574-00-00	ST OF UT "MM" 20-193	Gas Well	EMERY	NENE	20	17S-8E
43-015-30575-00-00	ST OF UT MM 20-194	Gas Well	EMERY	NWSW	20	17S-8E
43-015-30576-00-00	ST OF UT AA 07-147	Gas Well	EMERY	SESE	7	17S-8E
43-015-30577-00-00	ST OF UT BB 08-148	Gas Well	EMERY	NWSW	8	17S-8E
43-015-30578-00-00	ST OF UT AA 18-150	Gas Well	EMERY	NWNE	18	17S-8E
43-015-30579-00-00	ST OF UT NN 19-157	Gas Well	EMERY	NENE	19	17S-8E
43-015-30580-00-00	ST OF UT AA 17-152	Gas Well	EMERY	NENE	17	17S-8E
43-015-30581-00-00	ST OF UT OO 16-190	Gas Well	EMERY	NESW	16	17S-8E
43-015-30582-00-00	ST OF UT PP 16-191	Gas Well	EMERY	NESE	16	17S-8E
43-015-30583-00-00	ST OF UT AA 17-151	Gas Well	EMERY	NENW	17	17S-8E
43-015-30585-00-00	ST OF UT MM 21-195	Gas Well	EMERY	NENW	21	17S-8E
43-015-30586-00-00	ST OF UT GG 21-163	Gas Well	EMERY	NENE	21	17S-8E
43-015-30587-00-00	ZIONS FED 35-137	Gas Well	EMERY	NESE	35	16S-7E
43-015-30589-00-00	UTAH FED 01-205D	Gas Well	EMERY	SESW	1	17S-7E
43-015-30590-00-00	ZIONS FED 02-134	Gas Well	EMERY	NWNW	2	17S-7E
43-015-30591-00-00	UTAH FED 12-197	Gas Well	EMERY	SENE	12	17S-7E
43-015-30592-00-00	ST OF UT QQ 31-201	Gas Well	EMERY	SESW	31	16S-8E
43-015-30593-00-00	ST OF UT AA 17-155	Gas Well	EMERY	SWSW	17	17S-8E
43-015-30601-00-00	UTAH FED 12-199	Gas Well	EMERY	NESE	12	17S-7E
43-015-30602-00-00	UTAH FED 35-196	Gas Well	EMERY	NENW	35	16S-7E
43-015-30603-00-00	UTAH FED 35-136	Gas Well	EMERY	SWNE	35	16S-7E
43-015-30604-00-00	UT FED 12-200D	Gas Well	EMERY	NESE	12	17S-7E
43-015-30605-00-00	UT FED 12-198D	Gas Well	EMERY	SENE	12	17S-7E
43-015-30606-00-00	ST OF UT QQ 31-204D	Gas Well	EMERY	SESW	31	16S-8E
43-015-30607-00-00	ST OF UT QQ 31-203D	Gas Well	EMERY	SESW	31	16S-8E
43-015-30608-00-00	ST OF UT QQ 31-202D	Gas Well	EMERY	SESW	31	16S-8E
43-015-30609-00-00	ST OF UT HH 23-166	Gas Well	EMERY	NENW	23	17S-8E

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH
2. CDW
3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **8/1/2004**

FROM: (Old Operator): N0210-Chevron USA, Inc 11111 S Wilcrest Houston, TX 77099 Phone: 1-(281) 561-4991	TO: (New Operator): N2615-XTO Energy Inc 2700 Farmington Ave, Bldg K Suite 1 Farmington, NM 87401 Phone: 1-(505) 324-1090
--	--

CA No. Unit:

WELL(S)								
NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
UTAH FED D 34-12	34	170S	070E	4301530282	12074	Federal	GW	P
UTAH FED D 35-13	35	170S	070E	4301530285	12075	Federal	GW	P
UTAH FED D 35-14	35	170S	070E	4301530286	12076	Federal	GW	P
UTAH FED D 35-15	35	170S	070E	4301530287	12077	Federal	GW	P
UTAH FED M 6-25	06	170S	080E	4301530292	12345	Federal	GW	P
USA 3-74	03	180S	070E	4301530383	12823	Federal	GW	P
UTAH FED Q 4-44	04	180S	070E	4301530280	12237	Federal	GW	P
UTAH FED S 8-46	08	180S	070E	4301530274	12239	Federal	GW	P
UTAH FED R 9-45	09	180S	070E	4301530275	12236	Federal	GW	P
UTAH FED P 10-47	10	180S	070E	4301530258	11843	Federal	GW	P
UTAH FED P 10-42	10	180S	070E	4301530276	12195	Federal	GW	P
UTAH FED P 10-43	10	180S	070E	4301530277	12198	Federal	GW	P
FEDERAL C23-8	23	180S	070E	4301530245	11979	Federal	GW	P
FEDERAL A26-2	26	180S	070E	4301530244	11706	Federal	GW	P
FEDERAL A26-4	26	180S	070E	4301530246	11980	Federal	GW	P
FEDERAL A34-7	34	180S	070E	4301530249	11982	Federal	GW	P
FEDERAL A35-6	35	180S	070E	4301530247	11981	Federal	GW	P
FEDERAL A35-5	35	180S	070E	4301530248	11983	Federal	GW	P
FEDERAL B21-3	21	190S	070E	4301530243	11713	Federal	GW	TA
UTAH FED H 6-21	06	200S	070E	4301530294	12347	Federal	GW	TA

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/28/2004
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/28/2004
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 7/19/2004
- Is the new operator registered in the State of Utah: YES Business Number: 5655506-0143
- If **NO**, the operator was contacted on: _____
- 6a. (R649-9-2) Waste Management Plan has been received on: to follow
- 6b. Inspections of LA PA state/fee well sites complete on: being worked

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM not yet BIA n/a

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 9/28/2004

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 9/30/2004
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 9/30/2004
3. Bond information entered in RBDMS on: 9/30/2004
4. Fee/State wells attached to bond in RBDMS on: 9/30/2004
5. Injection Projects to new operator in RBDMS on: 9/30/2004
6. Receipt of Acceptance of Drilling Procedures for APD/New on: 9/28/2004

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 579173

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: n/a

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number 104312762

2. The FORMER operator has requested a release of liability from their bond on: n/a

The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 10/5/2004

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU-74823
2. Name of Operator XTO ENERGY INC.		6. If Indian, Allottee or Tribe Name
3a. Address 2700 Farmington Ave. Bldg K, Suite 1 Farmington, NM 87401	3b. Phone No. (include area code) (505) 324-1090	7. If Unit or CA/Agreement, Name and/or No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)		8. Well Name and No. All Wells on Lease
		9. API Well No. Multiple
		10. Field and Pool, or Exploratory Area Buzzard's Bench
		11. County or Parish, State Emery, Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Operator Change</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Effective August 1, 2004, the operator for lease # UTU 74823 changed from Chevron U.S.A. Inc. to XTO ENERGY INC.

XTO ENERGY's Nationwide Bond is 679473.

UTB000138 (Surety ID: 104312750)

RECEIVED
MOAB FIELD OFFICE
2004 SEP 29 P 3:02
DEPT OF THE INTERIOR
BUREAU OF LAND MGMT

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) <u>Edwin S. Ryan, Jr.</u>	Title <u>S.R. VP-Land</u>
Signature <u>Edwin S. Ryan, Jr.</u>	Date <u>9/27/04</u>

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by <u>ACCEPTED</u>	Title <u>Division of Resources</u>	Date <u>SEP 29 2004</u>
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office <u>Moab Field Office</u>	

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

cc: udogm

Conditions Attached

RECEIVED
OCT 27 2004

API Well Number	Well Name	Well Type	Well Status	County Name	Lease No.	Qtr/Qtr	Section	Location (Twn-Rng)
43-015-30282-00-00	UTAH FED D 34-12 ✓	Gas Well	Producing	EMERY	UTU74823	SESE	34	17S-7E
43-015-30285-00-00	UTAH FED D 35-13 ✓	Gas Well	Producing	EMERY	UTU74823	SWSW	35	17S-7E
43-015-30286-00-00	UTAH FED D 35-14 ✓	Gas Well	Producing	EMERY	UTU74823	NWNW	35	17S-7E
43-015-30287-00-00	UTAH FED D 35-15 ✓	Gas Well	Producing	EMERY	UTU74823	SWSE	35	17S-7E
43-015-30389-00-00	USA 34-80 ✓	Gas Well	Producing	EMERY	UTU74823	SENE	34	17S-7E
43-015-30390-00-00	USA 34-82 ✓	Gas Well	Shut-In	EMERY	UTU74823	SESW	34	17S-7E

XTO Energy Inc.
Well Nos. D 34-12, D 35-13, D 35-14,
D 35-15, USA 34-80 and USA 34-82
Sections 34 and 35, T. 18 S., R. 7 E.
Lease UTU74823
Emery County, Utah

CONDITIONS OF ACCEPTANCE

Acceptance of these applications does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be advised that XTO Energy Inc. is considered to be the operator of the above wells effective August 1, 2004, and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for these well is provided by UTB000138 (Principal – XTO Energy Inc.) via surety consent as provided for in 43 CFR 3104.2.

This office will hold the aforementioned operator and bond liable until the provisions of 43CFR 3106.7-2 continuing responsibility are met.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

4301530286 FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER UTU-73965
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR: 2700 Farmington, Bldg K-1 CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME
4. LOCATION OF WELL FOOTAGES AT SURFACE: 660' FSK & 792' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN SESE 10 17S 08E		8. WELL NAME and NUMBER: LM LEMMON #10-01
PHONE NUMBER: (505) 324-1090		9. API NUMBER: Various (see attached)
		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE
		COUNTY: EMERY
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start 1/1/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input checked="" type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. acquired wells from Chevron/Texaco on August 1, 2004. Chevron/Texaco failed to file a Notice of Intent to surface commingle these wells and XTO Energy Inc. was unaware until recently that nothing had been filed. We are including with this application for surace commingle a list of the wells in Emery County and a spreadsheet showing production figures for these wells. Each well has its own meter then runs through a central delivery point where allocations are made.

XTO Energy Inc. is requesting approval for the commingle of these wells as well as off-lease measurement. As wells are drilled, additional sundries will be submitted to add to our surface commingle.

COPY SENT TO OPERATOR
Date: 6-12-07
Initials: DM

NAME (PLEASE PRINT) HOLLY C. PERKINS	TITLE REGULATORY COMPLIANCE TECH
SIGNATURE <i>Holly C. Perkins</i>	DATE 5/15/2007

This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 5/11/07
BY: *[Signature]*

Federal Approval Of This
Action Is Necessary

RECEIVED
MAY 18 2007

DIV. OF OIL, GAS & MINING

Utah Wells Surface Commingled at Huntington CDP

Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-113	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

Utah Wells Surface Commingled at Huntington CDP

State of Utah FO 02-186	43-015-30533	Producing	State
State of Utah FO 02-188	43-015-30553	Producing	State
State of Utah GG 03-122	43-015-30499	Producing	State
State of Utah GG 04-115	43-015-30504	Producing	State
State of Utah HH 03-133	43-015-30500	Producing	State
State of Utah II 36-95	43-015-30509	Producing	State
State of Utah II 36-96	43-01530508	Shut In	State
State of Utah KK 32-144	43-015-30567	Producing	State
State of Utah QQ 31-201	43-015-30592	Producing	State
State of Utah SS 22-165	43-015-30520	Producing	State
State of Utah T 36-10	43-015-30268	Producing	State
State of Utah T 36-100	43-015-30506	Producing	State
UP&L 06-102	43-015-30441	Producing	State
UP&L 06-103	43-015-30483	Producing	State
UP&L 06-104	43-015-30442	Producing	State
UP&L Federal 01-101	43-015-30511	Producing	Federal
Utah Federal 01-205D	43-015-30589	Producing	Federal
* Utah Federal 16-7-35-21	43-015-30602	Producing	Federal
* Utah Federal 16-7-35-32	43-015-30603	Producing	Federal
* Utah Federal 17-7-12-22D	43-015-30605	Producing	Federal
* Utah Federal 17-7-12-24D	43-015-30604	Producing	Federal
* Utah Federal 17-7-12-42	43-015-30591	Producing	Federal
* Utah Federal 17-7-12-43	43-015-30601	Producing	Federal
Utah Federal 17-7-3-41D	43-015-30697	Producing	Federal
Utah Federal KK 01-140	43-015-30507	Producing	Federal
Utah Federal KK 01-141	43-015-30559	Producing	Federal
Utah Federal M 06-25	43-015-30292	Producing	Federal
WH Leonard 15-127	43-015-30485	Producing	State
Wm S Ivie 09-118	43-015-30443	Producing	State
Zion's Federal 35-135R	43-015-30521	Producing	Federal
* Zion's Federal 17-7-2-11	43-015-30590	Producing	Federal
Zion's Federal 35-137	43-015-30587	Producing	Federal

Utah Wells Surface Commingled at Orangeville CDP

Well Name	API #	Status	Lease	Notes
Curtis D&D 14-54	43-015-30319	Shut In	Federal	
Curtis L&M 10-58	43-015-30310	Shut In	Federal	
Curtis L&M 15-67	43-015-30325	Producing	Federal	
Federal A 18-7-26-12	43-015-30445	Producing	Federal	
Federal A 26-02	43-015-30244	Shut In	Federal	
Federal A 26-04	43-015-30246	Shut In	Federal	
Federal A 34-07	43-015-30249	Producing	Federal	
Federal A 35-05	43-015-30248	Producing	Federal	
Federal A 35-06	43-015-30247	Producing	Federal	
Federal A 35-89	43-015-30446	Producing	Federal	
Federal B 21-03	43-015-30243	Shut In	Federal	
Federal C 18-7-23-23R	43-015-30629	Producing	Federal	
Federal C 23-08	43-015-30245	Producing	Federal	
Federal P 03-92	43-015-30448	Producing	Federal	
Federal P 03-93	43-015-30449	Producing	Federal	
Federal T 18-07-22-34	43-015-30452	Producing	Federal	
Federal T 22-69	43-015-30451	Producing	Federal	
Federal T 27-87	43-015-30456	P&A	Federal	
Ferron St 4-36-18-7	43-015-30253	Producing	Federal	Operator: Merrion Oil & Gas
Jensen AL 27-09	43-015-30259	Shut In	State	
Jones D&A 09-59	43-015-30329	Producing	Federal	
Jones D&A 15-68	43-015-30318	Shut In	State	
Klinkhammer 1	43-015-30610	Shut In	Federal	Operator: Merrion Oil & Gas
Norris RG 14-40	43-015-30324	Producing	Federal	
Peacock 07-64	43-015-30327	Producing	Federal	
Peacock P&K 08-62	43-015-30320	Producing	Federal	
Peacock Trust 08-61	43-015-30326	Producing	Federal	
Peacock Trust 08-63	43-015-30328	Producing	Federal	
Peacock Trust 09-60	43-015-30321	Producing	Federal	
State of Utah 01-97	43-015-30498	Producing	State	
State of Utah 17-7-36-33R	43-015-30687	Producing	State	
State of Utah 17-8-19-11D	43-015-30695	P&A	State	
State of Utah 18-7-2-33R	43-015-30674	Producing	State	
State of Utah DD 31-98	43-015-30439	Producing	State	
State of Utah II 36-95	43-015-30509	Producing	State	
State of Utah II 36-96	43-015-30508	P&A	State	
State of Utah U 02-11	43-015-30270	Producing	State	
State of Utah U 02-48	43-015-30306	Producing	State	
State of Utah U 02-49	43-015-30309	P&A	State	
State of Utah U 02-50	43-015-30308	Producing	State	
State of Utah X 16-65	43-015-30312	Shut In	State	
State of Utah X 16-66	43-015-30311	Producing	State	
UP&L 14-53	43-015-30313	Producing	State	
UP&L 14-55	43-015-30314	Producing	Federal	
UP&L 23-51	43-015-30315	Producing	Federal	
UP&L 24-57	43-015-30316	Producing	State	
USA 03-74	43-015-30383	Producing	Federal	

Utah Wells Surface Commingled at Orangeville CDP

USA 03-75	43-015-30384	Producing	Federal
USA 11-72	43-015-30387	Producing	Federal
USA 18-7-11-23	43-015-30640	Producing	State
USA 34-80	43-015-30389	Shut In	Federal
USA 34-82	43-015-30390	Producing	Federal
Utah Federal 17-7-35-42	43-015-30641	Drilling	Federal
Utah Federal 18-7-27-44R	43-015-30628	Producing	Federal
Utah Federal 18-7-9-11	43-015-30639	Producing	Federal
Utah Federal D 34-12	43-015-30282	Producing	Federal
Utah Federal D 35-13	43-015-30285	Producing	Federal
Utah Federal D 35-14	43-015-30286	Producing	Federal
Utah Federal D 35-15	43-015-30287	Producing	Federal
Utah Federal H 06-21	43-015-30294	TA	Federal
Utah Federal P 10-42	43-015-30276	Producing	Federal
Utah Federal P 10-43	43-015-30277	Producing	Federal
Utah Federal P 10-47	43-015-30258	Producing	Federal
Utah Federal Q 04-44	43-015-30280	Producing	Federal
Utah Federal R 09-45	43-015-30275	Producing	Federal
Utah Federal S 08-46	43-015-30274	Producing	Federal
Utah State 01-76	43-015-30381	Producing	State
Utah State 36-78	43-015-30382	Producing	State

Apr-05

gton Wells

WELL No.	Days On	MONTHLY WATER PRODUCTION	FIELD ESTIMATED PRODUCTION										ACTUAL ALLOCATED SALES					FIELD PRODUCTION			
			Coastal Statement	PROD %	FIELD EST PROD	Gas	Lse Use Gas	Vented CO2	Vented GAS	VENIED GAS	ADJ	FIELD ESTIMATED SALES	ALLOCATED SALES	Lse Use Gas	Vented CO2	Vented GAS	VENIED GAS		ADJ		
10-01	30	455	1478	0.00488716	1479	45	36	98	1708	1708	179	1298	1248	91	98	98	179	1425			
T38-10	30	2667	19292	0.00048442	18298	45	447	1708	1708	2200	16095	15424	492	1708	1708	2200	17624				
MOB-25	30	723	19969	0.005610978	16975	45	414	2280	2280	2739	14236	14308	459	2280	2280	2739	17047				
HO6-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
07-106	30	579	5052	0.01673803	5064	45	124	789	789	958	4106	4268	169	789	789	958	5226				
09-119	30	85	7251	0.0024009	726	45	18	108	108	171	555	612	53	108	108	171	783				
10-124	30	129	9511	0.00314458	9511	45	23	38	38	106	845	902	68	38	38	106	908				
06-102	30	823	20112	0.00650244	20119	45	491	2219	2219	2755	17354	19959	536	2219	2219	2755	19714				
06-104	30	809	12922	0.04272795	12925	45	318	2156	2156	2516	10410	10895	350	2156	2156	2516	13412				
09-118	30	163	757	0.00263536	797	45	19	100	100	164	633	672	64	100	100	164	835				
09-120	30	214	899	0.00297264	899	45	22	80	80	147	752	758	67	80	80	147	905				
18-7-23-23	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
17-8-15-33	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
10-123	30	26	1348	0.0044573	1343	45	33	32	32	167	1182	1137	78	32	32	167	1304				
10-125	30	286	536	0.00177234	536	45	13	32	32	90	446	452	58	32	32	90	542				
11-129	29	0	396	0.00130942	395	44	10	16	16	59	327	334	53	16	16	59	403				
11-130	30	1847	152	0.00053557	162	45	4	7	7	56	106	137	49	7	7	56	193				
16-121	30	276	757	0.0025031	757	45	18	42	42	109	552	638	63	42	42	109	743				
05-107	29	242	8230	0.02721336	8233	44	201	1397	1397	1641	6591	6940	244	1397	1397	1641	8581				
05-108	30	611	4934	0.01631479	4936	45	120	830	830	955	3940	4160	165	830	830	955	5155				
05-109	30	113	1252	0.00413987	1252	45	31	133	133	209	1044	1056	76	133	133	209	1285				
05-110	30	31	1462	0.00483426	1463	45	36	194	194	275	1188	1233	81	194	194	275	1508				
05-103	30	946	9133	0.03019922	9136	45	223	1241	1241	1509	7627	7701	268	1241	1241	1509	9210				
15-125	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
15-127	30	1462	3530	0.01167232	3531	45	86	226	226	357	3174	2977	131	226	226	357	3334				
08-111	29	43	1513	0.00500289	1514	44	37	203	203	283	1230	1276	80	203	203	283	1558				
08-112	30	118	1326	0.00438456	1328	45	32	143	143	220	1106	1118	77	143	143	220	1338				
08-113	30	0	756	0.00249979	756	45	18	108	108	171	585	637	63	108	108	171	808				
07-105	30	909	6760	0.02235265	6762	45	165	1197	1197	1407	5355	5700	210	1197	1197	1407	7107				
03-122	30	0	456	0.00150781	456	45	11	30	30	86	370	385	56	30	30	86	471				
03-133	30	132	331	0.00109449	331	45	8	18	18	71	260	279	53	18	18	71	350				
09-117	30	37	545	0.00312805	946	45	23	136	136	204	742	796	66	136	136	204	1002				
04-116	30	114	603	0.00199388	603	45	15	63	63	123	480	508	60	63	63	123	631				
04-115	30	258	1185	0.00392163	1185	45	29	130	130	204	982	1000	74	130	130	204	1204				
136-100	30	3714	34839	0.11519881	34851	45	851	5000	5000	5896	28955	29376	896	5000	5000	5896	35272				
01-140	30	1506	4065	0.01344135	4088	45	99	482	462	506	3460	3428	144	462	462	506	4034				
01-101	30	1199	24478	0.08093908	24486	45	596	2937	2937	3580	20907	20640	643	2937	2937	3580	4224				
22-165	30	1690	4630	0.01530958	4632	45	113	162	162	320	4312	3904	158	162	162	320	1445				
35-135R	30	4133	1501	0.00496321	1502	0	37	142	142	179	1323	1266	37	142	142	179	4238				
14-171	30	3033	4645	0.01535918	4647	45	113	163	163	321	4325	3917	158	163	163	321	8927				
58-139	30	734	9013	0.02980243	9016	45	220	1082	1062	1327	7689	7600	265	1062	1062	1327	8927				
02-186	30	193	575	0.0019013	575	45	14	42	42	101	474	485	56	42	42	101	586				
36-138	30	555	5299	0.0175217	5301	45	129	396	396	570	4730	4468	174	396	396	570	6038				
03-151	30	61	558	0.00184509	558	45	14	48	48	107	452	471	59	48	48	107	578				
02-188	30	176	923	0.003052	923	45	23	45	45	113	811	778	68	45	45	113	891				
14-131	30	793	1957	0.00650409	1968	45	48	271	271	164	1804	1659	93	271	271	164	1823				
01-141	30	59	2208	0.00730098	2209	45	54	283	283	392	1827	1862	99	283	283	392	2244				
32-144	30	3738	31387	0.10378441	31398	45	766	5540	5540	6351	25047	26466	811	5540	5540	6351	32817				
07-146	30	672	2760	0.00912623	2761	0	67	538	538	605	2156	2327	57	538	538	605	2932				
35-137	30	1356	11613	0.0083996	11617	0	284	1276	1276	1580	10057	9792	284	1276	1276	1580	11352				
01-205D	30	4123	2659	0.00879225	2660	0	55	257	257	322	2338	2242	65	257	257	322	2564				
31-201	30	1531	35480	0.11731834	35492	0	866	4755	4755	5621	29871	29917	866	4755	4755	5621	35538				
			43726	302425	1	302529	1930	5	7383	38990	38990	48303	5	254225	5	255009	9312	38990	38990	48302	30331
									ETU							265006					

Well Name	Days On	MONTHLY WATER PRODUCTION	FIELD ESTIMATED PRODUCTION										ACTUAL ALLOCATED SALES				TOTAL ADJ	FIELD PRODUCTION			
			Costal Statement	PROD %	FIELD EST PROD	Irr Gas	Lse Use Gas	Vented Gas	Vented Gas	VENTED GAS	ADJ	FIELD ESTIMATED SALES	ALLOCATED SALES	Lse Use Gas	Vented CO2	TOTAL VENTED					
B21-03	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
A26-02	25	88	490	0.00165776	490	39	13	15	15	15	67	423	432	52	15	15	15	15	67	6,780	
C23-08	30	3432	9140	0.03092205	9,140	45	236	437	437	437	718	8,422	8,062	281	437	437	437	437	26	86	
A25-04	15	0	68	0.00023005	68	23	2	2	2	2	26	42	60	24	2	2	2	2	26	28,166	
A35-06	30	141	29088	0.00844307	29,088	45	750	1,706	1,706	1,706	2,501	26,597	25,665	795	1,706	1,706	1,706	7	41	298	
A35-05	18	700	289	0.00097773	289	27	7	7	7	7	41	248	255	34	7	7	7	7	41	5,293	
A34-07	30	2845	5383	0.01821153	5,383	45	39	361	361	361	545	4,838	4,748	184	361	361	361	6	220	343	
P10-47	30	734	391	0.00047028	391	210	4	6	6	6	229	81	123	214	6	6	6	6	229	0	
IAME PROB	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
U02-11	30	50211	15291	0.05173184	15,291	45	394	1,255	1,255	1,255	1,694	13,597	13,487	439	1,255	1,255	1,255	1,694	1,694	15,181	
S06-46	29	1	519	0.00175586	519	203	13	230	230	230	446	73	458	216	230	230	230	230	446	904	
R09-45	30	36	444	0.00150212	444	210	11	102	102	102	323	121	392	221	102	102	102	102	323	715	
P10-42	29	7609	819	0.00277308	819	44	21	144	144	144	206	610	722	65	144	144	144	144	206	931	
P10-43	30	3050	605	0.00204681	605	45	16	61	61	61	22	483	534	61	61	61	61	61	22	658	
Q04-44	16	5442	71	0.0002402	71	112	2	11	11	11	125	54	63	114	11	11	11	11	125	188	
D34-12	24	2583	1471	0.00497662	1,471	36	38	126	126	126	200	1,271	1,297	74	126	126	126	126	200	1,497	
D35-13	30	142110	896	0.000303131	896	45	23	349	349	349	417	479	790	68	349	349	349	349	417	1,207	
D35-14	24	647	233	0.00099126	233	36	8	57	57	57	101	192	258	44	57	57	57	57	101	359	
D35-15	30	1830	20903	0.07071811	20,903	45	539	1,325	1,325	1,325	1,910	18,993	18,488	584	1,325	1,325	1,325	1,910	1,910	20,346	
H06-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
U02-48	25	7527	2310	0.00781509	2,310	42	60	148	148	148	250	2,060	2,037	102	148	148	148	148	250	2,267	
U02-50	30	706	2703	0.00914457	2,703	45	70	165	165	165	280	2,423	2,384	15	165	165	165	165	280	2,664	
U02-49	15	173	347	0.00117395	347	23	9	18	18	18	49	296	305	21	18	18	18	18	49	355	
10-58	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
X16-66	28	307	290	0.00098112	290	42	7	38	38	38	87	203	256	49	38	38	38	38	87	343	
X16-65	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
14-53	30	298	827	0.00279787	827	45	21	50	50	50	116	711	729	56	50	50	50	50	116	845	
14-55	30	9023	85520	0.41965343	124,042	90	3,196	7,739	7,739	7,739	11,025	113,017	109,405	3,266	7,739	7,739	7,739	7,739	11,025	120,430	
14-55A	30	0	85520	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
23-51	30	175	259	0.00091007	259	45	7	9	9	9	61	208	237	52	9	9	9	9	61	298	
24-57	30	254	581	0.00230393	581	45	18	22	22	22	85	596	601	63	22	22	22	22	85	686	
15-68	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
14-54	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
08-62	29	23	491	0.00166113	491	44	13	178	178	178	235	256	433	56	178	178	178	178	235	650	
09-60	29	1445	1074	0.00363351	1,074	44	28	294	294	294	365	709	947	71	294	294	294	294	365	1,312	
14-40	30	4320	2701	0.0091379	2,701	45	70	154	154	154	269	2,432	2,382	115	154	154	154	154	269	2,851	
15-87	26	1202	251	0.000883	251	35	7	14	14	14	60	207	230	46	14	14	14	14	60	290	
08-61	30	478	9427	0.03189301	9,427	45	243	528	528	528	816	8,611	8,315	288	528	528	528	528	816	9,131	
07-54	30	1092	1857	0.00560589	1,857	45	43	495	495	495	583	1,074	1,461	88	495	495	495	495	583	2,044	
08-63	30	264	1654	0.00559574	1,654	45	43	777	777	777	855	789	1,459	88	777	777	777	777	855	2,324	
09-59	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
01-76	30	3108	4980	0.01684812	4,980	45	128	326	326	326	499	4,481	4,392	173	326	326	326	326	499	4,891	
36-78	30	903	5802	0.01962907	5,802	45	150	380	380	380	575	5,227	5,117	195	380	380	380	380	575	5,892	
03-74	27	24620	1325	0.00448258	1,325	41	34	30	30	30	105	1,220	1,169	75	30	30	30	30	105	1,274	
03-75	30	5879	4396	0.01487235	4,396	45	113	296	296	296	457	3,939	3,877	158	296	296	296	296	457	4,334	
11-72	30	45297	922	0.00311927	922	45	24	177	177	177	246	676	813	89	177	177	177	177	246	1,059	
34-80	15	44	113	0.0003823	113	24	3	21	21	21	48	65	100	27	21	21	21	21	48	148	
34-82	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
31-98	30	10	1482	0.00501384	1,482	45	38	133	133	133	216	1,268	1,307	83	133	133	133	133	216	1,523	
A35-89	30	9902	34803	0.11774399	34,803	45	897	2,021	2,021	2,021	2,963	31,840	30,696	942	2,021	2,021	2,021	2,021	2,963	33,659	
P03-92	30	1184	896	0.00299748	896	45	23	89	89	89	157	729	781	68	89	89	89	89	157	936	
P03-93	28	9434	546	0.00218552	546	42	17	96	96	96	156	491	570	59	96	96	96	96	156	725	
T22-59	30	320	1130	0.00382297	1,130	45	29	58	58	58	32	998	997	74	58	58	58	58	32	1,129	
T27-87	30	574	546	0.0018472	546	45	14	27	27	27	86	460	482	59	27	27	27	27	86	568	
01-97	30	0	1194	0.00403949	1,194	0	31	73	73	73	104	1,090	1,053	31	73	73	73	73	104	1,157	
36-95	30	61	470	0.00159008	470	0	12	49	49	49	61	409	415	12	49	49	49	49	61	476	
38-95	30	1503	1260	0.00426278	1,260	0	32	130	130	130	162	1,098	1,111	32	130	130	130	130	162	1,273	
MERRION GAS WELLS																					
hammer	29	10537	481	0.0016273	481	0	12	15	15	15	27	454	424	12	15	15	15	15	27	451	
al	30	985	433	0.0016879	433	0	0	28	28	28	28	465	435	0	28	28	28	28	28	463	
PIPELINE	7	38307	25582	0.0066782	25,582	2,481	502	20,777	20,777	20,777	30,529	264,753	260,704	10,043	20,777	20,777	20,777	20,777	30,832	291,535	
																					259,844

	20777								
	0								
	7604				7604				0
	2448			2448					
	0			0					
Id statement + memon	974								
	31803		295682	2448	7604				0

SALES DIFFERENCE

395211	597033	597137	4379	14975	59724	59724	79077	518060	514853	19355	58724	59724	79079	593932
--------	--------	--------	------	-------	-------	-------	-------	--------	--------	-------	-------	-------	-------	--------

OCT 12 2004

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL GAS WELL OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC. *N2615*

3. ADDRESS OF OPERATOR:
2700 Farmington Bldg K, Sul. Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY: Emery

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
Various Leases

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
See attached list

9. API NUMBER:
Multiple

10. FIELD AND POOL, OR WILDCAT:
Buzzard Bench

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective August 1, 2004, the operator changed from Chevron U.S.A. Inc. to XTO ENERGY INC. for all wells on the attached list.

BLM #579173

State and Fee Bond #104312762

RECEIVED
MAY 18 2007
DIV. OF OIL, GAS & MINING

Kenneth W. Jackson

Kenneth W. Jackson Regulatory Specialist ChevronTexaco for Chevron U.S.A. Inc. *N0210*

NAME (PLEASE PRINT) *James L. Death*
SIGNATURE *James L. Death*

TITLE *Vice President-Land*
DATE *8/16/04*

(This space for State use only)

APPROVED *9/30/2004*

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

(5/2000)

RECEIVED
SEP 28 2004

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-67532
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>	8. WELL NAME and NUMBER: FEDERAL A 18-7-26 #12	9. API NUMBER: 4301530445
2. NAME OF OPERATOR: XTO ENERGY INC.		10. FIELD AND POOL, OR WILDCAT: BUZZARD BENCH ABO
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg # CITY Farmington STATE NM ZIP 87401		PHONE NUMBER: (505) 324-1090
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1815' FNL & 897' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 26 18S 07E		COUNTY: EMERY STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>SURFACE</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>COMMINGLE</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to surface commingle the following two wells into our Orangeville CDP:

Federal A 18-7-26 #12; Sec 26-T18S-R07E; 1815' FNL & 897' FWL; 43-015-30445; UTU-67532; Buzzard Bench
Federal T 18-7-22 #34; Sec 22-T18S-R07E; 539' FSL & 1831' FEL; 43-015-30452; UTU-68535; Buzzard Bench

Both of these wells have their own wellhead allocation meter. Both wells will have the sales point or custody transfer at the Orangeville System.

COPY SENT TO OPERATOR
Date: 7-11-05
Initials: CHO

NAME (PLEASE PRINT) <u>HOLLY C. PERKINS</u>	TITLE <u>REGULATORY COMPLIANCE TECH</u>
SIGNATURE <u>Holly C. Perkins</u>	DATE <u>6/23/2005</u>

(This space for State use only)

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

RECEIVED

JUN 29 2005

DIV. OF OIL, GAS & MINING

(5/2000)

Date: 7/8/05 (See Instructions on Reverse Side)

By: Dustin Ducet

Dustin Ducet ??

IN WELLS FROM COASTAL STATEMENT

WELLS BY PERIOD

	0	302425			
	38990				
	104	104			
s Check #	256029				
s Check #2	0			0	
	0			0	0
	7383			7383	0
	1931		1930 5		
	0				
	304437	302529	1930 5	7383	0

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 382 CR 3100 CITY AZTEC STATE NM ZIP 87410		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (505) 333-3100		8. WELL NAME and NUMBER: MULTIPLE <u>Ut Fed D35-1A</u>
4. LOCATION OF WELL FOOTAGES AT SURFACE: MULTIPLE COUNTY: EMERY QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>17S 7E 35</u> STATE: UTAH		9. API NUMBER: MULTIPLE <u>43 015 30786</u>
		10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>SURFACE</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>COMMINGLE</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. applied for surface commingle on the attached list of wells on 7/5/07 and State of UT DOGM approval was received on 7/13/07. Due to the rejection of the Federal application, XTO would like to withdraw the commingling application and subsequent work will not be done.

NAME (PLEASE PRINT) <u>LORRI D. BINGHAM</u>	TITLE <u>REGULATORY COMPLIANCE TECH</u>
SIGNATURE 	DATE <u>9/23/2008</u>

(This space for State use only)

RECEIVED
SEP 29 2008

Utah Wells Surface Commingled at Orangeville CDP

USA 03-75	43-015-30384	Producing	Federal	
USA 11-72	43-015-30387	Producing	Federal	
USA 18-7-11-23	43-015-30640	Producing	State	
USA 34-80	43-015-30389	Shut In	Federal	
USA 34-82	43-015-30390	Producing	Federal	
Utah Federal 17-7-35-42	43-015-30641	Drilling	Federal	
Utah Federal 18-7-27-44R	43-015-30628	Producing	Federal	
Utah Federal 18-7-9-11	43-015-30639	Producing	Federal	
Utah Federal D 34-12	43-015-30282	Producing	Federal	
Utah Federal D 35-13	43-015-30285	Producing	Federal	
Utah Federal D 35-14	43-015-30286	Producing	Federal	
Utah Federal D 35-15	43-015-30287	Producing	Federal	
Utah Federal H 06-21	43-015-30294	TA	Federal	
Utah Federal P 10-42	43-015-30276	Producing	Federal	
Utah Federal P 10-43	43-015-30277	Producing	Federal	
Utah Federal P 10-47	43-015-30258	Producing	Federal	
Utah Federal Q 04-44	43-015-30280	Producing	Federal	
Utah Federal R 09-45	43-015-30275	Producing	Federal	
Utah Federal S 08-46	43-015-30274	Producing	Federal	
Utah State 01-76	43-015-30381	Producing	State	
Utah State 36-78	43-015-30382	Producing	State	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-74823
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: UTAH FED D 35-14	
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43015302860000	
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3159 Ext	9. FIELD and POOL or WILDCAT: BUZZARD BENCH
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1249 FNL 0360 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 35 Township: 17.0S Range: 07.0E Meridian: S	COUNTY: EMERY	
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/24/2011 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	
<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
XTO Energy Inc. has returned this well to production @ 1030 hours on Wednesday, 05/04/2011.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 5/6/2011	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-74823	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: XTO ENERGY INC		8. WELL NAME and NUMBER: UTAH FED D 35-14	
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410		9. API NUMBER: 43015302860000	
PHONE NUMBER: 505 333-3159 Ext		9. FIELD and POOL or WILDCAT: BUZZARD BENCH	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1249 FNL 0360 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 35 Township: 17.0S Range: 07.0E Meridian: S		COUNTY: EMERY	
		STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 50px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.			
XTO Energy Inc. has returned this well to production @ 2:00 p.m. on 10/12/2011.			
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY			
NAME (PLEASE PRINT) Dolena Johnson		PHONE NUMBER 505 333-3164	
SIGNATURE N/A		TITLE Regulatory Compliance Tech	
		DATE 10/13/2011	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-74823	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
		7. UNIT or CA AGREEMENT NAME:	
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: UTAH FED D 35-14		
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43015302860000		
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3145 Ext	9. FIELD and POOL or WILDCAT: BUZZARD BENCH	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1249 FNL 0360 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 35 Township: 17.0S Range: 07.0E Meridian: S	COUNTY: EMERY		
	STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/11/2012 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER		<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.			
XTO Energy Inc. has returned this well to production @ 1120 hours, 4/11/2012.			
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 11, 2012			
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech	
SIGNATURE N/A	DATE 4/12/2012		

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-74823
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: UTAH FED D 35-14
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43015302860000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3145 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1249 FNL 0360 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 35 Township: 17.0S Range: 07.0E Meridian: S	9. FIELD and POOL or WILDCAT: BUZZARD BENCH COUNTY: EMERY STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/9/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. intends to plug & abandon this well per the attached procedure. Also attached are current & proposed wellbore diagrams.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining**

Date: July 02, 2012

By: Derek Quist

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 6/15/2012	

Utah Federal D 35-14

Location: 1,249' FNL & 360' FWL, Section 35, T17S, R7E, Emery, UT
API: 43-015-30286
Open Perfs: Ferron Sand – 3,865'- 4,004'

PLUG AND ABANDONMENT PROCEDURE

Note: All cement volumes use 100% excess outside pipe and 50' excess inside. The stabilizing wellbore fluid will be 8.3 ppg, sufficient to balance all exposed formation pressures. All cement will be Class B, mixed at 15.6 ppg with a 1.18 cf/sx yield.

1. Install and test location rig anchors. MIRU pulling unit. Conduct safety meeting for all personnel on location. Record casing, tubing and bradenhead pressures. NU relief line and blow down well. Kill well with water as necessary and at least pump tubing capacity of water down the tubing. TOH and LD rods and pump. ND wellhead and NU BOP. Function test BOP. TOH with tubing and LD BHA.
2. Pump 10 sxs bentonite w/70 bbl fresh water down the bradenhead valve.
3. Round trip a 4-3/4" bit to 3,800'.
4. **Plug #1 (Ferron Sand, 3,800' – 3,700')**: TIH and set a 5-1/2" CIBP at 3,800'. Load casing with water and circulate well clean. Pressure test casing to 1000#. If the casing does not test, then spot or tag subsequent plugs as necessary. Mix cement and pump 17 sxs Class B cement above the CIBP to cover the Ferron Sand top. TOH.
5. **Plug #2 (Casing shoe, 390'– Surface)**: Perforate 4 squeeze holes at 390'. Do not proceed until the Bentonite has had at least 24 hours to set up. Establish circulation to surface. Mix and pump approximately 50 sxs cement down the 5-1/2". Shut in well and WOC for 1 hour. Mix and pump approximately 120 sxs cement down the 5-1/2" casing until good cement returns at surface. Shut in well and WOC.
6. ND BOP and cut off casing below surface casing flange. Install P&A marker with cement to comply with regulations. RD, move off location, cut off anchors and restore location.

Tops/Shoe information:

Casing shoe 336'
Ferron Sandstone 3,843'



XTO - Wellbore Diagram

Well Name: Utah Federal D 35-14

API/UWI 43015302860000	E/W Dist (ft) 360.0	E/W Ref FWL	N/S Dist (ft) 1,249.0	N/S Ref FNL	Location T17S-R07E-S35	Field Name Buzzard Bench	County Emery	State Utah
Well Configuration Type Vertical	XTO ID B 110463	Orig KB Elev (ft) 6,944.00	Gr Elev (ft) 6,934.00	KB-Grd (ft) 10.00	Spud Date 9/20/1996	PBTD (All) (ftKB) Original Hole - 4044.0	Total Depth (ftKB) 4,108.0	Method Of Production Beam

Well Config: Vertical - Original Hole, 4/25/2012 3:52:28 PM




Zones		Zone	Top (ftKB)	Blm (ftKB)						
Schematic - Actual		Ferron Sand	3,865.0	4,004.0						
Casing Strings										
0	Casing Description	OD (in)	Wt (lbs/ft)	String Grade	Top Connection	Set Depth (ftKB)				
	Surface	8 5/8	24.00			336.0				
10	Casing Description	OD (in)	Wt (lbs/ft)	String Grade	Top Connection	Set Depth (ftKB)				
	Production	5 1/2	17.00			4,107.0				
Cement										
26	Description	Type	String							
	Surface Casing Cement	casing	Surface, 336.0ftKB							
42	Comment									
54	Description	Type	String							
	Production Casing Cement	casing	Production, 4,107.0ftKB							
42	Comment									
Perforations										
3,726	Date	Top (ftKB)	Blm (ftKB)	Shot Dens (shots/ft)	Hole Diameter (in)	Phasing (*)	Curr... Status	Zone		
		3,865.0	3,876.0							
		3,905.0	3,925.0							
		3,968.0	3,971.0							
		3,988.0	4,004.0							
Tubing Strings										
3,876	Tubing Description	Run Date	Set Depth (ftKB)							
	Tubing - Production	1/31/2005	4,001.7							
Tubing Components										
3,905	Item Description	Jts	Model	OD (in)	Wt (lbs/...)	Gra...	Top Thread	Len (ft)	Top (ftKB)	Blm (ftKB)
3,925	Tubing	1	T&C Upset	2 7/8	6.50	J-55		31.52	10.0	41.5
3,951	Tubing Sub	2	T&C Upset	2 7/8	6.50	J-55		12.36	41.5	53.9
3,963	Tubing	118	T&C Upset	2 7/8	6.50	J-55		3,690.83	53.9	3,744.7
3,968	Anchor/catcher	1		2 7/8				2.81	3,744.7	3,747.5
3,969	Tubing	7	T&C Upset	2 7/8	6.50	J-55		221.08	3,747.5	3,968.6
3,969	Seat Nipple	1		2 7/8				1.10	3,968.6	3,969.7
3,970	Slotted Joint	1		2 7/8				31.50	3,969.7	4,001.2
3,970	Notched Collar	1		2 7/8				0.45	4,001.2	4,001.7
3,971	Rods									
3,971	Rod Description	Run Date	String Length (ft)		Set Depth (ftKB)					
	Rod String	1/31/2005	3,980.00		3,980.0					
Rod Components										
3,980	Item Description	Jts	Model	OD (in)	Wt (lbs/ft)	Len (ft)	Top (ftKB)	Blm (ftKB)		
	Polished Rod	1		1 1/2		26.00	0.0	26.0		
3,988	Sucker Rod w/Snap On Guides	148		3/4 D		3,700.00	26.0	3,726.0		
4,001	Sinker Bar	9		1 1/2 C		225.00	3,726.0	3,951.0		
	Stabilizer Rod	3		7/8 D		12.00	3,951.0	3,963.0		
	Rod Insert Pump	1		1 1/4		16.00	3,963.0	3,979.0		
4,002	Strainer Nipple	1		1		1.00	3,979.0	3,980.0		
Stimulations & Treatments										
4,004	Frac Start Date	Top Perf (ft...)	Bottom Pe...	V (slurry) (...)	Total Prop...	AIR (b...	ATP (psi)	MTP (psi)	ISIP (psi)	
4,044	Comment									
4,107	Frac Start Date	Top Perf (ft...)	Bottom Pe...	V (slurry) (...)	Total Prop...	AIR (b...	ATP (psi)	MTP (psi)	ISIP (psi)	
4,108	Comment									

PBTD, 4,044

TD, 4,108

Utah Federal D 35-14
Sec 35, T17S, R7E
API# 43-015-30286



STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-74823
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7.UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: UTAH FED D 35-14
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43015302860000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3145 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1249 FNL 0360 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 35 Township: 17.0S Range: 07.0E Meridian: S	9. FIELD and POOL or WILDCAT: BUZZARD BENCH COUNTY: EMERY STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/10/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. has plugged & abandoned this well per the attached summary report.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 August 14, 2012

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 8/13/2012	

Utah Federal D 35-14

8/9/2012: Notify Angela Wadman w/BLM with intent to P&A. MIRU rig, MIRU pmp truck. Pmped 20 sxs Bentonite w/70 bbl down BH viv. Ferron Coal perms fr/3,865'- 4,004'. SN @ 3,968'. EOT @ 4,001'. PBD @ 4,044'. Unseated pmp & LD 1-1/4" x 22' PR. MIRU Big Red hot oil, fishd rods w/60 bbl TFW. TOH & LD 7/8" skr d w/3 snap on guides pr rod. 9 1-1/2' SB, 4-7/8" x 3' rod subs & western pmp 1-1/4" x 16' RHBC. ND WH , NU BOP. RIs TAC. TOH & LD 2-7/8" tbg, TAC, 2-7/8" SN, slotted jt & NC. LD BHA. RIH w/5-1/2" GR to 3,830'. TOH LD GR. PU CIBP TIH & set @ 3,800'. RDMO WL. Plugging ops witnessed by Alan Walker w/BLM was on location.

8/10/2012: PU & TIH w/2-7/8" tbg, Load 5-1/2" csg w/80 BFW of jell wtr. PT csg to 1,000 psig w/0 BFW for 10". Tstd ok. RIsd press. MIRU cmt truck, pmp 25 sxs cmt plug (5.46 bbl slurry) of type 2 cmt fr/3,149' - 3,375'. TOH & LD 2-7/8" tbg. MIRU WL. RIH w/2-1/8" BI perf gun. Perf 4 sqz holes @ 393' FS. Pmp 21 BFW dwn csg 3 BPM @ 0 psig est circ. SD pmp. MIRU cmt truck, pmp 155 sxs cmt plug (46.51 bbl slurry) of type 2 cmt. fr/393' - surface. Cmt fell 30' topped off to surf. Dug up WH & cut off @ 4' below surf. Installed P&A marker. RDMO rig. Plugging ops witnessed by Alan Walker w/ BLM was on location. FR for P&A ops.

=====Utah Federal D 35-14 (PA)=====

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-74823	
SUNDRY NOTICES AND REPORTS ON WELLS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		7. UNIT or CA AGREEMENT NAME:	
1. TYPE OF WELL Gas Well		8. WELL NAME and NUMBER: UTAH FED D 35-14	
2. NAME OF OPERATOR: XTO ENERGY INC		9. API NUMBER: 43015302860000	
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155	PHONE NUMBER: 303 397-3727 Ext	9. FIELD and POOL or WILDCAT: BUZZARD BENCH	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1249 FNL 0360 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 35 Township: 17.0S Range: 07.0E Meridian: S		COUNTY: EMERY	
		STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/5/2012 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.			
<p>XTO Energy Inc. has completed the final reclamation of this well per the following: 8/27/2012: Nielson Construction: Moved in D-8 cat and 330 track hoe. 8/28/2012: Compl backfilling & reclaiming 40' of ROW. 9/4/2012 – 9/10/2012: Pushing fill slope to cut slope. 9/11/2012: Contouring location and drainage. 9/13/2012: Contouring location and spreading top soil. 9/17/2012: Contouring location, Pocking location. Started re-contouring access road, leaving two track ROW to power line. 9/18/2012: Final clean up on ROW, Removed iron gate from ROW. 9/19/2012: Loaded iron gate and concrete on trailer and hauled off. Final report until location is reseeded. 10/5/2012: Reseed location and ROW with approved seed mix, final report.</p>			
		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 12, 2013	
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 303-397-3736	TITLE Regulatory Compliance Tech	
SIGNATURE N/A		DATE 8/12/2013	