

May 8, 2006

Rich McClure
Bureau of Land Management
Moab Field Office
82 East Dogwood
Moab, Utah 84532

RE: Application for Permit to Drill—Elk Production Company, LLC
Federal #11-7, 1,846' FNL, 460' FWL, SW/4 NW/4,
Section 11, T20S, R21E, SLB&M, Grand County, Utah

Dear Rich:

On behalf of Elk Production, LLC (Elk), Buys & Associates, Inc. respectfully submits the enclosed original and three copies of the Application for Permit to Drill (APD) for the above referenced well. Included with the APD is the following supplemental information:

- Exhibit "A" - Survey plats, layouts and photos of the proposed well site;
- Exhibit "B" - Proposed location maps with access and utility corridors;
- Exhibit "C" - Drilling Plan;
- Exhibit "D" - Surface Use Plan;
- Exhibit "E" - Typical BOP and Choke Manifold diagram.

Please accept this letter as Elk Production's, written request for confidential treatment of all information contained in and pertaining to this application.

Thank you very much for your timely consideration of this application. Please feel free to contact myself or Kevin Weller, P.E. of Elk at 303-339-1922 if you have any questions or need additional information.

Sincerely,

Don Hamilton
Don Hamilton
Agent for Elk Production, LLC

cc: Diana Whitney, Division of Oil, Gas and Mining
Kevin Weller, P.E., Elk Production, LLC
Karin Kuhn, Elk Production, LLC

RECEIVED

MAY 12 2006

DIV. OF OIL, GAS & MINING

FILE COPY

CONFIDENTIAL

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

5. Lease Serial No. UTU-72600	
6. If Indian, Allottee or Tribe Name N/A	
7. If Unit or CA Agreement, Name and No. undesignated	
8. Lease Name and Well No. Federal 11-7	
9. API Well No. 43-019-31475	
10. Field and Pool, or Exploratory Greater Cisco	
11. Sec., T. R. M. or Blk. and Survey or Area Section 11, T20S, R21E, SLB&M	
12. County or Parish Grand	13. State UT
14. Distance in miles and direction from nearest town or post office* 15.67 miles northwest of Cisco, Utah	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 460'	16. No. of acres in lease 40 acres
17. Spacing Unit dedicated to this well	18. BLM/BIA Bond No. on file B 000971
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 3,000'	19. Proposed Depth 3,150'
20. Elevations (Show whether DF, KDB, RT, GL, etc.) 5,516' GR	21. Approximate date work will start* 06/15/2006
	22. Estimated duration 9 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|---|---|
| <ul style="list-style-type: none"> 1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | <ul style="list-style-type: none"> 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification 6. Such other site specific information and/or plans as may be required by the BLM. |
|---|---|

25. Signature Don Hamilton	Name (Printed/Typed) Don Hamilton	Date 05/08/2006
--------------------------------------	---	---------------------------

Title **Agent for Elk Production, LLC**

Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL <small>Office</small>	Date 05-25-06
-----------------------------	---	-------------------------

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

CONFIDENTIAL

*Federal Approval of this
Action is Necessary*


RECEIVED

MAY 12 2006

DIV. OF OIL, GAS & MINING

T20S, R21E, S.L.B.&M.

1919 Brass Cap,
Flush With 1.0'
High Pile of
Stones



BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.


(AUTONOMOUS NAD 83)
 LATITUDE = 39°04'59.34" (39.083150)
 LONGITUDE = 109°34'19.92" (109.572200)
 (AUTONOMOUS NAD 27)
 LATITUDE = 39°04'59.44" (39.083178)
 LONGITUDE = 109°34'17.47" (109.571519)

ELK PRODUCTION, LLC

Well location, FEDERAL #11-7, located as shown in the SW 1/4 NW 1/4 of Section 11, T20S, R21E, S.L.B.&M. Grand County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE SOUTHEAST CORNER OF SECTION 24, T20S, R21E, S.L.B.&M. TAKEN FROM THE CALF CANYON, QUADRANGLE, UTAH, GRAND COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5084 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

John A. ...
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 01-02-06	DATE DRAWN: 01-10-06
PARTY D.K. L.K. P.M.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE ELK PRODUCTION, LLC	

DRILLING PLAN

Elk Production, LLC
Federal #11-7
NWSE of Section 11, T-20-S, R-21-E
Grand County, UT

1,2,3 **Estimated Tops of Geological Markers and Formations Expected to Contain Water, Oil and Gas and Other Minerals**

<u>Formation</u>	<u>Depth</u>
Mancos Shale	Surface
Greenhorn	2441'
Graneros	2522'
Dakota	2552'*
Cedar Mountain	2623'*
Morrison-Brushy Basin	2742'*
Morrison Salt Wash	2939'*
Summerville	3142'
Total Depth	3150'

PROSPECTIVE PAY* oil and gas
** POSSIBLE OIL OR WATER

4 Casing Program

<u>HOLE SIZE</u>	<u>SETTING DEPTH</u>		<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>COND.</u>
	<u>from</u>	<u>to</u>					
11"	surface	250'	8 5/8"	24#	J55	N-80	New
7 7/8"	surface	3,150'	5 1/2"	15.5#	J55	N-80	New

5 Cementing Program

8 5/8" Surface Casing approximately 100 sx Portland cement containing 2% gel and 3% salt. Mixed at 14.8 ppg (yield – 1.37 ft³/sx). To be circulated to surface (calculated @ 100% excess).

5 1/2" Prod. Csg. approximately 270 sx 50/50 Class "G" Poz cement containing 2% gel, .3% Halad 322, .6% Halad 23, .3% Versaset, and .2% Super CBL. To be mixed at 14.2 ppg (yield – 1.33 ft³/sx). Estimated TOC 1500'.

6 Mud Program

<u>INTERVAL</u>	<u>WEIGHT</u>	<u>VISCOSITY</u>	<u>FLUID LOSS</u>	<u>REMARKS</u>
Surf. - 250'	NA/Air drilled			
250' – 3400'	NA/Air drilled			

Sufficient KC1 brine water to contain "kick" will be available at wellsite.

7 BOP and Pressure Containment Data

Depth Intervals

Surf. – 250'
250' – TD

BOP Equipment

No pressure control required
10" 3000# Ram Type double BOP
8" 2000# Rotating Head

Drilling spool to accommodate choke and kill lines.
Anticipated bottom hole pressure to be less than 1000 PSI

ANCILLARY EQUIPMENT AND CHOKE MANIFOLD RATED AT 3000#
ALL BOP AND BOPE TESTS WILL BE IN ACCORDANCE WITH THE REQUIREMENTS
OF ONSHORE ORDER NO. 2. PLAN TO TEST BOP TO 1500 PSI, TWICE THE POSSIBLE
SHUT-IN PRESSURE AMOUNT.

THE BLM AND THE STATE OF UTAH DIVISION OF OIL, GAS AND MINING
WILL BE NOTIFIED 24 HOURS IN ADVANCE OF ALL BOP PRESSURE TESTS.

8 Auxiliary equipment

- a) Lower Kelly cock will be installed while drilling
- b) Floor stabbing valve 5000#
- c) Safety valve(s) and subs to fit all string connections in use

9 Testing, Logging and Core Programs

Cores None anticipated
Testing None anticipated
Sampling 30' samples; surface casing to TD
Surveys Run every 1000' and on trips
Logging Resistivity, neutron density, temperature, gamma ray, and caliper from TD to
 surface casing

10 Anticipated Abnormal Pressures or Temperatures

No abnormal pressures or temperatures or other hazards are anticipated

11 Drilling Schedule

Spud As soon as permits can be obtained
Duration 4 - 5 days drilling time
 4 days completion time

HAZARDOUS MATERIAL DECLARATION

Federal #11-7

Elk Production, LLC guarantees that during the drilling and completion of the above referenced well, we will not use, produce, or store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Super Amendments and Reauthorization Act (SARA) of 1986.

Elk Production, LLC guarantees that during the drilling and completion of the above referenced well, we will use, produce, store, transport, or dispose less than the threshold planning quantity (TPQ) of any extremely hazardous substances as defined in 40 CFR 355.

SURFACE USE PLAN

Elk Production, LLC
Federal #11-7
SWNW of Section 11, T-20-S, R-21-E
Grand County, UT

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

The onsite inspection for the referenced well was conducted on Thursday, December 15, 2005.

1. Existing Roads:

- a. The proposed well site is located approximately 15.67 miles northwest of Cisco, Utah.
- b. Directions to the proposed well site have been attached at the end of Exhibit B.
- c. The use of roads under State and County Road Department maintenance are necessary to access the Cisco Dome Field. However, an encroachment permit is not anticipated since no upgrades to the State or County Road system are proposed at this time.
- d. All existing roads will be maintained and kept in good repair during all phases of operation.
- e. Vehicle operators will obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions.
- f. Since no improvements are anticipated to the State, County or BLM access roads no topsoil striping will occur.
- g. **An off-lease federal right-of-way is needed for the off-lease portion of the existing and proposed access road from the west line of UTU-72600 west to the existing Grand County maintained road. A federal Right-of-way grant for the existing and proposed access road is requested with this application.**

2. Planned Access Roads:

- a. From the existing CF #1 well site an access is proposed trending east approximately 0.15 miles to the proposed well site. The access consists of new disturbance that crosses no significant drainages. A road design plan is not anticipated at this time.
- b. The proposed access road will consist of a 14' travel surface within a 30' disturbed area.
- c. BLM approval to construct and utilize the proposed access road is requested with this application.
- d. A maximum grade of 10% will be maintained throughout the project with no cuts and fills required to access the well.
- e. No turnouts are proposed since the access road is only 0.15 miles long and adequate site distance exists in all directions.
- f. One 18" or larger culvert as the access road enters the well pad and no low-water crossings are anticipated at this time. Adequate drainage structures will be incorporated into the

remainder of the road.

- g. No surfacing material will come from federal lands.
- h. No gates or cattle guards are anticipated at this time.
- i. Surface disturbance and vehicular travel will be limited to the approved location access road.
- j. All access roads and surface disturbing activities will conform to the standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).
- k. The operator will be responsible for all maintenance of the access road including drainage structures.

3. Location of Existing Wells:

- a. Topo C of Exhibit B has a map reflecting existing wells within a one mile radius of the proposed well.

4. Location of Production Facilities:

- a. All permanent structures will be painted a flat, non-reflective Olive Black color to match the standard environmental colors. All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.
- b. Site security guidelines identified in 43 CFR 3163.7-5 and Onshore Oil and Gas Order No. 3 will be adhered to.
- c. A gas meter run will be constructed and located on lease within 500 feet of the wellhead. Meter runs will be housed and/or fenced. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.
- d. A tank battery will be constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain the storage capacity of the largest tank. All loading lines and valves will be placed inside the berm surrounding the tank battery. All liquid hydrocarbons production and measurement shall conform to the provisions of 43 CFR 3162.7-3 and Onshore Oil and Gas Order No. 4 and Onshore Oil and Gas Order No. 5 for natural gas production and measurement.
- e. Any necessary pits will be properly fenced to prevent any wildlife and livestock entry.
- f. All access roads will be maintained as necessary to prevent erosion and accommodate year-round traffic. The road will be maintained in a safe useable condition.
- g. The site will require periodic maintenance to ensure that drainages are kept open and free of debris, ice, and snow, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.

- h. **An off-lease federal right-of-way is needed for the off-lease portion of the proposed pipeline corridor from the west line of UTU-72600 west to the existing Grand County maintained road then southeast to the existing Elk Production, LLC pipeline. A federal Right-of-way grant for the proposed pipeline corridor is requested with this application.**
- i. A gas pipeline is associated with this application and is being applied for at this time. The proposed gas pipeline corridor will leave the west side of the well site and traverse 8,200' west then southeast to the existing pipeline corridor that services the existing Federal 14-5 pipeline corridor
- j. The gas pipeline will be installed immediately adjacent to the access road approximately 15' from the centerline of the road.
- k. The gas pipeline will be a 6" or less steel surface line within a 20' wide utility corridor. The use of the proposed well site and access roads will facilitate the staging of the pipeline construction. A new pipeline length of approximately 8,200' is associated with this well.
- l. Elk Production, LLC intends on installing the pipeline on the surface by welding many joints into long lengths, dragging the long lengths into position and then completing a final welding pass to join the long lengths together. Elk Production, LLC intends on connecting the pipeline together utilizing conventional welding technology.

5. Location and Type of Water Supply:

- a. Since this well will be air drilled the use of water for drilling is not anticipated.
- b. Water for drilling and completion operations, if necessary, will be trucked over approved access roads from Thompson, Utah. The water will be obtained through a direction purchase agreement with a private owner.

6. Source of Construction Material:

- a. The use of materials will conform to 43 CFR 3610.2-3.
- b. No construction materials will be removed from BLM lands.
- c. If any gravel is used, it will be obtained from a state approved gravel pit.

7. Methods of Handling Waste Disposal:

- a. All wastes associated with this application will be contained and disposed of utilizing approved facilities.
- b. Drill cuttings will be contained and buried on site.
- c. A reserve pit is not anticipated at this time and will be constructed only if necessary.
- d. The reserve pit will be located inboard of the location and along the north side of the pad.
- e. The reserve pit will be constructed so as not to leak, break, or allow any discharge.

- f. The reserve pit will be constructed of native material and will not be lined. Pit walls will be sloped no greater than 2:1. A minimum 2-foot freeboard will be maintained in the pit at all times during the drilling and completion operation.
- g. The reserve pit has been located in cut material. Three sides of the reserve pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. After the reserve pit has dried, all areas not needed for production will be rehabilitated.
- h. No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completion of the well.
- i. Trash will be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations. The contents of the trash container will be hauled off periodically to an approved landfill.
- j. Produced fluids from the well other than water will be produced into a test tank until such time as construction of production facilities is completed. Any spills of oil, gas, salt water or other produced fluids will be cleaned up and removed.
- k. After initial clean-up, a 400 bbl tank will be installed. The contents will be transported by truck from the tank to an approved disposal facility for disposal.
- l. Any salts and/or chemicals, which are an integral part of the drilling system, will be disposed of in the same manner as the drilling fluid.
- m. Sanitary facilities will be on site at all times during operations. Sewage will be placed in a portable chemical toilet and the toilet replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to an approved wastewater treatment facility in accordance with state and county regulations.

8. Ancillary Facilities:

- a. Garbage Containers and Portable Toilets are the only ancillary facilities proposed in this application.

9. Well Site Layout: (See Exhibit B)

- a. The well will be properly identified in accordance with 43 CFR 3162.6.
- b. Access to the well pad will be from the west.
- c. The pad and road designs are consistent with BLM specification
- d. A pre-construction meeting with responsible company representative, contractors and the BLM will be conducted at the project site prior to commencement of surface-disturbing activities. The pad and road will be construction-staked prior to this meeting.

- e. The pad has been staked at its maximum size of 150' X 200'; however it will be constructed smaller if possible, depending upon rig availability. Should the layout change, this application will be amended and approved utilizing a sundry notice.
- f. All surface disturbing activities, will be supervised by a qualified, responsible company representative who is aware of the terms and conditions of the APD and specifications in the approved plans.
- g. All cut and fill slopes will be such that stability can be maintained for the life of the activity.
- h. Diversion ditches will be constructed as shown around the well site to prevent surface waters from entering the well site area.
- i. The site surface will be graded to drain away from the pit to avoid pit spillage during large storm events.
- j. The stockpiled topsoil (first 6 inches or maximum available) will be stored in a windrow on the uphill side of the location to prevent any possible contamination. All topsoil will be stockpiled for reclamation in such a way as to prevent soil loss and contamination.
- k. Pits will remain fenced until site cleanup.
- l. The blooie line will be located at least 100 feet from the well head.
- m. Water injection may be implemented if necessary to minimize the amount of fugitive dust.

10. Plans for Restoration of the Surface:

- a. Site reclamation for a producing well will be accomplished for portions of the site not required for the continued operation of the well.
- b. The Operator will control noxious weeds along access road use authorizations, pipeline route authorizations, well sites, or other applicable facilities by spraying or mechanical removal. A list of noxious weeds may be obtained from the BLM or the appropriate County Extension Office. On BLM administered land, it is required that a Pesticide Use Proposal be submitted and approved prior to the application of herbicides, pesticides or possibly hazardous chemicals.
- c. Upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1. Once the reserve pit is dry, the plastic nylon reinforced liner shall be torn and perforated before backfilling of the reserve pit. The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours.
- d. The cut and fill slopes and all other disturbed areas not needed for the production operation will be top soiled and re-vegetated. The stockpiled topsoil will be evenly distributed over the disturbed area.
- e. Prior to reseeding the site, all disturbed areas, including the access road, will be scarified and left with a rough surface. The site will then be seeded and/or planted as prescribed by the BLM. The BLM recommended seed mix will be detailed within their approval documents.

11. Surface and Mineral Ownership:

- a. Surface Ownership – Federal under the management of the Bureau of Land Management - Moab Field Office, 82 East Dogwood, Moab, Utah 84532; 435-259-2127.
- b. Surface Ownership – Federal under the management of the Bureau of Land Management - Moab Field Office, 82 East Dogwood, Moab, Utah 84532; 435-259-2127.

12. Other Information:

- a. Senco-Phenix Archaeological Consultants has conducted a Class III archeological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by Senco-Phenix Archaeological Consultants.
- b. Our understanding of the results of the onsite inspection are:
 - a. No Threatened and Endangered flora and fauna species were found during the onsite inspection.
 - b. No raptor habitat is known to exist within 1 mile of the proposed wellsite.
 - c. A federal right-of-way grant is necessary for construction of the off-lease portion of the access road and pipeline corridor.
 - d. No drainage crossings that require additional State or Federal approval are being crossed.

13. Operator's Representative and Certification

Title	Name	Office Phone
Company Representative	Kevin Weller, P.E.	1-303-339-1922
Agent for Elk Production, LLC	Don Hamilton	1-435-719-2018

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exists; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Elk Production, LLC and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided under Elk Production's BLM bond. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Signature: Don Hamilton Date: 5-8-2006

**ELK PRODUCTION, LLC
FEDERAL #11-7
SECTION 11, T20S, R21E, S.L.B.&M.**

PROCEED IN AN EASTERLY DIRECTION FROM GREEN RIVER, UTAH ALONG INTERSTATE-70 APPROXIMATELY 43.2 MILES TO THE WHITE HOUSE EXIT; EXIT RIGHT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 13.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN RIGHT AND PROCEED IN A NORTHERLY, THEN NORTHWESTERLY DIRECTION APPROXIMATELY 2.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE EXISTING #1 AND THE BEGINNING OF THE PROPOSED ACCESS TO THE EAST; FOLLOW ROAD FLAGS IN AN EASTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE PROPOSED LOCATION.


TOTAL DISTANCE FROM GREEN RIVER, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 60.9 MILES.

ELK PRODUCTION, LLC

LOCATION LAYOUT FOR

FEDERAL #11-7
SECTION 11, T20S, R21E, S.L.B.&M.
1846' FNL 460' FWL



FIGURE #1



SCALE: 1" = 40'
DATE: 01-10-06
Drawn By: P.M.

NOTE:

Flare Pit is to be located a min. of 100' from the Well Head.



NOTES:

Elev. Ungraded Ground At Loc. Stake = 5515.8'
FINISHED GRADE ELEV. AT LOC. STAKE = 5515.8'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

ELK PRODUCTION, LLC

TYPICAL CROSS SECTIONS FOR

FEDERAL #11-7




SECTION 11, T20S, R21E, S.L.B.&M.

1846' FNL 460' FWL

FIGURE #2

1" = 10'
X-Section
Scale
1" = 40'

DATE: 01-10-06
Drawn By: P.M.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT		
(6") Topsoil Stripping	=	620 Cu. Yds.
Remaining Location	=	1,590 Cu. Yds.
TOTAL CUT	=	2,210 CU.YDS.
FILL	=	1,590 CU.YDS.

EXCESS MATERIAL	=	620 Cu. Yds.
Topsoil	=	620 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	0 Cu. Yds.

ELK PRODUCTION, LLC

FEDERAL #11-7

LOCATED IN GRAND COUNTY, UTAH
SECTION 11, T20S, R21E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: EASTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


01 05 06
MONTH DAY YEAR

PHOTO

TAKEN BY: D.K.

DRAWN BY: C.P.

REVISED: 00-00-00



**PROPOSED LOCATION:
FEDERAL #11-7**

SEE TOPO "B"

T20S

T21S

**R
21
E**

**R
22
E**

13.4 MI. +/-

1.5 MI. +/-

INTERSTATE-70

GREEN RIVER 43.2 MI. +/-

DENVER

LEGEND:

○ PROPOSED LOCATION



ELK PRODUCTION, LLC

**FEDERAL #11-7
SECTION 11, T20S, R21E, S.L.B.&M.
1846' FNL 460' FWL**



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**


01 05 06
MONTH DAY YEAR

SCALE: 1:100,000

DRAWN BY: C.P.

REVISED: 00-00-00





LEGEND:

- EXISTING ROAD
- - - - - PROPOSED ACCESS ROAD




ELK PRODUCTION, LLC

FEDERAL #11-7
SECTION 11, T20S, R21E, S.L.B.&M.
1846' FNL 460' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP	01	05	06	B TOPO
	<small>MONTH</small>	<small>DAY</small>	<small>YEAR</small>	
<small>SCALE: 1" = 2000'</small>		<small>DRAWN BY: C.P.</small>		<small>REVISED: 00-00-00</small>



LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ⊗ WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED


UEIS Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



ELK PRODUCTION, LLC

FEDERAL #11-7
 SECTION 11, T20S, R21E, S.L.B.&M.
 1846' FNL 460' FWL

TOPOGRAPHIC	01	05	06	C TOPO
MAP	<small>MONTH</small>	<small>DAY</small>	<small>YEAR</small>	
<small>SCALE: 1" = 2000'</small>		<small>DRAWN BY: C.P.</small>		<small>REVISED: 00-00-00</small>



APPROXIMATE TOTAL PIPELINE DISTANCE = 8,200' +/-

LEGEND:

-  PROPOSED ACCESS ROAD
-  EXISTING PIPELINE
-  PROPOSED PIPELINE



ELK PRODUCTION, LLC

FEDERAL #11-7
 SECTION 11, T20S, R21E, S.L.B.&M.
 1846' FNL 460' FWL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP
 01 | 05 | 06
MONTH DAY YEAR
 SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00



**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 05/12/2006

API NO. ASSIGNED: 43-019-31475

WELL NAME: FEDERAL 11-7
 OPERATOR: ELK PRODUCTION LLC (N2650)
 CONTACT: DON HAMILTON

PHONE NUMBER: 435-650-1886

PROPOSED LOCATION:

SWNW 11 200S 210E
 SURFACE: 1846 FNL 0460 FWL
 BOTTOM: 1846 FNL 0460 FWL
 COUNTY: GRAND
 LATITUDE: 39.08320 LONGITUDE: -109.5716
 UTM SURF EASTINGS: 623546 NORTHINGS: 4326773
 FIELD NAME: GREATER CISCO (205)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal
 LEASE NUMBER: UTU-72600
 SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: MRSN
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:


- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. B 000971)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. AIR DRILLE)
- RDCC Review (Y/N)
(Date:)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)

LOCATION AND SITING:

- R649-2-3.
- Unit: _____
- R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit
Board Cause No: 102-16(b)
Eff Date: 11-15-1979
Siting: See Cause order
- R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1. Federal Approval



GREATER CISCO FIELD
CAUSE: 102-16B / 11-15-1979


OPERATOR: ELK PROD LLC (N2650)

SEC: 11,14 T. 20S R. 21E

FIELD: GREATER CISCO (20S)

COUNTY: GRAND

CAUSE: 102-16B / 11-15-1979



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 24-MAY-2006

- Field Status**
- ABANDONED
 - ACTIVE
 - COMBINED
 - INACTIVE
 - PROPOSED
 - STORAGE
 - TERMINATED

- Unit Status**
- EXPLORATORY
 - GAS STORAGE
 - NF PP OIL
 - NF SECONDARY
 - PENDING
 - PI OIL
 - PP GAS
 - PP GEOTHERML
 - PP OIL
 - SECONDARY
 - TERMINATED

- Wells Status**
- GAS INJECTION
 - GAS STORAGE
 - LOCATION ABANDONED
 - NEW LOCATION
 - PLUGGED & ABANDONED
 - PRODUCING GAS
 - PRODUCING OIL
 - SHUT-IN GAS
 - SHUT-IN OIL
 - TEMP. ABANDONED
 - TEST WELL
 - WATER INJECTION
 - WATER SUPPLY
 - WATER DISPOSAL
 - DRILLING



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

May 25, 2006

Elk Production, LLC
1401 17th Street, Suite 700
Denver, CO 80202

Re: Federal 11-7 Well, 1846' FNL, 460' FWL, SW NW, Sec. 11, T. 20 South,
R. 21 East, Grand County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-019-31475.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Grand County Assessor
Bureau of Land Management, Moab District Office

Operator: Elk Production, LLC

Well Name & Number Federal 11-7

API Number: 43-019-31475

Lease: UTU-72600

Location: SW NW Sec. 11 T. 20 South R. 21 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-72600
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME: NA
2. NAME OF OPERATOR: Elk Production, LLC		8. WELL NAME and NUMBER: Federal 11-7
3. ADDRESS OF OPERATOR: 1401 17th. St., Suite 700 CITY Denver STATE CO ZIP 80202		9. API NUMBER: 4301931475
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1846' FNL, 460' FWL		10. FIELD AND POOL, OR WILDCAT: Greater Cisco
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 11 20S 21E S		COUNTY: Grand
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Extend APD</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Elk requests to extend APD expiration date for one year (expiring 5/25/08). Elk has not obtained Federal approval yet for this drilling location. See attached APD Request for Permit Extension Validation; there has been no changes to the original APD.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 06-28-07
By: [Signature]

6-29-07
RM

NAME (PLEASE PRINT) <u>Karin Kuhn</u>	TITLE <u>Sr. Engineering Technician</u>
SIGNATURE <u>[Signature]</u>	DATE <u>6/27/2007</u>

(This space for State use only)

RECEIVED
JUN 28 2007

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4301931475
Well Name: Federal 11-7
Location: SWNW Section 11-T20S-R21E, Grand County, UT
Company Permit Issued to: Elk Production, LLC
Date Original Permit Issued: 5/25/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No



Signature

6/27/2007

Date

Title: Sr. Engineering Technician

Representing: Elk Production, LLC

RECEIVED
JUN 28 2007
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-72600
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
		7. UNIT or CA AGREEMENT NAME: NA
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	8. WELL NAME and NUMBER: Federal 11-7	
2. NAME OF OPERATOR: Elk Production, LLC		9. API NUMBER: 4301931475
3. ADDRESS OF OPERATOR: 1401 17th. St., Suite 700 CITY Denver STATE CO ZIP 80202	PHONE NUMBER: (303) 296-4505	10. FIELD AND POOL, OR WILDCAT: Greater Cisco
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1846' FNL, 400' FWL		COUNTY: Grand
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 11 20S 21E S		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: EXTEND APD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Elk Production, LLC requests to extend the APD for the subject drilling location for another year (expiring 5/25/2009). There have been no changes to the original APD (approved by the State 5/25/2006). Attached is a Request for Permit Extension Validation checklist.

Approved by the
Utah Division of
Oil, Gas and Mining

COPY SENT TO OPERATOR
Date: 5.20.2008
Initials: KS

Date: 05-14-08
By: 

NAME (PLEASE PRINT) <u>Karin Kuhn</u>	TITLE <u>Sr. Engineering Technician</u>
SIGNATURE 	DATE <u>5/5/2008</u>

(This space for State use only)

RECEIVED
MAY 09 2008
DIV. OF OIL, GAS & MINING

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4301931475
Well Name: Federal 11-7
Location: SWNW Section 11-T20S-R21E, Grand County, UT
Company Permit Issued to: Elk Production, LLC
Date Original Permit Issued: 5/25/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No



Signature

5/5/2008

Date

Title: Sr. Engineering Technician

Representing: Elk Production, LLC

RECEIVED

MAY 09 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-72600
	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: FEDERAL 11-7
2. NAME OF OPERATOR: ELK PRODUCTION, LLC	9. API NUMBER: 43019314750000
3. ADDRESS OF OPERATOR: 1401 17th Street, Suite 700 , Denver, CO, 80202	PHONE NUMBER: 303 296-4505 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1846 FNL 0460 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 11 Township: 20.0S Range: 21.0E Meridian: S	9. FIELD and POOL or WILDCAT: GREATER CISCO COUNTY: GRAND STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/1/2009	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Please extend the APD for the subject drilling location for another year. There have been no changes to the original APD. Attached is a Request for Permit Extension Validation checklist.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: May 11, 2009

By: 

NAME (PLEASE PRINT) Karin Kuhn	PHONE NUMBER 303 296-4505	TITLE Sr. Engineering Technician
SIGNATURE N/A	DATE 5/7/2009	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43019314750000

API: 43019314750000

Well Name: FEDERAL 11-7

Location: 1846 FNL 0460 FWL QTR SWNW SEC 11 TWP 200S RNG 210E MER S

Company Permit Issued to: ELK PRODUCTION, LLC

Date Original Permit Issued: 5/25/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
- Has the approved source of water for drilling changed? Yes No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
- Is bonding still in place, which covers this proposed well? Yes No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Karin Kuhn

Date: 5/7/2009

Title: Sr. Engineering Technician **Representing:** ELK PRODUCTION, LLC

Date: May 11, 2009

By:



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

August 5, 2010

Elk Production LLC
1401-17th St., Ste. 700
Denver, CO 80202

Re: APD Rescinded – Federal 11-7, Sec.11, T.20S, R.21E
Grand County, Utah API No. 43-019-31475

Ladies and Gentlemen:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on May 25, 2006. On June 28, 2007, May 14, 2008 and May 11, 2009, the Division granted a one-year APD extension. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective August 5, 2010.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

Diana Mason
Environmental Scientist

cc: Well File
Bureau of Land Management, Moab

