

FILE NOTATIONS

Entered in NID File

Entered on R Sheet

Location Map Pinned

Card Indexed

IWR on Station Fee Land

Checked by Chief

Copy NID to Field Office

Approval Letter

Disposal Letter

ACQUISITION DATA

Date Well Logged 7-27-57

Location Indexed

CW VCY TA

Bonded

CW OS PA

Share of Fee Land


LOGS FILED

DH Log 3-5-58

Electric Logs (No.) 1

E I E-I GR GR-N Micro

Lat Mi-L Sonic Others



STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

STATE CAPITOL BUILDING
SALT LAKE CITY 14, UTAH

Fee and Patented.....
State
Lease No.
Public Domain
Lease No. 04114-B...
Indian
Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill.....	<input checked="" type="checkbox"/>	Subsequent Report of Water Shut-off.....	
Notice of Intention to Change Plans.....		Subsequent Report of Altering Casing.....	
Notice of Intention to Redrill or Repair.....		Subsequent Report of Redrilling or Repair.....	
Notice of Intention to Pull or Alter Casing.....		Supplementary Well History.....	
Notice of Intention to Abandon Well.....			

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

..... May 6, 1957

Well No. 1 is located 600 ft. from ~~WN~~ {S} line and 766 ft. from ~~WN~~ {E} line of Sec. 25
 SE $\frac{1}{4}$ SE $\frac{1}{4}$ Sec. 25 36S 22E S. L. B. M.
($\frac{1}{4}$ Sec. and Sec. No.) (Twp.) (Range) (Meridian)
 Wildcat San Juan Utah
(Field) (County or Subdivision) (State or Territory)

The elevation of the derrick floor above sea level is 5955 feet.

A drilling and plugging bond has been filed with U.S.G.S.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

Dakota	surface	13 3/8" 48# H-40 surface casing set at 400' and cemented with 300 sacks;
Navajo	1420	
Chile	2155	9 5/8" 32.3# H-40 set at 2100', cemented with 530 sacks
Shinarump	2855	5 1/2" 14 and 15.5# J-55 set at 6350' with 375 sacks.
Hermosa	5025	Any commercial shows of oil or gas will be drill stem tested. Paradox objectives will be diamond cored.
Paradox	6095	
Salt	6345	Well to be drilled to T.D. with rotary tools.
T.D.	6350	Estimated spud date: May 20, 1957


I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company Brewster-Bartle Drilling Company, Incorporated
 Address 1919 Bank of the Southwest Building By [Signature]
Houston, Texas Title Executive Vice President

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

SURVEY IN THE SE 1/4 OF THE SE 1/4 OF SEC. 25, TP. 36 S, R22, S.L.B.M.

SAN JUAN SURVEYING SERVICE
MONTICELLO, UTAH
MARCH 25, 1957



SCALE 1"=200'

Frank S. Sherer
REG. LAND SURVEYOR NO. 1361

FB T-6

BREWSTER-BARTLE DRILLING COMPANY

(INCORPORATED)

1919 BANK OF THE SOUTHWEST BUILDING

HOUSTON 2, TEXAS

May 9, 1957

State of Utah
Oil & Gas Conservation Commission
State Capitol Building
Salt Lake City 14, Utah

Attention: Mr. C. B. Feight

Gentlemen:

Enclosed are three copies of your form OGCC-1, Notice of Intention to Drill, together with three location plats. We would appreciate your processing this matter for us so that we may commence operations immediately on our Blanding Federal No. 1 well.

Thank you.

Yours very truly,


Executive Vice President

LS

May 10, 1957

Brewster-Bartle Drilling Company Inc.
1919 Bank of the Southwest Building
Houston 2, Texas

Gentlemen:

This is to acknowledge receipt of your notice of intention to drill Well No. Blanding-Federal 1, which is to be located 600 feet from the south line and 766 feet from the east line of Section 25, Township 36 South, Range 22 East, SLPM, San Juan County, Utah.

Please be advised that insofar as this office is concerned, approval to drill said well is hereby granted.

Yours very truly,

OIL & GAS CONSERVATION COMMISSION

OLSON B. FEIGHT
SECRETARY

OBf:en

cc: Don Russell, Dist. Eng.
USGS, Federal Bldg.
Salt Lake City, Utah

Brewster-Bartle Drilling Co., Inc.
BLANDING-FEDERAL NO. 1
San Juan County, Utah

Drilling Contractor: Exploration Drilling Co.
607 National Bank of Tulsa
Tulsa, Oklahoma

Started Rigging Up: 5-22-57
Started Drilling: 5-30-57
Completed Drilling: 7-19-57

FORMATIONS

Sandstone	0	319	Sand	4627	4643
Shale	319	351	Anhydrite & Red Bed	4643	4820
Sandstone & Shale	351	401	Shale W/Sand Strks.	4820	4909
Sand & Shale	401	2031	Anhydrite & Red Bed	4909	4954
Bentonite & Sand	2031	2140	Lime, Red Bed & Shale	4954	4994
Sand & Shale	2140	2964	Bentonite & Red Bed	4994	5058
Bentonite & Shale	2964	3051	Bent., Red Bed, & Shale	5058	5090
Bent., Sand, & Shale	3051	3147	Lime & Shale	5090	5134
Sand & Shale	3147	3265	Anhydrite & Shale	5134	5196
Anhy., Bent., & Shale	3265	3448	Lime, Red Bed, & Shale	5196	5221
Shale	3448	3474	Lime & Shale	5221	5283
Anhy., & Red Bed	3474	2540	Anhydrite & Shale	5283	5335
Bent., Sand, & Shale	3540	3603	Red Bed & Shale	5335	5358
Sand & Shale	3603	3641	Sand & Shale	5358	5362
Bent., Sand, & Shale	3641	3717	Lime	5362	5401
Sand & Shale	3717	3782	Lime & Shale	5401	5821
Bentonite & Red Bed	3782	3810	Lime, Red Bed, & Shale	5821	5833
Bent., Sand, & Shale	3810	3905	Lime & Shale	5833	5892
Bentonite & Shale	3905	3953	Chert, Lime, & Shale	5892	5927
Bent., Sand, & Shale	3953	3987	Lime & Shale	5927	6059
Sand & Shale	3987	4100	Anhydrite & Lime	6059	6067
Red Bed & Shale	4100	4130	Chert, Lime, & Shale	6067	6100
Bentonite, Sand & Shale	4130	4174	Lime & Shale	6100	6280
Red Bed & Shale	4174	4346	Chert & Lime	6280	6300
Anhydrite & Red Bed	4346	4431	Lime & Shale	6300	6316
Red Bed & Shale	4431	4488	Lime	6316	6340
Anhydrite & Red Bed	4488	4560	Lime & Shale	6340	6368
Red Bed & Shale	4560	4627	Lime	6368	6466
			Lime & Shale	6466	6500

This is to verify that the above and foregoing is a true, correct, and complete copy of the driller's log covering the **BLANDING-FEDERAL NO. 1** according to the records of this office and the best of my knowledge and belief.

EXPLORATION DRILLING COMPANY


By *Joseph Walker*
J. R. Living
Notary Public

Subscribed and sworn to before me this 25th day of July, 1957. My commission expires April 25, 1958.

15

**STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION**

State Capitol Building
Salt Lake City 14, Utah



LOCATE WELL CORRECTLY

To be kept Confidential until _____
(Not to exceed 4 months after filing date)

LOG OF OIL OR GAS WELL

1919 Bank of Southwest Bldg.

Operating Company BREWSTER-BARTLE DRILG. CO. Address Houston 2, Texas
 Lease or Tract: Blanding-Federal INC. Field Wildcat State Utah
 Well No. 1 Sec. 25 T. 36S R. 22E Meridian S. L. B. M. County San Juan
 Location 660 ft. $\left\{ \begin{smallmatrix} N. \\ S. \end{smallmatrix} \right\}$ of S. Line and 766 ft. $\left\{ \begin{smallmatrix} E. \\ W. \end{smallmatrix} \right\}$ of E. Line of Sec. 25 Elevation 5981
(Derrick floor relative to sea level)

The information given herewith is a complete and correct record of the well and all work done thereon so far as can be determined from all available records

Signed [Signature] Title Exec. Vice President
 Date 8/15-57

The summary on this page is for the condition of the well at above date.

Commenced drilling 5-30-57, 19____ Finished drilling 7-27-57, 19____

OIL OR GAS SANDS OR ZONES

(Denote gas by G)

No. 1, from _____ to _____ No. 4, from _____ to _____
 No. 2, from _____ to _____ No. 5, from _____ to _____
 No. 3, from _____ to _____ No. 6, from _____ to _____

IMPORTANT WATER SANDS

No. 1, from _____ to _____ No. 3, from _____ to _____
 No. 2, from _____ to _____ No. 4, from _____ to _____

CASING RECORD

Size casing	Weight per foot	Threads per inch	Make	Amount	Kind of shoe	Cut and pulled from	Perforated		Purpose
							From-	To-	
13-3/8	48	H-40	Natl.	388'					surface
25 sacks cement Bridge set @ FOLLOWING INTERVALS: 2090-2040; 1940-1890; 1350-1300;									
10 sack Cement Bridge Set @ Surface									

MUDDING AND CEMENTING RECORD

Size casing	Where set	Number sacks of cement	Method used	Mud gravity	Amount of mud used
13-3/8	398	300	pump	9.6	

MARK

50

PLUGS AND ADAPTERS

Heaving plug—Material Length Depth set

Adapters—Material Size

SHOOTING RECORD

Size	Shell used	Explosive used	Quantity	Date	Depth shot	Depth cleaned out

TOOLS USED

Rotary tools were used from 0 feet to 7035 feet, and from feet to feet

Cable tools were used from feet to feet, and from feet to feet

DATES

....., 19..... Put to producing DRY HOLE....., 19.....

The production for the first 24 hours was barrels of fluid of which% was oil;% emulsion;% water; and% sediment. Gravity, °Bé.

If gas well, cu. ft. per 24 hours Gallons gasoline per 1,000 cu. ft. of gas

Rock pressure, lbs. per sq. in.

EMPLOYEES

C. C. WAGES - toolpusher....., Driller H. E. WELLS....., Driller

E. C. McCRARY....., Driller C. KRAMER....., Driller

FORMATION RECORD

FROM—	TO—	TOTAL FEET	FORMATION
6500	6570	70	Lime
6570	6587	17	Shale
6587	6605	18	Shale & Lime
6605	6639	34	Lime
6639	6656	17	Shale & Lime
6656	6885	229	Shale
6885	6957	72	Lime & Shale
6957	7035	78	Shale & Salt

[OVER]

COPY

COPY

COPY

BREWSTER-BARTLE DRILLING COMPANY

(INCORPORATED)

1919 BANK OF THE SOUTHWEST BUILDING

HOUSTON 2, TEXAS

August 19, 1957

Mr. D. F. Russell, District Engineer
U. S. Geological Survey
457 Federal Building
Salt Lake City, Utah

Dear Sir:

Attached are the following forms:

1. Four copies 9-331a, Intention to Abandon
2. Four copies 9-331a, Subsequent Report of Abandonment
3. Three copies 9-330, Log of Oil or Gas Well
4. Duplicate copies of electrical log

Please advise if any additional information is required.

We would appreciate your returning two approved copies of each form for our records.

Yours very truly,

/s/ Louise Sherrill

L3

3787 2 HAM

February 18, 1958

Brewster-Bartle Drilling Company, Inc.
1919 Bank of the Southwest Building
Houston, Texas

Attention: Executive Vice-President

Re: Well No. Elanding-Federal 1,
Sec. 25, T. 36 S, R. 22 E,
SLEM, San Juan County, Utah

Gentlemen:

This letter is to advise you that the well log for the above mentioned well has not as yet been filed with this office as required by our rules and regulations, and is now past due.

Please complete the enclosed Forms OGGC-3, Log of Oil or Gas Well, in duplicate, and forward them to this office as soon as possible.

Yours very truly,

OIL & GAS CONSERVATION COMMISSION

OLEON B. FEIGHT
SECRETARY

CBF:en

Encl.

BREWSTER-BARTLE DRILLING COMPANY

(INCORPORATED)

1919 BANK OF THE SOUTHWEST BUILDING

HOUSTON 2, TEXAS

March 4, 1958

The State of Utah
Oil & Gas Conservation Commission
Salt Lake City 14, Utah

Attention: Mr. Cleon B. Feight, Secretary

Gentlemen:

Thank you for your letter of February 18, 1958, regarding Well No. Blanding-Federal 1, Sec. 25, T-36-S, R-22-E, SLBM, San Juan County, Utah. We are indeed sorry we failed to file well log records on this well with your office. As you will note from the enclosed copy of letter to Mr. D. F. Russell, District Engineer, U. S. Geological Survey, we mailed all form to him.

Enclosed are two copies of your Form OGCC-3. You will note that we have attached certified copies of the log to a depth of 6500'. Since we only have one copy of certified log for the additional drilling to total depth we have typed it on the formation record of your form.

Please advise if any additional information is needed for your file.

Yours very truly,

Louise Sherrill

Louise Sherrill
Ass't Sec'y.

LS
encls.

BREWSTER-BARTLE DRILLING COMPANY

(INCORPORATED)

1919 BANK OF THE SOUTHWEST BUILDING

HOUSTON 2, TEXAS

June 28, 1961

The State of Utah
Oil & Gas Conservation Commission
310 Newhouse Building
10 Exchange Place
Salt Lake City 11, Utah

Attention: Ann W. Glines, Records Clerk

Gentlemen:

This will acknowledge receipt of your letter of June 22, 1961. We are sorry that you were not furnished a copy of the log on our Blanding Federal No. 1 well in San Juan County, Utah, but we assumed our partner in Denver had filed it with you. We enclose a copy of this log for your files.

Yours very truly,

Louise Sherrill

Louise Sherrill
Assistant Secretary

LS