

FILE NOTATIONS

Entered in NID File ✓
Location Map Planned ✓
Card Indexed ✓

Checked by Chief
Approval Letter
Disapproval Letter ...

COMPLETION DATA:

Date Well Completed 11/10/79

Location Inspected

W. ✓ ... WW..... TA.....
W. ✓ ... OS..... PA.....

Bond released
State or Fee Land

LOGS FILED

Driller's Log..... ✓
Electric Logs (No.) ✓
E..... I..... Dual I Lat..... GR-N..... Micro.....
BHC Sonic GR..... Lat..... MI-L..... Sonic.....
CBLog..... CCLog..... Others.....

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
 DRILL DEEPEN PLUG BACK

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 MAPCO Inc.

3. ADDRESS OF OPERATOR
 Suite 320, Plaza West
 1537 Avenue D, Billings, Montana 59120

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)
 At surface (1) 1894' FWL, 2144' FSL
 At proposed prod. zone NE SW Section 14
 Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 14 miles SW of Ouray, Utah

16. NO. OF ACRES IN LEASE
 1882.20

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.
 7400'

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
 (2) 5157' Ungraded GL

23. PROPOSED CASING AND CEMENTING PROGRAM
 (8) and (9)

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" - New	24	500'	Cement to surface
7-7/8"	5-1/2" - New	17	8390'	As required

Data required to be included on Form 9-331C by NTL-6, dated 6-1-76, as Items No. (1), (2), (4), (5), (8), (9) and (14) are so noted above. The rest as follows:

(3) and (6): Uintah - Surface Chapita Wells - 5490'
 Green River - 1260' Uteland Bts. - 6690'
 Wasatch - 4760' Mesaverde - 7890'

(7): No water anticipated; possible thin, non-commercial oil bearing zones encountered in the Green River from approximately 1200'-4800'±; no commercially productive oil bearing sands encountered in this area previously; gas bearing formations will be the Wasatch, expected intermediate overall interval from 4800'-7900'±, and the Mesaverde from 7890'± to a total depth of 8390'.

(10): Figure #1 (attached) -- Continued on back of page

NOTICE OF APPROVAL

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED J. D. Holliman TITLE Manager of Operations Northern District DATE April 13, 1978
 (This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____
 APPROVED BY (ORIG. SGD.) W. P. MARTENS TITLE ACTING DISTRICT ENGINEER DATE MAY 15 1978
 CONDITIONS OF APPROVAL, IF ANY:

CONDITIONS OF APPROVAL ATTACHED TO OPERATOR'S COPY

*See Instructions On Reverse Side

NECESSARY FLARING OF GAS DURING DRILLING AND COMPLETION APPROVED SUBJECT TO ROYALTY (NTL-4)

State O&G

Instructions

General: This form is designed for submitting proposals to perform certain well operations, as indicated, on all types of lands and leases for appropriate action by either a Federal or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable State or Federal regulations concerning subsequent work proposals or reports on the well.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on this reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal or State agency offices.

Items 15 and 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective production zone.

Item 22: Consult applicable Federal or State regulations, or appropriate officials, concerning approval of the proposal before operations are started.

(11): The well is to be drilled with a salt water mud system maintaining a weight of approximately 9#/gal with weighting material on location sufficient to weight-up for pressure control as necessary.

(12): A mud logger will be used from 4000' to TD. No drill stem tests will be run. No coring will be done. The logging program will include Dual Induction and CNL-Density Logs.

(13): As noted in #(1), no abnormal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H_2S gas.


(15): Auxiliary equipment: (a) Kelly cock
(b) Full opening valve on floor with DP Connection for use when Kelly is not in string
(c) Pit volume totalizer equipment will be used.

PROJECT

MAPCO INC.

T 10 S, R 19 E, S.L.B. & M.

Well location, RIVER BEND UNIT #11-14 E, located as shown in the NE 1/4 SW 1/4 Section 14, T 10 S, R 19 E, S.L.B. & M. Uintah County, Utah.



X = Section Corners Located



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Dana Stewart

REGISTERED LAND SURVEYOR
REGISTRATION NO 3154
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
P.O. BOX Q - 110 EAST - FIRST SOUTH
VERNAL, UTAH - 84078


SCALE 1" = 1000'	DATE 3/28/78
PARTY MS KH	REFERENCES GLO Plat
WEATHER Fair	FILE MAPCO INC.

MAPCO INC.
PROPOSED LOCATION
RIVER BEND UNIT #11-14 E

ROOSEVELT

TOPO. MAP "A"

SCALE - 1" = 4 MI.



UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

5. LEASE DESIGNATION AND SERIAL NO.
U-013792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
River Bend

#14-08-0001-16305

8. FARM OR LEASE NAME

9. WELL NO.
RBU 11-14E

10. FIELD AND POOL, OR WILDCAT
River Bend

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Section 14,
T. 10 S., R. 19 E.

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
DRILL DEEPEN PLUG BACK

b. TYPE OF WELL
OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
MAPCO Inc.

3. ADDRESS OF OPERATOR
Suite 320, Plaza West
1537 Avenue D, Billings, Montana 59120

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)
At surface (1) 1894' FWL, 2144' FSL
At proposed prod. zone NE SW Section 14
Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
14 miles SW of Ouray, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any)
1894'

16. NO. OF ACRES IN LEASE
1882.20

17. NO. OF ACRES ASSIGNED TO THIS WELL
640

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.
7400'

19. PROPOSED DEPTH
(5) 8390'

20. ROTARY OR CABLE TOOLS
(4) Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
(2) 5157' Ungraded GL

22. APPROX. DATE WORK WILL START*
(14) 7-15-78 30 days

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" - New	24	500'	Cement to surface
7-7/8"	5-1/2" - New	17	8390'	As required

Data required to be included on Form 9-331C by NTL-6, dated 6-1-76, as Items No. (1), (2), (4), (5), (8), (9) and (14) are so noted above. The rest as follows:

- (3) and (6): Uintah - Surface Chapita Wells - 5490'
- Green River - 1260' Uteland Bts. - 6690'
- Wasatch - 4760' Mesaverde - 7890'

(7): No water anticipated; possible thin, non-commercial oil bearing zones encountered in the Green River from approximately 1200'-4800'[±]; no commercially productive oil bearing sands encountered in this area previously; gas bearing formations will be the Wasatch, expected intermediate overall interval from 4800'-7900'[±], and the Mesaverde from 7890'[±] to a total depth of 8390'.

(10): Figure #1 (attached) -- Continued on back of page --

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED J. D. Holliman TITLE Manager of Operations Northern District DATE April 13, 1978

PERMIT NO. 43-047-30410 APPROVAL DATE OIL, GAS, AND MINING

APPROVED BY _____ DATE: 4-15-78

CONDITIONS OF APPROVAL, IF ANY: _____ BY: C. B. Knight

Instructions

General: This form is designed for submitting proposals to perform certain well operations, as indicated, on all types of lands and leases for appropriate action by either a Federal or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable State or Federal regulations concerning subsequent work proposals or reports on the well.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on this reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal or State agency offices.

Items 15 and 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective production zone.

Item 22: Consult applicable Federal or State regulations, or appropriate officials, concerning approval of the proposal before operations are started.

(11): The well is to be drilled with a salt water mud system maintaining a weight of approximately 9#/gal with weighting material on location sufficient to weight-up for pressure control as necessary.

(12): A mud logger will be used from 4000' to TD. No drill stem tests will be run. No coring will be done. The logging program will include Dual Induction and CNL-Density Logs.

(13): As noted in #(11), no abnormal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H₂S gas.

(15): Auxiliary equipment: (a) Kelly cock
(b) Full opening valve on floor with DP connection for use when Kelly is not in string
(c) Pit volume totalizer equipment will be used.

MAPCO INCORPORATED

13 Point Surface Use Plan

for

Well Location

River Bend Unit #11-14 E

Located In

Section 14, T10S, R19E, S.L.B. & M.

Uintah County, Utah

Mapco Incorporated
River Bend Unit #11-14 E
Section 14, T10S, R19E, S.L.B. & M.

1. EXISTING ROAD

See attached Topographic Map "A".

To reach Mapco Incorporated, well location River Bend Unit #11-14 E, located in the NE 1/4 SW 1/4 Section 14, T10S, R19E, S.L.B. & M., Uintah County, Utah; proceed Westerly out of Vernal, Utah along U.S. Highway 40, 14 miles to the junction of this road and Utah State Highway 209; proceed South along Utah State Highway 209, 7 miles more or less to the junction of this Highway and Utah State Highway 88; proceed South along Utah State Highway 88-10 miles to Ouray, Utah; proceed on South along a county road known as the Seep Ridge road 9.2 miles along the Seep Ridge to its junction with an existing dirt service road to the South known as Turkey Trail Road; proceed southerly along this road 1.7 miles to the point that it intersects an existing dirt service road to the South, known as Willow Creek road; proceed in a Southerly direction along this road 1.3 miles to the point that it intersects an existing dirt service road to the West, known as the Hill Creek road; proceed Westerly along this road 0.5 miles to the point that it intersects an existing dirt service road to the North; proceed Northerly along this service road 2.8 miles to the point that it intersects an existing dirt service road to the Northwest; proceed Northwesterly along this service road 0.8 miles to the point that it intersects an existing dirt service road to the North; proceed along this same road to the Northwest 0.8 miles to Mapco Incorporated well location River Bend Unit #11-18 F, located in Section 18, T10S, R20E, S.L.B. & M.; continue on past this well 1.1 miles to the point that it intersects an existing dirt service road to the West; proceed Westerly along this service road 1.9 miles to the point that the planned access road (to be discussed in Item #2) leaves the existing road in a Southerly direction.

The Highways mentioned in the foregoing paragraph are bituminous surfaced road to Ouray, Utah at which point the County road is surfaced with native asphalt for \pm 4 miles and then is a gravel surface to the aforementioned service roads.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing areas they are located in and range from clays to a sandy-clay shale materials.

There is no anticipated construction on any portion of the above described road. They will meet the necessary standards required to facilitate an orderly flow of traffic during the drilling phase; completion phase and the production phase of this well at such time that production is established.

The roads that are required for access during the drilling phase, completion phase, and production phase of this well, will be maintained at the standards required by the B.L.M. or other controlling agencies.

2. PLANNED ACCESS ROAD

See Topographic Map "B".

The proposed access road leaves the existing service road in the NW 1/4 Section 14, T10S, R19E, S.L.B. & M. and proceeds in a Southerly direction 0.5 miles to the proposed location site.

In order to facilitate the anticipated traffic flow necessary to drill and

PLANNED ACCESS ROAD - continued

produce this well, the following standards will be met:

This proposed access road will be an 18' crown road (9' either side of the centerline) with drain ditches along either side of the proposed road where it is determined necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area.

Back slopes along the cut areas of the road will be 1 1/2 to 1 slopes and terraced.

The road will be centerline flagged prior to the commencement of construction.

The grade of this road will vary from flat to 8%, but will not exceed this amount. This road will be constructed from native borrow accumulated during construction.

If deemed necessary by the local governmental agencies or their representatives, turnouts will be installed for safety purposes every 0.25 miles or on the top of ridges or at intervals and locations that will provide the greatest sight distance. These turnouts will be 200' in length and 10' in width and will be tapered from the shoulder of the road for a distance of 50' in length at both the access and outlet ends.

Any fences that are encountered along this access road will be cut and replaced with a cattleguard with a minimum width of 18' and a loading factor large enough to facilitate the heavy trucks required in the drilling and production of this well.

If cattleguards are to be located at existing gates, they will be installed with the above requirements and with a new gate installed at one end of the cattleguard.

The access from the road to the gate will be of such a nature that there will be no impedance of traffic flow along the main access road and no difficulties encountered by traffic utilizing the gate, either leaving or entering the proposed access road.

The vegetation along this route consists of sparse amounts of sagebrush, rabbit-brush, some grasses and cacti with large areas that are devoid of vegetation.

3. LOCATION OF EXISTING WELLS

There are other wells within a one mile radius of this location (See Topographic Map "B"). For the exact location of this well in Section 14, T10S, R19E, S.L.B. & M. see the location plat.

4. LOCATION OF TANK BATTERIES, PRODUCTION FACILITIES, AND PRODUCTION GATHERING AND SERVICE LINES

At the present time there are no other Mapco Incorporated batteries, production facilities, oil gathering lines, gas gathering lines, injection and disposal lines within a one-mile radius.

In the event that production of this well is established, then the existing area of the location will be utilized for the establishment of the necessary production facilities.

LOCATION OF TANK BATTERIES, PRODUCTION FACILITIES, AND PRODUCTION GATHERING AND SERVICE LINES - continued

This area will be built, if possible, with native materials and if these materials are not available then the necessary arrangements will be made to get them from private sources.

The total area that is needed for the production of this well will be fenced and cattleguards will be utilized for access to these facilities.

If there is any deviation from the above, then all appropriate agencies will be notified prior to construction and all necessary requests and applications will be made.

5. LOCATION AND TYPE OF WATER SUPPLY

Water to be used for the drilling and production of this well will be hauled by truck from the Green River, at a point located in the SE 1/4 of Section 18, T10S, R19E, S.L.B. & M. approximately 4.5 road miles to the West from this proposed location.

In the event that the above source is not used other arrangements will be made with the proper authorities for an alternate source.

All regulations and guidelines will be followed and no deviations will be made unless all concerned agencies are notified.

6. SOURCE OF CONSTRUCTION MATERIALS

All construction materials for this location site and access road shall be borrow materials accumulated during construction of the location site and access road. No additional road gravels or pit lining materials from other sources are anticipated at this time, but if they are required, the appropriate actions will be taken to acquire them from private sources.

The native materials that will be used in the construction of this location site and access road will consist of a sandy-clay soils and sandstone and shale materials gathered in actual construction of the road and location.

7. METHODS FOR HANDLING WASTE DISPOSAL

A reserve and burn pit shall be constructed, and at least half of the depth of the reserve pit shall be below the existing ground surface. All trash and flammable materials will be burned in the burn pit. Non-flammable materials such as cuttings, salts, chemicals, etc. will be buried in the reserve pit and covered with a minimum of four feet of earth material. Prior to the onset of drilling, the burn pit will be fenced on all four sides with a net wire, and the reserve pit will be fenced on three sides. Upon completion of drilling, the fourth side of the reserve pit will be fenced and allowed to dry completely before backfilling and reclamation are attempted. A portable chemical toilet will be supplied for human waste.

8. ANCILLARY FACILITIES

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. WELL SITE LAYOUT

See attached Location Layout Sheet.

The B.L.M. District Manager shall be notified before any construction begins on the proposed location site and road.

As mentioned in Item #7, the pits will be unlined unless it is determined by the representatives of the agencies involved that the materials are too porous and would cause contamination to the surrounding area; then the pits will be lined with a gel and any other type of material necessary to make it safe and tight.

When drilling activities commence, all work shall proceed in a neat and orderly sequence.

10. PLANS FOR RESTORATION OF SURFACE

As there is some topsoil on the location site, all topsoil shall be stripped and stockpiled. (See location layout sheet and Item #9). When all drilling and production activities have been completed, the location site and access road will be reshaped to the original contour and stockpiled topsoil spread over the disturbed area. Fences around pits are to be removed upon completion of drilling activities and all waste being contained in the trash pit shall be buried with a minimum of 4' of cover. The reserve pit will be completely fenced and allowed to dry before covering. When restoration activities have been completed, the location site and access ramp shall be reseeded with a seed mixture recommended by the B.L.M. District Manager when the moisture content of the soil is adequate for germination. The Lessee further covenants and agrees that all of said cleanup and restoration activities shall be done and performed in a diligent and most workmanlike manner and in strict conformity with the above mentioned Items #7 and #10.

11. OTHER INFORMATION

The Topography of the General Area - (See Topographic Map "A").

The area is a basin formed between the Book Cliff Mountains to the South and the Uinta Mountains to the North. The area is interlaced with numerous canyons and ridges which are extremely steep with numerous ledges formed in sandstones, conglomerates, and shale deposits. The Green River is located approximately 3 miles to the West of the location site.

The majority of the washes and streams in the area are non-perennial in nature with the only ones in the area having a year round flow being Willow Creek to the Northeast and the Green River to the West, of which the numerous washes, draws and non-perennial streams are tributaries to the Green River.

The soils of this semi-arid area are of the Uinta Formation and Duchesne River formation (the Fluvial Sandstone and Mudstone) from the Eocene Epoch and Quaternary Epoch (gravel surfaces) and the visible geologic structures consists of light brownish-gray clays (OL) to sandy soils (SM-ML) with poorly graded gravels and shales with outcrops of rock (sandstone, mudstone, conglomerates and shales).

Due to the low precipitation average, climatic conditions and the marginal types of soils, the vegetation that is found in the area is common of the semi-arid region we are located in and in the lower elevations of the Uinta Basin. It consists of, as primary flora, areas of sagebrush, rabbitbrush, some grasses and

OTHER INFORMATION - continued

cacti, and large areas of bare soils devoid of any growth. In the areas away from and in the vicinity of non-perennial streams, cottonwoods, willows, tamarack, sagebrush, rabbitbrush, grasses and cacti can be found.

The fauna of the area is sparse and consists predominately of the mule deer, coyotes, pronghorn antelope, rabbits, and varieties of small ground squirrels and other types of rodents, and various reptiles common to the area.

The birds of the area are raptors, finches, ground sparrows, magpies, crows, and jays.

The area is used by man for the primary purpose of grazing domestic livestock.

The Topography of the Immediate Area (See Topographic Map "B")

River Bend Unit #11-14 E location site sits on a relatively flat area with a small wash approximately 200' to the West of this location site.

The geologic structure of the location is of the Uintah Formation and consists of light brownish-gray sandy clay (SP-CL) with some sandstone outcrops.

The ground slopes from the South through the location to the North at approximately a 4% grade.

The location is covered with some sagebrush and grasses.

There are no occupied dwellings or other facilities of this nature in the general area.

There are no visible archaeological, historical, or cultural sites within any reasonable proximity of the proposed location site. (see Topographic Map "B").

12. LESSEE'S OPERATOR'S REPRESENTATIVE

Darwin Kulland
Mapco Incorporated
P.O. Box 1360
Roosevelt, Utah 84066

TELE: 1-801-722-4521


13. CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Mapco Incorporated and its contractors and sub-contractors in conformity with this plan and terms and conditions with this plan and the terms and conditions under which it is approved.



April 17, 1978
Date

/s/ Darwin Kulland
Darwin Kulland

MAPCO INC.
RIVER BEND UNIT #11-14 E
CUT SHEET



C
R
O
S
S
S
E
C
T
I
O
N
S



APPROX. YARDAGES
CUT - 5,337 Cu. Yds.
FILL - 4,753 Cu. Yds.


1" = 10'
1" = 50'
SCALES

MAPCO INC.
PROPOSED LOCATION
RIVER BEND UNIT #11-14 E

TOPO. MAP "B"

SCALE - 1" = 2000'

ROAD CLASSIFICATION
1963
Light-duty ————— Unimproved dirt - - - - -



United States Department of the Interior
Geological Survey
8440 Federal Building
Salt Lake City, Utah 84138

Usual Environmental Analysis

Lease No. U-013792

Operator Mapco Inc.

Well No. RBU 11-14E

Location 1894' FWL & 2144' FSL NESWSec. 14

T. 10S R. 19E

County Uintah State Utah

Field River Bend

Status: Surface Ownership Public

Minerals Public

Joint Field Inspection Date May 2, 1978

Participants and Organizations:

Howard Lemm

USGS

Steve Ellis

BLM

Steve Hale

Mapco

Gene Stewart

Uintah

Related Environmental Analyses and References:

(1)

(2)

Analysis Prepared by:

Howard Lemm
Petroleum Engineer
Billings, Montana

Date May 9, 1978

NOTED JOHN T. EVANS, JR.

Proposed Action:

On April 19, 1978, Mapco Inc. filed an Application for Permit to Drill the No. RBU11-14E development well, an 8390 foot gas test of the Mesa-verde formation located at an elevation of 5157 feet in the NESW Sec. 14 10S 19E on Federal mineral lands and BLM surface; lease No. U-013792. There was no objection raised to the wellsite nor to the access road.

A rotary rig would be used for the drilling. An adequate casing and cementing program is proposed. Fresh-water sands and other mineral-bearing formations would be protected. A Blowout Preventer would be used during the drilling of the well. The proposed pressure rating should be adequate. Details of the operator's NTL-6 10-Point Subsurface and 13-Point Surface Protection Plans are on file in the U.S.G.S. District Office in Salt Lake City, Utah, and the U.S.G.S. Norther Rocky Mountain Area Office in Casper, Wyoming. The drilling operation would begin within 75 days upon approval of the A.P.D. and would be expected to last 30 days to reach total depth and complete the well for production if hydrocarbons are discovered.

A working agreement has been reached with the BLM, controlling surface agency. Rehabilitation plans would be decided upon as the well neared completion; the Surface Management Agency would be consulted for technical expertise on those arrangements. Written concurrence of the surface managing agency is attached.

Location and Natural Setting:

The proposed drillsite is approximately 14 miles southwest of Ouray, Utah, the nearest town. There are no dwellings in the area. A fair trail runs to within 0.5 miles of the location. This well is in the River Bend field.

The overall topography consists of numerous canyons and ridges. The location is situated on a semi-flat bench area. The surface geology is the Uinta formation. The soil is light brown-gray clays and sands. No geologic hazards are known near the drillsite.

Seismic risk for the area is minor. Anticipated geologic tops are filed with the 10-Point Subsurface Protection Plan. No mining of any sort is anticipated in the area. The land is used primarily for grazing. The climate is arid with abundant sunshine, hot summers and cold winters with temperature variations on a daily and seasonal basis. Annual precipitation is approximately 9 inches. Winds are medium and steady, occurring predominately from west to east. Air mass inversions are rare.

The area eventually drains into the Green River. The depths of fresh-water formations are listed in the 10-Point Subsurface Protection Plan.

Vegetation consists of sagebrush, rabbitbrush, native grasses and cacti. Mammalian wildlife in the area include horses, antelope, deer, coyote, rabbit, prairie dog, chipmunks, small gophers, and mice. There are numerous prairie and mountain birds in the general area, including the following: Sage hen, birds of prey such as owls, and various types of hawks and falcons. Snakes and small lizards are also present on a seasonal basis. There are no known endangered or threatened plant species in the area. There are no known endangered or threatened animal species in the area.

The inspecting archaeologist, Steve Hayes of AERC of Salt Lake City, found no sites that would conflict with the proposed operation. There are no known historical, cultural or archaeological sites in the area. There are no national, state, or local parks, forests, wildlife refuges or ranges, grasslands, monuments, trails or other formally designated recreational facilities near the proposed location.

The proposed location is within the Hill Creek Planning Unit. This Environmental Assessment Record was compiled by the Bureau of Land Management, the surface managing agency of the Federal surface in the area. The study includes additional information on the environmental impact of oil and gas operations in this area and gives land use recommendations. The E.A.R. is on file in the agency's State offices and is incorporated herein by reference.

Effects on the Environment by the Proposed Action:

The wellpad would disturb approximately 2½ acres. The access road would run approximately 0.5 miles. An estimated 8 foot cut and 5 foot fill would be necessary to level the pad area. The vegetation would be removed and minor relocation of wildlife in the immediate area, particularly small rodents, would be anticipated. If the test well results in a discovery of a gas pool, additional facilities would be needed requiring no additional surface acres. Construction of flowlines would disturb long, narrow strips of the surface for a short period of time.

The mud and reserve pits would contain all fluids used during the drilling operations. The potential for gas leaks and related accidents would be present. Should a gas leak occur, the effect on the atmosphere would be extremely short-lived. If the well should be productive, precautions would be taken against such accidents. Toxic or noxious gases would not be anticipated.

Some additional erosion would be expected in the area since surface vegetation would be removed. If erosion became serious, drainage systems such as water bars and dikes would be installed to minimize the problem. There would be no tangible effect on water migration in fresh-water aquifers. The pits would be unlined. If fresh water should be available from the well, the owner or surface agency may request completion as a water well if given approval under NTL-2B.

Waterways would not be affected directly due to their distance from the site.

Noise levels would be moderately high during drilling and completion operations. Upon completion, noise levels would be infrequent and significantly less. If the area is abandoned, noise levels should return to pre-drilling levels.

Relatively heavy traffic would be anticipated during the drilling-operations phase, increasing dust levels and exhaust pollutants in the area. If the well was to be completed for production, traffic would be reduced substantially to a maintenance schedule with a corresponding decrease of dust levels and exhaust pollutants to minor levels. If the project results in a dry hole, all operations and impact from vehicular traffic would cease after abandonment. Due to the limited number of service vehicles and limited time span of their operation, the air quality would not be substantially reduced.

A trash pit would be utilized for any solid wastes generated at the site and would be buried after the completion of the operations. Sewage would be handled according to State sanitary codes. For further information, see the 13-Point Surface Plan.

The animals and vegetation of the area would be disturbed for the life of the project. If the project was to produce hydrocarbons, adjustments in habitat occupancy would be expected. At abandonment, normal rehabilitation of the area such as contouring, reseeding, etc., would be undertaken with an eventual return to the present status as outlined in the 13-Point Surface Plan.

The site is not visible from any major roads. Should the wellsite be abandoned, surface rehabilitation would be done according to the surface agency's requirements and to USGS's satisfaction. This would involve leveling, contouring, reseeding, etc., of the location and possibly the access road. If the well should produce hydrocarbons, measures would be undertaken to protect wildlife and domestic stock from the production equipment. The anticipated traffic would have a minimal impact on traffic and vehicular safety problems. Normal precautions would be employed to prevent damage or injury to ranch property and personnel. Aside from recreational activities such as hunting, the only other human conflicts that would arise in normal useage of the area would be the oil and gas operations. These would be minor, with planned precautions to limit such conflict.

The economic and environmental impact of a single well is normally somewhat negligible. But should this well discover a significant new hydrocarbon source, local, state and possibly national economies might be improved. In this instance, other development wells would be anticipated, with substantially greater environmental and economic impacts.

Alternatives to the Proposed Action:

1. Under leasing provisions, the Geological Survey has an obligation to allow mineral development if the environmental consequences are not too severe or irreversible. Upon rehabilitation of the site, the environmental effects of this action would be substantially mitigated, if not totally annulled. Permanent damage to the surface and subsurface would be prevented as much as possible under U.S.G.S. and BLM supervision with rehabilitation planning reversing almost all effects. Additionally, the growing scarcity of oil and gas should be taken into consideration. Therefore, the alternative of not proceeding with the proposed action at this time is rejected.
2. Minor relocation of the wellsite and access road or any special, restrictive stipulations or modifications to the proposed program would not significantly reduce the environmental impact. There are no severe vegetative, animal or archaeological-historical-cultural conflicts at the site. Since only a minor impact on the environment would be expected, the alternative of moving the location is rejected.

Adverse Environmental Effects which cannot be Avoided:

Surface scars resulting from construction work, wellpad and the access road would be visible for the life of the project and for a period of time after abandonment while rehabilitation is completed. The disturbed areas would not be available for grazing purposes during the project's life time. Minor relocation of wildlife, notably small rodents, in the immediate area would be anticipated. Any improvement of existing roads would be a semi-permanent effect as traffic would

continue to utilize the access road. Some erosion would be anticipated with the removal of vegetative cover. Dust levels and exhaust pollutants would increase somewhat during the construction and drilling phases of the operation. Traffic hazards, though low, would be present. Noise levels would increase during construction and drilling. The potential for gas leaks and related accidents would be present. If hydrocarbons are discovered and produced, further oil and gas development of the area would be expected to occur which would result in the extraction of an irreplaceable resource, and further negative environmental impacts.


Determination:

This requested action does not constitute a major Federal Action significantly affecting the environment in the sense of NEPA, Section 102(2)(c).


District Engineer: _____



Salt Lake City, Utah



11-14 F
NE SW Sec. 14 10S 19E
4-013792 Mapco



mapco
INC.

PRODUCTION DIVISION - NORTHERN DISTRICT

April 20, 1978



State of Utah
Department of Natural Resources
Division of Oil & Gas Conservation
1588 West North Temple
Salt Lake City, Utah 84116

Attention: Cleon Feight

Re: Application for Permit to Drill
River Bend #14-08-0001-16305

Gentlemen:

Enclosed for your information is a copy of the Application for Permit to Drill and attachments for each of the following wells:

RBU No. 11-21E	RBU No. 5-11D
RBU No. 5-12D	RBU No. 11-10E
RBU No. 11-16F	RBU No. 15-17E
RBU No. 11-23E	RBU No. 7-25B
✓ RBU No. 11-14E	RBU No. 11-19F

Very truly yours,

MAPCO Inc.

James J. Benner
Reservoir and Production Engineer

JJB/jv

Enclosures

FROM: District Geologist, Salt Lake City, Utah

TO: District Engineer, Salt Lake City, Utah

Lease No.

SUBJECT: APD supplemental stipulations

4013792

Operator: Mapco Inc

Location: NE 1/4 SW 1/4 sec. 14 T. 10S, R. 19E

Well: RBU-11-14E

Utah Co., Utah SWM

1. Operator picked tops are adequate? Yes , No . If not: The following are estimated tops of important geologic markers:

Formation	Depth	Formation	Depth
-----------	-------	-----------	-------

2. Fresh water aquifers likely to be present below surface casing? Yes , No . If yes: Surface casing program may require adjustment for protection of fresh water aquifers to a depth of approximately 3000 feet in the Green River Formation.

3. Does operator note all prospectively valuable oil and gas horizons? Yes , No . If not: The following additional horizons will be adequately logged for hydrocarbons:

Unit	Depth	Unit	Depth
------	-------	------	-------


4. Any other leasable minerals present? Yes , No . If yes: 1. Logs (Full Operator Suite *) will be run through the Parachute Creek or Green River ** at approximate depths of 1600 to 2600 feet to adequately locate and identify anticipated oil shale beds. 2. Logs (_____ *) will be run through the _____ ** at approximate depths of _____ to _____ feet to adequately locate and identify anticipated _____ beds. 3. Logs (_____ *) will be run through the _____ ** at approximate depths of _____ to _____ feet to adequately locate and identify anticipated _____ beds.

5. Any potential problems that should be brought to operators attention (e.g. abnormal temperature, pressure, incompetent beds, H₂S)? Yes , No . If yes, what?

6. References and remarks:

* From 10 pt or others as necessary. ** Members, Formations.

Date: 5/15/78

Signed: 

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

** FILE NOTATIONS **

NE SW
Sec. 14
Mesaverde

Date: April 26 -

Operator: Mappes Inc.

Well No: Ruber Bud Unit 11-14E ~~#114E~~

Location: Sec. 14 T. 10S R. 14E County: Uintah

File Prepared:
Card Indexed:

Entered on N.I.D.:
Completion Sheet:

API NUMBER: 43-047-30410

CHECKED BY:

Administrative Assistant SW

Remarks: OK Unit Well

Petroleum Engineer OK

Remarks:

Director OK

Remarks:

INCLUDE WITHIN APPROVAL LETTER:

Bond Required: OK

Survey Plat Required:

Order No.

Surface Casing Change to

Rule C-3(c), Topographic exception/company owns or controls acreage within a 660' radius of proposed site

O.K. Rule C-3

O.K. In Ruber Bud Unit

Other:

Letter Written/Approved

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT- IN-TRIP DATE*
(Other instruction re-
verse side)

Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

U-013792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

River Bend Unit

8. FARM OR LEASE NAME

9. WELL NO.

RBU 11-14E

10. FIELD AND POOL, OR WILDCAT

River Bend

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Section 14,
T. 10 S., R. 19 E.

12. COUNTY OR PARISH 13. STATE

Uintah Utah

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR
MAPCO PRODUCTION COMPANY

3. ADDRESS OF OPERATOR Suite 320, Plaza West
1537 Ave. D., Billings, Montana 59102

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.)
At surface

NE SW Section 14 1894' FWL & 2144' FSL

14. PERMIT NO.
43-047-30410

15. ELEVATIONS (Show whether DF, RT, GR, etc.)
5157' Ungraded GL

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	Lay Flowline <input checked="" type="checkbox"/>

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Lay flowline as shown in red on Attachment #1. For details of flowline please see attached cover letter to E. W. Guynn dated March 2, 1979. The relationship of the wellhead with respect to the surface installations is shown on Attachment 2G.

18. I hereby certify that the foregoing is true and correct

SIGNED James J. Sumner

Production and Reservoir
TITLE Engineer

DATE March 2, 1979


(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:


TITLE _____

DATE _____

ATTACHMENT 2G



Tie-down Diagram



UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPPLICATE*
(Other instructions on reverse side)

Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

U-013792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL GAS WELL OTHER

7. UNIT AGREEMENT NAME

River Bend Unit

2. NAME OF OPERATOR

MAPCO PRODUCTION COMPANY

8. FARM OR LEASE NAME

3. ADDRESS OF OPERATOR Suite 320, Plaza West
1537 Ave. D., Billings, Montana 59102

9. WELL NO.

RBU 11-14E

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.)
At surface

NE SW Section 14 1894' FWL & 2144' FSL

10. FIELD AND POOL, OR WILDCAT

River Bend

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Section 14,
T. 10 S., R. 19 E.

14. PERMIT NO.

43-047-30410

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

5157' Ungraded GL

12. COUNTY OR PARISH

Uintah

13. STATE

Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF
FRACTURE TREAT
SHOOT OR ACIDIZE
REPAIR WELL
(Other)

PULL OR ALTER CASING
MULTIPLE COMPLETE
ABANDON*
CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF
FRACTURE TREATMENT
SHOOTING OR ACIDIZING
(Other)

REPAIRING WELL
ALTERING CASING
ABANDONMENT*

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

CHANGE OF CASING PROGRAM:

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
(1) 17-1/2"	13-3/8" New	48	120'	Cement to Surface
(2) 12-1/4"	8-5/8" NEW	24	3250'	Cement to Surface
(3) 7-7/8"	5-1/2" NEW	17	8500'	As required

APPROVED BY THE DIVISION OF
OIL, GAS, AND MINING

DATE: 3-19-79

BY: M. J. Minder

18. I hereby certify that the foregoing is true and correct

SIGNED

James J. Benna

TITLE

Petroleum Engineer

DATE March 14, 1979

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY
(FORM 9-329)
(2/76)
OMB 42-RO 356

MONTHLY REPORT
OF
OPERATIONS

Lease No. U-013792
Communitization Agreement No. NA
Field Name NA
Unit Name RIVER BEND UNIT
Participating Area NA
County UINTAH State UTAH
Operator MAPCO PRODUCTION COMPANY
 Amended Report

The following is a correct report of operations and production (including status of all unplugged wells) for the month of April, 1979

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	*Barrels of Oil	*MCF of Gas	*Barrels of Water	Remarks
11-14E	14-NE SW	10S	19E	DRG	0	0	0	0	Drilling well. Spud date: April 17, 1979.

*If none, so state.

DISPOSITION OF PRODUCTION (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLS)	Gas (MCF)	Water (BBLS)
*On hand, Start of Month	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Produced	<u>0</u>	<u>0</u>	<u>0</u>
*Sold	_____	_____	XXXXXXXXXXXXXXXXXX
*Spilled or Lost	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Flared or Vented	XXXXXXXXXXXXXXXXXX	_____	XXXXXXXXXXXXXXXXXX
*Used on Lease	_____	_____	XXXXXXXXXXXXXXXXXX
*Injected	_____	_____	_____
*Surface Pits	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX	_____
*Other (Identify)	_____	_____	_____
*On hand, End of Month	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*API Gravity/BTU Content	_____	_____	XXXXXXXXXXXXXXXXXX
Authorized Signature: <u><i>J. M. [Signature]</i></u>	Address: <u>1537 Ave. D., Suite 320, Billings, MT</u>		
Title: <u>Secretary</u>	Page _____	of _____	59102

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

(FORM 9-329)
(2/76)


OMB 42-RO 356

MONTHLY REPORT
OF
OPERATIONS

The following is a correct report of operations and production (including status of all unplugged wells) for the month of May, 1979.

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).



Lease No. U-013792
Communitization Agreement No. NA
Field Name NA
Unit Name RIVER BEND UNIT
Participating Area NA
County UINTAH State UTAH
Operator MAPCO PRODUCTION COMPANY
 Amended Report

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	*Barrels of Oil	*MCF of Gas	*Barrels of Water	Remarks
11-14E	14-NE SW	10S	19E	DRG	0	0	0	0	Drilling well. Rig released 5-11-79. Waiting on Completion.

*If none, so state.

DISPOSITION OF PRODUCTION (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLs)	Gas (MCF)	Water (BBLs)
*On hand, Start of Month		XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Produced	0	0	0
*Sold			XXXXXXXXXXXXXXXXXX
*Spilled or Lost		XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Flared or Vented	XXXXXXXXXXXXXXXXXX		XXXXXXXXXXXXXXXXXX
*Used on Lease			XXXXXXXXXXXXXXXXXX
*Injected			
*Surface Pits	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX	
*Other (Identify)			
*On hand, End of Month		XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*API Gravity/BTU Content			XXXXXXXXXXXXXXXXXX

Authorized Signature: J. M. Vogt Address: 1537 Ave. D., Suite 320, Billings, MT
Title: Secretary Page of 59102

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPPLICATE*
(Other instructions on re-
verse side)

Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

U-013792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR

MAPCO PRODUCTION COMPANY

3. ADDRESS OF OPERATOR Suite 320, Plaza West
1537 Ave. D., Billings, Montana 59102

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

NE SW Section 14 1894' FWL & 2144" FSL

7. UNIT AGREEMENT NAME

River Bend Unit

8. FARM OR LEASE NAME

9. WELL NO.

RBU 11-14E

10. FIELD AND POOL, OR WILDCAT

River Bend

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Section 14,
T. 10 S., R. 19 E.

14. PERMIT NO.

43-047-30410

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

5157' Ungraded GL

12. COUNTY OR PARISH

Uintah

13. STATE

Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other) Lay Flowline

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

The flowline was laid according to the Sundry Notice of Intent that was approved May 18, 1979.

18. I hereby certify that the foregoing is true and correct

SIGNED Richard Baumann

TITLE Engineering Technician

DATE 8-1-79

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____

DATE _____



SCOTT M. MATHESON
Governor

OIL, GAS, AND MINING BOARD

GORDON E. HARMSTON
Executive Director,
NATURAL RESOURCES

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES

CHARLES R. HENDERSON
Chairman

CLEON B. FEIGHT
Director

DIVISION OF OIL, GAS, AND MINING

1588 West North Temple

Salt Lake City, Utah 84116

(801) 533-5771

JOHN L. BELL
C. RAY JUVELIN
THADIS W. BOX
CONSTANCE K. LUNDBERG
EDWARD T. BECK
E. STEELE McINTYRE

December 28, 1979

Mapco Inc.
Suite #320 Plaza West
1537 Ave. D
Billings, Montana 59102

RE: SEE ATTACHED SHEET FOR WELLS.

Gentlemen:

This letter is to advise you that the Well Completion or Recompletion Report and Log for the above referred to well is due and has not been filed with this office as required by our rules and regulations.

Please complete the enclosed Form OGC-3, in duplicate, and forward them to this office as soon as possible.

Thank you for your cooperation relative to the above.

Very truly yours,

DIVISION OF OIL, GAS, AND MINING

DEBBIE BEAUREGARD
CLERK-TYPIST

ATTACHMENT SHEET.

- 1) River Bend Unit# 11-10E
Sec. 10, T. 10S, R. 19E,
Uintah County, Utah
- 2) River Bend Unit# 11-14E
Sec. 14, T. 10S, R. 19E,
Uintah County, Utah
- 3) River Bend Unit# 11-21E
Sec. 21, T. 10S, R. 19E,
Uintah County, Utah
- 4) River Bend Unit# 11-23E
Sec. 23, T. 10S, R. 19E,
Uintah County, Utah
- 5) River Bend Unit# 11-36B
Sec. 36, T. 9S, R. 19E,
Uintah County, Utah

**UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY**

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

Form approved.
Budget Bureau No. 42-R355.5

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL: OIL WELL GAS WELL DRY Other _____

b. TYPE OF COMPLETION: NEW WELL WORK OVER DEEP-EN PLUG BACK DIFF. RESVR. Other _____

2. NAME OF OPERATOR MAPCO PRODUCTION COMPANY
Alpine Executive Center

3. ADDRESS OF OPERATOR 1643 Lewis Ave., Suite 202
Billings, MT 59102

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface 1894' FWL & 2144' FSL, NE SW Section 14
At top prod. interval reported below
At total depth Same

5. LEASE DESIGNATION AND SERIAL NO.
U-013792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
River Bend
14-08-0001-16035

8. FARM OR LEASE NAME

9. WELL NO.
RBU 11-14E

10. FIELD AND POOL, OR WILDCAT

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA
Sec. 14, T. 10 S., R. 19 E.

14. PERMIT NO. 43-047-30410 **DATE ISSUED** 4-25-78

12. COUNTY OR PARISH Uintah **13. STATE** Utah

15. DATE SPUDED 4-17-79 **16. DATE T.D. REACHED** 5-8-79 **17. DATE COMPL. (Ready to prod.)** 11-10-79 **18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*** 5157' Ungraded G.L. **19. ELEV. CASINGHEAD**

20. TOTAL DEPTH, MD & TVD 8621' **21. PLUG, BACK T.D., MD & TVD** 8540' **22. IF MULTIPLE COMPL., HOW MANY*** 4 **23. INTERVALS DRILLED BY** Rotary **ROTARY TOOLS** Rotary **CABLE TOOLS**

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*
8424'-8267' Mesaverde 6408'-5923' Chapita Wells
7293'-7296' Uteland Buttes 5418'-5191' Upper Wasatch

25. WAS DIRECTIONAL SURVEY MADE No

26. TYPE ELECTRIC AND OTHER LOGS RUN Dual LateroLog, CNL, Sonic and F-log **27. WAS WELL CORED** No

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
13-3/8"	48#	125'	17-1/2"	150 sacks	
8-5/8"	24#	3292'	12-1/4"	1616 sacks	
5-1/2"	17#, 15.5#		7-7/8"	1681 sacks	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-3/8"	8328'	none

31. PERFORATION RECORD (Interval, size and number)
SEE ATTACHMENT

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED

33.* PRODUCTION

DATE FIRST PRODUCTION 11-10-79 **PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)** Flowing **WELL STATUS (Producing or shut-in)** Producing

DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
11-18-79	24	12/64"	→	0	1079	TSTM	NA

FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	WATER-OIL RATIO	WATER-GAS RATIO
1450 psi	1450 psi	→	0	1079	TSTM	NA	NA

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)
Sold

35. LIST OF ATTACHMENTS
1 - Perforation Record

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Richard Brumann TITLE Engineering Technician

DIVISION OF OIL, GAS & MINING
DATE 1-23-80

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 33.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments. **Items 22 and 24:** If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool. **Item 33:** Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

FORMATION	TOP	BOTTOM	TOP
<p>37. SUMMARY OF POROUS ZONES: SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES</p>			<p>38. GEOLOGIC MARKERS</p>
<p>DESCRIPTION, CONTENTS, ETC.</p>	<p>MEAS. DEPTH</p>	<p>TRUE VERT. DEPTH</p>	<p>NAME</p>
	<p>4740' 5414' 6488' 7916' 8621'</p>		<p>Wasatch Chapita Wells Uteland Buttes Mesaverde T.D.</p>

RIVER BEND UNIT NO. 11-14E
 MAPCO PRODUCTION COMPANY
 COMPLETION REPORT
 ATTACHMENT

PERFORATION RECORD		ACID, SHOT, FRACTURE, CEMENT SQUEEZE	
INTERVAL AND DEPTH	SIZE	NO.	AMOUNT AND KIND OF MATERIAL USED
8424-8416, 8360-8354, 8273-8267 Mesaverde	.34"	20	2000 gals HCl, 79,000 gals gelled H ₂ O, 115,000# 20-40 sand.
7293-7298 Uteland Buttes	.48"+	6	1000 gals 15% HCl, 13,600 gals gelled H ₂ O, 24,565# 20-40 sand.
6408-6402, 6290-6287, 6249-6246, 6242-6241, 5969-5966, 5956-5952, 5926-5923. Chapita Wells	.34"+	28	2500 gals 15% HCl, 71,650 gals gelled H ₂ O, 145,000# 10-20 sand.
5418-5191 Wasatch	.34"+	15	1500 gals 15% HCl, 25,700 gals gelled H ₂ O, 58,000# 10-20 sand.
			Open-ended tubing at 8328'.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other

2. NAME OF OPERATOR MAPCO PRODUCTION COMPANY
Alpine Executive Center

3. ADDRESS OF OPERATOR 1643 Lewis Ave., Suite 202
Billings, MT 59102

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: NE SW 1894' FWL & 2144' FSL
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH: SAME

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input checked="" type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input checked="" type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) <input type="checkbox"/>	<input type="checkbox"/>

5. LEASE U-013792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME River Bend Unit

8. FARM OR LEASE NAME

9. WELL NO. 11-14E

10. FIELD OR WILDCAT NAME River Bend

11. SEC., T., R., M. OR BLK. AND SURVEY OR AREA Section 14,
T. 10 S., R. 19 E.

12. COUNTY OR PARISH Uintah 13. STATE Utah


14. API NO. 43-047-30410

15. ELEVATIONS (SHOW DF, KDB, AND WD) 5157' Ungraded GL

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

SEE ATTACHED REPORT



Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Richard Baumann TITLE Engineering Tech DATE 2-12-80
Richard Baumann

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other

2. NAME OF OPERATOR MAPCO PRODUCTION COMPANY
Alpine Executive Center

3. ADDRESS OF OPERATOR 1643 Lewis Ave., Suite 202
Billings, MT 59102

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: NE SW 1894' FWL & 2144' FSL
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH: SAME

5. LEASE
U-013792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
River Bend Unit

8. FARM OR LEASE NAME

9. WELL NO.
11-14E

10. FIELD OR WILDCAT NAME
River Bend

11. SEC., T., R., M. OR BLK. AND SURVEY OR AREA
Section 14,
T. 10 S., R. 19 E.

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

14. API NO.
43-047-30410

15. ELEVATIONS (SHOW DF, KDB, AND WD)
5157' Ungraded GL

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF	<input type="checkbox"/>		<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>		<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>		<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>		<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>		<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>		<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>		<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>		<input type="checkbox"/>
(other) <u>Build improved production facilities</u>			

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

MAPCO intends to build improved production facilities at the RBU 11-14E. Please see attached diagram for details.

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 6-15-81
BY: M. J. Minder

JUN 8 1981

DIVISION OF
OIL, GAS & MINING

Subsurface Safety Valve: Manu. and Type _____

18. I hereby certify that the foregoing is true and correct

SIGNED Richard Baumann TITLE Engineering Tech. DATE 6-3-81

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:


RBU 11-14E

Proposed Production Facilities
Production to go to tanks after passing through dehydrator. When tanks are full fire tube heater in the tank will be started and the water drained to the pit.

Top View

160' from well to dehydrator

All flowlines and tanks insulated





CNG PRODUCING COMPANY
TULSA DIVISION

RECEIVED

FEB 22 1985

February 15, 1985

**DIVISION OF OIL
& GAS & MINING**

State of Utah
Division of Oil, Gas and Mining
335 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

Re: Transfer of Ownership and
Operations
Oil and Gas Wells
State of Utah

Gentlemen:

This letter is to inform you that:

CNG Producing Company
705 S. Elgin Ave., P. O. Box 2115
Tulsa, Oklahoma 74101-2115

has acquired the ownership and operations of oil and gas wells formerly
owned and operated by:

MAPCO Oil & Gas Company
Tulsa, Oklahoma

Attached is a listing of wells involved in the transfer. Should
there be any question regarding this matter, I may be contacted at
(918)599-4005.

Sincerely,

Greg Bechtol
Sr. Engineering Technician

GB/sr
Attachment



CNG PRODUCING COMPANY
TULSA DIVISION

RECEIVED

FEB 27 1985

February 25, 1985

**DIVISION OF OIL
GAS & MINING**

State of Utah
Division of Oil & Gas Mining
355 W. North Temple
3 Triad Center - Suite 350
Salt Lake City, Utah 84180-1203

Gentlemen:

Effective January 1, 1985, CNG Producing Company, New Orleans, LA., purchased the oil and gas properties of MAPCO Oil & Gas Company located in the state of Utah. Attached is a list of the properties sold for which CNG will now be responsible.

Please direct any future correspondence concerning these wells to the address shown below:

CNG Producing Company - Tulsa Division
P. O. Box 2115
Tulsa, OK 74101-2115
Attention: Joe C. Lineback

Yours truly,

Joe C. Lineback.
Manager of Accounting

JCL/cf

Attachment


RIVER BEND UNIT NO. 14-08-0001-16035
 UINTAH COUNTY, UTAH

Status of All Wells Located Within the River Bend Unit

<u>Well Name</u>	<u>Location</u>	<u>Status</u>
1. OSC No. 1	SE NW Sec. 17-T10S-R20E	Water supply well
2. OSC No. 2	NW SE Sec. 3-T01S-R20E	Suspended gas well
3. OSC No. 3	SW NE Sec. 10-T10S-R20E	Plugged & abandoned
4. OSC No. 4	NW NE Sec. 30-T 9S-R20E	Suspended gas well
5. OSC No. 4A	NW NE Sec. 30-T 9S-R20E	Suspended gas well
6. OSC No. 5	NE NE Sec. 2-T10S-R18E	Producing oil well
7. Natural 1-2	SE NW Sec. 2-T10S-R20E	Plugged & abandoned
8. OSC No. 7-15	SW NW Sec. 15-T10S-R19E	Producing gas well
9. RBU 11-16E	NE SW Sec. 16-T10S-R19E	Producing gas well
10. RBU 11-18F	NE SW Sec. 18-T10S-R20E	Producing gas well
11. RBU 11-13E	NE SW Sec. 13-T10S-R19E	Producing gas well
12. RBU 7-21F	SW NE Sec. 21-T10S-R20E	Producing gas well
13. RBU 11-15F	NE SW Sec. 15-T10S-R20E	Producing gas well
14. RBU 11-19F	NE SW Sec. 19-T10S-R20E	Producing gas well
15. RBU 11-10E	NE SW Sec. 10-T10S-R19E	Producing gas well
16. RBU 11-23E	NE SW Sec. 23-T10S-R19E	Producing gas well
17. RBU 11-21E	NE SW Sec. 21-T10S-R19E	Producing oil well
18. RBU 11-14E	NE SW Sec. 14-T10S-R19E	Producing gas well
19. RBU 11-16F	NE SW Sec. 16-T10S-R20E	Producing gas well
20. RBU 11-36B	NE SW Sec. 36-T 9S-R19E	Plugged & abandoned
21. FED 7-25B	SW NE Sec. 25-T 9S-R19E	Producing oil well
22. RBU 7-11F	SW NE Sec. 11-T10S-R20E	Producing gas well
23. RBU 11-17F	NE SW Sec. 17-T10S-R20E	Suspended gas well
24. RBU 5-11D	SW NW Sec. 11-T10S-R18E	Producing gas well
25. RBU 11-22E	NE SW Sec. 22-T10S-R19E	Producing gas well
26. RBU 4-11D	NW NW Sec. 11-T10S-R18E	Producing oil well
27. RBU 15-23F	SW SE Sec. 23-T10S-R20E	Plugged & abandoned
28. RBU 11-3F	NE SW Sec. 3-T10S-R20E	Producing gas well
29. RBU 11-2F	NE SW Sec. 2-T10S-R20E	Producing oil well
30. RBU 7-22F	SW NE Sec. 22-T10S-R20E	Producing gas well
31. RBU 8-14F	SE NE Sec. 14-T10S-R20E	Producing gas well
32. RBU 6-20F	SE NW Sec. 20-T10S-R20E	Producing gas well
33. RBU 11-24E	NE SW Sec. 24-T10S-R19E	Producing gas well
34. RBU 7-10F	SW NE Sec. 10-T10S-R20E	Producing gas well
35. RBU 1-10E	NE NE Sec. 10-T10S-R19E	Producing gas well
36. RBU 1-15E	NE NE Sec. 15-T10S-R19E	Producing gas well
37. RBU 1-22E	NE NE Sec. 22-T10S-R19E	Producing gas well
38. RBU 1-14E	NE NE Sec. 14-T10S-R19E	Producing gas well
39. RBU 1-23E	NE NE Sec. 23-T10S-R19E	Producing gas well
40. RBU 2-11D	NW NE Sec. 11-T10S-R18E	Producing oil well
41. RBU 4-19F	NW NW Sec. 19-T10S-R20E	Producing gas well
42. RBU 16-3F	SE SE Sec. 3-T10S-R20E	Producing gas well
43. RBU 13-11F	SW SW Sec. 11-T10S-R20E	Producing gas well
44. RBU 16-16F	SE SE Sec. 16-T10S-R20E	Producing gas well
45. RBU 6-2D	SE NW Sec. 2 T10S-R18E	Producing oil well



42-381 50 SHEETS 5 SQUARE
42-382 100 SHEETS 5 SQUARE
42-389 200 SHEETS 5 SQUARE
NATIONAL
MANUFACTURING CO.



This Well is in computer
under Meseverde + should
be in under WS-MSV.

-It is comingled + does
not affect the cum.

M.A.P.

R.B.U 11-14E

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number
U 13792

7. Indian Allottee or Tribe Name

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new well, deepen existing wells, or to reenter plugged and abandoned wells.

Use APPLICATION FOR PERMIT - for such proposals.

8. Unit or Communization Agreement

River Bend Unit
14-08-0001-16035

1. Type of Well
 Oil Well Gas Well Other (specify)

9. Well Name and Number

RBU 11-14E

2. Name of Operator
CNG Producing Company

10. API Well Number
43-047-30410

3. Address of Operator
1450 Poydras St., New Orleans, LA 70112-6000

4. Telephone Number
(504) 593-7260

11. Field and Pool, or Wildcat

5. Location of Well

Footage : 1,894' FWL & 2,144' FSL
QQ, SEC., T., R., M.: NE SW of Sec. 14-T10S-R19E

County : Uintah
State : UTAH

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other | |

- | | |
|--|---|
| <input type="checkbox"/> Abandonment * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other | Annual Status Report |

Approximate Date Work Will Start

Date of Work Completion

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

STATUS OF WELL

Shut-in

EXPLANATION FOR STATUS OF WELL

Under evaluation

FUTURE PLANS

Possible workover or recompletion



FEB 06 1992

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name & Signature Scott Childress Title Supervisor, Prod. Engineering
W. Scott Childress

Date January 31, 1992

(State Use Only)


**CNG Producing
Company**

A **CNG** COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

November 6, 1995

Mr. Wayne Bankert
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078



RE: Subsequent Report for
Plunger Lift Installations

Dear Wayne:

Prior to our conversation of last week it was not apparent that a Subsequent Sundry Notice must be filed for plunger lift installation on our wells. We have gone back through our files and would like to submit notice that plunger lift installations were completed on several RBU wells. Enclosed please find Sundry Notices for these wells.

We will be installing plunger lifts on several more RBU wells in the near future. As these operations are completed I will send in subsequent reports on those wells also.

Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, Scot Childress at (504) 593-7574.

Sincerely,

Susan H. Sachitana
Susan H. Sachitana
Coordinator, Regulatory Reports

Enclosure

cc: Frank Matthews - Utah Department of Oil, Gas & Mining
N. Decker
M. Hall
S. Childress
RBU Well Files

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FOIA APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

5. Lease Designation and Serial No.
U-013792

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator


CNG PRODUCING COMPANY

3. Address and Telephone No.

CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Surface - 1,894' FWL & 2,144' FSL of Sec. 14-T10S-



7. Unit or CA, Agreement Designation

River Bend Unit

8. Well Name and No.

W-14E

9. API Well No.

43-047-30410

10. Field and Pool, or Exploratory Area

Island

11. County or Parish, State

Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

Notice of Intent

Abandonment

Change of Plans

Subsequent Report

Recompletion

New Construction

Final Abandonment Notice

Plugging Back

Non-Routine Fracturing

Casing Repair

Water Shut-Off

Altering Casing

Conversion to Injection

Other - Plunger Lift

Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Installed plunger lift equipment on above well. Well on plunger.

14. I hereby certify that the forgoing is true and correct

Signed

Scot Childress

Title

Supervisor, Production Eng.

Date

November 2, 1995

Scot Childress

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

34



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
U-01470-A et al
(UT-932)

JUN 2 2000

NOTICE

Dominion Exploration & Production, Inc. : Oil and Gas Leases
1450 Poydras Street :
New Orleans, LA 70112-6000 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of CNG Producing Company to Dominion Exploration & Production, Inc. on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from your list of leases and a list of leases obtained from our automated records system. We have not abstracted the lease files to determine if the entity affected by the name change holds an interest in the leases identified nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interests. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

The following lease on your list is closed on the records of this office: U-029277.

Due to the name change, the name of the principal on the bond is required to be changed from CNG Producing Company to Dominion Exploration & Production, Inc. on Bond No. 524 7050 (BLM Bond No. WY1898). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to the Wyoming State Office.

/s/ Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure
Exhibit of Leases

RECEIVED

JUN 05 2000

DIVISION OF
OIL, GAS AND MINERAL
REVENUE

cc: Wyoming State Office
New Mexico State Office
Moab Field Office
Vernal Field Office
MMS-Reference Data Branch, MS 3130, Box 5860, Denver, CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114-5801
Irene Anderson (UT-932)
Teresa Thompson (UT-931)
LaVerne Steah (UT-942)

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well : OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: VARIOUS
2. Name of Operator: DOMINION EXPLORATION & PRODUCTION, INC.	6. If Indian, Allottee or Tribe Name:
3. Address and Telephone Number: 1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-7260	7. Unit Agreement Name:
4. Location of Well Footages: QQ, Sec, T., R., M.:	8. Well Name and Number: VARIOUS
	9. API Well Number
	10. Field and Pool, or Wildcat: Natural Buttes 630


County: UINTAH
State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (SUBMIT IN DUPLICATE)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon	<input type="checkbox"/> Abandon*
<input type="checkbox"/> Repair Casing	<input type="checkbox"/> Repair Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Change of Plans
<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Convert to Injection
<input type="checkbox"/> Fracture Treat or Acidize	<input type="checkbox"/> Fracture Treat or Acidize
<input type="checkbox"/> Multiple Completion	<input checked="" type="checkbox"/> Other
<input type="checkbox"/> Other	
	<u>OPERATOR NAME CHANGE FOR WELLS</u>
Approximate date work will start _____	Date of work completion _____
	Report results of Multiple Completion and Recompletion to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.
	*Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)


Please be advised that effective April 12, 2000, CNG Producing Company has changed its name to Dominion Exploration & Production, Inc. and would like to transfer the well permits into the name of Dominion Exploration & Production, Inc. Our new bond has been filed and is pending approval with the State of Utah. The bond number is 76S 63050 361.


John R. Lewis
Sr. Vice-President - CNG Producing Company

RECEIVED

JUN 29 2000

DIVISION OF
OIL, GAS AND MINING

13. Name & Signature:  Title: Sr. Vice-President - Dominion Expl. & Prod., Inc. Date: June 26, 2000

(This space for State use only)

Dominion Exploration & Production, Inc.
1450 Poydras Street, New Orleans, LA 70112-6000
Phone: 504-593-7000



June 27, 2000

Mr. Jimmy Thompson
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Name Change Documentation for CNG Producing Company

Dear Mr. Thompson:

CNG Producing Company has become Dominion Exploration & Production, Inc. effective April 12, 2000. Enclosed please find a sundry regarding the name change with an attached listing of all the permits in the name of CNG Producing Company to be changed to Dominion Exploration & Production, Inc. Also enclosed please find a Form UIC 5 for the Transfer of Authority to Inject for the Federal #1-26B well.

If you have any questions or require any additional information, please contact me at (504) 593-7260.

Sincerely,

DOMINION EXPLORATION & PRODUCTION, INC.

Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Nelda Decker

RECEIVED

JUN 29 2000

**DIVISION OF
OIL, GAS AND MINING**



State of Utah
DEPARTMENT OF COMMERCE
Division of Corporations & Commercial Code

552894
CO 106990
File Number

Check Appropriate Box	
<input checked="" type="checkbox"/>	Foreign Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Non-Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Limited Partnership \$25.00
<input type="checkbox"/>	Foreign Limited Liability Company \$35.00

Application To Amend The CERTIFICATE OF AUTHORITY OR REGISTRATION of

CNG Producing Company
Business Entity Name

Delaware
Name of Home State

I. AMENDING THE BUSINESS NAME

The business name is changed to: Dominion Exploration & Production, Inc.

The corporation shall use as its name in Utah: Dominion Exploration & Production, Inc.

(The corporation shall use its name as set forth on #1, unless this name is not available)

NOTE: If the business name has changed its name in the home state, a copy of the Certificate of Amendment or a certified copy of the amendment must accompany this application.

Check the following:

- The name of the corporation is changing its name in Utah to the new name of the corporation in the home state.
- The name of the corporation is being changed in Utah to comply with Utah State Insurance Regulations.

II. AMENDING THE DURATION OF THE BUSINESS EXISTENCE

The businesses period of duration is changed to: _____

III. AMENDING THE STATE OR COUNTRY OF INCORPORATION/REGISTRATION

The corporation's state or country of incorporation/registration is changed to: _____

IV. Other: _____

(Limited Partnership changing General Partners, Limited Companies changing Members or Managers. Change of statement who is managing, etc. Use an attached sheet if needed.)

Under penalties of perjury, I declare this Application to Amend the Certificate of Authority or Registration to be, to the best of my knowledge and belief, true and correct.

Signature

Vice President & Corporate Secretary
Title

April 20, 2000
Date

State of Utah
Department of Commerce
Division of Corporations and Commercial Code

I hereby certify that the foregoing has been filed and approved on this 25 day of April, 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner

Date



JOHNSON
Director

Date: 04/25/2000

Receipt Number: 22156

Amount Paid: \$50.00

STATE OF UTAH
DIVISION OF CORPORATIONS
AND COMMERCIAL CODE
160 East 300 South / Box 146705
Salt Lake City, UT 84114-6705
Service Center: (801) 530-4849
Web Site: <http://www.commerce.state.ut.us>

FILED

APR 25 2000

Well Name	Api Well Code	Operator Name	Production Status	Lease Type
EVANS FEDERAL #32-25	4304732406	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-25B	4304732445	DOMINION EXPLORATION & PR	LA	BLM
RBU #5-25B	4304732453	DOMINION EXPLORATION & PR	LA	BLM
RBU #11-25B	4304732482	DOMINION EXPLORATION & PR	LA	BLM
RBU #16-14EO	4304732507	DOMINION EXPLORATION & PR	LA	BLM
RBU #8-23EO	4304732508	DOMINION EXPLORATION & PR	LA	BLM
RBU #8-14EO	4304732514	DOMINION EXPLORATION & PR	LA	BLM
RBU #15-13EO	4304732599	DOMINION EXPLORATION & PR	LA	BLM
RBU #9-23EO	4304732601	DOMINION EXPLORATION & PR	LA	BLM
STATE #2-36E	4304732979	DOMINION EXPLORATION & PR	PR	STATE
STATE #2-36E	4304732979	DOMINION EXPLORATION & PR	PR	STATE
STATE #1-36E	4304733181	DOMINION EXPLORATION & PR	PR	STATE
RBU #1-16F	4304733360	DOMINION EXPLORATION & PR	DR	STATE
RBU #5-3F	4304733361	DOMINION EXPLORATION & PR	FUT	BLM
RBU #5-16F	4304733363	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-23F	4304733367	DOMINION EXPLORATION & PR	DR	BLM
EVANS FEDERAL #15-26E	4304733508	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #9-26E	4304733509	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #10-25E	4304733510	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #14-25E	4304733511	DOMINION EXPLORATION & PR	FUT	BLM
FEDERAL #13-30B	4304733581	DOMINION EXPLORATION & PR	FUT	BLM
STATE #13-36A	4304733598	DOMINION EXPLORATION & PR	FUT	STATE
RBU #1-1D	4304733599	DOMINION EXPLORATION & PR	FUT	BLM
OSC #1-17 *	430472030800S1	DOMINION EXPLORATION & PR	SIEC	BLM
OSC #2 *	430473008700S1	DOMINION EXPLORATION & PR	PR	BLM
OSC #4 *	430473011300S1	DOMINION EXPLORATION & PR	TA	BLM
OSC #4A-30 *	430473012200S1	DOMINION EXPLORATION & PR	SIEC	BLM
OSC #7-15E *	430473021100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-16E	430473026000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #11-18F	430473026600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-13E	430473037400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-15F	430473037500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-21F	430473037600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-19F	430473040500S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL #7-25B	430473040600S01	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-10E	430473040800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-11D	430473040900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-14E	430473041000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-23E	430473041100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-16F	430473041200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-17F	430473058400S1	DOMINION EXPLORATION & PR	PA	BLM
RBU #7-11F	430473058500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-16D	4304730608	DOMINION EXPLORATION & PR	PA	STATE
FEDERAL #7-25A	430473062400S01	DOMINION EXPLORATION & PR	PA	BLM
RBU #11-3F	430473068900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-22E	430473069800S1	DOMINION EXPLORATION & PR	PA	BLM
RBU #4-11D	430473071800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-23F	4304730719	DOMINION EXPLORATION & PR	PA	BLM
RBU #7-3E	430473072000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-24E	430473075900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-2F	430473076000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #7-10F	430473076100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #6-20F	430473076200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-22F	430473076800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-14F	430473082500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #2-11D	430473082600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-3F	430473088700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-15E	430473091500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-14E	430473092600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-22E	430473092700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-23E	430473097000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #4-19F	430473097100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-11F	430473097300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-10E	430473104600S1	DOMINION EXPLORATION & PR	PR	BLM

PGW


BLM

BLM

BLM

BLM

BLM



BLM

BLM

BLM

BLM

BLM

BLM

BLM

BLM

1-CDW	4-KAS ✓
2-CDW ✓	5-SJ ✓
3-JLT	6-FILE

OPERATOR CHANGE WORKSHEET

Check each listed item when completed. Write N/A if item is not applicable.

Change of Operator (Well Sold) Designation of Agent
X Operator Name Change Only Merger

The operator of the well(s) listed below has changed, effective: 4-12-00

TO:(New Operator) DOMINION EXPL & PROD INC.
 Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000
 Phone: 1-(504)-593-7000
 Account No. N1095

FROM:(Old Operator) CNG PRODUCING COMPANY
 Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000
 Phone: 1-(504)-593-7000
 Account No. N0605

WELL(S):	CA Nos.	or	RIVER BEND	Unit
Name: <u>RBU 8-23EO</u>	API: <u>43-047-32508</u>	Entity: <u>99998</u>	S <u>23</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013766</u>
Name: <u>RBU 16-14EO</u>	API: <u>43-047-32507</u>	Entity: <u>99998</u>	S <u>14</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013792</u>
Name: <u>RBU 15-13EO</u>	API: <u>43-047-32599</u>	Entity: <u>99998</u>	S <u>13</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013765</u>
Name: <u>RBU 9-23EO</u>	API: <u>43-047-32601</u>	Entity: <u>99998</u>	S <u>23</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013766</u>
Name: <u>RBU 5-3F</u>	API: <u>43-047-33361</u>	Entity: <u>99999</u>	S <u>03</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013767</u>
Name: <u>RBU 5-16F</u>	API: <u>43-047-33363</u>	Entity: <u>7052</u>	S <u>16</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-7206</u>
Name: <u>RBU 10-23F</u>	API: <u>43-047-33367</u>	Entity: <u>7050</u>	S <u>23</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-01470-A</u>
Name: <u>RBU 11-18F</u>	API: <u>43-047-30266</u>	Entity: <u>7050</u>	S <u>18</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013793</u>
Name: <u>RBU 11-13E</u>	API: <u>43-047-30374</u>	Entity: <u>7050</u>	S <u>13</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013765</u>
Name: <u>RBU 11-15F</u>	API: <u>43-047-30375</u>	Entity: <u>7050</u>	S <u>15</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-7206</u>
Name: <u>RBU 7-21F</u>	API: <u>43-047-30376</u>	Entity: <u>7050</u>	S <u>21</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013793-A</u>
Name: <u>RBU 11-19F</u>	API: <u>43-047-30405</u>	Entity: <u>7050</u>	S <u>19</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013769-A</u>
Name: <u>RBU 11-10E</u>	API: <u>43-047-30408</u>	Entity: <u>7050</u>	S <u>10</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013792</u>
Name: <u>RBU 5-11D</u>	API: <u>43-047-30409</u>	Entity: <u>9005</u>	S <u>11</u> T <u>10S</u> R <u>18E</u>	Lease: <u>U-013818-A</u>
Name: <u>RBU 11-14E</u>	API: <u>43-047-30410</u>	Entity: <u>7050</u>	S <u>14</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013792</u>
Name: <u>RBU 11-23E</u>	API: <u>43-047-30411</u>	Entity: <u>7050</u>	S <u>23</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013766</u>
Name: <u>RBU 11-17F</u>	API: <u>43-047-30584</u>	Entity: <u>7050</u>	S <u>17</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013769-C</u>

OPERATOR CHANGE DOCUMENTATION

- YES 1. A pending operator change file has been set up.
- YES 2. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator on 6-29-00.
- YES 3. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 6-29-00.
- YES 4. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? **Yes/No** If yes, the company file number is SEE ATTACHED. If no, Division letter was mailed to the new operator on _____.

- YES 5. **Federal and Indian Lease Wells.** The BLM or the BIA has approved merger, name change or operator change for all wells listed above involving Federal or Indian leases on 6-2-00.
- N/A 6. **Federal and Indian Units.** The BLM or the BIA has approved the successor of unit operator for all wells listed above involving unit operations on _____.
- N/A 7. **Federal and Indian Communitization Agreements ("CA").** The BLM or the BIA has approved the operator change for all wells listed above involved in the CA on _____.
- N/A 8. **Underground Injection Control ("UIC") Program.** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project and/or for the water disposal well(s) listed above.
- YES 9. Changes have been entered in the **Oil and Gas Information System** for each well listed on 7-26-00.
- YES 10. Changes have been included on the **Monthly Operator Change letter** on 7-26-00.

STATE BOND VERIFICATION

- N/A 1. State Well(s) covered by Bond No. _____.

FEE WELLS - BOND VERIFICATION / LEASE INTEREST OWNER NOTIFICATION

- N/A 1. (R649-3-1) The **NEW** operator of any fee lease well(s) listed above has furnished a proper bond.
- N/A 2. A **copy of this form** has been placed in the **new and former operator's bond files** on _____.
- N/A 3. The **FORMER** operator has requested a release of liability from their bond as of todays date _____? If yes, Division response was made to this request by letter dated _____, (see bond file).
- N/A 4. (R649-2-10) The **Former** operator of any Fee lease wells listed above has been contacted and informed by letter dated _____, of their responsibility to notify all interest owners of this change.
- N/A 5. Bond information added to **RBDMS** on _____.
- N/A 6. Fee wells attached to bond in **RBDMS** on _____.

FILMING

- ____ 1. All attachments to this form have been **microfilmed** on 2.22.01.

FILING

- ____ 1. **Originals/Copies** of all attachments pertaining to each individual well have been filed in each **well file**.
- ____ 2. The **original of this form** has been filed in the operator file and a copy in the old operator file.

COMMENTS

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING
1. DJJ
2. CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

7/1/2007

FROM: (Old Operator): N1095-Dominion Exploration & Production, Inc 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134 Phone: 1 (405) 749-1300	TO: (New Operator): N2615-XTO Energy Inc 810 Houston St Fort Worth, TX 76102 Phone: 1 (817) 870-2800
--	--

WELL NAME	CA No.	SEC	TWN	RNG	Unit:	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LIST										

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/6/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/6/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/6/2007
- a. Is the new operator registered in the State of Utah: Business Number: 5655506-0143
- b. If **NO**, the operator was contacted on: _____
- a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA
- Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: _____
- Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: _____
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 9/27/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/27/2007
- Bond information entered in RBDMS on: 9/27/2007
- Fee/State wells attached to bond in RBDMS on: 9/27/2007
- Injection Projects to new operator in RBDMS on: 9/27/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/27/2007

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000138
- Indian well(s) covered by Bond Number: n/a
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 104312762
- b. The **FORMER** operator has requested a release of liability from their bond on: 1/23/2008
 The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

		5. LEASE DESIGNATION AND SERIAL NUMBER:
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: SEE ATTACHED
2. NAME OF OPERATOR: XTO Energy Inc. <i>N2615</i>		9. API NUMBER: SEE ATTACHED
3. ADDRESS OF OPERATOR: 810 Houston Street CITY: Fort Worth STATE TX ZIP 76102		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective July 1, 2007, XTO Energy Inc. has purchased the wells listed on the attachment from:

Dominion Exploration & Production, Inc. *N1095*
14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134

James D. Abercrombie (405) 749-1300
James D. Abercrombie
Sr. Vice President, General Manager - Western Business Unit

Please be advised that XTO Energy Inc. is considered to be the operator on the attached list and is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands. Bond coverage is provided by Nationwide BLM Bond #104312750 and Department of Natural Resources Bond #104312762.

NAME (PLEASE PRINT) <u>Edwin S. Ryan, Jr.</u>	TITLE <u>Sr. Vice President - Land Administration</u>
SIGNATURE <i>Edwin S. Ryan, Jr.</i>	DATE <u>7/31/2007</u>

(This space for State use only)

APPROVED 9127107
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED
AUG 06 2007
DIV. OF OIL, GAS & MINING

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr	qtr	sec	twp	rng	lease_num	entity	Lease	well	stat
4304730087	OSCU 2	NWSE	03	100S	200E	U-037164	7050	Federal	GW	P	
4304730266	RBU 11-18F	NESW	18	100S	200E	U-013793	7050	Federal	GW	P	
4304730374	RBU 11-13E	NESW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304730375	RBU 11-15F	NESW	15	100S	200E	U-7206	7050	Federal	GW	P	
4304730376	RBU 7-21F	SWNE	21	100S	200E	U-013793-A	7050	Federal	GW	P	
4304730405	RBU 11-19F	NESW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304730408	RBU 11-10E	NESW	10	100S	190E	U-013792	7050	Federal	GW	P	
4304730410	RBU 11-14E	NESW	14	100S	190E	U-013792	7050	Federal	GW	P	
4304730411	RBU 11-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304730412	RBU 11-16F	NESW	16	100S	200E	U-7206	7050	Federal	GW	P	
4304730585	RBU 7-11F	SWNE	11	100S	200E	U-01790	7050	Federal	GW	P	
4304730689	RBU 11-3F	NESW	03	100S	200E	U-013767	7050	Federal	GW	P	
4304730720	RBU 7-3E	SWNE	03	100S	190E	U-013765	7050	Federal	GW	P	
4304730759	RBU 11-24E	NESW	24	100S	190E	U-013794	7050	Federal	GW	P	
4304730761	RBU 7-10F	SWNE	10	100S	200E	U-7206	7050	Federal	GW	P	
4304730762	RBU 6-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P	
4304730768	RBU 7-22F	SWNE	22	100S	200E	14-20-H62-2646	7050	Indian	GW	P	
4304730887	RBU 16-3F	SESE	03	100S	200E	U-037164	7050	Federal	GW	P	
4304730915	RBU 1-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	P	
4304730926	RBU 1-14E	NENE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304730927	RBU 1-22E	NENE	22	100S	190E	U-013792	7050	Federal	GW	P	
4304730970	RBU 1-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304730971	RBU 4-19F	NWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304730973	RBU 13-11F	SWSW	11	100S	200E	U-7206	7050	Federal	WD	A	
4304731046	RBU 1-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	S	
4304731115	RBU 16-16F	SESE	16	100S	200E	U-7206	7050	Federal	GW	P	
4304731140	RBU 12-18F	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P	
4304731141	RBU 3-24E	NENW	24	100S	190E	U-013794	7050	Federal	GW	P	
4304731143	RBU 3-23E	NENW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304731144	RBU 9-23E	NESE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304731145	RBU 9-14E	NESE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304731160	RBU 3-15E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P	
4304731161	RBU 10-15E	NWSE	15	100S	190E	U-013766	7050	Federal	GW	P	
4304731176	RBU 9-10E	NESE	10	100S	190E	U-013792	7050	Federal	GW	P	
4304731196	RBU 3-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304731252	RBU 8-4E	SENE	04	100S	190E	U-013792	7050	Federal	GW	P	
4304731322	RBU 1-19F	NENE	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304731323	RBU 5-10E	SWNW	10	100S	190E	U-013792	7050	Federal	GW	P	
4304731369	RBU 3-13E	NENW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304731518	RBU 16-3E	SESE	03	100S	190E	U-035316	7050	Federal	GW	P	
4304731519	RBU 11-11F	NESW	11	100S	200E	U-7206	7050	Federal	GW	P	
4304731520	RBU 1-17F	NENE	17	100S	200E	U-013769-B	7050	Federal	GW	P	
4304731605	RBU 9-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	P	
4304731606	RBU 3-22E	NENW	22	100S	190E	U-013792	7050	Federal	GW	P	
4304731607	RBU 8-24E	SENE	24	100S	190E	U-013794	7050	Federal	GW	P	
4304731608	RBU 15-18F	SWSE	18	100S	200E	U-013794	7050	Federal	GW	P	

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr	qtr	sec	twp	rng	lease_num	entity	Lease	well	stat
4304731613	RBU 5-11F	SWNW	11	100S	200E	U-7206	7050	Federal	GW	P	
4304731615	RBU 4-22F	NWNW	22	100S	200E	U-0143521-A	7050	Federal	GW	S	
4304731652	RBU 6-17E	SWNW	17	100S	190E	U-03535	7050	Federal	GW	P	
4304731715	RBU 5-13E	SWNW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304731717	RBU 13-13E	SWSW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304731739	RBU 9-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P	
4304732033	RBU 13-14E	SWSW	14	100S	190E	U-013792	7050	Federal	GW	P	
4304732037	RBU 11-3E	NESW	03	100S	190E	U-013765	7050	Federal	GW	P	
4304732038	RBU 6-18F	SENE	18	100S	200E	U-013769	7050	Federal	GW	P	
4304732040	RBU 15-24E	SWSE	24	100S	190E	U-013794	7050	Federal	GW	P	
4304732041	RBU 5-14E	SWNW	14	100S	190E	U-013792	7050	Federal	GW	P	
4304732050	RBU 12-20F	NWSW	20	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732051	RBU 7-13E	SWNE	13	100S	190E	U-013765	7050	Federal	GW	P	
4304732070	RBU 16-19F	SESE	19	100S	200E	U-013769-A	7050	Federal	WD	A	
4304732071	RBU 9-22E	NESE	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732072	RBU 15-34B	SWSE	34	090S	190E	U-01773	7050	Federal	GW	P	
4304732073	RBU 11-15E	NESW	15	100S	190E	U-013766	7050	Federal	GW	P	
4304732074	RBU 13-21F	SWSW	21	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732075	RBU 10-22F	NWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P	
4304732081	RBU 9-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732082	RBU 15-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304732083	RBU 13-24E	SWSW	24	100S	190E	U-013794	7050	Federal	GW	P	
4304732095	RBU 3-21E	NENW	21	100S	190E	U-013766	7050	Federal	GW	P	
4304732103	RBU 15-17F	SWSE	17	100S	200E	U-013769-C	7050	Federal	GW	P	
4304732105	RBU 13-19F	SWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304732107	RBU 1-21E	NENE	21	100S	190E	U-013766	7050	Federal	GW	P	
4304732128	RBU 9-21E	NESE	21	100S	190E	U-013766	7050	Federal	GW	P	
4304732129	RBU 9-17E	NESE	17	100S	190E	U-03505	7050	Federal	GW	P	
4304732133	RBU 13-14F	SWSW	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732134	RBU 9-11F	NESE	11	100S	200E	U-7206	7050	Federal	GW	P	
4304732138	RBU 5-21F	SWNW	21	100S	200E	U-013793	7050	Federal	GW	P	
4304732146	RBU 1-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P	
4304732149	RBU 8-18F	SENE	18	100S	200E	U-013769	7050	Federal	GW	P	
4304732153	RBU 13-23E	SWSW	23	100S	190E	U-13766	7050	Federal	GW	P	
4304732154	RBU 5-24E	SWNW	24	100S	190E	U-013794	7050	Federal	GW	P	
4304732156	RBU 5-14F	SWNW	14	100S	200E	U-013793A	7050	Federal	GW	P	
4304732166	RBU 7-15E	SWNE	15	100S	190E	U-013766	7050	Federal	GW	P	
4304732167	RBU 15-13E	SWSE	13	100S	190E	U-013765	7050	Federal	GW	P	
4304732189	RBU 13-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P	
4304732190	RBU 15-10E	SWSE	10	100S	190E	U-013792	7050	Federal	GW	P	
4304732191	RBU 3-17FX	NENW	17	100S	200E	U-013769-C	7050	Federal	GW	P	
4304732197	RBU 13-15E	SWSW	15	100S	190E	U-013766	7050	Federal	GW	P	
4304732198	RBU 7-22E	SWNE	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732199	RBU 5-23E	SWNW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304732201	RBU 13-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	S	
4304732211	RBU 15-15E	SWSE	15	100S	190E	U-013766	7050	Federal	GW	P	

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr	qtr	sec	twp	rng	lease_num	entity	Lease	well	stat
4304732213	RBU 5-19F	SWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304732217	RBU 9-17F	NESE	17	100S	200E	U-013769-C	7050	Federal	GW	P	
4304732219	RBU 15-14E	SWSE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304732220	RBU 5-3E	SWNW	03	100S	190E	U-03505	7050	Federal	GW	P	
4304732228	RBU 9-3E	NESE	03	100S	190E	U-035316	7050	Federal	GW	P	
4304732239	RBU 7-14E	SWNE	14	100S	190E	U-103792	7050	Federal	GW	P	
4304732240	RBU 9-14F	NESE	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732242	RBU 5-22E	SWNW	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732263	RBU 8-13E	SENE	13	100S	190E	U-013765	7050	Federal	GW	P	
4304732266	RBU 9-21F	NESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732267	RBU 5-10F	SWNW	10	100S	200E	U-7206	7050	Federal	GW	P	
4304732268	RBU 9-10F	NESE	10	100S	200E	U-7206	7050	Federal	GW	P	
4304732269	RBU 4-15F	NWNW	15	100S	200E	INDIAN	7050	Indian	GW	PA	
4304732270	RBU 14-22F	SESW	22	100S	200E	U-0143519	7050	Federal	GW	P	
4304732276	RBU 5-21E	SWNW	21	100S	190E	U-013766	7050	Federal	GW	P	
4304732289	RBU 7-10E	SWNE	10	100S	190E	U-013792	7050	Federal	GW	P	
4304732290	RBU 5-17F	SWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P	
4304732293	RBU 3-3E	NENW	03	100S	190E	U-013765	7050	Federal	GW	P	
4304732295	RBU 13-22E	SWSW	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732301	RBU 7-21E	SWNE	21	100S	190E	U-013766	7050	Federal	GW	P	
4304732309	RBU 15-21F	SWSE	21	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732310	RBU 15-20F	SWSE	20	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732312	RBU 9-24E	NESE	24	100S	190E	U-013794	7050	Federal	GW	P	
4304732313	RBU 3-20F	NENW	20	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732315	RBU 11-21F	NESW	21	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732317	RBU 15-22E	SWSE	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732328	RBU 3-19FX	NENW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304732331	RBU 2-11F	NWNE	11	100S	200E	U-01790	7050	Federal	GW	P	
4304732347	RBU 3-11F	NENW	11	100S	200E	U-7206	7050	Federal	GW	P	
4304732391	RBU 2-23F	NWNE	23	100S	200E	U-013793-A	7050	Federal	GW	S	
4304732392	RBU 11-14F	NESW	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732396	RBU 3-21F	NENW	21	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732407	RBU 15-14F	SWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732408	RBU 4-23F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732415	RBU 3-10EX (RIG SKID)	NENW	10	100S	190E	UTU-035316	7050	Federal	GW	P	
4304732483	RBU 5-24EO	SWNW	24	100S	190E	U-013794	11719	Federal	OW	S	
4304732512	RBU 8-11F	SENE	11	100S	200E	U-01790	7050	Federal	GW	P	
4304732844	RBU 15-15F	SWSE	15	100S	200E	14-20-H62-2646	7050	Indian	GW	P	
4304732899	RBU 3-14F	NENW	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732900	RBU 8-23F	SENE	23	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732901	RBU 12-23F	NWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P	
4304732902	RBU 1-15F	NENE	15	100S	200E	U-7260	7050	Federal	GW	S	
4304732903	RBU 3-15F	NENW	15	100S	200E	U-7260	7050	Federal	GW	P	
4304732904	RBU 9-15F	NESE	15	100S	200E	U-7260	7050	Federal	GW	P	
4304732934	RBU 3-10F	NENW	10	100S	200E	U-7206	7050	Federal	GW	P	
4304732969	RBU 11-10F	NESW	10	100S	200E	U-7206	7050	Federal	GW	P	

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304732970	RBV 12-15F	NWSW	15	100S	200E	U-7206	7050	Federal	GW	P
4304732971	RBV 15-16F	SWSE	16	100S	200E	U-7206	7050	Federal	GW	S
4304732972	RBV 1-21F	NENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304732989	RBV 13-10E	SWSW	10	100S	190E	U-013792	7050	Federal	GW	P
4304732990	RBV 13-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304732991	RBV 6-19F	SEW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733033	RBV 7-23E	NWNE	23	100S	190E	U-013766	7050	Federal	GW	P
4304733034	RBV 9-18F	NESE	18	100S	200E	U-013794	7050	Federal	GW	P
4304733035	RBV 14-19F	SEW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733087	RBV 6-23F	SEW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304733088	RBV 1-10F	NENE	10	100S	200E	U-7206	7050	Federal	GW	P
4304733089	RBV 8-22F	SENE	22	100S	200E	U-0143521	7050	Federal	GW	P
4304733090	RBV 11-22F	NESW	22	100S	200E	U-0143519	7050	Federal	GW	P
4304733091	RBV 16-22F	SESE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304733156	RBV 4-14E	NWNW	14	100S	190E	U-013792	7050	Federal	GW	P
4304733157	RBV 7-19F	SWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733158	RBV 7-20F	SWNE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304733159	RBV 7-24E	SWNE	24	100S	190E	U-013794	7050	Federal	GW	P
4304733160	RBV 8-15E	SENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304733161	RBV 16-10E	SESE	10	100S	190E	U-013792	7050	Federal	GW	P
4304733194	RBV 2-14E	NWNE	14	100S	190E	U-013792	7050	Federal	GW	P
4304733272	RBV 13-3F	SWSW	03	100S	200E	U-013767	7050	Federal	GW	P
4304733361	RBV 5-3F	SWNW	03	100S	200E	U-013767	7050	Federal	GW	P
4304733362	RBV 15-10F	SWSE	10	100S	200E	U-7206	7050	Federal	GW	P
4304733363	RBV 5-16F	SWNW	16	100S	200E	U-7206	7050	Federal	GW	P
4304733365	RBV 12-14E	NWSW	14	100S	190E	U-013792	7050	Federal	GW	P
4304733366	RBV 5-18F	SWNW	18	100S	200E	U-013769	7050	Federal	GW	P
4304733367	RBV 10-23F	NWSE	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304733368	RBV 14-23F	SEW	23	100S	200E	U-01470-A	7050	Federal	GW	S
4304733424	RBV 5-20F	SWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304733643	RBV 2-13E	NWNE	13	100S	190E	U-013765	7050	Federal	GW	P
4304733644	RBV 4-13E	NWNW	13	100S	190E	U-013765	7050	Federal	GW	P
4304733714	RBV 4-23E	NWNW	23	100S	190E	U-013766	7050	Federal	GW	P
4304733715	RBV 6-13E	SEW	13	100S	190E	U-013765	7050	Federal	GW	P
4304733716	RBV 10-14E	NWSE	14	100S	190E	U-013792	7050	Federal	GW	P
4304733838	RBV 8-10E	SENE	10	100S	190E	U-013792	7050	Federal	GW	P
4304733839	RBV 12-23E	NWSW	23	100S	190E	U-013766	7050	Federal	GW	P
4304733840	RBV 12-24E	NWSW	24	100S	190E	U-013794	7050	Federal	GW	P
4304733841	RBV 14-23E	SEW	23	100S	190E	U-013766	7050	Federal	GW	P
4304734302	RBV 1-23F	NENE	23	100S	200E	UTU-013793-A	7050	Federal	GW	P
4304734661	RBV 16-15E	SESE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734662	RBV 10-14F	NWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304734663	RBV 6-14E	SEW	14	100S	190E	U-013792	7050	Federal	GW	P
4304734670	RBV 8-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304734671	RBV 4-24E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304734701	RBV 12-11F	SEW	11	100S	200E	U-7206	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304734702	RBU 2-15E	NWNE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734703	RBU 4-17F	NWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734745	RBU 10-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734749	RBU 7-18F	SWNE	18	100S	200E	U-013769	7050	Federal	GW	P
4304734750	RBU 12-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P
4304734810	RBU 10-13E	NWSE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734812	RBU 1-24E	NENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734826	RBU 12-21F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734828	RBU 4-15E	NWNW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734844	RBU 14-14E	SESW	14	100S	190E	U-013792	7050	Federal	GW	P
4304734845	RBU 10-24E	NWSE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734888	RBU 4-21E	NWNW	21	100S	190E	U-013766	7050	Federal	GW	P
4304734889	RBU 16-24E	SESE	24	100S	190E	U-13794	7050	Federal	GW	P
4304734890	RBU 12-18F2	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734891	RBU 10-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304734892	RBU 8-22E	SENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304734906	RBU 6-22E	SENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304734907	RBU 2-24E	NWNE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734910	RBU 4-16F	NWNW	16	100S	200E	U-7206	7050	Federal	GW	P
4304734911	RBU 12-19F	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734912	RBU 14-20F	SESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734942	RBU 1-22F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304734945	RBU 8-19F	SENE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734946	RBU 8-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304734962	RBU 12-17F	NWSW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734963	RBU 2-17F	NWNE	17	100S	200E	U-013769-C	14117	Federal	GW	P
4304734966	RBU 14-18F	SESW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734967	RBU 10-18F	NWSE	18	100S	200E	U-013794	7050	Federal	GW	P
4304734968	RBU 10-19F	NWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734969	RBU 10-3E	NWSE	03	100S	190E	U-035316	7050	Federal	GW	P
4304734970	RBU 12-3E	NWSW	03	100S	190E	U-013765	7050	Federal	GW	P
4304734971	RBU 15-3E	SWSE	03	100S	190E	U-35316	7050	Federal	GW	P
4304734974	RBU 12-10E	NWSW	10	100S	190E	U-013792	14025	Federal	GW	P
4304734975	RBU 14-10E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734976	RBU 16-13E	SESE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734977	RBU 8-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304734978	RBU 6-15E	SENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734979	RBU 12-15E	NWSW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734981	RBU 16-17E	SESE	17	100S	190E	U-013766	7050	Federal	GW	P
4304734982	RBU 8-21E	SENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304734983	RBU 4-22E	NWNW	22	100S	190E	U-013792	7050	Federal	GW	P
4304734986	RBU 2-20F	NWNE	20	100S	200E	U-03505	7050	Federal	GW	P
4304734987	RBU 9-20E	SWNW	21	100S	190E	U-03505	7050	Federal	GW	P
4304734989	RBU 7-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P
4304734990	RBU 8-20E	SWNW	21	100S	190E	U-03505	14164	Federal	GW	P
4304735041	RBU 16-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304735042	RBU 12-22E	NWSW	22	100S	190E	U-013792	14165	Federal	GW	P
4304735058	RBU 7-23F	SWNE	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304735059	RBU 12-13E	NWSW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735060	RBU 14-13E	SESW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735061	RBU 2-22E	NWNE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735062	RBU 6-24E	SESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304735082	RBU 4-17E	NWNW	17	100S	190E	U-03505	7050	Federal	GW	P
4304735086	RBU 16-14E	NENE	23	100S	190E	U-013792	7050	Federal	GW	P
4304735087	RBU 2-3E	NWNE	03	100S	190E	U-013765	7050	Federal	GW	P
4304735088	RBU 6-3E	SESW	03	100S	190E	U-03505	7050	Federal	GW	P
4304735100	RBU 10-10E	NWSE	10	100S	190E	U-013792	7050	Federal	GW	P
4304735101	RBU 16-22E	SESE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735112	RBU 14-24E	SESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304735129	RBU 6-21F	SESW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735170	RBU 1-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P
4304735171	RBU 16-9E	NESE	09	100S	190E	U-013765	7050	Federal	GW	P
4304735232	RBU 14-21F	SESW	21	100S	200E	U-0143520	7050	Federal	GW	P
4304735250	RBU 13-19F2	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735251	RBU 15-19F	SWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735270	RBU 16-21E	SESE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735304	RBU 13-20F	SWSW	20	100S	200E	U-013769	7050	Federal	GW	P
4304735305	RBU 4-21F	NWNW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735306	RBU 16-21F	SESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304735468	RBU 15-22F	SWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304735469	RBU 11-23F	SESW	23	100S	200E	U-01470A	7050	Federal	GW	P
4304735549	RBU 1-14F	NENE	14	100S	200E	UTU-013793-A	7050	Federal	GW	P
4304735640	RBU 2-21E	NWNE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735644	RBU 10-17E	NWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304735645	RBU 12-21E	NWSW	21	100S	190E	U-013766	7050	Federal	GW	P
4304736200	RBU 8-17E	SWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736201	RBU 15-17EX	SWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736293	RBU 2-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	P
4304736294	RBU 6-10E	NENW	10	100S	190E	U-013792	7050	Federal	GW	P
4304736296	RBU 6-21E	SESW	21	100S	190E	U-013766	7050	Federal	GW	P
4304736297	RBU 10-22E	NWSE	22	100S	190E	U-013792	7050	Federal	GW	P
4304736318	RBU 14-22E	SESW	22	100S	190E	U-013792	7050	Federal	GW	P
4304736427	RBU 9-15E	NESE	15	100S	190E	U-013766	7050	Federal	GW	DRL
4304736428	RBU 2-17E	NWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736429	RBU 1-17E	NENE	17	100S	190E	U-013766	7050	Federal	GW	DRL
4304736432	RBU 3-19F2	NWNW	19	100S	200E	U-013769-A	15234	Federal	GW	P
4304736433	RBU 14-17F	SESW	17	100S	200E	U-03505	7050	Federal	GW	P
4304736434	RBU 2-19F	NWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304736435	RBU 5-19FX	SWNW	19	100S	200E	U-013769-A	15855	Federal	GW	P
4304736436	RBU 4-20F	NWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304736605	RBU 16-14F	SESE	14	100S	200E	U-013793A	7050	Federal	GW	P
4304736608	RBU 4-3E	NWNW	03	100S	190E	U-035316	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr	qtr	sec	twp	rng	lease_num	entity	Lease	well	stat
4304736609	RBU 8-3E	SENE	03	100S	190E	U-013765	7050	Federal	GW	P	
4304736610	RBU 14-3E	SESW	03	100S	190E	U-013765	7050	Federal	GW	P	
4304736686	RBU 13-3E	NWSW	03	100S	190E	U-013765	15235	Federal	GW	P	
4304736810	RBU 1-3E	NENE	03	100S	190E	U-013765	7050	Federal	GW	DRL	
4304736850	RBU 2-10F	NWNE	10	100S	200E	U-7206	7050	Federal	GW	P	
4304736851	RBU 8-21F	SENE	21	100S	200E	U-013793-A	7050	Federal	GW	P	
4304737033	RBU 4-10E	SWNW	10	100S	190E	U-035316	7050	Federal	GW	P	
4304737057	RBU 11-17E	NWSE	17	100S	190E	U-03505	7050	Federal	GW	DRL	
4304737058	RBU 3-17E	NENW	17	100S	190E	U-03505	7050	Federal	GW	P	
4304737201	RBU 3-23F	NENW	23	100S	200E	U-013793-A	7050	Federal	OW	P	
4304737341	RBU 11-20F	NESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304737342	RBU 5-15F	SWNW	15	100S	200E	U-7206	7050	Federal	OW	P	
4304737343	RBU 10-16F	NWSE	16	100S	200E	U-7206	7050	Federal	OW	P	
4304737344	RBU 9-16F	NESE	16	100S	200E	U-7206	7050	Federal	OW	S	
4304737450	RBU 14-17E	SESW	17	100S	190E	U-03505	7050	Federal	GW	P	
4304737747	RBU 15-9E	NWNE	16	100S	190E	U-013765	7050	Federal	GW	DRL	
4304737893	RBU 9-4EA	SENE	04	100S	190E	U-03505	7050	Federal	GW	P	
4304737998	RBU 13-23F	SWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P	
4304738181	RBU 12-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL	
4304738182	RBU 11-4E	SE/4	04	100S	190E	U-03505	99999	Federal	GW	DRL	
4304738294	RBU 2-4E	NWNE	04	100S	190E	U-013792	7050	Federal	GW	DRL	
4304738295	RBU 5-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL	
4304738543	RBU 28-18F	NESE	13	100S	190E	U 013793-A	7050	Federal	GW	DRL	
4304738548	RBU 32-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	DRL	
4304738555	RBU 27-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL	
4304738556	RBU 27-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL	
4304738557	RBU 30-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P	
4304738558	RBU 29-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL	
4304738595	RBU 31-10E	NENE	15	100S	190E	U-013792	7050	Federal	GW	DRL	
4304738596	RBU 17-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	DRL	
4304738780	RBU 8B-17E	SENE	17	100S	190E	U-013766	7050	Federal	GW	DRL	

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304730153	NATURAL 1-2	SENW	02	100S	200E	ML-10716	11377	State	OW	PA
4304730260	RBU 11-16E	NESW	16	100S	190E	ML-13214	7050	State	GW	S
4304730583	RBU 11-36B	NESW	36	090S	190E	ML-22541	99998	State	NA	PA
4304730608	RBU 8-16D	SENE	16	100S	180E	ML-13216	99998	State	NA	PA
4304730760	RBU 11-2F	NESW	02	100S	200E	ML-10716	9966	State	OW	S
4304731740	RBU 1-16E	NENE	16	100S	190E	ML-13214	7050	State	GW	P
4304732026	RBU 16-2F	SESE	02	100S	200E	ML-10716	7050	State	GW	P
4304732042	RBU 9-16E	NESE	16	100S	190E	ML-13214	7050	State	GW	P
4304732108	RBU 14-2F	SESW	02	100S	200E	ML-10716	7050	State	GW	P
4304732136	RBU 8-2F	SENE	02	100S	200E	ML-10716	7050	State	GW	P
4304732137	RBU 5-16E	SWNW	16	100S	190E	ML-13214	7050	State	GW	P
4304732245	RBU 7-16E	SWNE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732250	RBU 13-16E	SWSW	16	100S	190E	ML-13214	7050	State	GW	S
4304732292	RBU 15-16E	SWSE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732314	RBU 10-2F	NWSE	02	100S	200E	ML-10716	7050	State	GW	P
4304732352	RBU 3-16F	NENW	16	100S	200E	ML-3393-A	7050	State	GW	P
4304733360	RBU 1-16F	NENE	16	100S	200E	ML-3393	7050	State	GW	P
4304734061	RBU 6-16E	SWNE	16	100S	190E	ML-13214	7050	State	GW	P
4304734167	RBU 1-2F	NENE	02	100S	200E	ML-10716		State	GW	LA
4304734315	STATE 11-2D	NESW	02	100S	180E	ML-26968		State	GW	LA
4304734903	RBU 14-16E	SWSW	16	100S	190E	ML-13214	7050	State	D	PA
4304735020	RBU 8-16E	SENE	16	100S	190E	ML-13214	7050	State	GW	P
4304735021	RBU 10-16E	SWSE	16	100S	190E	ML-13214	7050	State	GW	P
4304735022	RBU 12-16E	NESW	16	100S	190E	ML-13214	7050	State	GW	P
4304735023	RBU 16-16E	SWSW	15	100S	190E	ML-13214	7050	State	GW	P
4304735033	RBU 2-16E	NWNE	16	100S	190E	ML-13214	7050	State	GW	P
4304735081	RBU 15-2F	SWSE	02	100S	200E	ML-10716	7050	State	GW	P
4304735348	RBU 13-16F	NWNW	21	100S	200E	ML-3394	7050	State	GW	DRL
4304736169	RBU 4-16E	NENW	16	100S	190E	ML-13214	7050	State	GW	P
4304736170	RBU 3-16E	NENW	16	100S	190E	ML-13214	7050	State	GW	P



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

Dominion Exploration & Production, Inc.
Attn: James D. Abercrombie
14000 Quail Springs Parkway, #600
Oklahoma City, OK 73134-2600

August 10, 2007

Re: River Bend Unit
Uintah County, Utah

Gentlemen:

On August 8, 2007, we received an indenture dated June 30, 2007, whereby Dominion Exploration & Production, Inc. resigned as Unit Operator and XTO Energy Inc. was designated as Successor Unit Operator for the River Bend Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective August 15, 2007. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the River Bend Unit Agreement.

Your statewide oil and gas bond No. UTB000138 will be used to cover all operations within the River Bend Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Greg J. Noble

Greg J. Noble
Acting Chief, Branch of Fluid Minerals

Enclosure

RECEIVED
AUG 16 2007
DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-013792
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: RIVER BEND
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 11-14E
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047304100000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3159 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2144 FSL 1894 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 14 Township: 10.0S Range: 19.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/1/2011	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <input type="text" value="DO CIBP & PWOP"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. intends to drill out a CIBP @ 8,276', reopening lower Mesaverde perforations, acidize & install rod pumping equipment per the attached procedure.

Accepted by the Utah Division of Oil, Gas and Mining

Date: 09/29/2011

By: *Derek Quist*

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 9/27/2011	

**RBW 11-14E PWOP
 Uintah County, Utah
 API 43-047-30410**

Prod CSG: 5-1/2", 17#, K-55 & N-80 @ 8,621'
Tbg: 2-3/8", 4.7#, J-55, 8rd EUE, SN & 1 jt 2-3/8" tbg, EOT @ 8,250'
Perfs: WA: 5,191'-94', 5,308'-12', 5,413'-18', 5,923'-26', 5,952'-56',
 5,966'-69', 6,241'-42', 6,246'-49', 6,287'-90', 6,402'-08',
 & 7,293'-98'
MV: 8,267'-73'
CIBP @ 8,276'
MV: 8,354'-60', 8,416'-24'
KB to GL: 14'
PBTD: 8,540' (Original). Currently CIBP @ 8,276'

DO CIBP & PWOP Procedure

- 1) MI and set a Lufkin RM-320-256-120 pumping unit.
- 2) MIRU PU. MI 8,490' 2-3/8" 4.7# L-80 EUE tbg. BD & KW w/ 2% KCl wtr. ND WH. NU BOP. TOH & LD 2-3/8" J-55 tbg currently in well. Report any scale or corrosion.
- 3) MIRU AFU. PU & TIH w/ 4-3/4" bit and 2-3/8" L-80 tbg. CO fill & DO CIBP @ 8,276'. CO and circ clean to original PBTD @ 8,540'. TOH. Report any scale bridges.
- 4) PU csg scraper. TIH w/ 4-3/4" bit and csg scraper to PBTD. TOH & LD bit and scraper.
- 5) TIH with RBP & treating packer. Treat each perf interval per the table below.

Pkr Depth	RBP Depth	Perf Depth	Scale Pill (bbls)	Spacer (bbls)	Acid (gals)	Flush (bbls)
8,170'	8,500'	8,267'-8,424' (net 20')	15	15	1,000	43
7,190'	7,400'	7,293'-7,298' (net 5')	15	15	250	36
5,820'	6,510'	5,923'-6,408' (net 23')	15	15	1,000	36
5,090'	5,520'	5,191'-5,418' (net 12')	15	15	250	33
Total:		Net 60'	60	60	2,500	148

NOTE: 2,500 gal 15% HCl acid to contain: 5 gpt MA-844, 20 gpt EGBME mutual solvent, FE-200 & FE-100 for iron sequestrating agents, and CI-350 corrosion inhibitor for 48 hrs protection at 180° F. **60 bbl scale pill to contain:** 165 gals Nalco EC-6652A scale inhibitor, 5 gal Nalco EC-6101 biocide, and 10 gals Nalco EC-9573A mutual solvent in fresh water w/ 2% equivalent, KCl liq substitute. **Spacer to contain:** fresh water w/ 2% equivalent KCl liq substitute.

- 6) TOH. LD treating pkr and RBP
- 7) RIH with production string as below:
 - 2-3/8" MSC
 - 2-3/8" × 5 1/2" Weatherford TAC
 - 2-3/8" × 6' EUE tubing sub
 - 2-3/8" × 4' EUE L-80 perforated tubing sub
 - 2-3/8" × 1.78" SN
 - ±8,490' 2-3/8", 4.7#, L-80, 8rd EUE tbg to surfaceLand tubing in 15K tension with TAC at 8,500' (use tbg subs to space out as needed).
ND BOP, NU WH.
- 8) Swab tbg until returns are clean and able to be pumped.
- 9) TIH with pump and rod string as below and install raddigan, rod rotator, ppg tee, & stuffing box:
 - 2" × 1-1/4" x 19' RHBC, w/ 1-1/4" × 8' GAC
 - 3/4" × 4' rod sub
 - 7/8" × 3' stabilizer bar
 - 3/4" 26k HF shear tool
 - 7/8" × 3' stabilizer bar
 - 12 – 1-1/4" API K sinker rods
 - 24 – 3/4" Norris 96 rods w/T cp + 5 molded guides per rod
 - ±304 – 3/4" Norris 96 rods w/T cp
 - 3/4" Norris 96 rod subs as necessary to space out
 - 1-1/2" × 26' PR
- 10) Load & PT tbg to 500 psi. Long stroke with rig to ensure pump action. HWO.
- 11) Start well ppg at 2.0 × 120" SPM. RDMO PU. Turn well over to production dept.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-013792	
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME: RIVER BEND	
2. NAME OF OPERATOR: XTO ENERGY INC		8. WELL NAME and NUMBER: RBU 11-14E	
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410		9. API NUMBER: 43047304100000	
PHONE NUMBER: 505 333-3145 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2144 FSL 1894 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 14 Township: 10.0S Range: 19.0E Meridian: S		COUNTY: UINTAH	
		STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 2/1/2012 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input checked="" type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="DO CIBP & PWOP"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.			
XTO Energy Inc. has drilled out the CIBP, acidized, & put this well on a pumping unit per the attached summary report.			
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 02, 2012			
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech	
SIGNATURE N/A		DATE 2/29/2012	

Riverbend Unit 11-14E

1/19/2012: MIRU.

1/20/2012: TOH & LD 269 jts 2-3/8" tbg. Found lt to med sc BU on ext of tbg fr/4,291'- EOT @ 8,250'.

1/23/2012: TIH w/4-3/4" bit & 2-3/8" tbg. Tgd 5-1/2" CIBP @ 8,280'.

1/24/2012: MIRU AFU. DO CIBP.

1/25/2012: CO fill to PBSD @ 8,540'. RDMO AFU. TOH w/tbg. TIH w/5-1/2" RBP, 5-1/2" pkr & 2-3/8" tbg.

1/26/2012: Pump 4 stg acid trtmnt as follows:

Stg #1: Isol MV perfs fr/8,267' - 8,424'. Trtd perfs w/15 bbl sc pill containing sc inhib, biocide & mutual solvent. Ppd 15 bbl 2% KCl wtr spacer. Contd w/1,000 gals 15% HCl ac w/adds mutual solvent, iron seq & corr inhib. Flsh w/43 bbls trtd wtr.

Stg #2: Isol MV perfs fr/7,293' - 7,898'. Trtd perfs w/15 bbl sc pill containing sc inhib, biocide & mutual solvent. Ppd 15 bbl 2% KCl wtr spacer. Contd w/250 gals 15% HCl ac w/adds mutual solvent, iron seq & corr inhib. Flsh w/36 bbls trtd wtr.

Stg #3: Isol WA perfs fr/5,923' - 6,408'. Trtd perfs w/15 bbl sc pill containing sc inhib, biocide & mutual solvent. Ppd 15 bbl 2% KCl wtr spacer. Contd w/1,000 gals 15% HCl ac w/adds mutual solvent, iron seq & corr inhib. Flsh w/36 bbls trtd wtr.

Stg #4: Isol WA perfs fr/5,191' - 5,418'. Trtd perfs w/15 bbl sc pill containing sc inhib, biocide & mutual solvent. Ppd 15 bbl 2% KCl wtr spacer. Contd w/250 gals 15% HCl ac w/adds mutual solvent, iron seq & corr inhib. Flsh w/33 bbls trtd wtr.

Rlsd tls. TOH w/tbg. LD RBP & pkr.

1/27/2012: TIH w/2-3/8" tbg. SN @ 8,477' & TAC/EOT @ 8,490'. Swab. BFL @ 4,200' FS. S. 0 BO, 89 BLW, 13 runs, 5 hrs. FFL @ 5,400 FS.

1/30/2012: Swab. BFL @ 4,900' FS. S. 0 BO. 62 BLW, 9 runs, 3 hrs. FFL @ 6,700' FS. TIH w/2" x 1-1/4" x 16' x 19' RHBC pmp & 3/4" rods.

1/31/2012: Cont TIH w/rods. HWO RDMO.

2/1/2012: RWTP. SL 120". 2.0 SPM.

=====**Riverbend Unit 11-14E**=====