

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
 DRILL DEEPEN PLUG BACK

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR
 P.O. Box 749, Denver, Colorado 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
 At surface 492' FNL/722' FEL (NE NE)
 At proposed prod. zone
 Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 Approximately 15 miles SE of Ouray, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 492'
 16. NO. OF ACRES IN LEASE 1363.21

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 4251'
 19. PROPOSED DEPTH 7100' (Wasatch)

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
 4944' Ungr. Gr

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/2"	9-5/8"	36#	200'	125 sx
8-3/4", 7-7/8"	4 1/2"	11.6#	7100'	Circulate cmt to surface to properly isolate the hydrocarbon bearing zones, the oil shale & shallow ground water.

Fresh water aquifers will be protected when the long string is run and cement is circulated back to surface.
 Please see the attached supplemental information:
 (1) Survey Plat
 (2) Ten-Point Program
 (3) BOP Schematic
 (4) Thirteen-Point Surface Use Program
 (5) Proposed Gas Well Production Hookup
 a. Typical Wellhead Installation
 b. Typical Connection to Main Lines & Pipe Anchor Detail
 c. Proposed Flowline Right-of-Way

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED H. E. Aab TITLE District Drilling Manager DATE June 21, 1932

(This space for Federal or State office use)
 PERMIT NO. _____ APPROVAL DATE _____

APPROVED BY _____ TITLE _____

CONDITIONS OF APPROVAL, IF ANY:
 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING
 DATE: 6/29/82
 BY: [Signature]

5. LEASE DESIGNATION AND SERIAL NO.
 U-01191-A
 6. IF INDIAN, ALLOTTEE OR TRIBE NAME
 N/A
 7. UNIT AGREEMENT NAME
 Natural Buttes Unit
 8. FARM OR LEASE NAME
 Natural Buttes Unit
 9. WELL NO.
 Natural Buttes Unit #86J
 10. FIELD AND POOL, OR WILDCAT
 Natural Buttes Field
 11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
 Section 3-T10S-R22E
 12. COUNTY OR PARISH 13. STATE
 Uintah Utah
 17. NO. OF ACRES ASSIGNED TO THIS WELL
 160
 20. ROTARY OR CABLE TOOLS
 Rotary
 22. APPROX. DATE WORK WILL START*
 July 15, 1982

RECEIVED
 JUN 23 1982
 DIVISION OF OIL, GAS & MINING

*See Instructions On Reverse Side


T 10 S, R 22 E, S.L.B.&M.

PROJECT

COASTAL OIL & GAS CORP.

Well location, *NATURAL BUTTES UNIT # 86 J*, located as shown in Lot 1, Section 3, T 10 S, R 22 E, S.L.B.&M. Uintah County, Utah.

S 89° 58' E (Measured)



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Lawrence K. Kelly
REGISTERED LAND SURVEYOR
REGISTRATION NO 3137
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
P.O. BOX Q - 85 SOUTH - 200 EAST
VERNAL, UTAH - 84078

SCALE	1" = 1000'	DATE	6 / 8 / 82
PARTY	D.A. J.K. R.S. S.B.	REFERENCES	GLO Plat
WEATHER	Fair	FILE	COASTAL OIL

X = Section Corners Located

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY OPERATIONS

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
 DRILL DEEPEN PLUG BACK

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER
 SALT LAKE CITY, UTAH SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR
 P.O. Box 749, Denver, Colorado 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
 At surface 492' FNL/722' FEL (NE NE)
 At proposed prod. zone Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 Approximately 15 miles SE of Ouray, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 492'

16. NO. OF ACRES IN LEASE 1363.21

17. NO. OF ACRES ASSIGNED TO THIS WELL 160

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 4251'

19. PROPOSED DEPTH 7100' (Wasatch)

20. ROTARY OR CABLE TOOLS Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.) 4944' Ungr. Gr

22. APPROX. DATE WORK WILL START* July 15, 1982

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/2"	9-5/8"	36#	200'	125 sx
8-3/4", 7-7/8"	4 1/2"	11.6#	7100'	Circulate cmt to surface to properly isolate the hydrocarbon bearing zones, the oil shale & shallow ground water.

RECEIVED
 DISTRICT OIL & GAS SUPERVISOR
 JUN 21 1982
 UTAH
 SALT LAKE CITY

Fresh water aquifers will be protected when the long string is run and cement is circulated back to surface.
 Please see the attached supplemental information:

- (1) Survey Plat
- (2) Ten-Point Program
- (3) BOP Schematic
- (4) Thirteen-Point Surface Use Program
- (5) Proposed Gas Well Production Hookup
 - a. Typical Wellhead Installation
 - b. Typical Connection to Main Lines & Pipe Anchor Detail
 - c. Proposed Flowline Right-of-Way

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED H. E. Aab TITLE District Drilling Manager DATE June 21, 1982

(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____
 APPROVED BY WT Martin FOR E. W. GUYNN
 CONDITIONS OF APPROVAL, IF ANY: _____ TITLE DISTRICT OIL & GAS SUPERVISOR DATE JUL 22 1982

FLARING OR VENTING OF GAS IS SUBJECT TO NTL 4-A DATED 1/1/80

NOTICE OF APPROVAL
 State of CO
 CONDITIONS OF APPROVAL ATTACHED TO OPERATOR'S COPY



United States Department of the Interior

IN REPLY REFER TO

T & R
U-802

BUREAU OF LAND MANAGEMENT

VERNAL DISTRICT OFFICE
170 South 500 East
Vernal, Utah 84078

July 8, 1982



Ed Guynn, District Engineer
Mineral Management Services
2000 Administration Building
1745 West 1700 South
Salt Lake City, UT 84104

Re: Coastal Oil & Gas Corporation
NBU #49J, Sec. 30, T9S, R22E
NBU #80J, Sec. 34, T9S, R22E
NBU #84J, Sec. 6, T10S, R22E
NBU #85J, Sec. 4, T10S, R22E
NBU #86J, Sec. 3, T10S, R22E
NBU #87J, Sec. 3, T10S, R22E

Dear Sir:

A joint field examination was made on June 30, 1982, of the above referenced well site locations and proposed access roads. We feel that the surface use and operating plans are adequate with the following revisions and stipulations:

1. Construction and maintenance of roads, rehabilitation of disturbed areas and construction of pipeline routes, shall be in accordance with surface use standards as set forth in the brochure, "Surface Operating Standards for Oil and Gas Exploration."
2. Traveling off access road right-of-ways will not be allowed. The maximum width of access pads (both existing and planned) will be 30 feet total disturbed area. Roads will be crowned and properly maintained. Turn-outs will not be required. Bar ditches will be installed where necessary.
3. The BLM will be notified at least 24 hours prior to any construction.
4. Burn pits will not be constructed. There will be no burning or burying of trash or garbage at the well sites. Refuse must be contained in trash cages and hauled to an approved disposal site.
5. A wire mesh or net type of fence, topped with at least one strand of barbed wire, will be used around the reserve pits.

6. The BLM will be contacted at least 24 hours prior to any rehabilitation activities. The operator may be informed of any additional needed seeding requirements.
7. At well #84J, the top 4" of topsoil will be stockpiled between reference corners #6 and #7.
8. At well #87J, the top 4-6" of topsoil will be stockpiled between reference corners #1 & #2 and #1 & #8. Also, the pits will be lined.
9. At well #80J, the top 4" of topsoil will be stockpiled between reference corners #1 & #2.
10. No topsoil will be stockpiled at the wells #85J, 49J, and 86J. These locations will be ripped to a minimum of 12" upon abandonment.
11. At well #49J, the drill hole was moved 30' to the south and the pad was rotated 180°.

The following stipulations shall govern the proposed flowlines for all the previously mentioned wells:

1. No installation will be allowed unless this office is notified at least 24 hours prior to the start of construction.
2. A bulldozer may be used to assist trucks in steep terrain, drag pipeline into position and for the construction of ford type crossings on drainages which cannot otherwise be crossed. Construction of drainage crossing is the only type surface disturbance authorized.
3. Pipeline construction shall not block, dam, or change the natural flow of any drainage.

All permanent (onsite for six (6) months duration or longer) structures constructed or installed, including the pumpjack and covering over tank installation, shall be painted a flat, non-reflective, earth tone color to match Tnemec 23-08351 Mesa Brown Enduratone or an approved equal. All facilities shall be painted within six (6) months of when the production facilities are put in place. Facilities that are required to comply with O.S.H.A. (Occupational Safety and Health Act) standards are excluded.

Choice of color stipulation may vary depending on location.

An archaeological clearance has been conducted by A.E.R.C. of the proposed drill site and proposed access road. No cultural materials were located on the surface of the surveyed areas.

The proposed activities do not jeopardize listed, threatened, or endangered flora, fauna, or their habitats.

The BLM representative will be Cory Bodman, (801) 789-1362.

Sincerely,

A handwritten signature in cursive script, appearing to read "Dean L. Evans".

Dean L. Evans
Area Manager
Bookcliffs Resource Area

cc: MMS, Vernal

JUL 15 1982

United States Department of the Interior
Minerals Management Service
2000 Administration Building
1745 West 1700 South
Salt Lake City, Utah 84104-3884

NEPA CATEGORICAL EXCLUSION REVIEW

PROJECT IDENTIFICATION

Operator Coastal Oil and Gas Corporation
Project Type Gas Well
Project Location 492' FNL 722' FEL Sec 3 - 105 - 22E
Well No. 86J Lease No. U-01191-A
Date Project Submitted June 23, 1982

FIELD INSPECTION

Date June 30, 1982

Field Inspection
Participants

Greg Darlington - MMS, Vernal
Cory Bodman - BLM, Vernal
Pat Bohner - Coastal Oil and Gas
Bill Kay - Coastal Oil and Gas
Floyd Murray - D.E. Casada

I have reviewed the proposal in accordance with the categorical exclusion review guidelines. This proposal would not involve any significant effects and, therefore, does not represent an exception to the categorical exclusions.

July 14, 1982
Date Prepared

Gregory Darlington
Environmental Scientist

I concur

JUL 15 1982

Date

W. J. Mantua FOR E. W. GUYNN
DISTRICT OIL & GAS SUPERVISOR
District Supervisor

Proposed Actions :

Coastal Oil and Gas Corporation plans to drill the NBU# 86J well, a 7100' gas test of the Wasatch formation. The existing access road must be rerouted from the front of the pad to the back of the pad. The existing road may be used to haul water by truck from the White River at a point approximately 2000' Northeast of the location. A pad 220' by 425' and a reserve pit 100' by 150' are indicated for the location. A 400' flowline route for the anticipated production hookup has also been indicated in the APD. Actually the existing surface line to be hooked into is adjacent to the back of the pad.

Recommended Approval Conditions:

The operator agrees to accept and adhere to the following conditions in addition to the plans outlined in the APD :

1. BLM stipulations
2. Lease stipulations
3. Provide adequate logs for the identification of other minerals as requested in the Mineral Evaluation Report and Mining Report.
4. Exercise care regarding what is apparently a buried pipeline near the back of the pad and for the surface 2" flowline near corner 2.

FIELD NOTES SHEET

Date of Field Inspection: June 30, 1982 PER onsite

Well No.: 86 J

Lease No.: U-01191-A

Approve Location: ✓

Approve Access Road: Routed to back of pad

Modify Location or Access Road: Stockpile NO Topsoil

PT may require lining. Operator promised to do so if rather porous material is encountered. Operator needs to be careful with old buried pipeline at the back of the pad.

Evaluation of Criteria for Categorical Exclusion

1. Public Health and Safety
2. Unique Characteristics
3. Environmentally Controversial Items
4. Uncertain and Unknown Risks
5. Establishes Precedents
6. Cumulatively Significant
7. National Register Historic Places
8. Endangered/Threatened Species
9. Violate Federal, State, Local, or Tribal Laws

If this project is not eligible for Categorical Exclusion circle the numbers of the above criteria requiring the preparation of an EA.

Comments and special conditions of approval discussed at onsite: (include local topography)

The operator's representatives handed us a copy of the APD in the field on the day of the onsite.

Salt Lake reviewed copy arrived on July 2, 1982

We think the access road is also a water haul road to the White River and might be used for water according to the APD.

CATEGORICAL EXCLUSION REVIEW INFORMATION SOURCE

Criteria 516 DM 2.3.A	Federal/State Agency			Local and private correspondence (date)	Previous NEPA	Other studies and reports	Staff expertise	Onsite inspection (date)	Other
	Corre- spondence (date)	Phone check (date)	Meeting (date)						
Public health and safety							1,2,4,6	June 30 1982	
Unique charac- teristics							1,2,4,6		
Environmentally controversial							1,2,4,6		
Uncertain and unknown risks							1,2,4,6		
Establishes precedents							1,2,4,6		
Cumulatively significant							1,2,4,6		
National Register historic places							1,6		
Endangered/ threatened species							1,6		
Violate Federal, State, local, tribal laws							1,2,4,6	↓	

CATEGORICAL EXCLUSION REVIEW COMMON REFERENCE LEGEND

1. Surface Management Agency Input
2. Reviews Reports, or information received from Geological Survey
(Conservation Division, Geological Division, Water Resource Division,
Topographic Division)
3. Lease Stipulations/Terms
4. Application Permit to Drill
5. Operator Correspondence
6. Field Observation
7. Private Rehabilitation Agreement
8. *Onsite Requirements other than the items 1-7.*

1. Geologic name of surface formation:

UINTA

2. The estimated tops of important geologic markers:

GREEN RIVER: 1240'

WASATCH: 4190'

3. The estimated depths at which anticipated water, oil, gas are expected to be encountered:

WASATCH - 4190' GAS -

4. The proposed casing program, including the size, grade and weight per foot each string and whether new or used:

9-5/8" - K-55, ST&C - 36# - NEW

4 -1/2" - N-80, LT&C - 11.6# - NEW

5. The operator's minimum specifications for pressure control equipment which is to be used, a schematic diagram thereof showing sizes, pressure ratings and testing procedures and testing frequency:

BOTTOM 3000# BOP W/4-1/2" pipe rams
 3000# BOP W/blind rams
 3000# Hydril

TOP: Grant rotating head

Manifold includes appropriate valves, positive and adjustable chokes and kill line to control abnormal pressures.

BOP's will be tested at installation and will be cycled on each trip.

6. The type and characteristics of the proposed circulating medium to be employed for rotary drilling and the quantities and types of mud and weighting material to be maintained:

(Continued on Page 2)

10-POINT PROGRAM - PAGE 2

6. Continued --

The well will be drilled with fresh water from surface to 4500' with a weight of 8.3 to 8.7 . From 4500' to TD the well will be drilled with fresh wtr mud with a weight from 8.7 to 10.4 . Sufficient weighting material (barite) will be on location to increase the mud weight if abnormal pressure is encountered.

7. The auxiliary equipment to be used:

- a. kelly cock
- b. monitoring equipment on the mud system
- c. a sub on the floor with a full opening valve to be stabbed into the drill pipe when the kelly is not in the string.

8. The testing, logging and coring program to be followed:

No DST's are planned
No cores are expected to be cut.

LOGS: Dual Induction Laterolog
Compensated Neutron-Formation Density

9. Any anticipated abnormal pressures or temperatures expected to be encountered:


No abnormal pressures or temperatures expected
No hydrogen sulfide expected

10. The anticipated starting date and duration of the operation:

July 15, 1982
Three weeks' duration

3000 psi

Working Pressure BOP's



Test Procedure

- 1) Flush BOP's and all lines to be tested with water.
- 2) Run test plug on test joint and seat in casing head (leave valve below test plug open to check for leak).
- 3) Test the following to rated pressure:
 - a) inside blowout preventer
 - b) lower kelly cock
 - c) upper kelly cock
 - d) stand pipe valve
 - e) lines to mud pump
 - f) kill line to BOP's
- 4) Close and test pipe rams to rated pressure.
- 5) Close and test Hydril to rated pressure.
- 6) Back off and leave test plug in place. Close and test blind rams to rated pressure.
- 7) Test all choke manifold valves to rated pressure.
- 8) Test kill line valves to rated pressure.

COASTAL OIL & GAS CORPORATION

13 Point Surface Use Plan

for

Well Location

N.B.U. #86J

Located In

Section 3, T10S, R22E, S.L.B. & M.

Uintah County, Utah

1. EXISTING ROADS

See attached Topographic Maps "A" & "B".

To reach COASTAL OIL & GAS CORPORATION, well location site N.B.U. #86J located in the NE 1/4 NE 1/4 (Lot 1) Section 3, T10S, R22E, S.L.B. & M., Uintah County, Utah:

Proceed Westerly out of Vernal, Utah along U.S. Highway 40 - 14 miles to the junction of this road and Utah State Highway 209; proceed South along Utah State Highway 209 - 7 miles more or less to the junction of this Highway and the Utah State Highway 88; proceed Southerly on Highway 88 - 10 miles to Ouray, Utah; proceed along South on a county road known as the Seep Ridge Road 11.4 miles to its junction with the Bitter Creek gas field service road to the East; proceed in a Easterly direction along this road 11.2 miles to the junction with an oil field service road to the North; proceed in a Northerly direction along this road 1.3 miles to its junction with a road to the Northeast; proceed in a Northeasterly direction along this road 2.2 miles to the proposed location site.

The highways mentioned above are bituminous surfaced roads to Ouray, Utah and are maintained by State road crews.

The county road known as the Seep Ridge Road is surfaced with native asphalt for + 4 miles and is then a gravel surface road. The above described county road is maintained by county road crews and will require no further maintenance. The dirt gas field roads described above are dirt surfaced road that were built out of the native materials of the area which were accumulated during their construction. These materials consist of light brown sandy clay materials with some poorly graded gravels. These gas field roads will be maintained by COASTAL OIL & GAS CORPORATION or its sub-contractors, this maintenance will consist of some minor grader work to smooth road grades and for snow removal.

There is no anticipated construction on any portion of the above described roads. They will meet the necessary standards required to facilitate an orderly flow of traffic during the drilling phase, completion phase, and production phase of this well at such time that production is established.

2. PLANNED ACCESS ROAD

See Topographic Map "B".

There will be no planned access road. The existing road goes to the location site. There will be some minor re-routing of the existing road to facilitate traffic around the rig during drilling operations.

3. EXISTING WELLS

There are approximately 11 existing producing gas wells and one abandoned well within a one mile radius of this location site. See Topographic Map "B" for the location of these wells relative to the proposed location site.

There are no water wells, temporarily abandoned wells, disposal wells, drilling wells, shut-in wells, injection wells, monitoring or observation wells for other resources located within a one-mile radius of this location site.

COASTAL OIL & GAS CORPORATION
N.B.U. #86J
Section 3, T10S, R22E, S.L.B. & M.

4. LOCATION OF EXISTING AND PROPOSED FACILITIES

At the present time there are existing facilities belonging to COASTAL OIL & GAS CORPORATION within a one-mile radius of this location site.

In the event that production is established at this location the production will be contained within the location site until a gas line can be run from this location to existing lines in the area. The exact location of this line is not known at this time. Detailed plans for this line will be submitted to the appropriate agencies before construction begins, showing the approximate final location of the facilities.

All areas used to contain these production facilities will be built out of the native materials accumulated during their construction. These facilities will be constructed using graders, bulldozers, and workman crews to construct and place the proposed facilities.

The proposed gas flow line will be an 18' right-of-way.

If there is any deviation from the above, all appropriate agencies will be notified.

5. LOCATION AND TYPE OF WATER SUPPLY

Water to be used for the drilling and production of this well will be hauled by truck from the White River at a point approximately 2000' Northeast of the location site.

In the event the above source cannot be improvised other arrangements will be made and all concerned agencies will be notified. All permits and necessary requirements will be strictly adhered to.

There will be no water well drilled at this location site.

6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location site and access road shall be borrow material accumulated during construction of the location site and access road. No additional road gravels or pit lining material from other sources are anticipated at this time, but if they are required, the appropriate actions will be taken to acquire them from private sources.

The native materials that will be used in the construction of this location site and access road will consist of a sandy-clay soil and sandstone and shale materials gathered in actual construction of the road and location.

7. METHODS OF HANDLING WASTE DISPOSAL

See Location Layout Sheet.

A reserve pit shall be constructed.

COASTAL OIL & GAS CORPORATION
N.B.U. #86J
Section 3, T10S, R22E, S.L.B.& M.

The reserve pit will be 8' deep and at least half of the depth of the reserve pit shall be below the existing ground surface.

One-half of the reserve pit will be used as a fresh water storage area during the drilling of this well and the other one half will be used to store non-flammable material such as cuttings, salts, drilling fluids, chemicals, produced fluids, etc.

If deemed necessary by the agencies concerned, to prevent contamination to surrounding areas, the reserve pit will be lined with a gel.

The pits will have wire and overhead flagging installed at such time as deemed necessary to protect the water fowl, wildlife, and domestic animals.

At the onset of drilling, the reserve pit will be fenced on three sides and at the time the drilling activities are completed, it will be fenced on the fourth side and allowed to dry completely prior to the time that backfilling and reclamation activities are attempted.

When the reserve pit dries and the reclamation activities commence, the pits will be covered with a minimum of four feet of soil and all requirements of Item #10 will be followed.

A portable trash basket will be placed on the location site and all trash will be hauled to the nearest Sanitary Landfill.

A portable chemical toilet will be supplied for human waste.

8. ANCILLARY FACILITIES

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. WELL SITE LAYOUT

See attached location layout sheet.

The B.L.M. Representative shall be notified before any construction begins on the proposed location site and road.

As mentioned in Item #7, the pits will be unlined unless it is determined by the representatives of the agencies involved that the materials are too porous and would cause contamination to the surrounding area; then the pits will be lined with a gel and any other type of material necessary to make it safe and tight.

When drilling activities commence, all work shall proceed in a neat and orderly sequence.

COASTAL OIL & GAS CORPORATION
N.B.U. #86J
Section 3, T10S, R22E, S.L.B. & M.

10. PLANS FOR RESTORATION OF SURFACE

As there is some topsoil on the location site, all topsoil shall be stripped and stockpiled. (See location layout sheet and Item #9). When all drilling and production activities have been completed, the location site and access road will be reshaped to the original contour and stockpiled topsoil spread over the disturbed area.

Any drainages re-routed during the construction activities shall be restored to their original line of flow as near as possible. Fences around pits are to be removed upon completion of drilling activities and all waste being contained in the trash basket shall be hauled to the nearest sanitary landfill.

Restoration activities shall begin within 90 days after completion of the well. Once Restoration activities have begun, they shall be completed within 30 days.

When restoration activities have been completed, the location site and access ramp shall be reseeded with a seed mixture recommended by the B.L.M. Representative when the moisture content of the soil is adequate for germination. The Lessee further covenants and agrees that all of said clean-up and restoration activities shall be done and performed in a diligent and most workmanlike manner and in strict conformity with the above mentioned Items #7 and #10.

11. OTHER INFORMATION

The Topography of the General Area - (See Topographic Map "A"):

The area is a large basin formed by the Uinta Mountains to the North and the Book Cliff Mountains to the South. The White River is located approximately 9 miles to the North of the location site.

The majority of the washes and streams in the area are non-perennial in nature with the only ones in the area having a year round flow being the White River and Green River to the North and Willow Creek to the West, of which the numerous washes, draws and non-perennial streams are tributaries to.

The majority of the surrounding drainages are of a non-perennial nature with normal flow limited to the early spring and extremely rare heavy thunderstorms, or rainstorms of high intensity that lasts over an extended period of time and are extremely rare in nature as the normal annual precipitation is only 8".

All drainages in the immediate area are non-perennial streams and flow to the North and are tributaries to the White River.

The soils of this semi-arid area are of the Uinta Formation and Duchesne River Formation (the Fluvial Sandstone and Mudstone) from the Eocene Epoch and Quaternary Epoch (gravels surfaces) and the visible geologic structure consists of light brownish-gray clays (OL) to sandy soils (SM-ML) with poor gravels and shales with outcrops of rock (sandstone, mudstone, conglomerates and shales).

COASTAL OIL & GAS CORPORATION
N.B.U. #86J
Section 3, T10S, R22E, S.L.B. & M.

Due to the low precipitation average, climatic conditions and the marginal types of soils, the vegetation that is found in the area are common of the semi-arid region we are located in and in the lower elevations of the Uintah Basin. It consists of, as primary flow areas of sagebrush, rabbitbrush, some grasses, and cacti and large areas of bare soils devoid of any growth in the areas away from and in the vicinity of non-perennial streams and along the areas that are formed along the edges of perennial streams, cottonwood, willows, tamarack sagebrush, rabbitbrush, grasses and cacti can be found.

The fauna of the area is sparse and consists predominantly of the mule deer, coyotes, pronghorn antelope, rabbits, and varieties of small ground squirrels and other types of rodents, and various reptiles common to this area.

The birds of the area are raptors, finches, ground sparrows, magpies, crows, and jays.

The area is used by man for the primary purpose of grazing domestic livestock.

The Topography of the Immediate Area - (See Topographic Map "B"):

N.B.U. #86J is located on a relatively flat area approximately 2000' West of the White River.

The geologic structure of the location is of the Uinta Formation and consists of light brownish-gray clay (SP-PL) with some sandstone outcrops.

The ground slopes through this location site from the West through the site to the East at approximately a 2.4% grade.

The location is covered with some sagebrush and grasses.

The total surface ownership affected by this location is administered by the B.L.M..

There are no occupied dwellings or other facilities of this nature in the general area.

There are no visible archaeological, historical, or cultural sites within any reasonable proximity of the proposed location site. (See Topographic Map "B").

12. LESSEE'S OR OPERATOR'S REPRESENTATIVE

COASTAL OIL & GAS CORPORATION
P.O. Box 749
Denver, CO. 80201

1-303-572-1121

COASTAL OIL & GAS CORPORATION
N.B.U. #86J
Section 3, T10S, R22E, S.L.B. & M.

13. CERTIFICATION

I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are to the best of my knowledge true and correct; and that the work associated with the operation proposed herein will be performed by COASTAL OIL & GAS CORPORATION and its contractors and sub-contractors in conformity with this plan and the terms and conditions under which it is approved.

June 21, 1982



Date

H. E. Aab

H. E. Aab
District Drilling Manager

COASTAL OIL & GAS CORP.
N.B.U. # 86 J


SCALE 1" = 50'



Scales:
1" = 50'

APPROXIMATE YARDAGES

Cubic Yards of Cut - 10,292
Cubic Yards of Fill - 2,498



OURAY 23.2 MILES

COASTAL OIL & GAS CORPORATION

N.B.U. # 86 J

PROPOSED LOCATION




SCALE - 1" = 2000'

ROAD CLASSIFICATION

Light-duty road, all weather, improved surface  Unimproved road, fair or dry weather 



UTAH



WHITE

RIVER

PIPELINE

Wash

T 9 S
T 10 S

R 22 E

BUTLER CREEK GAS FIELD

PROPOSED EXIT ROAD
100 FEET M. OR L.

PROPOSED LOCATION

PROPOSED ACCESS ROAD
100 FEET M. OR L.

2.2 MILES

N.B.U. # 86

PIPELINE

RIVER

0.5 N

Drill Hole
5105

Gas Well
Pumping Station

Pumping Station
Gas Well

L.T. 7

NBU # 10

NB 3-28.0

CIG 67D

CIG 1A

CIG 8

CIG 88D

NB 4-35 B

CIG 89D

CIG 25

NB 8

38

32

5187

5171

5225

5287

5165

5080

5236

5139

5100

5087

5070

5062

5040

5040

5040

5040

5040

5040

5040

5040

5040

5040

5040

5040

5040

4894

4942

4980

4989

4900

4978

4900

4900

4900

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

TRAIL

50090

4996

4973

4940

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5000

5032

5030

5030

5030

5030

5030

5030

5030

5030

5030

5030

5030

5030

5030

5030

5030

5030


5030

5030

5030

5030

5030




**COASTAL OIL & GAS
CORPORATION**

N.B.U. # 86 J

PROPOSED LOCATION



SCALE - 1" = 4 Mi.



COASTAL OIL & GAS CORPORATION
DENVER, COLORADO

Natural Buttes Unit #86J
Section 3-T10S-R22E
Uintah County, Utah

Statement for permit to lay flow line, to be included with application for Drilling Permit:

Upon approval of all concerned regulatory agencies, CIG proposes to install a surface flow line from NBU 86J in a northerly direction through the NE/4 of Section 3 connecting to Line F. 27-2" in the NE/4 of Section 3, all in 10S-22E. The line will be approximately 400' long, as shown on the attached sketches.

Pipe will be 2-3/8" O.D. x .154 W.T., Grade B EW. It will be butt-welded in place, using portable electric welding machines, and will be laid aboveground except where burial is necessary for road crossing, ditches, or other obstructions. Magnesium anodes will be installed at the dehydrator, meter setting, road crossings, underground piping at stream crossings, and at producer's separator for corrosion protection.

CIG will connect to producer's separator and install dehydration and metering facilities within 100' of the connection.

Some damage will be incurred by trucks transporting pipe and welding equipment over the pipeline route, but surface disturbance will be held to a minimum.

PIPELINE TO BE ADEQUATELY ANCHORED TO PREVENT UNDUE MOVEMENT OR STRAIN TO EXISTING FACILITY. NUMBER AND SPACING OF ANCHORS TO BE DETERMINED IN FIELD

FOR PIPE ANCHOR DETAIL SEE DWG. 80FM3-4A

20'±


O. O. Y. S. V.

EXIST. PIPELINE

ALTERNATE ANCHOR - BURY PIPELINE MIN. OF 18"

(TYP. FOR G.P.E. OR C.I.G.)

C.I.G. OTHER




TYP. FOR CONN. TO M.F.S.

Colorado Interstate Gas Co.
COLORADO SPRINGS COLORADO

TYPICAL CONNECTION TO MAIN LINES AND PIPE ANCHOR
DETAIL - NATURAL BUTTES FIELD

UINTA COUNTY, UTAH

1 2385B REVISE STARTING POINT 8-22-77 RWP



Colorado Interstate Gas Co.
 COLORADO SPRINGS, COLORADO

TYPICAL WELL HEAD INSTALLATION
 NATURAL BUTTES FIELD

UINTAH COUNTY, UTAH

ESTIMATE SKETCH

DATE: 5.24.82
STARTING DATE: _____
EST COMP. DATE: _____
 COMPANY CONTRACT

COLORADO INTERSTATE GAS COMPANY


W O NO.: _____
REVISION NO.: _____
BUDGET NO.: _____
RELATED DWG.: 115 FU-1F-1

LOCATION: NE·NE 3·10s·22E COUNTY: UTAH STATE: UTAH

DESCRIPTION OF WORK: CONNECT NBU 86J
COASTAL OIL & GAS
NATURAL BUTTES FIELD

REQUESTED BY: _____ APPROXIMATE MILEAGE: _____ PROJECT ENGINEER: JFK

RANGE: 22E



TOWNSHIP: 10S

** FILE NOTATIONS **

DATE: June 28, 1982

OPERATOR: Coastal Oil & Gas

WELL NO: NBU # 86J

Location: Sec. 3 T. 10S R. 22E County: Uintah

File Prepared:

Entered on N.I.D:

Card Indexed:

Completion Sheet:

API Number 43-047-31251

CHECKED BY:

Petroleum Engineer: _____

Director: _____

Administrative Aide: Unit Well

APPROVAL LETTER:

Bond Required:

Survey Plat Required:

Order No. _____

O.K. Rule C-3

Rule C-3(c), Topographic Exception - company owns or controls acreage within a 660' radius of proposed site

Lease Designation Lea

Plotted on Map

Approval Letter Written

Hot Line

P.I.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other

2. NAME OF OPERATOR
Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR
P. O. Box 749 Denver, Colorado 80201

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 492' FNL/722' FEL (NE NE)
AT TOP PROD. INTERVAL: SAME
AT TOTAL DEPTH: SAME

5. LEASE
U-01191-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
N/A

7. UNIT AGREEMENT NAME
Natural Buttes Unit

8. FARM OR LEASE NAME
Natural Buttes Unit

9. WELL NO.
Natural Buttes Unit #86J

10. FIELD OR WILDCAT NAME
Natural Buttes Field

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 3-T10S-R22E

12. COUNTY OR PARISH
Utah

13. STATE
Utah

14. API NO.
43-047-31251

15. ELEVATIONS (SHOW DF, KDB, AND WD)
4944' Ungr. Cr.

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

PULL OR ALTER CASING

MULTIPLE COMPLETE

CHANGE ZONES

ABANDON*

(other) Change Casing Program X

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

It is proposed to change casing program FROM:

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/2"	9-5/8"	36#	200'	125 ssx
7-7/8"	4 1/2"	11.6#	7100'	Circulate cmt to surface to properly isolate the hydrocarbon-bearing zones, the oil shale & shallow ground water.
TO:				
12 1/2"	9-5/8"	36#	200'	125 ssx
7-7/8"	5 1/2"	17#	7100'	Circulate cmt to surface to properly isolate the hydrocarbon-bearing zones, the oil shale & shallow ground water.

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 8/14/82
BY: [Signature]

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED: [Signature] TITLE: Dist. Dir. Mgt. DATE: July 27, 1982
H. E. Aad

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

June 29, 1982

Coastal Oil & Gas Corporation
P.O. Box 749
Denver, Colorado 80201

RE: Well No. NBU #86J
Sec. 3, T10S, R22E
Uintah County

Insofar as this office is concerned, approval to drill the above referred to gas well is hereby granted in accordance with Section 40-6-11, Utah Code Annotated 1953 and predicated on Rule A-3, General Rules and Regulations and Rules of Practice and Procedure.

Should you determine that it will be necessary to plug and abandon this well, you are hereby requested to immediately notify the following:


CLEON B. FEIGHT
Office: 533-5771
Home: 466-4455

Enclosed please find Form OGC-8-X, which is to be completed whether or not water sands (aquifers) are encountered during drilling. Your cooperation in completing this form will be appreciated.

Further, it is requested that this Division be notified within 24 hours after drilling operations commence and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-047-31251.

Sincerely,


RONALD J. FIRTH
CHIEF PETROLEUM ENGINEER

RJF:SC
cc: Minerals Management Service
Enclosure

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: COASTAL OIL & GAS

WELL NAME: NATURAL BUTTES UNIT 86-J

SECTION NENE 3 TOWNSHIP 10 S RANGE 22 E COUNTY Uintah

DRILLING CONTRACTOR All Western

RIG # 4

SPUDDED: DATE 8-9-82

TIME 8:00 AM

HOW Dry Hole

DRILLING WILL COMMENCE 8-12-82

REPORTED BY Sandy Crowell

TELEPHONE # 303-572-1121

DATE 8-10-82 1:10 PM SIGNED Norm S.

NOTICE OF SPUD

Mason ✓

Company: Coastal

Caller: Sandra Crowell

Phone: 303 572 1121

Well Number: 865

Location: N1/4 N1/4 Sec 3 T10S R22E

County: Uintah State: Utah

Lease Number: 11-11191A

Lease Expiration Date: _____

Unit Name (If Applicable): Natural Buttes

Date & Time Spudded: 8:00 AM Aug 9, 1982

Dry Hole Spudder/Rotary: _____

Details of Spud (Hole, Casing, Cement, etc.) _____

Rotary Rig Name & Number: All Western #4

Approximate Date Rotary Moves In: Aug 12, 1982

FOLLOW WITH SUNDRY NOTICE

Call Received By: Becky George

Date: August 11, 1982

State 396 ✓
Vernon Mills
Utah
TERESSA

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other

2. NAME OF OPERATOR
Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR
P. O. Box 749 Denver, Colorado 80201

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 492' FNL/722' FEL (NE NE)
AT TOP PROD. INTERVAL: SAME
AT TOTAL DEPTH: SAME

5. LEASE
U-01191-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
N/A

7. UNIT AGREEMENT NAME
Natural Buttes Unit

8. FARM OR LEASE NAME
Natural Buttes Unit

9. WELL NO.
Natural Buttes Unit #86J

10. FIELD OR WILDCAT NAME
Natural Buttes Field

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 3-T10S-R22E

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

14. API NO.
43-047-31251

15. ELEVATIONS (SHOW DF, KDB, AND WD)
4944' Und. Gr.

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

PULL OR ALTER CASING

MULTIPLE COMPLETE

CHANGE ZONES

ABANDON*

(other) Notice of Spud

SUBSEQUENT REPORT OF:

RECEIVED

AUG 16 1982

NOTE: Report results of multiple completion or zone change on Form 9-330.)

DIVISION OF
OIL, GAS & MINING

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

USGS and State notified on August 10, & August 11, regarding the attached Notice of Spud.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct
SIGNED H. E. Aab TITLE Dist. Drlg. Mgr. DATE August 11, 1982

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF SPUD

WELL NAME: NBU 86J

LOCATION: NE 1/4 NE 1/4 SECTION 3 T- 10S R- 22E

COUNTY: Uintah STATE: Utah

LEASE NO.: U-01191-A LEASE EXPIRATION DATE: -

UNIT NAME (If Applicable): Natural Buttes

DATE & TIME SPURRED: 8:00 A.M. 8-9-82

DRY HOLE SPUDDER: yes

DETAILS OF SPUD (Hole, Casing, Cement, etc.): 12 1/4" hole cmt w/Hoveo
w 125 SK CLASS 'G', 2% CaCl₂. Circ 5 BBS cmt to Surf.

ROTARY RIG NAME & NUMBER: Allwestern #4

APPROXIMATE DATE ROTARY MOVES IN: 8-12-82

FOLLOW WITH SUNDRY NOTICE

USGS CALLED: DATE: ~~8-9-82~~ 8-11-82

PERSON CALLED: Becky George

STATE CALLED: DATE: 8-10-82

PERSON CALLED: Norm Stout

REPORTED BY: Sandy Crowell

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

5. LEASE U-01191-A	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A	
7. UNIT AGREEMENT NAME Natural Buttes Unit	
8. FARM OR LEASE NAME Natural Buttes Unit	
9. WELL NO. Natural Buttes Unit #86J	
10. FIELD OR WILDCAT NAME Natural Buttes Field	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 3-T10S-R22E	
12. COUNTY OR PARISH Uintah	13. STATE Utah
14. API NO. 43-047-31251	
15. ELEVATIONS (SHOW DF, KDB, AND WD) 4944' Ungr. Gr.	

1. oil well gas well other

2. NAME OF OPERATOR
Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR
P. O. Box 749 Denver, Colorado 80201

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 492' FNL/722' FEL (NE NE)
AT TOP PROD. INTERVAL: SAME
AT TOTAL DEPTH: SAME

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) Operations <input type="checkbox"/>	X <input type="checkbox"/>

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Please see attached chronological for report of operations through 9/15/82.

RECEIVED
SEP 21 1982

DIVISION OF
OIL, GAS & MINING

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED H. E. Aab TITLE Dist. Drlg. Mgr. DATE September 15, 1982

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

FILE IN TRIPLICATE
FORM OGC-8-X

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING
1588 West North Temple
Salt Lake City, Utah 84116

REPORT OF WATER ENCOUNTERED DURING DRILLING

Well Name & Number COGC NBU #86J
Operator COASTAL OIL & GAS CORPORATION Address P. O. BOX 749, DNEVER, CO 80201
Contractor ALLWESTERN DRILLING INC. Address P. O. BOX 1518, VERNAL, UT 84078
Location NE 1/4 NE 1/4 Sec. 3 T. 10S R. 22E County UINTAH

Water Sands

<u>Depth</u>		<u>Volume</u>	<u>Quality</u>
From	To	Flow Rate or Head	Fresh or Salty
1.	NONE REPORTED		
2.			
3.			
4.			
5.			

(Continue of reverse side if necessary)

Formation Tops

WASATCH FORMATION 4192'

Remarks

- NOTE: (a) Report on this form as provided for in Rule C-20, General Rules and Regulations and Rules of Practice and Procedure.
- (b) If a water analysis has been made of the above reported zone, please forward a copy along with this form.

UNITED STATES DEPARTMENT OF THE INTERIOR GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE (See other instructions on reverse)

Form approved. Budget Bureau No. 42-R355.5.

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1. TYPE OF WELL: OIL WELL [] GAS WELL [X] DRY [] Other []

2. TYPE OF COMPLETION: NEW WELL [X] WORK OVER [] DEEP-EN [] PLUG BACK [] DIFF. RESVR. [] Other []

2. NAME OF OPERATOR COASTAL OIL & GAS CORPORATION

3. ADDRESS OF OPERATOR P. O. - BOX-749, DENVER, CO-80201

4. LOCATION OF WELL (Report location clearly and in accordance with State requirements) At surface 492' FNL & 722' FEL (NE-NE) At top prod. interval reported below SAME At total depth SAME

RECEIVED OCT 04 1982

14. PERMIT NO. DIVISION OF OIL & GAS & MINING 43-047-015

5. LEASE DESIGNATION AND SERIAL NO. U-01191A 6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A 7. UNIT AGREEMENT NAME NATURAL BUTTES UNIT 8. FARM OR LEASE NAME NATURAL BUTTES UNIT 9. WELL NO. NATURAL BUTTES UNIT #86J 10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES FIELD 11. SEC., T., R., M. OR BLOCK AND SURVEY SECTION 3-T10S-R22E 12. COUNTY OR PARISH UINTAH UTAH 13. STATE UTAH

15. DATE SPUNDED 8-9-82 16. DATE T.D. REACHED 8-31-82 17. DATE COMPL. (Ready to prod.) 9-25-82 18. ELEVATIONS (DF, BER, RT, OR, ETC.) 4944' Un. Gr. 19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD 6900' 21. PLUG, BACK T.D., MD & TVD 6776' 22. IF MULTIPLE COMPL., HOW MANY? N/S 23. INTERVALS DRILLED BY 28. INTERVALS DRILLED BY 0-TD 25. WAS DIRECTIONAL SURVEY MADE? YES 27. WAS WELL CORED? NO

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP BOTTOM, NAME (MD AND TVD)* 4907' - 6512' WASATCH/MESAVERDE 26. TYPE ELECTRIC AND OTHER LOGS RUN DILL FDC-CNL

CASING RECORD (Report all strings set in well)

Table with 6 columns: CASING SIZE, WEIGHT, LB./FT., DEPTH SET (MD), HOLE SIZE, CEMENTING RECORD, AMOUNT PULLED. Rows include 9-5/8" 36# 224' 12-1/4" 125 SX and 5-1/2" 17# 6900' 7-7/8" 2270 SX.

LINER RECORD

Table with 7 columns: SIZE, TOP (MD), BOTTOM (MD), BAGS CEMENT, SCREEN (MD), SIZE, DEPTH SET (MD), PACKER SET (MD). Row includes 2-3/8" 4723'.

31. PERFORATION RECORD (Interval, size and number) 3-1/8" CSG GUN AS FOLLOWS:

Table with 4 columns: Interval, Size, Number, Total. Rows include 4907' 5187' 5850' 6510', 4910' 5190' 5852' 6512', 5018' 5550' 6490', 5021' 5558' 6492' TOTAL: 14 HOLES.

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

Table with 2 columns: DEPTH INTERVAL (MD), AMOUNT AND KIND OF MATERIAL USED. Row includes 4907' - 6512' BRKDN W/2800 GAL 3% KCL WTR FRAC W/45,000 GAL GEL & 90,000 LBS 20/40 SAND.

33. PRODUCTION DATE FIRST PRODUCTION 9-25-82 PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) FLOWING WELL STATUS (Producing or shut-in) SI WOPLC

Table with 8 columns: DATE OF TEST, HOURS TESTED, CHOKE SIZE, PROD'N. FOR TEST PERIOD, OIL—BBL., GAS—MCF., WATER—BBL., GAS-OIL RATIO. Row includes 9-25-82 24 16/64" 0 2200 0.

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) VENTED TEST WITNESSED BY KARL ODEN

35. LIST OF ATTACHMENTS NONE

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records. SIGNED W. J. GOODEN TITLE PRODUCTION ENGINEER DATE 9-28-82

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments, interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES: SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF: CORED INTERVALS AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION TEST, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

38. GEOLOGIC MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH	TRUE VERT. DEPTH
				WASATCH FORMATION	4192'	

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other

2. NAME OF OPERATOR
Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR
P. O. Box 749 Denver, Colorado 80201

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 492' FNL/722' FEL (NE NE)
AT TOP PROD. INTERVAL: SAME
AT TOTAL DEPTH: SAME

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:		SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>
(other) <u>MONTHLY REPORT</u>		

5. LEASE
U-01191-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
N/A

7. UNIT AGREEMENT NAME
Natural Buttes Unit

8. FARM OR LEASE NAME
Natural Buttes Unit

9. WELL NO.
Natural Buttes Unit #86J

10. FIELD OR WILDCAT NAME
Natural Buttes Field

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 3-T10S-R22E

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

14. API NO.
43-047-31251

15. ELEVATIONS (SHOW DF, KDB, AND WD)
4944' Ungr. Gr.

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

WELL COMPLETED 9-25-82. COMPLETION REPORT FILED 9-28-82. SEE ATTACHED CHRONOLOGICAL FOR REPORT OF OPERATION THROUGH COMPLETION.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED H. E. Aab TITLE Dist. Drlg. Mgr. DATE OCTOBER 15, 1982

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

NBU #86J (COGC)

Natural Buttes Unit

Uintah County, Utah

AFE: 13048 WI: 100%

ATD: 6900' SD: 8-9-82/8-11-82

Coastal Oil & Gas Corp., Oper.

AllWestern #4, Contr.

9-5/8" @ 224' GL; 5½" @ 6900';

LOCATION: 492' FNL & 722' FEL
NE NE, Sec 3-T10S-R22E
Elv: 4944' GL (ungr)

TD: 6900'

PBSD: 6776'

Perf: 4907-6512' (14 holes)

9-23-82 Flw back to pit after frac.

RU Howco & tst lines to 5100 psi; held safety meeting; SITP & SICP 2000 psi; frac Wasatch perfs 4907-6512' (14 holes) dwn 2-3/8" tbg & 5½" csg annulus with 45,000 gal X-linked gel & 90,000# 20/40 sd as follows: 9000 gal 50# gel pad @ 20 BPM w/2200 psi; 9000 gal 40# w/1 ppg sd @ 30 BPM w/4700 psi; 9000 gal w/2 ppg sd @ 34.4 BPM w/4700 psi; 9000 gal w/3 ppg sd @ 35 BPM w/4600 psi; 9000 gal w/4 ppg sd @ 35 BPM w/4300 psi; flush w/3% KCl wtr; AR 35 BPM @ 4500 psi; ISIP 1710 psi, 30 min 1400 psi; start job @ 8:15 AM, fin @ 9:00 AM; well SION after frac. Cum Compl Csts: \$76,347.

9-24-82 Flw to pit after frac.

Opn to pit on 16/64" CK @ 12 Noon. Cum Csts: \$516,639.

9-25-82 Flwg to pit after frac.

FTP 1500 psi, SICP 1700 psi, 16/64" CK, 1750 MCFD w/10-15 BW (hvy mist) & Tr paraffin.

9-26-82 SI; WO PLC.

FTP 1450 psi, SICP 1550 psi, 16/64" CK, 2200 MCFD w/Tr paraffin & no wtr; SI @ 9:00 AM. Completed as single SIGW f/Wasatch/MV perfs 4907-6512' (14 holes) on 9-25-82, WO PLC. Cum Csts: \$516,639.

9-27-82 SI; WO PLC.

SITP 1975 psi, SICP 1925 psi. Cum Csts: \$520,619. Drop f/report.

Natural Buttes Unit
 Uintah, Utah

AFE: 13048 WI: 100%

ATD: 6900' SD: 8-9-82/8-11-82

LOCATION: NE/4 Sec. 3-T10S-R22E

Coastal Oil & Gas Corp., Oper.

492' FNL/722' FEL (NE NE)

Allwestern #4

4944' Ungr. Gr.

9-5/8" @ 224' GL

8-31-82 6897'; (277' - 23½ hrs); Drlg. 11 FPH.

Drlg.; RS; Drlg. BGG 30, CG 350. Drlg. Brks: 6641'-59', rate 7-3-6 mpf, gas 300-400-200; 6683-6705', rate 7-2-6.5 mpf, gas 200-575-250; 6726'-59', rate 6-1.5-6.5 mpf, gas 250-300-200; 6808-35', rate 7-1.5-7 mpf, gas 250-375-250; 6845'-47', rate 7-2-7 mpf, gas 200-275-200. MW 9.7, VIS 35, WL 11, PV 10, YP 5, Sand ¼, Solids 10, pH 10, ALK.:Pf .8, Mf 1.86, CL 2300, CA 40, GELS 3/6, Cake 2, MBT 15. Cum Csts: \$289,106.

9-1-82 6900'; (3' - ½ hrs); LD DP.

Drlg.; Circ & Cond Hole to Log; TOH to Log; RU "Go"; Logging - DIL, FDC, CL w/Caliper, Logger TD 6895'; RD "Go"; TIH; Circ & Cond Hole, LD DP. TG 1600. MW 9.6, VIS 40, WL, PV 9, YP 5, Sand Tr, Solids 9.5, pH 11, ALK.:Pf .7, Mf 1.5, CL 2300, CA 40, GELS 3/6, Cake 2, MBT 17.5. (1° @ 6900'). Cum Csts: \$297,884.

9-2-82 6900'; RD RT.

LD DP DC's; Cha. Rams; RU Csg. Crews, Run 162 jt's 5½" 17# K-55 LTUC & STC 6903' Land @ 6900' FC 6852'; Circ; Howco Cmt'd 820 sx. 50/50 poz 8% gel 10% salt 6/10% Halid - 24 5#/sk Gilsonite ¼ #/sx flocele. 1450 sx 50/50 poz 2% gel 10% salt 6/10% Halid - 24 ¼ #/sx flocele. good circ. 20 BBLS cmt to surface; ND BOP - set slips; Clean Pits; RD RT. Rig Release 12:00 midnight 9/1/82 will move to NBU 87J (6800'). \$365,726

9-3-82 Final Cost Report.

Cum Csts: \$440,291.

9-4-82 thru 9-7-82 WO CU.

9-8-82 TD 6900'; PBTB 6805'; WO CU.

Tag PBTB @ 6805' KB w/gauge ring & JB on slickline. Cum Csts: \$440,562.

9-9-82 thru 9-14-82 WO CU.

9-15-82 Road rig to loc; SDFN.

Cum Csts: \$443,227.

9-16-82 TD 6900'; PBTB 6776' WL; Prep to perf.

Road to loc; RU NL Well Service; NU BOP; PU, tally & std back 152 jnts 2-3/8" tbg; RU OWP & run GR-CCL f/PBTB of 6776' to 4100'; SDFN. Cum Csts: \$446,897.

9-17-82 Flw to pit after brkdn.

Road to loc; press tst csg to 4800 psi w/rig pmp; RU OWP & perf Wasatch w/3-1/8" csg gun w/1 JSPF as follows: 4907', 4910', 5018', 5021', 5550', 5558', 5850', 5852', 5187', 5190', 6490', 6492', 6510', 6512', Neutron Density depths (14 holes); RIH w/152 jnts 2-3/8" 4.7# J-55 tbg w/NC on btm; landed @ 4723' w/SN @ 4692' & 10' blast jnt at surf; ND BOP, NU tree; RU Western & brkdn Wasatch perms 4907-6512' (14 holes) w/71 bbl 3% KCl wtr w/clay stab & scale inhib & 28 BS; held safety meeting & press tst lines; est rate @ 5.8 BPM w/3200 psi, 9 bbl tot fl pmpd; 2 balls/bbl @ 6.5 BPM w/3900 psi, 23 bbl tot fl pmpd; flush @ 6.2 BPM w/4800 psi, 67 bbl tot fl pmpd; balled off - surge balls; est rate @ 6.8 BPM w/4800 psi, 71 bbl tot fl pmpd; ISIP 1200 psi, 15 min 950 psi; AR 6.2 BPM, AP 4200 psi; opn to pit on 18/64" CK; RD & rel SU. Cum Csts: \$497,332.

9-18-82 Flwg to pit after brkdn.

FTP 1100 psi, SICP 1150 psi, 18/64" CK - frozen; clean CK; flw 1½" stream wtr.

9-19-82 SI; WO frac.

FTP 1400 psi, SICP 1500 psi, 18/64" CK, 2600 MCFD w/mist wtr; SI @ 9:00 AM; WO frac; 9:30 AM SITP 1700 psi, SICP 1700 psi.

9-20-82 SI; WO frac.

SITP 1700 psi, SICP 1700 psi. Cum Compl Csts: \$57,040.

9-21-22-82 SI; WO frac.

Natural Buttes Unit

Uintah, Utah

AFE: 13048 WI: 100%

ATD: 6900' SD: 8-9-82/8-11-82

LOCATION: NE/4 Sec 3-T10S-R22E

Coastal Oil & Gas Corp., Oper.

492 FNL/722' FEL (NE NE)

Allwestern #4

4944' Ungr. Gr.

9-5/8" @ 224' GL

- 8-20-82 3590'; (482' - 23½ hrs); Drlg. 22 FPH.
Drlg.; Svy; Drlg. BGG 200, CG 280. MW 9.2, VIS 33, WL 19, PV 8, YP 3,
Sand ¼, Solids 6, pH 10, ALK.:Pf .2, Mf .4, CL 1100, CA 50, GELS 1/3, Cake 2, MBT 12.5.
(2° @ 3135'). Cum Csts: \$177,674.
- 8-21-82 4058'; (468' - 23½ hrs); Drlg. 18 FPH.
Drlg.; Svy; Drlg. BGG 200, CG 320. MW 9.2, VIS 35, WL 15.2, PV 7, YP 5,
Oil 0, Sand Tr, Solids 6, pH 10.5, ALK.:Pf .27, Mf .46, CL 1500, CA 40, GELS 2/4, Cake
2, MBT 15. (2½° @ 3702'). Cum Csts: \$186,843.
- 8-22-82 4351'; (192' - 18½ hrs); Drlg.
RS; Drlg.; Svy; Drlg. TFNB; Ream 60'; Drlg. BGG 100, CG 200. MW 9.1, VIS 34,
WL 18, PV 5, YP 5, Oil 0, Sand Tr, Solids 5.5, pH 10.5, ALK.:Pf .13, Mf .33, CL 2200,
CA 50, GELS 2/4, Cake 2, MBT 15. (2¼° @ 4202'). Cum Csts: \$195,564.
- 8-23-82 4723'; (372' - 23½ hrs); Drlg. @ 15 FPH.
Drlg.; RS; Drlg. Drlg. Brks: 4388'-4406', rate 5-2-4 mpf, gas 300-500-400;
4426'-4460', rate 4-2.5-4 mpf, gas 300-500-400; 4496'-4504', rate 4-1-3 mpf, gas 400-500-100
BGG 500, CG 550-650 Units. MW 9.1, VIS 34, WL 18, PV 5, YP 5, Oil 0, Sand Tr,
Solids 5.5, pH 10, ALK.:Pf .20, Mf .37, CL 2000, CA 50, GELS 2/4, Cake 2, MBT 15.
Cum Csts: \$207,266.
- 8-24-82 5120'; (397' - 23 hrs); Drlg.
Drlg.; Svy; Drlg.; RS; Drlg. BGG 500, CG 600. Drlg. Brks: 4914'-28', rate
3-1-3.5 mpf, gas 300-700-400; 4932'-38', rate 3.5-1.5-3.5 mpf, gas 400-500-400; 4979'-83',
rate 5-2-4 mpf, gas 600-750-650; 5014'-34', rate 3-1-4.5 mpf, gas 500-1150-650.
MW 9.2, VIS 35, WL 20, PV 6, YP 5, Sand Tr, Solids 6, pH 10, ALK.:Pf .16, Mf .25,
CL 2000, CA 50, GELS 3/6, Cake 2, MBT 15. (2° @ 4723'). Cum Csts: \$219,492.
- 8-25-82 5420'; (300' - 23 hrs); Drlg.
Drlg.; RS; Drlg.; Svy; Drlg. BGG 150, CG 500. Drlg. Brk: 5188'-5206';
rate 3-.5-4 mpf, gas 500-1025-100. MW 9.4, VIS 34, WL 18, PV 7, YP 5, Sand Tr, Solids 7.5,
pH 10, ALK.:Pf .11, Mf .39, CL 2200, CA 40, GELS 3/5, Cake 2, MBT 15. (1-3/4° @ 5324').
Cum Csts: \$227,507.
- 8-26-82 5700'; (280' - 23½ hrs); Drlg.
Drlg. RS. BGG 300, CG 350. Drlg. Brks: 5531'-39', rate 5-1.5-5 mpf, gas
140-700-150; 5555'-71', rate 6-1.5-5 mpf, gas 300-400-250. MW 9.3, VIS 33, WL 16,
PV 8, YP 5, Sand Tr, Solids 7.5, pH 11, ALK.:Pf .70, Mf 1.20, CL 2000, CA 50, GELS 2/4,
Cake 2, MBT 12.5. Cum Csts: \$237,666.
- 8-27-82 5925'; (225' - 18½ hrs); Drlg.
Drlg.; Svy; TFNB; Ream 60'; Drlg.; RS; Drlg. Svy; Drlg. Drlg. Brks: 5716'-22',
rate 8-2-5 mpf, gas 300-600-400; 5855'-64', rate 8-2.5-5 mpf, gas 500-1000-500. BGG 400,
CG 450. MW 9.4, VIS 32, WL 18, PV 8, YP 3, Sand Tr, Solids 7.5, pH 11, ALK.:Pf .62, Mf
1.1, CL 1900, CA 50, GELS 2/4, Cake 2, MBT 12.5. (1¼° @ 5787'). Cum Csts: \$250,285.
- 8-28-82 6202'; (277' - 23½ hrs); Drlg. @ 12 FPH.
Drlg.; RS Chk BOP's; Drlg. Drlg. Brk: 6073'-88', rate 6-1.5-6 mpf, gas
250-375-250. BGG 375, CG 575. MW 9.5, VIS 32, WL 17, PV 8, YP 2, Sand Tr, Solids 8,
pH 11, ALK.:Pf .52, Mf .98, CL 2000, CA 50, GELS 2/4, Cake 2, MBT 12.5. Cum Csts:
\$258,988.
- 8-29-82 6361'; (159' - 16½ hrs); Drlg.
Drlg.; RS, Chk BOP's; Drlg.; TOOH w/Bit #3; Dress Bit, PU Junk Basket;
TIH w/DC's; Cut & Slip Drill Line; TIH w/Bit #4; Ream 45' to Btm; Drlg. Drlg. Brk:
6288'92', rate 4.5-3-6 mpf, gas 400-400-400. BGG 400, CG 450. MW 9.4, VIS 34, WL 19,
PV 7, YP 6, Sand Tr, Solids 8, Ph 11.5, ALK.:Pf .45, Mf .98, CL 2200, CA 50, GELS 3/6,
Cake 2, MBT 15. Cum Csts: \$271,631.
- 8-30-82 6620'; (258' - 23 hrs); Drlg.
Drlg.; RS; Drlg. Svy; Drlg. Drlg. Brks: 6491'-6506', rate 5-1.5-5.5 mpf,
gas 300-875-500, 6511'-26', rate 5.5-1.5-5 mpf, gas 450-500-400; 6548'-52', rate 6.5-2-7 mpf,
gas 300-425-425; 6556'-61', rate 5-2-6 mpf, gas 425-450-400; 6574'-93'; rate 7.5-.5-7.5
mpf, gas 350-800-650. BGG 500, CG 550. MW 9.5, VIS 32, WL 16, PV 7, YP 4, Sand ¼,
Solids 8.5, pH 11.5, ALK.:Pf .6, Mf 1.35, CL 2100, CA 40, GELS 2/4, Cake 2, MBT 12.5.
(1¼° @ 6408'). Cum Csts: \$30,007.

NBU 86J

Natural Buttes Unit

Uintah, Utah

AFE: 13048 WI: 100%

ATD: 6900' SD: 8-9-82/8-11-82

Coastal Oil & Gas Corp., Oper.

Allwestern #4

9-5/8" @ 224' GL

Location: NE/4 Sec. 3-T10S-R22E


492' FNL/722 FEL (NE NE)

4944' Ungr. Gr.

- 8-9-82 224'; (224' - 8 hrs); WO RT.
Drlg 228' 12 1/4" Hole. Ran 5 jts 9-5/8" 47# N-80, LT&C (224'). Cmt w/Howco w/125 sk Class 'G', 2% CaCl2, 1/4#/sk Celoflake. Circ 5 BBLS Cmt to Surface. Job Complete @ 8:30 p.m., 8/7/82. Cum Csts: \$49,369.
- 8-11-82 224'; MIRT.
MI & RU Rig w/Jones Trucking. WO DL. Cum Csts: \$54,569.
- 8-12-82 654'; (426' - 9 1/2 hrs); Drlg.
RU RT. Press Test BOP to 3000 psi; PU BHA, Tag Cem @ 211'; Drlg. Cem 211' to 238'; Drill, Spud 7-7/8" @ 7:30 p.m. 8/11/82; Svy; Drill; Svy; Drill. MW 8.4, VIS 28. (1/2° @ 249'); (3/4° @ 503'). Cum Csts: \$66,009.
- 8-13-82 1800'; (1146' - 16 1/2 hrs); WOC Plug #1.
Drlg.; RS, Svy; Drlg., Lost Total Returns @ 1400'; Dry Drlg to 1800'; TOOH; TIH, Open-Ended to 840'; RU Howco Cmt w/300 sk Thixotropic Cmt, 10% Calseal, 3% CaCl2; TOOH & WOC Plug #1, Fill Hole At 5:00 a.m., Hole Standing Full; WOC Plug #1. MW 8.4, VIS 28. (1° @ 1002'). Cum Csts: \$73,654.
- 8-14-82 1800'; WOC Plug #3.
WOC Plug #1; TIH Tag Cem @ 875'; Drlg. Cem to 1412', Lost Returns; TOH; TIH Open-Ended to 1023'; W/O Howco; Cem Plug #2, 100 sks; 10% CaCl2, 3% CaCl2, 10#/sk Gilsonite, WOC Plug #2; Hole would Not Fill; TIH, No Cem; TOH; TIH Drlg. to 1023', W/O Howco; Plug #3, 250 sks, 10% Cal, 3% CaCl, 10#/sk Gilsonite, WOC F1 @ 100'. MW 8.4, VIS 28. Cum Csts: \$82,249.
- 8-15-82 1800'; WOC Plug #4.
WOC Plug #3; TIH Tag Cem 1021'; Drlg. Cem to 1345', Lost Returns; TOH & TIH to 1200'; W/O Howco; Cem w/150 sks Plug 4 Thix, 10% Cal Seal, 3% CaCl, 10#/sk Gilsonite,; TOH; WOC; Fill Hole after 4 Hrs, Std Full. MW 8.4, VIS 28. Cum Csts: \$102,074.
- 8-16-82 1800, WOC Plug #6.
Drlg. Cmt 1150-1408', Lost Circ @ 1408; POOH; TIH Open-Ended to 930'; WO Howco Cmt Plug #5 w/200 sx Thixotropic +10%, CalSeal + 2% CaCl2 +5#/sx Gilsonite; POOH Test Cmt w/200 psi; WOC - Hole Full; TIH TOC 1118'; Drlg. Cmt 1118'-1501', Lost Circ @ 1501'; POOH; TIH Open-Ended to 1023'; WO Howco Cmt Plug #6, 200 sx Thixotropic +10% CalSeal +2% CaCl2 +5%/sx Gilsonite; POOH Held 300 psi on Cmt; WOC. Cum Csts: \$110,744.
- 8-17-82 1800'; Drlg. Cmt @ 1341' w/Full Returns
WOC Plug #6, Hole Taking Fluid; TIH TOC 1420'; Drlg Cmt 1420'-1460', Lost Circ; POOH; TIH to 1123' Open-Ended; Set Plug #7 200 sx Cl "H" +3% CaCl2, Cmt Return to Surface; POOH in Stds, Squeezed Cmt to 25 psi; WOC, Fill Hole; WOC; TIH TOC @ 1118'; Drlg. Cmt 1118'-1341' w/Full Circ. MW 8.4, VIS 27. Cum Csts: \$150,364.
- 8-18-82 2401'; (601' - 7 hrs); Drlg. @ 55 FPH.
Drlg. Cmt From 1341' to (1500'); Drlg. w/Full Returns; Svy, R.S.; Drlg.; Circ Out Gas @ 2092'; Drlg.; Circ Out Gas @ 2195'; Drlg.; Circ & Cond Mud For Bit Trip & UnPlug 2 Nozzles; POOH Found 2 Nozzles Plugged w/Cmt, Cleaned Bit; TIH w/Same Bit; Drlg. w/Full Returns. BGG 275 Units. MW 9, VIS 36, WL 23, PV 8, YP 4, Sand Tr, Solids 4.5, pH 11.0, ALK.:Pf .43, Mf .92, CL 2200, CA 40, GELS 2/4, Cake 2, MBT 17.5. (1/2° @ 1841'). Cum Csts: \$158,772.
- 8-19-82 3108'; (707' - 22 hrs); Drlg. 20 FPH.
Drlg.; Svy; Drlg.; Work Tite Hole @ 2432'; Drlg.; RS & Svy; Drlg. Svy; Drlg. BGG 200, CG 300. Drlg. Brks: 2586'-2606', rate 2-1.5-2 mpf, gas 30-2425-250; 2656'-63', rate 2-.5-2 mpf, gas 50-50-50; 2688'-2700', rate 2.5-1-2 mpf, gas analyzer down; 2758'-68', rate 2-.5-2 mpf, gas analyzer down; 2866'-83', rate 2-.5-2.5 mpf, gas 70-110-70; 2897'-2902' rate 2.5-.5-2 mpf, gas 70-210-50; 2915'-25', rate 2-1-2 mpf, gas 60-80-60; 2976'-95', rate 2-1-2 mpf, gas 450-550-500; 3044'-54', rate 2-1-2.5 mpf, gas 300-510-400; 3063'-71', rate 2-1-2 mpf, gas 500-700-300. MW 9.2, VIS 34, WL 18, PV 9, YP 3, Sand 1/2, Solids 6/10, ALK.:Pf .25, Mf .35, CL 1106, CA 50, GELS 2/4, Cake 2, MBT 15. (1° @ 2373'); (1-3/4° @ 2431') (1 1/2° @ 2681'). Cum Csts: \$158,658.

NBU 86 J Sec 3 TIOS, RZEE

Hubly 1/11/89



separator

tanks

emergency pit

dehydrator

wellhead

meter run

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT" - for such proposals

5. Lease Designation and Serial No.

U-01191A

6. If Indian, Alottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

Natural Buttes Unit

8. Well Name and No.

NBU #86J

9. API Well No.

43-047-31251

10. Field and Pool, Or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, UT

SUBMIT IN TRIPLICATE

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P. O. Box 749, Denver, CO 80201-0749 (303) 573-4476

4. Location of Well (Footage, Sec., T., R., M., Or Survey Description)

492' FNL & 722' FEL
NE/NE Section 3-T10S-R22E

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

Notice of Intent
 Subsequent Report
 Final Abandonment Notice

Abandonment
 Recompletion
 Plugging Back
 Casing Repair
 Altering Casing
 Other Reperf, Lwr Tbg & Install
Plunger Lift Equipment

Change of Plans
 New Construction
 Non-Routine Fracturing
 Water Shut-Off
 Conversion to Injection
 Dispose Water

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markets and zones pertinent to this work.)*

Please see the attached workover procedure for work to be performed in the subject well.



14. I hereby certify that the foregoing is true and correct

Signed Sheila Bremer Title Environmental & Safety Analyst Date 08/31/95
Sheila Bremer

(This space for Federal or State office use)

APPROVED BY _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

NBU #86J

Section 3-T10S-R22E

PROCEDURE:

1. MI & RU. Kill well w/3% KCl water. ND WH. NU BOP. POOH w/2-3/8" tubing.
2. RU & perforate Wasatch & Mesaverde with 3-1/8" casing gun. Perforate from FDC-CNL log (8/82):

4906	5082	5557	6516	
4907	5087	5558		(88 holes)
4910	5090	5850		
4911	5190	6490		
5014	5192	6492		
5018	5546	6496		
5021	5550	6512		

3. RIH w/2-3/8" tubing to 6510' (new EOT). Swab & flow well to clean up.
4. Install plunger lift stop via WL. ND BOP. NU WH. complete plunger lift installation.
5. After returning well to sales line, obtain rates and pressures.

Rate (2/21/95) prior to W/O: 243 MCFD, 30/64" choke, FTP 300#, CP 450#, LP 268#.

COASTAL OIL & GAS CORP.

CHRONOLOGICAL HISTORY

NBU #86J (*Repair, Lwr. Tbg + PLE*)
Uintah County, Utah
Natural Buttes Field
WI: 100% COGC

5/15/95	Prepare to perforate. Morton & RU Flint #1472. FTP 350, SICP 475. Bleed well off, kill w/150 bbl KCl. ND well head. NU BOP. Ritt tag @ 6688'. POOH Lay down extra tbg. SDFN. DC: \$ 3,600	CC: \$ 3,600
5/16/95	Prepare to swab. SICP 250. Blow down & kill well w/15 bbls 3% KCl. RU Cutters WLS. Perf 22 intervals 4906'-6516'4 SPF (88 holes) w/3-1/8" csg gun. RD Cutters. RIH & broach prod tbg, 209 jts landed @ 6514' w/notched collar on bottom. SN 1 jt above @ 6482' & 10' blast jt on top. ND BOP NU WH. RD & MO Flint rig #1472. MI & RU Delsco swabbing rig. Made 6 swab runs, rec 20 BW, IFL 3500, FFL 3700. SICP 400 psi. Fluid sli gas. Cut no blow. SDFN. Swab well. Blow to tank 20 ch, 100 psi j, 500 casing. DC: \$10,090	CC: \$13,690
5/17/95	Flowing to pit. SICP 600. SITP 0. RU swab made 12 runs, rec 55 BW. IFL 3500, FFL 4800, SICP 450. Well kicked off. Flowed to pit overnight on 20/64 choke. FTP 100, SICP 450. Heavy mist wtr. RD & MO Delsco swbg rig. TP 190, CP 400, Ch 20. Blowing to 400 bbl tank, 15 bbls. DC: \$ 860	CC: \$14,550
5/18/95		
5/19/95	TP 300, CP 600, Ch 40, LP 289, MCF 415, Wtr 22, Down 2. DC: \$ 0.0	CC: \$14,550
5/20/95	TP 300, CP 600, Ch 48, LP 289, MCF 183, Wtr 20, Down 7. Hook up plunger lift 1:30 p.m. DC: \$ 0.0	CC: \$14,550
5/21/95	TP 315, CP 500, Ch 40, LP 289, MCF 509, Wtr 20, Down 8. Plunger lift. DC: \$ 0.0	CC: \$14,550
5/22/95	TP 310, CP 440, Ch 42, LP 301, MCF 544, Wtr 12, Down 4. Plunger lift. DC: \$ 0.0	CC: \$14,550
5/23/95	TP 310, CP 400, Ch 40, LP 301, MCF 517, Wtr 35, Down 2. Plunger lift. DC: \$ 0.0	CC: \$14,550
5/24/95	TP 310, CP 400, Ch 40, LP 289, MCF 471, Wtr 0, Down 5. Plunger lift. DC: \$ 0.0	CC: \$14,550

FINAL REPORT

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

43-047-31251

FORM APPROVED
Budget Bureau No. 1004-0135


Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

Use "APPLICATION FOR PERMIT" - for such proposals

SUBMIT IN TRIPPLICATE



1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	5. Lease Designation and Serial No. See attached spreadsheet
2. Name of Operator Coastal Oil & Gas Corporation	6. If Indian, Alottee or Tribe Name See attached spreadsheet
3. Address and Telephone No. P. O. Box 749, Denver, CO 80201-0749 (303) 573-4476	7. If Unit or CA, Agreement Designation Natural Buttes Unit
4. Location of Well (Footage, Sec., T., R., M., Or Survey Description) See attached spreadsheet	8. Well Name and No. See attached spreadsheet
	9. API Well No. See attached spreadsheet
	10. Field and Pool, Or Exploratory Area Natural Buttes
	11. County or Parish, State Uintah County, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input type="checkbox"/> Other
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Dispose Water

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markets and zones pertinent to this work.)*

The Operator requests approval to empty produced water into tanks on the listed locations. The produced water will then be transported by truck to the underground injection well NBU #159, located at NE/SW Section 35, T9S-R21E, for disposal. Furthermore, the Operator requests approval for the presence of small unlined pits, approximate dimensions of 7' x 7' x 4' deep, to be located immediately adjacent to the stock tanks on the listed locations. The small pits may be necessary to drain off water from the stock tanks at the time of condensate sales. The water will be emptied from the small pit and trucked to the NBU #159 disposal well. The volume of water to be disposed of at each facility will not exceed an average of 5 barrels per day on a monthly basis, in conformance with the requirements of Onshore Order #7.

The listed locations include all wells listed in a Request to Dispose Water sundry dated 10/11/96, as well as all wells drilled to date in the Operator's 1997 drilling program in the Natural Buttes field.

Accepted by the State
of Utah Division of
Oil, Gas and Mining

303-670-3077

14. I hereby certify that the foregoing is true and correct

Signed Bonnie Carson Title Senior Environmental Analyst Date: 12-1-97

Signed Bonnie Carson Title Senior Environmental Analyst By: [Signature] Date: 10/28/97

(This space for Federal or State office use)

APPROVED BY _____ Title _____ Date _____

Conditions of approval, if any:

Must meet pit lining guidelines

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Well Name & No.	API No.	Lease Designation & Serial Number	If Indian, Allottee or Tribe Name	Footages	Qtr/Qtr	Section	Township	Range	Field	County
CIGE #105D-1-10-22E	43-047-31758	U-011336	N/A	842' FNL & 2095' FWL	NENW	1	10	22	Natural Buttes	Uintah
CIGE #114-34-9-21	43-047-31915	ST U-01194-A	N/A	1931' FSL & 535' FEL	NESE	34	9	21	Natural Buttes	Uintah
CIGE #118-35-9-22	43-047-32025	U-010954-A	N/A	2116' FSL & 615' FEL	NESE	35	9	22	Natural Buttes	Uintah
CIGE #124-9-9-21	43-047-32045	U-01188	Ute Tribe Surface	1854' FSL & 1819' FEL	NWSE	9	9	21	Natural Buttes	Uintah
CIGE #129-18-9-21	43-047-32043	U-0581	Ute Tribe Surface	928' FNL & 1837' FWL	NENW	18	9	21	Natural Buttes	Uintah
CIGE #130-19-9-21	43-047-32030	U-0581	Ute Tribe Surface	772' FNL & 714' FEL	NENE	19	9	21	Natural Buttes	Uintah
CIGE #140-16-10-21	43-047-31977	ST ML-10755	N/A	380' FNL & 591' FEL	NENE	16	10	21	Natural Buttes	Uintah
CIGE #144-2-10-22	43-047-32022	ST ML-22651	N/A	1501' FNL & 1719' FEL	SWNE	2	10	22	Natural Buttes	Uintah
CIGE #149-8-10-21	43-047-32056	U-01791	N/A	833' FNL & 2011' FEL	NWNE	8	10	21	Natural Buttes	Uintah
CIGE #161-2-10-22	43-047-32168	ST ML-22651	N/A	297' FSL & 1033' FEL	SESE	2	10	22	Natural Buttes	Uintah
CIGE #164-34-9-22	43-047-32353	U-0149077	N/A	660' FNL & 1739' FWL	NENW	34	9	22	Natural Buttes	Uintah
CIGE #178-5-10-22	43-047-32330	U-01195	N/A	926' FWL & 685' FNL	NWNW	5	10	22	Natural Buttes	Uintah
CIGE #180-16-9-21	43-047-32478	ST ML-3141	N/A	333' FSL & 2557' FWL	SESW	16	9	21	Natural Buttes	Uintah
CIGE #183-20-9-21	43-047-32656	U-0575	Ute Tribe Surface	1725' FSL & 2386' FEL	SWSE	20	9	21	Natural Buttes	Uintah
CIGE #187-13-10-20	43-047-32607	U-4485	N/A	900' FNL & 2200' FWL	NENW	13	10	20	Natural Buttes	Uintah
CIGE #189-29-9-22	43-047-32813	USA U-462	N/A	1574' FNL & 720' FWL	SWNW	29	9	22	Natural Buttes	Uintah
CIGE #194-1-10-22	43-047-32932	USA U-011336	N/A	2017' FNL & 61' FWL	SWNW	1	10	22	Natural Buttes	Uintah
CIGE #197-7-9-21	43-07-32798	U-0149747	N/A	854' FNL & 2178' FEL	NWNE	7	9	21	Natural Buttes	Uintah
CIGE #198-9-9-21	43-047-32799	U-01188	Ute Tribe Surface	2502' FSL & 772' FEL	NESE	9	9	21	Natural Buttes	Uintah
CIGE #199-14-9-21	43-047-32801	U-01193	Ute Tribe Surface	959' FNL & 1760' FWL	NENW	14	9	21	Natural Buttes	Uintah
CIGE #200-16-9-21	43-047-32802	U-38409	Ute Tribe Surface	1950' FNL & 2500' FWL	SENE	16	9	21	Natural Buttes	Uintah
CIGE #201-18-9-21	43-047-32804	U-0575	Ute Tribe Surface	1814' FNL & 944' FEL	SENE	18	9	21	Natural Buttes	Uintah
CIGE #202-21-9-21	43-047-32805	U-0575	Ute Tribe Surface	785' FSL & 471' FEL	SESE	21	9	21	Natural Buttes	Uintah
CIGE #204-35-9-21	43-047-32794	ML-22582	N/A	2055' FNL & 1604' FEL	SWNE	35	9	21	Natural Buttes	Uintah
CIGE #205-1-10-21	43-047-32795	ML-23612	N/A	2110' FNL & 2607' FEL	SWNE	1	10	21	Natural Buttes	Uintah
CIGE #221-36-9-22	43-047-32868	ML-22650	N/A	550' FSL & 514' FEL	NESW	13	9	21	Natural Buttes	Uintah
CIGE #235-25-9-21	43-047-32858	U-01194-ST	N/A	1900' FSL & 1800' FEL	NWSE	25	9	21	Natural Buttes	Uintah
CIGE #236-34-9-21	43-047-32861	U-01194-A-ST	N/A	428' FSL & 882' FEL	SESE	34	9	21	Natural Buttes	Uintah
CIGE #23-7-10-22	43-047-30333	ST ML-23609	N/A	1573' FNL & 1024' FEL	SENE	7	10	22	Natural Buttes	Uintah
CIGE #25-34-9-22	43-047-30737	U-0149077	N/A	2037' FNL & 1608' FWL	SENE	34	9	22	Natural Buttes	Uintah
CIGE #3-32-9-22	43-047-30320	ST ML-22649	N/A	2270' FNL & 900' FEL	SENE	32	9	22	Natural Buttes	Uintah
CIGE #43-14-10-22	43-047-30491	U-01197-A-ST	N/A	1437' FWL & 1416' FNL	NW	14	10	22	Natural Buttes	Uintah
CIGE #59-21-10-21	43-047-30548	U-02278	N/A	809' FSL & 1081' FWL	SWSW	21	10	21	Natural Buttes	Uintah
CIGE #6-19-9-21 (GR)	43-047-30356	U-0581	N/A	1122' FSL & 1542' FEL	SWSE	19	9	21	Natural Buttes	Uintah
CIGE #63D-29-9-22P	43-047-30949	U-462	N/A	521' FNL & 977' FWL	NWNW	29	9	22	Natural Buttes	Uintah
CIGE #9-36-9-22	43-047-30419	ST ML-22650	N/A	2090' FSL & 1852' FEL	NWSE	36	9	22	Natural Buttes	Uintah
CIGE #97D-31-9-22	43-047-31729	U-01530-A-ST	N/A	548' FSL & 907' FEL	SESE	31	9	22	Natural Buttes	Uintah
Morgan State #10-36	43-047-32816	ML-22265	N/A	1794' FNL & 649' FEL	SENE	36	9	21	Natural Buttes	Uintah
Morgan State #11-36	43-047-32813	ML-22265	N/A	1943' FSL & 1843' FEL	NESW	36	9	21	Natural Buttes	Uintah
Morgan State #12-36	43-047-32814	ML-22265	N/A	1992' FSL & 722' FEL	NESE	36	9	21	Natural Buttes	Uintah
Morgan State #13-36	43-047-32817	ML-22265	N/A	540' FSL & 815' FEL	SESE	36	9	21	Natural Buttes	Uintah
Morgan State #2-36	43-047-32585	ST ML-22265	N/A	900' FNL & 804' FWL	NWNW	36	9	21	Natural Buttes	Uintah
Morgan State #4-36	43-047-32729	ST ML-22265	N/A	1912' FSL & 649' FWL	NWSW	36	9	21	Natural Buttes	Uintah
Morgan State #5-36	43-047-32735	ST ML-22265	N/A	2100' FSL & 1800' FEL	NWSE	36	9	21	Natural Buttes	Uintah
Morgan State #8-36	43-047-32812	ML-22265	N/A	650' FNL & 690' FEL	NENE	36	9	21	Natural Buttes	Uintah
Morgan State #9-36	43-047-32815	ML-22265	N/A	1894' FNL & 1978' FEL	SWNE	36	9	21	Natural Buttes	Uintah
NBU #105	43-047-32302	U-0575	N/A	1026' FSL & 1011' FWL	SWSW	17	9	21	Natural Buttes	Uintah
NBU #113	43-047-31931	U-0149077	N/A	580' FSL & 854' FEL	SESE	34	9	22	Natural Buttes	Uintah
NBU #118	43-047-31969	U-5077-B	Ute Tribe Surface	1700' FNL & 660' FEL	SENE	22	9	20	Natural Buttes	Uintah
NBU #12	43-047-30119	U-461	N/A	1563' FSL & 2328' FEL	NWSE	18	9	22	Natural Buttes	Uintah

NBU #121	43-047-32086	UTU-01193	Ute Tribe Surface	819' FNL & 2163' FEL	NWNE	13	9	21	Natural Buttes	Uintah
NBU #123	43-047-31974	U-01188	N/A	827' FNL & 916' FWL	NWNW	15	9	21	Natural Buttes	Uintah
NBU #131	43-047-31966	U-0149075	Ute Tribe Surface	1699' FSL & 800' FWL	NWSW	23	9	21	Natural Buttes	Uintah
NBU #134	43-047-32011	U-0576	N/A	138' FSL & 836' FWL	SWSW	28	9	21	Natural Buttes	Uintah
NBU #140	43-047-31947	U-01191-A	N/A	1031' FNL & 1879' FEL	NWNE	5	10	22	Natural Buttes	Uintah
NBU #148	43-047-31983	U-01191	N/A	279' FSL & 2127' FWL	SESW	4	10	22	Natural Buttes	Uintah
NBU #150	43-047-31992	U-01196-B	N/A	2042' FNL & 2002' FWL	SESW	9	10	22	Natural Buttes	Uintah
NBU #152	43-047-31990	U-01196-D	N/A	815' FSL & 754' FEL	SESE	9	10	22	Natural Buttes	Uintah
NBU #153	43-047-31975	ST U-01197-A	N/A	2500' FNL & 974' FWL	SWNW	11	10	22	Natural Buttes	Uintah
NBU #18	43-047-30221	U-025187	N/A	2401' FWL & 2337' FSL	SWNE	10	10	22	Natural Buttes	Uintah
NBU #180	43-047-32113	U-025187	N/A	843' FSL & 2075' FEL	SWSE	10	10	22	Natural Buttes	Uintah
NBU #182	43-047-32162	U-0141315	N/A	1809' FNL & 1519' FWL	SESW	11	9	21	Natural Buttes	Uintah
NBU #185	43-047-32171	U-01191-A	N/A	2132' FNL & 2126' FEL	SWNE	3	10	22	Natural Buttes	Uintah
NBU #187	43-047-32230	U-0149077	N/A	1057' FSL & 2321' FWL	SESW	34	9	22	Natural Buttes	Uintah
NBU #188	43-047-32234	U-01196-C	N/A	699' FWL & 1248' FSL	SWSW	10	10	22	Natural Buttes	Uintah
NBU #189	43-047-32236	U-0149075	Ute Tribe Surface	1551' FWL & 1064' FSL	SESW	23	9	21	Natural Buttes	Uintah
NBU #198	43-047-32357	U-010950-A	N/A	2041' FEL & 2107' FSL	NWSE	22	9	21	Natural Buttes	Uintah
NBU #201	43-047-32364	U-0149767	Ute Tribe Surface	2310' FNL & 500' FWL	SWNW	9	9	21	Natural Buttes	Uintah
NBU #206	43-047-32341	U-01196-C	N/A	2209' FNL & 303' FWL	SWNW	10	10	22	Natural Buttes	Uintah
NBU #207	43-047-32329	ST U-01197	N/A	912' FNL & 1685' FWL	NENW	10	10	22	Natural Buttes	Uintah
NBU #208	43-047-32343	U-01191	N/A	790' FSL & 569' FEL	SESE	4	10	22	Natural Buttes	Uintah
NBU #210	43-047-32340	U-01196-C	N/A	1956' FSL & 2060' FWL	NESW	10	10	22	Natural Buttes	Uintah
NBU #216	43-047-32487	U-010950-A	Ute Tribe Surface	1875' FSL & 1665' FWL	NESW	15	9	21	Natural Buttes	Uintah
NBU #223	43-047-32517	U-01194-ST	N/A	514' FNL & 2174' FWL	NENW	26	9	21	Natural Buttes	Uintah
NBU #228	43-047-32636	U-0575	Ute Tribe Surface	660' FSL & 1843' FEL	SWSE	17	9	21	Natural Buttes	Uintah
NBU #229	43-47-32594	U-01191-A	N/A	1019' FNL & 1712' FEL	NWNE	3	10	22	Natural Buttes	Uintah
NBU #230A	43-047-32908	U-01191-A	N/A	1849' FNL & 677' FEL	SENE	3	10	22	Natural Buttes	Uintah
NBU #231	43-047-32561	U-01191-A-ST	N/A	966' FNL & 1539' FEL	NWNE	10	10	22	Natural Buttes	Uintah
NBU #252	43-047-32800	U-0141315	Ute Tribal Surface	641' FNL & 1845' FWL	NENW	10	9	21	Natural Buttes	Uintah
NBU #254	43-047-32803	U-0575	Ute Tribal Surface	1840' FNL & 2014' FWL	NESW	17	9	21	Natural Buttes	Uintah
NBU #255	43-047-32806	U-0575	Ute Tribal Surface	642' FSL & 1235' FWL	SESW	21	9	21	Natural Buttes	Uintah
NBU #256	43-047-32807	U-0147566	Ute Tribal Surface	2213' FNL & 2312' FWL	SESW	22	9	21	Natural Buttes	Uintah
NBU #257	43-047-32790	ST U-01194	N/A	1756' FNL & 2150' FWL	SESW	25	9	21	Natural Buttes	Uintah
NBU #258	43-047-32791	ST U-01194	N/A	1880' FNL & 211' FEL	SENE	26	9	21	Natural Buttes	Uintah
NBU #259	43-047-32792	ST U-01194	N/A	2300' FNL & 1850' FEL	SWNE	26	9	21	Natural Buttes	Uintah
NBU #263	43-047-32793	ST U-01194-A	N/A	1641' FNL & 1832' FWL	SESW	34	9	21	Natural Buttes	Uintah
NBU #265	43-047-32796	ML-13826	N/A	1953' FSL & 632' FEL	NESE	2	10	21	Natural Buttes	Uintah
NBU #270	43-047-32862	ML-23608	N/A	1963' FNL & 801' FWL	SWNW	13	10	21	Natural Buttes	Uintah
NBU #280	43-047-32865	ML-32935-A	N/A	2596' FSL & 1459' FWL	NESW	31	9	22	Natural Buttes	Uintah
NBU #289	43-047-32910	U-01191	N/A	463' FSL & 2023' FWL	SESW	3	10	22	Natural Buttes	Uintah
NBU #291	43-047-32911	U-1196-D	N/A	457' FNL & 570' FEL	NENE	9	10	22	Natural Buttes	Uintah
NBU #38N2	43-047-30536	U-08512-ST	N/A	1752' FWL & 1768' FSL	CSW	13	10	22	Natural Buttes	Uintah
NBU #80V	43-047-31240	U-0149077	N/A	2042' FSL & 984' FWL	NWSW	34	9	22	Natural Buttes	Uintah
NBU #86J	43-047-31251	U-01191-A	N/A	492' FNL & 722' FEL	NENE	3	10	22	Natural Buttes	Uintah

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 8 South 1200 East CITY Vernal STATE Utah ZIP 84078		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: 435-789-4433		8. WELL NAME and NUMBER: Exhibit "A"
4. LOCATION OF WELL		9. API NUMBER:
FOOTAGES AT SURFACE:		10. FIELD AND POOL, OR WILDCAT:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		

COUNTY: _____ STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA



TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Name Change</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation	
NAME (PLEASE PRINT) John T. Elzner	TITLE Vice President
SIGNATURE 	DATE 06-15-01
El Paso Production Oil & Gas Company	
NAME (PLEASE PRINT) John T. Elzner	TITLE Vice President
SIGNATURE 	DATE 06-15-01

(This space for State use only)

RECEIVED
JUN 19 2001
DIVISION OF
OIL, GAS AND MINING

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

JUN 14 2001

DIVISION OF
OIL, GAS AND MINING



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

0610204 8100

AUTHENTICATION: 1061007

010162788

DATE: 04-03-01

CERTIFICATE OF AMENDMENT

OF

CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:

"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION

David L. Siddall
Vice President

Attest:

Margaret E. Roark, Assistant Secretary

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

JUL 12 2001

**DIVISION OF
OIL, GAS AND MINING**

In Reply Refer To:
3106
UTSL-065841
(UT-924)

JUL 10 2001

NOTICE

El Paso Production Oil & Gas Company : Oil and Gas
Nine Greenway Plaza :
Houston TX 77046-0095 :

Name Change Recognized


Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.



Opolonia L. Abeyta
Acting Chief, Branch of
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
~~State of Utah~~, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

Exhibit of Leases

UTUSL-065841A	UTU-47172	UTU-74415	UTU-53860
UTU-28652	UTU-50687	UTU-74416	UTU-66401
UTU-37943	UTU-52298	UTU-75091	UTU-67868
UTU-44089	UTU-0109054	UTU-75096	UTU-65389
UTU-44090A	UTU-0143511	UTU-75097	UTU-77084
UTU-61263	UTU-0143512	UTU-75673	UTU-61430
UTU-00343	UTU-38401	UTU-76259	UTU-72633
UTU-02651	UTU-38411	UTU-76260	UTU-72650
UTU-02651B	UTU-38418	UTU-76261	UTU-49692
UTU-0142175	UTU-38419	UTU-76493	UTU-57894
UTU-70235	UTU-38420	UTU-76495	UTU-76829
UTU-70406	UTU-38421	UTU-76503	UTU-76830
UTU-74954	UTU-38423	UTU-78228	UTU-76831
UTU-75132	UTU-38424	UTU-78714	
UTU-75699	UTU-38425	UTU-78727	
UTU-76242	UTU-38426	UTU-78734	
UTU-78032	UTU-38427	UTU-79012	
UTU-4377	UTU-38428	UTU-79011	
UTU-4378	UTU-53861	UTU-71694	
UTU-7386	UTU-58097	UTU-00576	
UTU-8344A	UTU-64376	UTU-00647	
UTU-8345	UTU-65222	UTU-01470D	
UTU-8347	UTU-65223	UTU-0136484	
UTU-8621	UTU-66746	UTU-8344	
UTU-14646	UTU-67178	UTU-8346	
UTU-15855	UTU-67549	UTU-8648	
UTU-25880	UTU-72028	UTU-28212	
UTU-28213	UTU-72632	UTU-30289	
UTU-29535	UTU-73009	UTU-31260	
UTU-29797	UTU-73010	UTU-33433	
UTU-31736	UTU-73013	UTU-34711	
UTU-34350	UTU-73175	UTU-46699	
UTU-34705	UTU-73434	UTU-78852	
UTU-37116	UTU-73435	UTU-78853	
UTU-37355	UTU-73444	UTU-78854	
UTU-37573	UTU-73450	UTU-075939	
UTU-38261	UTU-73900	UTU-0149767	
UTU-39223	UTU-74409	UTU-2078	
UTU-40729	UTU-74410	UTU-44426	
UTU-40736	UTU-74413	UTU-49530	
UTU-42469	UTU-74414	UTU-51026	

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH		4-KAS
2. CDW ✓		5-LP ✓
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X Merger

The operator of the well(s) listed below has changed, effective: **3-09-2001**

FROM: (Old Operator):
COASTAL OIL & GAS CORPORATION
Address: 9 GREENWAY PLAZA STE 2721
HOUSTON, TX 77046-0995
Phone: 1-(713)-418-4635
Account N0230

TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY
Address: 9 GREENWAY PLAZA STE 2721 RM 2975B
HOUSTON, TX 77046-0995
Phone: 1-(832)-676-4721
Account N1845

CA No.

Unit: NATURAL BUTTES

WELL(S)

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 20-1B	43-047-30319	2900	01-10S-22E	FEDERAL	GW	S
CIGE 105D-1-10-22	43-047-31758	2900	01-10S-22E	FEDERAL	GW	P
NBU CIGE 31-1-10-22	43-047-30511	2900	01-10S-22E	FEDERAL	GW	P
CIGE 194-1-10-22	43-047-32932	2900	01-10S-22E	FEDERAL	GW	P
CIGE 223-1-10-22	43-047-32983	2900	01-10S-22E	FEDERAL	GW	P
NBU 37XP	43-047-30724	2900	03-10S-22E	FEDERAL	GW	P
NBU 70	43-047-31100	2900	03-10S-22E	FEDERAL	GW	P
NBU 87J	43-047-31250	2900	03-10S-22E	FEDERAL	GW	S
NBU 86J	43-047-31251	2900	03-10S-22E	FEDERAL	GW	P
NBU 164	43-047-32055	2900	03-10S-22E	FEDERAL	GW	P
NBU 165	43-047-32057	2900	03-10S-22E	FEDERAL	GW	P
NBU 185	43-047-32171	2900	03-10S-22E	FEDERAL	GW	P
NBU 209	43-047-32345	2900	03-10S-22E	FEDERAL	GW	P
NBU 229	43-047-32594	2900	03-10S-22E	FEDERAL	GW	P
NBU 230A	43-047-32908	2900	03-10S-22E	FEDERAL	GW	P
NBU 289	43-047-32910	2900	03-10S-22E	FEDERAL	GW	P
NBU 285	43-047-32976	2900	03-10S-22E	FEDERAL	GW	S
NBU 286	43-047-32984	2900	03-10S-22E	FEDERAL	GW	P
NBU 287	43-047-32985	2900	03-10S-22E	FEDERAL	GW	P
NBU 288	43-047-32986	2900	03-10S-22E	FEDERAL	GW	P

OPERATOR CHANGES DOCUMENTATION

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
4. Is the new operator registered in the State of Utah: YES Business Number: 608186-0143

5. If **NO**, the operator was contacted on: N/A
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 07/10/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 07/10/2001
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: 07/10/2001
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 08/07/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 08/07/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: N/A

FEDERAL BOND VERIFICATION:

1. Federal well(s) covered by Bond No.: WY 2793

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond No: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

FILMING:

1. All attachments to this form have been **MICROFILMED** on: _____

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filed in each well file on: _____

COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".

JAN. 17. 2003 3:34PM

WESTPORT

NO. 173 P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5609

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Debby J. Black
Engineer Technician

Encl:



United States Department of the Interior **RECEIVED**

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:
3106
UTU-25566 et al
(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.


We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chrono





United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Washington, D.C. 20240

FEB 10 2003

IN REPLY REFER TO:
Real Estate Services

Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

Director, Office of Trust Responsibilities

ACTING

Enclosure



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

February 27, 2003

Westport Oil and Gas Company, L.P.
Attn: Gary D. Williamson
1670 Broadway, Suite 2800
Denver, Colorado 80202

Re: Natural Buttes Unit
Uintah County, Utah

Gentlemen:

On February 27, 2003, we received an indenture dated December 17, 2002, whereby El Paso Production Oil & Gas Company resigned as Unit Operator and Westport Oil and Gas Company, L.P., was designated as Successor Unit Operator for the Natural Buttes Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 27, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Natural Buttes Unit Agreement.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover all operations within the Natural Buttes Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
SITLA
Division of Oil, Gas & Mining
Minerals Adjudication Group
File - Natural Buttes Unit (w/enclosure)
Agr. Sec. Chron
Fluid Chron

UT922:TAThompson:tt:02/27/2003

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company		8. WELL NAME and NUMBER: Exhibit "A"
3. ADDRESS OF OPERATOR: 9 Greenway Plaza Houston TX 77064-0995		9. API NUMBER:
PHONE NUMBER: (832) 676-5933		10. FIELD AND POOL, OR WILDCAT:
4. LOCATION OF WELL FOOTAGES AT SURFACE: _____ COUNTY: _____ QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: _____ STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.


BOND # _____

State Surety Bond No. RLB0005236
Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: 
Jon R. Nelsen, Attorney-in-Fact

RECEIVED
FEB 28 2003
DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.	
NAME (PLEASE PRINT) David R. Dix	TITLE Agent and Attorney-in-Fact
SIGNATURE 	DATE 12/17/02

(This space for State use only)

Form 3160-5
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.
SEE ATTACHED EXHIBIT "A"
6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
SEE ATTACHED EXHIBIT "A"

9. API Well No.
SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State
UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
WESTPORT OIL & GAS COMPANY, L.P.

3a. Address
P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	SUCCESSOR OF
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed if testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF. BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)
CHERYL CAMERON

Title
OPERATIONS

Signature

Date
March 4, 2003

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

DIV. OF OIL, GAS & MINING

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH
2. CDW ✓
3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **12-17-02**

FROM: (Old Operator):	TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY	WESTPORT OIL & GAS COMPANY LP
Address: 9 GREENWAY PLAZA	Address: P O BOX 1148
HOUSTON, TX 77064-0995	VERNAL, UT 84078
Phone: 1-(832)-676-5933	Phone: 1-(435)-781-7023
Account No. N1845	Account No. N2115

CA No.

Unit:

NATURAL BUTTES

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 285	03-10S-22E	43-047-32976	2900	FEDERAL	GW	S
NBU 286	03-10S-22E	43-047-32984	2900	FEDERAL	GW	P
NBU 287	03-10S-22E	43-047-32985	2900	FEDERAL	GW	P
NBU 288	03-10S-22E	43-047-32986	2900	FEDERAL	GW	P
NBU 290	03-10S-22E	43-047-32987	2900	FEDERAL	GW	P
NBU 164	03-10S-22E	43-047-32055	2900	FEDERAL	GW	P
NBU 165	03-10S-22E	43-047-32057	2900	FEDERAL	GW	P
NBU 185	03-10S-22E	43-047-32171	2900	FEDERAL	GW	P
NBU 37XP	03-10S-22E	43-047-30724	2900	FEDERAL	GW	P
NBU 70N3	03-10S-22E	43-047-31100	2900	FEDERAL	GW	S
NBU 87J	03-10S-22E	43-047-31250	2900	FEDERAL	GW	S
NBU 86J	03-10S-22E	43-047-31251	2900	FEDERAL	GW	P
NBU 209	03-10S-22E	43-047-32345	2900	FEDERAL	GW	P
NBU 229	03-10S-22E	43-047-32594	2900	FEDERAL	GW	P
NBU 230	03-10S-22E	43-047-32591	2900	FEDERAL	GW	PA
NBU 230A	03-10S-22E	43-047-32908	2900	FEDERAL	GW	P
NBU 289	03-10S-22E	43-047-32910	2900	FEDERAL	GW	P
NBU 170	04-10S-22E	43-047-32169	2900	FEDERAL	GW	S
NBU 208	04-10S-22E	43-047-32343	2900	FEDERAL	GW	P
NBU 311	04-10S-22E	43-047-32837	2900	FEDERAL	GW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
5. If **NO**, the operator was contacted contacted on: _____

6. (R649-9-2) Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 03/24/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 03/24/2003

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238

2. The **FORMER** operator has requested a release of liability from their bond on: N/A

The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
WESTPORT OIL & GAS COMPANY, L.P.

3a. Address
P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Multiple Wells - see attached

5. Lease Serial No.
Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
891008900A

8. Well Name and No.
Multiple Wells - see attached

9. API Well No.
Multiple Wells - see attached

10. Field and Pool, or Exploratory Area
Natural Buttes Unit

11. County or Parish, State
Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped. The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached. Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) **J.T. Conley** Title **Operations Manager**

Signature *J.T. Conley* Date **9-2-2003** Initials **CHD**

SEP 10 2003
DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by _____ Title _____ Date _____

Office **Oil, Gas and Mining** Date **9/16/03**

Accepted by the Utah Division of Oil, Gas and Mining
Federal Approval of This Action Is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Westport Oil & Gas, L.P.
Project Economics Worksheet

Instructions:

Fill in blue areas with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name:

Condensate Shrinkage Economics

Is this job a well pull or production rig job ??? N (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0	\$150	\$150
WATER & HAULING			\$0
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350

Increased OPX Per Year

Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/860	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$/HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

Production & OPX Detail:

	Before		After		Difference	
Oil Production	0.192	BOPD	0.194	BOPD	0.002	BOPD
Gas Production	0	MCFPD	0	MCFPD	0	MCFPD
Wtr Production	0	BWPD	0	BWPD	0	BWPD
Horse Power		HP		HP	0	HP
Fuel Gas Burned		MCFPD		MCFPD	0	MCFPD

Project Life:

Life = Years
 (Life no longer than 20 years)

Internal Rate of Return:

After Tax IROR =

AT Cum Cashflow:

Operating Cashflow = (Discounted @ 10%)

Payout Calculation:

Payout = $\frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}} = 1$

Payout occurs when total AT cashflow equals investment
 See graph below, note years when cashflow reaches zero

Payout = Years or Days


Gross Reserves:

Oil Reserves = 6 BO
 Gas Reserves = 0 MCF
 Gas Equiv Reserves = 38 MCFE

Notes/Assumptions:

An average NBU well produces 0.192 Bcpd with no tank pressure. The production is increased to 0.196 Bcpd if 6 ozs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

WELL	LEGALS	STFLEASENO	CANUMBER	APINO
NBU 058N2	27-10-22 NENW	UTU473	891008900A	430473083800S1
NBU 060	26-9-21 NWSW	U01194	891008900A	430473172800S1 ✓
NBU 062N3	16-10-21 SENW	ML10755	891008900A	430473090900S1
NBU 063N3	12-9-21 SWNW	UTU0141317	891008900A	430473109700S1
NBU 064N3	8-9-21 NESE	UTU0575B	891008900A	430473109800S1
NBU 065N3	14-9-21 SESW	UTU01193	891008900A	430473109900S1
NBU 067A	4-10-22 SWNE	UTU01191	891008900A	430473173700S1
NBU 068N2	26-9-21 NESE	ML22934	891008900A	430473108900S1 ✓
NBU 069N2	35-9-21 SWSW	U01194	891008900A	430473109000S1 ✓
NBU 070N3	3-10-22 SWNW	UTU01191	891008900A	430473110000S1
NBU 072N3	12-10-20 NWNW	UTU4478	891008900A	430473108800S1
NBU 074N3	24-10-20 SWNE	ML22790	891008900A	430473108700S1
NBU 075N3	20-10-21 NENE	UTU02278	891008900A	430473110300S1
NBU 078	30-9-22 NWNW	U463	891008900A	430473176200S1
NBU 080V	34-9-22 NWSW	UTU0149077	891008900A	430473124000S1
NBU 081V	35-9-21 SWNW	U01194	891008900A	430473123200S1 ✓
NBU 083J	27-9-21 NESW	U01194A	891008900A	430473123500S1 ✓
NBU 084V	6-10-22 NWNE	UTU01195B	891008900A	430473124500S1
NBU 085J	4-10-22 SWNW	UTU01191A	891008900A	430473124600S1
NBU 086J	3-10-22 NENE	UTU01191A	891008900A	430473125100S1
NBU 087J	3-10-22 NESW	UTU01191	891008900A	430473125000S1
NBU 088V	26-9-21 NENE	U01194	891008900A	430473123300S1 ✓
NBU 093	33-9-22 NESE	UTU01191A	891008900A	430473175300S1
NBU 097	25-9-21 NENW	U01189	891008900A	430473174400S1 ✓
NBU 098V	34-9-21 SWSW	U01194A	891008900A	430473132700S1 ✓
NBU 099	25-9-21 SWSW	U01194	891008900A	430473174500S1 ✓
NBU 101	3-10-21 NWSE	UTU0149078	891008900A	430473175500S1
NBU 102	5-10-21 SESW	UTU01393D	891008900A	430473175700S1
NBU 1021-16G	16-10-21 SWNE	ML10755	891008900A	430473511100S1 ✓
NBU 1021-20	2-10-21 SWSE	ML13826	891008900A	430473511000S1 ✓
NBU 103	10-9-21 SENW	U0141315	891008900A	430473195600S1
NBU 104	16-9-21 SENE	ML3282	891008900A	430473195700S1
NBU 105	17-9-21 SWSW	UTU0575	891008900A	430473230200S1
NBU 106	21-9-21 NESW	UTU0576	891008900A	430473194600S1
NBU 107	26-9-21 SENW	U01194	891008900A	430473191600S1
NBU 108	19-9-22 SESE	UTU0284	891008900A	430473195800S1
NBU 109	27-9-21 SENE	U01194A	891008900A	430473191700S1 ✓
NBU 110	28-9-21 NENE	U05676	891008900A	430473192400S1
NBU 111	25-9-21 SWNW	U01194	891008900A	430473192000S1 ✓
NBU 112	33-9-22 SESE	UTU01191	891008900A	430473193000S1
NBU 113	34-9-22 SESE	UTU0149077	891008900A	430473193100S1
NBU 114	5-10-21 SWSW	UTU01393D	891008900A	430473192300S1
NBU 115	10-10-21 NENW	UTU0149079	891008900A	430473192900S1
NBU 116	6-10-22 NWNW	UTU464	891008900A	430473192500S1
NBU 117	10-10-22 NENE	U01197A	891008900A	430473191400S1
NBU 118	22-9-20 SENE	UTU0577B	891008900A	430473196900S1
NBU 119	22-9-20 SENW	UTU0577B	891008900A	430473197300S1
NBU 120	10-9-21 NWNW	U0141315	891008900A	430473197200S1
NBU 121	13-9-21 NWNE	U01193	891008900A	430473208600S1
NBU 122	13-9-21 SESE	U01193	891008900A	430473230300S1
NBU 123	15-9-21 NWNW	UTU01188	891008900A	430473197400S1
NBU 124	16-9-21 NWNE	ML3282	891008900A	430473197100S1
NBU 125	17-9-21 SESE	UTU0575	891008900A	430473235000S1
NBU 126	21-9-21 SENW	UTU0576	891008900A	430473234900S1
NBU 127	21-9-21 SWNW	UTU0576	891008900A	430473196300S1
NBU 128	21-9-21 SWSW	UTU0576	891008900A	430473196400S1
NBU 129	22-9-21 SENE	UTU010950A	891008900A	430473196500S1
NBU 130	22-9-21 SWNW	UTU0147566	891008900A	430473196700S1
NBU 131	23-9-21 NWSW	UTU0149075	891008900A	430473196600S1
NBU 132	26-9-21 NWNW	U01194	891008900A	430473193800S1 ✓
NRI 133	28-9-21 SWNE	U05676	891008900A	430473195000S1

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING
1. DJJ
2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective: **1/6/2006**

FROM: (Old Operator): N2115-Westport Oil & Gas Co., LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024	TO: (New Operator): N2995-Kerr-McGee Oil & Gas Onshore, LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024
---	--

WELL NAME	CA No.	Unit:	NATURAL BUTTES UNIT					
	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- 4a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- 4b. If **NO**, the operator was contacted on: _____
- 5a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- 5b. Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- 5c. Reports current for Production/Disposition & Sundries on: ok
- 6. Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
- 7. Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
- 8. Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- 9. Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 5/15/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
- Bond information entered in RBDMS on: 5/15/2006
- Fee/State wells attached to bond in RBDMS on: 5/16/2006
- Injection Projects to new operator in RBDMS on: _____
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: CO1203
- Indian well(s) covered by Bond Number: RLB0005239
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
KERR-McGEE OIL & GAS ONSHORE LP

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SEE ATTACHED

5. Lease Serial No.
MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006. KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203
 BIA BOND = RLB0005239

APPROVED 5116106

Earlene Russell
 Division of Oil, Gas and Mining
 Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) RANDY BAYNE	Title DRILLING MANAGER
Signature <i>Randy Bayne</i>	Date May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
WESTPORT OIL & GAS COMPANY L.P.

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SEE ATTACHED

5. Lease Serial No.
MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal
			<input type="checkbox"/> Water Shut-Off
			<input type="checkbox"/> Well Integrity
			<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
 Division of Oil, Gas and Mining
 Earlene Russell, Engineering Technician

RECEIVED
 MAY 10 2006

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) BRAD LANEY	Title ENGINEERING SPECIALIST
Signature	Date May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by <i>Brad Laney</i>	Title	Date 5-9-06
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Colorado State Office
2850 Youngfield Street
Lakewood, Colorado 80215-7076

IN REPLY REFER TO:

CO922 (MM)
3106
COC017387 et. al.

March 23, 2006

NOTICE

Kerr-McGee Oil & Gas Onshore L.P. :
1999 Broadway, Suite 3700 : Oil & Gas
Denver, CO 80202 :

Merger/Name Change - Recognized

On February 28, 2006 this office received acceptable evidence of the following mergers and name conversion:

Kerr-McGee Oil & Gas Onshore L.P., a Delaware Limited Partnership, and Kerr-McGee Oil & Gas Onshore LLC, a Delaware Limited Partnership merger with and into Westport Oil and Gas Company L.P., a Delaware Limited Partnership, and subsequent Westport Oil & Gas Company L.P. name conversion to Kerr-McGee Oil & Gas Onshore L.P.

For our purposes the merger and name conversion was effective January 4, 2006, the date the Secretary of State of Delaware authenticated the mergers and name conversion.

Kerr-McGee Oil & Gas Onshore L.P. provided a list of oil and gas leases held by the merging parties with the request that the Bureau of Land Management change all their lease records from the named entities to the new entity, Kerr-McGee Oil & Gas Onshore L.P. In response to this request each state is asked to retrieve their own list of leases in the names of these entities from the Bureau of Land Management's (BLM) automated LR2000 data base.

The oil and gas lease files identified on the list provided by Kerr-McGee Oil & Gas Onshore L.P. have been updated as to the merger and name conversion. We have not abstracted the lease files to determine if the entities affected by the acceptance of these documents holds an interest in the lease, nor have we attempt to identify leases where the entity is the operator on the ground that maintains vested record title or operating rights interests. If additional documentation, for change of operator, is required you will be contacted directly by the appropriate Field Office. The Mineral Management Services (MMS) and other applicable BLM offices were notified of the merger with a copy of this notice

Please contact this office if you identify additional leases where the merging party maintains an interest, under our jurisdiction, and we will document the case files with a copy of this notice. If the leases are under the jurisdiction of another State Office that information will be forwarded to them for their action.

Three riders accompanied the merger/name conversion documents which will add Kerr-McGee Oil and Gas Onshore LLC as a principal to the 3 Kerr-McGee bonds maintained by the Wyoming State Office. These riders will be forward to them for their acceptance.

The Nationwide Oil & Gas Continental Casualty Company Bond #158626364 (BLM Bond #CO1203), maintained by the Colorado State Office, will remain in full force and effect until an assumption rider is accepted by the Wyoming State Office that conditions their Nationwide Safeco bond to accept all outstanding liability on the oil and gas leases attached to the Colorado bond.

If you have questions about this action you may call me at 303.239.3768.

/s/Martha L. Maxwell
Martha L. Maxwell
Land Law Examiner
Fluid Minerals Adjudication

Attachment:

List of OG Leases to each of the following offices:

MMS MRM, MS 357B-1

WY, UT, NM/OK/TX, MT/ND, WY State Offices

CO Field Offices

Wyoming State Office

Rider #1 to Bond WY2357

Rider #2 to Bond WY1865

Rider #3 to Bond WY1127



United States Department of the Interior



BUREAU OF LAND MANAGEMENT
Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>

IN REPLY REFER TO:
3106
(UT-922)

March 27, 2006

Memorandum

To: Vernal Field Office

From: Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the merger recognized by the Bureau of Land Management, Colorado State Office. We have updated our records to reflect the merger from Westport Oil and Gas Company L.P. into Kerr-McGee Onshore Oil and Gas Company. The merger was approved effective January 4, 2006.

Chief, Branch of
Fluid Minerals

Enclosure

Approval letter from BLM COSO (2 pp)

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare
Dave Mascarenas
Susan Bauman

RECEIVED

MAR 28 2006

U.S. OF OIL, GAS & MINERALS

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-01191-A
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 86J
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.	9. API NUMBER: 43047312510000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6511 9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0492 FNL 0722 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 03 Township: 10.0S Range: 22.0E Meridian: S	COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/11/2012	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input checked="" type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The operator requests authorization to temporarily abandon the subject well location to drill the NBU 1022-3A Well Pad. Please see attached procedure. Thank you.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY

September 12, 2012

NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 9/11/2012	

Well Name: **NBU 86J**
 Surface Location: NENE Sec. 3, T10S, R22E
 Uintah County, UT

8/9/12

Recommended action for disposition of well bore:

This well will be temporarily abandoned to accommodate drilling operations in one of 2 ways. We will either plug the wellbore as outlined in the attached procedure or Shut-In in the following manner: a) Set a tubing plug near EOT, install a flange over the tbg hanger, removal of master valve, set VR plugs in casing head at surface, and removal of casing wing valves, replaced with blind flanges.

API: 4304731251 LEASE#: U-01191A
 ELEVATIONS: 4944' GL 4962' KB
 TOTAL DEPTH: 6900' PBSD: 6776'
 SURFACE CASING: 9 5/8", 36# @ 224'
 PRODUCTION CASING: 5 1/2", 17# @ 6900'
 No CBL on file
 PRODUCTION TUBING: 2 3/8" J-55 TBG @ 6405' (WL rpt 4/29/10)
 PERFORATIONS: WASATCH 4907' - 6512'

Tubular/Borehole	Drift inches	Collapse psi	Burst psi	Capacities		
				Gal./ft.	Cuft/ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624	0.02171	0.0039
5.5" 17# J-55	4.892	4910	5320	0.9764	0.1305	0.02324
9.625" 36# K-55	8.921	2020	3520	3.247	0.434	0.0773
Annular Capacities						
2.375" tbg. X 5 1/2" 17# csg				0.7013	0.0937	0.0167
5.5" csg X 9 5/8" 36# csg				2.0128	0.2691	0.0479
5.5" csg X 7.875 borehole				1.4407	0.1926	0.0343
9 5/8" csg X 12 1/4" borehole				2.3436	0.3132	0.0558

GEOLOGICAL TOPS:
 4192' Wasatch

NBU 86J TEMPORARY ABANDONMENT PROCEDURE

GENERAL

- H2S MAY BE PRESENT. CHECK FOR H2S AND TAKE APPROPRIATE PRECAUTIONS.
- CEMENT QUANTITIES BELOW ASSUME NEAT CLASS G, YIELD 1.145 CUFT./SX. IF A DIFFERENT PRODUCT IS USED, WELLSITE PERSONNEL ARE RESPONSIBLE FOR CORRECTING QUANTITIES TO YIELD THE STATED SLURRY VOLUME. WHEN SQUEEZING, INCLUDE 10% EXCESS PER 1000' OF DEPTH.
- TREATED FRESH WATER WILL BE PLACED BETWEEN ALL PLUGS INSTEAD OF BRINE.
- ALL DISPLACEMENT FLUID SHALL CONTAIN CORROSION INHIBITOR AND BIOCIDES. PREMIX 5 GALLONS PER 100 BBLs FLUID.
- NOTIFY BLM/UDOGM 24 HOURS BEFORE MOVING ON LOCATION.

PROCEDURE

Note: An estimated 35 sx of cement needed to perform procedure.

1. MIRU. KILL WELL AS NEEDED. ND WH, NU AND TEST BOPE.
2. RU WIRELINE. ENSURE WELLBORE IS CLEAN. **A GPS READING WILL NEED TO BE TAKEN AT THE WELL SITE AND RECORDED IN OPENWELLS. PLEASE TAKE IT TO THE 6TH DECIMAL PLACE.**
3. RUN GYRO SURVEY.
4. **PLUG #1, ISOLATE WAS PERFORATIONS (4907' - 6512')**: RIH W/ 5 1/2" CBP. SET @ ~4850'. RELEASE CBP, PUH 10', BRK CIRC W/ FRESH WATER. PRESSURE TEST CASING TO 500 PSI. INFORM ENGINEERING IF IT DOESN'T TEST. DISPLACE A MINIMUM OF **11 SX/ 2.3 BBL/ 13.1 CUFT.** ON TOP OF PLUG. PUH ABOVE TOC (~4750'). REVERSE CIRCULATE W/ TREATED FRESH WATER.
5. **PLUG #2, PROTECT TOP OF WASATCH (4192')**: PUH TO ~4300'. BRK CIRC W/ FRESH WATER. DISPLACE A MINIMUM OF **24 SX / 4.9 BBL / 27.4 CUFT** AND BALANCE PLUG W/ TOC @ ~4090' (210' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED FRESH WATER.
6. LOWER WELLHEAD TO GROUND LEVEL TO ACCOMMODATE DRILLING OPS AND INSTALL MARKER PER UDOGM GUIDELINES.
7. RDMO. TURN OVER TO DRILLING OPERATIONS.

ALM 8/14/12

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-01191-A
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well		8. WELL NAME and NUMBER: NBU 86J
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		9. API NUMBER: 43047312510000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0492 FNL 0722 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 03 Township: 10.0S Range: 22.0E Meridian: S		PHONE NUMBER: 720 929-6511
		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input checked="" type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 6/3/2013			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The operator has concluded the temporary abandonment operations on the subject well location on 06/03/2013. This well was plugged in order to expand and drill the NBU 1022-3A Pad wells. Please see the attached chronological well history for details. Thank you.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY
 August 16, 2013**

NAME (PLEASE PRINT) Teena Paulo	PHONE NUMBER 720 929-6236	TITLE Staff Regulatory Specialist
SIGNATURE N/A	DATE 7/19/2013	

US ROCKIES REGION
Operation Summary Report

Well: NBU 86J		Spud Date:						
Project: UTAH-UINTAH		Site: NBU 86J		Rig Name No:				
Event: ABANDONMENT		Start Date: 5/30/2013		End Date: 6/3/2013				
Active Datum: RKB @0.00usft (above Mean Sea Level)		UWI: NBU 86J						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
5/31/2013	-		ABANDT	34	I	P		MIRU CUTTERS WIRELINE.
	7:00 - 10:30	3.50	ABANDT	30	A	P		7AM. (DAY 1) JSA - - R/D RIG, ROADING RIG, R/U RIG. RDMO NBU 1022-10A2T. ROAD RIG TO NBU 86J. MIRU, SPOT EQUIPMENT. FTP=60#, SICIP=200#. BLEW WELL DN. KILL WELL W/ 20 BBLS DN TBG & 20 BBLS DN CSG. NDWH, NUBOP. RIG UP FLOOR & TBG EQUIPMENT.
	10:30 - 14:00	3.50	ABANDT	31	I	P		MIRU SCAN TECH. POOH SCANNING 209 JTS 2-3/8" J-55 TBG. 37 YELLOW, 114 BLUE, & 58 RED. BTM 10 JTS HAD SEVERE PITTING ON OD. KILL TBG W/ ANOTHER 20 BBLS TO GET REMAING 20 JTS OUT OF HOLE.
	14:00 - 15:30	1.50	ABANDT	34	I	P		MIRU CUTTERS WIRE LINE. RIH W/ GAUGE RING FOR 5.5" CSG TO 4932'. POOH & L/D GAUGE RING. RIH W/ HLBRTN 5.5" 8K CBP & SET @ 4858'. POOH , L/D TOOLS, RDMO CUTTERS.
	15:30 - 17:00	1.50	ABANDT	31	I	P		RIH OUT OF DERRICK ON 2-3/8" TBG. EOT @ 4810'. SWI-SDF-WE. PREP TO PMP 2 BALANCED CMT PLUGS ON MONDAY 6/3/13
6/3/2013	7:00 - 7:15	0.25	ABANDT	48		P		HSM, SLIPS, TRIPS & FALLS, PUMPING CMT, L/D TBG
	7:15 - 8:30	1.25	ABANDT	51	D	P		EOT @4,810' FILL CSG W/ 110 BBLS TMAC & PRESSURE TEST TO 500#. 0# LOST IN 5 MIN MIRU PRO PETRO. MIX & PMP 15 SX CMT 15.8# , 1.15 YEILD, CLASS G CMT. ESTIMATE CMT TOP @ 4,678'. POOH & L/D 16 JTS TBG ON FLOAT W/ EOT @ 4,306'. MIX & PMP 25 SX CMT, 15.8# , 1.15 YEILD, CLASS G CMT. ESTIMATE CMT TOP @ 4,086'. RDMO PRO PETRO.
	8:30 - 12:00	3.50	ABANDT	31	I	P		POOH LAYING DOWN ALL TUBING. R/D FLOOR & TBG EQUIP, ND BOP. PREP WELL HEAD FOR DRILLING OPS. GPS - - 39.98378 , 109.41851, & ELEVATION 4,944', RDMO TO NBU 921-27A PAD
6/10/2013	7:00 -							REMOVE PRODUCTION FACILITIES TO PREPARE LOCATION FOR PAD DRILLING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-01191-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 86J
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0492 FNL 0722 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 03 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047312510000
PHONE NUMBER: 720 929-6100		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input checked="" type="checkbox"/> OTHER	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 1/22/2014	<input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="SHUT-IN"/>	
<input type="checkbox"/> SPUD REPORT Date of Spud:		
<input type="checkbox"/> DRILLING REPORT Report Date:		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The subject well was temporarily abandoned to drill and complete the NBU 1022-03A Pad. On 1/22/2014. Well work had completed drilling out plugs and preparing well to return to production. The well is currently in a shut-in status. Please see attached daily summary.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 27, 2014		
NAME (PLEASE PRINT) Teena Paulo	PHONE NUMBER 720 929-6236	TITLE Staff Regulatory Specialist
SIGNATURE N/A	DATE 2/27/2014	

US ROCKIES REGION
Operation Summary Report

Well: NBU 86J		Spud Date:	
Project: UTAH-UINTAH		Site: NBU 1022-03A PAD	Rig Name No:
Event: ABANDONMENT		Start Date: 12/15/2013	End Date: 1/22/2014
Active Datum: RKB @0.00usft (above Mean Sea Level)		UWI: NBU 86J	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
12/15/2013	7:00 -							REBUILD PROD FACILITIES TO RETURN WELL TO PRODUCTION
1/20/2014	7:00 - 7:30	0.50	ABANDT	48		P		HSM, RIGGING DOWN & MOVING EQUIP.
	7:30 - 13:30	6.00	ABANDT	30	A	P		RD OFF NBU 922-3113CS, MIRU ND WH NU BOPS RU FLOOR & EQUIP.
	13:30 - 17:30	4.00	ABANDT	31	I	P		TALLY & PU 3 3/4 BIT & 126 JTS 23/8 J-55, TAG UP @ 3940' RU DRILG EQUIP, SWI SDFN.
1/21/2014	7:00 - 7:30	0.50	ABANDT	48		P		HSM, DRILLING CMT W/ POWER SWIVEL.
	7:30 - 15:00	7.50	ABANDT	44	A	P		BROKE CIRC REV, TEST BOPS TO 1,000 PSI, D/O CMT F/ 3940'-3960' 20' FELL FREE TO 4131', D/O CMT F/ 4130 -4330' 199' CMT. FELL FREE TO 4768' DRL CMT TO 4833' 66' CMT. CIRC CLN, RD SWIVEL.
	15:00 - 17:00	2.00	ABANDT	31	I	P		POOH W/ 154 JTS L/D BIT & BIT SUB.PU RIH W/ MILL & 70 JTS 23/8 SWI DRAIN EQUIP SDFN.
1/22/2014	7:00 - 7:30	0.50	ABANDT	48		P		HSM, WORKING W/ FAOM INIT.
	7:30 - 8:30	1.00	ABANDT	31	I	P		SICP 0, RIH W/ REM 84 JTS TOTAL 154. RU SWIVEL INSTALLED TSF PU JT 155.
	8:30 - 17:00	8.50	ABANDT	44	C	P		BROKE CIRC W/ AIR/FOAM IN 50 MIN. D/O 2' CMT D/O CBP @ 4858' IN 2 MIN NO INCREASE.CIRC CLN, PU JT 156, TAGGED NOTHING, KILL TBG, PULL UP REMOVED TSF, PU TBG TO 6629' 117' PAST BTM PERF, 212 JTS IN, CIRC WELL CLN W/ AIR/ FOAM. KILL TBG, LAY DWN 3 JTS LAND TBG ON 209 JTS 23/8 J-55.ND BOPS NU WH PUMPED OFF BIT SWI, RIG DWN MOVE OVER & RIGGED UP ON NBU 1022-30A1BS ND WH NU BOPS, SWI SDFN.
								KB = 18' HANGER 7 1/16 = .83' 209 JTS 23/8 J-55 = 6521.52' POBS W/ 1.875 X/N = 2.20' EOT @ 6542.55'
								TWLTR 60 BBLS

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-01191-A	
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		8. WELL NAME and NUMBER: NBU 86J	
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		9. API NUMBER: 43047312510000	
PHONE NUMBER: 720 929-6111		9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0492 FNL 0722 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 03 Township: 10.0S Range: 22.0E Meridian: S		COUNTY: UINTAH	
		STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 4/21/2014	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.			
<p>THE SUBJECT WELL WAS RETURNED TO PRODUCTION ON 4/21/2014 FROM A TEMPORARY ABANDON STATUS. DETAILS OF THE PLUG REMOVAL WAS SUBMITTED VIA SUNDRY ON 2/27/14.</p>			
<p>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 23, 2014</p>			
NAME (PLEASE PRINT) Teena Paulo	PHONE NUMBER 720 929-6236	TITLE Staff Regulatory Specialist	
SIGNATURE N/A		DATE 4/22/2014	