

CNG Producing
Company

CNG COMPANY

September 4, 1991

Mr. Ed Forsman
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: River Bend Unit
Application for Permit To Drill
RBU ~~River Bend Unit~~ 13-35B
Section 35-T9S-R19E

Gentlemen:

Enclosed please find original and two copies of the subject applications.
Attachment to this application includes the following:

Attachment No. 1	Location
Attachment No. 2	Certification Statement
Attachment No. 3	BOP Stack Schematic
Attachment No. 4	Drilling Plan
Attachment No. 5	13 Point Surface Use Plan
Attachment No. 6	Water Source and Access Route
Attachment No. 7	Water Permit

CNG Producing Company is requesting all information be held confidential.

It would be appreciated if this permit could be expedited since drilling is planned to begin on October 20, 1991.

Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, Doss Bourgeois at (504) 593-7719.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

Enclosure

cc: Utah Board of Oil, Gas & Mining

RECEIVED

SEP 05 1991

DIVISION OF
OIL GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE
(Other instruction on reverse side)

Form approved.
Budget Bureau No. 1004-0136
Expires August 31, 1985

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
 DRILL [X] DEEPEN [] PLUG BACK []

b. TYPE OF WELL
 OIL WELL [] GAS WELL [X] OTHER [] SINGLE ZONE [] MULTIPLE ZONE []

2. NAME OF OPERATOR
CNG PRODUCING COMPANY

3. ADDRESS OF OPERATOR
CNG Tower, 1450 Poydras St., New Orleans, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
 At surface
815' FWL & 814' FSL
 At proposed prod. zone
Same *5WSW*

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
10 Miles SW of Ouray

5. LEASE DESIGNATION AND SERIAL NO.
U-017713

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
~~River Bend Unit~~

8. FARM OR LEASE NAME
RBU

9. WELL NO.
13-35B

10. FIELD AND POOL, OR WILDCAT
ISLAND Undersaturated 002

11. SECS., T., R., M., OR BLK. AND SURVEY OR AREA
35-T9S-R19E

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

CONFIDENTIAL

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT.
 (Also to nearest drlg. unit line if any) **815'**

16. NO. OF ACRES IN LEASE **1,240'**

17. NO. OF ACRES ASSIGNED TO THIS WELL **160**

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE **3,850'**

19. PROPOSED DEPTH **8,300'**

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
4,923' GR

22. APPROX. DATE WORK WILL START
October 20, 1991

23. PROPOSED CASING AND CEMENTING PROGRAM				QUANTITY OF CEMENT
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	
12 1/4"	8 5/8"	24#	+/- 400	Cement to Surface
7 7/8"	5 1/2"	17#	+/- 8,300	Cement Calc to Surface

1. Drill a 12 1/4" hole with an air rig to +/-400', run 8 5/8", H-40 casing and cement to surface.
2. NU and pressure test BOP stack (Attach #2) prior to drilling out below surface pipe.
3. Operate pipe rams daily and blind rams as possible.
4. Drill a 7 7/8" hole to 8,300' with a salt water mud system. Coring is possible. DST's will be run as needed to evaluate unexpected shows.
5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, tests, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
6. Primary zones of interest are the Wasatch, Chapita Wells & Ute land Buttes.
7. All zones indicating potential for economically recoverable reserves will be tested in a normal prudent manner.
8. In the event circulation is lost, air or air assisted mud will be utilized.

RECEIVED

SEP 05 1991

DIVISION OF OIL GAS & MINING

CONFIDENTIAL

FORMATION TOPS	DEPTH
Wasatch Tongue	4,950'
Chapita Wells	6,100'
Ute land Buttes	7,200'

CNG Producing respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true verticle depth Give blowout preventer program, if any.

24. SIGNED *Doss R. Bourgeois* TITLE Supervisor, Drilling Engineering DATE 9/12/91

(This space for Federal or State office use)

PERMIT NO. 43-047-30094 APPROVAL DATE _____


APPROVED BY *JRM* TITLE 615-3-2

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side

**CNG PRODUCING CO.
WELL LOCATION PLAT
RBU 13-35B**

LOCATED IN THE SW $\frac{1}{4}$ OF THE SW $\frac{1}{4}$ OF
SECTION 35, T9S, R19E, S.L.B.&M.



SCALE: 1"=1000'

LEGEND & NOTES


◆ Monuments found and used by this survey.

The General Land Office (G.L.O.) plat was used for reference and calculations as was the U.S.G.S. map.

SURVEYOR'S CERTIFICATE

I hereby certify that this plat was prepared from field notes of an actual survey performed by me, during which the shown monuments were found or established.

Jerry D. Allred
 Jerry D. Allred, Registered Land Surveyor, Cert. No. 3817 (Utah)



JERRY D. ALLRED & ASSOCIATES
 Surveying & Engineering Consultants

121 North Center Street
 P.O. Drawer C
 DUCHEBNE, UTAH 84021
 (801) 738-5352

27 Aug '91

79-128-189

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Disgration River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T9S-R19E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Utah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Variance in casing	<input type="checkbox"/> Dispose Water
		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Under Onshore Order #2, casing and cementing requirements, it states " All casing, except the conductor casing, shall be new or reconditioned and tested used casing that meets or exceeds API standards for new casing" the 8 5/8" 24# H-40 surface casing designed for this well and other wells in the River Bend Unit meets all of the above criteria for the order. The 8 5/8" casing is a limited service pipe which means it does not meet API standards. However, the pipe is new and was Hydro statically tested to 2,700 PSI which equals API standards for 8 5/8" 24# K-55 casing.

We respectfully submit this sundry and attached letter from the company the pipe was purchased from.

If any additional information is needed, please advise.

CONFIDENTIAL

14. I hereby certify that the forgoing is true and correct

Signed Doss R. Bourgeois for Title Supervisor, Drilling Eng. Date September 4, 1991

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:



Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

DIVISION OF
OIL GAS & MINING

DRILLING PLAN
APPROVAL OF OPERATIONS

September 4, 1991

Attachment for Permit to Drill

Name of Operator: CNG PRODUCING COMPANY

Address: CNG TOWER - 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000

WELL LOCATION: Well No. 13-35B

Uintah, Utah

1. GEOLOGIC SURFACE FORMATION

Uintah

CONFIDENTIAL

2. ESTIMATE IMPORTANT GEOLOGIC MARKERS

<u>Formation</u>	<u>Depth</u>
Wasatch Tongue	4950'
Green River Tongue	5300'
Wasatch	5450'
Chapita Wells	6100'
Uteland Buttes	7200'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS

<u>Formation</u>	<u>Depth</u>	<u>Remarks</u>
Wasatch Tongue	4950'	Oil Zone
Chapita Wells	6100'	Gas Zone
Uteland Buttes	7200'	Gas Zone

4. PROPOSED CASING PROGRAM

8-5/8", 24#/ft, H-40, 0'-400' - Cemented to Surface
5", 17#/ft, N-80 & K-55, 0'- 8300' - Cemented to Surface

5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

See Attachment No. 2, Attached.

BOP stack has a 3000 psi working pressure. BOP will be pressure tested to 2,700 psi before drilling casing cement plug. Pipe rams will be operated daily and blind rams as possible.

6. The well is to be drilled with a Potassium Chloride mud system maintaining a weight of approximately 9#/gal.

CONFIDENTIAL

7. AUXILIARY EQUIPMENT TO BE USED

1. Kelly Cock.
2. Full opening valve on floor with DP connection for use when Kelly is not in string.
3. Pit volume totalizer equipment will be used.

8. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

A mud logger will be used from 3,500' to TD. Possible DST in Wasatch Tongue. The logging program will include Dual Lateral/GR log TD to Surface, Density/Neutron - TD - 3,500' possible dipmeter and rotary cores over selected intervals.

9. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

No normal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H₂S gas. The anticipated bottom hole pressure is 2,610 PSI.

10. WATER SUPPLY

- A. Water to be used for drilling will be hauled from the Green River located South 2,016' and East 1,590' from the West 1/4 corner of Section 19-T10S-R18E. Application #61599 Water Right No. #47-1761.
- B. No pipelines are anticipated. Hauling will be on the road(s) shown in Attachment No. 3.
- C. No water well is anticipated to be drilled at this time.

11. CEMENT SYSTEMS

Lead Slurry - 195 sk DS Hi-Lift, 3% D-44 Salt, 10#/sk D-42 Kolite,
.25#/sk D-29 Celloflake.

Tail Slurry - 335 sk RFC 10-0 (thixotropic).

12. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: October 20, 1991

Duration: 20 Days

Date NOS Received: _____

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: CNG PRODUCING COMPANY

Well Name & Number: RBU 13-35B

Lease Number: U-017713

Location: SW/4 of SW/4 Sec. 35 T. 9S R. 19E

Surface Ownership: Bureau of Land Management

NOTIFICATION REQUIREMENTS

- Location Construction - forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONFIDENTIAL

B. THIRTEEN POINT SURFACE USE PROGRAM:

Multipoint Requirement to Accompany APD

1. Existing Roads - describe the following and provide a legible map, labeled and showing:
 - a. Proposed wellsite as staked and access route to location, including distances from point where access route exists establish roads. (Actual staking should include tow directional reference stakes.)
 - b. Route and distance from nearest town or locatable reference point, such as a highway or county road, to where well access route leaves main road.
 - c. Access road(s) to location color-coded or labeled.
 - d. Plans for improvement and/or maintenance of existing roads. (Appropriate rights-of-way for off lease roads should be attached.)

2. Planned Access Roads--describe the following and provide a map of suitable scale indicating all necessary access roads (permanent and temporary) to be constructed or reconstructed, showing:
 - a. Length - 1,350
 - b. Width - 30 foot right-of-way with 18 foot running surface maximum.
 - c. Maximum grades - 8%
 - d. Turnouts - None
 - e. Drainage design - Bar Pits
 - f. Location and size of culverts and/or bridges, and brief description of any major cuts and fills - None
 - g. Surfacing material (source) - Native
 - h. Necessary gates, cattleguards, or fence cuts and/or modification to existing facilities - None

(New or reconstructed roads are to be centerline-flagged at time of location staking.)

All travel will be confined to existing access road rights-of-way.

Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

X Right-of-Way Application needed.

Needed for 700' long x 30' wide access road in NE/4 of NE/4 of sec. 3-T10S-R20E.

_____ The operator/lessee or his/her successor shall be responsible for all maintenance on cattleguards or gates associated with this oil and/or gas operation.

3. Location of Existing Wells - describe the following and provide a map or plat of all wells within a 1 mile radius of the proposed well location showing and identifying existing:

- a. Water wells
- b. Abandoned wells
- c. Temporarily abandoned wells
- d. Disposal wells
- e. Drilling wells
- f. Producing wells
- g. Shut-in wells
- h. Injection wells

CONFIDENTIAL

4. Location of Existing and/or Proposed Facilities

a. On well pad: Show the following existing area facilities and dimensions to be utilized if the well is successfully completed for production (detail painting plans and color if applicable):

- (1) Tank batteries
- (2) Production facilities
- (3) Oil gathering lines
- (4) Gas gathering lines
- (5) Injection lines
- (6) Disposal lines
- (7) Surface pits (separate application per NTL-2B requirements)

(Indicate if any of the above lines are buried.)

b. Off well pad: Same as above. Off lease flowlines may require rights-of-way or special use permits, check with the District Office Realty Specialist. (Include a diagram of the proposed attendant lines, i.e., flowlines, powerlines, etc., if off well pad location.)

(1) Proposed location and attendant lines shall be flagged off of well pad prior to archaeological clearance.

(2) Dimensions of facilities

(3) Construction methods and materials

CONFIDENTIAL

(4) Protective measures and devices to protect livestock and wildlife

Note: Operator has option of submitting information under 4A and B, after well is completed for production, by applying for approval of subsequent operations.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

Tank batteries will be placed on the Northwest side of
location

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Desert Tan.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

5. Location and Type of Water Supply

- a. Show location and type of water supply, either by 1/4, 1/4 section on a map or by written description Green River
- b. State method of transporting water, and show any roads or pipelines needed.
- c. If water well is to be drilled on lease, so state. _____

*The operator will be responsible for acquiring the necessary permit to obtain water to be used for drilling activities.

6. Source of Construction Materials

- a. Show information either on map or by written description - _____.
- b. Identify if from Federal or Indian (tribal or allotted) land.
- c. Describe where materials such as sand, gravel, stone, and soil material are to be obtained and used.

*If fill materials are needed to construct roads or well sites, proper permits must be obtained from the Surface Management Agency, unless materials are obtained from a private source.

*A mineral materials application (is/is not) required.

7. Methods of Handling Waste Disposal

- a. Describe methods and location of proposed safe containment and disposal of each type of waste material, including:
 - (1) Cuttings - bury in pit
 - (2) Sewage - haul to sewer lagoon
 - (3) Garbage (trash) and other waste material - haul to disposal
 - (4) Salts - not used
 - (5) Chemicals - non-toxic only; evaporate in pits
- b. Provide a plan for eventual disposal of drilling fluids and any produced oil or water recovered during testing operations. _____

*Burning will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BLM administered lands:

The reserve pit shall be constructed so as not to leak, break, or allow discharge.

The reserve pit (shall/shall not) be lined.

"If a plastic nylon reinforced liner is used, it will be a minimum of 10 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O."

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

On BIA administered lands:

All reserve pits will be lined with either native clay, commercial bentonite or plastic sufficient to prevent seepage. (If a plastic nylon reinforced liner is used, it shall be torn and perforated after the pit dries and before backfilling of the reserve pit.)

 To protect the environment.

If the reserve pit is lined the operator will provide the BLM a chemical analysis of the fluids in that pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements described by Part II, Standards of Quality for Waters of the State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.

 X To protect the environment (without a chemical analysis).

Reserve pits will be constructed so as not to leak, break, or allow discharge of liquids.

 Storage tanks will be used if drill sites are located on tribal irrigable land, flood plains, or on lands under crop production.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

- b. The net wire shall be no more than 2-inches above the ground. The barbed wire shall be 3-inches above the net wire. Total height of the fence shall be at least 42-inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguard (shall/shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. Plans for Restoration of Surface

CONFIDENTIAL

a. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 6 months from the date of well completion. Before any dirt work takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc., will be removed.

Contact appropriate surface management agency for required seed mixture.

b. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

On BIA administered lands:

Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) re-establishing irrigation systems where applicable, (b) re-establishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and, (c) ensuring revegetation of the disturbed areas to the specifications of the Ute Indian Tribe or the BIA at the time of abandonment.

11. Surface Ownership:

Access Road: Bureau of Land Management
Location: _____

CONFIDENTIAL

"If the access road and/or location involves private or state agency owned surface, a copy of the surface owners agreement is required prior to approval of the APD."

12. Other Additional Information

- a. The Operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to :

-whether the materials appear eligible for the National Register of Historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible to mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- b. The operator will control noxious weeds along right-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- c. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

On BIA administered land:

CONFIDENTIAL

Operator's employees, including subcontractors, will not gather firewood along roads constructed by operators. If wood cutting is required, a permit will be obtained from the Forestry Department of the BIA pursuant to 25 CFR 169.13 "Assessed Damages Incident to Right-of-Way Authorization". All operators, subcontractors, vendors and their employees or agents may not disturb salable timber (including firewood) without a duly granted wood permit from the BIA Forester.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved rights-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

All roads constructed by operators on the Uinta and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) that the land is owned by the Ute Indian Tribe, (b) the name of the operator, (c) that firearms are prohibited to all non-Ute Tribal members, (d) that permits must be obtained from the BIA before cutting firewood or other timber products and (e) only authorized personnel permitted.

All well site locations on the Uinta and Duray Indian Reservation will have an appropriate sign indicating the name of the operator, the lease serial number, the well name and number, the survey description of the well (either footages or the quarter-quarter section, the section, township, and range).

Additional Surface Stipulations

No construction or drilling activities shall be conducted between _____ and _____ because of _____

No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.

No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.

There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).

No cottonwood trees will be removed or damaged.

A silt catchment dam and basin will be constructed according to BLM specifications approximately 200 ft. north of the location, where flagged.

13. Lessee's or Operators Representative and Certification

Representative

Name: _____

Address: _____

Phone No: _____

CONFIDENTIAL

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and, that the work associated with the operations proposed here will be performed by CNG Producing Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

September 4, 1991
Date



Doss R. Bourgeois
Supervisor, Drilg. Eng.
Name and Title

Onsite Date: August 29, 1991

CONFIDENTIAL

Participants on Joint Inspection

Greg Darlington
Darwin Kulland

National Res. Prot. Spec.
Manager Production



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF WATER RIGHTS

Norman H. Bangerter
Governor
Dee C. Hansen
Executive Director
Robert L. Morgan
State Engineer

Eastern Area
State/County Building
152 East 100 North
Verna, Utah 84078-2110
801-781-0770 x 327

RECEIVED
MAY 2 1991
CNG PRODUCING CO.
Roosevelt, Utah

April 30, 1991

CNG Producing Company
P.O. Box 1360
Roosevelt, UT 84066

Dear Applicant:

RE: Application No. 47-1761 (A61599)
PROOF-DUE DATE: June 30, 1991


To appropriate water in Utah, or to change the point of diversion, place and nature of use of water, you must make application, receive approval, complete the intended development work and submit proof that the water has been put to beneficial use. Upon submission of satisfactory proof, a certificate will be issued, which is your evidence of a water right. Our records indicate that you have not made proof of appropriation or change on your application. This is due June 30, 1991.

Proof must be prepared by a registered engineer or land surveyor and must be filed in this office on or before the above proof-due date. Failure to make proof by this due date will allow the application to LAPSE. Blank forms for submitting proof will be sent upon request.

If proof cannot be submitted at this time, an extension of time may be requested by completing the enclosed form and submitting the request in affidavit form on or before the proof-due date. Submission of a request for an extension of time does not assure that it will be granted. An extension will generally be granted only after an applicant has made a showing of diligence to the State Engineer. Requests should not be made for unreasonable periods of time beyond that needed to complete the appropriation and proof.

Your contact with this office, should you need it, is with the Area Engineer, Robert Leake. The telephone number is (801)781-0770.

Yours truly,


Robert L. Morgan, P.E.
State Engineer

Enclosure: Form 29
Certified Mail

P R O O F D U E

PROOF OF APPROPRIATION OF WATER STATE OF UTAH

For the purpose of proving that diverting works are completed and that water is being applied to a beneficial use, proof of appropriation of water is hereby submitted to the State Engineer in accordance with Section 73-3-16 of the Utah Code Annotated 1953, as amended.

WATER RIGHT NO. 47 - 1761

APPLICATION NO. A 61599

1. OWNER INFORMATION

Name: CNG Producing Company Interest: _____ %
Address: P.O. Box 1360
City: Roosevelt State: Utah Zipcode: 84066

2. QUANTITY OF WATER: _____ cfs and/or 36.5 ac-ft

3. SOURCE: Green River * **DRAINAGE:** _____
which is tributary to Colorado River

which is tributary to _____
POINT(S) OF DIVERSION: _____ **COUNTY:** Uintah
South 2016 feet and East 1590 feet from the West Quarter Corner of Section 19,
T10S, R18E, Salt Lake Base and Meridian.

Description of Diverting Works and Carrying Works: Pumped into water hauling trucks.

4. POINT(S) OF REDIVERSION
The water is rediverted from _____ at a point: _____

Description of Diverting Works and Carrying Works: _____

5. POINT(S) OF RETURN
The amount of water consumed is _____ cfs or _____ ac-ft
The amount of water returned is _____ cfs or _____ ac-ft
The water is returned to the natural stream/source at a point(s): _____

6. STORAGE
Reservoir Name: _____ Storage Period: from _____ to _____
Capacity: _____ ac-ft. Inundated Area: _____ acres
Height of dam: _____ feet
Legal description of inundated area by 40 acre tract(s): _____

7. List any other water rights which are supplemental to this application: _____

* These items are to be completed by the Division of Water Rights

8. NATURE AND PERIOD OF USE

Irrigation: From _____ to _____
Stockwatering: From _____ to _____
Domestic: From _____ to _____
Municipal: From _____ to _____
Mining: From _____ to _____
Power: From _____ to _____
Other: Drilling and service of oil and gas wells From September 1 to September 1

9. PURPOSE AND EXTENT OF USE

Irrigation: _____ acres. Sole supply of _____ acres.
Stockwatering (number and kind): _____
Domestic: _____ Families and/or _____ Persons
Municipal (name): _____
Mining: _____ Mining District in the _____ Mine
Ores mined: _____
Power: Plant name: _____ Type: _____ Capacity: _____
Other (describe): Oil exploration, Drilling and servicing of oil and gas wells.

10. PLACE OF USE

Legal description of place of use by 40 acre tract(s): All parts of Sections 9, 10, 11, 12, 15, 16, and 19 of Township 10 South, Range 18 East of the Salt Lake Base and Meridian.

11. DEVELOPMENT HISTORY

Construction of works commenced: No construction needed. Used existing _____, 19 _____
and were completed: river access _____, 19 _____
Works were first used to convey water: September _____, 19 87
Water measured by (name): _____
Date: _____, 19 _____
Method of measurement: Quantity determined by capacity of tank on water truck.
(Give sufficient data in "EXPLANATORY" to enable the State Engineer to check the water measurement.)

12. EXPLANATORY (Use additional pages of same size if necessary)

(Fill in blank spaces but do not sign until proof has been submitted to the State Engineer and accepted as sufficient.)

CERTIFICATE OF APPLICANT

STATE OF UTAH) ss
COUNTY OF _____)

_____ being first duly sworn, certify that I am the person, assignee or agent of the person who filed in the State Engineer's office Application No. A _____; that I, as appropriator, employed _____ to compile information for the purpose of completion of proof of appropriation and that I hereby accept and submit this written proof together with tracings consisting of sheet Nos. _____ to _____ incl.; that said facts and tracings are hereby submitted, and that each and all items contained herein are true to the best of my knowledge and belief.

Applicant or His Agent

Subscribed and sworn to before me this _____ day of _____, 19 _____
My commission expires _____, 19 _____

Notary Public

Found marked stone at
W 1/4 Cor. Sec. 19, T10S, R1E
S.L.B. & M.

This point of diversion is located
South 2016 feet and East 1590 feet
from the W 1/4 Cor. in the SE 1/4 of
the SW 1/4 of Section 19, T10S, R1E,
S.L.B. & M.



1" = 800'


N 0° 00' 00" E 2575.32' (R) (Basis)

2016'

East 1590'


Access road
for water
trucks

Green River



Sec 24 Sec 19
Sec 25 Sec 30

R1E
R1E



Sec. 19, T10S, R1E, S.L.B. & M.
1" = 2000'

PROOF OF APPROPRIATION
CNG PRODUCING COMPANY
APPLICATION NO. 47-1761(A61599)

Sheet 1 of 1

21 June '91

79-128-179

	JERRY D. ALLRED & ASSOCIATES Surveying & Engineering Consultants
	121 North Center Street P.O. Drawer C DUCHESNE, UTAH 84021 (801) 738-5352



STATE OF UTAH
NATURAL RESOURCES
Water Rights

Norman H. Bangert, Governor
Dee C. Hansen, Executive Director
Robert L. Morgan, State Engineer

1636 West North Temple • Suite 220 • Salt Lake City, UT 84116-3156 • 801-533-6071

September 4, 1987

CNG Producing Company
P.O. Box 1360
Roosevelt, UT 84066

Dear Applicant:

RE: APPROVED APPLICATION
NUMBER 47-1761 (A61599)

Enclosed is a copy of approved Application No. 47-1761 (A61599). This is your authority to proceed with the actual construction work which under Section 73-3-10 and 73-3-12, Utah Code Annotated, 1953, as amended, must be diligently prosecuted to completion. The water must be put to beneficial use and proof of appropriation be made to the State Engineer on or before June 30, 1991, otherwise, the application will be lapsed.

Proof of Appropriation is evidence to the State Engineer that the water has been placed to its full intended beneficial use. By law, it must be prepared by a registered engineer or land surveyor, who will certify to the location and the uses for the water. Your proof of appropriation will become the basis for the extent of your water right.

Failure on your part to comply with the requirements of the statutes may result in forfeiture of this application.

Your contact with this office, should you need it, is with the Area Engineer, Mark Page. The telephone number is (801)637-1303.

Sincerely,


Robert L. Morgan, P.E.
State Engineer

RLM:rc

Encl.: Copy of Approved Application
Memorandum Decision

FIXED TIME

FILING FOR WATER IN THE STATE OF UTAH

APPLICATION TO APPROPRIATE WATER

Rec. by SA
Fec Paid \$ 30.00 2000
Platted _____
Microfilmed _____
Roll # _____

For the purpose of acquiring the right to use a portion of the unappropriated water of the State of Utah, application is hereby made to the State Engineer based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.

WATER USER CLAIM NO. 47 - 1761

APPLICATION NO. A61599

1. PRIORITY OF RIGHT: February 28, 1986

FILING DATE: February 28, 1986

2. OWNER INFORMATION

Name: CNG Producing Company
Address: P.O. Box 1360, Roosevelt, UT 84066
The land is not owned by the applicant(s), see explanatory.

3. QUANTITY OF WATER: 36.5 acre feet (Ac. Ft.)

4. SOURCE: Green River DRAINAGE: Nine Mile Creek
POINT(S) OF DIVERSION:

COUNTY: Utah

(1) S. 1700 feet, W. 1200 feet, from the NE Corner of Section 19,
Township 10 S, Range 19 E, SLB&M

Description of Diverting Works: Pump and tank trucks

COMMON DESCRIPTION: 11 mi. SW of Ouray, Utah

5. NATURE AND PERIOD OF USE

Oil Exploration From September 1 to September 1.

6. PURPOSE AND EXTENT OF USE

Oil Exploration: Drilling and servicing of oil and/or gas wells.

7. PLACE OF USE

The water is used in all or parts of each of the following legal subdivisions.

TOWN	RANGE	SEC	North East Quarter				North West Quarter				South West Quarter				South East Quarter			
			NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$
10 S	18 E	09	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	10	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	11	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	12	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	15	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	16	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	19	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X

All locations in Salt Lake Base and Meridian

MICROFILMED

EXPLANATORY

The land this water is used on is BLM land which is leased by CNG Producing Company.

The water is to be used for drilling and servicing of oil and/or gas wells. This application is being filed for a fixed time period of five years.

FIXED TIME

Appropriate

STATE ENGINEER'S ENDORSEMENT

WATER RIGHT NUMBER: 47 - 1761

APPLICATION NO. A61599


1. February 28, 1986 Application received by LN.
2. February 28, 1986 Priority of Application.
3. March 12, 1986 Application reviewed and approved for advertising by MP.
March 26, 1986 Publication began in Vernal Express.
May 13, 1986 Publication completed and verified by DL.
4. May 9, 1986 End of protest period.
Application protested: NO
5. September 1, 1987 Application designated for APPROVAL by MP and SG.
6. Comments:

This is a Fixed Time application.

Conditions:

This application is hereby APPROVED by Memorandum Decision, dated September 4, 1987, subject to prior rights and the following conditions:

- a. Actual construction work shall be diligently prosecuted to completion.
- b. Proof of Appropriation shall be submitted to the State Engineer's Office by June 30, 1991.


Robert L. Morgan, P.E.
State Engineer

Time for making Proof of Appropriation extended to _____

Proof submitted _____

BEFORE THE STATE ENGINEER IN THE STATE OF UTAH

IN THE MATTER OF APPLICATION TO

APPROPRIATE WATER 47-1761 (A61599)

)
) MEMORANDUM DECISION
)

Application 47-1761 (A61599) was filed on February 28, 1986 by CNG Producing Company to appropriate 0.05 cfs and/or 36.5 acre feet of water from the Green River at a point South 1700 feet and West 1200 feet from the NE Corner of Section 19, T10S, R19E, SLB&M. The water would be pumped from the Green River and hauled by tank truck and used on an annual basis for the drilling and servicing of oil and gas wells in Sections 9-12, 15, 16, 19, T10S, R19E, SLB&M. The application was advertised in the Vernal Express beginning March 26 and ending April 9, 1986. There were no protests filed against the granting of this application.

It is the opinion of the State Engineer that there is unappropriated water that could be drawn from the Green River and used as proposed in this application. However, this right cannot be granted in perpetuity because final development of pending water rights will utilize Utah's allocation of the Colorado River, of which this application would be a part. This matter has been discussed with the applicant and he is willing to accept approval of this application for a fixed time of five years.

It is therefore, ORDERED, and Application 47-1761 (A61599) is hereby APPROVED subject to all prior rights. This application is also approved subject to Section 73-3-8 of the Utah Code Annotated 1953, as revised, for a fixed time of five years at which time, this application will permanently lapse.

The applicant has the requirement of showing diligence in developing this right and for preparing and submitting Proof of Appropriation for the use of the water as required under Section 73-3-12 and 73-3-16, Utah Code Annotated.

This decision is subject to the provisions of Section 73-3-14, Utah Code Annotated, 1953, which provides for plenary review by the filing of a civil action in the appropriate district court within sixty days from the date hereof.


Dated this 4th day of September, 1987.



Robert L. Morgan, P.E., State Engineer

RLM:MP:rc

Mailed a copy of the foregoing Memorandum Decision this 4th day of September, 1987 to:

CNG Producing Company
P.O. Box 1360
Roosevelt, UT 84066

By: 
Robin Campbell Secretary



CONFIDENTIAL COPY

CONFIDENTIAL

NGC Producing Company
 P.O. Box 1360
 1400 North State Street
 Roosevelt, Utah 84068

SELF-CERTIFICATION STATEMENT


Self-certification statement. Under the Federal regulation in effect as of June 15, 1988 designation of operator forms are no longer required when the operator is not the 100% record title holder. An operator is now required to submit a self-certification statement to the appropriate Bureau office stating that said operator has the right to operate upon the leasehold premises. Said notification may be in the following format:

*Please be advised that CNG Producing Company is considered to be the operator of Well No. 13-35B SW 1/4 of SW 1/4 Section 35, Township 9, Range 19; Lease U-017713 Uintah County, Utah; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by American Casualty Company of Reading, PA, Bond #524 7050.




R. S. Gloger
Drilling Manager

BOP STACK



CHOKE MANIFOLD





State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Norman H. Bangertter
Governor
Dee C. Hansen
Executive Director
Dianne R. Nielson, Ph.D.
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

September 12, 1991

CNG Producing Company
CNG Tower-1450 Poydras Street
New Orleans, LA 70112-6000

Gentlemen:

Re: RBU 13-35B Well, 814 feet from the South line, 815 feet from the West line,
SW SW, Section 35, Township 9 South, Range 19 East, Uintah County, Utah

Approval to drill the referenced well is hereby granted in accordance with Utah Admin. R.615-3-2.

In addition, the following actions are necessary to fully comply with this approval:

1. Spudding notification within 24 hours after drilling operations commence.
2. Submittal of Entity Action Form 6, within five working days following spudding and whenever a change in operations or interests necessitates an entity status change.
3. Submittal of the Report of Water Encountered During Drilling, Form 7.
4. Prompt notification in the event it is necessary to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801) 538-5340, (Home) (801) 476-8613, or R. J. Firth, Associate Director, (Home) (801) 571-6068.
5. Compliance with the requirements of Utah Admin. R.615-3-20, Gas Flaring or Venting.

Page 2
CNG Producing Company
RBU 13-35B
September 12, 1991

6. Prior to commencement of the proposed drilling operations, plans for facilities for disposal of sanitary wastes at the drill site shall be submitted to the local health department. These drilling operations and any subsequent well operations must be conducted in accordance with applicable state and local health department regulations. A list of local health departments and copies of applicable regulations are available from the Department of Environmental Quality, Division of Drinking Water/Sanitation, telephone (801) 538-6159.
7. This approval shall expire one (1) year after date of issuance unless substantial and continuous operation is underway or an application for an extension is made prior to the approval expiration date.

The API number assigned to this well is 43-047-32094.

Sincerely,



R. J. Firth
Associate Director, Oil & Gas

tas
Enclosures
cc: Bureau of Land Management
J. L. Thompson
we14/1-4

Revised November 1990

Date NOS Received: 08/28/91
Date APD Received: 09/05/91

CONDITIONS OF APPROVAL
FOR APPLICATION FOR PERMIT TO DRILL

Company/Operator: CNG Producing Company
Well Name & Number: 13-35B RBU
Lease Number: U-017713
Location: SW SW Sec. 35 T. 9S R. 19E
Surface Ownership: Public lands administered by BLM

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

The special drilling requirements in Onshore Order No. 2 regarding air or gas drilling shall be adhered to if air is used as the principle drilling medium, i.e. if the rig mud pumps are not being utilized while drilling.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

The Vernal District Office shall be notified at least twenty-four (24) hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the usable water zone, identified at 440 ft.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the Authorized Officer. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the Authorized Officer (AO).

A cement bond log (CBL) shall be utilized to determine the top of cement (TOC) and bond quality for the production casing.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the A0, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells, as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated, or the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the A0 will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of thirty (30) days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the A0. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram, as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4, shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations, as specified in Onshore Oil and Gas Order No. 3, shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the A0. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be

obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his/her representative or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or

allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka (801) 781-1190
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

BLM FAX Machine (801) 789-3634

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous:

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids.

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt wastes.

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation, and miscellaneous solids

B. THIRTEEN POINT SURFACE USE PROGRAM:

1. Planned Access Roads--describe the following and provide a map of suitable scale indicating all necessary access roads (permanent and temporary) to be constructed or reconstructed, showing:

Length - 2600 feet of new road construction is involved.

2. Methods for Handling Waste Disposal

The reserve pit shall be lined to conserve water and drilling fluids.

"If a plastic nylon reinforced liner is used, it will be a minimum of 10 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O."

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the A0's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

3. Additional Surface Stipulations

A silt catchment dam and basin will be constructed according to BLM specifications approximately 200 ft. east of the location, where flagged.

DIVISION OF OIL, GAS AND MINING

WATER PERMIT OK

API NO. 43-047-32094

SPODDING INFORMATION

NAME OF COMPANY: CNG PRODUCING COMPANY

WELL NAME: RBU 13-35B

SECTION SWSW 35 TOWNSHIP 9S RANGE 19E COUNTY UINTAH

DRILLING CONTRACTOR _____

RIG # _____

SPODDED: DATE 11-6-91

TIME 11:00 a.m.

HOW DRY

CONFIDENTIAL

DRILLING WILL COMMENCE _____

REPORTED BY DANNY

TELEPHONE # 722-4469

DATE 11-13-91 SIGNED TAS/CAK

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Disgration River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E 95.	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Spud Notice	<input type="checkbox"/> Dispose Water
		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

This is to notify you that the RBU 13-35B was spudded by Leon Ross Drilling on 11-6-91 at 11:00 AM.

They drilled 405' of 12 1/4" hole and ran 8 5/8" 24# 14-40 casing with guide shoe.

Cemented by Dowell with 224 sks Class "G" cement, 15.4#/gal with @% S-1, 1/4#/sk D-24 Celloflake.

RECEIVED

DEC 09 1991

14. I hereby certify that the forgoing is true and correct

Signed Doss R. Bourgeois Title Supervisor, Drilling Eng. Date December 4, 1991

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

DIVISION OF
OIL GAS & MINING

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

ENTITY ACTION FORM - FORM 6

ADDRESS CNG Tower

1450 Poydras Street

New Orleans, LA 70112-6000

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	07050	43-047-32094	RBU 13-35B	SW SW	35	9S	19E	Uintah	11/06/91	
WELL 1 COMMENTS: This well is located within River Bend Unit on BLM land. <i>(Entity added 12-11-91) fr</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instruction on back of form)

- A - establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

RECEIVED

DEC 09 1991

Susan M. Hubert

Signature

Regulatory Reports Asst. II

Title

December 4, 1991

Date

NOTE: Use COMMENT section to explain why each Action Code was selected.

DIVISION OF
OIL GAS & MINING

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED BUDGET BUREAU NO. 1004-0135 EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

5. Lease Designation and Serial No. U-017713

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE

1. Type of Well [] Oil Well [X] Gas Well [] Other

2. Name of Operator CNG PRODUCING COMPANY

3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-105-R19E

7. If Unit or CA, Agreement Designation River Bend Unit

8. Well Name and No. 13-35B

9. API Well No. 43-047-32094

10. Field and Pool, or Exploratory Area Island

11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

[] Notice of Intent

[X] Subsequent Report

[] Final Abandonment Notice

[] Abandonment

[] Recompletion

[] Plugging Back

[] Casing Repair

[] Altering Casing

[X] Other - Weekly Report

[] Change of Plans

[] New Construction

[] Non-Routine Fracturing

[] Water Shut-Off

[] Conversion to Injection

[] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

February 7, 1992

Rig up and nipple up to pressure test. Test BOP, etc. OK. Rig up. Pick up bit and drill collar. Drill cement, insert baffle, shoe joint, and guide shoe. Drilling new formation with aerated fluid.

14. I hereby certify that the foregoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date February 7, 1992

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

5. Lease Designation and Serial No.
U-017713
6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E 9	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

February 8 - February 14, 1992

Drilling. Thaw reserve pit and fluid transfer pump. Drilling. Wait on water. Drilling. Survey at 837'. Drilling. Rig services. Drilling. Survey at 1,306'. Drilling. Survey at 1,306'. Drilling. Survey at 2,214'. Drilling. Drilling. Rig service. Drilling. Survey at 2,729'. Drilling. Survey at 3,228'. Drilling. Rig service. Drilling. Survey at 3,720'. Drilling. Survey at 4,228' and service rig. Drilling. Survey at 4,711'. Drilling. Survey at 5,205'. Service rig. Drilling. Drop survey and trip for new bit. Drilling. Service rig. Drilling. Rig repair to #1 pump. Drilling from 5,972-6,018'. Survey at 5,978'. Drilling from 6,018-6,144'. Rig service. Drilling from 6,144-6,488'. TD at 6,488'. Mud wt. 8.5.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date February 14, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED BUDGET BUREAU NO. 1004-0135 EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

[] Oil Well [X] Gas Well [] Other

2. Name of Operator

CNG PRODUCING COMPANY

3. Address and Telephone No.

CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-5000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E

5. Lease Designation and Serial No. U-017713

6. If Indian, Allottee or Tribe Name

7. If Unit or GA, Agreement Designation River Bend Unit

8. Well Name and No. 13-35B

9. API Well No. 43-047-32094

10. Field and Pool, or Exploratory Area Island

11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

[] Notice of Intent

[] Abandonment

[] Change of Plans

[X] Subsequent Report

[] Recompletion

[] New Construction

[] Final Abandonment Notice

[] Plugging Back

[] Non-Routine Fracturing

[] Casing Repair

[] Water Shut-Off

[] Altering Casing

[] Conversion to Injection

[X] Other - Weekly Report

[] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work)*

February 15 - February 21, 1992

Drilling. Survey at 6,503'. Drilling. Service rig. Drilling. Survey at 6,969'. Service rig. Drilling. Rig repair to rotating head. Drilling. Survey at 7,466'. Service rig. Drilling to 7,638'. Trip for new bit. Drilling. Service rig. Drilling. Survey at 7,974'. Drilling. Service rig. Drilling TD 7 7/8" hole. Circulate and condition hole. 20 stand short trip. Circulate and condition hole. Trip out. Move in and rig up logger. Loggers TD at 8,200'. Log with Halliburton Logging Service. Trip in hole to 8,100'. Lay down drill pipe. Run 158 jts 5 1/2" 17# N-80 casing to 6,899.44'. Circulate. Cement with 410 sks Hillift followed by 875 sks RFC-10.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date February 21, 1992

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	MAR 09 1992	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	DIVISION OF	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	OIL GAS & MINING	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E	95	10. Field and Pool, or Exploratory Area Island
		11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water
		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

March 5 - March 6, 1992

Rig up Schlumberger. Run GR/CCL from TD to 4,500'. Rig up Schlumberger. Run in hole with 4" casing gun loaded with 1 SPF. Perforate 6,682', 6,675', 6,646', 6,596', 6,592', 6,586', 6,418', 6,412'. Pull out of hole. Run in hole with casing gun, set down at 4,700'. Couldn't get through. Pull out of hole. Lay down 1' section of gun that was swelled to 4 1/4". Run in hole. Couldn't get below 3,400'. Acted like something was floating in hole. Pull out of hole. Rig down wireline truck. Run in hole with retrieving head. Pick up and run in hole with tubing to 6,755'. Circulate hole. Pull out of hole with 20 stands.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date March 6, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-5000	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E 95	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water
		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measure and true vertical depths for all markers and zones pertinent to the work.)*

March 7 - March 13, 1992

Pull out of hole with 208 jts of tubing and retrieving head. Rig up Schlumberger. Run in hole with 4" casing gun loaded with 1 SPF. Couldn't get below 3,800'. Pull out of hole, change out section of gun. Run in hole. Perforate 6,408', 6,389', 6,386', 5,927', 5,924', 5,918', 5,913'. Pull out of hole, rig down wireline truck. Run in hole with 1 jt seating nipple and 207 jts, set at 6,690'. Rig up Western. Spot 1,000 gallons 15% HCL acid. Pull out of hole, lay down, 28 jts casing at 5,795'. Landed tubing with blast jt under hanger. Nipple down BOP, nipple up tree. Breakdown Zones with 30 bbls of 15% HCL acid. Dropping 1 ball per bbls, 7 balls at start of flush. Pumping at 7 BPM at 4500 PSI. Last 9 bbls of flush had good ball action. Pumping 3.6 BPM at 5000 PSI. Open tubing to pit on 18/64 choke, bled pressure down. Well died. Made 3 runs, 25 bbls well started flowing. Left well flowing overnight, well had 500 PSI on tubing and 600 PSI on casing with a rate of 1,035 MCF/D. Western rigged up testing lines to 7200 PSI. Frac'd well using 117 tons CO2 & 292,500 lbs of 20/40 frac sand. Lost a set of perfs and the pressure went to screen out. Went to flush, cut CO2 & dropped rate to 82 BPM. Able to flush to top perf. Open well up on 18/64 choke. Flow tubing pressure 1100 PSI, returning very heavy mist. Tubing had 700 PSI and casing had 350 PSI, returning mist at a rate of 1,450 MCF/D, gas will not burn.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date March 13, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E 95	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measure and true vertical depths for all markers and zones pertinent to the work.)*

March 14 - March 20, 1992

Rig up wireline truck to tubing. Run in hole, tagged fluid. Found end of tubing at 5,785'. Run in hole to TD at 6,676'. Pull out of hole with wireline. Rig down with 1300 PSI on tubing and 1500 PSI on casing. Tubing had 900 PSI returning 1,864 MCF/D, would burn. Well made sufficient amount of oil that pit caught on fire. Burned for 3 hrs. Flowing tubing to pit on 18/64 choke. Tubing had 900 PSI and casing had 1300 PSI. Returning gas and yellow oil, would burn at the rate of 1,864 MCF/D.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date March 20, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED

BUDGET BUREAU NO. 1004-0135

EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a
different reservoir. Use "APPLICATION FOR PERMIT" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

 Notice of Intent Abandonment Change of Plans Recompletion New Construction Subsequent Report Plugging Back Non-Routine Fracturing Casing Repair Water Shut-Off Final Abandonment Notice Altering Casing Conversion to injection Other - Weekly Report Dispose Water(Note: Report results of multiple
completion on Well Completion or
Recompletion Report and Log form.)13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including
estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measure
and true vertical depths for all markers and zones pertinent to the work.)*March 21 - March 27, 1992Rig up Halliburton Logging Services logging truck to run tracer scan log. Pick up and run in hole with logging tool
and CCL to 6,700'. Run tracer scan log. Pull out of hole and lay down CCL & logging tool. Rig down Halliburton
Logging Services logging truck. All zones treated.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. II Date March 27, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any: _____Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or
agency of the United States any false, fictitious or fraudulent statements or representations as to any matter
within its jurisdiction.

*See Instructions on Reverse Side

April 22, 1992

RECEIVED

APR 27 1992

DIVISION OF
OIL GAS & MINING

Mr. David Little
District Manager
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: Application for Disposal of Produced Water
NTL-2B

Dear Mr. Little:

Pursuant to NTL-2B Revised August 1, 1978, CNG Producing Company hereby makes applications under Section 1, Exception No. 4. This request is for a 40 x 40 x 6' pit adjacent to gas separator in which production water is collected. The wells make less than five (5) bbls per day. The evaporation rate for the area is four (4) feet per year and the percolation rate of the soil is approximately 1" per day.

Some of the pits are unlined, (except with native clay), when they are not located next to drainage. These pits have also been tested for water loss. The pits that showed water loss are lined with native clay and a .12 mil liner.

The accompanying map shows the location of the pits, however, exact location of the pits have been submitted with the site security diagram. All wells are located within the River Bend Unit, Uintah County, Utah.

	<u>Well Name</u>	<u>Lease Number</u>	<u>Well Location</u>	<u>Section, Township & Range</u>
1.	RBU 8-2F	ML-10716	SE NE	2-T10S-R20E
2.	RBU 9-9E	U-03505	NE SE	9-T10S-R19E
3.	RBU 5-13E	U-013765	SW NW	13-T10S-R19E
4.	RBU 13-13E	U-01376	SW SW	13-T10S-R19E
5.	RBU 15-13E	U-013765	SW SE	13-T10S-R19E
6.	RBU 7-15E	U-013766	SW NE	15-T10S-R19E
7.	RBU 1-16E	ML-13214	NE NE	16-T10S-R19E
9.	RBU 3-17FX	U-013769-C	NE NW	17-T10S-R20E
9.	RBU 8-18F	U-013769	SE NE	18-T10S-R20E
10.	RBU 13-23E	U-013766	SW SW	23-T10S-R19E
11.	RBU 5-24E	U-013794	SW NW	24-T10S-R19E
12.	RBU 13-35B	U-017713	SW SW	35-T9S-R19E

Mr. David Little, District Manager
Bureau of Land Management

Page 2
April 22, 1992

If you have any questions or need any further information, please feel free to contact either myself at (504) 593-7260 or our project engineer, Scot Childress, at (504) 593-7574. Thank you for your cooperation.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

Enclosure

cc: Utah Board of Oil, Gas & Mining
Yvonne Abadie
Scot Childress
Brian Coffin
Darwin Kulland
Jim Nicas
RBU Well files

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED

BUDGET BUREAU NO. 1004-0135

EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35E
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T19S-R19E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION


 Notice of Intent Abandonment Change of Plans Subsequent Report Recompletion New Construction Final Abandonment Notice Plugging Back Non-Routine Fracturing Casing Repair Water Shut-Off Altering Casing Conversion to Injection Other - Notice of Initial
Production Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Well was placed on initial production on May 8, 1992 at 12:00 PM.

Note: Verbal notification of initial production telephoned into BLM by Sue Hebert, CNG. Information given to Sally Gardner, BLM on May 11, 1992, 9:26 AM.



MAY 13 1992

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Senior Drilling Engineer Date May 11, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

CNG Producing
Company

May 19, 1992

Mr. Ed Forsman
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RECEIVED

MAY 22 1992

DIVISION OF
OIL GAS & MINING

RE: River Bend Unit
Well Completion Report
River Bend Unit 13-15E
Section 15-T10S-R19E
River Bend Unit 13-35B
Section 35-T9S-R19E

Dear Ed:

Enclosed please find the original and two copies of the above referenced reports.

CNG Producing Company is requesting all information be held confidential.

Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, Scot Childress at (504) 593-7574.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

Enclosure

cc: Ms. Tammy Searing - Utah Department of Oil, Gas & Mining
Y. Abadie
B. Coffin
V. Corpening
C. Guiteau
D. Kulland
D. Linger
D. Montelaro
R. Mueller
J. Nicas

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

SUBMIT IN DUPLICATE*
(See other in-

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

CONFIDENTIAL
Instructions on reverse side

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL: OIL WELL GAS WELL DRY **RECEIVED**

1b. TYPE OF COMPLETION: NEW WORK WELL OVER DEEP-EN PLUG BACK DIFF. RESVR. Other **MAY 22 1992**

2. NAME OF OPERATOR: **CNG Producing Company**

3. ADDRESS OF OPERATOR: **CNG Tower - 1450 Poydras St., New Orleans, LA 70112-6000**

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements):
At surface **815' FWL & 814' FSL of Sec. 35-T9S-R19E**
At top prod. interval reported below
At total depth

5. LEASE DESIGNATION AND SERIAL NO.: **U-017713**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME: **River Bend Unit**

8. FARM OR LEASE NAME: **RBU**

9. WELL NO.: **13-35B**

10. FIELD AND POOL, OR WILDCAT: **Island**

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA: **SW of SW of 35-T9S-R19E**

12. COUNTY OR PARISH: **Uintah**

13. STATE: **Utah**

14. PERMIT NO.: **43-047-32094**

DATE ISSUED: **09/12/91**

15. DATE SPUDDED: **11/06/91**

16. DATE T.D. REACHED: **02/19/92**

17. DATE COMP (Ready to prod.): **3-13-92 per Scot Childress**

18. ELEVATION (OF RKB, RT, GR, ETC.): **4,923' GR**

19. ELEV. CASINGHEAD

20. TOTAL DEPTH MD & TVD: **8,200'**

21. PLUG, BACK T.D. MD & TVD: **6,798'**

22. IF MULTIPLE COMPL., HOW MANY*: **1 Zone**

23. INTERVALS DRILLED BY: **Rotary**

24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)*: **5,913-27', 6,386-6,418', 6,586-6,596', 6,646', 6,675-82'**

25. WAS DIRECTIONAL SURVEY MADE: **No**

26. TYPE ELECTRIC AND OTHER LOGS RUN: **DLL, GR, Cal, Den/Neu MUD LOG 3-18-92**

27. WAS WELL CORED: **No**

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB/FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8 5/8"	24#	405'	12 1/4"	224 sks Class "G" cement with 2% S-1,	1/4#/sk D-24 Celloflot
5 1/2"	17# N-80	6,899.44'	5-1/2"	410 sks Hi-Lift cement, followed by 875 sks RFC-10	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	30. TUBING RECORD SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"		

31. PERFORATION RECORD (Interval, size and number): **Zone #1 - 5,913-27', 6,386-6,418', 6,586-6,596', 6,646', 6,675-82'**

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
Zone #1	292,500 lbs of 20/40 Frac Sand

33. PRODUCTION

DATE FIRST PRODUCTION	PRODUCTION MET (Flowing, gas lift, pumping - size and type of pump)	WELL STATUS (Producing or shut-in)					
05/08/92	Flowing	Producing					
DATE OF TEST	HOURS TESTED	CHOKED SIZE	PROD'N FOR TEST PERIOD	OIL-BBL.	GAS-MCF.	WATER-BBL.	GAS-OIL RATIO
05/13/92	24	17/64	----->	-	350	-	-
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24 HR RATE	OIL-BBL.	GAS-MCF.	WATER-BBL.	OIL GRAVITY-API (CORR.)	
875	1450	----->	-	350	-	-	-

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.): **Sold**

35. LIST OF ATTACHMENTS

TEST WITNESSED BY: **Mitch Hall**

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.


SIGNED: W. Scot Childress TITLE: Supervisor, Prod. Eng. DATE: May 18, 1992

*(See Instruction and Spaces for Additional Data on Reverse Side)

CNG Producing
Company

August 3, 1992

Mr. Ed Forsman
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078



RE: Confidentiality on
River Bend Unit Wells

Dear Ed:

Please accept this letter as evidence that we would like to extend the confidential period for another year on the following River Bend Unit wells:

<u>Well Name</u>	<u>Qtr/Qtr</u>	<u>Section</u>	<u>API Number</u>
RBU 7-13E	SW NE	13-T10S-R19E	43-047-32051
RBU 11-15E	NE SW	15-T10S-R19E	43-047-32073
RBU 9-20F	NE SE	20-T10S-R20E	43-047-32081
RBU 12-20F	NW SW	20-T10S-R20E	43-047-32050
RBU 1-21E	NE NE	21-T10S-R19E	43-047-32107
RBU 3-21E	NE NW	21-T10S-R19E	43-047-32095
RBU 9-22E	NE SE	22-T10S-R19E	43-047-32071
RBU 15-23E	SW SE	23-T10S-R19E	43-047-32082
RBU 13-24E	SW SW	24-T10S-R19E	43-047-32083
RBU 15-34B	SW SE	34-T9S-R19E	43-047-32072
RBU 15-35B	SW SW	35-T9S-R19E	43-047-32094

If you have any questions or need any additional information, please feel free to contact me at (504) 593-7260. Thanks for your continued cooperation.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

cc: Ms. Tammy Searing - Utah Board of Oil, Gas & Mining
Yvonne Abadie
RBU Well Files

OPERATOR C.N.G. PRODUCING

OPERATOR ACCT. NO. N 0605

ENTITY ACTION FORM - FORM 6

ADDRESS _____

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
C	7050	7058	43-047-32094	RBU 13-35B	SWSW	35	9S	19E	UINTAH	11-6-91	3-13-92
WELL 1 COMMENTS: *THIS WELL IS NOT IN THE RIVER BEND UNIT "WSTC-MVRD P.A.", IS REPORTED ON A LEASE BASIS. OPERATOR REQUESTED THAT IT BE SET UP UNDER ENTITY 7058 "SAME AS RBU 11-34B".											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

L. ROMERO (DOG M)

Signature

ADMIN. ANALYST


7-15-92

Title

Date

Phone No. ()

CNG Producing
Company



April 22, 1992

Mr. David Little
District Manager
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

VERNAL DIST.
ENG. *CD 4-2-92*
GEOCL. _____
ES. *LD*
PET. _____
AN. _____

RE: Application for Disposal of Produced Water
NTL-2B

Dear Mr. Little:

Pursuant to NTL-2B Revised August 1, 1978, CNG Producing Company hereby makes applications under Section 1, Exception No. 4. This request is for a 40 x 40 x 6' pit adjacent to gas separator in which production water is collected. The wells make less than five (5) bbls per day. The evaporation rate for the area is four (4) feet per year and the percolation rate of the soil is approximately 1" per day.

Some of the pits are unlined, (except with native clay), when they are not located next to drainage. These pits have also been tested for water loss. The pits that showed water loss are lined with native clay and a .12 mil liner.

The accompanying map shows the location of the pits, however, exact location of the pits have been submitted with the site security diagram. All wells are located within the River Bend Unit, Uintah County, Utah.

<u>Well Name</u>	<u>Lease Number</u>	<u>Well Location</u>	<u>Section, Township & Range</u>
1. RBU 8-2F	ML-10716	SE NE	2-T10S-R20E
2. RBU 9-9E	U-03505	NE SE	9-T10S-R19E
3. RBU 5-13E	U-013765	SW NW	13-T10S-R19E
4. RBU 13-13E	U-01376	SW SW	13-T10S-R19E
5. RBU 15-13E	U-013765	SW SE	13-T10S-R19E
6. RBU 7-15E	U-013766	SW NE	15-T10S-R19E
7. RBU 1-16E	ML-13214	NE NE	16-T10S-R19E
8. RBU 3-17FX	U-013769-C	NE NW	17-T10S-R20E
9. RBU 8-18F	U-013769	SE NE	18-T10S-R20E
10. RBU 13-23E	U-013766	SW SW	23-T10S-R19E
11. RBU 5-24E	U-013794	SW NW	24-T10S-R19E
12. RBU 13-35B	U-017713	SW SW	35-T9S-R19E

Mr. David Little, District Manager
Bureau of Land Management

Page 2
April 22, 1992

If you have any questions or need any further information, please feel free to contact either myself at (504) 593-7260 or our project engineer, Scot Childress, at (504) 593-7574. Thank you for your cooperation.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

Enclosure

cc: Utah Board of Oil, Gas & Mining
Yvonne Abadie
Scot Childress
Brian Coffin
Darwin Kulland
Jim Nicas
RBU Well files



United States Department of the Interior



BUREAU OF LAND MANAGEMENT

Vernal District Office
170 South 500 East
Vernal, Utah 84078

IN REPLY REFER TO:

Phone (801) 789-1362

FAX (801) 789-3634

3162.32
UT085

JUL 31 1992

CNG Producing Company
Attn: Susan Hebert
Regulatory Reports Assistant
CNG Tower, 1450 Polydras Street
New Orleans, LA 70112-6000

Re: NTL-2B Applications for 12 wells
in River Bend Unit
Uintah County, Utah

Dear Ms. Hebert:

In your letter of April 22, 1992, you requested NTL-2B authorization for 12 wells. We have reviewed your request for permission to dispose of produced water at these locations as per the regulations under Section IV exception 4. The volume of water to be disposed of per facility does not exceed 5 barrels per day on a monthly basis.


Your request includes two wells located on State of Utah leases where the State of Utah has jurisdiction over regulating your production of produced water. The RBU 8-2F well involves Federal Surface. For it we simply stipulate that the pit size not exceed 40 feet by 40 feet by 6 feet and the APD fencing requirements be followed when you seek your required NTL-2B approval from the state of Utah for the two state wells:

OK
RBU 8-2F on lease ML-10716 SENE, Sec. 2, T10S, R20E
RBU 1-16E on lease ML-13214 NENE, Sec. 16, T10S, R19E

93-047-32136
93-047-31740

For the other 10 wells, your request is approved subject to guidelines and requirements provided for in Section V, NTL-2B, and subject to the stipulations:

1. No pit larger than 40 feet by 40 feet by 6 feet is authorized as a permanent disposal pit at any of these 10 wells unless it is justified by a subsequent request from CNG and substantial evidence to support that request.
2. The fencing requirements in the approved APD for each well site will be followed.



CNG should be aware that the following requirements were part of the APD approvals for the 10 wells:

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a. 39-inch net wire shall be used with at least one strand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

A recent inspection of these 10 well sites showed that one of them had a drain pit constructed as part of their recent installation of production equipment. You have requested only one pit at each well in your letter. A separate request is needed if additional drain pits are needed. Drain pits are presently at the 7-13E, 5-14E, 13-14E, 9-20F, 15-23E, and 13-24E wells. The drain pit at well 5-13E is filed for in your other letter of April 22, 1992.

A list of the 10 wells where one NTL-2B pit is authorized under this approval is as follows:

<u>No.</u>	<u>Well Name</u>	<u>Lease Number</u>	<u>Well Location</u>	<u>Section, Township, & Range</u>
1.	RBU 9-9E	U-03505	NESE	9-T10S-R19E 43-047-31739
2.	RBU 5-13E	U-013765	SWNW	13-T10S-R19E 43-047-31715
3.	RBU 13-13E	U-013765	SWSW	13-T10S-R19E 43-047-21717
4.	RBU 15-13E	U-013765	SWSE	13-T10S-R19E 43-047-32167
5.	RBU 7-15E	U-013766	SWNE	15-T10S-R19E 43-047-22166
6.	RBU 3-17FX	U-013769-C	NENW	17-T10S-R20E 43-047-32191
7.	RBU 8-18F	U-013769	SENE	18-T10S-R20E 43-047-32149
8.	RBU 13-23E	U-013766	SWSW	23-T10S-R19E 43-047-32153
9.	RBU 5-24E	U-013794	SWNW	24-T10S-R19E 43-047-32154
10.	RBU 13-35B	U-017713	SWSW	35-T 9S-R19E 43-047-32094



United States Department of the Interior



BUREAU OF LAND MANAGEMENT

Vernal District Office
170 South 500 East
Vernal, Utah 84078

IN REPLY REFER TO:

Phone (801) 789-1362

FAX (801) 789-3634

3162.32
UT085

JUL 31 1992

CNG Producing Company
Attn: Susan Hebert
Regulatory Reports Assistant
CNG Tower, 1450 Polydras Street
New Orleans, LA 70112-6000

Re: NTL-2B Applications for 12 wells
in River Bend Unit
Uintah County, Utah

Dear Ms. Hebert:

In your letter of April 22, 1992, you requested NTL-2B authorization for 12 wells. We have reviewed your request for permission to dispose of produced water at these locations as per the regulations under Section IV exception 4. The volume of water to be disposed of per facility does not exceed 5 barrels per day on a monthly basis.


Your request includes two wells located on State of Utah leases where the State of Utah has jurisdiction over regulating your production of produced water. The RBU 8-2F well involves Federal Surface. For it we simply stipulate that the pit size not exceed 40 feet by 40 feet by 6 feet and the APD fencing requirements be followed when you seek your required NTL-2B approval from the state of Utah for the two state wells:

OK
RBU 8-2F on lease ML-10716 SENE, Sec. 2, T10S, R20E
RBU 1-16E on lease ML-13214 NENE, Sec. 16, T10S, R19E

93-047-32136
93-047-31740

For the other 10 wells, your request is approved subject to guidelines and requirements provided for in Section V, NTL-2B, and subject to the stipulations:

1. No pit larger than 40 feet by 40 feet by 6 feet is authorized as a permanent disposal pit at any of these 10 wells unless it is justified by a subsequent request from CNG and substantial evidence to support that request.
2. The fencing requirements in the approved APD for each well site will be followed.



CNG should be aware that the following requirements were part of the APD approvals for the 10 wells:

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a. 39-inch net wire shall be used with at least one strand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

A recent inspection of these 10 well sites showed that one of them had a drain pit constructed as part of their recent installation of production equipment. You have requested only one pit at each well in your letter. A separate request is needed if additional drain pits are needed. Drain pits are presently at the 7-13E, 5-14E, 13-14E, 9-20F, 15-23E, and 13-24E wells. The drain pit at well 5-13E is filed for in your other letter of April 22, 1992.


A list of the 10 wells where one NTL-2B pit is authorized under this approval is as follows:

<u>No.</u>	<u>Well Name</u>	<u>Lease Number</u>	<u>Well Location</u>	<u>Section, Township, & Range</u>
1.	RBU 9-9E	U-03505	NESE	9-T10S-R19E 43-047-31739
2.	RBU 5-13E	U-013765	SWNW	13-T10S-R19E 43-047-31715
3.	RBU 13-13E	U-013765	SWSW	13-T10S-R19E 43-047-21717
4.	RBU 15-13E	U-013765	SWSE	13-T10S-R19E 43-047-32167
5.	RBU 7-15E	U-013766	SWNE	15-T10S-R19E 43-047-22166
6.	RBU 3-17FX	U-013769-C	NENW	17-T10S-R20E 43-047-32191
7.	RBU 8-18F	U-013769	SENE	18-T10S-R20E 43-047-32149
8.	RBU 13-23E	U-013766	SWSW	23-T10S-R19E 43-047-32153
9.	RBU 5-24E	U-013794	SWNW	24-T10S-R19E 43-047-32154
10.	RBU 13-35B	U-017713	SWSW	35-T 9S-R19E 43-047-32094

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

November 6, 1995

Mr. Wayne Bankert
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078



RE: Subsequent Report for
Plunger Lift Installations

Dear Wayne:

Prior to our conversation of last week it was not apparent that a Subsequent Sundry Notice must be filed for plunger lift installation on our wells. We have gone back through our files and would like to submit notice that plunger lift installations were completed on several RBU wells. Enclosed please find Sundry Notices for these wells.

We will be installing plunger lifts on several more RBU wells in the near future. As these operations are completed I will send in subsequent reports on those wells also.

Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, Scot Childress at (504) 593-7574.

Sincerely,

Susan H. Sachitana
Susan H. Sachitana
Coordinator, Regulatory Reports

Enclosure

cc: Frank Matthews - Utah Department of Oil, Gas & Mining
N. Decker
M. Hall
S. Childress
RBU Well Files

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-35B
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32094
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 815' FWL and 814' FSL of Sect 35-T10S-R19E 95	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah


CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Plunger Lift	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Installed plunger lift equipment on above well. Well on plunger.



14. I hereby certify that the forgoing is true and correct

Signed Scot Childress Title Supervisor, Production En Date November 2, 1995
Scot Childress


(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000



August 28, 1996

**Mr. Wayne Bankart
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078**

**RE: RBU 3-20F
RBU 7-21E
RBU 11-34B
RBU 13-35B**

Dear Wayne:

Enclosed please find an original and two copies of subsequent Sundries for tubing configuration work for the above referenced wells.

CNG Producing Company is requesting all information be held confidential.

If you have any questions or need any further information, please feel free to contact me at (504) 593-7260 or our project engineer, Ralph Hamrick, at (504) 593-7303. Thank you for your continued cooperation.

Sincerely,

Susan H. Sachitana
**Susan H. Sachitana
Coordinator, Regulatory Reports**

**cc: Utah Board of Oil, Gas & Mining
Brian Coffin
Nelda Decker
Ralph Hamrick**

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

R E C E I V E D

AUG 9 1996

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS DIV OF OIL, GAS & MINING

Do not use this form for proposals to drill or to deepen abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

<p>1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other</p> <p>2. Name of Operator CNG PRODUCING COMPANY</p> <p>3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-8000</p> <p>3b. Phone No. (include area code) (504) 593-7000</p> <p>4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 815' FWL & 814' FSL of Sec. 35-T^{9S}10S-R19E</p>	<p>5. Lease Serial No. 11027713</p> <p>6. Indian, Allottee or Tribe Name</p> <p>7. If Unit or CAI Agreement, Name and/or No. RIVER BEND UNIT</p> <p>8. Well Name and No. RBU 13-35B</p> <p>9. API Well No. 43-047-32094</p> <p>10. Field and Pool, or Exploratory Area ISLAND</p> <p>11. County or Parish, State UINTAH, UTAH</p>
---	---

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input checked="" type="checkbox"/> Fracturing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompletes horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

Tubing reconfiguration work performed on 7/31/96.

Remove plunger stop and spring from well with wireline - Delsco. Rig up rig and equipment. Bleed well down. Control well with 60 bbls 2% KCL down casing - 20 bbls 2% KCL down tubing. Nipple down well head. Nipple up BOPs. Trip in with 2 3/8" tubing to clean out to 6,614'. Pull out of hole and spot end of tubing at 6,408'. Hang off 2 3/8" N-80 tubing. Nipple down BOPs. Nipple up well head. Rig down rig and equipment. Move off location at 4:30 PM on 7/31/96. Swabbed well onto production.

<p>14. I hereby certify that the forgoing is true and correct</p> <p>Name (Printed/Typed) SUSAN H. SACHITANA</p> <p>Signature </p>	<p>Title COORDINATOR, REGULATORY REPORTS</p> <p>Date 082896</p>
--	---

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

<p>Approved by</p>	<p>Title</p>	<p>Date 12/9/96</p>
<p>Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.</p>		

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

ORIGINAL FILING
AMENDED FILING

DESIGNATION OF WORKOVER OR RECOMPLETION

1. Name of Operator CNG PRODUCING COMPANY		2. Utah Account Number N- 0605	5. Well Name and Number REU 13-35B	
3. Address of Operator CNG TOWER, 1450 POYDRAS STREET NEW ORLEANS, LA 70112-6000			6. API Well Number 43-047-32094	
4. Telephone Number 504-593-7291		7. Field Name ISLAND		8. Field Code Number
9. Location of Well Footage : OO, Sec. T., R. : SEC. 35 - T9S - R19E County : UTAH State : UTAH				

COMPLETE ALL SECTIONS. ATTACH ADDITIONAL SHEETS IF NEEDED.

10. TYPE OF WORK (Check One) <input checked="" type="checkbox"/> Production enhancement <input type="checkbox"/> Convert to injection	<input type="checkbox"/> Recompletion <input type="checkbox"/> Repair well	11. Date work commenced <u>7/23/96</u> Date work completed <u>8/2/96</u>
---	---	---

12. THE FOLLOWING EXPENSES FOR OPERATIONS ARE SUBMITTED FOR DESIGNATION AS WORKOVER OR RECOMPLETION EXPENSES UNDER U.C.A. 59-5-102(4):

- a. Location preparation and cleanup
- b. Move-in, rig-up and rig-down (including trucking)
- c. Rig charges (including fuel)
- d. Drill pipe or other working string
- e. Water and chemicals for circulating fluid (including water hauling)
- f. Equipment purchase
- g. Equipment rental
- h. Cementing
- i. Perforating
- j. Acidizing
- k. Fracture stimulation
- l. Logging services
- m. Supervision and overhead
- n. Other (itemize)
SEE ATTACHED
- o. Total submitted expenses
- p. Total approved expenses

Expenses	Division Approval
\$	
2,114.50	
226.19	
156.91	
194.39	
952.03	
\$ 3,644.02	3,644

13. LIST CONTRACTORS PROVIDING SERVICES VALUED AT MORE THAN \$3,000.00.

Contractor	Location (city, state)	Services Provided
N/A		

14. LIST WORKING INTEREST OWNERS WHO TAKE PRODUCT IN KIND AND ARE AUTHORIZED TO SHARE IN THE TAX CREDIT.

Name	Address	Utah Account No.	Percent of Interest
In October, 1996 CNG Producing Company purchased 100% of the interest of Enserch Exploration, Inc. effective April, 1 1996 in the subject well.			

I hereby certify that the foregoing is true and correct

Name & Signature Melinda A. Parks Title SR. ACCT. II, TAX Date 12/9/96

(State Use Only) 8/29/96

UTAH SEVERANCE TAX CREDIT
FORM 15 - ITEM NO. : OTHER

WELL NO. RBU 13-35B
AFE NO. M960181

1.	FISHING TOOLS	210	_____
2.	MISC. SUPPLIES	211	_____
3.	TRANSPORTATION	212	<u>952.03</u>
4.	SUPPLIES	216	_____
5.	COMM. EQUIP.	238	_____
6.	EMPLOYEES EXP.	287	_____
7.	EXP. EXP. OTHER	288	_____
8.			_____
9.			_____
10.			_____
	TOTAL		\$ <u>952.03</u>



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

February 28, 1997

Melinda G. Parks, Sr. Acct. II, Tax
CNG Producing Company
CNG Tower
1450 Poydras Street
New Orleans, Louisiana 70112-6000

Re: Designation of Workover or Recompletion, Form 15

Dear Ms. Parks:

Enclosed are copies of the referenced form submitted by CNG Producing Company for the following wells:

RBU 14-22F	RBU 03-20F	RBU 09-20F
RBU 15-14F	RBU 11-14F	RBU 09-14F
RBU 13-14F	RBU 03-11F	RBU 02-11F
RBU 05-10F	RBU 14-2F	RBU 16-02F
RBU 07-21E	RBU 13-35B	RBU 11-34B

The total approved workover/recompletion expenses qualifying for the severance tax credit are indicated on each form.

Please contact me if you require further information regarding this matter.

Sincerely,


R. L. Firth
Associate Director

lwp

Enclosures

cc: James W. Carter, Director
Utah Tax Commission w/ enclosure



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
U-01470-A et al
(UT-932)

JUN 2 2000

NOTICE

Dominion Exploration & Production, Inc. : Oil and Gas Leases
1450 Poydras Street :
New Orleans, LA 70112-6000 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of CNG Producing Company to Dominion Exploration & Production, Inc. on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from your list of leases and a list of leases obtained from our automated records system. We have not abstracted the lease files to determine if the entity affected by the name change holds an interest in the leases identified nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interests. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

The following lease on your list is closed on the records of this office: U-029277.

Due to the name change, the name of the principal on the bond is required to be changed from CNG Producing Company to Dominion Exploration & Production, Inc. on Bond No. 524 7050 (BLM Bond No. WY1898). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to the Wyoming State Office.

/s/ Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure
Exhibit of Leases

RECEIVED

JUN 05 2000

**DIVISION OF
OIL, GAS AND**

cc: Wyoming State Office
New Mexico State Office
Moab Field Office
Vernal Field Office
MMS—Reference Data Branch, MS 3130, Box 5860, Denver, CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114-5801
Irene Anderson (UT-932)
Teresa Thompson (UT-931)
LaVerne Steah (UT-942)

Dominion Exploration & Production, Inc.
1450 Poydras Street, New Orleans, LA 70112-6000
Phone: 504-593-7000



June 27, 2000

Mr. Jimmy Thompson
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Name Change Documentation for CNG Producing Company

Dear Mr. Thompson:

CNG Producing Company has become Dominion Exploration & Production, Inc. effective April 12, 2000. Enclosed please find a sundry regarding the name change with an attached listing of all the permits in the name of CNG Producing Company to be changed to Dominion Exploration & Production, Inc. Also enclosed please find a Form UIC 5 for the Transfer of Authority to Inject for the Federal #1-26B well.

If you have any questions or require any additional information, please contact me at (504) 593-7260.

Sincerely,

DOMINION EXPLORATION & PRODUCTION, INC.

Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Nelda Decker

RECEIVED

JUN 29 2000

DIVISION OF
OIL, GAS AND MINING

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

- 5. Lease Designation and Serial Number:
VARIOUS
- 6. If Indian, Allottee or Tribe Name:
- 7. Unit Agreement Name:
- 8. Well Name and Number:
VARIOUS
- 9. API Well Number
- 10. Field and Pool, or Wildcat:
Natural Buttes 630

- 1. Type of Well :
OIL GAS OTHER:
- 2. Name of Operator:
DOMINION EXPLORATION & PRODUCTION, INC.
- 3. Address and Telephone Number:
1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-7260
- 4. Location of Well
Footages:
QQ, Sec, T., R., M.:

County: UINTAH
State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(SUBMIT IN DUPLICATE)

SUBSEQUENT REPORT
(Submit Original Form Only)

- Abandon
- Repair Casing
- Change of Plans
- Convert to Injection
- Fracture Treat or Acidize
- Multiple Completion
- Other
- New Construction
- Pull or Alter Casing
- Recomplete
- Reperforate
- Vent or Flare
- Water Shut-Off

- Abandon*
- Repair Casing
- Change of Plans
- Convert to Injection
- Fracture Treat or Acidize
- Other
- New Construction
- Pull or Alter Casing
- Reperforate
- Vent or Flare
- Water Shut-Off

OPERATOR NAME CHANGE FOR WELLS

Date of work completion


Approximate date work will start

Report results of Multiple Completion and Recompletion to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

*Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)


Please be advised that effective April 12, 2000, CNG Producing Company has changed its name to Dominion Exploration & Production, Inc. and would like to transfer the well permits into the name of Dominion Exploration & Production, Inc. Our new bond has been filed and is pending approval with the State of Utah. The bond number is 76S 63050 361.


John R. Lewis
Sr. Vice-President - CNG Producing Company

RECEIVED

JUN 29 2000

DIVISION OF
OIL, GAS AND MINING

13. Name & Signature:  Title: Sr. Vice-President - Dominion Expl. & Prod., Inc. Date: June 26, 2000

(This space for State use only)

552894
CO 106990
File Number



State of Utah
DEPARTMENT OF COMMERCE
Division of Corporations & Commercial Code

**Application To Amend The
CERTIFICATE OF AUTHORITY OR
REGISTRATION of**

CNG Producing Company
BUSINESS ENTITY NAME

Delaware
NAME OF HOME STATE

Check Appropriate Box	
<input checked="" type="checkbox"/>	Foreign Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Non-Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Limited Partnership \$25.00
<input type="checkbox"/>	Foreign Limited Liability Company \$35.00

I. AMENDING THE BUSINESS NAME

The business name is changed to: Dominion Exploration & Production, Inc.

The corporation shall use as its name in Utah: Dominion Exploration & Production, Inc.

(The corporation shall use its name as set forth on #1, unless this name is not available)

NOTE: If the business name has changed its name in the home state, a copy of the Certificate of Amendment or a certified copy of the amendment must accompany this application.

Check the following:

- The name of the corporation is changing its name in Utah to the new name of the corporation in the home state.
- The name of the corporation is being changed in Utah to comply with Utah State Insurance Regulations.

II. AMENDING THE DURATION OF THE BUSINESS EXISTENCE

The businesses period of duration is changed to: _____

III. AMENDING THE STATE OR COUNTRY OF INCORPORATION/REGISTRATION

The corporation's state or country of incorporation/registration is changed to: _____

IV. Other: _____

(Limited Partnership changing General Partners, Limited Companies changing Members or Managers, Change of statement who is managing, etc.)
Use an attached sheet if needed.

Under penalties of perjury, I declare this Application to Amend the Certificate of Authority or Registration to be, to the best of my knowledge and belief, true and correct.

[Signature]
Signature

Vice President & Corporate Secretary
Title

April 20 2000
Date

State of Utah
Department of Commerce
Division of Corporations and Commercial Code

I Herby certify that the foregoing has been filed and approved on this 25 day of April 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner [Signature] Date 2/4/00



[Signature]
MICHAEL JENSEN
DIRECTOR

Date: 04/25/2000

Receipt Number: 22156

Amount Paid: \$60.00

STATE OF UTAH
DIVISION OF CORPORATIONS
AND COMMERCIAL CODE
160 East 300 South / Box 146705
Salt Lake City, UT 84114-6705
Service Center: (801) 530-4849
Web Site: <http://www.commerce.state.ut.us>

FILED

APR 25 2000

Well Name	Api Well Code	Operator Name	Production Status	Lease Type
EVANS FEDERAL #32-25	4304732406	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-25B	4304732445	DOMINION EXPLORATION & PR	LA	BLM
RBU #5-25B	4304732453	DOMINION EXPLORATION & PR	LA	BLM
RBU #11-25B	4304732482	DOMINION EXPLORATION & PR	LA	BLM
RBU #16-14EO	4304732507	DOMINION EXPLORATION & PR	LA	BLM
RBU #8-23EO	4304732508	DOMINION EXPLORATION & PR	LA	BLM
RBU #8-14EO	4304732514	DOMINION EXPLORATION & PR	LA	BLM
RBU #15-13EO	4304732599	DOMINION EXPLORATION & PR	LA	BLM
RBU #9-23EO	4304732601	DOMINION EXPLORATION & PR	LA	BLM
STATE #2-36E	4304732979	DOMINION EXPLORATION & PR	PR	STATE
STATE #2-36E	4304732979	DOMINION EXPLORATION & PR	PR	STATE
STATE #1-36E	4304733181	DOMINION EXPLORATION & PR	PR	STATE
RBU #1-16F	4304733360	DOMINION EXPLORATION & PR	DR	STATE
RBU #5-3F	4304733361	DOMINION EXPLORATION & PR	FUT	BLM
RBU #5-16F	4304733363	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-23F	4304733367	DOMINION EXPLORATION & PR	DR	BLM
EVANS FEDERAL #15-26E	4304733508	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #9-26E	4304733509	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #10-25E	4304733510	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #14-25E	4304733511	DOMINION EXPLORATION & PR	FUT	BLM
FEDERAL #13-30B	4304733581	DOMINION EXPLORATION & PR	FUT	BLM
STATE #13-36A	4304733598	DOMINION EXPLORATION & PR	FUT	STATE
RBU #1-1D	4304733599	DOMINION EXPLORATION & PR	FUT	BLM
OSC #1-17 *	430472030800S1	DOMINION EXPLORATION & PR	SIEC	BLM
OSC #2 *	430473008700S1	DOMINION EXPLORATION & PR	PR	BLM
OSC #4 *	430473011300S1	DOMINION EXPLORATION & PR	TA	BLM
OSC #4A-30 *	430473012200S1	DOMINION EXPLORATION & PR	SIEC	BLM
OSC #7-15E *	430473021100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-16E	430473026000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #11-18F	430473026600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-13E	430473037400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-15F	430473037500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-21F	430473037600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-19F	430473040500S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL #7-25B	430473040600S01	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-10E	430473040800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-11D	430473040900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-14E	430473041000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-23E	430473041100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-16F	430473041200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-17F	430473058400S1	DOMINION EXPLORATION & PR	PA	BLM
RBU #7-11F	430473058500S1	DOMINION EXPLORATION & PR	PR-RBU	BLM
RBU #8-16D	4304730608	DOMINION EXPLORATION & PR	PA	STATE
FEDERAL #7-25A	430473062400S01	DOMINION EXPLORATION & PR	PA	BLM
RBU #11-3F	430473068900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-22E	430473069800S1	DOMINION EXPLORATION & PR	PA	BLM
RBU #4-11D	430473071800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-23F	4304730719	DOMINION EXPLORATION & PR	PA	BLM
RBU #7-3E	430473072000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-24E	430473075900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-2F	430473076000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #7-10F	430473076100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #6-20F	430473076200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-22F	430473076800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-14F	430473082500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #2-11D	430473082600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-3F	430473088700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-15E	430473091500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-14E	430473092600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-22E	430473092700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-23E	430473097000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #4-19F	430473097100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-11F	430473097300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-10E	430473104600S1	DOMINION EXPLORATION & PR	PR	BLM

PGW


BLM

BLM

BLM

BLM

BLM



Well Name	Api Well Code	Operator Name	Production Status	Lease Type
RBU #16-16F	430473111500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-34B	430473113800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #12-18F	430473114000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-24E	430473114100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-23E	430473114300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-23E	430473114400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-14E	430473114500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-15E	430473116000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-15E	430473116100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-10E	430473117600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #14-2D	430473119100S1	DOMINION EXPLORATION & PR	SIEC	STATE
RBU #6-11D	430473119200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-14E	430473119600S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL 33-18J	430473120000S01	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-4E	430473125200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-2D	430473128000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #1-19F	430473132200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-10E	430473132300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-20F	430473132400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-3D	430473135200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-11D	430473135700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-11D	430473135800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-10D	430473136400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-13E	430473136900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #12-2D	4304731452S02	DOMINION EXPLORATION & PR	PR	STATE
RBU #16-3E	430473151800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-11F	430473151900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-17F	430473152000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-3D	430473153900S1	DOMINION EXPLORATION & PR	PR	BLM
* HILL CREEK FEDERAL #1-30	430473160100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-13E	430473160500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-22E	430473160600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-24E	430473160700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-18F	430473160800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-11F	430473161300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-16F	430473161400S2	DOMINION EXPLORATION & PR	PR	BLM
RBU #4-22F	430473161500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #12-12D	430473165100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #6-17E	430473165200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-13E	430473171500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-13E	430473171700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-35B	430473172400S1	DOMINION EXPLORATION & PR	TA	BLM
RBU #9-9E	430473173900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-16E	430473174000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #2-10D	430473180100S1	DOMINION EXPLORATION & PR	PR - RBU	BLM
APACHE FEDERAL #12-25	430473188100S1	DOMINION EXPLORATION & PR	PR	BLM BIA
APACHE FEDERAL #44-25	430473192200S2	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-2F	430473202600S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #13-14E	430473203300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-3E	430473203700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #6-18F	430473203800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-24E	430473204000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-14E	430473204100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-16E	430473204200S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #12-20F	430473205000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-13E	430473205100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-19F	430473207000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-22E	430473207100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-34B	430473207200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-15E	430473207300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-21F	430473207400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-22F	430473207500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-20F	430473208100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-23E	430473208200S1	DOMINION EXPLORATION & PR	PR	BLM

Well Name	Api Well Code	Operator Name	Production Status	Lease Type
RBU #13-24E	430473208300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-35B	430473209400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-21E	430473209500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-17F	430473210300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-19F	430473210500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-21E	430473210700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #14-2F	430473210800S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #9-21E	430473212800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-17E	430473212900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-14F	430473213300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-11F	430473213400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-2F	430473213600S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #5-16E	430473213700S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #5-21F	430473213800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-20E	430473214600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-18F	430473214900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-23E	430473215300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-24E	430473215400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-14F	430473215600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-15E	430473216600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-13E	430473216700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-10F	430473218900S1	DOMINION EXPLORATION & PR	PR	BIA
RBU #15-10E	430473219000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-17FX	430473219100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-15E	430473219700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-22E	430473219800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-23E	430473219900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-18F	430473220100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-15E	430473221100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-19F	430473221300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-17F	430473221700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-17F	430473221800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-14E	430473221900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-3E	430473222000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-35B	430473222200S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL #11-24B	430473222300S01	DOMINION EXPLORATION & PR	PR	BLM
STATE #9-36A	430473222500	DOMINION EXPLORATION & PR	TA	STATE
RBU #9-3E	430473222800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-14E	430473223900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-14F	430473224000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-17F	430473224100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-22E	430473224200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-17E	430473224300	DOMINION EXPLORATION & PR	PA	BLM
RBU #7-16E	430473224500S1	DOMINION EXPLORATION & PR	PR	STATE
FEDERAL #1-26B - GIW	4304732248	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-16E	430473225000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #8-13E	430473226300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-21F	430473226600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-10F	430473226700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-10F	430473226800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #14-22F	430473227000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-34B	430473227400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-21E	430473227600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-10E	430473228900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-17F	430473229000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-16E	430473229200S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #3-3E	430473229300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-22E	430473229500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-21E	430473230100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-21F	430473230900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-20F	430473231000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-24E	430473231200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-20F	430473231300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-2F	430473231400S1	DOMINION EXPLORATION & PR	PR	STATE

OPERATOR CHANGE WORKSHEET

1-CDW	4-KAS ✓
2-CDW ✓	5- CDW ✓
3-JLT	6-FILE

Check each listed item when completed. Write N/A if item is not applicable.

Change of Operator (Well Sold) Designation of Agent
X Operator Name Change Only Merger

The operator of the well(s) listed below has changed, effective: 4-12-00

TO:(New Operator) DOMINION EXPL & PROD INC.
 Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000
 Phone: 1-(504)-593-7000
 Account No. N1095

FROM:(Old Operator) CNG PRODUCING COMPANY
 Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000
 Phone: 1-(504)-593-7000
 Account No. N0605

WELL(S):	CA Nos.	or	Unit					
Name: <u>RBU 1-1D</u>	API: <u>43-047-33599</u>	Entity: <u>99999</u>	S <u>01</u>	T <u>10S</u>	R <u>18E</u>	Lease: <u>U-013820</u>		
Name: <u>RBU 11-34B</u>	API: <u>43-047-31138</u>	Entity: <u>7058</u>	S <u>34</u>	T <u>09S</u>	R <u>19E</u>	Lease: <u>U-017713</u>		
Name: <u>RBU 11-35B</u>	API: <u>43-047-31724</u>	Entity: <u>11502</u>	S <u>35</u>	T <u>09S</u>	R <u>19E</u>	Lease: <u>U-017713</u>		
Name: <u>RBU 13-35B</u>	API: <u>43-047-32094</u>	Entity: <u>7058</u>	S <u>35</u>	T <u>09S</u>	R <u>19E</u>	Lease: <u>U-017713</u>		
Name: <u>RBU 15-35B</u>	API: <u>43-047-32222</u>	Entity: <u>11365</u>	S <u>35</u>	T <u>09S</u>	R <u>19E</u>	Lease: <u>U-017713</u>		
Name: _____	API: _____	Entity: _____	S _____	T _____	R _____	Lease: _____		

OPERATOR CHANGE DOCUMENTATION

- YES 1. A pending operator change file has been set up.
- YES 2. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator on 6-29-00.
- YES 3. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 6-29-00.
- YES 4. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? **Yes/No** If yes, the company file number is SEE ATTACHED. If no, Division letter was mailed to the new operator on _____.
- YES 5. **Federal and Indian Lease Wells.** The BLM or the BIA has approved the merger, **name change** or operator change for all wells listed above involving Federal or Indian leases on 6-2-00.
- N/A 6. **Federal and Indian Units.** The BLM or the BIA has approved the successor of unit operator for all wells listed above involving unit operations on _____.
- N/A 7. **Federal and Indian Communitization Agreements ("CA").** The BLM or the BIA has approved the operator change for all wells listed above involved in the CA on _____.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
 Dominion Exploration & Production, Inc.

3a. Address Suite 600
 14000 Quail Springs Parkway, OKC, OK 73134

3b. Phone No. (include area code)
 (405) 749-5263

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
 814' FSL & 815' FWL, Sec. 35-9S-19E

5. Lease Serial No.
 U-017713

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
 River Bend Unit

8. Well Name and No.
 RBU 13-35B

9. API Well No.
 43-047-32094

10. Field and Pool, or Exploratory Area
 Natural Buttes

11. County or Parish, State
 Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13 Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Water produced from the above referenced well will be held in tanks until there is enough water to be hauled by a water truck. The water will then be disposed at the RBU 16-19F disposal well. Permit #43-10447.

COPY SENT TO: 2
 Date: 8-12-02
 Initials: CHO

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) Carla Christian Title Regulatory Specialist

Signature *Carla Christian* Date 8/6/2002

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by Title Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: 8/12/2002
 By: *D. R. DeF...*

Federal Approval Of This
Action Is Necessary

RECEIVED
 AUG 12 2002
 DIVISION OF
OIL, GAS AND MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

Dominion Exploration & Production, Inc.

3a. Address Suite 600
14000 Quail Springs Parkway, OKC, OK 73134

3b. Phone No. (include area code)
(405) 749-5263

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

814' FSL & 815' FWL, Sec. 35-9S-19E

5. Lease Serial No.

U-017713

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

River Bend Unit

8. Well Name and No.

RBU 13-35B

9. API Well No.

43-047-32094

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION				
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off	
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity	
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Recomplete	<input type="checkbox"/> Other	
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon		
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal		

13 Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

9/6/06 Re-perf'd Wasatch interval #1, 6572' - 98', 2 spf. Frac'd w/67,811# 20/40 Ottawa sd. W/264.2 mscf of N2 & 526 bbls YF120ST. 9/7/06 Perf'd Wasatch interval #2, 6322 - 36,(New) and existing perf's 6383- 92, & 6402- 14, 2 spf, Frac'd w/89,474# 20/40 Ottawa sd. W/328.8 mscf of N2 & 650 bbls of YF120ST. 9/8/06 Perf'd interval #3 Wasatch 6108- 16, 6124- 32, 2 spf. Frac'd on 9/14/06 w/45,222# 20/40 Ottawa sd., w/192.3 mscf of N2 and 375 bbls YF120ST. Well turned back to production.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Carla Christian

Title Sr. Regulatory Specialist

Signature

Carla Christian

Date 10/6/2006

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

OCT 11 2006

REGISTRY DIVISION

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

7/1/2007

FROM: (Old Operator): N1095-Dominion Exploration & Production, Inc 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134 Phone: 1 (405) 749-1300	TO: (New Operator): N2615-XTO Energy Inc 810 Houston St Fort Worth, TX 76102 Phone: 1 (817) 870-2800
--	--

WELL NAME	CA No.	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LIST									

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/6/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/6/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/6/2007
- a. Is the new operator registered in the State of Utah: Business Number: 5655506-0143
- b. If **NO**, the operator was contacted on:
- a. (R649-9-2) Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on:
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on:
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on:

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 9/27/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/27/2007
- Bond information entered in RBDMS on: 9/27/2007
- Fee/State wells attached to bond in RBDMS on: 9/27/2007
- Injection Projects to new operator in RBDMS on: 9/27/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/27/2007

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000138
 - Indian well(s) covered by Bond Number: n/a
 - a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 104312762
 - b. The **FORMER** operator has requested a release of liability from their bond on: 1/23/2008
- The Division sent response by letter on:

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on:

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: XTO Energy Inc. <i>N2615</i>		8. WELL NAME and NUMBER: SEE ATTACHED
3. ADDRESS OF OPERATOR: 810 Houston Street CITY Fort Worth STATE TX ZIP 76102		9. API NUMBER: SEE ATTACHED
		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective July 1, 2007, XTO Energy Inc. has purchased the wells listed on the attachment from:

Dominion Exploration & Production, Inc. *N1095*
14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134

James D. Abercrombie (405) 749-1300
James D. Abercrombie
Sr. Vice President, General Manager - Western Business Unit

Please be advised that XTO Energy Inc. is considered to be the operator on the attached list and is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands. Bond coverage is provided by Nationwide BLM Bond #104312750 and Department of Natural Resources Bond #104312762.

NAME (PLEASE PRINT) <u>Edwin S. Ryan, Jr.</u>	TITLE <u>Sr. Vice President - Land Administration</u>
SIGNATURE <i>Edwin S. Ryan, Jr.</i>	DATE <u>7/31/2007</u>

(This space for State use only)

APPROVED 9127107
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED
AUG 06 2007
DIV. OF OIL, GAS & MINING

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4301530633	SKYLINE U 1-6	NENE	06	160S	060E	UTU-77263	99999	Federal	GW	DRL
4304731138	RBU 11-34B	NESW	34	090S	190E	U-017713	7058	Federal	GW	P
4304731179	BARTON FED 1-26	NWSE	26	100S	190E	U-43156	8005	Federal	GW	P
4304731724	RBU 11-35B	NESW	35	090S	190E	U-017713	11502	Federal	GW	S
4304731818	WILLOW CREEK UNIT 2	SESW	05	110S	200E	U-39223	11604	Federal	GW	TA
4304731878	EVANS FED 3-25	NENW	25	100S	190E	U-43156	11106	Federal	GW	P
4304731879	EVANS FED 41-26	NENE	26	100S	190E	U-43156	11034	Federal	GW	P
4304731881	APACHE 12-25	NWSW	25	100S	190E	UTU-3405	11080	Indian	GW	P
4304731897	END OF THE RAINBOW 21-1	SWSE	21	110S	240E	U-54224	11223	Federal	GW	S
4304731922	APACHE FED 44-25	SESE	25	100S	190E	U-3405	11185	Federal	GW	S
4304732094	RBU 13-35B	SWSW	35	090S	190E	U-017713	7058	Federal	GW	S
4304732222	RBU 15-35B	SWSE	35	090S	190E	U-017713	11365	Federal	GW	S
4304732237	FEDERAL 13-26B	SWSW	26	090S	190E	UTU-68625	11370	Federal	GW	S
4304732394	EVANS FED 12-25A	SWNW	25	100S	190E	U-43156	11451	Federal	GW	P
4304732395	EVANS FED 32-26	SWNE	26	100S	190E	U-43156	11447	Federal	GW	P
4304732515	WHB 1-25E	NENE	25	100S	190E	U-73011	11720	Federal	GW	P
4304732557	FEDERAL 12-11	SWNW	11	120S	240E	UTU-66425	11761	Federal	GW	S
4304732558	FEDERAL 34-30	SWSE	30	110S	230E	UTU-66410	11747	Federal	GW	S
4304732559	FEDERAL 22-22	SENW	22	110S	230E	UTU-66409	11746	Federal	GW	P
4304732560	FEDERAL 21-27	NENW	27	100S	240E	UTU-66422	11762	Federal	GW	P
4304732600	RBU 1-21EO	NENE	21	100S	190E	U-013766	11783	Federal	OW	S
4304732681	LANDING STRIP FEDERAL 44-10	SESE	10	120S	240E	UTU-69430	11853	Federal	GW	S
4304733019	BLACK DRAGON UNIT 31-34	NWNE	34	100S	240E	UTU-66422	12280	Federal	GW	P
4304733242	FEDERAL K 23-22	NESW	22	110S	210E	UTU-75098	13107	Federal	GW	P
4304733299	FED K 12-22	SWNW	22	110S	210E	UTU-75098	13133	Federal	GW	P
4304733508	EVANS FED 15-26E	SWSE	26	100S	190E	U-3405	12767	Federal	GW	P
4304733509	EVANS FED 9-26E	NESE	26	100S	190E	UTU-3405	12749	Federal	GW	P
4304733510	EVANS FED 10-25E	NWSE	25	100S	190E	U-3405	12927	Federal	GW	P
4304733511	EVANS FED 14-25E	SESW	25	100S	190E	U-3405	12793	Federal	GW	P
4304734000	RBU 1-18E	NENE	18	100S	190E	UTU-3576	14549	Federal	GW	P
4304734669	EVANS FED 4-25E	NENE	26	100S	190E	U-43156	13588	Federal	GW	P
4304734887	EVANS FED 2-26E	NWNE	26	100S	190E	U-43156	13830	Federal	GW	P
4304734908	EVANS FED 15-25E	NWSE	25	100S	190E	U-3405	14023	Federal	GW	P
4304734909	WH FED 11-26E	NESW	26	100S	190E	UTU-3405	14629	Federal	GW	P
4304734984	WHB 4-26E	NWNW	26	100S	190E	U-43156	14898	Federal	GW	P
4304734985	WHB 6-26E	SENW	26	100S	190E	U-43156	14886	Federal	GW	P
4304735034	EVANS FED 8-26E	SENE	26	100S	190E	U-43156	14145	Federal	GW	P
4304735035	WHB 12-26E	NWSW	26	100S	190E	UTU-3405	14899	Federal	GW	P
4304735036	EVANS FED 11-25E	NESW	25	100S	190E	UTU-3405	14134	Federal	GW	P
4304735037	EVANS FED 13-25E	SWSW	25	100S	190E	UTU-3405	14090	Federal	GW	P
4304735043	EVANS FED 16-26E	SESE	26	100S	190E	UTU-3405	14372	Federal	GW	P
4304735063	EVANS FED 8-25E	SENE	25	100S	190E	U-43156	14089	Federal	GW	P
4304735064	EVANS FED 6-25E	SENW	25	100S	190E	U-43156	14135	Federal	GW	P
4304735065	EVANS FED 9-25E	NESE	25	100S	190E	UTU-3405	13983	Federal	GW	P
4304735102	EVANS FED 2-25E	NWNE	25	100S	190E	U-43156	13956	Federal	GW	P
4304737451	WHB 13-26E	SWSW	26	100S	190E	UTU-3405	16058	Federal	GW	P
4304738869	LOVE 4-20G	NWNW	20	110S	210E	UTU-076040	16249	Federal	GW	DRL
4304739064	UTE TRIBAL 2-11H	NENW	11	110S	200E	14-20-H62-5611	16072	Indian	GW	DRL

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

api	well name	qtr	qtr	sec	twp	rng	lease num	entity	Lease	well	stat
4304731777	STATE 4-36E	NWNW	36	100S	190E	ML-42175	11186	State	GW	P	
4304731784	STATE 12-36E	NWSW	36	100S	190E	ML-42175	99998	State	GW	LA	
4304732019	STATE 11-36E	NESW	36	100S	190E	ML-42175	11232	State	GW	P	
4304732224	STATE 5-36B	SWNW	36	090S	190E	ML-45173	11363	State	GW	PA	
4304732249	STATE 9-36B	NESE	36	090S	190E	ML-45173	11372	State	GW	PA	
4304732316	RBU 12-2F	NWSW	02	100S	200E	ML-10716	99998	State	GW	LA	
4304732404	STATE 2-36E	NWNE	36	100S	190E	ML-42175	99998	State	GW	LA	
4304732405	STATE 9-36E	NESE	36	100S	190E	ML-42175	99998	State	GW	LA	
4304732845	H R STATE S 22-2	SENW	02	120S	230E	ML-42215		State	GW	LA	
4304732870	H R STATE S 24-2	SESW	02	120S	230E	ML-42215		State	GW	LA	
4304732940	H R STATE S 42-2	SENE	02	120S	230E	ML-42215	13175	State	D	PA	
4304732979	STATE 2-36E	NWNE	36	100S	190E	ML-42175	12390	State	GW	P	
4304733129	STATE G 22-32	SENW	32	100S	230E	ML-47063		State	GW	LA	
4304733130	H R STATE S 44-2	SESE	02	120S	230E	ML-42215		State	GW	LA	
4304733169	STATE M 42-2	SENE	02	110S	230E	ML-47078		State	GW	LA	
4304733173	STATE M 23-2	NESW	02	110S	230E	ML-47078		State	GW	LA	
4304733174	STATE M 44-2	SESE	02	110S	230E	ML-47078		State	GW	LA	
4304733175	STATE N 31-16	NWNE	16	110S	240E	ML-47080		State	GW	LA	
4304733176	STATE Q 44-16	SESE	16	120S	210E	ML-47085	13134	State	D	PA	
4304733181	STATE 1-36E	NENE	36	100S	190E	ML-42175	12539	State	GW	P	
4304733738	STATE 1-2D	NENE	02	100S	180E	ML-26968		State	GW	LA	
4304733740	STATE 9-2D	NESE	02	100S	180E	ML-13215-A		State	GW	LA	
4304733837	STATE 7-36E	SWNE	36	100S	190E	ML-42175	13186	State	GW	P	
4304734012	CLIFFS 15-21L	SWSE	21	110S	250E	FEE		Fee	GW	LA	
4304734123	STATE 15-36E	SWSE	36	100S	190E	ML-42175	13784	State	GW	P	
4304734124	STATE 9-36E	NESE	36	100S	190E	ML-42175	13760	State	GW	P	
4304734241	STATE 5-36E	SWNW	36	100S	190E	ML-42175	13753	State	GW	P	
4304734284	STATE 13-36E	SWSW	36	100S	190E	ML-42175	13785	State	GW	P	
4304734285	STATE 6-36E	SENW	36	100S	190E	ML-42175	13370	State	GW	P	
4304735089	WHB 8-36E	SENE	36	100S	190E	ML-42175	14024	State	GW	P	
4304735612	WHB 14-36E	SESW	36	100S	190E	ML-42175	14759	State	GW	P	
4304736292	WHB 12-36E	NWSW	36	100S	190E	ML-42175	15116	State	GW	P	
4304736666	KINGS CANYON 1-32E	NENE	32	100S	190E	ML-47058	14958	State	GW	P	
4304736667	KINGS CANYON 10-36D	NWSE	36	100S	180E	ML-047058	14959	State	GW	P	
4304737034	AP 15-2J	SWSE	02	110S	190E	ML-36213	15778	State	GW	P	
4304737035	AP 10-2J	NWSE	02	110S	190E	ML-36213	16029	State	GW	S	
4304737036	AP 9-2J	NESE	02	110S	190E	ML-36213	15881	State	GW	P	
4304737037	AP 8-2J	SENE	02	110S	190E	ML-36213	15821	State	GW	P	
4304737038	AP 5-2J	SWNW	02	110S	190E	ML-36213	16043	State	D	PA	
4304737039	AP 3-2J	NENW	02	110S	190E	ML-36213	15910	State	GW	P	
4304737040	AP 2-2J	NWNE	02	110S	190E	ML-36213	99999	State	GW	DRL	
4304737041	AP 1-2J	NENE	02	110S	190E	ML-36213	15882	State	GW	P	
4304737659	KC 8-32E	SENE	32	100S	190E	ML-047059	15842	State	GW	P	
4304737660	KC 9-36D	SESE	36	100S	180E	ML-047058	99999	State	GW	DRL	
4304738261	KINGS CYN 2-32E	NWNE	32	100S	190E	ML-047059	15857	State	GW	DRL	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
U-017713

6. If Indian, Allottee or Tribe Name
N/A

7. If Unit or CA/Agreement, Name and/or No.
RIVERBEND UNIT

8. Well Name and No.
13-35B

9. API Well No.
43-047-32094

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH UTAH

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
XTO Energy Inc.

3a. Address **382 CR 3100 Aztec, NM 87410** 3b. Phone No. (include area code) **505-333-3100**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
814' FSL & 815' FWL SWSW SEC 35-T9S-R19E

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>WTR ISO/PWOP</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BJA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

XTO Energy Inc. requests permission to squeeze off unproductive/water producing intervals and PWOP per the attached procedure.

Accepted by the
Utah Division of
Oil, Gas and Mining

Date: 11/24/08
By: [Signature]

Federal Approval Of This
Action Is Necessary

COPY SENT TO OPERATOR

Date: 11.26.2008
Initials: KS

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed) **BARBARA NICOL** Title **FILE CLERK**

Signature Barbara Nicol Date **10/29/2008**

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Office _____

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED
DOG M COPY
NOV 03 2008

**Riverbend Unit #13-35B
 Sec 35, T 09 S, R 19 E
 Uintah County, Utah**

Water Isolation/Put Well on Pump

Surf csg: 8-5/8", 24#, J-55, ST&C csg @ 405'. Circ cmt to surface.
Prod csg: 5-1/2", 17#, N-80, LT&C csg @ 6,899'. PBD @ 6,798'. Circ cmt to surface.
Tbg: 2-3/8" 4.7# N-80 tbg, SN @ 6,376', EOT @ 6,406'.
Perfs: WA: 5,913'-27', 6,108'-16', 6,124'-32', 6,322'-36', 6,383'-92', 6,386'-18', 6,402'-14', 6,572'-98', 6,586'-96', 6,675'-82'.
Purpose: Squeeze off unproductive/water producing intervals and PWOP.

Water Isolation/PWOP Procedure

- 1) MIRU PU. Set 1 -500 bbl tank filled with 2% KCl water, & flow back tank.
- 2) NDWH, NU BOP. TIH and tag fill. Report fill to Brock Hendrickson. TOH w/2-3/8" tbg.
- 3) TIH w/5-1/2" RBP, packer, & SN on 2-3/8" tbg to +/- 6,090'. Set RBP @ +/- 6,090' and pressure test csg/RBP to 1,000 psi. Retrieve RBP and swab test each zone list below. One or more of the intervals may be squeezed off with cement depending on the test result. Report results to Brock Hendrickson.

Interval	RBP set Depth	PKR set Depth
6,675'-6,682'	+/- 6,720'	+/- 6,650'
6,572'-6,598'	+/- 6,650'	+/- 6,540'
6,322'-6,336'	+/- 6,360'	+/- 6,280'
6,108'-6,132'	+/- 6,170'	+/- 6,050'

- 4) TOH w/BHA.
- 5) If a squeeze is necessary, a composite BP and cast iron cement retainer will be used. Set composite BP on wireline as required; run retainer on tubing and set ± 50' above perforations to be squeezed. Move retainer to closed position and pressure test tubing to 5000 psi. Open retainer, mix and pump Class G containing 0.3% FL 200 fluid loss additive, 0.2% CD-20 cement dispersant @ 15.8 ppg, (1.15 cf/sk yield, volumes to be determined). Shut down displacement with 1/2 BBL cement left in tubing; sting out of retainer and dump remaining 1/2 BBL cement on top of retainer. Pull 1 jt tubing, pump additional 1 BBL to clear tubing. TOH and WOC. Use Superior cementing service if possible.
- 6) TIH with bit, casing scraper, collars, and SN on 2.375" tubing. Drill out and test individual squeezed interval to 500 psi. DO and clean out to PBD @ 6,798'. TOH tbg & BHA. **At this point if significant water zones are isolated and squeezed off then we will attempt to return the well back to production on plunger lift, otherwise proceed with PWOP and continue to step#7.**

- 7) MI and set a Lufkin RM-320-256-120 pumping unit (min ECB 8,177 lbs) with a C-96 engine. Set CB weights as follows:

Description	Weight	Position
Left Lag	3CRO+3BS	32.4
Left Lead	3CRO+3BS	32.4
Right Lag	3CRO+3BS	32.4
Right Lead	3CRO+3BS	32.4

- 8) AN EXTERNAL, CHEMICAL, CAPILLARY STRING WILL BE BANDED TO THE TUBING, WHEN RUNNING IN WITH THE PUMP BHA.

- 9) TIH with tubing BHA as follows:

- a) 5-1/2" TECH TAC (2" ID), open ended
- b) 2-3/8" x 1 jt w/1/2" vent hole located 1' from top
- c) 2-3/8" (1.90) API SN
- d) 2-3/8" tubing to surface, SN @ 6,689', EOT @ 6,720'

- 10) Swab well until clean fluid is obtained.

- 11) TIH with rod BHA as follows:

- a) 3/4" x 8' - 0.012" Mesh Screen Dip Tube
- b) 2" x 1-1/4" x 15' x 18' RWAC
- c) 3/4" x 4' Guided Rod Sub w/mold-on guides
- d) 3/4" - 21,000 lb HF Shear Tool
- e) 10 - 1-1/4" API K Sinker Bars
- f) 32- 3/4" Norris-96 Rods w/mold-on guides
- g) 226- 3/4" Norris-96 Rods w/T-couplings
- h) 3/4" x 2' & 3/4" x 4' Norris-96 Spacer Subs
- i) 1-1/4" x 22' Polished Rod w/liner

- 12) Space out pump with spacer subs. Load tubing and long stroke with rig to ensure pump action. HWO.

- 13) RDMO PU.

- 14) Gauge tanks. Shoot FL and run dynamometer during pumping unit startup. Start well pumping at 4 SPM and 120" SL for 24 hours. Check fluid level and tank gauges.

- 15) Report pre and post start up data to Brock Hendrickson.

Regulatory

- Submit subsequent report to BLM and Utah Division of Oil Gas & Mining for water shut-off and installation of pumping unit.

Services/Material

- 5-1/2" RBP & packer
- 4-3/4" bit
- AFU
- Superior or Big Four cementing services

Equipment

- Lufkin RM-320-256-120 pumping unit (min ECB 8,177 lbs) with a C-96 engine

Tubing

- 5-1/2" TECH TAC (2" ID), open ended
- 2-3/8" x 1 jt w/1/2" vent hole located 1' from top
- 2-3/8" (1.90) API SN
- 2-3/8" tubing to surface, SN @ 6,689', EOT @ 6,720'

Rods

- 3/4" x 8' – 0.012" Mesh Screen Dip Tube
- 2" x 1-1/4" x 15' x 18' RWAC
- 3/4" x 4' Guided Rod Sub w/mold-on guides
- 3/4" – 21,000 lb HF Shear Tool
- 10 – 1-1/4" API K Sinker Bars
- 32– 3/4" Norris-96 Rods w/mold-on guides
- 226– 3/4" Norris-96 Rods w/T-couplings
- 3/4" x 2' & 3/4" x 4' Norris-96 Spacer Subs
- 1-1/4" x 22' Polished Rod w/liner

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 13-35B
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047320940000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3159 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/29/2009	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: CLEANOUT & PWOP

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. has cleaned out this well & put it on a pump per the attached Executive Summary Report.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 October 06, 2009

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Clerk
SIGNATURE N/A	DATE 10/5/2009	

EXECUTIVE SUMMARY REPORT

8/4/2009 - 10/5/2009
Report run on 10/5/2009 at 12:41 PM

Riverbend Unit 13-35B

Section 35-09S-19E, Uintah, Utah, Roosevelt
Objective: CO well & PWOP

8/7/2009 First rpt for PWOP. PBDT 6,798'. SN @ 6,406'. EOT @ 6,408'. Perfs fr/5,913' - 6,682'. MIRU Temples WS rig #1. MI & spot rig pmp & tks. Bd well. KW dwn TCA w/60 bbl 2% KCl wtr. ND WH. NU BOP. Unland tbg and LD hgr. PU & TIH w/11 jts 2-3/8", J-55, 4.7#, EUE, 8rd tbg. Tgd fill @ 6,745' (63' blw btm perf & 53' of fill). LD 11 jts tbg. TOH w/199 jts 2-3/8", J-55, 4.7#, EUE, 8rd tbg, SN & top half of Weatherford B.R.S. Found vry sli external sc. Found internal sc in last 2 jts to SN, LD & replsd jts. 3 plngrs & BHBS recd @ SN. Smpls taken for analysis. KW dwn csg w/30 bbl 2% KCl wtr. PU & TIH w/4-3/4" tricone bit, 5-1/2" csg scr, SN & 148 jts 2-3/8" tbg. EOT @ 4,786'. Leave well selling over weekend. SDFWE.

8/10/2009 ===== Riverbend Unit 13-35B =====
PBDT 6,798'. EOT @ 4,786''. Perfs fr/5,913' - 6,682'. Cont TIH w/60 jts tbg, SN, 5-1/2" csg scr w/4-3/4" tricone bit. Tgd @ 6,745' (63' blw btm perf & 53' of fill). Estb circ w/AFU. CO sptd sc fr/6,745' to 6,782' (100' blw btm perf & 16' of fill) w/2 jts tbg. Tgd hard @ 6,782' (Note: field well files indicate pmp off bit sub & bit left IH). Circ hole cln 2 hrs. RDMO AFU. TOH w/206 jts tbg, SN, 5-1/2" csg scr & 4-3/4" tricone bit. LD 5-1/2" csg scr & bit. KW dwn TCA w/40 bbl 2% KCl wtr. PU & TIH w/5-1/2" x 2-3/8" Tech Tac TAC w/mule shoe col, 1 jt 2-3/8" J-55 w/1/2" weep hole 1' from top, New 2-3/8" SN, 110 jts 2-3/8" 4.7#, J-55, EUE, 8rd tbg. RU swb tls & RIH w/1-1/2" sbs to 3,360' FS. POH & PU XTO's 1.91" tbg broach. RIH to SN. No ti spots. Cont TIH w/68 jts 2-3/8" 4.7#, J-55, EUE, 8rd tbg EOT @ 5,790'. Shut dn due to rig equ problems. Leave well selling over night. SDFN. Ppd 90 bbl 2% KCl trtd wtr w/AFU.

8/11/2009 ===== Riverbend Unit 13-35B =====
EOT @ 4,786''. Bd well. Fin TIH w/27 jts 2-3/8" tbg, 6' X 2-3/8" N-80 tbg sub, 10' X 2-3/8" N-80 tbg sub & 1jt 2-3/8" 4.7#, J-55, EUE, 8rd tbg. RU swb tls & RIH w/1-1/2" sbs to 4,500' FS. POH & PU XTO's 1.91" tbg broach. RIH to SN. No ti spots. POH & LD broach. Ppd dwn tbg w/20 bbl 2% KCl trtd wtr for pad. Dropd SV. PT tbg to 1,000 psig for 15" w/15 bbl 2% KCl trtd wtr. Tstd OK. Rlsd press. Retr SV. ND BOP. Ld tbg on hgr w/12K tension & NU WH. Fin equ run: 5-1/2" x 2-3/8" Tech TAC 40K shear w/mule shoe col, 1 jt 2-3/8" J-55 tbg w/1/2" weep hole 1' from top, new 2-3/8" SN, 205 jts 2-3/8" 4.7#, J-55, EUE, 8rd tbg, 6' X 2-3/8" N-80 tbg sub, 10' X 2-3/8" N-80 tbg sub & 1jt 2-3/8" 4.7#, J-55, EUE, 8rd tbg. SN @ 6,687'. EOT @ 6,724'. WA perfs fr/5,913' - 6,682'. TOF @ 6,782'. PBDT 6,798'. RU & RIH w/swb tls. BFL @ 3,900' FS. S.0 BO, 45 BLW, 13 runs, 4.5 hrs. FFL @ 4,000' FS w/tbg on vac, drk brn fld smpls, & tr of sd. SICP 500 psig. SWI & SDFN.

8/12/2009 ===== Riverbend Unit 13-35B =====
RU & RIH w/swb tls. BFL @ 3,900' FS. S. 0 BO, 30 BLW, 13 runs, 4.5 hrs, FFL @ 4,000' FS w/tbg on sli blw, milky wht fl smpls w/no sd or solids. SICP 950 psig. Bd well. RD swb tls. PU & loaded 2" x 1-1/4" x 20' RHAC, w/steel chrome barrel, 60 RG PA, pmp (XTO #198) w/3/4" x 1' stnr nip. PU & TIH w/pmp, 4' x 3/4" guided rod sub, shear tl (pinned to 26K), 4' x 3/4" guided rod sub, 1 - 1-1/4" API K sbs, 32 - 3/4" Norris 96 skr d w/5 molded guides pr rod, 224 - 3/4" slick Norris 96 skr d w/T cplg's, 2 - 2' x 3/4" Norris 97 rod subs & 1-1/4" x 26' PR w/1-1/2" x 14' lnr. SN @ 6,687'. EOT @ 6,724'. WA perfs fr/5,913' - 6,682'. TOF @ 6,782'. PBDT 6,798'. Seated pmp. PT tbg to 1,000 psig w/15 bbls trtd 2% kcl wtr for 10". Tstd ok. Rlsd press. LS pmp w/rig to 1000 psig. GPA. Rlsd press. Clamp off rods. SWI. RDMO Temples WS rig #1. Unable to RWTP surf equip not ready.
===== Riverbend Unit 13-35B =====

EXECUTIVE SUMMARY REPORT

8/4/2009 - 10/5/2009
Report run on 10/5/2009 at 12:41 PM

9/28/2009 Well started flwg @ 4:00 p.m. IFR of 800 mcfd. SITP 1,075 psig. FCP 1,045 psig. PU left down overnight to bring dwn head press. and awaiting mechanics to tighten motor anchors.

9/29/2009 ===== Riverbend Unit 13-35B =====
Prep ppg ut for st up. SITP 100 psig. FCP 100 psig. Std ppg ut @ 2:00 p.m.
Ppg @ 2.5 x 74" SPM. Test data to follow.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 13-35B
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047320940000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3159 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: CHEMICAL TREATMENT
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 12/2/2009			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. has performed a chemical treatment on this well:
 12/02/2009: MIRU Champion Chemical pmp trk. SN @ 6687'. Pmpd 2 bbls 15% HCL ac dwn csg. Chased w/ 1 BW. RDMO Champion Chemical trk. RWTH @ 9:00 a.m. 12/2/09. Final rpt. Test data to follow.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 December 08, 2009

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 12/8/2009	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 13-35B
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047320940000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3159 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 1/12/2011	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. has performed an acid treatment on this well per the attached summary report.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A		DATE 1/18/2011

Riverbend Unit 13-35B

1/5/2011: MIRU. Unseat pmp and fishd tbg w/30 bbls of hot trtd 2% kcl wtr. Re-seated pmp and att to PT tbg, no tst. TOH w/rods & pmp. Rods showed hvy wear in couplings fr/4,875' - 5,325'. (LD 18 bad 3/4" slick rods). The last 15 skr d showed ltl external sc BU. Rod insert pmp, appeared gd. Drop SV and followed w/30 bbls of hot trtd 2% kcl wtr, no tst, possible HIT. SWI & SDFN.

1/6/2011: ND WH & NU BOP. Rlsd TAC, TIH tgd 24' of fill @ 6,774'. TOH stand back 146 jts of tbg, LD 51 jts tbg w/bad rod wear and 6 jts w/up to 1/4" of sc on the outside. Found hole in jt #202 FS @ 6,544' FS. TIH w/prod tbg to 5,503'. RU & RIH w/1.901" tbg broach to 5,503'. No ti spots. POH & LD broach. SWI & SDFN.

1/7/2011: EOT @ 6,726'. Fin TIH w/prod tbg as follows: 2-3/8" mule shoe col, 5-1/2" Tech SH TAC, 1 jt 2-3/8" 4.7#, J-55, EUE, 8rd tbg w/weep hole, 2-3/8" SN, 153 jts 2-3/8" 4.7#, J-55, EUE 8rd tbg, 52 jts new 2-3/8" 4.7#, L-80, EUE 8rd tbg, 2 - 2-3/8" N-80 tbg subs, 1 jt new 2-3/8" 4.7#, L-80, EUE 8rd tbg & tbg hngr. Set TAC and Ld tbg on hgr w/EOT @ 6,726', SN @ 6,688' and 12K tens on TAC. RU & RIH w/1.901" tbg broach to SN @ 6,688'. No ti spots. POH & LD broach. RU swb tls. BFL 4,500' FS. S. 0 BO, 31 BLW, 7 runs, 3 hrs, FFL 4,800' FS. FTP 0 psig, SICP 0 psig. RD swb tls & SWIFPBU & SDFWE.

1/10/2011: MIRU Frac-Tech acid crew. PT surf lines to 3,000 psig. Ppd 250 gal 15% HCl ac dwn tbg. Fishd tbg w/26 bbls TFW. Shut tbg in. Ppd 500 gal 15% HCl ac dwn csg. Fishd csg w/30 bbls TFW. No press while ppg ac & fish. RDMO Frac-Tech. SWI & let ac soak for 4 hrs. RU swb tls. BFL 4,300' FS. S. 0 BO, 40 BLW, 10 runs, 3 hrs. FFL 4,700, SICP 150 psig. RD swb tls. SWI. SDFN.

1/11/2011: RU swb tls. BFL @ 4,600' FS. S. 0 BO, 96 BLW, 26 runs, 8 hrs, FFL @ 5,600' FS, SICP 375 psig. RD swb tls. SWI. SDFN.

1/12/2011: RU & RIH w/swb tls. BFL @ 5,000' FS. S. 0 BO, 18 BLW, 6 runs, 2 hrs, FFL @ 5,200' FS, SICP 250 psig. RD swb tls. PU & loaded 2" x 1-1/4" x 19' RHAC w/new 1' x 1" strn nip. TIH w/pmp BHA, 4' x 7/8" stabilizer rod, new shear tl pinned to 26 K, 4' x 7/8" stabilizer rod, 2 - 1-1/4" sbs, 1 - 4' x 7/8" rod stabilizer sub, 2 - 1-1/4" sbs, 1 - 4' x 7/8" rod stabilizer sub, 2 - 1-1/4" sbs, 1 - 4' x 7/8" rod stabilizer sub, 2 - 1-1/4" sbs, 1 - 4' x 7/8" rod stabilizer sub, 2 - 1-1/4" sbs, 1 - 4' x 7/8" rod stabilizer sub, 2 - 1-1/4" sbs, 69 - 3/4" Norris 96 skr d w/5 molded guides pr rod, 182 slick 3/4" Norris 96 skr d, 3 rod subs (6', 4' & 4') & 26' x 1-1/4" PR w/14' x 1-1/2" Inr. Seated pmp. PT tbg to 1,000 psig. Tstd ok. Rlsd press. LS pmp w/rig to 1,000 psig. Gd PA. Rlsd press. HWO. RWTP @ 2:00 p.m. ppg @ 4 SPM, 74" SL. RDMO.

=====**Riverbend Unit 13-35B**=====

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
		7. UNIT or CA AGREEMENT NAME:	
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 13-35B		
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047320940000		
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3145 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S	COUNTY: UINTAH		
	STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/3/2012 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input checked="" type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER		<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.			
<p>XTO Energy Inc. has performed an acid treatment on this well per the following: 3/28/2012: MIRU. TOH w/rods & pmp. Stnr nip was 95% plgd w/sc. TOH w/2-3/8" tbg. 3/29/2012: Cont TOH w/2-3/8" tbg. Btm 20 jts had hvy sc. TIH w/4-3/4" bit, 5-1/2" csg scr & 2-3/8" tbg. MIRU AFU. CO to 6,774'. TOH tbg, bit & scr. 3/30/2012: TIH w/2-3/8" tbg. MIRU acid pmp trk. Pmp 250 gal 10% HCL w/adds dwn tbg. Flush tbg w/26 bbls TFW. Pmp 500 gal 10% HCL w/adds dwn TCA. Flush w/30 bbls TFW. 4/2/2012: Swab. BFL @ 5,500' FS. S. 0 BO, 61 BLW, 23 runs, 7 hrs, FFL tgd 6,000' FS. 4/3/2012: TIH 2" x 1-1/4" x 19' RHBC w/new 8' GA & rods. RWTP. RDMO.</p>		<p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>FOR RECORD ONLY</p> <p>May 15, 2012</p>	
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech	
SIGNATURE N/A	DATE 5/1/2012		

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713	
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: XTO ENERGY INC		8. WELL NAME and NUMBER: RBU 13-35B	
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155		9. API NUMBER: 43047320940000	
PHONE NUMBER: 303 397-3727 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S		COUNTY: UINTAH	
		STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. has returned this well to production @ 1200 hours on Sunday, 10/05/2014.			
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 09, 2014			
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 303-397-3736	TITLE Regulatory Analyst	
SIGNATURE N/A		DATE 10/6/2014	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 13-35B
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047320940000
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155	PHONE NUMBER: 303 397-3727 Ext
9. FIELD and POOL or WILDCAT: NATURAL BUTTES	4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S
	COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 2/25/2016	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. Intends to plug back the Wasatch formation and open new zones in the Green River formation per the attached procedure.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: _____

By: *Derek Dunt*
 January 19, 2016

Please Review Attached Conditions of Approval

NAME (PLEASE PRINT) Malia Villers	PHONE NUMBER 303 397-3670	TITLE Lead Permitting Analyst
SIGNATURE N/A	DATE 1/18/2016	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047320940000

A minimum of 100' cement should be placed on the CIBP@5800' to permanently plug back the Wasatch formation as required by R649-3-24-3.2

RBU 13-35B
Green River Recompletion (3 Stage Fracture Stimulation) Procedure
Sec 35, T9S, R19E
Uintah County, Utah/ API 43-047-32094

XTO plans to plug the Wasatch zones in the RBU 13-35B and open new zones in the Green River oil play using a propped fracture treatment. Once the well has been stimulated, it will be put on pumping unit. The proposed plan is described below:

Plugback:

Set 10K CIBP @ +/-5,800' to isolate Wasatch formation. Spot 3 sxs 15.8 ppg cement on top of plug (est. plug height 25').

WOC. Test plug to 5,000 psi in preparation for fracture stimulation.

Run CBL from 5500 – 4000' to find TOC and confirm cement integrity.

Stage 1 Fracture Stimulation

Perf Information:

GR Perfs Stg 1			
Intervals			Holes
5132		5136	8
5113		5115	4
5107		5110	6
5080		5081	2
5073		5075	4
Total Holes			24

Total Fluid: 33,372 gal

Total Sand: 78,000 lbs

Stage 2 Fracture Stimulation

Perf Information:

GR Stg 2			
Interval			Holes
+/- 5060'			10k CFP
5045		5048	6
5035		5038	6
5014		5015	2
4993		4995	4
4984		4988	8
Total Holes			26

Total Fluid: 48,369 gal

Total Sand: 123,500 lbs

Stage 3 Fracture Stimulation

Perf Information:

GR Stg 3			
Interval			Holes
+/- 4935			10k CFP
4913		4914	2
4909		4911	4
4904		4906	4
4896		4901	10
4889		4891	4
Total Holes			24

Sundry Number: 69173 API Well Number: 43047320940000

Total Fluid: 33,155 gal

Total Sand: 78,000 lbs

Contact Information

Meghan Wilson, Operations Engineer (Denver); 303-397-3692 (office), 713-205-9494 (cell)

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
1. TYPE OF WELL Gas Well	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: XTO ENERGY INC	7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155	8. WELL NAME and NUMBER: RBU 13-35B
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S	9. API NUMBER: 43047320940000
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155	PHONE NUMBER: 303 397-3727 Ext
9. FIELD and POOL or WILDCAT: NATURAL BUTTES	COUNTY: UINTAH
STATE: UTAH	STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 3/8/2016	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. has permanently plugged back the WSTC formation and recompleted this well to the GRRV formation per the attached summary report and current WBD.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY
 April 11, 2016**

NAME (PLEASE PRINT) Rhonda Smith	PHONE NUMBER 505 333-3215	TITLE Regulatory Clerk
SIGNATURE N/A	DATE 4/8/2016	

Riverbend Unit 13-35B

2/10/16: Regulatory approval given by BLM, State DOGM & UDAQ to begin D&C Operations. TOH w/rods, pump and 2-3/8", 4.7# tbg. TIH w/ 4.75" bit & 5.5" scr To 5900'.

2/11/16: Ld bit/scr. TIH w/ CIBP and set @ 5,805'. Pump 17 sks class G cement from 5,805' to 5,655'. Run CBL under 1,000 psig fr/ 5,550' -200'. TOC @ 2,540'. PT 5.5" csgn to 4,200 psig. for 30 mins. Tstd Gd. perf GR stg #1 fr/5132-36', 5113-15', 5107-10', 5080-81', & 5073-75', w/2 JSPF 0.55" EHD 24 holes.

02/15/16: NU 5K frav valve, Flow cross, & Frac valve. Install hanger and test Frac stack to 5000 psig for 30 mins.

02/22/16: RIH w/ BHP & Temp log.

02/24/16: MIRU. Frac & Wireline service.

02/25/16: Fracd GR stg #1 fr/5,073-5,136' w/34,776 gals fld carrying 78,483# 20/40 White & 7,702# 20/40 SLC sd. Flshd frac w/130 bbls gel wtr. set 8K CBP @ 5,065'. PT CBP to 4,000 psig. Tstd gd. Perf GR stg #2 fr/4984-88', 4993-95', 5014-15', 5035-38', & 5045-48', w/2 JSPF 0.55" EHD 26 holes. Fracd GR stg #2 fr/4,984-5,048' w/47,502 gals fld carrying 122,504# 20/40 White & 12,949# 20/40 SLC sd. Flshd frac w/126 bbls gel wtr. set 8K CBP @ 4,950'. PT CBP to 4,000 psig. Tstd gd. Perf GR stg #3 fr/4889-91', 4896-4901', 4904-06', & 4913-14', w/2 JSPF 0.55" EHD 24 holes. Fracd GR stg #3 fr/4,889-4,914' w/32,844 gals fld carrying 77,212# 20/40 White & 7,549# 20/40 SLC sd. Flshd frac w/123 bbls gel wtr. RDMO.

03/03/16: MIRU. TIH w/ 4.75" bit.

03/04/16: Con't TIH. Tgd CBP @ 4950'. DO same. TIH w/ tbg. Tgd 50' sand @ 5,015'. CO to CBP @ 5,065'. DO same. TIH w/ tbg. Tgd sand bridge @ 5,100-15'. CO to PBTD of 5,655'.

03/07/16: TIH w/ 4.75" bit. Tgd PBTD @ 5,655'. Circ well bore clean. POH. TIH 2-7/8", 6.5#, L-80 tbg. SN @ 5,190'. EOT @ 5200'.


03/08/16: Swabbed. TIH w/pump BHA. Seated pmp. LS pmp w/rig to 1,000 psig. GPA. RDMO. RWTP.



Downhole Well Profile - with Schematic

Well Name: Riverbend Unit 13-35B

API/UWI 43047320940000	XTO Accounting ID 162575	Permit Number	State/Province Utah	County Uintah
Location T09S-R19E-S35	Spud Date 11/6/1991 00:00	Original KB Elevation (ft) 4,935.00	Ground/Corrected Ground Elevation (ft) 4,921.00	KB-Ground Distance (ft) 14.00




Wellbores							
Wellbore Name Original Hole	Parent Wellbore Original Hole	Wellbore API/UWI					
Start Depth (ftKB)	Profile Type	Kick Off Depth (ftKB)					
Section Des	Size (in)	Act Top (ftKB)	Act Btm (ftKB)				
SURFACE	12 1/4	14.0	405.0				
PROD1	7 7/8	405.0	8,200.0				
Zones							
Zone Name	Top (ftKB)	Btm (ftKB)	Current Status				
Green River	4,700.0	5,500.0					
Wasatch	5,138.0	6,682.0					
Casing Strings							
Csg Des	Set Depth (ftKB)	OD (in)	Wt/Len (lb/ft)	Grade			
Surface	405.0	8 5/8	24.00	J-55			
Production	6,899.0	5 1/2	17.00	N-80			
Cement							
Des	Type	String					
Surface Casing Cement	Casing	Surface, 405.0ftKB					
Production Casing Cement	Casing	Production, 6,899.0ftKB					
Tubing Strings							
Tubing Description	Run Date	Set Depth (ftKB)					
Item Des	OD (in)	Wt (lb/ft)	Grade	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)
Rod Strings							
Rod Description	Run Date	Set Depth (ftKB)					
Item Des	OD (in)	Wt (lb/ft)	Grade	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)
Other In Hole							
Run Date	Des	OD (in)	Top (ftKB)	Btm (ftKB)			
	Fish	4 3/4	6,774.0	6,776.0			
	Fill	5	6,777.0	6,798.0			
2/12/2016	CIBP	4.892	5,805.0	5,808.0			
2/12/2016	Cement	4.8	5,655.0	5,805.0			
Perforations							
Date	Top (ftKB)	Btm (ftKB)	Zone				
2/25/2016	4,889.0	4,891.0	Green River, Original Hole				
2/25/2016	4,896.0	4,901.0	Green River, Original Hole				
2/25/2016	4,904.0	4,906.0	Green River, Original Hole				
2/25/2016	4,909.0	4,911.0	Green River, Original Hole				
2/25/2016	4,913.0	4,914.0	Green River, Original Hole				
2/25/2016	4,984.0	4,988.0	Green River, Original Hole				
2/25/2016	4,993.0	4,995.0	Green River, Original Hole				



Downhole Well Profile - with Schematic

Well Name: Riverbend Unit 13-35B

API/UWI 43047320940000	XTO Accounting ID 162575	Permit Number	State/Province Utah	County Uintah
Location T09S-R19E-S35	Spud Date 11/6/1991 00:00	Original KB Elevation (ft) 4,935.00	Ground/Corrected Ground Elevation (ft) 4,921.00	KB-Ground Distance (ft) 14.00



Perforations				
Date	Top (ftKB)	Btm (ftKB)	Zone	
2/25/2016	5,014.0	5,015.0	Green River, Original Hole	
2/25/2016	5,035.0	5,038.0	Green River, Original Hole	
2/25/2016	5,045.0	5,048.0	Green River, Original Hole	
2/11/2016	5,073.0	5,075.0	Green River, Original Hole	
2/11/2016	5,080.0	5,081.0	Green River, Original Hole	
2/11/2016	5,107.0	5,110.0	Green River, Original Hole	
2/11/2016	5,113.0	5,115.0	Green River, Original Hole	
2/11/2016	5,132.0	5,136.0	Green River, Original Hole	
3/6/1992	5,913.0	5,913.0	Wasatch, Original Hole	
3/6/1992	5,918.0	5,918.0	Wasatch, Original Hole	
3/6/1992	5,924.0	5,924.0	Wasatch, Original Hole	
3/6/1992	5,927.0	5,927.0	Wasatch, Original Hole	
9/8/2006	6,108.0	6,116.0	Wasatch, Original Hole	
9/8/2006	6,124.0	6,132.0	Wasatch, Original Hole	
9/7/2006	6,322.0	6,336.0	Wasatch, Original Hole	
9/7/2006	6,383.0	6,392.0	Wasatch, Original Hole	
3/6/1992	6,386.0	6,386.0	Wasatch, Original Hole	
3/6/1992	6,389.0	6,389.0	Wasatch, Original Hole	
9/7/2006	6,402.0	6,414.0	Wasatch, Original Hole	
3/6/1992	6,408.0	6,408.0	Wasatch, Original Hole	
3/5/1992	6,412.0	6,412.0	Wasatch, Original Hole	
3/5/1992	6,418.0	6,418.0	Wasatch, Original Hole	
9/6/2006	6,572.0	6,598.0	Wasatch, Original Hole	
3/5/1992	6,586.0	6,586.0	Wasatch, Original Hole	
3/5/1992	6,592.0	6,592.0	Wasatch, Original Hole	
3/5/1992	6,596.0	6,596.0	Wasatch, Original Hole	
3/5/1992	6,646.0	6,646.0	Wasatch, Original Hole	
3/5/1992	6,675.0	6,675.0	Wasatch, Original Hole	
3/5/1992	6,682.0	6,682.0	Wasatch, Original Hole	

Stimulations & Treatments						
Frac #	Top Perf (ftKB)	Bottom Perf (ftKB)	AIR (bbl/min)	MIR (bbl/min)	TWP (bbl)	Total Proppant (lb)
	5913	6682	35.0			292,500.0
	6572	6598				67,811.0
	6322	6414				89,474.0
	6108	6132				45,222.0
1.00	5073	5136	30.0	30.90	1,034.0	86,185.0
2.00	4984	5048	29.7	32.40	1,131.0	135,452.0
3.00	4889	4914	30.0	32.00	987.0	91,788.0

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9	
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713	
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: XTO ENERGY INC		8. WELL NAME and NUMBER: RBU 13-35B	
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155		9. API NUMBER: 43047320940000	
PHONE NUMBER: 303 397-3727 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S		COUNTY: UINTAH	
		STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. has first delivered from the GRRV formation of this well @1200 hours on Tuesday, 03/08/16. There is a CIBP @ 5808' (above the WSTC formation).			
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 11, 2016			
NAME (PLEASE PRINT) Rhonda Smith	PHONE NUMBER 505 333-3215	TITLE Regulatory Clerk	
SIGNATURE N/A	DATE 4/8/2016		

RECOMPLETION

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

<p>1a. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____</p> <p>b. TYPE OF WORK: NEW WELL <input type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input checked="" type="checkbox"/> OTHER _____</p>	<p>5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 017713</p> <p>6. IF INDIAN, ALLOTTEE OR TRIBE NAME</p> <p>7. UNIT or CA AGREEMENT NAME</p> <p>8. WELL NAME and NUMBER: RBU 13-35B</p>
--	--

2. NAME OF OPERATOR: XTO Energy Inc.	9. API NUMBER: 4304732094
--	-------------------------------------

3. ADDRESS OF OPERATOR: P.O. BOX 6501 CITY ENGLEWOOD STATE CO ZIP 80155	PHONE NUMBER: (303) 397-3727
---	--

4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 814' FSL 815' FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:	10 FIELD AND POOL, OR WILDCAT Watsach/Greenriver
	11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 35 9S 19E
	12. COUNTY: UINTAH 13. STATE: UTAH

14. DATE SPURRED: 11/6/1991	15. DATE T.D. REACHED: 2/19/1992	16. DATE COMPLETED: 3/8/2016	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 4923' GL
---------------------------------------	--	--	---	--

18. TOTAL DEPTH: MD 8,200 TVD	19. PLUG BACK T.D.: MD 5,655 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? * 2 tti / 1 plugged	21. DEPTH BRIDGE MD 5,805 PLUG SET: TVD
---	--	--	---

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) Prev. Drilling logs sub 1992 Current CBL, Temp Survey	23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)
---	---

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12 1/4"	8 5/8 J55	24	0	405		Class 224		0	
7 7/8"	5 1/2 N80	17	0	6,899		RFC 1,285		2540	
			0						
			0						

25. TUBING-RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 7/8"	5,200							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS	
(A) Watsach	5,913	6,682			5,913 6,682			Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(B) Watsach	6,108	6,598			6,108 6,598			Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(C) Greenriver	4,889	5,136			4,889 5,136	0.55	74	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
5913-6682	1992-Fracd w/292,500lbs of Frac Sand
6108-6598	2006-Fracd w/202,507lbs 20/40 Ottawa sand w/785.3 mscf of N2 & 1551 bls YF120ST
4889-5136	2016-Fracd w/115,122 gal YF117 Flex fld carrying 306,399 lbs 20/40 sd. Flsd w/379 bbls gel wtr.

<p>29. ENCLOSED ATTACHMENTS:</p> <p><input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS <input type="checkbox"/> GEOLOGIC REPORT <input type="checkbox"/> DST REPORT <input type="checkbox"/> DIRECTIONAL SURVEY</p> <p><input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION <input type="checkbox"/> CORE ANALYSIS <input checked="" type="checkbox"/> OTHER: CBL, Temp Svy</p>	<p>30. WELL STATUS: Prod.</p>
---	---

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
3/10/2016		3/8/2016		24			25	0	103	Flowing
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
24/64	220	250	1,077.00	1			25	0	103	Producing

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Green River Watsach	4,700 5,138

35. ADDITIONAL REMARKS (Include plugging procedure)

Rig released 03/12/2016. Watsach permanently abandoned 02/11/2016. A separate summary has been submitted.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Rhonda Smith TITLE REGULATORY CLERK
 SIGNATURE *Rhonda Smith* DATE 4/8/2016

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).


Send to: Utah Division of Oil, Gas and Mining Phone: 801-538-5340
 1594 West North Temple, Suite 1210
 Box 145801 Fax: 801-359-3940
 Salt Lake City, Utah 84114-5801



Downhole Well Profile - with Schematic

Well Name: Riverbend Unit 13-35B

API/UWI 43047320940000	XTO Accounting ID 162575	Permit Number	State/Province Utah	County Uintah
Location T09S-R19E-S35	Spud Date 11/6/1991 00:00	Original KB Elevation (ft) 4,935.00	Ground/Corrected Ground Elevation (ft) 4,921.00	KB-Ground Distance (ft) 14.00




Wellbores				
Wellbore Name Original Hole	Parent Wellbore Original Hole	Wellbore API/UWI		
Start Depth (ftKB)	Profile Type	Kick Off Depth (ftKB)		
Section Des	Size (in)	Act Top (ftKB)	Act Btm (ftKB)	
SURFACE	12 1/4	14.0	405.0	
PROD1	7 7/8	405.0	8,200.0	
Zones				
Zone Name	Top (ftKB)	Btm (ftKB)	Current Status	
Green River	4,700.0	5,500.0		
Wasatch	5,138.0	6,682.0		
Casing Strings				
Csg Des	Set Depth (ftKB)	OD (in)	Wt/Len (lb/ft)	Grade
Surface	405.0	8 5/8	24.00	J-55
Production	6,899.0	5 1/2	17.00	N-80
Cement				
Des	Type		String	
Surface Casing Cement	Casing		Surface, 405.0ftKB	
Production Casing Cement	Casing		Production, 6,899.0ftKB	
Tubing Strings				
Tubing Description	Run Date	Set Depth (ftKB)		
Item Des	OD (in)	Wt (lb/ft)	Grade	Jts
Len (ft)	Top (ftKB)	Btm (ftKB)		
Rod Strings				
Rod Description	Run Date	Set Depth (ftKB)		
Item Des	OD (in)	Wt (lb/ft)	Grade	Jts
Len (ft)	Top (ftKB)	Btm (ftKB)		
Other In Hole				
Run Date	Des	OD (in)	Top (ftKB)	Btm (ftKB)
	Fish	4 3/4	6,774.0	6,776.0
	Fill	5	6,777.0	6,798.0
2/12/2016	CI BP	4.892	5,805.0	5,808.0
2/12/2016	Cement	4.8	5,655.0	5,805.0
Perforations				
Date	Top (ftKB)	Btm (ftKB)	Zone	
2/25/2016	4,889.0	4,891.0	Green River, Original Hole	
2/25/2016	4,896.0	4,901.0	Green River, Original Hole	
2/25/2016	4,904.0	4,906.0	Green River, Original Hole	
2/25/2016	4,909.0	4,911.0	Green River, Original Hole	
2/25/2016	4,913.0	4,914.0	Green River, Original Hole	
2/25/2016	4,984.0	4,988.0	Green River, Original Hole	
2/25/2016	4,993.0	4,995.0	Green River, Original Hole	



Downhole Well Profile - with Schematic

Well Name: Riverbend Unit 13-35B

API/DAI 43047320940000	XTO Accounting ID 162575	Permit Number	State/Province Utah	County Uintah
Location T09S-R19E-S35	Spud Date 11/6/1991 00:00	Original KB Elevation (ft) 4,935.00	Ground/Corrected Ground Elevation (ft) 4,921.00	KB-Ground Distance (ft) 14.00



Perforations				
Date	Top (ftKB)	Btm (ftKB)	Zone	
2/25/2016	5,014.0	5,015.0	Green River, Original Hole	
2/25/2016	5,035.0	5,038.0	Green River, Original Hole	
2/25/2016	5,045.0	5,048.0	Green River, Original Hole	
2/11/2016	5,073.0	5,075.0	Green River, Original Hole	
2/11/2016	5,080.0	5,081.0	Green River, Original Hole	
2/11/2016	5,107.0	5,110.0	Green River, Original Hole	
2/11/2016	5,113.0	5,115.0	Green River, Original Hole	
2/11/2016	5,132.0	5,136.0	Green River, Original Hole	
3/6/1992	5,913.0	5,913.0	Wasatch, Original Hole	
3/6/1992	5,918.0	5,918.0	Wasatch, Original Hole	
3/6/1992	5,924.0	5,924.0	Wasatch, Original Hole	
3/6/1992	5,927.0	5,927.0	Wasatch, Original Hole	
9/8/2006	6,108.0	6,116.0	Wasatch, Original Hole	
9/8/2006	6,124.0	6,132.0	Wasatch, Original Hole	
9/7/2006	6,322.0	6,336.0	Wasatch, Original Hole	
9/7/2006	6,383.0	6,392.0	Wasatch, Original Hole	
3/6/1992	6,386.0	6,386.0	Wasatch, Original Hole	
3/6/1992	6,389.0	6,389.0	Wasatch, Original Hole	
9/7/2006	6,402.0	6,414.0	Wasatch, Original Hole	
3/6/1992	6,408.0	6,408.0	Wasatch, Original Hole	
3/5/1992	6,412.0	6,412.0	Wasatch, Original Hole	
3/5/1992	6,418.0	6,418.0	Wasatch, Original Hole	
9/6/2006	6,572.0	6,598.0	Wasatch, Original Hole	
3/5/1992	6,586.0	6,586.0	Wasatch, Original Hole	
3/5/1992	6,592.0	6,592.0	Wasatch, Original Hole	
3/5/1992	6,596.0	6,596.0	Wasatch, Original Hole	
3/5/1992	6,646.0	6,646.0	Wasatch, Original Hole	
3/5/1992	6,675.0	6,675.0	Wasatch, Original Hole	
3/5/1992	6,682.0	6,682.0	Wasatch, Original Hole	

Stimulations & Treatments						
Frac #	Top Perf (ftKB)	Bottom Perf (ftKB)	AIR (bbl/min)	MIR (bbl/min)	TWP (bbl)	Total Proppant (lb)
	5913	6682	35.0			292,500.0
	6572	6598				67,811.0
	6322	6414				89,474.0
	6108	6132				45,222.0
1.00	5073	5136	30.0	30.90	1,034.0	86,185.0
2.00	4984	5048	29.7	32.40	1,131.0	135,452.0
3.00	4889	4914	30.0	32.00	987.0	91,788.0

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		8. WELL NAME and NUMBER: RBU 13-35B
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155		9. API NUMBER: 43047320940000
PHONE NUMBER: 303 397-3727 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/22/2016	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. performed an Acid Treatment on this well per the following: 04/22/16: MIRU acid pumper. Pump 2,000 gals 15% HCL w/adds dwn TCA. Then flush w/140 bls TFW w/30gals DN-89.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
May 04, 2016**

NAME (PLEASE PRINT) Rhonda Smith	PHONE NUMBER 505 333-3215	TITLE Regulatory Clerk
SIGNATURE N/A	DATE 5/3/2016	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well		8. WELL NAME and NUMBER: RBU 13-35B
2. NAME OF OPERATOR: XTO ENERGY INC		9. API NUMBER: 43047320940000
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155	PHONE NUMBER: 303 397-3727 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/19/2016 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input checked="" type="checkbox"/> OTHER	
	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text" value="Chemical Trtmt/Record Clea"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
XTO Energy Inc. performed a Chemical Treatment on this well per the following: 05/19/16: MIRU pmp trk. Pmpd 20 gal Flo Improver chem dwn csg. RDMO pmp trk. MIRU pmp trk. Pmpd 30 bbl prod W dwn csg @ 225 deg. F. RWTP 05/19/16. RDMO.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY July 05, 2016		
NAME (PLEASE PRINT) Rhonda Smith	PHONE NUMBER 505 333-3215	TITLE Regulatory Clerk
SIGNATURE N/A		DATE 7/5/2016

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-017713
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		8. WELL NAME and NUMBER: RBU 13-35B
3. ADDRESS OF OPERATOR: PO Box 6501 , Englewood, CO, 80155		9. API NUMBER: 43047320940000
PHONE NUMBER: 303 397-3727 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0814 FSL 0815 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 35 Township: 09.0S Range: 19.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/19/2016	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <input type="text" value="Chemical Treatment"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. performed a Chemical Treatment on this well per the following: 07/19/16: MIRU pmp trk. Pmpd 25 gal Parafree chem dwn csg. RDMO pmp trk. RWTP.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
August 04, 2016**

NAME (PLEASE PRINT) Rhonda Smith	PHONE NUMBER 505 333-3215	TITLE Regulatory Clerk
SIGNATURE N/A	DATE 8/3/2016	