

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
 b. TYPE OF WELL
 OIL WELL GAS WELL OTHER
 DRILL DEEPEN
 SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
WEXPRO COMPANY

3. ADDRESS AND TELEPHONE NO.
P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
 At surface **604' FWL, 755' FSL, SW SW**
 At proposed prod. zone **500' FWL, 2400' FSL, NW SW**
607785.82
4423521.0'

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
Approximately 20 miles southwest of Ouray, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)
604

16. NO. OF ACRES IN LEASE
640

17. NO. OF ACRES ASSIGNED TO THIS WELL
NA

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETE OR APPLIED FOR, ON THIS LEASE, FT.
Approx. 2000'

19. PROPOSED DEPTH
7672' TVD

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR. etc.)
GR 5048'

22. APPROX. DATE WORK WILL START*
Upon approval

23. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
20"	Corrugated Conductor		35'	Please refer to drilling plan
12-1/4"	9-5/8", K-55	36#	300'	Please refer to drilling plan
7-1/2"	4-1/2", N-80	11.6#	8165'	Please refer to drilling plan

5. LEASE DESIGNATION AND SERIAL NO.
U-4484

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
NA

7. UNIT AGREEMENT NAME
ISLAND

8. FARM OR LEASE NAME, WELL NO.
ISLAND UNIT NO. 67

9. API WELL NO.
PENDING

10. FIELD AND POOL, OR WILDCAT
ISLAND UNIT

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
12-10S-19E

12. COUNTY OR PARISH
UINTAH


13. STATE
UTAH

Please refer to attached Drilling Plan for details.

Please be advised that Wexpro Company is considered to be the operator of the above well and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Nationwide Bond No. SL67308873, BLM Bond No. ES0019.

This well will be drilled directionally from the Island Unit Well No. 10 location.

**Federal Approval of this
Action is Necessary**



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED *G. T. Nimmo* TITLE **G. T. Nimmo, Operations Manager** DATE *02/03/99*

(This space for Federal or State office use)
 PERMIT NO. *43047-33307* APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
 CONDITIONS OF APPROVAL IF ANY:
 APPROVED BY *Bradley G. Hill* TITLE **BRADLEY G. HILL
RECLAMATION SPECIALIST III** DATE *4/19/99*

* See Instructions On Reverse Side

T10S, R19E, S.L.B.&M.



WEXPRO COMPANY

Well location, ISLAND UNIT #67, located as shown in the SW 1/4 SW 1/4 of Section 12, T10S, R19E, S.L.B.&M. Uintah County, Utah.

S89°37'W - 80.76 (G.L.O.)

BASIS OF ELEVATION

TRIANGULATION STATION (DIVIDE) LOCATED IN THE NE 1/4 OF SECTION 23, T10S, R19E, S.L.B.&M. TAKEN FROM THE BIG PACK MOUNTAIN NW, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5375 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert A. Key
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 10437
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 12-9-98	DATE DRAWN: 12-29-98
PARTY J.F. D.A. C.B.T.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE WEXPRO COMPANY	

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

6666 80 80 80 80 80
 6666 80 80 80 80 80

0004

WEXPRO

MON 15:22 FAX 1 307 352 7575
03/22/99

T10S, R19E, S.L.B.&M.



WEXPRO COMPANY

Well location, ISLAND UNIT #67, located as shown in the SW 1/4 SW 1/4 of Section 12, T10S, R19E, S.L.B.&M. Uintah County, Utah.

S89°37'W - 80.76 (G.L.O.)

BASIS OF ELEVATION

TRIANGULATION STATION (DIVIDE) LOCATED IN THE NE 1/4 OF SECTION 23, T10S, R19E, S.L.B.&M. TAKEN FROM THE BIG PACK MOUNTAIN NW, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5375 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert J. Selby

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING		
85 SOUTH 200 EAST - VERNAL, UTAH 84070		
(435) 789-1017		
SCALE 1" = 1000'	DATE SURVEYED: 12-9-98	DATE DRAWN: 12-29-98
PARTY J.F. D.A. C.B.T.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE WEXPRO COMPANY	

- LEGEND:**
- └─┘ = 90° SYMBOL
 - = PROPOSED WELL HEAD.
 - ▲ = SECTION CORNERS LOCATED.

**Drilling Plan
Wexpro Company
Island Unit Well No. 67
Uintah County, Utah**

1. SURFACE FORMATION, ESTIMATED TOPS AND WATER, OIL, GAS OR MINERAL BEARING FORMATIONS:


Formation	TVD Depth	Remarks
Uintah	Surface	
Green River	1,349'	Gas, Secondary Objective
Birds Nest Aquifer	2,199'	
Kick Off Point	2,200'	
Wasatch Tongue	4,307'	
Green River Tongue	4,667'	Gas, Secondary Objective
Wasatch	4,817'	Gas, Secondary Objective
Total Depth	7,672'	TVD Chapita Wells Zone, Gas, Major Objective

All fresh water and prospectively valuable minerals encountered during drilling, will be recorded by depth and adequately protected.

2. **PRESSURE CONTROL EQUIPMENT:** (See attached diagram) Operator's minimum specifications for pressure control equipment require an 11-inch 3000 psi double gate hydraulically operated blowout preventer and an 11-inch 3000 psi annular preventer. BOP equipment will be tested to its rated working pressure or 70-percent of the internal yield of the surface casing. The annular preventer will be tested at 50-percent of its rated working pressure. **NOTE:** The surface casing will be pressure tested to a minimum of 1500 psi. BOP's will be checked daily as to mechanical operating condition and will be tested by rig equipment after each string of casing is run. All ram type preventers will have hand wheels which will be operative and accessible at the time the preventers are installed.

AUXILIARY EQUIPMENT:

- a. Manually operated kelly cock
- b. No floats at bit



- c. Monitoring of mud system will be visual
- d. Full opening floor valves in the full open position, capable of fitting all drill stem connections manually operated

3. CASING PROGRAM:

Size	Top	Bottom	Weight	Grade	Thread	Condition
9-5/8"	sfc	300'	36	K55	STC	New
4-1/2"	sfc	8,165' MD	11.6	N80	LTC	New

Casing Strengths:				Collapse	Burst	Tensile (minimum)
9-5/8"	36 lb.	K55	STC	2,020 psi	3,520 psi	423,000 lb.
4-1/2"	11.6 lb.	N80	LTC	6,350 psi	7,780 psi	223,000 lb

CEMENTING PROGRAMS:

9-5/8-inch Surface Casing: 222 cubic feet of Class G with 3% CaCl₂ (1/4% celloflake will only be used if lost circulation is encountered).

4-1/2-inch Production Casing: 2037 cubic feet of 50/50 Poz-gel followed by 1162 cubic feet of Class G with reducer and fluid loss additives, if needed.

4. **MUD PROGRAM:** Fresh water with gel sweeps will be used from surface to 300 feet. Fresh water with 2% KCL will be used from 300' to total depth.


Sufficient mud materials to maintain mud properties, control lost circulation and to contain blowout will be available at the wellsite.

No chrome constituent additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. **LOGGING:** Electric Logs will be run as deemed necessary.

TESTING: None

CORING: None



6. **ABNORMAL PRESSURE AND TEMPERATURE:** No abnormal pressures are anticipated. A BHT of 137 degrees F and a BHP of 2900 psi are expected.

7. **ANTICIPATED STARTING DATE:** Upon Approval


DURATION OF OPERATION: 15 days

Surface Use and Operations

Wexpro Company

Island Unit Well No. 67

Uintah County, Utah



1. Existing Road:
 - A. Proposed Well Site as Staked: Refer to well location plat and area map.
 - B. Proposed Access Route: Refer to general area map. All access roads are within lease boundaries.
 - C. Plans for Improvement and/or Maintenance: All existing roads utilized will be maintained in their present condition and no improvements will be made.

2. Planned Access Roads:
 - A. No new road construction is anticipated, however, any road upgrading will be crowned and ditched with a 16 foot running surface. Construction of the access road will necessitate a 30-foot wide right-of-way (maximum disturbance).
 - B. Maximum grade: Will not exceed 8 percent.
 - C. Turnouts: Water turnouts will be constructed as required to divert runoff water from the road ditch in such a manner as to not cause erosion.
 - D. Location (centerline): Access road has been staked and flagged. Surface disturbance and vehicular travel will be limited to the approved access route, additional area needed will be approved in advance.
 - E. Surface materials: Surface materials will be obtained from cuts along the access road and location. Spot surfacing may be required to maintain the running surface.
 - F. Any topsoil (approximately 6-inches) removed in conjunction with road construction will be spread in the borrow ditches or windrowed to the side. Borrow areas will be seeded as discussed in reclamation procedures.

3. Location of Existing Wells: Refer to area map for the location of existing wells within a one-mile radius.

4. Location of Existing and/or Proposed Facilities: Refer to area maps. Layout of new facilities will be submitted via sundry Notice prior to installation.

All permanent (onsite for six months or longer) structures constructed or installed will be painted Desert Brown, a flat, non-reflective, earthtone color to match the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation. Facilities required to comply with Occupational Safety and Health Act will be excluded.

If a tank battery is constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain one-and-a-half times the storage capacity of the battery.

Facilities will be applied for via Sundry Notice prior to installation.

All loading lines will be placed inside the berm surrounding the tank battery.

All site security guidelines identified in 43 CFR 3162.7 regulations will be adhered to.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from Authorized Officer.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried from the wellhead to the meter and anchored securely downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new installations and at least quarterly thereafter. The Authorized Officer will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with the API standards for liquid hydrocarbons and the AGA standard for natural gas measurement.

5. Location and Type of Water Supply: Water will be hauled by tank trucks from the William E. Brown water well located in Section 32-T6S-R20E, Water Use Claim #43-9077, Application #20262.
6. Source of Construction Materials: All materials will be derived from cuts at the location and along the access road. Construction material will be located on lease.
7. Methods for Handling Water Disposal: Cuttings and drilling fluids will be placed in an unlined mud pit which will be constructed with at least one half of its holding capacity below ground level. The mud pit will be fenced on three sides with a sheep-tight fence of woven wire prior to the onset of drilling. Immediately upon completion of drilling,

the fourth side will be fenced and the liquids allowed to evaporate. The fence will be maintained until restoration. Any produced liquids will be contained in test tanks and hauled out by tank trucks. Garbage and other waste materials will be placed in a trash cage, the contents of which will be disposed of in the nearest legal landfill. Portable sewage facilities will be utilized for the disposal of human waste.

Produced waste water will be confined to an unlined pit for a period not to exceed 90 days after initial production. During the 90 day period an application for approval of a permanent disposal method and location will be submitted for the Authorized Officer's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance, and will be grounds for issuing a shut-in order.

8. Ancillary Facilities: Camp facilities will not be required.
9. Wellsite Layout: Refer to drawing.
10. Plans for Restoration of the Surface: During construction, all woody vegetation and the top six-inches of topsoil material will be removed from the pad and stockpiled separately. All pits will remain fenced until cleanup begins. Overhead flagging will be installed if oil is in the mud pit.

Immediately upon completion of drilling, the location and surrounding area will be cleared of all debris, materials, trash and junk not required for production. The reserve pit and that portion of the location and access road not needed for production or production facilities will be reclaimed.

Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed. All disturbed areas will be recontoured to the approximate natural contours to the satisfaction of the Authorized Officer.

The stockpiled topsoil will be evenly distributed over the disturbed areas. Prior to reseeded, all disturbed areas, including the access roads, will be scarified and left with a rough surface. Reseeding will be done in the Fall before ground frost.

A seed drill equipped with a regulator will be required. Seed will be drilled 1/4-1/2 inch deep on the contour using a seed mixture specified by the Bureau of Land Management.

Where drilling is not possible a broadcast/rake method will be used doubling the seed mixture.

11. Surface and Mineral Ownership: Surface ownership along the access road is federal and surface ownership at the wellsite is federal.

12. Other Information: Greg Darlington of the Bureau of Land Management, Bookcliffs Resource Area, in Vernal, Utah will be notified at least 72-hours prior to commencement of both construction and reclamation operations.

A Class III Cultural Resource Inventory has been completed and the report forwarded to the Bureau of Land Management. If any cultural resources are found during construction, all work will stop, and the Authorized Officer will be notified.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


13. Lessee's or Operators Representative and Certification:


G. T. Nimmo, Operations Manager, P. O. Box 458, Rock Springs, Wyoming 82902, telephone number (307) 382-9791.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions which currently exist, that the statements made in the plan area, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Wexpro Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Date: 02/03/99


Name: 
G. T. Nimmo, Operations Manager



RECEIVED
 FEB 08 1999
 DIV. OF OIL, GAS & ...

**WEXPRO/CELSIUS
3K psi Blowout Prevention Equipment**

NOTE: Drilling spool & choke lines will be a minimum of 3" on choke side and 2" minimum on kill side



Choke Manifold System

- NOTE: 1. Minimum Choke Manifold Configuration
2. Vent Lines will be on a downward grade from choke manifold to pit and anchored securely

WEXPRO COMPANY

LOCATION LAYOUT FOR


ISLAND UNIT #68, #67, #10DD
SECTION 12, T10S, R19E, S.L.B.&M.
SW 1/4 SW 1/4

SCALE: 1" = 50'

DATE: 12-29-98

Drawn By: C.B.T.

REC'D
FEB 18 1999



Elev. Ungraded Ground at Location Stake #67 = 5047.9'
Elev. Graded Ground at Location Stake #67 = 5047.4'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East Vernal, Utah (435) 789-1017





WEXPRO COMPANY

TYPICAL CROSS SECTIONS FOR

**ISLAND UNIT #68, #67, #10DD
SECTION 12, T10S, R19E, S.L.B.&M.
SW 1/4 SW 1/4**

1" = 20'
X-Section Scale
1" = 50'

DATE: 12-29-98
Drawn By: C.B.T.



NOTE:


Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE YARDAGES

(6") Topsoil Stripping	= 1,610 Cu. Yds.
Remaining Location	= 18,730 Cu. Yds.
TOTAL CUT	= 18,340 CU.YDS.
FILL	= 2,060 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	= 16,170 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,790 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 12,380 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East Vernal, Utah (435) 788-1017



PROPOSED LOCATION:
ISLAND UNIT #68, #67, & #10DD

LEGEND:

⊙ PROPOSED LOCATION

FEB 08 1999

WEXPRO COMPANY

ISLAND UNIT #68, #67 & #10DD
SECTION 12, T10S, R19E, S.L.B.&M.
SW 1/4 SW 1/4




Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC 11 9 98
MAP MONTHS DAY YEAR

SCALE: 1:100,000 DRAWN BY: J.L.G. [REVISED: 12-30-96]



T10S



PROPOSED LOCATION:
ISLAND UNIT #68, #67, & #10DD

GURAY 10.6 MI. +/-

GURAY 10.6 MI. +/-

R 19 E
R 20 E

LEGEND:

--- PROPOSED ACCESS ROAD
— EXISTING ROAD

FEB 08 1999

WEXPRO COMPANY

ISLAND UNIT #68, #67, & #10DD
SECTION 12, T10S, R19E, S.L.B.&M.
SW 1/4 SW 1/4



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

11 9 98
MONTH DAY YEAR

B
1000

SCALE: 1" = 2000' DRAWN BY: J.L.G. (REVISED: 12-30-98)

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 02/08/1999

API NO. ASSIGNED: 43-047-33307

WELL NAME: ISLAND UNIT 67
 OPERATOR: WEXPRO COMPANY (N1070)
 CONTACT: B.T. Nimmo (307)382-9791

PROPOSED LOCATION:
 SWSW 12 - T10S - R19E
 SURFACE: 0755-FSL-0604-FWL
 BOTTOM: 2400-FSL-0500-FWL (NWSW)
 UINTAH COUNTY
 NATURAL BUTTES FIELD (630)

INSPECT LOCATN BY: / /		
TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: FED
 LEASE NUMBER: U-4484
 SURFACE OWNER: Federal

PROPOSED FORMATION: WSTC

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Federal State Fee
 (No. SL 67308873, ES0019)
- Potash (Y/N)
- Oil Shale (Y/N) *190-5(B)
- Water Permit
 (No. 43-9077)
- RDCC Review (Y/N)
 (Date: _____)
- Fee Surf Agreement (Y/N)

LOCATION AND SITING:

- R649-2-3. Unit Island
- R649-3-2. General
- R649-3-3. Exception
- Drilling Unit
 Board Cause No: _____
 Date: _____
- R649-3-11 Direct. Drill.

COMMENTS: Need add'l info. "Exempt. For & Direct. Drill." (Rec'd 4-16-99)
* spoke w/ op. & atty regarding Unit Agreements & St. Rules.

STIPULATIONS: ① FEDERAL APPROVAL




OPERATOR: WEXPRO COMPANY (N1070)

FIELD: NATURAL BUTTES (630)

SEC.12, TWP 10S, RNG 19E & SEC.7, TWP10S, RNG 20E

COUNTY: UINTAH UNIT: ISLAND

Department of Natural Resources
Division of Oil, Gas & Mining




PREPARED
DATE: 16-FEB-1999



Julie A. Wray
Direct Line: (801) 324-2736
E-Mail: JulieWr@QSTR.COM

April 14, 1999



State of Utah
Department of Natural Resources
Division of Oil, Gas and Mining
P. O. Box 145801
Salt Lake City, Utah 84114-5801
Attn: Lisha Cordova

Re: *Island Unit APD's
Uintah County, Utah*

Dear Ms. Cordova:

On February 3, 1999, Wexpro Company submitted for approval Applications for Permit to Drill (APD's) for Island Unit Wells No. 67 and 68. On March 16, 1999, Wexpro received notification from your office that approval of the APD's were being withheld because Wexpro was not in compliance with Rule No. R649-3-11 of the regulations of the Utah Division of Oil, Gas and Mining (the Division) dealing with directional drilling.

The above-referenced wells are all located within an approved federal exploratory unit -- the federal Island Unit Area "A." As such, all well permitting, location and deviation are governed under federal rules and regulations and the federal unit operating agreement. Wexpro has complied with these provisions and takes exception to the Division's imposition of additional requirements concerning Wexpro's application to drill directional wells within this federal unit. Notwithstanding, as a matter of courtesy and convenience to provide the Division with a record of its activities, Wexpro is providing the following information which should satisfy the Division's concerns.


Well	Location	Lease	Ownership
Island Unit 67	SL: SWSW, Sec 12, T10S, R19E BHL: NESW, Sec 12, T10S, R19E	U-4484	Wexpro Company - 100%
Island Unit 68	SL: SWSW, Sec 12, T10S, R19E BHL: NESW, Sec 12, T10S, R19E	U-4484	Wexpro Company - 100%

Ladies and Gentlemen
April 14, 1999
Page 2

As you can see, Wexpro is the only Working Interest Owner, thereby not requiring approval of other parties for our intended operations. We are also submitting plats which show a 460 foot radius circle drawn around our intended well bores.

We respectfully request that the Division approve our APD's as were earlier submitted. Should you have any questions, please call me at (801) 324-2736.

Sincerely,



Julie A. Wray
Staff Attorney

Enclosure

cc: Bureau of Land Management

JAW/cr



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Kathleen Clarke
Executive Director

Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

April 19, 1999

Wexpro Company
P.O. Box 458
Rock Springs, Wyoming 82902

Re: Island Unit No. 67 Well, 755' FSL, 604' FWL, SW SW, Sec. 12, T. 10 S.,
R. 19 E., Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33307.

Sincerely,

A handwritten signature in black ink that reads "John R. Baza". The signature is written in a cursive style with a large, sweeping initial 'J'.

John R. Baza
Associate Director

lwp

Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Wexpro Company

Well Name & Number: Island Unit No. 67

API Number: 43-047-33307

Lease: Federal **Surface Owner:** Federal

Location: SW SW **Sec.** 12 **T.** 10 S. **R.** 19 E.

Permitted Bottom Hole Location: 2400 FSL, 500 FWL

Sec. 12 **T.** 10 S. **R.** 19 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well. Contact Carol Daniels at (801)538-5284.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Dan Jarvis at (801) 538-5338 or Robert Krueger at (801) 538-5274.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval which must be obtained prior to drilling.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK

DRILL DEEPEN

b. TYPE OF WELL

OIL WELL GAS WELL OTHER

SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR

WEXPRO COMPANY

3. ADDRESS AND TELEPHONE NO.

P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

At surface 604' FWL, 755' FSL, SW SW
At proposed prod. zone 500' FWL, 2400' FSL, NW SW

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately 20 miles southwest of Ouray, Utah

15. DISTANCE FROM PROPOSED LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)

604

16. NO. OF ACRES IN LEASE

640

17. NO. OF ACRES ASSIGNED TO THIS WELL

NA

18. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETE OR APPLIED FOR, ON THIS LEASE, FT.

Approx. 2000'

19. PROPOSED DEPTH

7672' TVD

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

GR 5048'

22. APPROX. DATE WORK WILL START*

Upon approval

5. LEASE DESIGNATION AND SERIAL NO.

U-4484

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

NA

7. UNIT AGREEMENT NAME

ISLAND

8. FARM OR LEASE NAME, WELL NO.

ISLAND UNIT NO. 67

9. API WELL NO.

PENDING

10. FIELD AND POOL, OR WILDCAT

ISLAND UNIT

11. SEC., T., R., M., OR BLK AND SURVEY OR AREA

12-10S-19E

12. COUNTY OR PARISH

UINTAH

13. STATE

UTAH


23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
20"	Corrugated Conductor		35'	Please refer to drilling plan
12-1/4"	9-5/8", K-55	36#	300'	Please refer to drilling plan
7-1/2"	4-1/2", N-80	11.6#	8165'	Please refer to drilling plan

Please refer to attached Drilling Plan for details.

Please be advised that Wexpro Company is considered to be the operator of the above well and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Nationwide Bond No. SL67308873, BLM Bond No. ES0019.

This well will be drilled directionally from the Island Unit Well No. 10 location.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED G. T. Nimmo TITLE G. T. Nimmo, Operations Manager DATE 02/23/99

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED TO OPERATOR'S COPY

PERMIT NO. _____ APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

APPROVED BY [Signature] TITLE Assistant Field Manager Mineral Resources

DATE APR 13 1999

* See Instructions On Reverse Side

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Wexpro Company

Well Name & Number: Island Unit 67

API Number: 43-047-33307

Lease Number: U - 4484

Surface Location: SWSW Sec. 12 T. 10S R. 19E

Down Hole Location: NWSW Sec. 12 T. 10S R. 19E

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative by the operator to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 3M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the usable water zone, identified at 3,600(MD) ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to the **Top of Cement** and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

At a minimum, a DIL-SFL-GR log will be ran from TD to the kick off point.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. **One copy of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4.** Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted on initial meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension

period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Ed Forsman (435) 789-7077
Petroleum Engineer

Wayne P. Bankert (435) 789-4170
Petroleum Engineer

Jerry Kenczka (435) 781-1190
Petroleum Engineer

BLM FAX Machine (435) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

SURFACE CONDITIONS OF APPROVAL

WEXPRO COMPANY

ISLAND UNIT WELL 67

BOTTOM PRODUCTION ZONE NWSW SECTION 12, T.10 S., R.19 E.

SURFACE SWSW Section 12, T. 10 S., R. 19 E.

Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

The road shall be maintained/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, and crowning (2 to 3%). Graveling or capping the roadbed will be required as necessary to provide a well constructed safe road. Prior to construction/upgrading, the proposed road surface or existing road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Should mud holes develop, they shall be filled in to prevent detours. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainage be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. When snow is removed from the road during the winter months, the snow should be pushed outside of the burrow ditches and the turn outs should be kept clear so that when the snow melts the water will be channeled away from the road.

Surface areas that will receive new disturbance will have topsoil removed and windrowed to one side of the location (in this case the north side). The windrowed topsoil will then be seeded with the seed mixture listed and the seed worked into the soil. When the reserve pit is reclaimed and those portions of the location not needed for production are reclaimed use of this seed mixture is also recommended.

At the time of final reclamation of this site all cuts, fills, berms and borrow ditches will be returned to near natural contours. Stockpiled topsoil will then be spread over the surface of the location and the soils immediately reseeded with the following seed mix. The seeding should be drilled but if broadcasted, double the pounds per acre shall be used and the seed raked in with the soils worked mechanically to cover the seed.

Shadscale Saltbush	Atriplex confertifolia	4 lbs/acre
Mat Saltbush	Atriplex corrugata	4 lbs/acre
Galleta	Hilaria jamesii	2 lbs/acre
Indian Rice Grass	Oryzopsis hymenoides	2 lbs/acre.

Following the construction of the reserve pit, Greg Darlington or Stan Olmstead are to be notified and consulted regarding whether to line the mud pit. An unlined pit will not be authorized for drilling unless the pit has been inspected prior to drilling operations.

Produced waste water will be confined to the reserve pit/mud pit for a period not to exceed 90 days after initial production.

All pits will be fenced according to the following minimum standards:

39-inch net wire shall be used with at least one strand of barbed wire on top of the net wire (If pipe or some type of reinforcement rod is attached to the top of the entire fence, the barbed wire is not necessary.)

The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be braced in such a manner as to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces.

Maximum distance between any two posts shall not exceed 16 feet.

All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit will be fenced on three sides during drilling operations and on the fourth side when the rig moves off location. (In the APD this Reserve Pit is referred to as the Mud Pit.) Fences around existing pits will be maintained until the pit reclamation operations occur and the pits are backfilled.

If vertebrate fossils are revealed by construction activity, the operator is to immediately stop work that might further disturb such fossils, and contact the authorized officer of the BLM and the project paleontologist for guidance regarding mitigation requirements.

If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer of the BLM regarding the discovery for guidance regarding mitigation requirements.

The operator will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. On BLM land it is required that a Pesticide Use Proposal shall be submitted, and receive approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

All lease and/or unit operations will be conducted in a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the operator's field representative to ensure compliance. A complete copy of the approved APD shall be on location during construction of the location and drilling activities.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: WEXPRO COMPANY

Well Name: ISLAND UNIT 67

Api No. 43-047-33307 Lease Type: FEDERAL

Secton 12 Township 10S Range 19E County UINTAH

Drilling Contractor _____ RIG # _____

SPUDDED:

Date 07/27/99

Time _____

How ROTARY

Drilling will commence _____

Reported by GAY RONHOLDT

Telephone # _____

Date 08/03/99 Signed: JLT / CHD

DIVISION OF OIL, GAS AND MINING

AMENDED

SPUDDING INFORMATION

Name of Company: WEXPRO COMPANY

Well Name: ISLAND UNIT 67

Api No. 43-047-33307 Lease Type: FEDERAL

Secton 12 Township 10S Range 19E County UINTAH

Drilling Contractor TRUE RIG # 27

SPUDDED:

Date 08/04/99

Time 6:00 PM

How ROTARY

Drilling will commence _____

Reported by DIANNE

Telephone # 307-352-7560

Date 08/04/99 Signed: JLT / CHD

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. TYPE OF WELL <input type="checkbox"/> OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NO. U-4484
2. NAME OF OPERATOR WEXPRO COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME NA
3. ADDRESS AND TELEPHONE NO. P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791		7. IF UNIT OR CA. AGREEMENT DESIGNATION ISLAND
4. LOCATION OF WELL (FOOTAGE, SEC., T., R., M., OR SURVEY DESCRIPTION) 604' FWL, 755' FSL, SW SW 12-10S-19E (Surface Location) 500' FWL, 2400' FSL, NW SW 12-10S-19E (Bottom Hole Location)		8. WELL NAME AND NO. ISLAND UNIT NO. 67
		9. API WELL NO. 43-047-33307
		10. FIELD AND POOL, OR EXPLORATORY AREA ISLAND
		11. COUNTY OR PARISH, STATE UINTAH COUNTY, UTAH


12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other WELL HISTORY
	<input type="checkbox"/> Change in Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The above well was spud at 6:00 pm, August 4, 1999 using True Rig No. 27.
Present operation, drilling at 1,373 feet.



14. I hereby certify that the foregoing is true and correct

Signed G. T. Nimmo Title G. T. Nimmo, Operations Manager Date 08/05/99

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S. C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

OPERATOR WEXPRO COMPANY

OPERATOR ACCT. NO. N 1070

ENTITY ACTION FORM - FORM 6


ADDRESS P. O. BOX 458

ROCK SPRINGS, WYOMING 82902

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	1060	43-047-33307	ISLAND UNIT WELL NO. 67	SW SW	12	10S	19E	UINTAH	08/04/99	
WELL 1 COMMENTS: <i>990812 entity added, (Island w/ WSTC#) KDR</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)



[Signature]
 Signature G. T. NIMMO
 OPERATIONS MANAGER 08/06/99
 Title Date
 Phone No. 307-352-7577

NOTE Use COMMENT section to explain why each Action Code was selected.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. TYPE OF WELL

OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR

WEXPRO COMPANY

3. ADDRESS AND TELEPHONE NO.

P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791

4. LOCATION OF WELL (FOOTAGE, SEC., T., R., M., OR SURVEY DESCRIPTION)

604' FWL, 755' FSL SW SW 12-10S-19E (Surface Location)
500' FWL, 2400' FSL, NW SW 12-10S - 19E (Bottom Hole Location)

5. LEASE DESIGNATION AND SERIAL NO.

U-4484

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

NA

7. IF UNIT OR CA, AGREEMENT DESIGNATION

ISLAND

8. WELL NAME AND NO.

ISLAND UNIT WELL NO. 67

9. API WELL NO.

43-047-33307

10. FIELD AND POOL, OR EXPLORATORY AREA

ISLAND

11. COUNTY OR PARISH, STATE

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

Notice of Intent
 Subsequent Report
 Final Abandonment Notice


TYPE OF ACTION

Abandonment
 Recompletion
 Plugging Back
 Casing Repair
 Altering Casing
 Other Well History
 Change in Plans
 New Construction
 Non-Routine Fracturing
 Water Shut-Off
 Conversion to Injection
 Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Attached are the detailed drilling reports through August 6, 1999.



14. I hereby certify that the foregoing is true and correct

Signed [Signature] Title G. T. NIMMO, Operations Manager Date August 9, 1999

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S. C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

ISLAND UNIT NO. 67

Island Unit No. 67
Wexpro Company
604' FWL, 755' FSL
SWSW-12-T10S-R19E
Uintah, UT

API No:
Lease No: U-4484
Projected Depth: 7672'
Ground Elevation: 5048'+
KB Elevation: 5060'+

Drilling Contractor: True Rig No. 27

8/4/99: Day 1
RU rotary tools. RD, skid rig and KU. G. Ronholdt

8/5/99: Day 1
Drilling in the Surface formation at 1373 ft. Drilled 1068' in 11 hrs. MW:8.4 VIS:27 WL:12. 4 hrs - pressure test BOP. 1 hr - drill out hole for mouse hole. 3-1/2 hrs - PU BHA. 2-1/2 hrs - drilling cement and shoe. 1 hr - surveyed. Surveys: 1/4° at 520' and 1/4° at 1008'. Spudded at 6 pm on 8/4/99 w/True 27.
G. Ronholdt

8/6/99: Day 2
Drilling in the Bird's Nest formation at 2660 ft. Drilled 1287' in 15-1/2 hrs. MW:8.4 VIS:27 WL:12. 1/2 hr - serviced rig. 1/2 hr - surveyed. 1-1/2 hrs - trip out for directional tools. 1 hr - LD DC, PU directional tools. 2 hrs - TIH, orient tools. 3 hrs - TOH, MWD failed.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
1583'	1.25	144.00	2297'	5.40	357.60	2482'	13.30	354.40
2170'	0.50	247.50	2360'	7.90	-	2544'	16.40	356.20
2233'	1.90	6.00	2420'	10.90	357.20	2607'	19.70	357.90

G. Ronholdt

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. TYPE OF WELL
 OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR
WEXPRO COMPANY

3. ADDRESS AND TELEPHONE NO.
P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791

4. LOCATION OF WELL (FOOTAGE, SEC., T., R., M., OR SURVEY DESCRIPTION)
604' FWL, 755' FSL SW SW 12-10S-19E (Surface Location)
500' FWL, 2400' FSL, NW SW 12-10S - 19E (Bottom Hole Location)

FORM APPROVED
 Budget Bureau No. 1004-0135
 Expires: March 31, 1993

5. LEASE DESIGNATION AND SERIAL NO.
U-4484

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
NA

7. IF UNIT OR CA, AGREEMENT DESIGNATION
ISLAND

8. WELL NAME AND NO.
ISLAND UNIT WELL NO. 67

9. API WELL NO.
43-047-33307

10. FIELD AND POOL, OR EXPLORATORY AREA
ISLAND

11. COUNTY OR PARISH, STATE
UINTAH COUNTY, UTAH


12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other Well History
	<input type="checkbox"/> Change in Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Attached are the detailed drilling reports through August 15, 1999.
 Attached is the detailed casing report for the 4-1/2" casing run on August 14, 1999.
 The rig was released at 4:00 p.m. on 08/14/99. Present operations is waiting on completion.



14. I hereby certify that the foregoing is true and correct

Signed *G. T. Nimmo* Title G. T. NIMMO, Operations Manager Date August 23, 1999

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
 Conditions of approval, if any:

Title 18 U.S. C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

ISLAND UNIT NO. 67

Island Unit No. 67
Wexpro Company
604' FWL, 755' FSL
SWSW-12-T10S-R19E
Uintah, UT

API No:
Lease No: U-4484
Projected Depth: 7672'
Ground Elevation: 5048'±
KB Elevation: 5060'±

Drilling Contractor: True Rig No. 27

8/4/99 - RU rotary tools. RD, skid rig and RU. G. Ronholdt

8/5/99: Day 1

Drilling in the Surface formation at 1373 ft. Drilled 1068' in 11 hrs. MW:8.4 VIS:27 WL:12. 4 hrs - pressure test BOP. 1 hr - drill out hole for mouse hole. 3-1/2 hrs - PU BHA. 2-1/2 hrs - drilling cement and shoe. 1 hr - surveyed. Surveys: 1/4° at 520' and 1/4° at 1008'. Spudded at 6 pm on 8/4/99 w/True 27.

G. Ronholdt

8/6/99: Day 2

Drilling in the Bird's Nest formation at 2660 ft. Drilled 1287' in 15-1/2 hrs. MW:8.4 VIS:27 WL:12. 1/2 hr - serviced rig. 1/2 hr - surveyed. 1-1/2 hrs - trip out for directional tools. 1 hr - LD DC, PU directional tools. 2 hrs - TIH, orient tools. 3 hrs - TOH, MWD failed.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
1583'	1.25	144.00	2297'	5.40	357.60	2482'	13.30	354.40
2170'	0.50	247.50	2360'	7.90	-	2544'	16.40	356.20
2233'	1.90	6.00	2420'	10.90	357.20	2607'	19.70	357.90

G. Ronholdt

8/7/99: Day 3

Drilling in the Bird's Nest fm. at 3950 ft. Drilled 1290' in 23-1/2 hrs. MW:8.4 VIS:27 WL:12. 1/2 hr - serviced rig.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
2669'	21.90	355.50	2980'	33.90	352.30	3389'	37.00	353.70
2731'	23.90	353.40	3043'	36.60	351.60	3481'	37.40	355.80
2793'	25.90	354.40	3136'	38.70	352.70	3575'	38.50	357.90
2855'	28.30	352.00	3199'	38.30	352.00	3668'	37.40	357.60
2917'	31.20	351.60	3294'	37.50	350.60	3763'	39.10	1.10

G. Ronholdt

ISLAND UNIT NO. 67

8/8/99: Day 4

Drilling in the Wasatch Tongue formation at 4650 ft. Drilled 700' in 15 hrs. MW:8.4 VIS:27 WL:12. ½ hr - serviced rig. 3 ½ hrs - trip for bit. 2 hrs - TOH (MWD failure). ½ hr - change out MWD. 2 ½ hrs - TIH.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
3855'	36.90	0.40	4137'	36.20	358.60	4420'	36.00	358.90
3948'	37.80	359.70	4231'	36.70	358.60	4515'	35.60	357.60
4043'	38.80	0.40	4325'	48.20	468.60	4610'	37.10	359.30

G. Ronholdt

8/9/99: Day 5

Drilling in the Wasatch formation at 5695 ft. Drilled 1045' in 23-1/2 hrs. MW:8.4 VIS:27 WL:12. ½ hr - serviced rig.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
4704'	35.80	358.30	4953'	34.50	357.90	5232'	22.90	348.80
4797'	38.80	358.30	5046'	31.60	356.20	5325'	19.20	349.50
4890'	37.60	358.60	5139'	27.60	352.70	5419'	15.50	347.40
-	-	-	-	-	-	5511'	12.00	352.00

G. Ronholdt

8/10/99: Day 6

Drilling in the Wasatch formation at 6480 ft. Drilled 785' in 23-1/2 hrs. MW:8.5 VIS:27 WL:12. ½ hr - serviced rig.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
5604'	8.50	350.60	5851'	0.40	172.30	6254'	1.30	142.10
5697'	5.40	348.40	5975'	0.60	160.40	6443'	1.70	140.70
5760'	2.60	352.70	6100'	0.70	138.90	-	-	-

G. Ronholdt

8/11/99: Day 7

Drilling in the Wasatch formation at 7100 ft. Drilled 620' in 17-1/2 hrs. MW:8.5 VIS:27 WL:12.5. ½ hr - service rig. 6 hrs - trip for locked up mud motor. Surveys: 1.7° at 6565', 1.7° at 6721', 1.7° at 6755'. G. Ronholdt

ISLAND UNIT NO. 67

8/12/99: Day 8

Drilling in the Wasatch formation at 7875 ft. Drilled 775' in 23 hrs. MW:8.5 VIS:27 WL:10.5. ½ hr - service rig. ½ hr - surveyed. Survey:1.25° at 7470'. G. Ronholdt

8/13/99: Day 9

Trip out for logs in the Wasatch formation at 8155 ft. Drilled 280' in 11 hrs. MW:8.8 VIS:33 WL:8. ½ hr - surveyed. 6 ½ hrs- trip for bit. 1 hr - wash and ream to bottom. 3 ½ hrs - displace mud and circ for logs. 1 ½ hrs - survey and trip out for logs. Survey:1.75° at 7963'. G. Ronholdt

8/14/99: Day 10

RU casers in the Wasatch formation at 8205 ft. Drilled 50' in 5 ½ hrs. MW:8.8 VIS:32 WL:10.5. 3 hrs- TOH for logs. 6 hrs - logging. 4 hrs - TIH. 5 hrs - LD drill string. ½ hr - RU casers. Survey:1.0° at 8155'. G. Ronholdt

8/15/99: Day 11

Rig Down in the Wasatch formation at 8205 ft. 4 hrs - run 4 ½ " casing. ½ hr - circ casing. 2 ½ hrs - cement casing. 1 hr - ND, set slips (70,000# on slips). 2 hrs - clean tanks, set out rental equip. Released Rig at 4 p.m. on 8/15/99. G. Ronholdt

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. TYPE OF WELL
 OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR
WEXPRO COMPANY

3. ADDRESS AND TELEPHONE NO.
P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791

4. LOCATION OF WELL (FOOTAGE, SEC., T., R., M., OR SURVEY DESCRIPTION)
604' FWL, 755' FSL SW SW 12-10S-19E (Surface Location)
500' FWL, 2400' FSL, NW SW 12-10S - 19E (Bottom Hole Location)

FORM APPROVED
 Budget Bureau No. 1004-0135
 Expires: March 31, 1993

5. LEASE DESIGNATION AND SERIAL NO.
U-4484

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
NA

7. IF UNIT OR CA, AGREEMENT DESIGNATION
ISLAND

8. WELL NAME AND NO.
ISLAND UNIT WELL NO. 67

9. API WELL NO.
43-047-33307

10. FIELD AND POOL, OR EXPLORATORY AREA
ISLAND

11. COUNTY OR PARISH, STATE
UINTAH COUNTY, UTAH


12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other Well History
	<input type="checkbox"/> Change in Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Attached are the detailed drilling reports through August 15, 1999.
 Attached is the detailed casing report for the 4-1/2" casing run on August 14, 1999.
 The rig was released at 4:00 p.m. on 08/14/99. Present operations is waiting on completion.



14. I hereby certify that the foregoing is true and correct

Signed *G. T. Nimmo* Title G. T. NIMMO, Operations Manager Date August 23, 1999

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
 Conditions of approval, if any:

Title 18 U.S. C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

ISLAND UNIT NO. 67

Island Unit No. 67
Wexpro Company
604' FWL, 755' FSL
SWSW-12-T10S-R19E
Uintah, UT

API No:
Lease No: U-4484
Projected Depth: 7672'
Ground Elevation: 5048'±
KB Elevation: 5060'±

Drilling Contractor: True Rig No. 27

8/4/99 - RU rotary tools. RD, skid rig and RU. G. Ronholdt

8/5/99: Day 1

Drilling in the Surface formation at 1373 ft. Drilled 1068' in 11 hrs. MW:8.4 VIS:27 WL:12. 4 hrs - pressure test BOP. 1 hr - drill out hole for mouse hole. 3-1/2 hrs - PU BHA. 2-1/2 hrs - drilling cement and shoe. 1 hr - surveyed. Surveys: 1/4° at 520' and 1/4° at 1008'. Spudded at 6 pm on 8/4/99 w/True 27.
G. Ronholdt

8/6/99: Day 2

Drilling in the Bird's Nest formation at 2660 ft. Drilled 1287' in 15-1/2 hrs. MW:8.4 VIS:27 WL:12. 1/2 hr - serviced rig. 1/2 hr - surveyed. 1-1/2 hrs - trip out for directional tools. 1 hr - LD DC, PU directional tools. 2 hrs - TIH, orient tools. 3 hrs - TOH, MWD failed.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
1583'	1.25	144.00	2297'	5.40	357.60	2482'	13.30	354.40
2170'	0.50	247.50	2360'	7.90	-	2544'	16.40	356.20
2233'	1.90	6.00	2420'	10.90	357.20	2607'	19.70	357.90

G. Ronholdt

8/7/99: Day 3

Drilling in the Bird's Nest fm. at 3950 ft. Drilled 1290' in 23-1/2 hrs. MW:8.4 VIS:27 WL:12. 1/2 hr - serviced rig.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
2669'	21.90	355.50	2980'	33.90	352.30	3389'	37.00	353.70
2731'	23.90	353.40	3043'	36.60	351.60	3481'	37.40	355.80
2793'	25.90	354.40	3136'	38.70	352.70	3575'	38.50	357.90
2855'	28.30	352.00	3199'	38.30	352.00	3668'	37.40	357.60
2917'	31.20	351.60	3294'	37.50	350.60	3763'	39.10	1.10

G. Ronholdt

ISLAND UNIT NO. 67

8/8/99: Day 4

Drilling in the Wasatch Tongue formation at 4650 ft. Drilled 700' in 15 hrs. MW:8.4 VIS:27 WL:12. ½ hr - serviced rig. 3 ½ hrs - trip for bit. 2 hrs - TOH (MWD failure). ½ hr - change out MWD. 2 ½ hrs - TIH.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
3855'	36.90	0.40	4137'	36.20	358.60	4420'	36.00	358.90
3948'	37.80	359.70	4231'	36.70	358.60	4515'	35.60	357.60
4043'	38.80	0.40	4325'	48.20	468.60	4610'	37.10	359.30

G. Ronholdt

8/9/99: Day 5

Drilling in the Wasatch formation at 5695 ft. Drilled 1045' in 23-1/2 hrs. MW:8.4 VIS:27 WL:12. ½ hr - serviced rig.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
4704'	35.80	358.30	4953'	34.50	357.90	5232'	22.90	348.80
4797'	38.80	358.30	5046'	31.60	356.20	5325'	19.20	349.50
4890'	37.60	358.60	5139'	27.60	352.70	5419'	15.50	347.40
-	-	-	-	-	-	5511'	12.00	352.00

G. Ronholdt

8/10/99: Day 6

Drilling in the Wasatch formation at 6480 ft. Drilled 785' in 23-1/2 hrs. MW:8.5 VIS:27 WL:12. ½ hr - serviced rig.

DEPTH	INC.	AZM	DEPTH	INC.	AZM	DEPTH	INC.	AZM
5604'	8.50	350.60	5851'	0.40	172.30	6254'	1.30	142.10
5697'	5.40	348.40	5975'	0.60	160.40	6443'	1.70	140.70
5760'	2.60	352.70	6100'	0.70	138.90	-	-	-

G. Ronholdt

8/11/99: Day 7

Drilling in the Wasatch formation at 7100 ft. Drilled 620' in 17-1/2 hrs. MW:8.5 VIS:27 WL:12.5. ½ hr - service rig. 6 hrs - trip for locked up mud motor. Surveys: 1.7° at 6565', 1.7° at 6721', 1.7° at 6755'. G. Ronholdt

ISLAND UNIT NO. 67

8/12/99: Day 8

Drilling in the Wasatch formation at 7875 ft. Drilled 775' in 23 hrs. MW:8.5 VIS:27 WL:10.5. ½ hr - service rig. ½ hr - surveyed. Survey:1.25° at 7470'. G. Ronholdt

8/13/99: Day 9

Trip out for logs in the Wasatch formation at 8155 ft. Drilled 280' in 11 hrs. MW:8.8 VIS:33 WL:8. ½ hr - surveyed. 6 ½ hrs- trip for bit. 1 hr - wash and ream to bottom. 3 ½ hrs - displace mud and circ for logs. 1 ½ hrs - survey and trip out for logs. Survey:1.75° at 7963'. G. Ronholdt

8/14/99: Day 10

RU casers in the Wasatch formation at 8205 ft. Drilled 50' in 5 ½ hrs. MW:8.8 VIS:32 WL:10.5. 3 hrs- TOH for logs. 6 hrs - logging. 4 hrs - TIH. 5 hrs - LD drill string. ½ hr - RU casers. Survey:1.0° at 8155'. G. Ronholdt

8/15/99: Day 11

Rig Down in the Wasatch formation at 8205 ft. 4 hrs - run 4 ½ " casing. ½ hr - circ casing. 2 ½ hrs - cement casing. 1 hr - ND, set slips (70,000# on slips). 2 hrs - clean tanks, set out rental equip. Released Rig at 4 p.m. on 8/15/99. G. Ronholdt

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. TYPE OF WELL
 OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR
WEXPRO COMPANY

3. ADDRESS AND TELEPHONE NO.
P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791

4. LOCATION OF WELL (FOOTAGE, SEC., T., R., M., OR SURVEY DESCRIPTION)
SW SW 12-10S-19E

FORM APPROVED
 Budget Bureau No. 1004-0135
 Expires: March 31, 1993

5. LEASE DESIGNATION AND SERIAL NO.
U-4481

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
NA

7. IF UNIT OR CA. AGREEMENT DESIGNATION
ISLAND

8. WELL NAME AND NO.
ISLAND UNIT NO. 10,67,68

9. API WELL NO.
43-047-30725, 33307, 33308

10. FIELD AND POOL, OR EXPLORATORY AREA
ISLAND

11. COUNTY OR PARISH, STATE
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other <u>Install Facilities</u>
	<input type="checkbox"/> Change in Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water


(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Wexpro Company proposes to install production facilities at the above location to accommodate the newly drilled wells of Island Unit Nos. 67 and 68. Wexpro will be installing a 6' X 6' culvert pit as a water tank drain on the production tank. Please refer to the attached schematic. The pit will have an earthen bottom and an expanded metal lid. The culvert pit will be regularly maintained so that water drained from the production tank does not overflow.

The tanks on location will be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility. Soil used to construct the containment dike shall not be taken from existing topsoil stockpiles. The culvert pit will be located within the berm of the production tanks. A berm will also be placed around the blowdown tank and will be large enough to contain the contents of the blowdown tank.

All excess produced water will be collected and hauled by tank truck to the Ace Disposal Pit which is approved by the State of Utah.



14. I hereby certify that the foregoing is true and correct


Signed G. T. Nimmo Title Operations Manager Date _____

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



Location Layout
Island Unit No. 68, 10 and 67

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

Form approved
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. LEASE DESIGNATION AND SERIAL NO
U-4484

1a. TYPE OF WELL: OIL WELL GAS WELL DRY WELL OTHER

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

b. TYPE OF COMPLETION: NEW WELL WORK OVER DEEP-EN PLUG BACK DIFF RESVR. OTHER:

7. UNIT AGREEMENT NAME
ISLAND

8. FARM OR LEASE NAME
UNIT

2. NAME OF OPERATOR

WEXPRO COMPANY

9. WELL NO

67

3. ADDRESS OF OPERATOR

P. O. BOX 458, ROCK SPRINGS, WYOMING 82902

10. FIELD AND POOL, OR WILDCAT

ISLAND - WASATCH

4. LOCATION OF WELL

At surfac **604' FWL, 755' FSL, SW SW**

At top prod. interval reported below **500' FWL, 2400' FSL, NW SW 12, 10S, 19E**

At total depth **same**

11. SEC., T., R., M., OR BLOCK & SURVEY OR AREA

12-10S-19E

14. PERMIT NO.

43-047-33307

DATE ISSUED

4/13/99

12. COUNTY / PARISH

UINTAH

13. STATE

UTAH

15. DATE SPUDDED

8/4/99

16. DATE TD REACHED

8/14/99

17. DATE COMPLETED (ready to prod.)

10/19/99

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)

5060' KB 5048 GR

19. ELEV. CASINGHEAD

5,046.50

20. TOTAL DEPTH, MD & TVD

MD: 8205 TVD: 7702

21. PLUG BACK TD, MD & TVD

MD: 8155 TVD: 7652

22. IF MULT. COMPL. HOW MANY

N/A

23. INTERVALS DRILLED BY

----->

ROTARY TOOLS

0 - 8205

CABLE TOOLS

NA

24. PRODUCING INTERVAL(S) OF THIS COMPLETION - TOP, BOTTOM, NAME, (MD AND TVD)

MD: 6914 - 8084 (Gross) TVD: 6411 - 7581 (Gross) Wasatch

25. WAS DIRECTIONAL SURVEY MADE

YES

26. TYPE ELECTRIC AND OTHER LOGS RUN

FDC-CNL, HRIL, CBL and GR

27. WAS WELL CORED

NO

8-17-99

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT LB/FT	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
9 5/8	36	319.75	12 1/4	176 SACKS CLASS G	NONE
4 1/2	11.6	8,206.13	7 7/8	410 SACKS HI-LIFT and 600 SACKS "G" SELFSTRESS II	NONE

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-3/8"	7,512.00	

31. PERFORATION RECORD (Interval, size, and number)

6914-6946 - .35" - 2 SPF
7062-7072 - .35" - 4 SPF
7716-7726 - .35" - 4 SPF
7892-7902 - .35" - 4 SPF
8066-8084 - .35" - 2 SPF

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
313-315 (leak)	SQUEEZED W/110 SACKS CLASS G TO 2840 PSIG
6914-6946	FRAC - 139,201# 20/40 SAND, 1049 BBLS YF125 FLUID
7062-7072	FRAC - 124,514# 20/40 SAND, 848 BBLS YF125 FLUID
7716-7726	FRAC - 124,546# 20/40 SAND, 855 BBLS YF125 FLUID
7892-7902	FRAC - 124,445# 20/40 SAND, 863 BBLS YF125 FLUID
8066-8084	FRAC - 123,112# 20/40 SAND, 856 BBLS YF125 FLUID

33. PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping - size and type of pump)				WELL STATUS (Producing or shut-in)	
WAITING ON HOOK-UP		FLOWING				SHUT-IN: WAITING ON HOOK-UP	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL-BBL	GAS-MCF	WATER-BBL	GAS-OIL RATIO
10/17-19/99	44	20/64	----->	0	910	890 (LOAD)	NA
FLOW TUB. PRESS.	CASING PRESSURE	CALCULATED 24 HOUR RATE	OIL-BBL	GAS-MCF	WATER-BBL	OIL GRAVITY-API (CORR.)	
725	970	----->	0	1195	0	NA	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

VENTED

TEST WITNESSED BY

John Gordon

35. LIST OF ATTACHMENTS

DEC - 2 1999

36. I hereby certify that the foregoing and attached information is complete and correct as far as I know and to the best of my ability.

SIGNED

[Signature]

TITLE

Director Technical Services

DATE

11/30/99

DIVISION OF OIL, GAS & MINING

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof: cored intervals; and all drill-stem tests, including depth interval, cushion used, time tool open, flowing and shut-in pressures, and recoveries)	38. GEOLOGIC MARKERS			
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	
			NAME	TOP
			MEAS. DEPTH	TRUE VERT. DEPTH
			Log Tops UINTAH GREEN RIVER BIRD'S NEST AQUIFER WASATCH TONGUE GREEN RIVER TONGUE WASATCH	surface 1,300 2,132 4,700 5,158 5,324
				surface 1,300 2,132 4,299 4,677 4,830

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. TYPE OF WELL
 OIL WELL GAS WELL OTHER

2. NAME OF OPERATOR
WEXPRO COMPANY

3. ADDRESS AND TELEPHONE NO.
P. O. BOX 458, ROCK SPRINGS, WY 82902 (307) 382-9791

4. LOCATION OF WELL (FOOTAGE, SEC., T., R., M., OR SURVEY DESCRIPTION)
604' FWL, 755' FSL, SW SW 12-10S-19E (Surface Location)
500' FWL, 2400' FSL, NW SW 12-10S-19E (Bottom Hole Location)

FORM APPROVED
 Budget Bureau No. 1004-0135
 Expires: March 31, 1993

5. LEASE DESIGNATION AND SERIAL NO.
U-4484

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
NA

7. IF UNIT OR CA, AGREEMENT DESIGNATION
ISLAND

8. WELL NAME AND NO.
ISLAND UNIT NO. 67

9. API WELL NO.
43-047-33307

10. FIELD AND POOL, OR EXPLORATORY AREA
ISLAND

11. COUNTY OR PARISH, STATE
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change in Plans	
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction	
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing	
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off	
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection	
	<input checked="" type="checkbox"/> Other <u>Well Turn-On</u>	<input type="checkbox"/> Dispose Water	


(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

The above referenced well was brought on for initial production at 12:00 noon on December 7, 1999.
 Please consider the fax of this sundry notice to be initial notification. The original and copies will be mailed.

RECEIVED
DEC 10 1999
 DIVISION OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed  Title G. T. Nimmo, Operations Manager Date December 7, 1999

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
 Conditions of approval, if any:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004- 0137
Expires: July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on page 2.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-4484
2. Name of Operator Wexpro Company		6. If Indian, Allottee, or Tribe Name N/A
3a. Address P.O. Box 458 Rock Springs, WY 82902	3b. Phone No. (include area code) 307.382.9791	7. If Unit or CA. Agreement Name and/or No. UTU063026X Island Unit
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 755' FSL 604' FWL SW SW 12-10S-19E		8. Well Name and No. Island Unit No. 67
		9. API Well No. 43-047-33307
		10. Field and Pool, or Exploratory Area Wasatch
		11. County or Parish, State Uintah Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input checked="" type="checkbox"/> Production (Start/ Resume)	<input type="checkbox"/> Water Shut-off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths or pertinent markers and sands. Attach the Bond under which the work will performed or provide the Bond No. on file with the BLM/ BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notice shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The above well resumed production, after being off for more than 90 days, on October 17, 2007 at 10:45 A.M.

14. I hereby certify that the foregoing is true and correct.

Name (Printed/ Typed) G.T. Nimmo	Title Operations Manager
Signature 	Date October 18, 2007

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001 AND Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and fraudulently to make any statement or representation to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED

OCT 23 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004- 0137
Expires: July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on page 2.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
Wexpro Company

3a. Address
**P.O. Box 458
 Rock Springs, WY 82902**

3b. Phone No. (include area code)
307.382.9791

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
755' FSL 604' FWL SW SW 12-10S-19E

5. Lease Serial No.
U-4484

6. If Indian, Allottee, or Tribe Name
N/A

7. If Unit or CA. Agreement Name and/or No.
UTU063026X Island Unit

8. Well Name and No.
Island Unit No. 67

9. API Well No.
43-047-33307

10. Field and Pool, or Exploratory Area
Wasatch

11. County or Parish, State
Uintah Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/ Resume)	<input type="checkbox"/> Water Shut-off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and abandon	<input type="checkbox"/> Temporarily Abandon	_____
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug back	<input checked="" type="checkbox"/> Water Disposal	_____

13. Describe Proposed or Completed Operation (clearly state all pertinent details including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths or pertinent markers and sands. Attach the Bond under which the work will be performed or provide the Bond No. on file with the BLM/ BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notice shall be filed only after all requirements, including reclamantion, have been completed, and the operator has determined that the site is ready for final inspection.)

Water produced from the above well will be disposed of in a water / blow down tank as previously approved.
 Excess water production will be hauled to the following State of Utah approved disposal sites:

R N Industries Inc Sec. 4-2S-2W - Bluebell
 LaPoint Recycle & Storage Sec. 12-5S-19E - LaPoint
 Dalbo, Inc Sec. 02-6S-20E - Vernal

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY**

All excess produced water will be hauled by tank truck over Unit, Tribal, County and State roads.

14. I hereby certify that the foregoing is true and correct.


Name (Printed/ Typed)

G.T. Nimmo

Title

Operations Manager

Signature



Date

April 24, 2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001 AND Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED

APR 28 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-4484
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: ISLAND
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: ISLAND UNIT 67
2. NAME OF OPERATOR: WEXPRO COMPANY	9. API NUMBER: 4304733307000
3. ADDRESS OF OPERATOR: P.O. Box 458 , Rock Springs, WY, 82902	PHONE NUMBER: 307 922-5612 Ext
9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0755 FSL 0604 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 12 Township: 10.0S Range: 19.0E Meridian: S	COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 5/1/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Wexpro Company requests permission to alter the calibration scheduling requirements in Onshore Order 5 for wells producing less than 100 MCF/d on a monthly basis. Current schedule is quarterly per OO 5, Due to the low volume of saleable product, Wexpro requests to change calibration scheduling on these wells to every 4 months or three times a year.

**Accepted by the
Utah Division of
Oil, Gas and Mining
May 13, 2014**

Date: _____
 By: David K. Quist

NAME (PLEASE PRINT) Paul Jibson	PHONE NUMBER 307 352-7561	TITLE Permit Agent
SIGNATURE N/A	DATE 5/8/2014	

Well Name	API #	Meter ID #	Qtr/Qtr	Sec	Twn	Rng	County	Dec 2013	Nov 2013	Oct 2013	Sep 2013	Aug 2013	Jul 2013
								Avg per Day					
Island Pad 8 (10, 67 & 68)		005484	SW SW	12	10S	19E	Uintah	45	56	54	69	70	86
Island 30	43-047-31749	002988	NW NE	12	10S	19E	Uintah	23	64	58	63	72	83
Island 33	43-047-33929	005659	SW SW	8	10S	20E	Uintah	30	40	46	55	57	59
Island 27	43-047-31703	002934	NE NW	9	10S	20E	Uintah	75	77	81	86	80	82
Island 32	43-047-31751	002987	SW NE	8	10S	20E	Uintah	82	70	87	88	92	95
Island 83	43-047-33930	005660	SW SW	11	10S	19E	Uintah	50	31	45	42	36	48