

UTAH OIL AND GAS CONSERVATION COMMISSION

REMARKS: WELL LOG _____ ELECTRIC LOGS _____ FILE WATER SANDS _____ LOCATION INSPECTED _____ SUB. REPORT/abd. _____

000819 LA'D, eff 8-11-00:

DATE FILED MARCH 5, 1999

LAND: FEE & PATENTED _____ STATE LEASE NO. _____ PUBLIC LEASE NO. UTU-76280 INDIAN _____

DRILLING APPROVED: MARCH 18, 1999

SPUDDED IN:

COMPLETED: _____ PUT TO PRODUCING: _____

INITIAL PRODUCTION:

GRAVITY A.P.I.

GOR:

PRODUCING ZONES:

TOTAL DEPTH:

WELL ELEVATION:

DATE ABANDONED: LA'D 8-11-00

FIELD: WALKER HOLLOW

UNIT:

COUNTY: UINTAH

WELL NO. WALKER HALLOW 13-31 API NO. 43-047-33310

LOCATION 523 FSL FT. FROM (N) (S) LINE, 1297 FWL FT. FROM (E) (W) LINE. SE SW 1/4 - 1/4 SEC. 31

TWP.	RGE.	SEC.	OPERATOR	TWP.	RGE.	SEC.	OPERATOR
				6S	23E	31	RETAMCO OPERATING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
 DRILL DEEPEN

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 Retamco Operating Inc.

3. ADDRESS AND TELEPHONE NO.
 HCR Box 1010 Roberts, MT 59070

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)
 At surface 1297.4' FWL, 522.9' FSL of Sec. 31 T6S, R23E
 At proposed prod. zone 159' Same
 RECEIVED
 638247.41
 4156868.52
 OCT 19 1998

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 7.4 miles West of Red Wash

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any) 522.9'

16. NO. OF ACRES IN LEASE 1,383.41

17. NO. OF ACRES ASSIGNED TO THIS WELL 537.37

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 3,000'

19. PROPOSED DEPTH 3,000'

20. ROTARY OR CABLE TOOLS Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.) 5072.8' GR

22. APPROX. DATE WORK WILL START* 4/1/99

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
 SESW 31 T6S, R23E

12. COUNTY OR PARISH Uintah

13. STATE Utah

23. PROPOSED CASING AND CEMENTING PROGRAM


SIZE OF HOLE	GRADE SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/2"	8 5/8" K55	24#	200'	Cement to surface
7 7/8"	4 1/2" N80	11.6#	3000'	See page 1

Operator requests permission to drill the subject well and to change the name of well from the Gusher 13-31 to the Walker Hallow 13-31. Please see the attached 10 Point Drilling Program and 13 Point Surface Use Plan.

If you require additional information please contact:

Joe Glennon
 671 Garnet
 Billings, MT 59105
 406/248-5594

Federal Approval of this Action is Necessary



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Joe Glennon TITLE Joe Glennon, A-I-F DATE 9/15/98

(This space for Federal or State office use)

PERMIT NO. 43-047-33310 APPROVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:


APPROVED BY Bradley G. Hill TITLE BRADLEY G. HILL RECLAMATION SPECIALIST III DATE 3/18/99

*See Instructions On Reverse Side

T6S, R23E, S.L.B.&M.

RETAMCO OPERATING COMPANY

WEST - 68.66 (G.L.O.)



NO°04'W (G.L.O.)



**WELL LOCATION:
GUSHER #13-31**
ELEV. UNGRADED GROUND = 5072.8'

NOTE:
The well location bears N68°02'21"E
1398.2' from the Southwest Corner
of Section 31.

1/16 Corner
Sec. 36
NO°04'W G.L.O.
(Basis of Bearings)
1275.66' (Meas.)


Southeast Cor.
Sec. 36

WEST - 66.98 (G.L.O.)

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (REDWASH)

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF A LAND SURVEY
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF. GENE STEWART



TRI STATE LAND SURVEYING & CONSULTING	
38 WEST 100 NORTH - VERNAL, UTAH 84078 (435) 781-2501	
SCALE: 1" = 1000'	SURVEYED BY: G.S.
DATE: 8-12-98	WEATHER: WARM
DRAWN BY: J.R.S.	REVISIONS:

4. Proposed Casing Program: (Continued)

- Note: Actual volumes to be calculated from log. Anticipated cement tops will be reported as to depth; not the expected number of sacks of cement to be used. The District office should be notified, with sufficient lead time, in order to have a BLM representative on location while running all casing string and cementing.
- After cementing but before commencing any test, the casing string shall stand cemented until cement has reached a compressive strength of at least 500 psi at the shoe. WOC time shall be recorded in the drillers log.

5. Pressure Control Equipment: (See Attached)

Retamco Operating Inc.'s anticipated bottom hole pressure will be less than 3000 psi.

BOP system as described has a 3000 psi working pressure. BOP will be installed and maintained from the 8 5/8" surface casing. The BOP system including the casing will be pressure tested to the minimum standards set forth in "On Shore Order #2".

The BOP will be mechanically checked daily during the drilling operation.

6. Mud Program:

The proposed circulating mediums to be employed in drilling are as follows:

<u>Interval</u>	<u>Mud Type</u>	<u>Mud Wt.</u>	<u>Visc.</u>	<u>F/L</u>
0-200'	Water/Gel	Clean Water	----	N/C
200-3000'	Water/Gel	N/A	----	N/C
At TD	LSDN	8.4 - 8.8	34-38	10-15cc

- Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control during the course of drilling operations.
- A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, static filtration loss and PH.

Mud monitoring equipment to be used is as follows:

Periodic checks will be made each tour of the mud system. The mud level will be checked visually

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

No Chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds and no extremely hazardous substances in threshold planning quantities, (as defined in 40 CFR 355) will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3

7. Auxiliary equipment to be used is as follows:

- a. Kelly cock.
- b. No bit float is deemed necessary.
- c. A sub with a full opening valve.

8. Testing Logging and Coring Program:

A mud logger will be used from 800' to TD. No drill stem tests are anticipated. The logging program will consist of a DIL-GR from TD to base of Surface casing and a DSI-GR will be run from TD to the base of surface casing. No cores are anticipated.

Well completion reports and 2 copies all logs and will be submitted to the BLM not later than 30 days after completion of the well.


9. Anticipated Abnormal Pressures or Temperatures Expected:


No abnormal temperatures or pressures are anticipated. No H₂S has been encountered in the formations to be penetrated from previous wells drilled to similar depths in the general area.

10. Anticipated Starting Date and Duration Of The Operation:

Starting date: April 1, 1999
Duration: 10 days

TYPICAL
GAS WELL





SELF-CERTIFICATION STATEMENT


The following self-certification is provided per Federal requirements dated June 15, 1988.

Please be advised that Retamco Operating Inc. is considered to be the operator of the following well.

Walker Hallow #13-31
SESW Section 31, T6S,R23E
Lease UTU 76280
Uintah County, Utah

Retamco Operating Inc. is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands.



State Wide Bond Coverage is provided by Bond Fed. UT-1088.



Joe Glennon, A-I-F
Retamco Operating Inc.
671 Garnet
Billings, MT 59105
406/248-5594 Office
406/860-2626 Cell
406/248-6068 Fax

RETAMCO OPERATING COMPANY

GUSHER #13-31
SEC. 31, T6S, R23E, S.L.B.&M.



REFERENCE POINTS


195' NORTHEAST = 5064.0'
 246' NORTHEAST = 5063.8'

SURVEYED BY:	G.S.
DRAWN BY:	J.R.S.
DATE:	8-13-98
SCALE:	1" = 50'
FILE:	

Tri State
 Land Surveying, Inc.
 (801) 781-2501
 38 WEST 100 NORTH VERNAL, UTAH 84078

CROSS SECTIONS

GUSHER #13-31




APPROXIMATE YARDAGES

CUT = 9,490 Cu. Yds.
FILL = 9,480 Cu. Yds.
PIT = 720 Cu. Yds.
6" TOPSOIL = 1,010 Cu. Yds.


Tri State
Land Surveying, Inc.
(801) 781-2501
38 WEST 100 NORTH VERNAL, UTAH 84078

TYPICAL RIG LAYOUT

GUSHER #13-31




Tri State
Land Surveying, Inc.
(801) 781-2501
38 WEST 100 NORTH, VERNAL, UTAH 84078



RETAMCO OPERATING COMPANY
GUSHER #13-31
SEC. 31, T6S, R23E, S.L.B.&M.
TOPOGRAPHIC MAP "B"



Drawn By: SS	Revision:
Scale: 1" = 2000'	File:
Date: 8/12/98	
Tri-State Land Surveying Inc. P.O. Box 533, Vernal, UT 84078 435-781-2501 Fax 434-781-2518	



RETAMCO OPERATING COMPANY

GUSHER #13-31
SEC. 31, T6S, R23E, S.L.B.&M.
TOPOGRAPHIC MAP "A"



Drawn By: SS	Revision:
Scale: 1:100,000	File:
Date: 8/12/98	
Tri-State Land Surveying Inc. P.O. Box 533, Vernal, UT 84078 435-781-2501 Fax 434-781-2518	

Multi-Point Surface Use and Operations Plan

RETAMCO OPERATING COMPANY
GUSHER #13-31
SE SW SEC. 31, T6S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. Existing Roads: Refer to Maps "A" & "B"

- A. The proposed well site is staked and reference stakes are present.
- B. The Gusher #13-31 Location is located 5 miles Northwest of Red Wash Utah in the SE1/4 SW1/4 Section 31, T6S, R23E, SLB&M, Uintah County, Utah. To reach the Gusher #13-31, proceed West from Red Wash, Utah for 6.4 miles to the proposed access road sign. Follow flags 1.0 miles to location.
- C. Access roads - refer to Maps "A" and "B".
- D. Access roads within a one-mile radius - refer to map "B".
- E. The existing roads will be maintained in the same or better condition as existed prior to the commencement of operations and said maintenance will continue until final abandonment and reclamation of the well location.

2. Planned Access Roads: Refer to Map "B"

Approximately 1.0 miles of new road construction will be required for access to the proposed well location.

- A. Width - maximum 30-foot overall right-of-way with an 18-foot road running surface, crowned & ditched and/or sloped and dipped.
- B. Construction standard - the access road will be constructed so as to conform to the standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. (1989)

The road will be constructed to meet the standards of the anticipated traffic flow and all-weather requirements. Construction will include ditching, draining, crowning, and capping or sloping and dipping the roadbed as necessary to provide a well constructed and safe road. Prior to construction/upgrading, the roadway shall be cleared of any snow cover and allowed to dry completely.

Traveling off of the thirty (30) foot right-of-way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossing shall be designed so they will not cause siltation or the accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts.

Upgrading shall not be allowed during muddy conditions.

Should mud holes develop, they shall be filled in and detours around them avoided.

- C. Maximum grade - Less than 8%
- D. Turnouts - no turnouts will be required on this access road.
- E. Drainage design - the access road will be crowned and ditched or sloped and dipped, and water turnouts installed as necessary to provide for proper drainage along the access road route.
- F. Culverts, cuts and fills - none.
- G. Surface materials - all construction materials will be native material taken from onsite.
- H. Gates, cattleguards or fence cuts - none required.
- I. Road maintenance - during both the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and will be maintained in accordance with the original construction standards. All drainage ditches and culverts will be kept clear and free-flowing, and will also be maintained in accordance with the original construction standards. The access road right-of-way will be kept free of trash during operations.
- J. The proposed access road has been centerline flagged.
- K. If a right-of-way is required please consider this APD the application for said right-of-way.

3. Location of Existing Wells Within a One-Mile Radius:

- A. Water wells - none known.
- B. Abandoned wells - none known
- C. Temporarily abandoned wells - none known.
- D. Disposal wells - none known.
- E. Drilling wells - none known.
- F. Producing wells - none known.
- G. Shut-in wells - none known.
- H. Injection wells - none known.
- I. Monitoring wells - none known.

4. Location of Existing and/or Proposed Facilities Owned by Retamco Operating Co. Within a One-Mile Radius:

A. Existing

- 1. Tank batteries - none.
- 2. Production facilities - none.
- 3. Oil gathering lines - none.
- 4. Gas gathering lines - none.

B. New Facilities Contemplated

- 1. All production facilities will be located on the disturbed portion of the well pad and at a minimum of twenty-five (25) feet from the toe of the backslope or toe of the fill slope.
- 2. The production facilities will consist primarily of a pumping unit, Two tanks and an emergency pit. A diagram showing the proposed production facility layout is included in this APD.
- 3. Production facilities will be accommodated on the existing well pad. Construction materials required for installation of the production facilities will be obtained from the site; any additional materials required will be purchased from a local supplier having a permitted (private) source of materials within the area.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

- 4. All permanent (onsite for six months or longer) above the ground structures constructed or installed (including pumping units) will be painted Desert Brown. All production facilities will be painted within six

(6) months of installation. Facilities required to comply with Occupational Health and Safety Act Rules and Regulations will be excluded from this painting requirement.

- C. The production (emergency) pit will be 12'x12' and will be fenced. Said fence will be maintained in good condition.
- D. During drilling and subsequent operations, all equipment and vehicles will be confined to the access road right-of-way and any additional areas as specified in the approved Application for Permit to Drill.
- E. Reclamation of disturbed areas no longer needed for operation will be accomplished by grading, leveling and seeding as recommended by the Bureau of Land Management.

For Pipeline:

- F. Any proposed pipelines will be submitted to the authorized officer Via Sundry Notice for approval of subsequent operations.
- G. Retamco Operating Company shall be responsible for road maintenance from the beginning to completion of operations.

5. Location and Type of Water Supply

- A. Water to be used for the drilling of these wells will be hauled by truck over the roads described in item #1 and item #2. *Target Trucking 43.8290 per Op. 3-17-99. Jc*
- B. No water well will be drilled on this location.

6. Source of Construction Materials

- A. No construction materials are needed for drilling operations. In the event of production, the small amount of gravel needed for facilities will be hauled in by truck from a local gravel pit over existing access roads to the area. No special access other than for drilling operations and pipeline construction is needed.
- B. All access roads crossing Federal land are described under item #2, and shown on Map #A.

All construction material for this location site and access roads shall be borrowed material accumulated during the construction of the location sites and access roads. No additional construction material from other sources is

anticipated at this time, if in the future it is required the appropriate actions will be taken to acquire it from private sources.

- C. All surface disturbance area is on B.L.M. lands.
- D. The trees on this location and along the access road will be disposed of in whatever manner the B.L.M. recommends .

7. Methods of Handling Waste Materials:

- A. Cuttings - the cuttings will be deposited in the reserve pit.
- B. Drilling fluids - including salts and chemicals will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within one hundred twenty (120) days after termination of drilling and completion activities.

In the event adverse weather conditions prevent removal of the fluids from the reserve pit within this time period, an extension may be granted by the Authorized Officer upon receipt of a written request from Retamco Operating Company.

The reserve pit will be constructed so as not to leak, break, or allow discharge. The reserve pit will be lined with a 12 mil plastic reinforced liner.

- C. Produced fluids - liquid hydrocarbons produced during completion operations will be placed in test tanks on the location. Produced waste water will be confined to a lined pit (reserve pit) or storage tank for a period not to exceed ninety (90) days after initial production. During the ninety (90) day period, in accordance with Onshore Order #7, an application for approval of a permanent disposal method and location, along with the required water analysis, shall be submitted for the Authorized Officer's approval. Failure to file an application within the time frame allowed will be considered an incidence of noncompliance.

Any spills of oil, gas, salt water or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

- D. Sewage - self-contained, chemical toilets will be provided for human waste disposal. Upon completion of operations, or as needed, the toilet holding tanks will be pumped and

the contents thereof disposed of in the nearest, approved, sewage disposal facility.

- E. Garbage and other waste material - garbage, trash and other waste materials will be collected in a portable, self-contained and fully-enclosed trash cage during drilling and completion operations. Upon completion of operations (or as needed) the accumulated trash will be disposed of at an authorized sanitary landfill. No trash will be burned on location or placed in the reserve pit.
- F. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No adverse materials will be left on the location. Any open pits will be fenced during the drilling operation and the fencing will be maintained until such time as the pits are backfilled.
- G. The reserve and/or production pit will be constructed on the existing location and will not be located in natural drainages where a flood hazard exists or surface runoff will destroy or damage the pit walls. All pits will be constructed so as not to leak, break, or allow the discharge of liquids therefrom.

8. Ancillary Facilities:

None anticipated.

9. Wellsite Layout:

- A. Plat #1 shows the drill site layout as staked. Cross sections have been drafted to visualize the planned cuts and fills across the location. An average minimum of six (6) inches of topsoil will be stripped from the location (including areas of cut, fill, and/or subsoil storage) and stockpiled for future reclamation of the well site. Refer to Figure #1 for the location of the topsoil and subsoil stockpiles.
- B. Plat #2 is a diagram showing the rig layout. No permanent living facilities are planned. There may be as many as three (3) trailers on location during drilling operation.
- C. A completion rig will be moved onto location for completion operations after drilling operations have been completed and the drilling rig has been moved off location.
- D. A diagram showing the proposed production facility layout

is included in this APD.

- E. The reserve pit will be constructed so as to be capable of holding 20,000 bbls. of fluid.

The reserve pit will be lined with a 12 mil plastic liner, it will be torn and perforated after the pit dries and before backfilling of the reserve pit.

- F. Prior to the commencement of drilling operations, the reserve pit will be fenced on three (3) sides using 39-inch net wire with one strand of barbed wire on top of the net wire. The net wire will be no more than two inches above the ground. the barbed wire will be three inches above the net wire. total height of the fence will be at least 42-inches.

1. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
2. Standard steel, wood, or pipe posts shall be used between the corner braces. The maximum distance between any two (2) posts shall be no greater than sixteen (16) feet.
3. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The fourth side of the reserve pit will be fenced immediately upon removal of the drilling rig and the fencing will be maintained until the pit is backfilled.

- G. Any hydrocarbons on the pit will be removed from the pit as soon as possible after completion operations are completed.

10. Plans for Reclamation of the Surface:

The B.L.M. will be contacted prior to commencement of any reclamation operations.

A. Production

1. Immediately upon well completion, the well location and surrounding area(s) will be cleared of all debris, materials, trash and junk not required for production.
2. Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.

3. The plastic pit liner shall be torn and perforated before backfilling of the reserve pit.
4. Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed.

Other waste and spoil materials will be disposed of immediately upon completion of drilling and workover activities.

5. The reserve pit and that portion of the location and access road not needed for production facilities/operations will be reclaimed within one hundred twenty (120) days from the date of well completion, weather permitting.
6. If the well is a producer, Retamco Operating Company will, upgrade and maintain access roads as necessary to prevent soil erosion, and accommodate year round traffic. Reshape areas unnecessary to operations, distribute topsoil, disk and seed all disturbed areas outside the work area according to the recommended seed mixture. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

If the well is abandoned/dry hole, Retamco Operating Company will, restore the access road and location to approximately the original contours. During reclamation of the site, push the fill material into cuts and up over the backslope. Leave no depressions that will trap water or form ponds. Distribute topsoil evenly over the location, and seed according to the above seed mixture. The access road and location shall be ripped or disked prior to seeding. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

Seedbed will be prepared by disking, following the natural contours. Seed will be drilled on contours at a depth no greater than one-half inch (1/2"). In areas that cannot be drilled, seed will be broadcast at double the seeding rate and harrowed into soil. Certified seed will be used whenever available.

Fall seeding will be completed after September 15 and prior to prolonged ground frost. Spring seeding, to be effective, will be completed after the frost has left the ground and prior to May 15th.

7. Upon completion of backfilling, leveling and

recontouring, the stockpiled topsoil will be evenly spread over the reclaimed area(s). Prior to reseeding, all disturbed surfaces will be scarified and left with a rough surface. No depressions will be left that would trap water and form ponds. All disturbed surfaces will be reseeded with the seed mixture stipulated by the B.L.M.

Seed will be drilled on the contour to a approximate depth of one-half (1/2) inch. All seeding will be conducted after September 15 and prior to ground frost. Spring seeding will be done after the frost leaves the ground and no later than May 15. If the seeding is unsuccessful, Retamco Operating Company may be required to make subsequent seedings.

B. Dry Hole/Abandoned Location

1. On lands administered by the Bureau of Land Management, abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include:
 - (a) ensuring revegetation of the disturbed areas to the specifications of the Bureau of Land Management at the time of abandonment.
2. All disturbed surfaces will be recontoured to the approximate natural contours and reseeded according to BLM specifications. Reclamation of the well pad and access road will be performed as soon as practical after final abandonment and reseeding operations will be performed in the fall or spring following completion of reclamation operations.

11. Surface Ownership:

The well site and proposed access road are situated on surface lands administered by

Bureau of Land Management
Vernal District Office
Vernal, Utah

12. Other Information:

- A. Topographic and geologic features of the area (reference Topographic Map #A) are:

The proposed drill site is located in the Walker Hollow area, which lies in a large basin formed by the Uinta

Mountains to the North and the Bookcliff Mountains to the South. The site is located approximately 4.0 miles South of the Green River, which is the major drainage for this area, and approximately 5 miles Northwest of Red Wash Utah.

This basin floor is interlaced with numerous canyons and ridges formed by the non-perennial streams of the area. The sides of these canyons are steep and ledges formed in sandstone, conglomerate deposits and shale are common in this area.

The geologic structures that are visible in the area are of the Uinta formation (Eocene Epoch) tertiary period and the cobblestone and younger alluvial deposits from the Quaternary period.

The soils in the semi-arid area of the Williams Fork Formation (Upper Cretaceous) and Wasatch Formation (Eocene) consist of light brownish gray clay (OL) to sand soil (SM-ML) type with poorly graded gravels.

Outcrops of sandstone ledges, conglomerate deposits and shale are common in this area.

The topsoils in the area range from a sandy clay (SM-ML) type soil to a clayey (OL) soil.

The majority of the numerous washes and draws in the area are of a non-perennial nature flowing during the early spring run-off and heavy rain storms of long duration which are rare as the normal annual rainfall in the area is only 8".

The flora of the area includes sagebrush, mountain mahogany, serviceberry, rabbit brush, greasewood, four-wing saltbush, Gambel scrub oak, willow, tamarack, shadscale, Spanish bayonet, indian rice grass, cheatgrass, wheatgrass, curly grass, crested wheatgrass, sweet clover, gum weed, foxtail, mustard, Canadian thistle, Russian thistle, Kochia, sunflowers and cacti.

The fauna of the area includes cattle, horses, elk, deer, coyotes, rabbits, rodents, lizards, bull snakes, rattle snakes, water snakes and horned toads. Birds of the area are ground sparrows, bluejays, bluebirds, magpies, ravens, raptors, morning doves, swallows, nighthawks, hummingbirds, and chukar.

- B. The surface ownership is Federal. The surface use is grazing and petroleum production.

- C. 1. The closest live water is the Green River which is approximately 5.0 miles North of the proposed site.
2. There are no occupied dwellings in the immediate area
3. An archaeological report will be forwarded upon completion.
4. There are no reported restrictions or reservations noted on the oil and gas lease.

13. Lessee's or Operator's Representative:

Retamco Operating Company
671 Garnet
Billings, Montana 59105
(406)248-5594
FAX: (406)248-6068

Joe Glennon,

Home (406)248-5594

14. certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that any statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Retamco Operating Company, and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

9/15/98

Date

Joe Glennon

Joe Glennon

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 03/05/1999

API NO. ASSIGNED: 43-047-33310

WELL NAME: WALKER HALLOW 13-31
 OPERATOR: RETAMCO OPERATING INC (N6020)
 CONTACT: Joe Glennon (406) 248-5594

PROPOSED LOCATION: (TPR-SEC)
 SESW 31 - T06S - R23E
 SURFACE: 0523-FSL-1297-FWL
 BOTTOM: 0523-FSL-1297-FWL
 UINTAH COUNTY
 WALKER HOLLOW FIELD (700)

INSPECT LOCATN BY: / /		
TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: FED
 LEASE NUMBER: UTU-76280
 SURFACE OWNER: Federal

PROPOSED FORMATION: GRRV

RECEIVED AND/OR REVIEWED:


Plat
 Bond: Federal State[] Fee[]
 (No. UT-1088)
 Potash (Y/N)
 Oil Shale (Y/N) *190-5(B)
 Water Permit
 (No. 43-8290 Target Trucking)
 RDCC Review (Y/N)
 (Date: _____)
 Fee Surf Agreement (Y/N)

LOCATION AND SITING:

R649-2-3. Unit _____
 R649-3-2. General
 R649-3-3. Exception
 Drilling Unit
 Board Cause No: _____
 Date: _____

COMMENTS: _____

STIPULATIONS: ① FEDERAL Approval




Division of Oil, Gas & Mining

OPERATOR: RETAMCO OPERATING INC. (N6020)

FIELD: WALKER HOLLOW (700)

SEC. 31, TWP 6S, RNG 23E

COUNTY: UINTAH UNIT:



PREPARED
DATE: 15-MAR-1999



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Kathleen Clarke
Executive Director
Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

March 18, 1999

Retamco Operating, Inc.
HCR Box 1010
Roberts, Montana 59070

Re: Walker Hallow 13-31 Well, 523' FSL, 1297' FWL, SE SW, Sec. 31, T.6 S., R. 23 E.,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33310.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

John R. Baza
Associate Director

lwp

Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Retamco Operating, Inc.

Well Name & Number: Walker Hallow 13-31

API Number: 43-047-33310

Lease: Federal Surface Owner: Federal

Location: SE SW Sec. 31 T. 6 S. R. 23 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well. Contact Carol Daniels at (801)538-5284.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Dan Jarvis at (801) 538-5338 or Robert Krueger at (801) 538-5274.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval which must be obtained prior to drilling.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
 DRILL DEEPEN

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
 Retamco Operating Inc.

3. ADDRESS AND TELEPHONE NO.
 HCR Box 1010 Roberts, MT 59070

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
 At surface
 1297.4' FWL, 522.9' FSL of Sec. 31 T6S, R23E
 At proposed prod. zone
 Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
 7.4 miles West of Red Wash

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drilg. unit line, if any) 522.9'

16. NO. OF ACRES IN LEASE
 1,383.41

17. NO. OF ACRES ASSIGNED TO THIS WELL
 537.37

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.
 3,000'

19. PROPOSED DEPTH
 3,000'

20. ROTARY OR CABLE TOOLS
 Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
 5072.8' GR

22. APPROX. DATE WORK WILL START*
 4/1/99

5. LEASE DESIGNATION AND SERIAL NO.
 UTU 76280

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME, WELL NO.
 Walker Hallow 13-31

9. API WELL NO.
 43-047-33310

10. FIELD AND POOL, OR WILDCAT

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
 SESW 31 T6S, R23E

12. COUNTY OR PARISH
 Uintah

13. STATE
 Utah


23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/2"	8 5/8" K55	24#	200'	Cement to surface
7 7/8"	4 1/2" N80	11.6#	3000'	See page 1

Operator requests permission to drill the subject well and to change the name of well from the Gusher 13-31 to the Walker Hallow 13-31. Please see the attached 10 Point Drilling Program and 13 Point Surface Use Plan.

If you require additional information please contact:

Joe Glennon
 671 Garnet
 Billings, MT 59105
 406/248-5594



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Joe Glennon TITLE Joe Glennon, A-I-F DATE 9/15/98

(This space for Federal or State office use)

NOTICE OF APPROVAL CONDITIONS OF APPROVAL ATTACHED

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY Thomas B. Cleary TITLE Assistant Field Manager Mineral Resources DATE 6/4/99

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Retamco Operating Inc.
Well Name & Number: Walker Hallow 13-31
API Number: 43-047-33310
Lease Number: U - 76280
Location: SESW Sec. 31 T. 06S R. 23E

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

The operator is fully responsible for the actions of his All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a **3M** system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. One copy of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5(d) shall be submitted to the appropriate Field Office within 60 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (1).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted on initial meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Ed Forsman (435) 789-7077
Petroleum Engineer

Wayne P. Bankert (435) 789-4170
Petroleum Engineer

Jerry Kenczka (435) 781-1190
Petroleum Engineer

BLM FAX Machine (435) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

**SURFACE USE PROGRAM
Conditions of Approval (COA's)**

-Due to the presence of an occupied ferruginous hawk nest within 0.25 mile of proposed construction activity, no construction or drilling will be allowed from March 1 to July 15.

-All permanent (onsite for six months or longer) above the ground structures constructed or installed including pumping units, will be painted Carlsbad Canyon rather than the Desert Brown mentioned in the APD.

-The fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. A cattle guard with an adjacent 16 foot gate shall be installed. If the well is a producer, the cattle guard shall be permanently mounted on concrete bases.

-The topsoil shall be windrowed on the northeast end of the location and the reserve pit spoils shall be piled around the pit instead of as shown on the cut sheet. Seed the windrowed topsoil with the seed mixture listed below, immediately after windrowing, and work seed into the soil by track walking with a caterpillar type tractor.

Stockpile enough topsoil near the reserve pit so that when the reserve pit is reclaimed, it can be respread over the reserve pit location. When reclaiming the pit it shall be returned to natural contours, respread the topsoil over the pit, reseed with the seed mix listed below, then work the seed into the soil the in the same way mentioned above.

Recommended Seed Mixture:

Needle and Threadgrass
Fourwing Saltbush
Indian ricegrass
Shadscale

Stipa comata
Atriplex canescens
Oryzopsis hymenoides
Atriplex confertifolia

2 lbs/acre
4 lbs/acre
3 lbs/acre
3 lbs/acre

All poundages are in Pure Live Seed

This seed mixture shall also be used for final abandonment.

-Subsoil shall be used for the construction of tank dikes. **Topsoil is not to be used for dike construction.**

-The operator will control noxious weeds along rights-of-way for roads pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is require that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

-Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Vernal Field Office

170 South 500 East

Vernal, Utah 84078-2799

<http://www.blm.gov/utah/vernal>

Phone: (435) 781-4400

Fax: (435) 781-4410

IN REPLY REFER TO:

3160

UT08300

August 9, 2000

Retamco Operating Inc.
Attn: Joe Gannon
HCR Box 1010
Roberts, MT 59070

Re: Notification of Expiration
Well No. Walker Hallow 13-31
SESW, Section 31, T6S, R23E
Lease No. U-76280
Uintah County, Utah

Dear Mr. Gannon:

43-047-33310

The Application for Permit to Drill the above-referenced well was approved on June 15, 1999. Since that date, no known activity has transpired at the approved location. Applications for Permit to Drill are effective for a period of one year. In view of the foregoing, this office is notifying you the approval of the referenced application has expired. If you intend to drill at this location at a future date, a new Application for Permit to Drill must be submitted.

This office requires a letter confirming that no surface disturbance has been made for this drill site. Any surface disturbance associated with the approved location of this well is to be rehabilitated. A schedule for this rehabilitation must be submitted to this office. Your cooperation in this matter is appreciated.

Sincerely,

Margie Herrmann

Margie Herrmann
Legal Instruments Examiner

cc: State Div. OG&M

DOGm
'LA'
DATE →

RECEIVED

AUG 11 2000

DIVISION OF
OIL, GAS AND MINING