

NOTICE OF STAKING
 (Not to be used in place of
 Application to Drill Form 9-331-C)

RMOGA
 5/5/82

5. Lease Number
 U-01470-A

1. Oil Well Gas Well Other

6. If Indian, Allottee or Tribe Name

7. Unit Agreement Name
 River Bend Unit

2. Name of Operator
 CNG Producing Company

CONFIDENTIAL

8. Farm or Lease Name
 RBU

3. Address of Operator or Agent
 CNG Tower, 1450 Poydras Street, New Orleans, Louisiana 70112-6000

9. Well No.
 14-23F **43-047-33368**

4. Surface Location of Well
 (Government 1/4 or 1/4 1/4)

 SE, SW, Section 23 -T10S-R20E
 Attach: Topographical or other acceptable map
 showing location, access road, and lease boundaries.

10. Field or Wildcat Name
 Natural Buttes 630

11. Sec., T., R., M., or
 Blk and Survey or Area

 Sec. 23 -T10S-R20E

14. Formation Objective(s)
 Wasatch

15. Estimated Well Depth
 7,000' +/-


12. County or Parish
 Uintah

13. State
 Utah

16. To be completed by Operator Prior to Onsite
 a. Location must be staked
 b. Access Road Flagged
 c. Sketch and/or map of location, showing road, pad dimensions, reserve pit, cuts, and fills
 (To be provided at onsite)

17. To be Considered By Operators Prior to Onsite
 a. H2S Potential
 b. Private Surface Ownership
 c. Cultural Resources (Archaeology)
 d. Federal Right of Way

18. Additional Information



Signed Susan Sachitana Title Regulatory Reports Administrator
 Susan H. Sachitana

Date May 17, 1999

CNG Producing
Company

A CNG COMPANY

10/17/99
10/17/99
10/17/99
10/17/99

July 27, 1999

Mr. Wayne Bankart
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: Application for Permit to Drill
RBU 12-14E Sec. 12-T10S-R19E
RBU 5-18F Sec. 18-T10S-R20E
RBU 10-23F Sec. 23-T10S-R20E
RBU 14-23F Sec. 23-T10S-R20E

Dear Wayne:

Enclosed please find an original and two copies of the above referenced Applications for Permit to Drill for the above referenced wells.

CNG Producing Company is requesting that all well information be held strictly confidential.


Should you have any questions please feel free to contact either myself at (504) 593-7260 or our project engineer, David Linger at (281) 873-1561.

Sincerely,


Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Utah Board of Oil, Gas & Mining
David Linger
Nelda Decker
Mitch Hall



SELF-CERTIFICATION STATEMENT

CONFIDENTIAL

Self-certification statement. Under the Federal regulation in effect as of June 15, 1988 designation of operator forms are no longer required when the operator is not the 100% record title holder. An operator is now required to submit a self-certification statement to the appropriate Bureau office stating that said operator has the right to operate upon the leasehold premises. Said notification may be in the following format:

"Please be advised that CNG Producing Company is considered to be the operator of Well No. 14-23F SE 1/4 of SW 1/4 Section 23, Township 10S, Range 20E; Lease U-01470-A; Uintah County, Utah; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by American Casualty Company of Reading, PA, Bond #524 7050.

David L. Linger / s/l
David L. Linger
Onshore Drilling Manager

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPPLICATE*
(Other instructions on
reverse side)

APPROVED
1004-0136
July 28, 1999

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK
 DRILL DEEPEN **CONFIDENTIAL**

b. TYPE OF WELL
 OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
CNG PRODUCING COMPANY

3. ADDRESS AND TELEPHONE NO.
CNG TOWER - 1450 POYDRAS STREET, NEW ORLEANS, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements*.)
 At surface 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E *616, 835 E*
 At proposed prod. zone *4,420, 452 N*

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
10 MILES SW OF OURAY

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. line, if any) 793'

16. NO. OF ACRES IN LEASE 400

17. NO. OF ACRES ASSIGNED TO THIS WELL 80 ACRES

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT 1,800'

19. PROPOSED DEPTH 8,500'

20. ROTARY OR CABLE TOOLS ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.) 5,187'

22. APPROX. DATE WORK WILL START AUGUST 20, 1999

5. LEASE DESIGNATION AND SERIAL NO.
U-01470-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
RIVERBEND UNIT

8. FARM OR LEASE NAME WELL NO.
RBU 14-23F **CONFIDENTIAL**

9. API WELL NO.

10. FIELD AND POOL, OR WILDCAT
NATURAL BUTTES 630

11. SEC, T., R., M., OR BLK. AND SURVEY OR AREA
23-T10S-R20E

12. COUNTY OR PARISH UINTAH


13. STATE UTAH

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
17 1/2"	13 3/8"	54.5#	84'	
12 1/4"	8 5/8"	24#	3,000'	
7 7/8"	5 1/2"	17#	8,500'	

1. Drill a 17 1/2" hole to 84'. Run 13 3/8" 54.5 #/ft K-55 casing and cement to surface.
2. Drill a 12 1/4" hole with an air rig to 3,000', run 8 5/8", K-55 casing and cement to surface.
3. Nipple up and pressure test BOP stack prior to drilling out below surface pipe.
4. Operate pipe rams daily and blind rams as possible.
5. Drill a 7 7/8" hole to 8,500' with a KCL water mud system. Coring is possible. DST's will be run as needed to evaluate unexpected shows.
6. Run logs, set 5 1/2" 17# N-80 casing as dictated by drilling shows, tests, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
7. Primary zones of interests are the Wasatch, Chapita Wells and Uteland Buttes.
8. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.
9. In the event circulation is lost, air or air assisted mud will be utilized.

FORMATION TOPS	DEPTHS
Wasatch Tongue	3,925'
Green River Tongue	4,260'
Wasatch	4,402'
Chapita Wells	5,162'
Uteland Buttes	6,144'
Mesaverde	7,152'



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED David L. Linger / oh TITLE Onshore Drilling Manager DATE July 28, 1999
 David L. Linger

(This space for Federal or State office use)
 PERMIT NO. 43-047-333/68 OVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
 CONDITIONS OF APPROVAL, IF ANY:
BRADLEY G. HILL
RECLAMATION SPECIALIST III
 APPROVED BY [Signature] TITLE _____ DATE 8/20/99
 *See Instructions On Reverse Side


T10S, R20E, S.L.B.&M.

CNG PRODUCING CO.


Well location, RBU #14-23F, located as shown in the SE 1/4 SW 1/4 of Section 23, T10S, R20E, S.L.B.&M. Uintah County Utah.

BASIS OF ELEVATION

SPOT ELEVATION LOCATED IN THE NW 1/4 OF SECTION 26, T10S, R20E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN. NW. QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5187 FEET.



CONFIDENTIAL



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert McKay

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.


LATITUDE = 39°55'40"
LONGITUDE = 109°37'57"

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017


SCALE 1" = 1000'	DATE SURVEYED: 5-18-99	DATE DRAWN: 6-4-99
PARTY K.K. D.R. D.COX	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE CNG PRODUCING CO.	

BOP STACK

CONFIDENTIAL



CHOKER MANIFOLD



**DRILLING PLAN
APPROVAL OF OPERATIONS**

July 28, 1999

Attachment for Permit to Drill

Name of Operator: CNG PRODUCING COMPANY
Address: CNG TOWER - 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000

CONFIDENTIAL

WELL LOCATION: Well No. 14-23F

Uintah, Utah

1. **GEOLOGIC SURFACE FORMATION**

Uintah

2. **ESTIMATE IMPORTANT GEOLOGIC MARKERS**

Formation	Depth
Wasatch Tongue	3925'
Green River Tongue	4260'
Wasatch	4402'
Chapita Wells	5162'
Uteland Buttes	6144'
Mesaverde	7,152'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS**

Formation	Depth	Remarks
Wasatch Tongue	3925'	Oil Zone
Green River Tongue	4260'	Oil Zone
Wasatch	4402'	Gas Zone
Chapita Wells	5162'	Gas Zone
Uteland Buttes	6144'	Gas Zone
Mesaverde	7152'	Gas Zone

4. **PROPOSED CASING PROGRAM**

All casing used to drill this well will be new casing.
13 3/8", 54.5 #/ft K-55 - 0' - 84' - Cemented to Surface
8-5/8", 24#/ft, K-55, STL (Thread type) 0'-3000' - Cemented to Surface
5 1/2", 17#/ft, N-80, LTC (Thread type) 0'- 8500' - Cemented to Surface

5. **OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL**

BOP stack has a 3000 PSI working pressure. BOP will be pressure tested to 3,000 PSI before drilling casing cement plug. Pipe rams will be operated daily and blind rams as possible.

6. The well is to be drilled with a KCL mud system maintaining a weight of approximately 9 - 9.7#/gal.
7. An automatic ignitor will not be installed on the blooie line.
8. A 90° bend on the blooie line, located approximately 50' from the wellhead on the pit side past the mud tank will be installed. Total length of the blooie line will remain 100' from the wellhead.

9. **AUXILIARY EQUIPMENT TO BE USED**

CONFIDENTIAL

1. Kelly Cock.
2. Full opening valve on floor with DRILL PIPE connection for use when Kelly is not in string.

10. **TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED**

Possible DST in Wasatch Tongue. The logging program will include Dual Lateral/GR log TD to Surface, Density/Neutron, TD - 3,500' possible dipmeter and rotary cores over selected intervals.

11. **ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED**

No normal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H₂S gas. The anticipated bottom hole pressure is 2,610 PSI.

12. **WATER SUPPLY**

- A. Water to be used for drilling will be hauled Section 32-T6S-R20E. User's Claim - Code #43, Serial #9077.
- B. No pipelines are anticipated. Hauling will be on the road(s) shown in Attachment No. 3.
- C. No water well is anticipated to be drilled at this time.

13. **CEMENT SYSTEMS**

CONDUCTOR

Ready-mix cement to surface.

SURFACE

Tail Slurry: +/-250 sks Class "G" cement, 2% CaCl₂, and .25#/sk flake. Mixed at 15.8 ppg. Yield 1.16 ft³/sk, water 4.96 gal/sk.

Lead Slurry: +/-600 sk 28:72 Poz and 10% gel + 6 lb/sk KOL seal + 3 lb/sk CSE + .5% SM + .25 lb Flake mixed at 11.0 lb/gel yield - 3.37 ft³/sk, excess 100%.

PRODUCTION

Lead Slurry: +/-350 sk 28:72 Poz and 10% gel + 6 lb/sk KOL seal + 3 lb/sk CSE + .5% SM + .25 lb Flake mixed at 11.0 lb/gel yield - 3.37 ft³/sk.

Tail Slurry: +/-770 sk Class G, 10% gypsum, 3% Salt, .2% retarder mixed at 14.8 ppg, yield - 1.47 ft³/sk water - 6.93 gal/sk

14. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS**

Starting Date: August 20, 1999
Duration: 20 Days

CONFIDENTIAL

SURFACE CASING CEMENT PROGRAM

Set 8 5/8" casing in 12 1/4" open hole cement to surface. Volume calculated using 75% excess.

SPACER:

Pump 20 bbls lightly gelled water followed by 5 bbls fresh H₂O ahead of cement to water wet the well bore after air drilling. Displace with fresh water.

CEMENT SYSTEM

± 500 SKS Lead Cement 28:72 Poz (28% Poz: 72% Class C) + 10% gel + 6 lb/sk KOL seal + 3 lb/sk CSE + .5% SM + .25 lb/sk Cello Flake

Weight	11.0 lb/gal
Yield	3.37 ft ³ /sk
Water	20.48 gal/sk
Thickening Time at 118°	5+ hours
Compressive Strength at 80°	24 hrs 375 PSI

± 250 SKS Class G "Tail-In" Cement, 2% CaCl₂, .25#/sk Celloflake.

Weight	15.80 lb/gal
Yield	1.17 ft ³ /sk
Water	4.99 gal/sk
Thickening Time at 118°	1:42 minutes
Compressive Strength at 80°	8 hrs 750 PSI 16 hrs 1800 PSI 24 hrs 2400 PSI

± 100 - 200 sks Top-out cement, 2% CaCl₂, .25#/sk Celloflake

Run 1" tubing in annulus to ± 200' and cement to surface.

CASING HARDWARE:

1 Cement Guide Shoe
1 Insert Float
3 Centralizers
1 Stop Ring
1 Thread Lock
1 Top Wood Plug

LONGSTRING CEMENT

Set 5 1/2" casing in a 7 7/8" open hole.
Lease cement slurry to fill from 750' above top pay zone to surface.
Tail cement slurry to fill from TD to 750' above the pay zone.
Both volumes are calculated using 25% excess.

CONFIDENTIAL

SPACER:

(KCL Mud System) 10 bbl water

Displace with 3% KCL water using .2% L-55 Clay Stabilizer in the first 50 bbls of displacement.

CEMENT SYSTEMS

Lead Slurry

± 350 sks Hi-Lift, 3% Salt, 10#/sk silsonite, .25#/sk Celloflake.

Weight	11.00 lb/gal
Yield	3.42 ft ³ /sk
Water	21.07 gal/sk

Thickening Time at 180°	4 hrs +
Compressive Strengths in 24 hrs	375 PSI
Fluid Loss	240 cc/30 minutes

Tail Slurry

± 700 sks Class G, 10% gypsum, 3% Salt, .2% retarder

Weight	14.8 lb/gal
Yield	1.47 ft ³ /sk
Water	6.93 gal/sk

Thickening Time at 165° BHCT	
Compressive Strength in 12 hrs	845 PSI
24 hrs	1470 PSI

Revised November 1990

Date NOS Received: _____

**CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL**

CONFIDENTIAL

Company/Operator: CNG Producing Company

Well Name & Number: RBU 14-23F

Lease Number: U-01470-A

Location: SE SW Sec. 23 T. 10S R. 20E

Surface Ownership: Bureau of Land Management

NOTIFICATION REQUIREMENTS

- Location Construction - forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related - twenty-four (24) hours prior to initiating pressure Equipment Tests tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

B. **THIRTEEN POINT SURFACE USE PROGRAM:**

CONFIDENTIAL

Multipoint Requirement to Accompany APD

1. **Existing Roads** - describe the following and provide a legible map, labeled and showing:
 - a. Proposed wellsite as staked and access route to location, including distances from point where access route exists establish roads. (Actual staking should include tow directional reference stakes.) The proposed well site is located approximately 44 miles southwest of Vernal, Utah.
 - b. Route and distance from nearest town or locatable reference point, such as a highway or county road, to where well access route leaves main road. - From Vernal proceed West on Highway 40 about 17 miles to Highway 88. Turn left on Highway 88 and proceed South about 16 miles to Ouray. Continue South on Sea Ridge Road about 12.7 miles and turn right. go one mile to access road on right.
 - c. Access road(s) to location color-coded or labeled. (See Topographic Map A & B for details.)
 - d. Plans for improvement and/or maintenance of existing roads. (Appropriate rights-of-way for off lease roads should be attached.)

2. **Planned Access Roads**--describe the following and provide a map of suitable scale indicating all necessary access roads (permanent and temporary) to be constructed or reconstructed, showing:
 - a. Length - Existing road
 - b. Width - 30 foot right-of-way with 18 foot running surface maximum.
 - c. Maximum grades - 8%
 - d. Turnouts - None
 - e. Drainage design - Bore pit
 - f. Location and size of culverts and/or bridges, and brief description of any major cuts and fills - None
 - g. Surfacing material (source) - Native
 - h. Necessary gates, cattleguards, or fence cuts and/or modification to existing facilities - None

(New or reconstructed roads are to be centerline-flagged at time of location staking.)

All travel will be confined to existing access road rights-of-way.

Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather

road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

_ Right-of-Way Application needed.

CONFIDENTIAL

___ The operator/lessee or his/her successor shall be responsible for all maintenance on cattleguards or gates associated with this oil and/or gas operation.

3. Location of Existing Wells - describe the following and provide a map or plat of all wells within a 1 mile radius of the proposed well location showing and identifying existing:

- a. Water wells - None
- b. Abandoned wells - RBU 15-23F
- c. Temporarily abandoned wells - None
- d. Disposal wells - None
- e. Drilling wells - None
- f. Producing wells - RBU 2-23F, RBU 4-23F, RBU 6-23F, RBU 12-23F, RBU 8-22F, RBU 10-22F, RBU 16-22F, NBU #71, NBU #43,
- g. Shut-in wells - None
- h. Injection wells - None

4. Location of Existing and/or Proposed Facilities

a. On well pad: Show the following existing area facilities and dimensions to be utilized if the well is successfully completed for production (detail painting plans and color if applicable):

- (1) Tank batteries
- (2) Production facilities
- (3) Oil gathering lines
- (4) Gas gathering lines
- (5) Injection lines
- (6) Disposal lines
- (7) Surface pits - After the well is hydraulically fraced, the well will be flowed back into the surface pits. After first production, a 300 bbl tank will be installed to contain produced waste water. Plans are to run a 2" line from the separator to the 300 bbl tank.

(Indicate if any of the above lines are buried.)

b. Off well pad: Same as above. Off lease flowlines may require rights-of-way or special use permits, check with the District Office Realty Specialist. (Include a diagram of the proposed attendant lines, i.e., flowlines, powerlines, etc., if off well pad location.)

- (1) Proposed location and attendant lines shall be flagged off of well pad prior to archaeological clearance.
- (2) Dimensions of facilities
- (3) Construction methods and materials
- (4) Protective measures and devices to protect livestock and wildlife

CONFIDENTIAL

Note: Operator has option of submitting information under 4A and B, after well is completed for production, by applying for approval of subsequent operations.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

Tank batteries will be placed on the Northwest stake #4

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Desert Brown

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

5. Location and Type of Water Supply

- a. Show location and type of water supply, either by 1/4, 1/4 section on a map or by written description Sec 32-T6S-R20E No. 43-9077
- b. State method of transporting water, and show any roads or pipelines needed.
- c. If water well is to be drilled on lease, so state. _____*The operator will be responsible for acquiring the necessary permit to obtain water to be used for drilling activities.

6. Source of Construction Materials

- a. Show information either on map or by written description - Surface and subsoil materials in the immediate area will be utilized to build the location

b. Identify if from Federal or Indian (tribal or allotted) land. The use of materials under BLM jurisdiction will conform with 43 CFR 3610.2.3. Construction material will not be located on lease.

CONFIDENTIAL

c. Describe where materials such as sand, gravel, stone, and soil material are to be obtained and used. No construction materials will be removed from Federal land.

*If fill materials are needed to construct roads or well sites, proper permits must be obtained from the Surface Management Agency, unless materials are obtained from a private source.

*A mineral materials application (is/is not) required.

7. Methods of Handling Waste Disposal

a. Describe methods and location of proposed safe containment and disposal of each type of waste material, including:

- (1) Cuttings - bury in pit
- (2) Sewage - haul to sewer lagoon
- (3) Garbage (trash) and other waste material - haul to disposal
- (4) Salts - not used
- (5) Chemicals - non-toxic only; evaporate in pit

After first production, produced waste water will be confined to an unlined or lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with Onshore Order No. 7, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

b. Provide a plan for eventual disposal of drilling fluids and any produced oil or water recovered during testing operations. evaporate in pit

After initial clean up period, a 300 bbls tank will be installed to contain produced waste water. This water will be transported from the 300 bbl tank to CNG disposal well located at RBU 16-19F for disposal.

*Burning will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

c. No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of wells with the NBU. Furthermore, extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will not be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of wells within the NBU. Specific APDs shall address any modifications from this policy.

On BLM administered lands:

The reserve pit shall be constructed so as not to leak, break, or allow discharge.

The reserve pit shall be lined with a 12 mil pit liner only under the following conditions:

1. If we have to blast the pit, or
2. If the non-blasted pit will not hold fluid.

If these conditions do not exist, we will not line the pit.

CONFIDENTIAL

If a plastic nylon reinforced liner is used, it will be a minimum of 12 mil in thickness.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. Ancillary Facilities

Camp facilities or airstrips will not be allowed unless otherwise approved.

9. Well Site Layout--provide a plat (not less than 1" = 50') showing:

- a. Cross-sections of proposed drill pad with approximate cuts and fills and the relation to topography.
- b. Location of mud tanks, reserve, and flare pits, pipe racks, living facilities, and soil material stockpiles, etc. (Approval as used in this section means field approval of location.)
- c. Rig orientation, parking areas, and access roads, etc.

The reserve pit will be located on the: Northwest stakes #4 & #5

The flare pit will be located downwind of the prevailing wind direction on the right of the reserve pit a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil (first four inches) will be stored on the: Southwest stake #1 and #2

Access to the well pad will be from the: existing road

___ Diversion ditch(es) shall be constructed on the _____ side of the location (above / below) the cut slope, draining to the _____.

___ Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____.

___ The drainage(s) shall be diverted around the _____ side(s) of the well pad location.

___ The reserve pit and/or pad location shall be constructed long and narrow for topographic reasons _____.

___ The _____ corners of the well pad will be rounded off to avoid _____.

Fencing Requirements

CONFIDENTIAL

All pits will be fenced according to the following minimum standards:

- a. 39-inch net wire shall be used with at least one stand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- b. The net wire shall be no more than 2-inches above the ground. The barbed wire shall be 3-inches above the net wire. Total height of the fence shall be at least 42-inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly traveled. If the well is a producer, the cattleguard (shall/shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. Plans for Restoration of Surface

a. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 6 months from the date of well completion. Before any dirt work takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc., will be removed.

Contact appropriate surface management agency for required seed mixture.

b. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

11. Surface Ownership:

CONFIDENTIAL

Access Road: Bureau of Land Management Location: Bureau of Land Management

"If the access road and/or location involves private or state agency owned surface, a copy of the surface owners agreement is required prior to approval of the APD."

12. Other Additional Information

a. The Operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to :

-whether the materials appear eligible for the National Register of Historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible to mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

b. The operator will control noxious weeds along right-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

c. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

d. A 2" pipeline is proposed to run approximately 225' and run parallel to the access road until it ties into the main gathering system.

Additional Surface Stipulations

CONFIDENTIAL

- ___ No construction or drilling activities shall be conducted between _____ and _____ because of _____
- ___ No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.
- ___ No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.
- ___ There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).
- ___ No cottonwood trees will be removed or damaged.
- ___ A silt catchment dam and basin will be constructed according to BLM specifications, where flagged.
- ___ _____
- ___ _____
- ___ _____

13. Lessee's or Operators Representative and Certification

Representative

Name: _____

Address: _____

Phone No: _____

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

CONFIDENTIAL

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and, that the work associated with the operations proposed here will be performed by CNG Producing Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

July 28, 1999 David L. Linger David L. Linger, Onshore Drilling Manager
Date Name and Title

Onsite Date: July 21, 1999

Participants on Joint Inspection

<u>Robert Kay</u>	<u>Uintah Basin Engineer</u>
<u>Tony Pummel</u>	<u>Ponderosa Construction</u>
<u>Randy Jackson</u>	<u>Jackson Construction</u>
<u>Greg Darlington</u>	<u>Bureau of Land Management</u>
<u>Greg Overmiller</u>	<u>Greg Construction</u>
<u>Mitch Hall</u>	<u>CNG Producing Company</u>

CNG PRODUCING CO.


LOCATION LAYOUT FOR

RBU #14-23F


SECTION 23, T10S, R20E, S.L.B.&M.

793' FSL 2405' FWL

Handwritten signature



SCALE: 1" = 50'
DATE: 6-3-99
Drawn By: D.COX



Elev. Ungraded Ground at Location Stake = 5186.6'
 Elev. Graded Ground at Location Stake = 5184.9'





UINTAH ENGINEERING & LAND SURVEYING
 85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

CNG PRODUCING CO.
TYPICAL CROSS SECTIONS FOR
RBU #14-23F
SECTION 23, T10S, R20E, S.L.B.&M.
793' FSL 2405' FWL

1" = 20'
 X-Section Scale
 1" = 50'

DATE: 6-3-99
 Drawn By: D.COX

Handwritten signature




APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,090 Cu. Yds.
Remaining Location	= 3,670 Cu. Yds.
TOTAL CUT	= 4,760 CU.YDS.
FILL	= 2,020 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	= 2,630 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 2,620 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 10 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
 85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



LEGEND:

○ PROPOSED LOCATION



CNG PRODUCING CO.

RBU #14-23F
SECTION 23, T10S, R20E, S.L.B.&M.
793' FSL 2405' FWL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

6 3 99
 MONTH DAY YEAR

SCALE: 1: 100,000 | DRAWN BY: C.G. | REVISED: 00-00-00



T10S

Black Bridge

OURRY 127 MI. 41-

PROPOSED ROAD RE-ROUTE

PROPOSED LOCATION:
RBU #14-23F

R
20
E

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING ROAD



CNG PRODUCING CO.

RBU #14-23F
SECTION 23, T10S, R20E, S.L.B.&M.
793' FSL 2405' FWL




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

7	0	0	0
MONTH	DAY	YEAR	
SCALE: 1" = 200'		DRAWN BY: C.G. [REVISED: 00-00-00]	

B
TOPO

T10S



PROPOSED LOCATION:
RBU #14-23F

R
20
E

LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- ⬮ SHUT IN WELLS
- ⊗ WATER WELLS
- ⬮ ABANDONED WELLS
- ⬮ TEMPORARILY ABANDONED

CNG PRODUCING CO.

RBU #14-23F
SECTION 23, T10S, R20E, S.L.B.&M.
793' FSL 2405' FWL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

SCALE: 1" = 2000' DRAWN BY: C.G. REVISED: 00-00-00



T10S



R
20
E

APPROXIMATE TOTAL PIPELINE DISTANCE = 1.600' --

LEGEND:

- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED ACCESS

CNG PRODUCING CO.

RBU #14-23F
SECTION 23, T10S, R20E, S.L.B.&M.
793' FSL 2405' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC MAP
 MONTH: 6 DAY: 3 YEAR: 99
 SCALE: 1" = 1000' DRAWN BY: C.G. REVISED: 00-00-00

D
TOPO



LEGEND	
O	= Oil Line
G	= Gas Line
W	= Water Line
R	= Relief Line (Pressure)
C	= Condensate Line
V	= Vent Line
D	= Drain Line
M	= Gas Meter
P	= Pump
BP	= Back Pressure Valve
SWS	= Sealed When Shipping
SUS	= Sealed Unless Shipping
T	= Heat Traced Line
H	= Heater
BL	= Buried Line
⋈	= Valve
↗	= Check Valve
SC	= Sealed Closed Valve
NC	= Normally Closed
BD	= Blowdown Line



The site security plan is on file in CNGP's district office located at 1400 N. State St., Roosevelt, Utah. It can be inspected during office hours, from 6:30 AM thru 3:30 PM, Monday thru Friday..


CNG PRODUCING COMPANY		
Well: RBU 14-23F	RIVER BEND FIELD, UINTA COUNTY	not to scale
SDR/RBU FLOW/SEP	TYPICAL FLOW DIAGRAM	date: 7 /28/99.

**CNG PRODUCING COMPANY
RIVER BEND UNIT
UNTAH COUNTY, UTAH
PARTICIPATING AREAS LAND PLAT**

LEGEND

- INDIAN RESERVATION BOUNDARY
- PARTICIPATING AREAS A & B
- [Hatched Box] INDIAN LAND
- [Diagonal Line Box] STATE LAND

FILE UTRBL.PLT



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 07/28/1999

API NO. ASSIGNED: 43-047-33368

WELL NAME: RBU 14-23F
 OPERATOR: CNG PRODUCING COMPANY (N0605)
 CONTACT: Sue Sachitane (504) 593-7260

PROPOSED LOCATION:
 SESW 23 - T10S - R20E
 SURFACE: 0793-FSL-2405-FWL
 BOTTOM: 0793-FSL-2405-FWL
 UINTAH COUNTY
 NATURAL BUTTES FIELD ()

INSPECT LOCATN BY: / /		
TECH REVIEW	Initials	Date
Engineering	<i>RSK</i>	8-19-99
Geology		
Surface		

o.i.
shale
Only.

LEASE TYPE: FED
 LEASE NUMBER: U-01470-A
 SURFACE OWNER: Federal

PROPOSED FORMATION: WSTC

<p>RECEIVED AND/OR REVIEWED:</p> <p><input checked="" type="checkbox"/> Plat</p> <p><input checked="" type="checkbox"/> Bond: Fed <input checked="" type="checkbox"/> Ind[] Sta[] Fee[] (No. # <u>5247050</u>)</p> <p><input type="checkbox"/> Potash (Y/N)</p> <p><input checked="" type="checkbox"/> Oil Shale (Y/N) *190-5(B)</p> <p><input checked="" type="checkbox"/> Water Permit (No. <u>43-9077</u>)</p> <p><input type="checkbox"/> RDCC Review (Y/N) (Date: _____)</p> <p><input type="checkbox"/> Fee Surf Agreement (Y/N)</p>	<p>LOCATION AND SITING:</p> <p>___ R649-2-3. Unit <u>River Bend</u></p> <p>___ R649-3-2. General</p> <p><input checked="" type="checkbox"/> R649-3-3. Exception</p> <p>___ Drilling Unit Board Cause No: _____ Date: _____</p> <p>___ R649-3-11. Directional Drill</p>
---	--

COMMENTS: Need add'l info "Ex. Loc." (Rec'd 8-6-99)

STIPULATIONS: ① In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rule R649-3-31 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. For the proposed well this interval is approximately 3,410 ' to 3,485 ' below GL. The Operator shall report the actual depth the oil shale is encountered to the Division.

② FEDERAL APPROVAL

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

<date>

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 1999 Plan of Development River Bend Unit Uintah County, Utah.

Pursuant to email between Lisha Cordova, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management. The following wells are planned for calendar year 1999 within the River Bend Unit, Uintah County, Utah.


API #	WELL NAME	LOCATION
43-047-33360	RBU 1-16F	0547-FNL 0969-FEL 16 10S 20E
43-047-33361	RBU 5-3F	2127-FNL 0645-FWL 03 10S 20E
43-047-33362	RBU 15-10F	1013-FSL 1776-FEL 10 10S 20E
43-047-33363	RBU 5-16F	2095-FNL 0914-FWL 16 10S 20E
43-047-33365	RBU 12-14E	2213-FSL 0203-FWL 14 10S 19E
43-047-33366	RBU 5-18F	1855-FNL 1406-FWL 18 10S 20E
43-047-33367	RBU 10-23F	2483-FSL 1951-FEL 23 10S 20E
43-047-33368	RBU 14-23F	0793-FSL 2405-FWL 23 10S 20E

This office has no objection to permitting the well(s) at this time.

/s/ Michael L. Coulthard

bcc: File - River Bend Unit
Division of Oil Gas and Mining
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:<date>-<date>-<date>




**CNG Producing
Company**

A **CNG** COMPANY

1100 North
11th Street
Salt Lake City, UT 84111-1000
(801) 438-2200

August 3, 1999

Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801



ATTN: Lisha

RE: Well Spacing Exception Locations

RBU 15-10F	Sec. 10-T10S-R20E	RBU 5-16F	Sec. 16-T10S-R20E
RBU 12-14E	Sec. 14-T10S-R19E	RBU 10-23F	Sec. 23-T10S-R20E
RBU 1-16F	Sec. 16-T10S-R20E	RBU 14-23F	Sec. 23-T10S-R20E

Dear Lisha:

CNG Producing Company would like to apply for a spacing exception for the above referenced locations due to topography. In accordance with Rule 649-3-2 enclosed is a vicinity map of our Riverbend Unit with a 460' radius circled around each of these wells.

The Bureau of Land Management is the surface owner for all of these wells except for RBU 1-16F which the Ute Tribe is surface owner. CNG Producing Company is the operator of the area within the 460' radius surrounding these wells. None of these wells are closer to another well by 920'.

If you have any questions or need any additional information to process this exception, please contact me at (504) 593-7260.

Sincerely,

CNG PRODUCING COMPANY

Susan H. Sachitana
Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Wayne Bankart - BLM
Tomasina Appah - BIA
Nelda Decker
David Linger
Mitch Hall
Well History Files



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Kathleen Clarke
Executive Director
Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

August 20, 1999

CNG Producing Company
CNG Tower
1450 Poydras Street
New Orleans, Louisiana 70112-6000

Re: RBV 14-23F Well, 793' FSL, 2405' FWL, SE SW, Sec. 23, T. 10 S., R. 20 E., Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM by the operator and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33368.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

John R. Baza
Associate Director

lwp

Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: CNG Producing Company
Well Name & Number: RBU 14-23F
API Number: 43-047-33368
Lease: Federal **Surface Owner:** Federal
Location: SE SW **Sec.** 23 **T.** 10 S. **R.** 20 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well. Contact Carol Daniels at (801)538-5284.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Dan Jarvis at (801) 538-5338 or Robert Krueger at (801) 538-5274.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval which must be obtained prior to drilling.

5. In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rule R649-3-31 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. For the proposed well this interval is approximately 3410' to 3485' below GL. The operator shall report the actual depth the oil shale is encountered to the Division.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE*
(Other instructions on
reverse side)

APPROVED
1004-0136
July 28, 1995

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK

DRILL DEEPEN

b. TYPE OF WELL

OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR

CNG PRODUCING COMPANY

3. ADDRESS AND TELEPHONE NO.

CNG TOWER - 1450 POYDRAS STREET, NEW ORLEANS, LA 70112-0000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

At surface 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E

At proposed prod. zone

5. LEASE DESIGNATION AND SERIAL NO.

U-01470-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

RIVERBEND UNIT

8. FARM OR LEASE NAME WELL NO.

RBU 14-23F

9. API WELL NO.

CONFIDENTIAL

10. FIELD AND POOL, OR WILDCAT

NATURAL BUTTES 630

11. SEC. T., R., M., OR BLK. AND SURVEY OR AREA

23-T10S-R20E

12. COUNTY OR PARISH

UINTAH

13. STATE

UTAH

15. DISTANCE FROM PROPOSED LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT.

(Also to nearest drlg. line, if any) 793'

16. NO. OF ACRES IN LEASE

400

17. NO. OF ACRES ASSIGNED TO THIS WELL

80 ACRES

18. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.

1,800'

19. PROPOSED DEPTH

8,500'

20. ROTARY OR CABLE TOOLS

ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5,187'

22. APPROX. DATE WORK WILL START

AUGUST 20, 1999


23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
17 1/2"	13 3/8"	54.5#	84'	
12 1/4"	8 5/8"	24#	3,000'	
7 7/8"	5 1/2"	17#	8,500'	

1. Drill a 17 1/2" hole to 84'. Run 13 3/8" 54.5 #/ft K-55 casing and cement to surface.
2. Drill a 12 1/4" hole with an air rig to 3,000', run 8 5/8", K-55 casing and cement to surface.
3. Nipple up and pressure test BOP stack prior to drilling out below surface pipe.
4. Operate pipe rams daily and blind rams as possible.
5. Drill a 7 7/8" hole to 8,500' with a KCL water mud system. Coring is possible. DST's will be run as needed to evaluate unexpected shows.
6. Run logs, set 5 1/2" 17# N-80 casing as dictated by drilling shows, tests, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
7. Primary zones of interests are the Wasatch, Chapita Wells and Uteland Buttes.
8. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.
9. In the event circulation is lost, air or air assisted mud will be utilized.

CONFIDENTIAL

FORMATION TOPS	DEPTHS
Wasatch Tongue	3,925'
Green River Tongue	4,260'
Wasatch	4,402'
Chapita Wells	5,162'
Uteland Buttes	6,144'
Mesaverde	7,152'



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED David L. Linger / sbs TITLE Onshore Drilling Manager

DATE July 28, 1999

(This space for Federal or State office use)

PERMIT NO. **NOTICE OF APPROVAL** OVAL DATE _____

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY [Signature]

Assistant Field Manager
Mineral Resources

DATE 11/2/99

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

OPERATIONS COPY

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: CNG Producing Company

Well Name & Number: RBU 14-23F

API Number: 43-047-33368

Lease Number: U-01470-A

Location: SESW Sec. 23 T. 10S R. 20E

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative by the operator to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report **ALL** water shows and water-bearing sands to Tim Ingwell of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 3M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

If conductor pipe is set it will be cemented to surface. If drive pipe is used it will be pulled prior to cementing surface casing.

As a minimum, the usable water shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the shallowest potential productive zone. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

The Gamma Ray and Induction Logs need to be pulled from TD to the Surface Shoe.

A cement bond log (CBL) will be run from the production casing shoe to **Top of Cement** and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. **One** copy of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours **prior** to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.), and shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted following initial installation and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approval or notification is necessary, please contact one of the following individuals:

Wayne Bankert Petroleum Engineer	(801) 789-4170
Ed Forsman Petroleum Engineer	(801) 789-7077
Jerry Kenczka Petroleum Engineer	(801) 789-1190
BLM FAX Machine	(801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

SURFACE CONDITIONS OF APPROVAL

Thirty (30) foot wide Rights-Of-Way (ROWs) corridor shall be granted for the following:

Access roads which shall have constructed travel width limited to 18 feet, except as needed for sharp curves or intersections or where deep cuts are required for road construction. The new access will be about 200 feet in length and will be routed through the proposed pad. The surface flowline planned for this location will be in a corridor shared with the existing access road to producing well 12-23F. It will be about 1600 feet in length. CNG has provided a map for the APD showing this route for the flowline.

Surface pipelines will be constructed to lay on the soil surface, and the ROW for the pipeline will not be bladed or cleared of vegetation. The line shall either be constructed on the road and then lifted from the road to its intended location paralleling the road, or it shall be welded in place at a welding station at the wellsite or on the access road and then dragged into place with a suitable piece of equipment so it will not destroy the natural vegetation.

CNG has been informed that the area has been identified as crucial pronghorn (antelope) habitat. Construction and drilling activities would not be conducted during the season May 15 through June 20. This would allow CNG to avoid construction during the antelope kidding season and be consistent with our RMP Lease Notice for pronghorn.

Topsoil will be stockpiled as shown in the layout diagram. Topsoil from the reserve pit may be stockpiled adjacent to the pit waste material so that it can easily be respread over the pit after the pit is filled in.. The pit will be reclaimed within six months from the date of well completion.. At the time when the reserve pit is reclaimed, topsoil from the reserve pit should be respread over it and reseeded as per the recommended seed mixture. The reserve pit is in cut material at this location. The pit should be filled in then recontoured to blend in with the original contours. The topsoil from the reserve pit area should be spread over the reserve pit prior to the reseeding with the recommended seed mixture.

Recommended Seed Mixture:

Nuttalls saltbush	Atriplex nuttalli v.cuneata	3 lbs./acre
Fourwing Saltbush	Atriplex canescens	4 lbs./acre
Shadscale	Atriplex confertifolia	3 lbs./acre
Squirreltail	Sitanion hystrix	2 lbs./acre

All poundages are Pure Live Seed. This seed mixture is to be used when the reserve pit is reclaimed and also is recommended for final abandonment reseeding.

Before the site is abandoned, the company will be required to restore the well site and new access road to near their original state. The disturbed areas will be reseeded with desirable perennial vegetation.

Noxious weeds will be controlled on the well site and rights-of-way. If noxious weeds spread from the project area onto adjoining land, the company will also be responsible for their control.

Reserve pits will be lined with impervious synthetic liners if pit construction requires blasting or if the nonblasted pit leaks and will not hold fluid. If a plastic liner is used, it will be a minimum of 12 mil in thickness. Liners will be constructed to lay under the mud tanks, and they will be reinforced to prevent the liner from developing holes where fluids flow from the mud tank into the reserve pit. Prior to backfilling the reserve pit all fluids will be pumped from the pit into trucks and hauled to approved disposal sites. When the pits are backfilled, the surplus oil and mud etc. will be buried a minimum depth of 3.0 feet below the surface of the soil.

The flare pit will be adjacent to the reserve pit.

A closed production system will be used after the 90 day testing period mentioned in the APD.. After First Production is established a 300 bbl tank will be installed and Production fluids will be contained in this tank. All production fluids will be disposed of at approved disposal sites. The indiscriminate dumping of production fluids on roads, wellsites or other areas will not be allowed.

The following applies to related pipeline construction for the well:(see APD map)

1. No blading will be allowed on surface pipelines unless the Vernal Field Office minerals staff are consulted and approval has been obtained prior to the blading.
2. Greg Darlington of the Vernal Office Minerals Staff will be notified 24 hours prior to the start of construction.
3. Surface lines will be either black or brown in color. If the line is insulated then the color of the pipeline should be similar to the color of the well pad facilities in the vicinity.
4. Pipeline construction will not occur during periods of wet soil conditions.
5. The surface gas line shall not block or change the course of existing drainages. Drainage crossings will be designed to prevent damage to the flowline during periods of high seasonal and storm runoff.
6. If cultural resources are found during construction, all work which could impact these resources will stop and the Vernal Field Office will be notified.
7. Vehicle use will be restricted to the pipeline route in off road areas. It will be authorized there as needed for construction and maintenance and operations on the lease.
8. The metering of all gas production will be done in accordance with Onshore Order No. 5.

RECEIVED

OPERATOR CNG PRODUCING COMPANY OPERATOR ACCT. NO. N0605

ENTITY ACTION FORM - FORM 6

DEC 10 1999

ADDRESS CNG TOWER - 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000

DIVISION OF OIL, GAS & MINING

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	7050	43-047-33368	RBU #14-23F	SE SW	23	10S	20	UINTAH	12/02/99	
WELL 1 COMMENTS: <i>091220 entity added; (Riverbend u/NSMVD A-B) RBR</i> CONFIDENTIAL Well within the Riverbend Unit.											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instruction on back of form)

- A - establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

Susan H. Sachitana

Signature Susan H. Sachitana

Regulatory Reports Administrator

Title

11/06/1999

Date

Phone No. (504) 593-7260

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED
DEC 10 1999

CONFIDENTIAL

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		7. If Unit or CAJ Agreement, Name and/or No. RIVER BEND UNIT
2. Name of Operator CNG PRODUCING COMPANY		8. Well Name and No. RBU 14-23F
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	9. API Well No. 43-047-33368
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>SPUD NOTICE</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

The RBU 14-23F was spud on 12/02/99.

Drilling rathole with air hammer. Trip out of hole. Ran 13 3/8" conductor casing and set at 97'. Nipple up airhead. Cement conductor. Wait on cement. Trip in hole. Drill with air to 575'. Survey at 600' - 1/8". Drilling ahead to 725'.

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA Signature <i>Susan A. Sachitana</i>	Title REGULATORY REPORTS ADMINISTRATOR
	Date 991206

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an
abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		CONFIDENTIAL	5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY			6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000		3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E			8. Well Name and No. RBU 14-23F
			9. API Well No. 43-047-33368
			10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
			11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR DECEMBER 2, 1999 - DECEMBER 10, 1999

Drilling rathole with air hammer. Trip out of hole. Ran 13 3/8" conductor casing and set at 97'. Nipple up airhead. Cement conductor. Wait on cement. Trip in hole. Drill with air to 575'. Survey at 600' - 1/8". Drilling ahead to 725'. Load hole with fluid and circulate clean. Trip out of hole. Trip in hole with new bit. Drilling ahead to 1,250'. Survey at 1,621' - 3/4". Drilling ahead with fluid to 3,030'. Circulate and condition hole. Trip out of hole. Ran 48 jts of 8 5/8" 32#, J-55 casing. Set casing at 3,023' with 675 sks of Poz / Class "G" cement. Nipple up BOP. Test blind rams, pipe rams, and check valves to 3,000 PSI. Test annular to 1,500 PSI. Test casing to 1,000 PSI. All test good. Nipple up airhead and trip in hole. Drill ahead to 3,454'. Drilling with fluid to 4,422'. Survey at 3,840' - 1 1/2".

RECEIVED

DEC 13 1999

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title DIVISION OF OIL, GAS & MINING REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H. Sachitana</i>	Date 991210

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
2. Name of Operator CNG PRODUCING COMPANY		8. Well Name and No. RBU 14-23F
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	9. API Well No. 43-047-33368
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

CONFIDENTIAL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR DECEMBER 11, 1999 - DECEMBER 17, 1999

Trip out of hole. Pick up bit and trip in hole. Drill to 4,928'. Survey at 4,928' - 1°. Drill to 5,300'. Survey at 5,095' - 2°. Drilling to 6,600'. Drill to 6,752'. Survey at 6,720' - 2°. Drill to 7,000'. Circulate and pump slug. Trip out of hole with bit #5. Trip in hole with bit #6. Drill to 7,220'. Drilling ahead to 7,596'. Mud weight 8.9 PPG.

14. I hereby certify that the forgoing is true and correct	
Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H. Sachitana</i>	Date 991217

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED
DEC 27 1999

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		3. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		8. Well Name and No. RBU 14-23F
		9. API Well No. 43-047-33368
		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

CONFIDENTIAL

NATURE OF NOTICE, REPORT, OR OTHER DATA

SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR DECEMBER 18, 1999 - DECEMBER 22, 1999

Drilling with fluid from 7,800' to 8,043'. Circulate and pump sweep. Trip out of hole with bit #6. Trip in hole with bit #7. Fill pipe and ream 45' to bottom. Drilling with 9.2 wt. fluid from 8,043' to 8,250'. Circulate and condition hole. Short trip 10 stands, no problems. Circulate and condition hole for logs. Strap pipe out for logs. Fast line sheave in crown block bearings went out, try to remove sheave. Trip in hole. Circulate and condition hole for logs. Trip out of hole. Rig up Schlumberger. Trip in hole to log TD to 8,250'. Ran DLL - MSFL - Den Neu to 3,024', Gamma Ray to surface. Rig down loggers. Trip in hole. Circulate and condition hole to run casing. Lay down drill pipe and collars. Rig up casing crew and start running 5 1/2" casing.

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H. Sachitana</i>	Date 991222

APPROVAL OR STATE OFFICE USE	Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

CONFIDENTIAL

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		8. Well Name and No. RBU 14-23F
		9. API Well No. 43-047-33368
		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input checked="" type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof.

If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

CNG Producing Company request permission to replace the 2" pipeline at the RBU 12-23F with a 4" pipeline and run a 4" pipeline from the RBU 12-23F to the RBU 14-23F instead of the 2" pipeline proposed in the permit to drill application. No additional surface disturbance or grading will be required as these are surface lines.

Verbal approval was given to James Sweat by Greg Darlington on 12/20/99 to begin operations.

RECEIVED

DEC 28 1999

DIVISION OF OIL, GAS & MINING


14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan Sachitana</i>	Date 991220

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
-------------	-------	------

Conditions of approval, if any, are attached. Approval of this notice does not warrant Office certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



Run 4" pipe line from 14-23F to
4" pipe line @ 12-23F

at change
-10E
1

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
2. Name of Operator CNG PRODUCING COMPANY		8. Well Name and No. RBU 14-23F
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-8000	3b. Phone No. (include area code) (504) 593-7000	9. API Well No. 43-047-33368
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

CONFIDENTIAL

NATURE OF NOTICE, REPORT, OR OTHER DATA

SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other: <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompletes horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR DECEMBER 23, 1999 - JANUARY 7, 2000

Rig up Schlumberger. Pick up and run in hole with CBL Gamma Ray Tool and tag at 8,154'. Log to surface. Showed good cement all hole. Lay down logging tool. Rig up hot oiler and pressure test to 5,000 PSI. Held for 30 minutes. OK. Rig down hot oiler. Pick up and run in hole with 4" casing gun and perforate interval #1 (8,080'-73') with 3 SPF. Rig down Schlumberger. Rig up BJ Services. Break down interval #1 (8,080'-73'). Formation broke at 3,620 PSI. Average treating pressure 3100 PSI, ISDP 2804 PSI. Rig down BJ. Rig up Schlumberger. Pick up and run in hole with 4" casing gun and reperforate interval #1 (8,080'-73') with 3 SPF. Pull out of hole. Rig up BJ Services and pressure test to 5,850 PSI. Pump 30 bbls 2% KCL water. Bleed off pressure. Pump 2nd pump in test with 30 bbls 2% KCL water. Pick up and run in hole with HB composite bridge plug and set at 7,950'. Pull out of hole. Pick up and run in hole with 4" casing gun and perforate interval #2 (7,904'-08', 7,914'-22') with 3 SPF. Pull out of hole. Rig down wireline. Break down interval #2. Rig up BJ frac equipment and test lines to 6,200 PSI. Held OK. Frac'd interval #2 (7,904'-08' & 7,914'-22') with 60,673 lbs of 20/40 frac sand and 720 bbls of 30# Viking. Initial post shut-in pressure was 3,420 PSI. Opened well up with 3,400 PSI and performed a forced closure flowing back 15 bbls at 1/2 BPM rate. Casing pressure declined to 3,146 PSI in 1/2 hr. Opened casing to pit on 12/64" choke with 3,140 PSI. Flowed casing to reserve pit on a 12/64" choke. Well had 710 PSI on casing. 15 hr after treatment wouldn't burn. Well produced 607 MCFD with mist of treating fluid. Installed 18/64" choke and left casing flowing to reserve pit. Well had 300 PSI on casing returning of 620 MCF, gas would burn but still wet. Left well flowing to pit on 18/64" choke.

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan Sachitana</i>	Date 20000107

FEDERAL OR STATE OFFICE USE	
Approved by	Title Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED
JAN 10 2000
DIVISION OF OIL, GAS & MIN

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		CONFIDENTIAL	5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY			6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT	8. Well Name and No. RBU 14-23F
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		9. API Well No. 43-047-33368	10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH	

STATE NATURE OF NOTICE, REPORT, OR OTHER DATA

SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13 Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR JANUARY 8, 2000 - JANUARY 14, 2000

Fenced front side of pit. Rig up test lines. Set sival dehy/separat set sival 300 bbl and 210 bbl tanks. Ran 2" sch 80 flow line from dehy to wellhead. Also ran 3/4" plastic gas line to pump at wellhead from dehy. Run 2" sch 80 blow line from dehy to 210 bbl tank. Ran 1" water dump line to 210 bbl tank. Install sival tank heater. Ran 3/4" plastic gas line from dehy to heater in water tank. Ran 1" condensate dump line to 300 bbl tank from dehy. Ran 4" sch 40 sales line to 12-23F from dehy and tied it in. Run 3/8" steel line in plastic to water dump from pump at wellhead. Run cable for plunger to dehy from wellhead. Rig up gas meter and filled unit with glycol and put well on production. Well flowing to sales line through unit on 18/64" choke made 40 MCF with 321 PSI on casing and 315 PSI on sales line. Returned 0 bbls water. Rig up Schlumberger. Pick up and run in hole with 4.5 gauge ring to 7,900'. Pull out of hole. Pick up and run in hole with 5-1/2" composite bridge plug and set at 7,810'. Pull out of hole. Rig up BJ Services. Fill hole with 162 bbls filtered 2% KCL water and pressure test to 5000 PSI for 10 min. Held OK. Pick up and run in hole with 4" casing gun and perforate interval #3 (7,774'-86") with 3 SPF. Pump 1 bbl water. Pressured up to 5500 PSI. Formation would not break. Bleed off. Rig down Schlumberger and BJ. Move in rig. Rig up rig and equipment. Nipple down frac valve. Nipple up BOPE. Trip in hole with 250 jts. 2-3/8" tubing and 4' pup jt. with end of tubing at 7,776'. Rig up BJ Services and pressure test to 6000 PSI. Pump 500 gal. 15% HCL flush with 30 bbls filtered 2% KCL water. Pull out of hole with 4 jts tubing. End of tubing at 7,852'. Pump 30 bbls filtered 2% KCL water. Formation broke at 4,859 PSI. ISDP 3180 PSI. 5 min. 2800, 10 min. 2570, 15 min. 2410, 20 min. 2320, 25 min. 2170, 30 min. 2080, .849 FG. Nipple down BJ. Pull out of hole and lay down 225 jts. 2-3/8" tubing with end of tubing at 752'. Pull out of hole and lay down 151 jts of 2 3/8" tubing, Nipple down BOP. Nipple up frac valve. Rig down rig and equipment.

RECEIVED

JAN 24 2000

DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H. Sachitana</i>	Date 20000114

FEDERAL OR STATE OFFICE USE	
Approved by	Title
	Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an
abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
2. Name of Operator CNG PRODUCING COMPANY		8. Well Name and No. RBU 14-23F
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	9. API Well No. 43-047-33368
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

CONFIDENTIAL

**NATURE OF NOTICE, REPORT, OR OTHER DATA
SUBMISSION TYPE OF ACTION**

<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other: <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13 Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR JANUARY 15, 2000 - JANUARY 21, 2000

Rig up BJ frac equipment and test line to 6000 PSI. Held OK. Frac'd interval #3 (7,774'-7,786') with 26,350 lbs of 20/40 frac sand and 429 bbls 30# / bbl Viking gel. Initial post frac shut-in pressure was 3,775 PSI. Opened well up and performed a forced closure flowing back 15 bbls at 1/2 BPM rate. Casing pressure declined to 3,180 PSI in 1/2 hr. Opened casing to pit on 12/64" choke with 3,180 PSI.

RECEIVED

JAN 26 2000

DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H. Sachitana</i>	Date 20000121

FEDERAL OR STATE OFFICE USE	
Approved by	Title Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		CONFIDENTIAL	5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY			6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000		3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		8. Well Name and No. RBU 14-23F	
		9. API Well No. 43-047-33368	
		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630	
		11. County or Parish, State UINTAH, UTAH	

NATURE OF NOTICE, REPORT, OR OTHER DATA

SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR JANUARY 22, 2000 - JANUARY 28, 2000

Rig up Schlumberger. Pick up and run in hole with 4.50" gauge ring to 7,425'. Pull out of hole. Pick up and run in hole with HB 5-1/2" bridge plug and set at 7,420'. Pull out of hole. Rig up BJ Services and pressure test to 5500 PSI. Fill hole with 147 bbls filtered 2% KCL water and pressure test to 5000 PSI for 10 minutes. Held OK. Pick up and run in hole with 4" casing gun and perforate interval #4 (7,350'-60') with 3 SPF. Pull out of hole. Rig down Schlumberger. Pump in test, pump to 5000 PSI. Formation would not break. Surge well and pump to 5500 PSI. Would not break. Rig down BJ. Rig up workover rig and equipment. Nipple down frac valve. Nipple up BOP. Pick up and run in hole with 237 jts. 2-3/8" tubing with end of tubing at 7,361'. Rig up BJ Services and pressure test to 6,000 PSI. Pump 500 gals 15% HCL to end of tubing and spot on perforations. Pull out of hole with 4 jts. tubing. Pump 30 bbls filtered 2% KCL water at 5.3 BPM. Broke at 3490 PSI. Average pump PSI was 3200. Rig down BJ. Pull out of hole. Lay down 129 jts. 2-3/8" tubing. Well had 20 PSI on tubing and casing. Bleed PSI to rig tank. Pull out of hole and laid down 108 jts 2 3/8" tubing. Nipple down BOP. Nipple up frac valve. Rig down rig. Rig up BJ frac equipment and test lines to 6000 PSI. Tested OK. Frac'd Interval #4 (7,350'-7,360') with 22,474 lbs of 20/40 frac sand and 384 bbls of 30#/bbl Viking. Initial post frac shut-in pressure was 3,240 PSI. Opened well and performed a forced closure flowing back 15 bbls at 1/2 BPM rate. Casing pressure declined to 2,750 in 1/2 hr. Opened casing to pit on 12/64" with 2,750 PSI.

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature 	Date 20000128

RECEIVED

FEB 03 2000

DIVISION OF
OIL, GAS AND MINING

FEDERAL OR STATE OFFICE USE	
Approved by	Title
	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

NOT RECORDED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		8. Well Name and No. RBU 14-23F
		9. API Well No. 43-047-33368
		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

STATE NATURE OF NOTICE, REPORT, OR OTHER DATA

SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof.

If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomplate in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR JANUARY 29, 2000 - FEBRUARY 4, 2000

Rig up Schlumberger. Run in hole with HB 5-1/2" composite bridge plug and set at 7,110'. Pull out of hole and rig down wireline. Rig up workover rig and equipment. Nipple down frac valve. Nipple up BOP and test to 250 PSI & 5000 PSI. Pick up and run in hole with 4.75" bit, bit sub with dart in place, 1 jt. 2-3/8" tubing, 1.78 "F" nipple and 228 jts. 2-3/8" tubing with end of tubing at 7,071'. Nipple up hydril. Rig up swivel and foam unit. Rig up string float. Run in hole to 7,110' and drill up bridge plug. Run in hole and tag sand at 7,350'. Drill and circulate to bridge plug at 7,420'. Drill up plug. Run in hole and tag sand at 7,775'. Drill and circulate to bridge plug at 7,810'. Drill up plug. Run in hole and tag sand at 7,923'. Drill and circulate to bridge plug at 7,950'. Drill up plug. Run in hole and tag sand at 8,142'. Drill and circulate to plugged back total depth at 8,154'. Pump 10 bbl. sweep and circulate well clean. Rig down swivel. Pull out of hole to string float at 7,071' and lay down float. Run in hole with 257 jts. 2-3/8" tubing and land hanger with 1.78 "F" nipple at 7,965', end of tubing at 7,996'. Nipple down stack. Nipple up wellhead. Drop ball - attempt to pump off bit - pressure to 2200 PSI - bit would not pump off. Rig down rig and equipment and foam unit. Well had 2200 PSI on tubing and 1800 PSI on casing. Rig up wireline. Pick up and run in hole with 1-9/16" strip gun and CCL and 17' of 1-9/16" wt. bars. Shoot bottom jt. below "F" nipple at 7,988' with 4 - .50" holes. Pull out of hole. At 1,900' line blew up hole. Line was knotted in lubricator. Shut-in wireline BOP. Lay down lubricator and cut line with 20' above BOP. Rig up 4' sub on BOP. Rig down wireline. Put well on production with all intervals open.

RECEIVED

FEB 10 2000

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
	Date 20000204

**DIVISION OF
OIL, GAS AND MINING**

FEDERAL OR STATE OFFICE USE	
Approved by	Title
	Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

FORM PREVIOUSLY APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		8. Well Name and No. RBU 14-23F
		9. API Well No. 43-047-33368
		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

NATURE OF NOTICE, REPORT, OR OTHER DATA

SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof.

If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomplate in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR FEBRUARY 5, 2000 - FEBRUARY 11, 2000

Rig up wireline and hot oiler. Pump 20 bbls formation water from well down tubing to control well. Open BOP and pull out of hole with 1/4" braided line. Only able to fish 150' piece of wire. Rig down wireline and hot oiler. Return well to production.

RECEIVED

FEB 14 2000

DIVISION OF
~~OIL, GAS AND MINING~~

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H. Sachitana</i>	Date 20000211

FEDERAL OR STATE OFFICE USE	
Approved by	Title Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant Office certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an
abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		CONFIDENTIAL	5. Lease Serial No. U-01470-A
2. Name of Operator CNG PRODUCING COMPANY			6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000		3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E			8. Well Name and No. RBU 14-23F
			9. API Well No. 43-047-33368
			10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
			11. County or Parish, State UINTAH, UTAH

NATURE OF NOTICE, REPORT, OR OTHER DATA

SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR FEBRUARY 18, 2000 - FEBRUARY 25, 2000

Rig up workover rig, equipment and wire line truck. Pump 30 bbls 2% KCL water down tubing and 30 bbls down casing to control well. Nipple down wellhead. Nipple up BOP. Unland tubing. Pull out of hole with 257 jts. 2-3/8" tubing and bottom hole assembly. Pump off bit had 2' of sediment on ball so ball could not seat to shear pins. Retrieved 1,800' of 1/4" braided wire line and tubing perforation tools. Bottom jt. of tubing had 4 1/2" holes shot from tubing gun. Found hole ripped in 37th and 69th jts. of tubing. Replace bad jts. and run in hole with 1 jt. 2-3/8" tubing, 1.78" "F" nipple and 256 jts. 2-3/8" tubing. Land tubing on hanger, "F" nipple at 7,962' with end of tubing at 7,995'. Left casing flowing to tank on 12/64" choke. Well had 0 PSI on casing and 100 PSI on tubing. Bled tubing off to rig tank. Rig down tubing equipment and floor. Nipple down BOP. Nipple up wellhead. Rig down circulation equipment. Rig up swab equipment. Fluid level on first run was at 1,300'. Made 30 swab runs. Recovered 143 bbls water. Fluid level on last run was at 3,200' with 745 PSI on casing. Well had 450 PSI on tubing and 1200 PSI on casing. Bled tubing pressure off to tank. Workover rig started swabbing. Made 6 swab runs. Recovered 41 bbls gas cut fluid. Rig down workover rig. Rig up swab rig. Made 16 swab runs. Recovered 80 bbls gas cut fluid. Total bbls swabbed today 121 bbls. Well started flowing. Cleaned up to tank and put well to sales line. Well had 400 PSI on tubing and 1,550 PSI on casing. Bled well off to swab. Made 4 runs and well flowed. Swabbed back 15 bbls. Rig up telemetry equipment. Drop spring, stop and plunger. Put well on production on 21/64" choke.

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H Sachitana</i>	Date 20000225

FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL
UNCLASSIFIED
OMB No. 1004-0185
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an
abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
2. Name of Operator CNG PRODUCING COMPANY		8. Well Name and No. RBU 14-23F
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	9. API Well No. 43-047-33368
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 793' FSL & 2,405' FWL of Sec. 23-T10S-R20E		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

CONFIDENTIAL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other: <u>SUMMARY OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

SUMMARY OF OPERATIONS FOR FEBRUARY 26, 2000 - MARCH 3, 2000

Well had 400 PSI on tubing and 1550 PSI on casing. Bled well off to swab. Made 4 runs, well flowed. Swabbed back 15 bbls. Rig up telemetry equipment. Drop spring, stop and plunger. Put well on production on 21/64" choke.

RECEIVED

MAR 08 2000

DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H Sachitana</i>	Date 20000303

FEDERAL OR STATE OFFICE USE		
Approved by	Title	Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant Office
certify that the applicant holds legal or equitable title to those rights in the subject lease
which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**CNG Producing
Company**

A **CNG** COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

CONFIDENTIAL

April 4, 2000

Ms. Vicki Dyson
Utah Board of Oil, Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, Utah 84114-5801

RE: Open Hole Logs
RBU 14-23F Sec.23-T10S-R20E - 43-049-33368

Dear Ms. Dyson:

Enclosed please find one (1) copy of open hole logs for the above referenced wells. The logs are being sent to you per State requirements. *Logs filed in log file/CHC*

If you have any questions or need any additional information, please feel free to contact me at (504) 593-7260.

Sincerely,

CNG PRODUCING COMPANY

Susan H. Sachitana
Susan H. Sachitana
Regulatory Reports Administrator

cc: Nelda Decker
Tom Auld
David Linger
Mitch Hall

RECEIVED

APR 05 2000

DIVISION OF
OIL, GAS AND MINING

CNG Producing
Company

CNG

170 South 500 East
Vernal, Utah 84078
801-839-7100

April 4, 2000

CONFIDENTIAL

Mr. Wayne Bankert
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: Well Completion Report
RBU 14-23F Sec. 23-T10S-R20E

Dear Wayne:

Enclosed please find an original and two copies of the above referenced report.

CNG Producing Company is requesting all information be held confidential.

Should you have any question please feel free to contact either myself at (504) 593-7260 or our project engineer, Ralph Hamrick at (281) 873-1562.

Sincerely,

CNG PRODUCING COMPANY



Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Utah Department of Oil, Gas & Mining
T. Auld
D. Thomas
N. Decker
M. Hall
D. Hipkiss
S. Howard
M. O'Donnell
A. Burnside
M. Nwaokobia
R. Hamrick
D. Linger
RBU Well Files

RECEIVED

APR 07 2000

DIVISION OF
OIL, GAS AND MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE*

(See other instructions on reverse side)

FORM APPROVED
OMB NO. 1004-0137

Expires: February 28, 1995

5. LEASE DESIGNATION AND SERIAL NO.

U-01470-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL: OIL WELL GAS WELL DRY Other
1b. TYPE OF COMPLETION: NEW WORK DEEP- PLUG DIFF. WELL OVER EN BACK RESVR. Other

7. UNIT AGREEMENT NAME
RIVERBEND UNIT

8. FARM OR LEASE NAME, WELL NO.

RBU 14-23F

9. API WELL NO.

43-047-33368

10. FIELD AND POOL, OR WILDCAT
NATURAL BUTTES 630

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

SE SW of Sec. 23-T10S-R20E

2. NAME OF OPERATOR

CNG Producing Company

3. ADDRESS AND TELEPHONE NO.

CNG Tower - 1450 Poydras St., New Orleans, LA 70112-6000 (504) 593-7260

Contact Person: Sue Sachitana

4. LOCATION OF WELL

(Report location clearly and in accordance with any State requirements)*

At surface 793' FSL & 2,405' FWL of Sec. 23-T10S-R19E

At top prod. interval reported below

At total depth

CONFIDENTIAL

14. PERMIT NO. 43-047-33368 DATE ISSUED 08/20/99 12. COUNTY OR PARISH UINTAH 13. STATE UTAH

15. DATE SPUDDED 12/02/1999 16. DATE T.D. REACHED 12/19/1999 17. DATE COMPL. (Ready to prod.) 02/23/2000 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* GR 5,187', KB 5,202' 19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD 8,250' 21. PLUG, BACK T.D., MD & TVD 8,154' 22. IF MULTIPLE COMPL., HOW MANY* 4 Zones 23. INTERVALS DRILLED BY ROTARY 24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)* Wasatch - Mesa Verde Formations 8,060'-73', 7,904'-08, 7,914'-22', 7,774'-86' & 7,350'-60'

25. WAS DIRECTIONAL SURVEY MADE NO

26. TYPE ELECTRIC AND OTHER LOGS RUN

DLL - FDC - CNL - MUDLOG 4-5-2000

27. WAS WELL CORED

NO

28. CASING RECORD (Report all strings set in well)					
CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENT RECORD	AMOUNT PULLED
13 3/8"		97'	17 1/2"	Surface	
8 5/8" J-55	32#	3,023'	12 1/4"	675 sks Poz / Class "G" cement	
5 1/2" N-80	17#	8,250'		1,362 sks Class "G"	

29. LINER RECORD				30. TUBING RECORD		
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)
					2 3/8"	7,998'

31. PERFORATION RECORD (Interval, size and number)		32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.	
ZONE	INTERVAL	DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
ZONE #1	8,060'-73'		
ZONE #2	7,904'-08 & 7,914'-22'		
ZONE #3	7,774'-86'		
ZONE #4	7,350'-60'		
		ZONE #2	60,673 lbs of 20/40 frac sand and 720 bbls of 30# Viking.
		ZONE #3	26,350 lbs of 20/40 frac sand and 429 bbls 30# Viking
		ZONE #4	22,474 lbs of 20/40 frac sand and 384 bbls of 30# Viking.

33. PRODUCTION							
DATE FIRST PRODUCTION		PRODUCTION METHOD		WELL STATUS			
01/20/2000		FLOWING		PRODUCING			
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL-BBL.	GAS-MCF.	WATER-BBL.	GAS-OIL RATIO
02/03/2000	24	19/64"		0	259	15	
FLOW: TUBING PRESS.	CASING PRESSURE	CALCULATED 24 HOUR RATE	OIL-BBL.	GAS-MCF.	WATER-BBL.	OIL GRAVITY-API (CORR.)	
321	350		0	259	15		

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) SOLD TEST WITNESSED BY JAMES SWEAT

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

SIGNED DAVID J. MC BRIDE TITLE MANAGER, EH&S DATE 04/04/2000

*(See instruction and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

CONFIDENTIAL
PERIOD EXPIRED
ON 3-23-01

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);

38. GEOLOGICAL MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
Mesa Verde	7,348'	7,360'	GAS	WASATCH TONGUE	3,951'	3,951'
Mesa Verde	7,774'	7,791'	GAS	GREEN RIVER TONGUE	4,286'	4,286'
Mesa Verde	7,889'	7929'	GAS	WASATCH	4,428'	4,428'
Mesa Verde	8,056'	8072'	GAS	CHAPITA WELLS	5,152'	5,152'
				UTELAND BUTTES	6,118'	6,118'
				MESA VERDE	7,168'	7,168'

RECEIVED

APR 07 2000

DIVISION OF
OIL, GAS AND MINING

CONFIDENTIAL

DOMINION EXPLORATION & PRODUCTION

SPUD: 12/1/99
COMPLETED:
WORKED OVER:

RIVERBEND UNIT 14-23F
SEC: 23, T: 10S R: 20E
API: 43-047-33368


DATE: February 15, 2000

PRESENT

SALES -
BHP -
TUBING - 2-3/8" 4.7# N-80 8rd

NOTE: Unless Stated All Depths
are Measured.
NOT DRAWN TO SCALE.

8 5/8", 32# J-55 @ 3023' Cmt'd w/ 675 sxs Class G.



- 1. 2-3/8" 8rd Hanger
- 2. 256 Jts 2-3/8 " 8rd N-80 Tubing
- 3. 1.81 "XN" Nipple
- 4. 1 Jt 2-3/8" 8rd N-80 Tubing
- 5. Pump Off Bit Sub

Interval #4
7350 - 7360' @ 3 spf (30 Holes)
Frac - 22M # 20/40 Pre-Cured sd.

Interval #3
7774 - 7786' @ 2 spf (36 Holes)
Frac - 28M # 20/40 Pre-Cured sd.

Interval #2
7904 - 7908', 7914 - 7922' @ 3 spf (36 Holes)
Frac - 60M # 20/40 Pre-Cured sd.

SN @ 7,954.53'
EOT @ 7,997.66'

Interval #1
8060 - 8073' @ 3 spf (39 Holes)
Frac - 32M # 20/40 Pre-Cured sd.

Pump off Bit & Bit Sub @ 8154'

PBTB @ 8,154'

5-1/2" 17# L-80 @ 8249'. Cmt'd w/ 1362 sxs Class G.

TD 8250'

RECEIVED
APR 07 2000
DIVISION OF
OIL, GAS AND MINING

Dominion Exploration & Production, Inc.
1450 Poydras Street, New Orleans, LA 70112-6000
Phone: 504-593-7000



June 27, 2000

Mr. Jimmy Thompson
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Name Change Documentation for CNG Producing Company

Dear Mr. Thompson:

CNG Producing Company has become Dominion Exploration & Production, Inc. effective April 12, 2000. Enclosed please find a sundry regarding the name change with an attached listing of all the permits in the name of CNG Producing Company to be changed to Dominion Exploration & Production, Inc. Also enclosed please find a Form UIC 5 for the Transfer of Authority to Inject for the Federal #1-26B well.

If you have any questions or require any additional information, please contact me at (504) 593-7260.

Sincerely,

DOMINION EXPLORATION & PRODUCTION, INC.

Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Nelda Decker

RECEIVED

JUN 29 2000

**DIVISION OF
OIL, GAS AND MINING**

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS


Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well : OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER: _____	5. Lease Designation and Serial Number: VARIOUS
2. Name of Operator: DOMINION EXPLORATION & PRODUCTION, INC.	6. If Indian, Allottee or Tribe Name:
3. Address and Telephone Number: 1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-7260	7. Unit Agreement Name:
4. Location of Well Footages: QQ, Sec. T., R., M.:	8. Well Name and Number: VARIOUS
	9. API Well Number
	10. Field and Pool, or Wildcat: Natural Buttes 630
	County: UINTAH State: UTAH

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA	
NOTICE OF INTENT (SUBMIT IN DUPLICATE)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other _____	<input type="checkbox"/> Abandon* <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input checked="" type="checkbox"/> Other <u>OPERATOR NAME CHANGE FOR WELLS</u> Date of work completion _____ <small>Report results of Multiple Completion and Recompletion to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.</small> <small>*Must be accompanied by a cement verification report.</small>
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recomplete <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off
Approximate date work will start _____	

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that effective April 12, 2000, CNG Producing Company has changed its name to Dominion Exploration & Production, Inc. and would like to transfer the well permits into the name of Dominion Exploration & Production, Inc. Our new bond has been filed and is pending approval with the State of Utah. The bond number is 76S 63050 361.



 John R. Lewis
 Sr. Vice-President - CNG Producing Company

RECEIVED

JUN 29 2000

DIVISION OF
OIL, GAS AND MINING

13.

Name & Signature: 	Title: Sr. Vice-President - Dominion Expl. & Prod., Inc.	Date: June 26, 2000
---	--	---------------------

(This space for State use only)



State of Utah
DEPARTMENT OF COMMERCE
Division of Corporations & Commercial Code

552894
CO 106990
File Number

Table with 2 columns: Check Appropriate Box, Fee Amount. Rows include Foreign Profit Corporation (\$35.00), Foreign Non-Profit Corporation (\$35.00), Foreign Limited Partnership (\$25.00), Foreign Limited Liability Company (\$35.00).

Application To Amend The
CERTIFICATE OF AUTHORITY OR
REGISTRATION of

CNG Producing Company
Business Entity Name

Delaware
Name of Home State

I. AMENDING THE BUSINESS NAME

The business name is changed to: Dominion Exploration & Production, Inc.
The corporation shall use as its name in Utah: Dominion Exploration & Production, Inc.

(The corporation shall use its name as set forth on #1, unless this name is not available.)

NOTE: If the business name has changed its name in the home state, a copy of the Certificate of Amendment or a certified copy of the amendment must accompany this application.

Check the following:

- [X] The name of the corporation is changing it's name in Utah to the new name of the corporation in the home state.
[] The name of the corporation is being changed in Utah to comply with Utah State Insurance Regulations.

II. AMENDING THE DURATION OF THE BUSINESS EXISTENCE

The businesses period of duration is changed to:

III. AMENDING THE STATE OR COUNTRY OF INCORPORATION/REGISTRATION

The corporation's state or country of incorporation/registration is changed to:

IV. Other:
(Limited Partnership changing General Partners, Limited Companies changing Members or Managers, Change of statement who is managing, etc.)
Use an attached sheet if needed.

Under penalties of perjury, I declare this Application to Amend the Certificate of Authority or Registration to be, to the best of my knowledge and belief, true and correct.

Signature: [Handwritten Signature] Title: Vice President & Corporate Secretary Date: April 20 2000

STATE OF UTAH
DIVISION OF CORPORATIONS
AND COMMERCIAL CODE
160 East 300 South / Box 146705
Salt Lake City, UT 84114-6705
Service Center: (801) 530-4849
Web Site: http://www.commerce.state.ut.us

State of Utah
Department of Commerce
Division of Corporations and Commercial Code

I hereby certify that the foregoing has been filed and approved on this 25 day of April 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner: [Signature] Date: 7/4/00



W. JENSON
Director

Date: 04/25/2000
Receipt Number: 22156
Amount Paid: \$50.00

FILED
APR 25 2000

EXHIBIT A
OIL & GAS LEASES AFFECTED BY THE NAME CHANGE

U-01470-A	U-017713	U-46825
U-01790	U-035316	U-62232
U-02896-A	U-037164	UTU-66743
U-03505	U-0143519	UTU-68108
U-03576	U-0143520-A	UTU-68388
U-013429-A	U-0143521-A	UTU-68625
U-013765	U-0147541	UTU-69166
U-013766	U-0147541-A	UTU-73011
U-013767	U-3405	UTU-73433
U-013769	U-7206	UTU-76499
U-013769-A	U-9803	UTU-76500
U-013769-B	U-10291	UTU-76717
U-013769-C	U-16544	UTU-76718
U-013792	U-19266	
U-013793	U-28203	U-60759 (CA)
U-013793-A	U-29784	U-60940 (CA)
U-013794	U-30693	UTU-77360 (CA)
U-013818-A	U-37246	U-63054X (River Bend)
U-013820	U-39221	UTU-73218X
U-013821-A	U-43156	(West Willow Creek Unit)

api	well_name	well_status_main	lease_num
4304732111	RBU 7-15F	LA	14-20-H62-2645
4304732189	RBU 13-10F	P	14-20-H62-2645
4304730768	RBU 7-22F	P	14-20-H62-2646
4304732109	RBU 15-15F	LA	14-20-H62-2646
4304732844	RBU 15-15F	P	14-20-H62-2646
4304732269	RBU 4-15F	PA	INDIAN
4304733360	RBU 1-16F	DRL	ML-3393
4304731980	STATE 2-36E	LA	ML-42175
4304731801	RIVER BEND U 2-10D	S	U-013429-A
4304731551	RBU 10X-15E	PA	U-013760
4304731716	RIVER BEND U 7-13E	LA	U-013765
4304731718	RBU 15-13E	LA	U-013765
4304732600	RBU 1-21EO	P	U-013766
4304733033	RBU 7-23E	P	U-013766
4304733160	RBU 8-15E	P	U-013766
4304733272	RBU 13-3F	P	U-013767
4304733366	RBU 5-18F	P	U-013769
4304732991	RBU 6-19F	P	U-013769-A
4304733157	RBU 7-19F	P	U-013769-A
4304732454	RBU 9-14EO	P	U-013792
4304732514	RBU 8-14EO	LA	U-013792
4304732678	RBU 13-22EO	LA	U-013792
4304732989	RBU 13-10E	P	U-013792
4304733156	RBU 4-14E	P	U-013792
4304733161	RBU 16-10E	P	U-013792
4304733194	RBU 2-14E	P	U-013792
4304733365	RBU 12-14E	P	U-013792
4304732990	RBU 13-18F2	P	U-013793
4304732396	RBU 3-21F	P	U-013793-A
4304732407	RBU 15-14F	P	U-013793-A
4304732408	RBU 4-23F	P	U-013793-A
4304732899	RBU 3-14F	P	U-013793-A
4304732900	RBU 8-23F	P	U-013793-A
4304732972	RBU 1-21F	P	U-013793-A
4304733087	RBU 6-23F	P	U-013793-A
4304733158	RBU 7-20F	P	U-013793-A
4304733424	RBU 5-20F	P	U-013793-A
4304732392	RBU 11-14F	P	U-013793A
4304731719	RBU 5-24E	LA	U-013794
4304732483	RBU 5-24EO	P	U-013794
4304733034	RBU 9-18F	P	U-013794
4304733159	RBU 7-24E	P	U-013794
4304731352	RBU 16-3D	P	U-013820
4304733599	RBU 1-1D	APD	U-013820
4304733090	RBU 11-22F	P	U-0143519
4304733089	RBU 8-22F	P	U-0143521
4304732901	RBU 12-23F	P	U-01470-A
4304733091	RBU 16-22F	P	U-01470-A
4304733368	RBU 14-23F	P	U-01470-A
4304731138	RBU 11-34B	P	U-017713
4304731724	RBU 11-35B	S	U-017713
4304732094	RBU 13-35B	P	U-017713
4304732222	RBU 15-35B	S	U-017713
4304730585	RBU 7-11F	P	U-01790
4304732512	RBU 8-11F	P	U-01790
4304731739	RBU 9-9E	P	U-03505
4304732415	RBU 3-10EX (RIG SKID)	P	U-035316
4304733035	RBU 14-19F	P	U-13769-A
4304731881	APACHE 12-25	S	U-3405
4304732417	FEDERAL 3-25B	P	U-39221
4304731782	SADDLE TREE DRAW 13-34	LA	U-57598
4304732934	RBU 3-10F	P	U-7206
4304732969	RBU 11-10F	P	U-7206
4304732970	RBU 12-15F	P	U-7206
4304732971	RBU 15-16F	P	U-7206



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
U-01470-A et al
(UT-932)

JUN 2 2000

NOTICE

Dominion Exploration & Production, Inc. : Oil and Gas Leases
1450 Poydras Street :
New Orleans, LA 70112-6000 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of CNG Producing Company to Dominion Exploration & Production, Inc. on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from your list of leases and a list of leases obtained from our automated records system. We have not abstracted the lease files to determine if the entity affected by the name change holds an interest in the leases identified nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interests. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

The following lease on your list is closed on the records of this office: U-029277.

Due to the name change, the name of the principal on the bond is required to be changed from CNG Producing Company to Dominion Exploration & Production, Inc. on Bond No. 524 7050 (BLM Bond No. WY1898). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to the Wyoming State Office.

/s/ Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure
Exhibit of Leases

RECEIVED

JUN 05 2000

DIVISION OF
OIL, GAS AND MINERAL

cc: Wyoming State Office
New Mexico State Office
Moab Field Office
Vernal Field Office
MMS–Reference Data Branch, MS 3130, Box 5860, Denver, CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114-5801
Irene Anderson (UT-932)
Teresa Thompson (UT-931)
LaVerne Steah (UT-942)

OPERATOR CHANGE WORKSHEET

<input type="checkbox"/>	4-KAS <input checked="" type="checkbox"/>
2-CDW <input checked="" type="checkbox"/>	5857 <input checked="" type="checkbox"/>
3-JLT	6-FILE

Check each listed item when completed. Write N/A if item is not applicable.

Change of Operator (Well Sold) Designation of Agent
X Operator Name Change Only Merger

The operator of the well(s) listed below has changed, effective: 4-12-00

TO:(New Operator) DOMINION EXPL & PROD INC.
 Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000
 Phone: 1-(504)-593-7000
 Account No. N1095

FROM:(Old Operator) CNG PRODUCING COMPANY
 Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000
 Phone: 1-(504)-593-7000
 Account No. N0605

WELL(S):	CA Nos.	or	RIVER BEND	Unit
Name: <u>RBU 1-21F</u>	API: <u>43-047-32972</u>	Entity: <u>7050</u>	S 21 T 10S R 20E	Lease: <u>U-013793-A</u>
Name: <u>RBU 6-23F</u>	API: <u>43-047-33087</u>	Entity: <u>7050</u>	S 23 T 10S R 20E	Lease: <u>U-013793-A</u>
Name: <u>RBU 5-20F</u>	API: <u>43-047-33424</u>	Entity: <u>7050</u>	S 20 T 10S R 20E	Lease: <u>U-013793-A</u>
Name: <u>RBU 11-14F</u>	API: <u>43-047-32392</u>	Entity: <u>7050</u>	S 14 T 10S R 20E	Lease: <u>U-013793-A</u>
Name: <u>RBU 9-18F</u>	API: <u>43-047-33034</u>	Entity: <u>7050</u>	S 18 T 10S R 20E	Lease: <u>U-013794</u>
Name: <u>RBU 7-24E</u>	API: <u>43-047-33159</u>	Entity: <u>7050</u>	S 24 T 10S R 19E	Lease: <u>U-013794</u>
Name: <u>RBU 16-3D</u>	API: <u>43-047-31352</u>	Entity: <u>7070</u>	S 03 T 10S R 18E	Lease: <u>U-013820</u>
Name: <u>RBU 11-22F</u>	API: <u>43-047-33090</u>	Entity: <u>7050</u>	S 22 T 10S R 20E	Lease: <u>U-0143519</u>
Name: <u>RBU 8-22F</u>	API: <u>43-047-33089</u>	Entity: <u>7050</u>	S 22 T 10S R 20E	Lease: <u>U-0143521</u>
Name: <u>RBU 12-23F</u>	API: <u>43-047-32901</u>	Entity: <u>7050</u>	S 23 T 10S R 20E	Lease: <u>U-01470-A</u>
Name: <u>RBU 16-22F</u>	API: <u>43-047-33091</u>	Entity: <u>7050</u>	S 22 T 10S R 20E	Lease: <u>U-01470-A</u>
Name: <u>RBU 14-23F</u>	API: <u>43-047-33368</u>	Entity: <u>7050</u>	S 23 T 10S R 20E	Lease: <u>U-01470-A</u>
Name: <u>RBU 8-11F</u>	API: <u>43-047-32512</u>	Entity: <u>7050</u>	S 11 T 10S R 20E	Lease: <u>U-01790</u>
Name: <u>RBU 9-9E</u>	API: <u>43-047-31739</u>	Entity: <u>7050</u>	S 09 T 10S R 19E	Lease: <u>U-03505</u>
Name: <u>RBU 3-10EX</u>	API: <u>43-047-32415</u>	Entity: <u>7050</u>	S 10 T 10S R 19E	Lease: <u>U-035316</u>
Name: <u>RBU 14-19F</u>	API: <u>43-047-33035</u>	Entity: <u>7050</u>	S 19 T 10S R 20E	Lease: <u>U-13769-A</u>
Name: <u>RBU 3-10F</u>	API: <u>43-047-32934</u>	Entity: <u>7050</u>	S 10 T 10S R 20E	Lease: <u>U-7206</u>
Name: <u>RBU 11-10F</u>	API: <u>43-047-32969</u>	Entity: <u>7050</u>	S 10 T 10S R 20E	Lease: <u>U-7206</u>
Name: <u>RBU 12-15F</u>	API: <u>43-047-32970</u>	Entity: <u>7050</u>	S 15 T 10S R 20E	Lease: <u>U-7206</u>
Name: <u>RBU 15-16F</u>	API: <u>43-047-32971</u>	Entity: <u>7050</u>	S 16 T 10S R 20E	Lease: <u>U-7206</u>

OPERATOR CHANGE DOCUMENTATION

- YES 1. A pending operator change file has been set up.
- YES 2. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator on 6-29-00.
- YES 3. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 6-29-00.
- YES 4. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? **Yes/No** If yes, the company file number is SEE ATTACHED. If no, Division letter was mailed to the new operator on _____.

- YES 5. **Federal and Indian Leases Wells.** The BLM or the BIA has approved the merger, **name change** or operator change for all wells listed above involving Federal or Indian leases on 6-2-00.
- N/A 6. **Federal and Indian Units.** The BLM or the BIA has approved the successor of unit operator for all wells listed above involving unit operations on _____.
- N/A 7. **Federal and Indian Communitization Agreements ("CA").** The BLM or the BIA has approved the operator change for all wells listed above involved in the CA on _____.
- N/A 8. **Underground Injection Control ("UIC") Program.** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project and/or for the water disposal well(s) listed above.
- YES 9. Changes have been entered in the **Oil and Gas Information System** for each well listed on 8-1-00.
- YES 10. Changes have been included on the **Monthly Operator Change letter** on 8-1-00.

STATE BOND VERIFICATION

- N/A 1. State Well(s) covered by Bond No. _____.

FEE WELLS - BOND VERIFICATION / LEASE INTEREST OWNER NOTIFICATION

- N/A 1. (R649-3-1) The **NEW** operator of any fee lease well(s) listed above has furnished a proper bond.
- N/A 2. A **copy of this form** has been placed in the **new and former operator's bond files** on _____.
- N/A 3. The **FORMER** operator has requested a release of liability from their bond as of today's date _____? If yes, Division response was made to this request by letter dated _____. (see bond file).
- N/A 4. (R649-2-10) The **Former** operator of any Fee lease wells listed above has been contacted and informed by letter dated _____, of their responsibility to notify all interest owners of this change.
- N/A 5. Bond information added to **RBDMS** on _____.
- N/A 6. Fee wells attached to bond in **RBDMS** on _____.

FILMING

- _____ 1. All attachments to this form have been **microfilmed** on 2.23.01.

FILING

- _____ 1. **Originals/Copies** of all attachments pertaining to each individual well have been filed in each **well file**.
- _____ 2. The **original of this form** has been filed in the operator file and a copy in the old operator file.

COMMENTS

Dominion Exploration & Production, Inc.
Four Greenspoint Plaza
16945 Northchase Drive, Suite 1750, Houston, TX 77060-2133



Dominion™

October 11, 2000

CONFIDENTIAL

Mr. Ed Forsman
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: Sundries & Completion Reports

Dear Sir:

Attached are an original and two copies of the Well Completion Report and an original with three copies of each subsequent sundry for each of the following wells:

Evans Federal 10-25E
Federal 16-26A (sundries only)
Evans Federal 14-25E
RBU 14-23F
RBU 5-3F

Dominion is requesting that all information be held confidential.

If you have any questions or require additional information, please contact me at 281/873-3692.

Sincerely,

DOMINION EXPL. & PROD., INC.

Diann Flowers
Administrator, Regulatory Reports

Cc: Utah Board of Oil, Gas & Mining
Kevin Rupert
Ralph Hamrick
Genny Donaldson
Mitch Hall
Nelda Decker
Michael Nwaokobia
Joan Elterman
Deborah Thomas
Well Files

RECEIVED

OCT 16 2000

DIVISION OF
OIL, GAS AND MINING

SUBMIT IN DUPLICATE*
(See other instructions on reverse side)

FORM APPROVED
OMB NO. 1004-0137
Expires: February 28, 1995

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

5. LEASE DESIGNATION AND SERIAL NO.

U-01470-A

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

RIVERBEND UNIT

8. FARM OR LEASE NAME, WELL NO.

RBU 14-23F

9. API WELL NO.

43-047-33368

10. FIELD AND POOL, OR WILDCAT

NATURAL BUTTES 630

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

23-T10S-R20E

1a. TYPE OF WELL: OIL WELL GAS WELL DRY Other

b. TYPE OF COMPLETION: NEW DRILL WORK OVER DEEP-EN PLUG BACK DIFF. RESRV. Other

CONFIDENTIAL

2. NAME OF OPERATOR
DOMINION EXPL. & PROD., INC.

3. ADDRESS AND TELEPHONE NO.
CNG TOWER, 1450 POYDRAS STREET NEW ORLEANS, LA 70112

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface 793' FSL & 2405' FWL SE SW of Sec. 23-T10S-R20E
At top prod. interval reported below
At total depth

14. PERMIT NO. 43-047-33368
DATE ISSUED 08/20/99

12. COUNTY OR PARISH
UINTAH

13. STATE
UTAH

15. DATE SPUDDED 12/02/99
16. DATE T.D. REACHED 12/19/99
17. DATE COMPL. (Ready to prod.) 07/29/00
18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* GR: 5187'
19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD 8250'
21. PLUG, BACK T.D., MD & TVD 8154'
22. IF MULTIPLE COMPL., HOW MANY*
22. INTERVALS DRILLED BY
ROTARY TOOLS X
CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)*
CHAPITA WELLS 5484-5550 MESAVERDE 7350-8073
25. WAS DIRECTIONAL SURVEY MADE
NO

26. TYPE ELECTRIC AND OTHER LOGS RUN
27. WAS WELL CORED
NO

28. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
13-3/8"	54.5#	97'	17-1/2"	CONDUCTOR/SURFACE	
8-5/8" J-55	24.0#	3023'	12-1/4"	SURFACE; 675 SX	
5-1/2" L-80	17.0#	8250'	7-7/8"	SURFACE; 1362 SX	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-3/8"	5538'	NONE

31. PERFORATION RECORD (Interval, size and number)
INT 1: 8060-8073
INT 2: 7904-7922
INT 3: 7774-7786
INT 4: 7350-7360
INT 5: 5484-5550, 41"; 40 HOLES (New perfs this workover are as detailed: 5484-5490, 5522-5526, and 5540-5550)

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.
DEPTH INTERVAL (MD) 5484' - 5550'
AMOUNT AND KIND OF MATERIAL USED
Frac w/220,200# 20/40 Mesh Proppant

33.* PRODUCTION
DATE FIRST PRODUCTION 07/29/00
PRODUCTION METHOD (Flowing, gas lift, pumping - size and type of pump) FLOWING
WELL STATUS (Producing or shut-in) PRODUCING

DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL-BBL	GAS-MCF	WATER - BBL	GAS-OIL RATIO
09/21/00	24	15/64		-	888	8	-

FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL - BBL	GAS - MCF	WATER - BBL	OIL GRAVITY-API (CORR.)
965	1040		-	888	8	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)
SOLD
TEST WITNESSED BY
JAMES SWEAT

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records
SIGNED Diana Johnson TITLE REGULATORY REPORTS ADM. DATE 10/11/00

*(See Instructions and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

CONFIDENTIAL

38. GEOLOGIC MARKERS

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries); DESCRIPTION, CONTENTS, ETC.

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH	TOP	TRUE VERT. DEPTH
CHAPITA WELLS	5483	5490	GAS	WASATCH TONGUE	3951		
CHAPITA WELLS	5518	5526	GAS	GREEN RIVER TONGUE	4286		
CHAPITA WELLS	5538	5564	GAS	WASATCH	4428		
UTELAND BUTTES	6822	6840	GAS	CHAPITA WELLS	5152		
MESAVERDE	7350	7358	GAS	UTELAND BUTTES	6118		
MESAVERDE	7774	7788	GAS	MESAVERDE	7168		
MESAVERDE	7897	7929	GAS				
MESAVERDE	8058	8074	GAS				

OF THE
 UNITED STATES
 GEOLOGICAL SURVEY
 WASHINGTON, D. C. 20540

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposal to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
U-01470-A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
RIVERBEND UNIT

8. Well Name and No.
RBU 14-23F

9. API Well No.
43-047-33368

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

CONFIDENTIAL

2. Name of Operator
DOMINION EXPL. & PROD., INC.

3a. Address
**CNG TOWER 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000**

3b. Phone No. (include area code)
281/873-3692

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
**793' FSL & 2405' FWL
SE SW of Sec. 23-T10S-R20E**

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input checked="" type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>SUMMARY</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	OF ACTIVITY
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

SUMMARY OF ACTIVITY (07/17/00 THROUGH 09/19/00)

MIRU WO equipment. Blow well down. ND wellhead. Perforated 5484-5550, using 23 gram, 41 hole charges. Detailed perfs: 5484-5490, 5522-5526 and 5540-5550. Fracture treat 5484-5550 with 220200# 20/40 mesh proppant. Swabbed and flow tested well. RIH with 5-1/2" composite plug and set at 5390'. Drilled up two composite drill plugs and cleaned hole to PBDT of 8176'. Landed EOT at 5538'. ND BOPE and NU tree. All zones flowing to sales line.

Resumed Production on 09/19/00.

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)
DIANN FLOWERS

Title **REGULATORY REPORTS ADMINSTRATOR**

Date **10/10/00**

Signature *Diann Flowers*

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Office _____

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

7/1/2007

FROM: (Old Operator): N1095-Dominion Exploration & Production, Inc 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134 Phone: 1 (405) 749-1300	TO: (New Operator): N2615-XTO Energy Inc 810 Houston St Fort Worth, TX 76102 Phone: 1 (817) 870-2800
--	--

WELL NAME	CA No.	SEC	TWN	RNG	Unit:	API NO	ENTITY NO	LEASE TYPE	RIVER BEND	WELL TYPE	WELL STATUS
SEE ATTACHED LIST											

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/6/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/6/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/6/2007
- a. Is the new operator registered in the State of Utah: Business Number: 5655506-0143
- b. If **NO**, the operator was contacted on: _____
- a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: _____
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: _____
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 9/27/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/27/2007
- Bond information entered in RBDMS on: 9/27/2007
- Fee/State wells attached to bond in RBDMS on: 9/27/2007
- Injection Projects to new operator in RBDMS on: 9/27/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/27/2007

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000138
- Indian well(s) covered by Bond Number: n/a
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 104312762
- b. The **FORMER** operator has requested a release of liability from their bond on: 1/23/2008
The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

		5. LEASE DESIGNATION AND SERIAL NUMBER:
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: SEE ATTACHED
2. NAME OF OPERATOR: XTO Energy Inc. N2615		9. API NUMBER: SEE ATTACHED
3. ADDRESS OF OPERATOR: 810 Houston Street CITY Fort Worth STATE TX ZIP 76102		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective July 1, 2007, XTO Energy Inc. has purchased the wells listed on the attachment from:

Dominion Exploration & Production, Inc. **N1095**
14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134

James D. Abercrombie (405) 749-1300
James D. Abercrombie
Sr. Vice President, General Manager - Western Business Unit

Please be advised that XTO Energy Inc. is considered to be the operator on the attached list and is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands. Bond coverage is provided by Nationwide BLM Bond #104312750 and Department of Natural Resources Bond #104312762.

NAME (PLEASE PRINT) <u>Edwin S. Ryan, Jr.</u>	TITLE <u>Sr. Vice President - Land Administration</u>
SIGNATURE <i>Edwin S. Ryan, Jr.</i>	DATE <u>7/31/2007</u>

(This space for State use only)

APPROVED 9127107
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED
AUG 06 2007
DIV. OF OIL, GAS & MINING

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well name	qtr	qtr	sec	twp	rng	lease num	entity	Lease	well	stat
4304730087	OSCU 2	NWSE	03	100S	200E	U-037164	7050	Federal	GW	P	
4304730266	RBU 11-18F	NESW	18	100S	200E	U-013793	7050	Federal	GW	P	
4304730374	RBU 11-13E	NESW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304730375	RBU 11-15F	NESW	15	100S	200E	U-7206	7050	Federal	GW	P	
4304730376	RBU 7-21F	SWNE	21	100S	200E	U-013793-A	7050	Federal	GW	P	
4304730405	RBU 11-19F	NESW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304730408	RBU 11-10E	NESW	10	100S	190E	U-013792	7050	Federal	GW	P	
4304730410	RBU 11-14E	NESW	14	100S	190E	U-013792	7050	Federal	GW	P	
4304730411	RBU 11-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304730412	RBU 11-16F	NESW	16	100S	200E	U-7206	7050	Federal	GW	P	
4304730585	RBU 7-11F	SWNE	11	100S	200E	U-01790	7050	Federal	GW	P	
4304730689	RBU 11-3F	NESW	03	100S	200E	U-013767	7050	Federal	GW	P	
4304730720	RBU 7-3E	SWNE	03	100S	190E	U-013765	7050	Federal	GW	P	
4304730759	RBU 11-24E	NESW	24	100S	190E	U-013794	7050	Federal	GW	P	
4304730761	RBU 7-10F	SWNE	10	100S	200E	U-7206	7050	Federal	GW	P	
4304730762	RBU 6-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P	
4304730768	RBU 7-22F	SWNE	22	100S	200E	14-20-H62-2646	7050	Indian	GW	P	
4304730887	RBU 16-3F	SESE	03	100S	200E	U-037164	7050	Federal	GW	P	
4304730915	RBU 1-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	P	
4304730926	RBU 1-14E	NENE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304730927	RBU 1-22E	NENE	22	100S	190E	U-013792	7050	Federal	GW	P	
4304730970	RBU 1-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304730971	RBU 4-19F	NWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304730973	RBU 13-11F	SWSW	11	100S	200E	U-7206	7050	Federal	WD	A	
4304731046	RBU 1-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	S	
4304731115	RBU 16-16F	SESE	16	100S	200E	U-7206	7050	Federal	GW	P	
4304731140	RBU 12-18F	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P	
4304731141	RBU 3-24E	NENW	24	100S	190E	U-013794	7050	Federal	GW	P	
4304731143	RBU 3-23E	NENW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304731144	RBU 9-23E	NESE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304731145	RBU 9-14E	NESE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304731160	RBU 3-15E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P	
4304731161	RBU 10-15E	NWSE	15	100S	190E	U-013766	7050	Federal	GW	P	
4304731176	RBU 9-10E	NESE	10	100S	190E	U-013792	7050	Federal	GW	P	
4304731196	RBU 3-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304731252	RBU 8-4E	SENE	04	100S	190E	U-013792	7050	Federal	GW	P	
4304731322	RBU 1-19F	NENE	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304731323	RBU 5-10E	SWNW	10	100S	190E	U-013792	7050	Federal	GW	P	
4304731369	RBU 3-13E	NENW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304731518	RBU 16-3E	SESE	03	100S	190E	U-035316	7050	Federal	GW	P	
4304731519	RBU 11-11F	NESW	11	100S	200E	U-7206	7050	Federal	GW	P	
4304731520	RBU 1-17F	NENE	17	100S	200E	U-013769-B	7050	Federal	GW	P	
4304731605	RBU 9-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	P	
4304731606	RBU 3-22E	NENW	22	100S	190E	U-013792	7050	Federal	GW	P	
4304731607	RBU 8-24E	SENE	24	100S	190E	U-013794	7050	Federal	GW	P	
4304731608	RBU 15-18F	SWSE	18	100S	200E	U-013794	7050	Federal	GW	P	

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304731613	RBU 5-11F	SWNW	11	100S	200E	U-7206	7050	Federal	GW	P
4304731615	RBU 4-22F	NWNW	22	100S	200E	U-0143521-A	7050	Federal	GW	S
4304731652	RBU 6-17E	SWNW	17	100S	190E	U-03535	7050	Federal	GW	P
4304731715	RBU 5-13E	SWNW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731717	RBU 13-13E	SWSW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731739	RBU 9-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P
4304732033	RBU 13-14E	SWSW	14	100S	190E	U-013792	7050	Federal	GW	P
4304732037	RBU 11-3E	NESW	03	100S	190E	U-013765	7050	Federal	GW	P
4304732038	RBU 6-18F	SENW	18	100S	200E	U-013769	7050	Federal	GW	P
4304732040	RBU 15-24E	SWSE	24	100S	190E	U-013794	7050	Federal	GW	P
4304732041	RBU 5-14E	SWNW	14	100S	190E	U-013792	7050	Federal	GW	P
4304732050	RBU 12-20F	NWSW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732051	RBU 7-13E	SWNE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732070	RBU 16-19F	SESE	19	100S	200E	U-013769-A	7050	Federal	WD	A
4304732071	RBU 9-22E	NESE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732072	RBU 15-34B	SWSE	34	090S	190E	U-01773	7050	Federal	GW	P
4304732073	RBU 11-15E	NESW	15	100S	190E	U-013766	7050	Federal	GW	P
4304732074	RBU 13-21F	SWSW	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732075	RBU 10-22F	NWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304732081	RBU 9-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732082	RBU 15-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P
4304732083	RBU 13-24E	SWSW	24	100S	190E	U-013794	7050	Federal	GW	P
4304732095	RBU 3-21E	NENW	21	100S	190E	U-013766	7050	Federal	GW	P
4304732103	RBU 15-17F	SWSE	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732105	RBU 13-19F	SWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304732107	RBU 1-21E	NENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732128	RBU 9-21E	NESE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732129	RBU 9-17E	NESE	17	100S	190E	U-03505	7050	Federal	GW	P
4304732133	RBU 13-14F	SWSW	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732134	RBU 9-11F	NESE	11	100S	200E	U-7206	7050	Federal	GW	P
4304732138	RBU 5-21F	SWNW	21	100S	200E	U-013793	7050	Federal	GW	P
4304732146	RBU 1-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P
4304732149	RBU 8-18F	SENE	18	100S	200E	U-013769	7050	Federal	GW	P
4304732153	RBU 13-23E	SWSW	23	100S	190E	U-13766	7050	Federal	GW	P
4304732154	RBU 5-24E	SWNW	24	100S	190E	U-013794	7050	Federal	GW	P
4304732156	RBU 5-14F	SWNW	14	100S	200E	U-013793A	7050	Federal	GW	P
4304732166	RBU 7-15E	SWNE	15	100S	190E	U-013766	7050	Federal	GW	P
4304732167	RBU 15-13E	SWSE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732189	RBU 13-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P
4304732190	RBU 15-10E	SWSE	10	100S	190E	U-013792	7050	Federal	GW	P
4304732191	RBU 3-17FX	NENW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732197	RBU 13-15E	SWSW	15	100S	190E	U-013766	7050	Federal	GW	P
4304732198	RBU 7-22E	SWNE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732199	RBU 5-23E	SWNW	23	100S	190E	U-013766	7050	Federal	GW	P
4304732201	RBU 13-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	S
4304732211	RBU 15-15E	SWSE	15	100S	190E	U-013766	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr	qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304732213	RBU 5-19F	SWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304732217	RBU 9-17F	NESE	17	100S	200E	U-013769-C	7050	Federal	GW	P	
4304732219	RBU 15-14E	SWSE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304732220	RBU 5-3E	SWNW	03	100S	190E	U-03505	7050	Federal	GW	P	
4304732228	RBU 9-3E	NESE	03	100S	190E	U-035316	7050	Federal	GW	P	
4304732239	RBU 7-14E	SWNE	14	100S	190E	U-103792	7050	Federal	GW	P	
4304732240	RBU 9-14F	NESE	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732242	RBU 5-22E	SWNW	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732263	RBU 8-13E	SENE	13	100S	190E	U-013765	7050	Federal	GW	P	
4304732266	RBU 9-21F	NESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732267	RBU 5-10F	SWNW	10	100S	200E	U-7206	7050	Federal	GW	P	
4304732268	RBU 9-10F	NESE	10	100S	200E	U-7206	7050	Federal	GW	P	
4304732269	RBU 4-15F	NWNW	15	100S	200E	INDIAN	7050	Indian	GW	PA	
4304732270	RBU 14-22F	SESW	22	100S	200E	U-0143519	7050	Federal	GW	P	
4304732276	RBU 5-21E	SWNW	21	100S	190E	U-013766	7050	Federal	GW	P	
4304732289	RBU 7-10E	SWNE	10	100S	190E	U-013792	7050	Federal	GW	P	
4304732290	RBU 5-17F	SWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P	
4304732293	RBU 3-3E	NENW	03	100S	190E	U-013765	7050	Federal	GW	P	
4304732295	RBU 13-22E	SWSW	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732301	RBU 7-21E	SWNE	21	100S	190E	U-013766	7050	Federal	GW	P	
4304732309	RBU 15-21F	SWSE	21	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732310	RBU 15-20F	SWSE	20	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732312	RBU 9-24E	NESE	24	100S	190E	U-013794	7050	Federal	GW	P	
4304732313	RBU 3-20F	NENW	20	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732315	RBU 11-21F	NESW	21	100S	200E	U-0143520-A	7050	Federal	GW	P	
4304732317	RBU 15-22E	SWSE	22	100S	190E	U-013792	7050	Federal	GW	P	
4304732328	RBU 3-19FX	NENW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304732331	RBU 2-11F	NWNE	11	100S	200E	U-01790	7050	Federal	GW	P	
4304732347	RBU 3-11F	NENW	11	100S	200E	U-7206	7050	Federal	GW	P	
4304732391	RBU 2-23F	NWNE	23	100S	200E	U-013793-A	7050	Federal	GW	S	
4304732392	RBU 11-14F	NESW	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732396	RBU 3-21F	NENW	21	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732407	RBU 15-14F	SWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732408	RBU 4-23F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732415	RBU 3-10EX (RIG SKID)	NENW	10	100S	190E	UTU-035316	7050	Federal	GW	P	
4304732483	RBU 5-24EO	SWNW	24	100S	190E	U-013794	11719	Federal	OW	S	
4304732512	RBU 8-11F	SENE	11	100S	200E	U-01790	7050	Federal	GW	P	
4304732844	RBU 15-15F	SWSE	15	100S	200E	14-20-H62-2646	7050	Indian	GW	P	
4304732899	RBU 3-14F	NENW	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732900	RBU 8-23F	SENE	23	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732901	RBU 12-23F	NWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P	
4304732902	RBU 1-15F	NENE	15	100S	200E	U-7260	7050	Federal	GW	S	
4304732903	RBU 3-15F	NENW	15	100S	200E	U-7260	7050	Federal	GW	P	
4304732904	RBU 9-15F	NESE	15	100S	200E	U-7260	7050	Federal	GW	P	
4304732934	RBU 3-10F	NENW	10	100S	200E	U-7206	7050	Federal	GW	P	
4304732969	RBU 11-10F	NESW	10	100S	200E	U-7206	7050	Federal	GW	P	

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well name	qtr	qtr	sec	twp	rng	lease num	entity	Lease	well	stat
4304732970	RBU 12-15F	NWSW	15	100S	200E	U-7206	7050	Federal	GW	P	
4304732971	RBU 15-16F	SWSE	16	100S	200E	U-7206	7050	Federal	GW	S	
4304732972	RBU 1-21F	NENE	21	100S	200E	U-013793-A	7050	Federal	GW	P	
4304732989	RBU 13-10E	SWSW	10	100S	190E	U-013792	7050	Federal	GW	P	
4304732990	RBU 13-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P	
4304732991	RBU 6-19F	SENW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304733033	RBU 7-23E	NWNE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304733034	RBU 9-18F	NESE	18	100S	200E	U-013794	7050	Federal	GW	P	
4304733035	RBU 14-19F	SESW	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304733087	RBU 6-23F	SENW	23	100S	200E	U-013793-A	7050	Federal	GW	P	
4304733088	RBU 1-10F	NENE	10	100S	200E	U-7206	7050	Federal	GW	P	
4304733089	RBU 8-22F	SENE	22	100S	200E	U-0143521	7050	Federal	GW	P	
4304733090	RBU 11-22F	NESW	22	100S	200E	U-0143519	7050	Federal	GW	P	
4304733091	RBU 16-22F	SESE	22	100S	200E	U-01470-A	7050	Federal	GW	P	
4304733156	RBU 4-14E	NWNW	14	100S	190E	U-013792	7050	Federal	GW	P	
4304733157	RBU 7-19F	SWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P	
4304733158	RBU 7-20F	SWNE	20	100S	200E	U-013793-A	7050	Federal	GW	P	
4304733159	RBU 7-24E	SWNE	24	100S	190E	U-013794	7050	Federal	GW	P	
4304733160	RBU 8-15E	SENE	15	100S	190E	U-013766	7050	Federal	GW	P	
4304733161	RBU 16-10E	SESE	10	100S	190E	U-013792	7050	Federal	GW	P	
4304733194	RBU 2-14E	NWNE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304733272	RBU 13-3F	SWSW	03	100S	200E	U-013767	7050	Federal	GW	P	
4304733361	RBU 5-3F	SWNW	03	100S	200E	U-013767	7050	Federal	GW	P	
4304733362	RBU 15-10F	SWSE	10	100S	200E	U-7206	7050	Federal	GW	P	
4304733363	RBU 5-16F	SWNW	16	100S	200E	U-7206	7050	Federal	GW	P	
4304733365	RBU 12-14E	NWSW	14	100S	190E	U-013792	7050	Federal	GW	P	
4304733366	RBU 5-18F	SWNW	18	100S	200E	U-013769	7050	Federal	GW	P	
4304733367	RBU 10-23F	NWSE	23	100S	200E	U-01470-A	7050	Federal	GW	P	
4304733368	RBU 14-23F	SESW	23	100S	200E	U-01470-A	7050	Federal	GW	S	
4304733424	RBU 5-20F	SWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P	
4304733643	RBU 2-13E	NWNE	13	100S	190E	U-013765	7050	Federal	GW	P	
4304733644	RBU 4-13E	NWNW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304733714	RBU 4-23E	NWNW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304733715	RBU 6-13E	SENW	13	100S	190E	U-013765	7050	Federal	GW	P	
4304733716	RBU 10-14E	NWSE	14	100S	190E	U-013792	7050	Federal	GW	P	
4304733838	RBU 8-10E	SENE	10	100S	190E	U-013792	7050	Federal	GW	P	
4304733839	RBU 12-23E	NWSW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304733840	RBU 12-24E	NWSW	24	100S	190E	U-013794	7050	Federal	GW	P	
4304733841	RBU 14-23E	SESW	23	100S	190E	U-013766	7050	Federal	GW	P	
4304734302	RBU 1-23F	NENE	23	100S	200E	UTU-013793-A	7050	Federal	GW	P	
4304734661	RBU 16-15E	SESE	15	100S	190E	U-013766	7050	Federal	GW	P	
4304734662	RBU 10-14F	NWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P	
4304734663	RBU 6-14E	SENW	14	100S	190E	U-013792	7050	Federal	GW	P	
4304734670	RBU 8-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304734671	RBU 4-24E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P	
4304734701	RBU 12-11F	SENW	11	100S	200E	U-7206	7050	Federal	GW	P	

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304734702	RBU 2-15E	NWNE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734703	RBU 4-17F	NWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734745	RBU 10-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734749	RBU 7-18F	SWNE	18	100S	200E	U-013769	7050	Federal	GW	P
4304734750	RBU 12-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P
4304734810	RBU 10-13E	NWSE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734812	RBU 1-24E	NENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734826	RBU 12-21F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734828	RBU 4-15E	NWNW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734844	RBU 14-14E	SESW	14	100S	190E	U-013792	7050	Federal	GW	P
4304734845	RBU 10-24E	NWSE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734888	RBU 4-21E	NWNW	21	100S	190E	U-013766	7050	Federal	GW	P
4304734889	RBU 16-24E	SESE	24	100S	190E	U-13794	7050	Federal	GW	P
4304734890	RBU 12-18F2	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734891	RBU 10-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304734892	RBU 8-22E	SENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304734906	RBU 6-22E	SENW	22	100S	190E	U-013792	7050	Federal	GW	P
4304734907	RBU 2-24E	NWNE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734910	RBU 4-16F	NWNW	16	100S	200E	U-7206	7050	Federal	GW	P
4304734911	RBU 12-19F	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734912	RBU 14-20F	SESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734942	RBU 1-22F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304734945	RBU 8-19F	SENE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734946	RBU 8-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304734962	RBU 12-17F	NWSW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734963	RBU 2-17F	NWNE	17	100S	200E	U-013769-C	14117	Federal	GW	P
4304734966	RBU 14-18F	SESW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734967	RBU 10-18F	NWSE	18	100S	200E	U-013794	7050	Federal	GW	P
4304734968	RBU 10-19F	NWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734969	RBU 10-3E	NWSE	03	100S	190E	U-035316	7050	Federal	GW	P
4304734970	RBU 12-3E	NWSW	03	100S	190E	U-013765	7050	Federal	GW	P
4304734971	RBU 15-3E	SWSE	03	100S	190E	U-35316	7050	Federal	GW	P
4304734974	RBU 12-10E	NWSW	10	100S	190E	U-013792	14025	Federal	GW	P
4304734975	RBU 14-10E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734976	RBU 16-13E	SESE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734977	RBU 8-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304734978	RBU 6-15E	SENW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734979	RBU 12-15E	NWSW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734981	RBU 16-17E	SESE	17	100S	190E	U-013766	7050	Federal	GW	P
4304734982	RBU 8-21E	SENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304734983	RBU 4-22E	NWNW	22	100S	190E	U-013792	7050	Federal	GW	P
4304734986	RBU 2-20F	NWNE	20	100S	200E	U-03505	7050	Federal	GW	P
4304734987	RBU 9-20E	SWNW	21	100S	190E	U-03505	7050	Federal	GW	P
4304734989	RBU 7-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P
4304734990	RBU 8-20E	SWNW	21	100S	190E	U-03505	14164	Federal	GW	P
4304735041	RBU 16-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304735042	RBU 12-22E	NWSW	22	100S	190E	U-013792	14165	Federal	GW	P
4304735058	RBU 7-23F	SWNE	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304735059	RBU 12-13E	NWSW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735060	RBU 14-13E	SESW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735061	RBU 2-22E	NWNE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735062	RBU 6-24E	SESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304735082	RBU 4-17E	NWNW	17	100S	190E	U-03505	7050	Federal	GW	P
4304735086	RBU 16-14E	NENE	23	100S	190E	U-013792	7050	Federal	GW	P
4304735087	RBU 2-3E	NWNE	03	100S	190E	U-013765	7050	Federal	GW	P
4304735088	RBU 6-3E	SESW	03	100S	190E	U-03505	7050	Federal	GW	P
4304735100	RBU 10-10E	NWSE	10	100S	190E	U-013792	7050	Federal	GW	P
4304735101	RBU 16-22E	SESE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735112	RBU 14-24E	SESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304735129	RBU 6-21F	SESW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735170	RBU 1-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P
4304735171	RBU 16-9E	NESE	09	100S	190E	U-013765	7050	Federal	GW	P
4304735232	RBU 14-21F	SESW	21	100S	200E	U-0143520	7050	Federal	GW	P
4304735250	RBU 13-19F2	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735251	RBU 15-19F	SWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735270	RBU 16-21E	SESE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735304	RBU 13-20F	SWSW	20	100S	200E	U-013769	7050	Federal	GW	P
4304735305	RBU 4-21F	NWNW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735306	RBU 16-21F	SESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304735468	RBU 15-22F	SWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304735469	RBU 11-23F	SESW	23	100S	200E	U-01470A	7050	Federal	GW	P
4304735549	RBU 1-14F	NENE	14	100S	200E	UTU-013793-A	7050	Federal	GW	P
4304735640	RBU 2-21E	NWNE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735644	RBU 10-17E	NWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304735645	RBU 12-21E	NWSW	21	100S	190E	U-013766	7050	Federal	GW	P
4304736200	RBU 8-17E	SWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736201	RBU 15-17EX	SWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736293	RBU 2-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	P
4304736294	RBU 6-10E	NENW	10	100S	190E	U-013792	7050	Federal	GW	P
4304736296	RBU 6-21E	SESW	21	100S	190E	U-013766	7050	Federal	GW	P
4304736297	RBU 10-22E	NWSE	22	100S	190E	U-013792	7050	Federal	GW	P
4304736318	RBU 14-22E	SESW	22	100S	190E	U-013792	7050	Federal	GW	P
4304736427	RBU 9-15E	NESE	15	100S	190E	U-013766	7050	Federal	GW	DRL
4304736428	RBU 2-17E	NWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736429	RBU 1-17E	NENE	17	100S	190E	U-013766	7050	Federal	GW	DRL
4304736432	RBU 3-19F2	NWNW	19	100S	200E	U-013769-A	15234	Federal	GW	P
4304736433	RBU 14-17F	SESW	17	100S	200E	U-03505	7050	Federal	GW	P
4304736434	RBU 2-19F	NWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304736435	RBU 5-19FX	SWNW	19	100S	200E	U-013769-A	15855	Federal	GW	P
4304736436	RBU 4-20F	NWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304736605	RBU 16-14F	SESE	14	100S	200E	U-013793A	7050	Federal	GW	P
4304736608	RBU 4-3E	NWNW	03	100S	190E	U-035316	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304736609	RBU 8-3E	SENE	03	100S	190E	U-013765	7050	Federal	GW	P
4304736610	RBU 14-3E	SESW	03	100S	190E	U-013765	7050	Federal	GW	P
4304736686	RBU 13-3E	NWSW	03	100S	190E	U-013765	15235	Federal	GW	P
4304736810	RBU 1-3E	NENE	03	100S	190E	U-013765	7050	Federal	GW	DRL
4304736850	RBU 2-10F	NWNE	10	100S	200E	U-7206	7050	Federal	GW	P
4304736851	RBU 8-21F	SENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304737033	RBU 4-10E	SWNW	10	100S	190E	U-035316	7050	Federal	GW	P
4304737057	RBU 11-17E	NWSE	17	100S	190E	U-03505	7050	Federal	GW	DRL
4304737058	RBU 3-17E	NENW	17	100S	190E	U-03505	7050	Federal	GW	P
4304737201	RBU 3-23F	NENW	23	100S	200E	U-013793-A	7050	Federal	OW	P
4304737341	RBU 11-20F	NESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304737342	RBU 5-15F	SWNW	15	100S	200E	U-7206	7050	Federal	OW	P
4304737343	RBU 10-16F	NWSE	16	100S	200E	U-7206	7050	Federal	OW	P
4304737344	RBU 9-16F	NESE	16	100S	200E	U-7206	7050	Federal	OW	S
4304737450	RBU 14-17E	SESW	17	100S	190E	U-03505	7050	Federal	GW	P
4304737747	RBU 15-9E	NWNE	16	100S	190E	U-013765	7050	Federal	GW	DRL
4304737893	RBU 9-4EA	SENE	04	100S	190E	U-03505	7050	Federal	GW	P
4304737998	RBU 13-23F	SWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304738181	RBU 12-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL
4304738182	RBU 11-4E	SE/4	04	100S	190E	U-03505	99999	Federal	GW	DRL
4304738294	RBU 2-4E	NWNE	04	100S	190E	U-013792	7050	Federal	GW	DRL
4304738295	RBU 5-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL
4304738543	RBU 28-18F	NESE	13	100S	190E	U 013793-A	7050	Federal	GW	DRL
4304738548	RBU 32-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	DRL
4304738555	RBU 27-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738556	RBU 27-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738557	RBU 30-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304738558	RBU 29-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738595	RBU 31-10E	NENE	15	100S	190E	U-013792	7050	Federal	GW	DRL
4304738596	RBU 17-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	DRL
4304738780	RBU 8B-17E	SENE	17	100S	190E	U-013766	7050	Federal	GW	DRL

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr	qtr	sec	twp	rng	lease_num	entity	Lease	well	stat
4304730153	NATURAL 1-2	SE	NW	02	100S	200E	ML-10716	11377	State	OW	PA
4304730260	RBU 11-16E	NE	SW	16	100S	190E	ML-13214	7050	State	GW	S
4304730583	RBU 11-36B	NE	SW	36	090S	190E	ML-22541	99998	State	NA	PA
4304730608	RBU 8-16D	SE	NE	16	100S	180E	ML-13216	99998	State	NA	PA
4304730760	RBU 11-2F	NE	SW	02	100S	200E	ML-10716	9966	State	OW	S
4304731740	RBU 1-16E	NE	NE	16	100S	190E	ML-13214	7050	State	GW	P
4304732026	RBU 16-2F	SE	SE	02	100S	200E	ML-10716	7050	State	GW	P
4304732042	RBU 9-16E	NE	SE	16	100S	190E	ML-13214	7050	State	GW	P
4304732108	RBU 14-2F	SE	SW	02	100S	200E	ML-10716	7050	State	GW	P
4304732136	RBU 8-2F	SE	NE	02	100S	200E	ML-10716	7050	State	GW	P
4304732137	RBU 5-16E	SW	NW	16	100S	190E	ML-13214	7050	State	GW	P
4304732245	RBU 7-16E	SW	NE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732250	RBU 13-16E	SW	SW	16	100S	190E	ML-13214	7050	State	GW	S
4304732292	RBU 15-16E	SW	SE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732314	RBU 10-2F	NW	SE	02	100S	200E	ML-10716	7050	State	GW	P
4304732352	RBU 3-16F	NE	NW	16	100S	200E	ML-3393-A	7050	State	GW	P
4304733360	RBU 1-16F	NE	NE	16	100S	200E	ML-3393	7050	State	GW	P
4304734061	RBU 6-16E	SW	NE	16	100S	190E	ML-13214	7050	State	GW	P
4304734167	RBU 1-2F	NE	NE	02	100S	200E	ML-10716		State	GW	LA
4304734315	STATE 11-2D	NE	SW	02	100S	180E	ML-26968		State	GW	LA
4304734903	RBU 14-16E	SW	SW	16	100S	190E	ML-13214	7050	State	D	PA
4304735020	RBU 8-16E	SE	NE	16	100S	190E	ML-13214	7050	State	GW	P
4304735021	RBU 10-16E	SW	SE	16	100S	190E	ML-13214	7050	State	GW	P
4304735022	RBU 12-16E	NE	SW	16	100S	190E	ML-13214	7050	State	GW	P
4304735023	RBU 16-16E	SW	SW	15	100S	190E	ML-13214	7050	State	GW	P
4304735033	RBU 2-16E	NW	NE	16	100S	190E	ML-13214	7050	State	GW	P
4304735081	RBU 15-2F	SW	SE	02	100S	200E	ML-10716	7050	State	GW	P
4304735348	RBU 13-16F	NW	NW	21	100S	200E	ML-3394	7050	State	GW	DRL
4304736169	RBU 4-16E	NE	NW	16	100S	190E	ML-13214	7050	State	GW	P
4304736170	RBU 3-16E	NE	NW	16	100S	190E	ML-13214	7050	State	GW	P



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

Dominion Exploration & Production, Inc.
Attn: James D. Abercrombie
14000 Quail Springs Parkway, #600
Oklahoma City, OK 73134-2600

August 10, 2007

Re: River Bend Unit
Uintah County, Utah

Gentlemen:

On August 8, 2007, we received an indenture dated June 30, 2007, whereby Dominion Exploration & Production, Inc. resigned as Unit Operator and XTO Energy Inc. was designated as Successor Unit Operator for the River Bend Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective August 15, 2007. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the River Bend Unit Agreement.

Your statewide oil and gas bond No. UTB000138 will be used to cover all operations within the River Bend Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Greg J. Noble

Greg J. Noble
Acting Chief, Branch of Fluid Minerals

Enclosure

RECEIVED
AUG 16 2007
DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-01470-A
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: RIVER BEND
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 14-23F
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047333680000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3159 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0793 FSL 2405 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 23 Township: 10.0S Range: 20.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/15/2010	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: PWOP

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to acidize & put this well on a pump with the intent of increasing production. Please see the attached procedure.

Accepted by the Utah Division of Oil, Gas and Mining

Date: June 07, 2010

By: *Don K. [Signature]*

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 5/26/2010	

**RBU 14-23F PWOP
 Sec 23, T 10S, R 20 E
 Uintah County, Utah
 API- 43-047-33368
 XTO # 162592**

AFE # 1002985

Put well on pump

Surf csg: 8-5/8", 32#, J-55, ST&C csg @ 3023' Cmt to surface
Prod csg: 5-1/2", 17#, L-80, LT&C csg @ 8250' PBDT 8154'
Tbg: 2-3/8" N-80 EUE tubing w/ SN; EOT @ 7998'
WA: 5484'-90', 5522'-26', 5540'-50'
MV: 7350'-60', 7774'-86', 7904'-08', 7914'-22', 8060'-73'

Note: Initial MV completion C/O to 8154', no BRS left in hole; later WA completion may have left BRS in hole. Watch for top half BRS on tubing.

PWOP Procedure

- 1) MI and set a Lufkin C160-200-74 pumping unit (min ECB 15,200#) with a C-96 engine. Sheave unit to run 3 SPM in the 74" stroke. Set CB weights as follows:

Description	Weight	Position
Left Lag	3 CRO + 1-3BS	12" from end of crank
Left Lead	3 CRO + 1-3BS	12" from end of crank
Right Lag	3 CRO + 1-3BS	12" from end of crank
Right Lead	3 CRO + 1-3BS	12" from end of crank

- 2) MIRU PU. Blow down casing and kill well w/ 2% KCl. ND WH, NU BOP. Unseat tubing hanger. Lower tubing to tag, then tally out of hole. Monitor tubing for indications of scale or corrosion. If heavy scale is seen, round trip bit & scraper to clean out. If BRS is in hole, TIH with short wash shoe and drill down to ±8200'. Circulate hole clean, POH.

- 3) TIH w/ "TS" bridge plug, "HD" packer, and 2 3/8" tubing. Treat individual zones per below table. After stages are treated, release tools and POH.

Packer Depth Ft	Plug Depth Ft	Perforations Ft	Acid Gal	Flush BBL
5454	5589	5484-5550	598	24
7320	7390	7350-7360	299	31
7744	7816	7774-7786	359	33
7874	7952	7904-7922	358	33
8030	8103	8060-8073	386	34
Total			2000	155

Note: 2000 gal 15% HCL to contain: 5 g/1000 MA-844, 20 g/1000 EGBME mutual solvent, FE 200 & FE 100 iron sequesterant, CI 350 corrosion inhibitor for 48 hrs protection at 180 °F, and 150 gal Nalco EC6652 scale inhibitor.

- 4) RIH with production string as follows:
- 2 3/8" x 5 1/2" TEC tubing anchor
 - 2 3/8" x 6' EUE tubing sub
 - 2 3/8" x 4' EUE perforated tubing sub
 - 2 3/8" x 1.78" S/N
 - 2 3/8" 4.7# EUE L-80 tubing to surface

Land tubing in tension with TAC at ±8125'. ND BOP, NU wellhead.

- 5) Swab tubing until returns are clean and able to be pumped. RIH w/ pump and rod string as follows:
- 2"x 1 1/4"x 16' x 19' RHBC, w/ 8' dip tube
 - 3/4" x 4' rod sub
 - 3/4" – 21,000 lb HF shear tool
 - 8- 1 1/4" API K Sinker Rods
 - 60 - 3/4" Norris 96 Rods w/ "T" couplings, 5 molded guides/rod
 - 257 - 3/4" Norris 96 Rods w/ "T" couplings
 - 3/4" Norris 96 Pony rods as necessary to space out
 - 1 1/4" x 22' Polish rod w/ 1 1/2" liner
- 6) Space out pump as required with pony rods. Load tubing and long stroke with rig to ensure pump action. RDMO PU.
- 7) Start well pumping at 3 SPM and 74" SL. Run dyno and shoot fluid level ± 1 week after unit has started.
- 8) Report pre and post start up data to Tom Boyce

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-01470-A
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: RIVER BEND
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RBU 14-23F
2. NAME OF OPERATOR: XTO ENERGY INC	9. API NUMBER: 43047333680000
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410	PHONE NUMBER: 505 333-3159 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0793 FSL 2405 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 23 Township: 10.0S Range: 20.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/8/2010	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: CLEANOUT & PWOP

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 XTO Energy Inc. has cleaned out, acidized & put this well on a pumping unit per the attached summary report.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 July 20, 2010

NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 7/12/2010	

Riverbend Unit 14-23F

6/10/2010: First rpt to PWOP. MIRU Temples WS rig #1. Bd well. Ppd dwn csg w/40 bbls TFW & KW. ND WH & NU BOP. TIH w/5 jts 2-3/8" tbg, tgd fill @ 8120'. TOH w/174 jts 2-3/8" 4.7#, N-80, EUE, 8rd tbg, 73 jts 2-3/8" 4.7#, J-55, EUE, 8rd tbg, 2-3/8" SN & 2-3/8" mule shoe col. Tbg showed lt external sc BU fr/ 5178' to 7375' & Hvy external sc BU fr/ 7465' to EOT @ 7997'. Smpl taken for analysis. Recd BHBS in SN. TIH w/ 4-3/4" bit, 5-1/2" csg scr & 113 jts 2-3/8" tbg. EOT @ 3512'. SWI & SDFN.

6/11/2010: Bd well. Contd TIH w/124 jts 2-3/8" tbg, tgd sc bridge @ 7362'. RU pwr swvl & AFU. Att to estab circion w/no success. Bd tbg press. Att to unplg tbg using rig pmp w/no success. TOH w/8 jts 2-3/8" tbg. Att to clear plgd tbg using rig pmp w/no success. RU & RIH w/swb tls. Swbd tbg dry to 7000' FS. Contd TOH w/229 jts 2-3/8" tbg, 2-3/8" SN, 5-1/2" csg scr & 4-3/4" bit. SN was plgd w/sd & sc. Cln tls. TIH w/4-3/4" bit, 5-1/2" csg scr, 2-3/8" SN & 100 jts 2-3/8" tbg. EOT @ 3100'. SWI & SDFWE.

6/14/2010: Contd TIH w/ 132 jts 2-3/8" tbg, tgd sc bridge @ 7362'. RU pwr swvl & AFU. Estb circion. CO multiple sc bridges on perms fr/ 7362' to 8080' & 80' of fill fr/ 8120' to 8200'. Circ hole cln for 1-1/2 hr's. Ppd dwn tbg w/ 15 bbls TFW & kld tbg. RD pwr swvl & AFU. TOH w/ 96 jts 2-3/8" tbg. EOT @ 5424'. SWI & SDFN.

6/15/2010: Bd well. TIH w/96 jts 2-3/8" tbg. EOT @ 8097'. Drop SV & PT tbg to 3000 psig w/27 bbls TFW, 5". Tstd ok. Bd tbg press. RU & RIH w/fishing tls on sd ln, retrv SV. POH & LD fishing tl & SV. TOH w/260 jts 2-3/8" tbg, 2-3/8" SN, 5-1/2" csg scr & 4-3/4" bit. LD tls. PU & TIH w/ 5-1/2" RBP, pkr, 2-3/8" SN & 168 jts 2-3/8" tbg. EOT @ 5250'. SWI & SDFN.

6/16/2010: Bd well. Contd TIH w/92 jts 2-3/8" tbg. MIRU Frac Tech ac equ. PT surf equip to 5000 psig. Proceed w/5 stage ac trtmnt as follows: Stage #1. Isol MV perms fr/8060' - 8073'. Trtd perms w/386 gals 15% HCL ac w/adds, mutual solvent, iron seq, corr inhib & sc inhib. Flshd w/34 bbls TFW. Max trtg press 3420 psig @ 1.6 BPM. ISIP 2350 psig, 5" SIP 866 psig. Stage #2. Move tls & isol MV perms fr/7904' - 7922'. Trtd perms w/358 gals 15% HCL ac w/ adds, mutual solvent, iron seq, corr inhib & sc inhib. Flshd w/33 bbls TFW. Max trtg press 3009 psig @ 2.7 BPM. ISIP 2257 psig, 5" SIP 0 psig. Stage #3. Move tls & Isol MV perms fr/7774' - 7786'. Trtd perms w/359 gals 15% HCL ac w/adds mutual solvent, iron seq, corr inhib & sc inhib. Flshd w/33 bbls TFW. Max trtg press 3029 psig @ 1.4 BPM. ISIP 2736 psig, 5" SIP 1459 psig. Stage #4. Move tls & Isol MV perms fr/7350' - 7360'. Trtd perms w/299 gals 15% HCL ac w/adds, mutual solvent, iron seq, corr inhib & sc inhib. Flshd w/31 bbls TFW. Max trtg press 3009 psig @ 3.4 BPM. ISIP 1960 psig, 5" SIP 0 psig. Stage #5. Move tls & Isol WA perms fr/5484' - 5550'. Trtd perms w/598 gals 15% HCL ac w/adds, mutual solvent, iron seq, corr inhib & sc inhib. Flshd w/24 bbls TFW. Max trtg press 666 psig @ 4.9 BPM. ISIP 0 psig. Rltd tls. TOH w/14 jts 2-3/8" tbg. EOT @ 5250'. SWI & SDFN Due to high winds.

6/17/2010: Bd well. Ppd dwn csg w/30 bbls TFW & KW. Contd TOH w/168 jts 2-3/8" tbg, 2-3/8" SN, 5-1/2" RBP & pkr. LD tls. TIH w/2-3/8" mule shoe col, 5-1/2" SH TAC, 6' x 2-3/8" 4.7#, N-80, EUE, 8rd tbg sub, 4' x 2-3/8" 4.7#, N-80, EUE, 8rd, perf tbg sub, 2-3/8" SN, 84 jts 2-3/8" 4.7#, J-55, EUE, 8rd tbg, 175 jts 4.7#, N-80, EUE, 8rd tbg, 8' x 2-3/8" 4.7#, N-80, EUE, 8rd, tbg sub & 1 jt 2-3/8" 4.7#, L-80, EUE, 8rd tbg. EOT @ 8125'. RU & RIH w/ XTO 1.901 tbg broach to SN. No ti spots. POH & LD broach. ND BOP. Set 5-1/2" SH TAC @ 8125' w/12 K tens. NU WH. SN @ 8110'. EOT @ 8125'. WA perms fr/5484' - 5550'. MV perms fr/7350' - 8073'. PBTD @ 8200'. RU & RIH w/swb tls. BFL @ 5000' FS. S. 0 BO, 7 BLW, 2 runs, 1 hr. Smpl taken. Blk wtr, hvy solids (sc), tr of O, PH 7. FFL @ 5000' FS. SICP 0 psig. SWI & SDFN.

6/18/2010: RU & RIH w/ swb tls. BFL @ 4600' FS. S,0 BO, 72 BLW, 20 runs, 8 hrs. Smpl taken. Brown gas cut wtr, hvy solids, (corr & sc), tr of O. PH 7. FFL @ 6600' FS. SICP 280 psig. SWI & SDFWE.

6/21/2010: SD fr/7:00 AM to 9:00 AM, Due to rig reps. RU & RIH w/swb tls. BFL @ 5600' FS. S. 0 BO, 50 BLW, 12 runs, 6 hrs. Fld smpls of brown gas cut wtr, lt solids, tr of O, PH 7. FFL @ 6600' FS. SICP 300 psig. SWI & SDFN.

6/22/2010: RU & RIH w/swb t/s. BFL @ 6600' FS. S. 0 BO, 8 BLW, 2 runs, 1 hr. Fld smpls of brown gas cut wtr, tr of solids, tr of O, PH 7. FFL @ 6600' FS. SICP 300 psig. PU & loaded new 2" x 1-1/4" x 16' x 19' RHBC pmp (XTO # 287) w/ 8' x 1" GAC. TIH w/pmp, 1- 7/8" x 4' rod stabilizer sub, 26 K shear tl, 1- 7/8" x 4' rod stabilizer sub, 8 - 1-1/4" APIK sbs w/T 410 cplg, 60 - 3/4" Norris 96 skr d w/ " T " cplg, 5 molded guides per rod, 255 - 3/4" Norris 96 slick skr d w/ " T " cplg, 2 - 3/4" rod subs (4', 2') & 1-1/4" x 26' PR w/1.5" x 14' lnr. Seated pmp & SWO. PT tbg to 500 psig w/23 BW. LS pmp to 1000 psig w/rig. Gd PA. SWO & clamped off rods for PU installation. SWI. RDMO Temples WS rig # 1. Rpt suspnd, turn well over to facilities.

7/8/2010: The River Bend Unit 14-23F PWOP. Stroke length 74", 3.00 SPM. This well is on Route #211. XTO allocation Meter # RS 1047 RF. RTU Group 10. Address 207. Waynes Check CDP Meter #RS1264CT. RWTP @ 12:00 p.m., 7/8/10. IFR 140 MCFPD, FTP 295 psig, FCP 411 psig.

=====**Riverbend Unit 14-23F**=====

End of Report