


**HANKEN
ENERGY
CORPORATION**

417 W. 18th Street, Suite 101
Edmond, Oklahoma 73013-3663
(405) 340-2363 • Fax (405) 340-2365



February 15, 2000

Utah Division of Oil, Gas & Mining
P O Box 145801
Salt Lake City, UT 84114-5801

RE: APD's
Uintah County, Utah

Dear Sir(s):

Enclosed please find four (4) completed APD's, in triplicate, for the wells we are currently wishing to drill on our Fee acreage block. The surface is owned by the DWR and we have also sent a copy to their office in Salt Lake City as well as their Vernal office.

I hope you find everything in order but please do not hesitate to call should you have any questions whatsoever. Thank you for your continued support.

Sincerely,

A handwritten signature in black ink, appearing to read "Randolph L. Coy". The signature is fluid and cursive.

Randolph L. Coy
President

RLC:jr
enc.

(utogm2rc)

RECEIVED

FEB 16 2000

DIVISION OF
OIL, GAS AND MINING

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR PERMIT TO DRILL OR DEEPEN		5. Lease Designation and Serial Number: Fee	
		6. If Indian, Allottee or Tribe Name:	
1A. Type of Work: DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/>		7. Unit Agreement Name:	
B. Type of Well: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER: SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>		8. Farm or Lease Name:	
2. Name of Operator: RANKEN ENERGY CORPORATION		9. Well Number: Ranken Energy DWR 14-28	
3. Address and Telephone Number: 417 W. 18th St., Ste. 101, Edmond, OK 73013-3663 405/340-2363		10. Field and Pool, or Wildcat:	
4. Location of Well (Footages) At Surface: 1246' FSL & 2032' FWL At Proposed Producing Zone: 4400086N 641425E		11. Cr/Cr, Section, Township, Range, Meridian: SE/4 SW/4 Section 28-T18S-R23E 123	
14. Distance in miles and direction from nearest town or post office:		12. County: Uintah	13. State: UTAH
15. Distance to nearest property or lease line (feet): 5982'	16. Number of acres in lease: 10903	17. Number of acres assigned to this well: 40	
18. Distance to nearest well, drilling, completed, or applied for, on this lease (feet): 1700'	19. Proposed Depth: 3500'	20. Rotary or cable tools: Rotary	
21. Elevations (show whether DF, RT, GR, etc.): 5661' Ground level		22. Approximate date work will start: April 15, 2000	

23. **PROPOSED CASING AND CEMENTING PROGRAM**

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24	300'	To surface
7 7/8"	4 1/2"	10.5	T.D.	Cement top to cover the oil shale

DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

Operator requests permission to drill the subject well. Please see the attached 10 Point & 13 Point Surface Use Plan.

RECEIVED

FEB 16 2000

DIVISION OF
OIL, GAS AND MINING

24. **Randolph L. Coy**
Name & Signature: *Randolph L. Coy* Title: President Date: 2/14/00

(This space for State use only)

API Number Assigned: 43-042-33483

Approval:

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 2/25/00
By: *[Signature]*

T12S, R23E, S.L.B.&M.

RANKEN ENERGY CORP.

Well location, DWR #14-28, located as shown in the SE 1/4 SW 1/4 of Section 28, T12S, R23E, S.L.B.&M. Uintah County, Utah.

1922 Brass Cap,
2.0' High, Pile
of Stones

N89°48'16"W 2657.57' (Meas.)

N89°52'W - 40.06 (G.L.O.)

1922 Brass
Cap, 20.' High,
No Stones


BASIS OF ELEVATION

BENCH MARK 82 EAM LOCATED IN THE SW 1/4 SW 1/4 OF SECTION 21, T12S, R23E, S.L.B.&M. TAKEN FROM THE ARCHY BENCH SE. QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5584 FEET.

N00°09'W - G.L.O. (Basis of Bearings)
2642.32' - (Measured)

N00°06'46"W 2638.83' (Meas.)

N00°08'W - (G.L.O.)



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert J. Key
REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 01-31-00	DATE DRAWN: 02-09-00
PARTY D.K. L.J. D.R.B.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE RANKEN ENERGY CORP.	

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
BITTER CREEK NO. 5
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
BITTER CREEK NO. 6
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
BITTER CREEK NO. 7
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
BITTER CREEK NO. 8
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
BITTER CREEK NO. 9
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
HYDROCARBON NO. 7
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
HYDROCARBON NO. 8
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
HYDROCARBON NO. 9
160 AC

STATE OF UTAH
DNR
DEPT. OF WILDLIFE
RESOURCES
HYDROCARBON NO. 10
160 AC

28

DWR #14-28
Elev. Ungraded Ground = 5661'

N89°55'W - 40.00 (G.L.O.)

NOTE:
THE PROPOSED WELL HEAD BEARS
N58°32'03"E 2379.65' FROM THE
SOUTHWEST CORNER OF SECTION
28, T12S, R23E, S.L.B.&M.

LATITUDE = 39°44'27"
LONGITUDE = 109°20'58"

1922 Brass Cap
2.0' High, Pile
of Flat Stones

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.


SELF-CERTIFICATION STATEMENT

Please be advised that Ranken Energy Corporation are considered to be the Operator of the following well.

Ranken Energy DWR 14-28
SE/4 SW/4, Section 28-T12S-R23E
Lease Fee
Uintah County, Utah

Ranken Energy Corporation is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands.

Bond N 6258 provides state-wide bond coverage on all Fee and State Lands.



RANDOLPH L. COY

President

Ranken Energy Corporation
417 West 18th Street, Suite 101
Edmond, OK 73013-3663

405/340-2363

405/340-2365, fax

exp65@swbell.net, e-mail

(135671)
lc

Ten Point Plan

Ranken Energy Corporation

Ranken Energy DWR 14-28

Surface Location: SE/4 SW/4 Section 28-T12S-R23E

1. Surface Formation:

Green River

2. Estimated Formation Tops and Datum:

<u>Formation</u>	<u>Depth</u>	<u>Datum</u>
Green River	Surface	+5661', G.L.
Oil Shale	700'	+4961'
Wasatch	2061'	+3600'
T.D.	3500'	+2161'

3. Producing Formation Depth:

Formation objective includes the Wasatch and their sub-members.

Offset Well Information: Producing from a Wasatch sand found at 2000'.

Offset well: Ranken Energy - DWR 5-28

4. Proposed Casing:

<u>Hole Size</u>	<u>Casing Size</u>	<u>Grade Weight/Ft.</u>	<u>Setting & Thread</u>	<u>Casing Depth</u>	<u>New/Used</u>
12 1/4	8 5/8	24	J-55/STC	300	New
7 7/8	4 1/2	10.5	J-55/LTC	T.D.	New

Cementing Program:

<u>Casing Size</u>	<u>Cement Type</u>	<u>Cement Amount</u>	<u>Cement Yield</u>	<u>Cement Weight</u>
8 5/8	Prem. Plus 2% Calcium Chloride .25 lb/sx Flocele	207 sx +/-	1.20 cu. ft/sx	15.6 lbs./gal
4 1/2	2% Bentonite, .25 lb/sx Flocele, .3% CFR-3, .5% Halad-9, 2% Micro-Bond, .2% Super CBL	670 sx +/-	1.24 cu. ft/sx	14.50 lbs/gal

5. BOP and Pressure Containment Data:

The anticipated bottom hole pressure will be less than 3000 psi.

A 3000-psi WP BOP system as described in the BOP and Pressure Containment Data (attached) will be installed and maintained from the 8 5/8" surface casing. The BOP system including the casing will be pressure tested to the minimum standards set forth in "On Shore Order #2". The BOP will be mechanically checked daily during the drilling operation.

6. Mud Program:

<u>Interval</u>	<u>Mud weight lbs./gal.</u>	<u>Viscosity Sec./Ot.</u>	<u>Fluid Loss M1/30 Mins.</u>	<u>Mud Type</u>
0-300	Air/Clean Wtr	---	No control	Water/gel
300-1800	Clear Water	---	No control	Water/gel
1800-T.D.	8.4 - 8.6	30	8 - 10	Water/gel

7. Auxiliary Equipment:

Upper Kelly cock, full opening stabbing valve, 2 1/2" choke manifold and pit level indicator.

8. Testing, Coring, Sampling and Logging:

- a) Test: None are anticipated.
- b) Coring: There is the possibility of sidewall coring.
- c) Sampling: Every 10' from 1900' to T.D.
- d) Logging:

<u>Type</u>	<u>Interval</u>
DLL/SFL W/GR and SP	T.D. to Surface Casing
FDC/CNL W/GR and CAL	T.D. to Surface Casing

9. Abnormalities (including sour gas):

No abnormal pressures, temperatures or other hazards are anticipated. Oil and gas shows are anticipated in the Wasatch and Mesaverde formation. Other wells drilled in the area have not encountered over pressured zones or H₂S.

10. Drilling Schedule:

The anticipated starting date is April 15, 2000. Duration of operations expected to be 20 days.

(utah adps:dwr 14-28)

RANKEN ENERGY CORPORATION

13 POINT SURFACE USE PLAN

FOR WELL

RANKEN ENERGY - DWR 14-28

LOCATED IN

SE/4, SW/4

SECTION 28-T12S-R23E, U.S.B&M.

UINTAH COUNTY, UTAH

LEASE NUMBER: FEE

SURFACE OWNERSHIP:

**STATE OF UTAH
DIVISION OF WILDLIFE RESOURCES**

1. Existing Roads

To reach the Ranken Energy Corporation well DWR 14-28, in Section 28-T12S-R23E, from Bonanza, Utah:

Starting in Bonanza, Utah, proceed south on the paved road for 4 miles. Turn south (left) on the Book Cliffs road (dirt road). Proceed south 3.9 miles to the Greeks Corrals. Turn west (right) at the fork in the road. Proceed 8.3 miles to the Asphalt Wash sign. Stay to the south (left) of the sign. Proceed .7 miles to the Rainbow sign. Stay to the west (right) of the sign. This is also called the Kings Well road. Turn south (left). Proceed 1.7 miles. Turn west (right). Proceed 4.0 miles. The proposed access road will start at this point.

All existing roads to the proposed location are State or County Class D roads.

Please see the attached map for additional details.

2. Planned access road

The proposed location will require approximately 1584 feet of new road construction on DWR ground.

The road will be built to the following standards:

- A) Approximate length 1584 Ft.
- B) Right of Way width 30 Ft.
- C) Running surface 18 Ft.
- D) Surfacing material Native soil
- E) Maximum grade 5%
- F) Fence crossing None

- G) Culvert None
- H) Turnouts None
- I) Major cuts and fills None
- J) Road flagged Yes
- K) Access road surface ownership

1584'..... State of Utah, Division of Wildlife Resources

- L) All new construction on lease Yes
- M) Pipe line crossing None

Please see the attached location plat for additional details.

Right of way's will be required for the access road. A right-of-way application for both the location and road has been made to the Division of Wildlife Resources.

3. Location of existing wells

The following wells are located within a one mile radius of the location site:

- A) Producing well: Ranken Energy - DWR 5-28
- B) Water well None
- C) Abandoned well None
- D) Temp. abandoned well None
- E) Disposal well None
- F) Drilling/Permitted well None
- G) Shut-in wells None
- H) Injection well None
- I) Monitoring or observation well None

Please see the attached map for additional details.

4. Location of tank batteries, production facilities, and production gathering service lines.

All production facilities are to be contained within the proposed location site. Please see the attached plat plan for a typical gas well separator installation and well-site piping.

All permanent (on site for more than six months or longer) structures constructed or installed will be painted a **Juniper Green** or **Desert Tan** color. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

All tanks will be surrounded by a dike of sufficient capacity to contain the storage capacity of the largest tank in the battery. The integrity of the dike will be maintained.

If the well is capable of economic production, a surface gas line will be required.

A proposed line will be constructed from the subject well and will tie into Ranken's Meter (CDP) at their DWR 5-28 wellsite.

Approximately 1584' of 2" or 4" gathering line would be constructed on DWR lands.

Please see the attached location diagrams and map for pipeline location. The Operator proposes to bury the line under the surface. The Operator will install the line on DWR lands only. The route would be approximately the same length.

A gas check meter run will be located within 500' of the well head. The gas line will be buried or anchored down from the well head to the meter. Meter runs will be housed and/or fenced.

The gas meter will be calibrated and the tank strapped in place prior to any deliveries. All measurement facilities will conform to API (American Petroleum Institute) and AGA (American Gas Association) standards for gas and liquid hydrocarbon measurement.

5. Location and type of water supply

Water for drilling and cementing the subject well will be trucked or piped from Bitter Creek in Sec. 28-T12S-R23E. Permit # T72132. A second location may be used. It would be Evacuation Creek permit #49-1595. The Evacuation Creek distribution point is in Sec. 7-T11S-R25E. Water for completion will come from the same supply or Vernal City.

Water may be used from two existing test wells next to Bitter Creek. The wells are adjacent to the water take out point. Water quality tests will have to be performed before the water can be used.

6. Source of construction materials

All construction material for this location site and access road shall be borrowed material accumulated during construction of the location site and access road. Additional road gravels or pit lining material will be obtained from private sources.

7. Methods for handling waste disposal

A) Pit construction and liners:

The reserve pit will be approximately 10 feet deep and most of the depth shall be below the surface of the existing ground. Please see the attached plat for details.

The reserve pit will be lined, if necessary.

The reserve pit will not be used to store water for drilling. A semi-closed system will be used to drill the well. All fresh water for drilling will come from a frac tank placed on location and from the rig tank. The pit will be used to hold non-flammable materials such as cuttings, salt, drilling fluids, chemicals, produced from fluids, etc.

B) Produced fluids:

Produced water will be confined to the reserve pit, or if deemed necessary, a storage tank for a period not to exceed 90 days after initial production. Produced water will be trucked to a State of Utah approved disposal pit or well.

C) Garbage:

A trash cage fabricated from expanded metal will be used to hold trash on location and will be removed to an authorized land fill location.

D) Sewage:

A portable chemical toilet will be supplied for human waste. The

human waste facilities will be permitted through Uintah County Health Department and disposal of human waste will conform with the county permit.

E) Site clean-up:

After the rig is moved off the location, the well site area will be cleaned and all refuse removed.

8. **Ancillary facilities**

There are no ancillary facilities planned at this time and none are foreseen for the future.

9. **Well-site layout and location**

The proposed location has been staked at 1246' FSL & 2032' FWL.

Well-site layout

Location dimensions are as follows:

- A) Pad length 300 ft.
- B) Pad width 150 ft.
- C) Pit depth 10 ft.
- D) Pit length 156 ft.
- E) Pit width 30 ft.
- F) Max cut 12.0 ft.
- G) Max fill 14 ft.
- H) Total cut yds. 12060 cu yds
- I) Pit location southwest side
- J) Top soil location: south & southwest end
- K) Access road location: northwest end
- L) Flare pit corner B

Please see the attached location diagram for additional details.

All pits will be fenced according to the following minimum standards:

- A) Thirty-nine inch net wire shall be used with at least one strand of wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- B) The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C) Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- D) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- E) All wire shall be stretched by using a stretching device before it is attached to the corner posts.

10. Plans for restoration of the surface

Prior to construction of the location, the top 6 inches of soil material will be stripped off the location and the pit area. The topsoil removed and piled will amount to approximately 1000 cubic yards of material. **Topsoil will be stock-piled in one distinct pile.** Placement of the topsoil is noted on the attached location plat. **The topsoil pile from the location will be seeded as soon as the soil is stock piled with the seed mix listed.** When all drilling and completion activities have been completed and the

pit back-filled, the topsoil from the pit area will be spread on the pit area. **The pit area will be seeded when the soil has been spread.** The unused portion of the location (the area outside the dead men) will be recontoured.

The dirt contractor will be provided with an approved copy of the surface use plan prior to construction activities.

Changes to the drainage during the construction activities shall be restored to its original line of flow or as near as possible when the pit is back-filled.

All disturbed areas will be recontoured to the approximate natural contours. Prior to back-filling the pit, the fences around the reserve pit will be removed.

The reserve pit will be reclaimed within 90 days of well completion. If the reserve pit has not dried sufficiently to allow back-filling, an extension on the time requirement for back-filling the pit will be requested. Once reclamation activities have begun, they shall be completed within 30 days.

After the reserve pit has been reclaimed, no depressions in the soil covering the reserve pit will be allowed. The objective is to keep seasonal rainfall and runoff from seeping into the soil used to cover the reserve pit. Diversion ditches and water bars will be used to divert runoff as needed.

When restoration activities have been completed, the location site and new access road cuts and shoulders shall be reseeded. Prior to reseeding, all disturbed areas will be scarified and left with a rough surface.

- A) Seeding Dates: Seed will be spread when the top soil is stock piled and when reclamation work is performed.

The seed mix and quantity required will be provided by the Division of Wildlife Resources.

- B) Seed Mix: At such time as the well is plugged and abandoned, the Operator will submit a surface reclamation plan to the surface management agency for prescribed seed mixture and reseeding requirements.

11. Surface ownership:

Access road: **DWR**

Location: **State of Utah Division of Wildlife Resources**

Pipeline: **DWR**

12. Other information

- A) Vegetation:

The vegetation coverage is slight. The majority of the existing vegetation consists of sagebrush. Rabbit brush, bitter brush and Indian rice grass are also found on the location.

- B) Dwellings:

There are no dwellings or other facilities within a one mile radius of the location.

- C) Archeology and Paleontology:

The location has been surveyed with copies enclosed.

If, during operations, any archaeological or historical sites, or any objects of antiquity (subject to the antiquities act of June 8, 1906) are discovered, all operations which would effect such sites will be suspended and the discovery reported promptly to the surface management agency.

- D) Water:

The nearest water is the Bitter Creek 1 mile west of the location.

- E) Chemicals:

No pesticides, herbicides or other possible hazardous chemicals will be used without the Division of Wildlife Resources approval.

- F) Notification:

The Division of Wildlife Resources and the Division of Oil, Gas and Mining will be notified as follows:

- a) **Location construction**

At least forty-eight (48) hours prior to construction of location and access roads.

- b) **Location completion**

Prior to moving on the drilling rig.

- c) **Spud notice**

At least twenty-four (24) hours prior to spudding the well.

- d) **Casing string and cementing**

At least twenty-four (24) hours prior to running casing and cementing all casing strings.

e) **BOP and related equipment tests**

At least twenty-four (24) hours prior to initial pressure tests.

f) **First production notice**

Within five (5) business days after the new well begins, or production resumes after well has been off production for more than ninety (90) days.

g) **Completion and work over**

At least twenty-four (24) hours prior to moving on location.

Division of Wildlife Resources
(434)789-3103

Division of Oil, Gas and Mining
(801)538-5340 or (435)722-3417

H) Flare pit:

The flare pit will be located in corner C of the reserve pit outside the pit fence and 75 feet from the bore hole on the **southwest side of location**. All fluids will be removed from the pit within forty-eight (48) hours of occurrence.

13. **Leases or Operator's representative and certification**

A) Representative

William A. Ryan

Rocky Mountain Consulting
350 South 800 East
Vernal, UT 84078

Office: (435)789-0968
Fax (435)789-0970
Cellular (435)828-0968

All lease operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

This drilling permit will be valid for a period of one year from the date of approval. After permit termination, a new application will be filed for approval for any future operations.

B) Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill-site and access route, that I am familiar with the conditions which presently exist, that the statements made in this plan are, to the best of my knowledge and belief, true and correct, and that the work associated with the operation herein will be performed by **Ranken Energy Corporation** and its contractors and subcontractors in conformity with this plan and terms and conditions with this plan and the terms and conditions under which it is approved.


Date: _____


William A. Ryan, Agent
Rocky Mountain Consulting

Onsite Date: _____

(utah adps:dwr 14-28)

Ranken Energy
Typical
Gas Well






RANKEN ENERGY CORP.

LOCATION LAYOUT FOR

DWR #14-28

SECTION 28, T12S, R23E, S.L.B.&M.

1246' FSL 2032' FWL



SCALE: 1" = 50'
DATE: 02-09-00
Drawn By: D.R.B.


Sta. 3+25

F-3.1'
El. 56.3'


C-24.6'
El. 84.0'

C-13.9'
El. 73.3'

Topsoil Stockpile



Approx. Top of Cut Slope



C-7.5'
FLARE PIT El. 66.9'

El. 76.1'
C-26.7'
(btm. pit)

PIPE RACKS

CATWALK


DATA

175'

C-1.4'
El. 60.8'

Sta. 1+50

Pit Capacity With 2' of Freeboard is 3,720 Bbls. ±



RIG DOG HOUSE

100'

F-12.1'
El. 47.3'

Approx. Toe of Fill Slope

MUD TANKS

WATER

PUMP

MUD SHED

TOILET

TRAILER

HOPPER

POWER

TOOLS

Sta. 0+50

FUEL

STORAGE TANK

Round Corners as Needed

TRASH

Sta. 0+00

El. 70.6'
C-21.2'
(btm. pit)

F-0.7'
El. 58.7'

F-9.4'
El. 50.0'

Topsoil Stockpile

F-15.9'
El. 43.5'

Reserve Pit Backfill & Spoils Stockpile

Proposed Access Road

Elev. Ungraded Ground at Location Stake = 5660.8'
Elev. Graded Ground at Location Stake = 5659.4'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

RANKEN ENERGY CORP.

TYPICAL CROSS SECTIONS FOR


DWR #14-28

SECTION 28, T12S, R23E, S.L.B.&M.

1246' FSL 2032' FWL

1" = 20'
X-Section
Scale
1" = 50'

DATE: 02-09-00
Drawn By: D.R.B.




APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 940 Cu. Yds.
Remaining Location	= 11,120 Cu. Yds.
TOTAL CUT	= 12,060 CU.YDS.
FILL	= 10,040 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	= 1,490 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 1,490 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



LEGEND:

○ PROPOSED LOCATION


UeLs **Uintah Engineering & Land Surveying**
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



RANKEN ENERGY CORP.

DWR #14-28
SECTION 28, T12S, R23E, S.L.B.&M.
1246' FSL 2032' FWL

TOPOGRAPHIC **2 8 00**
MAP **MONTH DAY YEAR**
SCALE: 1:100,000 **DRAWN BY: J.L.G.** **REVISED: 00-00-00** **A**
TOPO



LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING ROAD



RANKEN ENERGY CORP.

DWR #14-28
 SECTION 28, T12S, R23E, S.L.B.&M.
 1246' FSL 2032' FWL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
 MAP**

2	8	00
MONTH	DAY	YEAR

SCALE: 1" = 2000' DRAWN BY: J.L.G. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 1300' +/-

LEGEND:

- EXISTING PIPELINE
- - - PROPOSED PIPELINE
- PROPOSED ACCESS



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



RANKEN ENERGY CORP.

DWR #14-28
 SECTION 28, T12S, R23E, S.L.B.&M.
 1246' FSL 2032' FWL

**TOPOGRAPHIC
MAP**

2 8 00
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: J.L.G. REVISED: 00-00-00



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 02/16/2000

API NO. ASSIGNED: 43-047-33483

WELL NAME: DWR 14-28
 OPERATOR: RANKEN ENERGY CORP (N6250)
 CONTACT: RANDOLPH COY

PHONE NUMBER: 405-340-2363

PROPOSED LOCATION:
 SESW 28 120S 230E
 SURFACE: 1246 FSL 2032 FWL
 BOTTOM: 1246 FSL 2032 FWL
 UINTAH
 UNDESIGNATED (2)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	<i>RJK</i>	3-27-00
Geology		
Surface		

LEASE TYPE: 4-Fee
 LEASE NUMBER: FEE
 SURFACE OWNER: 3-State / DWR

PROPOSED FORMATION: WSTC

RECEIVED AND/OR REVIEWED:


Plat
 Bond: Fed[] Ind[] Sta[] Fee[4]
 (No. 135671)
 Potash (Y/N)
 Oil Shale (Y/N) *190 - 5 (B)
 Water Permit
 (No. T72132)
 RDCC Review (Y/N)
 (Date: _____)
 Fee Surf Agreement (Y/N)

LOCATION AND SITING:

___ R649-2-3. Unit _____
 ___ R649-3-2. General
 Siting: _____
 R649-3-3. Exception
 ___ Drilling Unit
 Board Cause No: _____
 Eff Date: _____
 Siting: _____
 ___ R649-3-11. Directional Drill

COMMENTS: Need Presite. (Conducted 3/10/00)


STIPULATIONS: ① STATEMENT OF BASIS



Utah Oil Gas and Mining

Serving the Industry, Protecting the Environment

OPERATOR: RANKEN ENERGY (N6250)
FIELD: UNDESIGNATED (002)
S EC. 16, 21 & 28, T 12 S, R 23 E
COUNTY: UINTAH UNIT: HANGING ROCK



PREPARED
DATE: 17-Feb-2000


RECEIVED

FEB 22 2000

**RANKEN
ENERGY
CORPORATION**

DIVISION OF
OIL, GAS AND MINING

417 W. 18th Street, Suite 101
Edmond, Oklahoma 73013-3663
(405) 340-2363 • Fax (405) 340-2365



February 18, 2000

Utah Division of Oil, Gas & Mining
1594 West North Temple, Suite 1210
P O Box 145801
Salt Lake City, UT 84114-5801

RE: DWR 14-28
SE/4 SW/4 Sec. 28-T12S-R23E
Uintah County, Utah
Lease Fee

Dear Sirs:

Ranken Energy Corporation respectfully requests a spacing location exception for the subject well. The well has been moved from the center of the SE/4 SW/4 due to topographic considerations and access conditions. Please see attached map.

The well is currently staked 1246' FSL and 2032' FWL in Section 28-T12S-R23E. The location falls 386' to the north, outside of the 200' radius rule to the center of the 40 acre unit. The southerly direction is within the 200' window. A 460' radius around the proposed location is well within our Fee acreage lease.

Please do not hesitate to call should you have any questions whatsoever. Thank you for your consideration.

Sincerely,

A handwritten signature in black ink, appearing to read "Randolph L. Coy". The signature is fluid and cursive.

Randolph L. Coy
President

RLC:jr
enc.

cc: Mr. Bill Ryan

(utogmrc)

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: RANKEN ENERGY CORP.

WELL NAME & NUMBER: DWR 14-28

API NUMBER: 43-047-33483

LEASE: FEE **FIELD/UNIT:**

LOCATION: 1/4,1/4 SE/SW SEC:28 TWP:12S RNG: 23E

1246' F S L 2032' F W L

LEGAL WELL SITING: Statewide 400 foot window in center of 40
acre tract and no closer than 920 feet from
another well.

GPS COORD (UTM): 12641350E 4400296N

SURFACE OWNER: DIVISION OF WILDLIFE RESOURCES

PARTICIPANTS:

BILL RYAN (RANKEN), JACK LYTLE (DWR), DAVID HACKFORD (DOGM),
NATALIE GALE, (DWR).

REGIONAL/LOCAL SETTING & TOPOGRAPHY:

SITE IS IN THE MOUTH OF A CANYON RUNNING WEST TOWARD BITTER
CREEK 500 FEET AWAY. A DRY STREAM BED RUNS DOWN CANYON ADJACENT
TO SITE. THERE ARE STEEP SLOPES TO THE NORTH AND EAST.

SURFACE USE PLAN:

CURRENT SURFACE USE: WILDLIFE AND LIVESTOCK GRAZING.
HUNTING.

PROPOSED SURFACE DISTURBANCE: LOCATION WOULD BE 325' BY 185'
AND ACCESS ROAD WOULD BE 0.3 MILES OF NEW CONSTRUCTION.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: SEE
ATTACHED MAP FROM GIS DATABASE

LOCATION OF PRODUCTION FACILITIES AND PIPELINES:
ALL PRODUCTION FACILITIES WILL BE ON LOCATION AND ADDED
AFTER DRILLING WELL. PIPELINE WILL FOLLOW ACCESS ROAD.

SOURCE OF CONSTRUCTION MATERIAL: ALL CONSTRUCTION MATERIAL
WILL BE BORROWED FROM SITE DURING CONSTRUCTION OF LOCATION.

ANCILLARY FACILITIES: NONE WILL BE REQUIRED.

WASTE MANAGEMENT PLAN:

DRILLED CUTTINGS WILL BE SETTLED INTO RESERVE PIT. LIQUIDS FROM PIT WILL BE ALLOWED TO EVAPORATE. FORMATION WATER WILL BE CONFINED TO STORAGE TANKS. SEWAGE FACILITIES, STORAGE AND DISPOSAL WILL BE HANDLED BY COMMERCIAL CONTRACTOR. TRASH WILL BE CONTAINED IN TRASH BASKETS AND HAULED TO AN APPROVED LAND FILL.

ENVIRONMENTAL PARAMETERS:

AFFECTED FLOODPLAINS AND/OR WETLANDS: NONE

FLORA/FAUNA: NATIVE GRASSES, GREASEWOOD, PRICKLY PEAR, CHEAT GRASS, SHADSCALE: SONG BIRDS, RAPTORIAL BIRDS, RODENTS, COYOTES, DEER, ELK, PRONGHORN, COUGAR, BOBCATS.

SOIL TYPE AND CHARACTERISTICS: LIGHT BROWN SANDY CLAY LOAM WITH VERY LIGHT SHALE ROCKS.

EROSION/SEDIMENTATION/STABILITY: MINOR NATURAL EROSION ON STEEP SLOPE TO THE EAST. SEDIMENTATION AND STABILITY ARE NOT A PROBLEM AND LOCATION CONSTRUCTION SHOULDN'T CAUSE ANY INCREASE IN STABILITY OR EROSION PROBLEMS.

PALEONTOLOGICAL POTENTIAL: NONE OBSERVED. SUE ANN BILBY FROM THE VERNAL MUSEUM OF NATURAL HISTORY WILL PERFORM A PALEO STUDY FOR RANKEN AT DWR REQUEST.

RESERVE PIT:

CHARACTERISTICS: 156' BY 30' AND 10'DEEP.

LINER REQUIREMENTS (Site Ranking Form attached): A LINER WILL NOT BE REQUIRED.

SURFACE RESTORATION/RECLAMATION PLAN:

AS PER LANDOWNER AGREEMENT OR AS DIRECTED BY DIVISION.

SURFACE AGREEMENT: A SURFACE AGREEMENT HAS NOT BEEN SIGNED AT THIS TIME.

CULTURAL RESOURCES/ARCHAEOLOGY: SITE WILL BE INSPECTED BY SAGE-BRUSH CONSULTING. A REPORT OF THIS INVESTIGATION WILL BE PLACED ON FILE.

OTHER OBSERVATIONS/COMMENTS:

THE PRE-DRILL INVESTIGATION TOOK PLACE ON A WARM SUNNY DAY.

ATTACHMENTS:

PHOTOS OF SITE WILL BE PLACED ON FILE.


DAVID W. HACKFORD
DOG M REPRESENTATIVE


3/10/00 2:30PM
DATE/TIME


**Evaluation Ranking Criteria and Ranking Score
For Reserve and On-site Pit Liner Requirements**


<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>10</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	15	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>0</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	15	
TDS >10000 or Oil Base	20	
Mud Fluid containing high levels of hazardous constituents		<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility		
Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>
Final Score		<u>15</u>











**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS**

Operator Name: RANKEN ENERGY CORP.

Well Name & Number: DWR #14-28

API Number: 43-047-33483

Location: 1/4,1/4 SE/SW Sec. 28 T. 12S R. 23E

Geology/Ground Water:

Ranken Energy has proposed setting 300 feet of 8 5/8" surface casing which will be cemented to surface at this location. The base of the moderately saline groundwater is estimated to be at a depth of 3100 feet. This is near the proposed total depth of this well in the Wasatch formation. A search of Division of Water Rights records show no water wells within 10,000 feet of the center of Section 28. The proposed surface casing program should adequately protect Ground water resources in the area.

Reviewer: Brad Hill

Date: 3/23/00

Surface:

The pre-drill investigation of the surface was performed on 3/10/00. The Division of Wildlife Resources is the surface owner, and they were represented by Jack Lytle and Natalie Gale. Mr. Lytle stated that all DWR concerns and stipulations would be addressed in the Landowner Agreement. The nearest moving water to this site is Bitter Creek 500 feet to the west. Access road to this site will cross Bitter Creek. A bridge or culvert will be necessary. Exception spacing requested to keep well a safe distance from Bitter Creek.

Reviewer: David W. Hackford

Date: 3/14/00

Conditions of Approval/Application for Permit to Drill:

1. The operator must contact Army Corp of Engineers concerning creek crossing.

3-00 Ranken DWR ~~11~~
Casing Schematic 14-28

Surface

8-5/8"
MW 8.3
Frac 19.3

TOC @
0.

~ 22%

Surface
300. MD

TOC @
720.

~ 10%

Cement tops with
% hole
washout

4-1/2"
MW 8.6

Production
3500. MD

UTAH DIVISION OF WATER RIGHTS
WATER RIGHT POINT OF DIVERSION PLOT CREATED THU, MAR 23, 2000, 4:04 PM
PLOT SHOWS LOCATION OF 4 POINTS OF DIVERSION

PLOT OF AN AREA WITH A RADIUS OF 10000 FEET FROM A POINT
FEET, FEET OF THE CT CORNER,
SECTION 28 TOWNSHIP 12S RANGE 23E SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 4000 FEET

N O R T H

**

**

*

*

*

*

*

*

*

*

*

*

*

*

*

*

0

1

2

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*


*

*

*

*

*



UTAH DIVISION OF WATER RIGHTS
 NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	QUANTITY CFS	AND/OR AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER DEPTH YEAR LOG	POINT OF DIVERSION DESCRIPTION NORTH EAST CNR SEC TWN RNG B&M
0	49 113	.0000	250000.00	White River & Tributaries	N 2620 E 1700 SW 21 12S 23E SL
				WATER USE(S): DOMESTIC MINING POWER	PRIORITY DATE: 05/19/196
				State of Utah Board of Water Resources	1594 West North Temple, Ste 310 Salt Lake City
0	49 304	.0000	105000.00	White River & tributaries	N 2620 E 1700 SW 21 12S 23E SL
				WATER USE(S): DOMESTIC POWER OTHER	PRIORITY DATE: 05/19/196
				State of Utah Board of Water Resources	1594 West North Temple, Ste 310 Salt Lake City
1	49 1560	.0000	10.00	Bitter Creek	N 700 E 500 SW 21 12S 23E SL
				WATER USE(S): OTHER	PRIORITY DATE: 07/26/199
				Jim Nebeker Trucking	Route 2 Box 2060 Roosevelt
2	49 1633	.0000	10.00	Bitter Creek	N 300 E 800 SW 21 12S 23E SL
				WATER USE(S): OTHER	PRIORITY DATE: 05/12/199
				Dalbo Inc.	P. O. Box 1168 Vernal

Well name:

3-00 Ranken DWR ~~14-28~~ 14-28

Operator: Ranken Energy Corporation

String type: Surface

Project ID:

43-047-3348 3

Location: Uintah Co.

Design parameters:

Collapse

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 79 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 300 ft

Cement top: 1 ft

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.433 psi/ft
Calculated BHP 130 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 262 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 300 ft
Next mud weight: 8.330 ppg
Next setting BHP: 130 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 300 ft
Injection pressure 300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	300	8.625	24.00	J-55	ST&C	300	300	7.972	14.4
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	130	1370	10.56	130	2950	22.73	6	244	38.74 J

Prepared by: Bob Krueger
Utah Dept. of Natural Resources

Phone: (801) 538-5274
FAX: (801) 359-3940

Date: March 27, 2000
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.
Collapse is based on a vertical depth of 300 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes.
Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	3-00 Ranken DWR 421 14-28		
Operator:	Ranken Energy Corporation		
String type:	Production	Project ID:	43-047-3348 3 3
Location:	Uintah Co.		

Design parameters:

Collapse

Mud weight: 8.600 ppg
 Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
 Surface temperature: 75 °F
 Bottom hole temperature: 124 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 1,500 ft

Cement top: 720 ft

Burst

Max anticipated surface pressure: 0 psi
 Internal gradient: 0.447 psi/ft
 Calculated BHP 1,564 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.80 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.

Neutral point: 3,052 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft ³)
1	3500	4.5	10.50	J-55	ST&C	3500	3500	3.927	73.1
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1564	4010	2.56	1564	4790	3.06	37	132	3.59 J

Prepared by: Bob Krueger
 Utah Dept. of Natural Resources

Phone: (801) 538-5274
 FAX: (801) 359-3940

Date: March 27, 2000
 Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.
 Collapse is based on a vertical depth of 3500 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes.
 Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

SAGEBRUSH CONSULTANTS, L.L.C.

Cultural Resources • Environmental Studies • Historic Preservation



March 27, 2000

John Basa
Utah Division of Oil, Gas and Minerals
P.O. Box 145801
1594 West North Temple, Suite 210
Salt Lake City, Utah 84114-5801

RE: A Cultural Resource Survey of Ranken Energy Wells DWR #12-28, DWR #14-28,
DWR #8-29, DWR #10-29 and Associated Access Corridors, Uintah County, Utah

Dear John;

We have completed an inventory of four proposed wells for Ranken Energy, Incorporated in Uintah County, Utah. All are located on state lands administered by DWR. No sites were found. Enclosed please find a copy of the report entitled *A Cultural Resource Survey of Ranken Energy Wells DWR #12-28, DWR #14-28, DWR #8-29, DWR #10-29 and Associated Access Corridors, Uintah County, Utah*. The SHPO has also been contacted for consultation with regard to this project.

Please let me know if you have any questions.

Sincerely,

A handwritten signature in black ink, appearing to read "Michael R. Polk". The signature is fluid and cursive.

Michael R. Polk
Principal Archaeologist/Owner

enclosures

RECEIVED

MAR 28 2000

DIVISION OF
OIL, GAS AND MINING

**A CULTURAL RESOURCE SURVEY OF RANKEN ENERGY WELLS
DWR #12-28, DWR #14-28, DWR #8-29, DWR #10-29
AND ASSOCIATED ACCESS CORRIDORS, UINTAH COUNTY, UTAH**

by

Michael R. Polk
Principal Archaeologist/Owner

and

James R. Christensen
Assistant Archaeologist

Prepared for:

Ranken Energy, Inc.
417 West 18th Street
Edmond, Oklahoma 73013-3663

Prepared by:

Sagebrush Consultants, L.L.C.
3670 Quincy Avenue, Suite 203
Ogden, Utah 84403

Under Authority of Utah State Antiquities Permit No. U-00-SJ-0034s

Archaeological Report No. 1153

March 27, 2000

INTRODUCTION

In February 2000, Ranken Energy Corporation (Ranken) of Vernal, Utah requested that Sagebrush Consultants, L.L.C. (Sagebrush) conduct a cultural resource inventory of Ranken Energy Wells DWR #12-28, DWR #14-28, DWR #8-29, DWR #10-29 and associated access corridors in Uintah County, Utah. The purpose of this inventory is to identify cultural resource sites which may be present within the proposed project area.

The proposed wells are located in T. 12S., R. 23E., S. 28 and 29 on USGS 7.5' Quadrangle Cooper Canyon (1966) (Figure 1). Footages for the proposed well locations are as follows: DWR #12-28 (2105' FSL 550' FWL); DWR #14-28 (1246' FSL 2032' FWL); DWR #8-29 (2432' FNL 658' FEL); DWR # 10-29 (1592' FSL 2026' FEL). The proposed well pad locations and associated access corridors lie on Utah State Lands administered by the Division of Wildlife Resources. A survey of the project area was carried out by Michael R. Polk on March 16 and 17, 2000 under authority of Utah State Antiquities Permit No. U-00-SJ-0034s.

A file search for previously recorded cultural resource sites located near the current project area was conducted by Heather M. Weymouth and James R. Christensen at the Bureau of Land Management, Vernal District Office on June 11, 1999. An updated file search was conducted by James R. Christensen at the Utah State Historic Preservation Office in Salt Lake City, Utah on March 20, 2000.

More than 20 previous cultural resource projects have been conducted in the vicinity of the current project. Due to the large number of projects conducted in this area, individual project descriptions will not be listed. Despite the large number of projects that have been conducted in the vicinity of the current project area, none have resulted in the documentation of a cultural resource site within a one mile radius of the proposed project. The NRHP was also consulted prior to the commencement of fieldwork for the present project. No NRHP listed sites were found to be located in the vicinity of the current project area.

ENVIRONMENT

The project area lies in the dissected tablelands southwest of the Oil Springs Oil and Gas Field. The elevation of the areas surveyed range from between approximately 5680 and 6090 feet a.s.l. Sediments consist of tan to brown sandy silt. Vegetation in the higher elevations covers approximately 30 percent of the ground surface and consists of pinyon-juniper community species including ephedra, yucca, juniper, pinyon pine, mountain mahogany and cactus. Vegetation in the lower elevations covers approximately 45 percent of the ground surface and consists of pinyon-juniper community species including sagebrush, greasewood, cactus, spiny hopsage, pinyon pine and juniper. The nearest significant permanent water source is Bitter Creek which is located approximately 0.4 to 1.6 km (0.25 to 1.0 miles) west of the proposed well locations.




Figure 1. Location of the area surveyed for Ranken Energy's proposed wells DWR #12-28, #14-28, #8-29, #10-29, associated access roads and pipelines. Taken from USGS 7.5' Quadrangle Cooper Canyon, Utah (1966; P.R. 1987).

Numerous seasonal drainages and washes are present throughout the general vicinity. Natural disturbance in the area consists of arroyo cutting, sheetwash and aeolian erosion. Cultural disturbance includes existing well pad locations and access roads, pipelines and sheep and cattle grazing.

METHODOLOGY

The project area inventoried consists of four 40,469 m² (10 ac) parcels of land 201-by-201 m (660-by-660 ft) centered on the proposed well heads, and 1.74 km (1.08 mi) of proposed access corridor. The well pads were inventoried in parallel transects spaced no more than 15 m (50 ft) apart. The access roads and pipelines were walked in two parallel transects spaced 10 m (32 ft) apart to cover a corridor width of 30m (100 ft). The area surveyed during this project (including proposed well pads and access corridors) totaled 21.5 ha (53.1 ac).

RESULTS

A cultural resource inventory was conducted for proposed Ranken Energy Wells DWR #12-28, DWR #14-28, DWR #8-29, DWR #10-29 and associated access corridors in Uintah County, Utah. No cultural resource sites or isolated artifacts were identified during this inventory despite the relative proximity of several of the well locations and access corridors to a permanent source of water (Bitter Creek).

RECOMMENDATIONS

A cultural resource inventory was conducted for proposed Ranken Energy Wells DWR #12-28, DWR #14-28, DWR #8-29, DWR #10-29 and associated access corridors in Uintah County, Utah. No cultural resource sites or isolated artifacts were identified during this inventory. As such, cultural resource clearance is recommended for the proposed project.

This investigation was conducted with techniques which are considered to be adequate for evaluating cultural resources that are available for visual inspection and could be adversely affected by the proposed project. However, should such resources be discovered during construction, a report should be made immediately to the State Archaeologist, Division of State History, Utah State Historic Preservation Office, Salt Lake City, Utah.



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Kathleen Clarke
Executive Director
Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

April 25, 2000

Ranken Energy Corporation
417 West 18th Street, Suite 101
Edmond, OK 73013-3663


Re: DWR 14-28 Well, 1246' FSL, 2032' FWL, SE SW, Sec. 28, T. 12S, R. 23E,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the enclosed Conditions of Approval, approval to drill the referenced well is granted.

This approval will expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33483.

Sincerely,



John R. Baza
Associate Director

er

Enclosures

cc: Uintah County Assessor
Division of Wildlife Resources

Operator: Ranken Energy Corporation

Well Name & Number: DWR 14-28

API Number: 43-047-33483

Lease: Fee

Location: SE SW Sec. 28 T. 12S R. 23E

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division of the following actions during drilling of this well:

- . 24 hours prior to cementing or testing casing
- . 24 hours prior to testing blowout prevention equipment
- . 24 hours prior to spudding the well
- . within 24 hours of any emergency changes made to the approved drilling program
- . prior to commencing operations to plug and abandon the well

Division contacts (please leave a voice mail message if the person is not available to take the call):

- . Dan Jarvis at (801)538-5338
- . Robert Krueger at (801)538-5274 (plugging)
- . Carol Daniels at (801)538-5284 (spud)

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations you are required to immediately suspend all operations and immediately inform the Division of Wildlife Resources and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)



State of Utah

GOVERNOR'S OFFICE OF PLANNING AND BUDGET
Resource Development Coordinating Committee

John,
FYI for you folks
RECEIVED
APR 27 2000
UTAH CENTENNIAL
DIVISION OF WILDLIFE RESOURCES
NORTHEASTERN REGIONAL OFFICE

Michael O. Leavitt
Governor
Brad T. Barber
State Planning Coordinator
James L. Dykmann
Committee Chairman
John A. Harja
Executive Director

116 State Capitol Building
Salt Lake City, Utah 84114
(801) 538-1027
Fax: (801) 538-1547

April 20, 2000

RECEIVED
MAY 15 2000
DIVISION OF
OIL, GAS AND MINING

Jack Lytle
Division of Wildlife Resources
1594 West North Temple
Salt Lake City, Utah 84114

SUBJECT: Ranken Energy Corporation Easement Applications for wells #: DWR-4-21;
DWR-16-16; DWR3-21; DWR-10-29; DWR2-21; DWR-8-29; DWR-12-28;
DWR-14-16; DWR-14-28; and DWR-1-21
State Identification Number: UT000323-040 to 130

Dear Mr. Lytle,

The Resource Development Coordinating Committee (RDCC), representing the State of Utah, has reviewed this proposal. State agencies' comments are as follows:

Utah Geological Survey

There are no paleontological localities recorded in this project area. However, the Eocene Green River and Uinta Formations are exposed throughout this area, and there is potential for the occurrence of significant paleontological resources. Other exposures of these two formations in this region have yielded sites with vertebrates, plants, and insect fossils. Any surface areas that may be disturbed should be surveyed and if needed mitigated by a qualified paleontologist.

Trust Lands Administration


The Trust Lands Administration is not opposed to issuance of rights-of-way or drill site locations on lands managed by Division of Wildlife Resources ("DWR"). The Trust Lands Administration is withholding permission to Ranken Energy Corporation ("Ranken") to cross adjacent trust land to access the DWR land pending a decision by the Bureau of Land Management ("BLM") and DWR that Ranken's oil and gas drilling, road construction, travel and presence on the DWR lands and adjoining trust land and BLM land will not negatively affect the intention of the Resource Development Group ("RDG") partners to proceed with oil and gas development in the adjacent RDG environmental assessment area.

Jack Lytle
Ranken Energy Corporation Easement Applications
2

The Trust Lands Administration notes that the DWR appears to be acting inconsistently in recommending approval of surface disturbance for oil and gas exploration and development on DWR land while encouraging BLM to limit the RDG proposal.

The Committee appreciates the opportunity to review this proposal. Please direct any other written questions regarding this correspondence to the Utah State Clearinghouse at the above address or call Carolyn Wright at (801) 538-1535 or John Harja at (801) 538-1559.

Sincerely,


for Brad T. Barber
State Planning Coordinator

BTB/ar

RDCC Agenda

April 11, 2000

2

6. UT000323-070 Division of Wildlife Resources/Uintah
County: Ranken Energy Corporation
Easement Application for well DWR-10-29
(Sec. 21, T12S, R23E). Comments due
4/11/00.
7. UT000323-080 Division of Wildlife Resources/Uintah
County: Ranken Energy Corporation
Easement Application for well DWR-2-21
(Sec. 21, T12S, R23E). Comments due
4/11/00.
8. UT000323-090 Division of Wildlife Resources/Uintah
County: Ranken Energy Corporation
Easement Application for well DWR-8-29
(Sec. 29, T12S, R23E). Comments due
4/11/00.
9. UT000323-100 Division of Wildlife Resources/Uintah
County: Ranken Energy Corporation
Easement Application for well #DWR-12-28
(Sec. 28, T12S, R23E). Comments due
4/11/00.
10. UT000323-110 Division of Wildlife Resources/Uintah
County: Ranken Energy Corporation
Easement Application for well DWR-14-16
(Sec. 16, T12S, R23E). Comments due
4/11/00.
11. UT000323-120 Division of Wildlife Resources/Uintah
County: Ranken Energy Corporation
Easement Application for well #DWR-14-28
(Sec. 28, T13S, R23E). Comments due
4/11/00.
12. UT000323-130 Division of Wildlife Resources/Uintah
County: Ranken Energy Corporation
Easement Application for well #DWR-1-21
(Sec. 21, T12S, R23E). Comments due
4/11/00.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL GAS OTHER:

2. Name of Operator:
RANKEN ENERGY CORPORATION

3. Address and Telephone Number:
417 W. 18th St., Ste. 101, Edmond, OK 73013-3663

4. Location of Well
Footages: 1246' FSL, 2032' FWL
CO, Sec., T., R., M.: SE/4 SW/4 Sec. 28-12S-23E

5. Lease Designation and Serial Number:

Fee

6. If Indian, Allottee or Tribe Name:

7. Unit Agreement Name:

8. Well Name and Number:
Ranken Energy DWR 14-28

9. API Well Number:
43-047-33483

10. Field and Pool, or Wildcat:

County: Uintah

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- Abandon
- Repair Casing
- Change of Plans
- Convert to Injection
- Fracture Treat or Acidize
- Multiple Completion
- Other _____
- New Construction
- Pull or Alter Casing
- Recomplete
- Reperforate
- Vent or Flare
- Water Shut-Off

Approximate date work will start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- Abandon *
- Repair Casing
- Change of Plans
- Convert to Injection
- Fracture Treat or Acidize
- Other _____
- New Construction
- Pull or Alter Casing
- Reperforate
- Vent or Flare
- Water Shut-Off

Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Well was originally proposed to drill to 3500'. Proposed new total depth is 4350'.

RECEIVED

JUL 12 2000


DIVISION OF
OIL, GAS AND MINING

13. Name & Signature: Randolph L. Coy  Title: President Date: 7/10/00

(This space for State use only)

COPY SENT TO OPERATOR
Date: 7-18-00
Initials: CRD

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 7/17/00
By: 

7-00 Ranken DWR 14-28 Rev.		
Well name:		
Operator:	Ranken Energy Corporation	
String type:	Production	Project ID: 43-047-33483
Location:	Uintah Co.	

Design parameters:

Collapse

Mud weight: 8.600 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 138 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 1,719 ft

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.447 psi/ft
Calculated BHP 2,010 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 3,924 ft

Non-directional string.

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	4500	4.5	10.50	J-55	ST&C	4500	4500	3.927	94
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2010	4010	1.99	2010	4790	2.38	47	132	2.79 J

Prepared by: Bob Krueger
Utah Dept. of Natural Resources

Phone: (801) 538-5274
FAX: (801) 359-3940


Date: July 17,2000
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.
Collapse is based on a vertical depth of 4500 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes.
Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

7-00 Ranken DWR 14-28 Rev.
Casing Schematic



STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

5. Lease Designation and Serial Number:

Free

6. If Indian, Allottee or Tribe Name:

7. Unit Agreement Name:

8. Well Name and Number:

Ranken Energy DWR 14-28

9. API Well Number:

43-047-33483

10. Field and Pool, or Wildcat:

Wildcat

1. Type of Well: OIL GAS OTHER:

2. Name of Operator:
RANKEN ENERGY CORPORATION

3. Address and Telephone Number:
417 W. 18th St., Ste. 101 Edmond, OK 73013-3663

4. Location of Well
Footages: 1246' FSL, 2032' FWL
QQ, Sec., T., R., M.: SE/4 SW/4 Sec. 28-12S-23E

County: Uintah

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- Abandon
- Repair Casing
- Change of Plans
- Convert to Injection
- Fracture Treat or Acidize
- Multiple Completion
- Other _____
- New Construction
- Pull or Alter Casing
- Recomplete
- Reperforate
- Vent or Flare
- Water Shut-Off

Approximate date work will start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- Abandon *
- Repair Casing
- Change of Plans
- Convert to Injection
- Fracture Treat or Acidize
- Other _____
- New Construction
- Pull or Alter Casing
- Reperforate
- Vent or Flare
- Water Shut-Off

Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

This is a second request to take the depth to 4500'.

RECEIVED

JUL 17 2000

DIVISION OF
OIL, GAS AND MINING

13. Name & Signature: Randolph L. Coy  Title: President Date: 7/13/00


(This space for State use only)

COPY SENT TO OPERATOR

Date: _____
Initials: _____

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 7/13/00

By: 

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: RANKEN ENERGY CORPORATION
 Address: 417 W. 18th St., Ste. 101
Edmond, OK 73013-3663

Operator Account Number: N 6250

Phone Number: 405/340-2363

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-33483	DWR 14-28		SE SW	28	12S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	12813	6/30/00		7-26-00		
Comments: <i>000726 Entity Added</i>							

Well 2


API Number	Well Name		QQ	Sec	Twp	Rng	County
47-047-33489	DWR 16-16		SE SE	16	12S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	12814	5/10/00		7-26-00		
Comments: <i>000726 Entity Added</i>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-33487	DWR 8-29		SE NE	29	12S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	12815	6/18/00		7-26-00		
Comments: <i>000726 Entity Added</i>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Randolph L. Coy
 Name (Please Print)

 Signature
 President
 Title
 7/20/00
 Date

RECEIVED

JUL 25 2000

DIVISION OF
 OIL, GAS AND MINING

RECEIVED

FORM 8

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

DEC 05 2000

DIVISION OF
OIL, GAS AND MINING

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

3. LEASE DESIGNATION AND SERIAL NO.

Fee

INDIAN, ALLOTTEE OR TRIBE NAME

1. TYPE OF WELL: OIL WELL GAS WELL DRY Other _____

1. TYPE OF COMPLETION: NEW WELL WORK OVER DEEP-EN PLUG BACK DIFF. RESTR. Other _____

2. NAME OF OPERATOR
RANKEN ENERGY CORPORATION

3. ADDRESS OF OPERATOR
417 W. 18th St., Ste. 101, Edmond, Oklahoma 73013-3663

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)
At surface 1246' FSL, 2032' FWL SE/4 SW/4
At top prod. interval reported below
At total depth

7. UNIT AGREEMENT NAME

5. FARM OR LEASE NAME
DWR

9. WELL NO.
14-28

10. FIELD AND POOL, OR WILDCAT
Wildcat

11. SEC. T., R., M., OR BLOCK AND SURVEY OR AREA
Section 28-12S-23W⁵

14. API NO. 43-047-33483 DATE ISSUED 8-24-00 12. COUNTY Uintah 13. STATE UT

15. DATE SPUDDED 6-30-00 16. DATE T.D. REACHED 7-11-00 17. DATE COMPL. (Ready to prod.) 11-4-00 (Plug & Abd.) 18. ELEVATIONS (DF, BEB, AT, CR, ETC.) 5661' 19. ELEV. CASINGHEAD -0-

20. TOTAL DEPTH, MD & TVD 4497 21. PLUG BACK T.D., MD & TVD 22. IF MULTIPLE COMPL. HOW MANY -0- 23. INTERVALS DRILLED BY ROTARY TOOLS 0-4497 CABLE TOOLS -0-

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD) None 25. WAS DIRECTIONAL SURVEY MADE No

26. TYPE ELECTRIC AND OTHER LOGS RUN Spectral Litho Density¹⁷ WAS WELL CORED YES NO (Submit analysis)
Micro Resistivity, Simultaneous Triple Induction BRILLIEM TEST YES NO (See reverse side)

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
14"		32'	17 1/2"	None	
8 5/8"	24#	321'	12 1/4"	230 sx prem.	
4 1/2"	11.6#	4091'	7 7/8"	675 sx prem & sx prem	
				300	

29. LINER RECORD 30. TUBING RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

31. PERFORATION RECORD (Interval, size and number)

3965' - 3973' (4 SPF)	
3744' - 3754' (4 SPF)	

32. ACID, SHOT, FRACTURE CEMENT SQUEEZE ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
3965'-73'	750 Gals./15% Acid
3744'-54'	750 Gals./7 1/2% Acid

33. PRODUCTION
DATE FIRST PRODUCTION PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) WELL STATUS (Producing or shut-in) S.I.

DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL	GAS—MCF	WATER—BBL	GAS-OIL RATIO

FLOW, TUBING PRESS. CASING PRESSURE CALCULATED 24-HOUR RATE OIL—BBL GAS—MCF WATER—BBL OIL GRAVITY-API (CORR.)

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) TEST WITNESSED BY

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records
SIGNED Randolph L. Coy TITLE President DATE 12-1-00

See Spaces for Additional Data on Reverse Side



State of Utah

Department of
Natural Resources

Division of
Oil, Gas & Mining

ROBERT L. MORGAN
Executive Director

LOWELL P. BRAXTON
Division Director

MICHAEL O. LEAVITT
Governor

OLENE S. WALKER
Lieutenant Governor

February 20, 2004

CERTIFIED MAIL NO. 7002 0510 0003 8602 4958

Karen Kuntz
Ranken Energy Corp.
417 West 18th Street
Suite 101
Edmond, Oklahoma 73013-3663

Re: Extended Shut-in and Temporary Abandoned Well Requirements for Fee or State Leases.

Dear Ms. Kuntz:

Ranken Energy Corp., as of February 2004, has nine (9) Fee Lease Wells (see attachment A) that are currently in non-compliance for extended shut-in or temporary abandonment status. Wells SI/TA beyond twelve (12) consecutive months requires filing a Sundry Notice (R649-3-36-1). Wells with five (5) years non-activity or non-productivity shall be plugged, unless the Division grants approval for extended shut-in time upon a showing of good cause by the operator (649-3-36-1.3.3). For extended SI/TA consideration the operator shall provide the Utah Division of Oil, Gas & Mining with the following:

1. Reasons for SI/TA of the well (R649-3-36-1.1).
2. The length of time the well is expected to be SI/TA (R649-3-36-1.2), and
3. An explanation and supporting data if necessary, for showing the well has integrity, meaning that the casing, cement, equipment condition, static fluid level, pressure, existence or absence of Underground Sources of Drinking Water and other factors do not make the well a risk to public health and safety or the environment (R649-3-36-1.3).

Page 2
February 20, 2004
Karen Kuntz

Submitting the information suggested below may help show well integrity and may help qualify your well for extended SI/TA. **Note: As of July 1, 2003, wells in violation of the SI/TA rule R649-3-36 may be subject to full cost bonding (R649-3-1-4.2, 4.3).**

1. Wellbore diagram, and
2. Copy of recent casing pressure test, and
3. Current pressures on the wellbore (tubing pressure, casing pressure, and casing/casing annuli pressure) showing wellbore has integrity, and
4. Fluid level in the wellbore, and
5. An explanation of how the submitted information proves integrity.

If the required information is not received within 30 days of the date of this notice, further actions may be initiated. If you have any questions concerning this matter, please contact me at (801) 538-5281.

Sincerely,



Dustin K. Doucet
Petroleum Engineer


jc
cc: John Baza
Well File

	Well Name	API	Lease Type	Years Inactive
1	DWR 15-16	43-047-33346	Fee	2 Years 8 Months
2	DWR 12-22	43-047-33345	Fee	3 Years 0 Months
3	DWR 12-28	43-047-33481	Fee	3 Years 2 Months
4	DWR 14-28	43-047-33483	Fee	3 Years 3 Months
5	DWR 16-16	43-047-33489	Fee	3 Years 3 Months
6	DWR 8-29	43-047-33487	Fee	3 Years 5 Months
7	DWR 1-21	43-047-33480	Fee	3 Years 7 Months
8	DWR 14-16	43-047-33482	Fee	3 Years 7 Months
9	DWR 12-21	43-047-33344	Fee	4 Years 1 Month

Attachment A

RANKEN ENERGY CORPORATION

417 W. 18th Street, Suite 101
Edmond, Oklahoma 73013-3663
(405) 340-2363 • Fax (405) 340-2365



March 3, 2004

RE: Well Status of Ranken Energy Corporation Wells
Uintah County, Utah
Oil Springs Ranch Project

Mr. Dustin K. Doucet, Petroleum Engineer
State of Utah
Department of Natural Resources
Division of Oil, Gas & Mining
1594 West North Temple, Suite 1210
Salt Lake City, Utah 84114-5801

RECEIVED

APR 05 2004

DIV. OF OIL, GAS & MINING

Dear Mr. Doucet:

Per our telephone discussion on this date concerning the reason why some of our wells are currently shut in on our fee leasehold and the death of my partner, please let me reiterate further. Approximately 2 years ago Ranken's largest investor/partner suddenly passed away due to an accident. He controlled 62.5% of the working interest in our project and unfortunately he had no children. His heirs are his brothers and sisters who are exceedingly older and know nothing about the oil and gas industry. His estate is currently being liquidated. Needless to say, when he passed away, no further expenditures took place in our project. Our project essentially ceased at the time of his death. Some of our wells haven't even been completed as yet. Additional zones of interest behind pipe exist in many of the wells.

We have been trying to replace this interest w/ other companies/investors for quite some time. Only in recent months, since the gas prices in the Rocky's have gained some momentum, have we been able to attract some serious consideration. We currently have some on-going dialog with seven different companies at this time. We are cautiously optimistic that a deal will be done this year, perhaps even quicker, and our project will move forward once again.

Per your request, listed below is a status report on the wells that you listed in your letter to Ranken Energy Corporation dated February 20, 2004:

1. DWR 15-16: This well was completed in the Wasatch in July 1999. New 15.5 #/ft. casing was run in the hole. A DV tool was set at 2790' and packer was set at 2717'. Top perfs are at 2803' - 13'. A plunger lift system was installed on 5-9-2000. The estimated top of cement is 700'. Current SITP is 680 PSI and SICP is 760 PSI. We

2. are planning on putting this well back on production pending the results of a short period flow test currently underway.
3. DWR 12-21: This well was completed in the Wasatch and Mesa Verde in December 1999. New 15.5 #/ft 5 1/2" casing was run in the hole. A DV tool was set at 3672'.
4. The top perfs are at 2685' – 95'. The estimated top of cement is at 722'. Current SICP is 180 PSI and the SITP is 320 PSI. This well would be part of a localized compression system that may be installed.
5. DWR 12-22: This well was completed in the Mesa Verde in December 1999. New 15.5 #/ft 5 1/2" casing was run in the hole with DV tool at 2994'. The well was later drilled out horizontally in the Mesa Verde and a subsequent completion report was filed in October 2001. The well currently has a SICP of 440 PSI and a SITP of 360 PSI. This well is also part of our compression plan. In addition, this well produces about 30-40 BWP/D. A disposal well is being considered in the area to not only handle this water but also produced water from other wells on our fee block.
6. DWR 12-28: This well was completed in the Wasatch in July 2000. New 4 1/2" 10.5 #/ft casing was run in the hole. The well currently has a SICP of 320 PSI and a SITP of zero. This well has a down hole positive displacement pump installed with a 6 cylinder gas engine to turn the rod string. This well will make 200-300 BWP/D and 150-250 MCF/GPD. However, the cost to haul water is too great to justify. The possible SWDW mentioned above would also service this well.
7. DWR 14-28: This well was completed in the Wasatch in November 2000. New 4 1/2" 11.6 #/ft casing was run in the hole. The well currently has a SICP of 10 PSI and SITP of 10 PSI. Cement was circulated to surface after pumping a total of 975 sacks of cement. The original zones that were perforated were not commercially productive. However, there are additional zones behind pipe that remain prospective and need to be tested prior to abandonment of the wells.
8. DWR 14-16: This well was completed in the Green River formation in June 2000. New 4 1/2" 10.5 #/ft casing was run in the hole and was cemented with 725 sacks of cement. Cement was circulated to surface. The well currently has a SICP of zero and a SITP of 5 PSI. Additional potential exists in the shallower formations in this well and should be tested prior to abandonment.
9. DWR 16-16: This well was drilled and completed in the Wasatch in January 2000. New 4 1/2" 10.5 #/ft casing was run in the hole and was cemented with 755 sacks of cement. Cement was circulated to surface. The well currently has 80 PSI SICP and 80 PSI SITP. Additional potential exists in the shallower formations in this well and should be tested prior to abandonment. Both this well and the DWR 14-14 could be tied into the compression facility mentioned earlier.
10. DWR 8-29: This well was drilled and completed in the Mesa Verde and Wasatch in August 2000. New 4 1/2" 10.5 #/ft casing was run in the hole and cemented with 510 sacks cement. Cement was circulated to surface. The current SICP is zero and the current SITP is also zero. The original zones that were perforated were not


commercially productive without compression. Additional zones of interest are present behind pipe and should be tested prior to abandonment.

11. DWR 1-21: This well was drilled and completed in the Green River and Wasatch in June 2000. New 4 1/2" 10.5 #/ft casing was run in the hole and cemented with 605 sacks of cement. Cement was circulated to surface. The current SICP is 160 PSI and the current SITP is 140. This well cannot produce without the aid of compression.

As you can now see, 5 of the 9 wells listed on your report have cement to surface. The remaining 4 wells all have "produceable" pressures that either need compression help or a water disposal well. We are making progress with potential new partners and if successful, new completion work on existing wells will take place.

In summary, we respectfully request that shut in status be granted for these wells. Should you have any questions please do not hesitate to call or write. Thank you for your consideration and cooperation.

Sincerely,



Randolph L. Coy
President

RLC/adb



State of Utah

Department of
Natural Resources

Division of
Oil, Gas & Mining

ROBERT L. MORGAN
Executive Director

LOWELL P. BRAXTON
Division Director

May 10, 2004

CERTIFIED MAIL NO. 7002 0510 0003 8602 5412

Mr. Randolph L. Coy
Ranken Energy Corporation
417 W. 18th Street Suite 101
Edmond, Oklahoma 73013-3663

Re: Extended Shut-in and Temporary Abandoned Well Requirements for Fee or State Leases dated February 20, 2004.

Dear Mr. Coy,

The Division of Oil, Gas and Mining (DOG M) is in receipt of your letter dated March 3, 2004 in regards to the nine (9) shut-in wells operated by Ranken Energy Corporation (Ranken). It is our understanding Ranken is actively seeking a partner or investor for these properties to share the financial burden necessary to make these wells productive.

Based upon the proposed plan to complete this project and put these properties into production this year and other information provided at this time, DOGM approves the nine (9) wells for extended shut-in until January 1, 2005. However, in the future it will be necessary to address all requirements described in the DOGM February 20, 2004 correspondence before these properties will be considered for any additional extended SI/TA status.

For reference, Attachment A lists the wells subject to this request. If you have any questions or need additional assistance in regards to the above matters please contact me at (801) 538-5281.

Sincerely,

Dustin Doucet
Petroleum Engineer

cc Well File

	Well Name	API	Lease Type	Years Inactive
1	DWR 15-16	43-047-33346	Fee	2 Years 8 Months
2	DWR 12-22	43-047-33345	Fee	3 Years 0 Months
3	DWR 12-28	43-047-33481	Fee	3 Years 2 Months
4	DWR 14-28	43-047-33483	Fee	3 Years 3 Months
5	DWR 16-16	43-047-33489	Fee	3 Years 3 Months
6	DWR 8-29	43-047-33487	Fee	3 Years 5 Months
7	DWR 1-21	43-047-33480	Fee	3 Years 7 Months
8	DWR 14-16	43-047-33482	Fee	3 Years 7 Months
9	DWR 12-21	43-047-33344	Fee	4 Years 1 Month

Attachment A

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: SEE ATTACHED
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SEE ATTACH
		7. UNIT or CA AGREEMENT NAME: OIL SPRINGS
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	8. WELL NAME and NUMBER: SEE ATTACHED	
2. NAME OF OPERATOR: MAK-J ENERGY PARTNERS, LTD		9. API NUMBER:
3. ADDRESS OF OPERATOR: 370 17TH ST STE 2710 CITY DENVER STATE CO ZIP 80202		10. FIELD AND POOL, OR WILDCAT:
4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED LIST		COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: _____		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
EFFECTIVE DATE: August 23, 2004

<p>OLD OPERATOR:</p> <p>RANKEN ENERGY CORP. N 6250 417 W. 18TH STREET SUITE EDMOND, OKLAHOMA 73013-3663 405-340-2363</p>	<p>NEW OPERATOR:</p> <p>MAK-J ENERGY PARTNERS, LTD N 2670 370 17TH STREET, SUITE 2710 DENVER, CO 80202 303-468-0090</p>
---	--

PLEASE SEE ATTACHED WELL LIST. *State/fee Bond # SLCPPD X02546*

RANDOLPH COY
PRESIDENT
RANKEN ENERGY CORP.

NAME (PLEASE PRINT) STEVE VAN HOOK TITLE VICE PRESIDENT

SIGNATURE *[Signature]* DATE 8/23/2004

(This space for State use only)

RECEIVED
AUG 25 2004

MAK ENERGY

370 17th Street, Suite 2710
Denver, Colorado, 80202

303-468-0090 VOICE
303-468-0092 FAX


STATE OF UTAH
EARLENE

MAK-J ENERGY PARTNERS LEFT OFF OR FORM 9 OPERATOR CHANGE TWO WELLS THAT
THE LOCATION WAS BUILT.

PLEASE ADD TO YOUR LIST.

DWR #2-21 - 43-047-33484
DWR #3-21 - 43-047-33485

PLEASE LET ME KNOW IF YOU NEED ME TO FILL OUT ANOTHER SUNDRY.



CINDY BUSH
OPERATIONS COORDINATOR

APPROVED 9114104

ER

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED

SEP 02 2004

DIV. OF OIL, GAS & MINING

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH
2. CDW
3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **8/23/2004**

FROM: (Old Operator):
 N6250-Ranken Energy Corp
 417 W 18th St, Suite 101
 Edmond, OK 73013-3663
 Phone: 1-(405) 340-2363

TO: (New Operator):
 N2670-MAK-J Energy Partners, LTD
 370 17th St, Suite 2710
 Denver, CO 80202
 Phone: 1-(303) 468-0090

CA No.

Unit:

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
DWR 5-28	28	120S	230E	4304733343	12605	Fee	GW	P
DWR 12-21	21	120S	230E	4304733344	12606	Fee	GW	S
DWR 12-22	22	120S	230E	4304733345	12640	Fee	GW	S
DWR 15-16	16	120S	230E	4304733346	12641	Fee	GW	S
DWR 1-21	21	120S	230E	4304733480	12811	Fee	GW	S
DWR 12-28	28	120S	230E	4304733481	12810	Fee	GW	S
DWR 14-16	16	120S	230E	4304733482	12812	Fee	GW	S
DWR 14-28	28	120S	230E	4304733483	12813	Fee	GW	S
DWR 8-29	29	120S	230E	4304733487	12815	Fee	GW	S
DWR 16-16	16	120S	230E	4304733489	12814	Fee	GW	S
DWR 2-21	21	120S	230E	4304733484		Fee	GW	LA TA
DWR 3-21	21	120S	230E	4304733485		Fee	GW	LA

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/25/2004
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/25/2004 & 9/2/2004
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/30/2004
- Is the new operator registered in the State of Utah: YES Business Number: 5690747-0181
- If **NO**, the operator was contacted on: _____
- (R649-9-2)Waste Management Plan has been received on: To Follow
- Inspections of LA PA state/fee well sites complete on: 8/31/2004

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM n/a BIA n/a

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: n/a

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 8/31/2004 & 9/14/2004
 2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 8/31/2004 & 9/14/2004
 3. Bond information entered in RBDMS on: 8/31/2004 & 9/14/2004
 4. Fee/State wells attached to bond in RBDMS on: 8/31/2004 & 9/14/2004
 5. Injection Projects to new operator in RBDMS on: n/a
 6. Receipt of Acceptance of Drilling Procedures for APD/New on: n/a
-

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: n/a
-

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: n/a
-

FEE AND STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number SLCPPDX02546
 2. The **FORMER** operator has requested a release of liability from their bond on: 8/24/2004
The Division sent response by letter on: 9/1/2004
-

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 8/31/2004 & 9/14/2004
-

COMMENTS:

Two LA wells had locations built by Ranken; the DWR 2-21 had surface casing set.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	8. WELL NAME and NUMBER: DWR #14-28	
2. NAME OF OPERATOR: MAK-J ENERGY OPERATING COMPANY, LLC		9. API NUMBER: 4304733483
3. ADDRESS OF OPERATOR: 370 17TH STREET, STE 271 CITY DENVER STATE CO ZIP 80202	PHONE NUMBER: (303) 339-5871	10. FIELD AND POOL, OR WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246' FSL & 2032' FWL		COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 28 12S 23E		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>EXTEND SI PERIOD</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MAK-J ENERGY RESPECTFULLY REQUEST EXTENDED SHUT IN FOR THE ABOVE MENTIONED WELL UNTIL DECEMBER 31, 2005.

NAME (PLEASE PRINT) <u>CINDY BUSH</u>	TITLE <u>OPERATIONS COORDINATOR</u>
SIGNATURE	DATE <u>12-14-04</u>

(This space for State use only) APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING

DATE: 4/13/05
BY: [Signature] (See Instructions on Reverse Side)

* See attached letter dated April 13, 2005


RECEIVED
DEC 16 2004

DIV. OF OIL, GAS & MINING

WELL NAME: DWR 14-28
 1246' FSL & 2032' FWL
 LOCATION: Sec 28-12S-23E
 FIELD: Unnamed

GL: 5661'
 KB: 5672'
 API NO: 430-4733-483
 Fed Lse No:
 PBTD: 3825'
 TD: 4372'

Surveys:	
Depth Ft	Depth Ft
1 1/4	413'
1	1639'
1	2063'
1 1/4	2258'
1 1/4	2315'
2	3083'
1	3516'
1/4	4497'



WELL HISTORY

Spudded 12 1/4" hole 7/1/00. Drilled 12 1/4" hole to 329'. Ran 8 5/8", 24# casing and landed at 324'. Cemented with 230 sks Premium Cement containing 2% CaCl & 1/4 #/sk Celluloflake. Drilled 7 7/8" hole to TD of 4372' losing circulation at 1356'. Regained with no further problems. TD was lengthened due to unavailability of loggers.

Mud log shows: 2000' - 2100': 128 units w/ maximum connection gas of 992 units (connection gas lasted for the next 500), 3795' - 3808': 4 units before - increasing to 29 units, 3829' - 3842': 15 units before - increasing to 30 units, 3889' - 3904': 20 units before - increasing to 44 units, 3909' - 3921': 34 units before - increasing to 54 units, 3921' - 3939': 19 units before - increasing to 69 units, 3960' - 3968': 26 units before - increasing to 423 units, 4103' - 4120': 11 units before - increasing to 194 units, 4126' - 4138': 19 units before - increasing to 221 units, 4157' - 4163': 15 units before - increasing to 253 units, 4163' - 4168': 14 units before - increasing to 75 units, 4174' - 4182': 19 units before - increasing to 77 units, 4259' - 4277': 13 units before - increasing to 144 units, 4303' - 4309': 17 units before - increasing to 42 units, 4327' - 4336': 18 units before - increasing to 44 units, 4360' - 4372': 11 units before - increasing to 75 units.

Ran 97 joints 4 1/2", 11.6 #/ft J55 casing. Landed at 4091'. Cemented with 225 sacks of Premium V cement w/ Hi-Fill standard mixed at 11#/gal followed by 450 sks Premium 300 w/ 1/4#/sk Poly-E-Flake, 3/10 of 1% CFR-3, 5/10 of 1% Halad 12, 2% gel, 2% microbond & 2/10 of 1% Super CBL mixed at 15.6#/gal. Circulated 11 bbls of cement to surface.

Perforated Mesaverde interval from 3965' - 3973', 4 JSPF. Acidized w/ 750 gallons 15% acid and ball sealers. No show of gas after swabbing and recovered water above and beyond load water - this zone is definitely wet. Set CIBP at 3825' w/ 2 sks of cement on top. Perforate Mesaverde from 3744' - 3754', 4 JSPF. Acidize w/ 750 gallons 7 1/2% HCL acid and ball sealers. Slight show of oil and gas after swabbing. Trip out of hole with packer and tubing. Well is currently shut in.

Prepared by:

TSM

Date:

12/7/2004

MAK-J ENERGY

MAK-J Energy Operating Company, LLC
370 17TH Street, Suite 2710
Denver, Colorado, 80202

303-468-0090 VOICE
303-468-0092 FAX

December 7, 2004

Dustin K. Doucet
State of Utah
Department of Natural Resources
Division of Oil, Gas & Mining

Re: Request for Extended Shut-in

RECEIVED
DEC 16 2004
DIV. OF OIL, GAS & MINING

Dear Mr. Doucet,

Mak-J Energy Operating Company, LLC recently purchased certain oil and gas assets from Ranken Energy Corp., Edmond, Oklahoma. These assets include 10 wells and associated equipment generally located in Sections 16 – 28, T12S-R22E, Uintah County. The wells are located on lands owned by the Division of Wildlife. One (1) of the ten wells is currently producing. Mak-J officially took over operations on August 1st, 2004.

This letter is in reference to your letter to Ranken Energy dated May 10, 2004 granting extended shut-in for nine wells until January 1, 2005. Enclosed are 9 Sundry Notices requesting continued shut-in status for these wells. Since July of this year Mak-J has amassed approximately 37,000 gross acres in and around these properties. We currently have four Applications for Permit to Drill pending with the Bureau of Land Management, Vernal. It is our intent to be extremely active in this area and hopefully build it into a core area for this company. We are currently working the regional geology and reviewing well histories in an attempt to learn these properties in greater detail. Based upon our current studies our plans for the property are as follows:

1. Convert the DWR #12-28 (API #43-047-33481) into a salt water disposal well
2. Re-complete, open new pay, and fracture stimulate the DWR #12-21 (API #43-047-33344)

In order to make the wells in this area economic to operate it is essential one finds a cheaper way to dispose of produced water. Currently, produced water is being trucked to Ace Disposal, approximately 10 miles west of Vernal at a cost of approximately \$2.00 per barrel. These wells cannot support this expense. Submittal of our application for an underground water disposal permit is approximately 2 weeks away. Because these lands are located in "Indian Country" the permitting process is administered by Region 8 of the Environmental Protection Agency. The filing process and paper work is long and tedious.

I am sure you are well aware activity in the basin is at an all time high. The recent Federal lease sale is proof of this. The heightened activity is due primarily to the success operators are experiencing drilling and completing Mesaverde wells. In the past most completion attempts have been in the shallower Wasatch Formation. The DWR #12-21 well is completed both in the Mesaverde and the Wasatch. However, coals in the Mesaverde interval were



MAK-J Energy Operating Company, LLC
370 17TH Street, Suite 2710
Denver, Colorado, 80202

303-468-0090 VOICE
303-468-0092 FAX

perforated not the sands. It is Mak-J's intent to cement squeeze the existing perforated intervals in both the Mesaverde and Wasatch Formations and then perforate sands within the Mesaverde group and fracture stimulate. It is anticipated that 4 separate fracture treatments will be done on this well. Due to the remote nature of the well in addition to the competitive nature of securing services (pump trucks, pulling units, consultants) it is our intent to perform this operation as part of our larger drilling/completion program. According to the BLM we should be receiving approved APD's sometime around April of next year.

Because of the aforementioned Mak-J is requesting extended shut-in of the nine wells until December 31, 2005.

Enclosed are wellbore diagrams of the nine wells. In every instance new casing was run and cemented in the well. It is highly unlikely in just 5 years time that any of the casings has failed. Especially in light of the fact most primary cement work involved the pumping of two stages of cement using DV tools to assure high cement lift. In fact 7 of the 9 wells circulated cement to surface. To ensure casing integrity Mak-J proposes to monitor and record surface pressures, both tubing and casing, on a quarterly basis. The wells have been shut in long enough that any variations in surface pressures from quarter to quarter may indicate a potential problem. If that is the case Mak-J will expedite a rig to location and verify integrity or lack thereof. In the case of the latter and after approval is granted by the State, operations will be immediately undertaken to either cure the problem or abandon the well.

Again, Mak-J Operating Company, LLC respectfully requests continued shut-in status be granted to these wells until December 31, 2005. If you have any questions in regards to the above matters please do not hesitate and contact me at (303) 339-5873.

Sincerely,

Todd S. McDonald
Vice President

RECEIVED
JAN 24 2005
DIV. OF OIL, GAS & MINING

January 17, 2005

Clinton Dworshak
State of Utah
Department of Natural Resources
Division of Oil, Gas & Mining
1594 West North Temple, Suite 1210
Salt Lake City, Utah 84114-5801

Re: Request for Extended Shut-in

Dear Mr. Dworshak,

This is a follow up letter to our late December phone discussion regarding the requested extended shut-in on our recently purchased Ranken Energy wells in Uintah County, Utah. Since our talk Mak-J Energy has collected tubing and casing pressures on all of the wells, has performed a casing integrity test on the DWR #12-28, and took the preliminary steps to convert the DWR #12-28 well into a produced water disposal well. Pressures were recorded on December 20th and the results are as follows:

	<u>Tubing</u>	<u>Casing</u>
DWR #14-28	285 psi	285 psi
DWR #12-21	165 psi	? (casing valve is half buried in frozen dirt, unable to free up)
DWR #12-22	280 psi	415 psi
DWR #14-16	0 psi	0 psi
DWR #15-16	760 psi	760 psi
DWR #16-16	80 psi	80 psi
DWR #1-21	150 psi	150 psi
DWR #5-28	producing	
DWR #12-28	integrity test performed	

As mentioned in my earlier letter, tubing and casing pressures will be monitored and recorded on a quarterly basis. Mak-J Energy believes quarterly monitoring of wellhead pressures is an effective tool to verify casing integrity. Most casing failures are due to corrosive waters coming into contact with un-cemented pipe. All of the wells in the field, during the cementing of each production string, circulated cement to surface. Indicating, in all likelihood, the protection of the pipe is good. If a casing leak did occur one would think the casing would fill with water and both the tubing and casing pressure would go to zero. Initial reservoir pressure of these wells is normal or slightly below normal pressures (< 0.433 psi/ft). Although the DWR #14-16 has no pressure on the tubing and/or casing, in this

MAK-J ENERGY

MAK-J Energy Operating Company, LLC
370 17TH Street, Suite 2710
Denver, Colorado, 80202

303-468-0090 VOICE
303-468-0092 FAX

instance, I do believe the well has casing integrity. This well is perforated near the surface (620' – 670') in the Green River Formation. This interval tested wet and after 4 days of being shut-in on initial completion, with a packer in the hole, the tubing registered 0 psi.

Mak-J Energy plans to re-complete the DWR #12-21 well. Mak-J Energy has filed for four (4) drilling permits in the immediate area. We also began staking an additional 16 on January 13th. It is anticipated that drilling will occur sometime in July with completion operations taking place in August. Mak-J proposes to re-complete the DWR #12-21 in the Mesaverde Formation in August / September of this year when services are in the immediate area.

Mak-J Energy performed the necessary pump in tests on the DWR #12-28 to convert it to a salt water disposal well. It is imperative that a cheaper way to dispose of water in this area be found. Unfortunately, this well proved to have to low of permeability in the interval chosen to dispose of water into. Pressures were exceedingly high at low injection rates and the conversion of this well has been canceled. Another candidate will have to be chosen. Again, this will take place this summer. A casing integrity test however was performed on this well. The casing was tested to 2,550 psi and held for 30 minutes with 6 psi of falloff (see enclosed job log).

Again, Mak-J Operating Company, LLC respectfully requests continued shut-in status be granted to these wells until December 31, 2005. If you have any questions in regards to the above matters please do not hesitate and contact me at (303) 339-5873.

Sincerely,



Todd S. McDonald
Vice President



State of Utah

Department of
Natural Resources

MICHAEL R. STYLER
Executive Director

Division of
Oil, Gas & Mining

MARY ANN WRIGHT
Acting Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

4304733483
12523E Sec. 28

April 13, 2005

Mak-J Energy Operating Company, LLC
Attn: Todd S. McDonald
370 17th Street, Suite 271
Denver, CO 80202

Re: Approval for Extension of Shut-in or Temporarily Abandoned Status for Wells on Fee or State Leases

Dear Mr. McDonald,

The Division of Oil, Gas and Mining (the "Division") is in receipt of your letters dated December 7, 2004 (received by the Division on December 16, 2004) and January 17, 2005 (received by the Division on January 24, 2005) in regards to the ten (10) shut-in or operation suspended wells operated by Mak-J Energy Operating Company, LLC (Mak-J). The Division understands that Mak-J intends to recompleate 1 well immediately (Sundry Notice of Intent approved April 1, 2005 for the DWR # 12-21 well) and intends to evaluate the other 9 wells for future potential based on results of this recompleation and other wells that are scheduled to be drilled this summer.

Mak-J has provided explanations of integrity and will continue monitoring pressures on a quarterly basis to ensure continued integrity. All wells appear to have stable pressures and cement circulated to or near surface. If there is a change in pressures, Mak-J will do a casing integrity test and make any repairs necessary to restore integrity.

Based on the submitted information and plan of action, the Division approves your request for extended SI/TA for the 10 SI/TA wells on Fee leases (see attachment A) until January 1, 2006. If you have any questions or need additional assistance in regards to the above matters please contact me at (801) 538-5281.

Sincerely,

Dustin Doucet
Petroleum Engineer

MAK-J ENERGY																		
Tubing & Casing Pressures of SI Wells																		
Well #	12-28		14-28		12-21		12-22		14-16		15-16		16-16		1-21		8-29	
Date	Tbg#	Csg#	Tbg#	Csg#	Tbg#	Csg#												
3/1/04	0	320	10	10	320	180	360	440	5	0	680	760	80	80	140	160	0	0
12/6/04	0	360	285	285	165	185	280	415	0	0	760	760	80	80	150	150	0	0
3/19/05	260	260	285	285	260	185	280	415	0	0	760	760	80	80	150	150	0	0

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME: N/A
2. NAME OF OPERATOR: Enduring Resources, LLC		8. WELL NAME and NUMBER: DWR 14-28
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 <small>CITY</small> Denver <small>STATE</small> CO <small>ZIP</small> 80202		9. API NUMBER: 4304733483
PHONE NUMBER: (303) 350-5719		10. FIELD AND POOL, OR WILDCAT: Oil Springs
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246' FSL - 2032' FWL		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: sesw 28 12S 23E S		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well Name/Number</u> <u>Change.</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Well Name Change From: DWR 14-28
Well Name Change To: DWR 12-23-24-28

Utah State Bond #RLB0008031
Operator No. N2750

NAME (PLEASE PRINT) <u>Evette Bissett</u>	TITLE <u>Regulatory Compliance Assisnat</u>
SIGNATURE <u><i>Evette Bissett</i></u>	DATE <u>8/30/2006</u>

(This space for State use only)

RECEIVED
SEP 05 2006

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

- | |
|--------|
| 1. DJJ |
| 2. CDW |

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

8/15/2006

FROM: (Old Operator): N2670-Mak-J Energy Operating, LLC 370 17th St, Suite 2710 Denver, CO 80202 Phone: 1-(303) 339-5871	TO: (New Operator): N2750-Enduring Resources, LLC 475 17th Street, Suite 1500 Denver, CO 80202 Phone: 1-(303) 350-5102
---	--

WELL NAME	CA No.			Unit:		ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
	SEC	TWN	RNG	API NO					
DWR 12-23-12-28	28	120S	230E	4304733343	12605	Fee	GW	P	
DWR 12-23-13-21	21	120S	230E	4304733344	12606	Fee	GW	P	
DWR 12-23-13-22	22	120S	230E	4304733345	12640	Fee	GW	S	
DWR 12-23-34-16	16	120S	230E	4304733346	12641	Fee	GW	S	
DWR 12-23-41-21	21	120S	230E	4304733480	12811	Fee	GW	S	
DWR 12-23-13-28	28	120S	230E	4304733481	12810	Fee	GW	S	
DWR 12-23-24-16	16	120S	230E	4304733482	12812	Fee	GW	S	
DWR 12-23-24-28	28	120S	230E	4304733483	12813	Fee	GW	S	
DWR 12-23-31-21	21	120S	230E	4304733484	14411	Fee	GW	OPS	
DWR 12-23-42-29	29	120S	230E	4304733487	12815	Fee	GW	S	
DWR 12-23-44-16	16	120S	230E	4304733489	12814	Fee	GW	S	

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 10/11/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 10/11/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/22/2005
- Is the new operator registered in the State of Utah: YES Business Number: 5771233-0161
- (R649-9-2)Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a
- Reports current for Production/Disposition & Sundries on: ok

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 10/11/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 10/11/2006
- Bond information entered in RBDMS on: 10/11/2006
- Fee/State wells attached to bond in RBDMS on: 10/11/2006
- Injection Projects to new operator in RBDMS on: n/a
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

FEE & STATE WELL(S) BOND VERIFICATION:

- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0008031
- The **FORMER** operator has requested a release of liability from their bond on: n/a

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 10/11/2006

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING


FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	8. WELL NAME and NUMBER: DWR 14-28 <u>12-23-24-28</u>	
2. NAME OF OPERATOR: MAK-J ENERGY OPERATING COMPANY, LLC		9. API NUMBER: 4304733483
3. ADDRESS OF OPERATOR: 370 17TH STREET CITY Denver STATE CO ZIP 80202	PHONE NUMBER: (303) 339-5871	10. FIELD AND POOL, OR WILDCAT: OIL SPRINGS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246 FSL, 2032 FWL		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 28 12S 23E S		STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


Mak-J Energy Operating, LLC has sold its interest in the above referenced well to Enduring Resources, LLC effective: 8/15/2006.


Steve Van Hook, Vice President
Mak-J Energy Operating, LLC (N2670)
370 17th Street, Suite 2710
Denver, CO 80202


8/15/06
Date


Alex B. Campbell, Vice President
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, CO 80202

08/15/06
Date

NAME (PLEASE PRINT) <u>Steve Van Hook</u>	TITLE <u>Vice President</u>
SIGNATURE 	DATE <u>8/15/2006</u>

(This space for State use only)

APPROVED 10/11/06

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
OCT 11 2006

May 20, 2008

Sent via Certified Mail

Enduring Resources, LLC
Attn: Alex Campbell
475 17th Street, Suite 1500
Denver, CO 80202

The Houston Exploration Company
1100 Louisiana, Suite 2000
Houston, TX 77002-5215

Re: Notice of Lease Termination and Demand for Release
Oil and Gas Lease dated March 30, 1999, covering 8060.10 acres, more or less,
Township 12 South, Range 23 East and Township 13 South, Range 23 East,
Uintah County, Utah (copy enclosed)

Gentlemen:

Pursuant to my telephone conversation with Alex Campbell on May 13, 2008, we wish to inform you that the subject oil and gas lease ("Lease") has terminated for your failure to comply with provision 7 of said Lease. Specifically, your drilling rig was released on March 5, 2007, at 10:00 pm from your DWR 12-23-31-21 well location according to the information furnished by your office. As a result of your cessation of operations lasting more than one hundred eighty (180) consecutive days, said Lease terminated as to all lands and depths except those producing from the Proration Units (as defined in said Lease) for the DWR #5-28 well and the DWR #12-21 well, on or about September 2, 2007.

Also, our records show that we have not received any shut-in payments as provided for in provision 9 of said Lease. This provision clearly states, "...Should such shut-in royalty payments not be made in a timely manner as provided for above, then, in that event, it shall be considered for all purposes that there is no production of gas from any such well or wells and, unless this Lease is being maintained by any other preservative provision hereof, this Lease shall terminate automatically at midnight on the last day provided for the payment of such shut-in royalties, and Lessee shall thereupon furnish to Lessor a release of all of its interest in and to this Lease as provided in Section 17...." For your information, we enclose Exhibit "B" from the Assignment, Conveyance and Bill of Sale of said Lease unto Enduring Resources, LLC, et al, showing the "shut-in" status of numerous wells on the leased premises.

RECEIVED

MAY 23 2008

DIV. OF OIL, GAS & MINING

Enduring Resources, LLC
The Houston Exploration Company
May 20, 2008
Page Two


Further, since your acquisition of the lease in August of 2006, we have not received any of the data and information required in items A, B, C, and E of provision 15. Notifications Required of said Lease. Please furnish all required data and information immediately.

If within thirty (30) days from the date hereof we do not receive a fully executed, recordable release and plat showing the proration units designated by you in accordance with Section 17 of said Lease, we will pursue all remedies available to us in the appropriate court of law, including without limitation, all our costs and expenses (including attorneys fees and expenses) as set forth in provision 18. Indemnification of said Lease.

If you have any questions or comments, I can be reached at 405.627.6025.

Sincerely,

EXOK, INC.



Steven D. Bryant
President

SDB:mkb
Enclosures

cc: Utah Royalty Owners Association
Box 192
Roosevelt, UT 84066

✓ State of Utah Department of Natural Resources
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, UT 84114-5801

Exhibit "B"

Attached to and made a part of that certain Assignment, Conveyance and Bill of Sale dated August 15, 2006 by and between MAK-J Energy Partners, Ltd, as Assignor and Enduring Resources, LLC, etal, as Assignee.

<u>Well</u>	<u>API No.</u>	<u>Location</u>	<u>Status</u>
<u>Oil Springs Area</u>			
	DWR 12-23-2A-28		
DWR 1-21	43-047-33480-00-00	NENE of Section 21-T12S-R23E	Shut in
DWR 2-21	43-047-33484-00-00	NWNE of Section 21-T12S-R23E	Surface pipe only-APD rescinded
DWR 3-21	43-047-33485-00-00	NENW of Section 21-T12S-R23E	Location built-APD rescinded
DWR 4-21	43-047-33486-00-00	NWNW of Section 21-T12S-R23E	Surveyed location only-APD rescinded
DWR 5-28	43-047-33343-00-00	SWNW of Section 28-T12S-R23E	Producing
DWR 8-29	43-047-33487-00-00	SENE of Section 29-T12S-R23E	Shut in
DWR 10-29	43-047-33488-00-00	NWSE of Section 29-T12S-R23E	Surveyed location only
DWR 12-21	43-047-33344-00-00	NWSW of Section 21-T12S-R23E	Producing
DWR 12-22	43-047033345-0-00	NWSW of Section 22-T12S-R23E	Shut in
DWR 12-28	43-047-33481-00-00	NWSW of Section 28-T12S-R23E	Shut in
DWR 14-16	43-047-33482-00-00	SESW of Section 16-T12S-R23E	Shut in (no surface equip)
DWR 14-28	43-047-33483-00-00	SESW of Section 28-T12S-R23E	Shut in (no surface equip)
DWR 15-16	43-047-33346-00-00	SWSE of Section 16-T12S-R23E	Shut in
DWR 16-16	43-047-33489-00-00	SESE of Section 16-T12S-R23E	Shut in
DWR 16-29	none	SESE of Section 29-T12S-R23E	Location only-APD not issued

End of Exhibit "B"

OIL AND GAS LEASE

This Agreement, made and entered into this 30th day of March, 1999 by and between Exok, Inc., an Oklahoma corporation whose address is 6410-B North Santa Fe, Oklahoma City, Oklahoma 73116, as Lessor, and Ranken Energy Corporation, whose address is 601 N. Kelly, Suite 103, Edmond, Oklahoma 73003-4855, as Lessee, Witnesseth:

1. That Lessor, in consideration of the cash bonus in hand paid, of the royalties herein provided, and of the agreements of Lessee herein contained, hereby grants, leases and lets exclusively unto Lessee for the sole and only purpose of exploring, drilling and operating for and producing oil and gas and of laying pipeline, storing oil and building tanks, roads, and structures thereon to produce, save, care for, treat and transport said substances produced from the land leased hereunder, the following described land (sometimes referred to in this lease as the "leased premises"), to wit:

Patented Placer Mining Claims, County of Uintah, State of Utah

Parcel I

Bitter Creek Nos. 2, 3, 4, 5, 6, 7, 8, 9 and 10.
Hydrocarbon Nos. 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11 and 12.
Denver-Los Angeles Nos. 1, 2, 3, 4, 5, 6, 7, 8, and 9.
Seep Ridge Nos. 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 and 11.
Button Nos. 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11 and 12.
Button Hole Nos. 1, 2 and 3.
Gasoline Nos. 1, 2, 3, 4, 5, 6, 7, 8, 11 and 12.

Parcel II

Bitter Creek No. 1.
Gasoline No. 9.
Gasoline No. 10.

Insofar and only insofar as said Patented Placer Mining Claims cover the lands specifically located in the governmental sections set forth below:

Township 12 South, Range 23 East, S.L.M.

All or part of Sections 16,17,19,20,21,22,27,28,29,32,33,34 and 35;

Township 13 South, Range 23 East, S.L.M.

All or part of Sections 2,3,4,5,8,9,10 and 11

containing approximately 8060.10 acres, more or less.

Lessor expressly reserves and retains from this lease all of that portion of the Patented Placer Mining Claims described hereinabove insofar and only insofar as said mining claims cover lands located in governmental Sections 14,15,16,17,18,19,20,21,22 and 29, Township 13 South, Range 23 East, S.L.M. together with all rights of ingress and egress over and across the leased premises reasonably necessary to enable Lessor, its' successors or assigns, to develop, operate and produce wells on the lands reserved herefrom.

2. **Term.** Subject to the provisions hereinafter contained, this Lease shall be for a term of five (5) years from this date (hereinafter referred to as "primary term"), and so long thereafter as oil and gas, or either of them, is produced in paying quantities from the leased premises, or operations are conducted as hereinafter provided. Upon the termination or any partial termination of this Lease, Lessee shall prepare, execute and deliver to Lessor a recordable release of such acreage in accordance with Section 17 of this Lease.

At the expiration of the primary term, this Lease shall automatically terminate as to all lands except those included in a proration unit attributable to a well capable of producing oil and/or gas in paying quantities unless operations are then being conducted in accordance with the Continuous Development provisions of Section 6 below or the Additional Drilling or Reworking provisions of Section 7 below, in which case the terms of Sections 6 and 7 shall control.

If at the expiration of the primary term, this Lease is perpetuated by production of oil and/or gas in paying quantities, then, with respect to each proration unit on the leased premises, this Lease shall automatically terminate as to all rights granted by this Lease below 100 feet below the deepest depth from which oil and/or gas is then being produced. Provided, however, if at the expiration of the primary term, Lessor is engaged in drilling an additional well or wells pursuant to the provisions of Section 6 of this Lease, then this Lease shall not terminate with respect to the depths described in this paragraph so long as development continues in accordance with the terms of Section 6 of this Lease. Furthermore, if at the expiration of the primary term, Lessee is engaged in deepening an existing well, then for purposes of this paragraph only, the deepening of an existing well will be considered a continuous development operation under Section 6 of this Lease, and so long as Lessee continues developing the leased premises in accordance with the terms of Section 6, the rights to the depths described in this paragraph will not terminate.

If at any time after the expiration of the primary term, should the deepest producing formation attributable to any proration unit on this Lease cease to produce in paying quantities, then Lessee shall have one hundred eighty (180) days to begin either deepening that well or commencing the drilling of another well or wells on that proration unit in accordance with the provisions of Section 7 of this Lease, or this Lease, insofar as it covers such proration unit, shall automatically terminate with regard to all depths below 100 feet below the deepest depth from which oil and/or gas is then being produced.

To the extent that any part of this Lease remains in effect, Lessee shall retain such easements across the terminated portions of the Lease as shall be reasonably necessary for ingress and egress to enable Lessee to develop and operate the remaining portion of this Lease.

3. **Obligation Wells.** Lessee covenants and agrees to drill, or cause to be drilled, four (4) test wells (hereinafter referred to as "Obligation Wells") during the first year of the primary term hereof; locations for such Obligation Wells to be chosen by Lessee's geologists.

In order to qualify as an Obligation Well, each such well drilled hereunder shall be drilled to a minimum depth sufficient to test the Wasatch formation. Except as provided in Section 16 herein, failure by Lessee to cause or commence the actual drilling of all four (4) Obligation Wells on or before March 29, 2000 shall constitute and result in the automatic termination of this lease, except as to the proration unit for each such well previously drilled and capable of producing oil and/or gas in paying quantities and designated by Lessee in writing as hereafter provided. The only other penalty for Lessee's failure to timely commence all four (4) Obligation Wells shall be the loss of all additional rights earnable hereunder.

4. **Royalty.** Lessee covenants and agrees to pay Lessor the following royalties monthly, subject to the provisions of Section 5 hereof:

(a) 15.75% of 8/8ths of the gross proceeds of all oil and other liquid hydrocarbons recovered or separated on the leased premises, produced and saved from the leased premises and sold by Lessee in an arms' length transaction; and as to such oil and other liquid hydrocarbons not sold by Lessee in an arms' length transaction, royalties of that share or percentage calculated by using the highest price, plus premium, if any, paid or offered for oil and other liquid hydrocarbons of comparable quality in the general area where produced and when run; or after sixty (60) days written notice from Lessor, which notice may be given from time to time, Lessee shall deliver free of cost to Lessor at the well, or to the credit of Lessor into the pipeline to which the well is connected, such share or percentage of all oil and other liquid hydrocarbons produced and saved from the leased premises; and

(b) 15.75% of 8/8ths of the gross proceeds received by Lessee for all gas recovered or separated on the leased premises, produced from the leased premises and sold by Lessee in an arms' length transaction; and as to such gas not sold by Lessee in an arms' length transaction, royalties of that share or percentage calculated by using the highest price paid or offered for gas of comparable quality in the general area where produced and when run.

5. **Royalty.** (a) Lessee shall pay Lessor royalty on all oil and other liquid hydrocarbons, including condensate, and on all gas, including all substances contained in such gas, (all hereinafter collectively called "Products" and each individually called a "Product") produced from a well on the leased premises, whether or not such Products are produced to the credit of Lessee or sold under a contract executed by or binding on Lessee, and;

(b) In no event shall Lessor's royalty for a Product be based on a price less than the price paid Lessee for Lessee's share of that Product produced hereunder. For purposes of this lease, an arms' length transaction is a sale of a Product by Lessee to a buyer not affiliated with Lessee or with any subsidiary or other affiliate of Lessee under an agreement negotiated in good faith by all parties. Lessor shall not bear any production or post-production cost or expense, including without limitation, cost or expense for storing, separating, dehydrating, transporting, compressing, treating, gathering, or otherwise rendering marketable or marketing the Products, and Lessee shall make no deduction or reduction for any such cost or expense when computing any royalty due Lessor under this Lease.

6. **Continuous Development.** At the end of the primary term or upon the completion of any well then drilling on the leased premises as a well capable of producing in paying quantities or as a dryhole (completion being the release of the completion rig, or if the well is a dry hole, the release of the drilling rig), Lessee shall have the recurring right for one hundred eighty (180) days thereafter, to commence the drilling of another well or wells on the leased premises (commencement being the actual spudding of the succeeding well), with no more than one hundred eighty (180) days elapsing between the completion of one well as a producer or a dryhole and the commencement of the next succeeding well. Failure to commence such additional well or wells within the time herein provided, shall terminate this Lease ipso facto as to all lands except those included within the surface boundaries of any proration unit otherwise being maintained under the provisions of this Lease. Lessee shall also have the right to accelerate the drilling of additional wells and thereby accumulate and perpetuate this Lease for an additional one eighty (180) days for each additional well drilled in accordance herewith. Lessee's right to accumulate additional time hereunder is expressly limited to wells other than the four (4) Obligation Wells provided for in Section 3 above.

7. **Additional Drilling or Reworking.** If, at the expiration of the primary term, or the expiration of any extended term provided in Section 6 above, whichever is later, oil and/or gas are being produced in paying quantities, but production thereafter ceases from any cause this Lease shall not terminate as to the proration unit attributable to the well or wells affected thereby if Lessee commences reworking or additional actual drilling within one hundred eighty (180) days thereafter, and such reworking or additional drilling is diligently prosecuted with no cessation of more than one hundred eighty (180) consecutive days, and production in paying quantities thereafter resumes.

If, at the expiration of the primary term, or the expiration of any extended term provided in Section 6 above, whichever is later, oil and/or gas are not then being produced from any well or wells on the leased premises, but Lessee is then engaged in operations (as defined hereinafter) on any such well or wells, this Lease shall remain in force for so long as such operations are diligently prosecuted with no cessation of more than one hundred eighty (180) consecutive days between such cessation and the resumption of such operations. If such operations result in the production of oil or gas in paying quantities, this Lease shall not terminate as to the proration unit attributable to the well or wells then producing oil or gas in such quantities; but this Lease shall terminate as to all other acreage unless Lessee shall have commenced drilling a new well or wells in accordance with the Continuous Development provisions of Section 6 of this Lease.

Wherever used in this Lease the word "operations" shall mean operations for and any of the following: actual drilling, testing, completing, sidetracking, reworking, recompleting, deepening, plugging back or repairing of a well in search for or in an endeavor to obtain production of oil or gas in paying quantities.

8. **Right to Take Production in Kind.** Lessor shall always have the right, at any time and from time to time, upon reasonable written notice to Lessee, to take Lessor's share of oil, gas and processed liquids in kind. Lessor may elect to take Lessor's gas in kind at the well, or at the point of delivery where Lessee delivers Lessee's gas to any third party. If gas is processed, lessor may elect to take Lessor's share of the residue gas attributable to production from the leased premises, at the same point of delivery where Lessee received its share of residue gas or has its share of residue gas delivered to a third party. Lessor may elect to have its royalty share of processed liquids stored in tanks at the plant or delivered into pipelines on the same basis as Lessee's share of liquids is stored or delivered. Lessor shall reimburse Lessee for all reasonable costs incurred by Lessee in installing, operating or maintaining additional facilities necessary for Lessor's royalty gas and processed liquids to be separately metered, accounted for, and delivered to a third party, but Lessor shall not be charged for any expense in the production, gathering, dehydration, separation, compression, transportation, treatment, processing or storage of Lessor's share of gas and processed liquids along with Lessee's share of gas and processed liquids.

9. **Shut-in Payments.** While there is a well on the leased premises capable of producing gas in paying quantities but the production thereof is shut-in, shut-down or suspended for lack of a market, available pipeline, or because of government restrictions or, if it is economically inadvisable for Lessee to sell gas for a time, then, Lessee may pay as shut-in royalty on or before ninety (90) days after the date on which (1) production from any such well is shut-in, shut-down or suspended; or (2) this Lease is no longer maintained by compliance with one of the other preservation provisions hereof, whichever is the later date, and thereafter at annual intervals the sum of One Hundred Dollars (\$100.00) per well, for each and every shut-in, shut-down or suspended well. If such payment is made in accordance with the terms hereof, this Lease shall not terminate, but shall continue in force for a period of one (1) year from the date of making such shut-in payment (subject to the exceptions set out hereafter) and it will be considered that gas is being produced from the leased premises in paying quantities within the meaning of each pertinent provision of this Lease. Any shut-in royalty payment shall not be a credit against production nor credited with prior production royalty. In the event that production is begun or resumed during the year following the payment of a shut-in royalty payment and is subsequently shut-in, during such year the second annual shut-in payment shall be due and payable on the anniversary date of the first payment. If there is production on such first anniversary date and the well is subsequently shut-in, shut-down or suspended, then the second shut-in payment shall be made on or before ninety (90) days after such new shut-in date or the Lease shall terminate. Notwithstanding anything to the contrary set out above, should the shut-in period extend beyond the expiration of the primary term such shut-in provision will maintain the rights granted by this Lease only to the producing units and horizons of such gas well(s) as if they were producing gas in paying quantities pursuant to Section 2 above. Should such shut-in royalty payments not be made in a timely manner as provided for above, then, in that event, it shall be considered for all purposes that there is no production of gas from any such well or wells and, unless this Lease is being maintained by any other preservation provision hereof, this Lease shall

terminate automatically at midnight on the last day provided for the payment of such shut-in royalties, and Lessee shall thereupon furnish to Lessor a release of all of its interest in and to this Lease as provided in Section 17.

10. **Pooling.** Lessee does not have the right and power to pool or combine the acreage covered by this Lease or any portion thereof as to oil and gas, or either of them, with any other land or leases.

11. **Assignability.** The rights of either party hereunder may be assigned in whole or in part and the provisions hereof shall extend to the heirs, executors, administrators, successors and assigns of the parties hereto.

12. **Proration Unit.** The term "proration unit" where used in this Lease, shall mean *i*) forty (40) acres plus a tolerance of ten percent (10%) surrounding each well classified as an oil well by the appropriate governmental authority; and *ii*) one hundred sixty (160) acres plus a tolerance of ten percent (10%) surrounding each well classified as a gas well by the appropriate governmental authority.

13. **Water.** To the extent Lessor owns any water rights, Lessee shall have the free use of water from the leased premises, for all operations solely on the leased premises. Lessee shall comply with all applicable rules in disposition (by reinjection or otherwise) of salt water, brine or other fluids utilized in or resulting from operations, and shall not cause or permit any such substances to damage or pollute the surface of the leased premises or any fresh water sands lying thereunder.

14. **Limitation to Oil and Gas.** This Lease is intended to cover only oil and gas producible by conventional oil and gas industry accepted means (ie. the drilling and producing of vertical and/or horizontal wellbores.) Lessor expressly reserves and retains herefrom all gilsonite, trona, oil shale reserved by a prior owner and all other minerals (except oil and gas) which may underlie all or part of the leased premises. The term "oil shale" is defined as a mineable, kerogen-bearing, finely laminated brown or black sedimentary rock that will yield liquid or gaseous hydrocarbons on distillation.

15. **Notifications Required.** Lessee shall advise Lessor in writing of the location of each well to be drilled upon the leased premises after commencement of operations, and shall advise Lessor in writing the date of completion and/or abandonment of each well drilled on the leased premises (such notice shall include furnishing Lessor a copy of the applicable completion or plugging report filed with any governmental or regulatory agency) within thirty (30) days after completion or abandonment. As to any well drilled under the provisions of this Lease, Lessor, or Lessor's representatives, or any one or more of the same, shall have access to such well and upon request shall be furnished with copies of daily drilling reports. Such reports and information shall be furnished within seven (7) days after the same are obtained or compiled by Lessee. In addition, Lessee shall upon written request furnish Lessor within thirty (30) days from the date of the request or thirty (30) days from the date that the data is received by Lessee:

A. Plats or maps showing the location of the well on this Lease.

B. The details of any tests taken in said well, and the results of any core analysis or analyses which shall be run on any cores taken while drilling said well.

C. Upon commencement of any drilling or reworking operations on this Lease with copies of all reports filed with the appropriate governmental authority or other governmental agency having jurisdiction in connection with such operation.

D. Upon completion of any drilling or reworking operations on this Lease with copies of all logs run in such well and copies of core or other type of formation analysis subject to a confidentiality obligation on Lessor's part if filed as confidential with the appropriate governmental authority.

E. A summary report, to be made annually on the anniversary date of this Lease and commencing upon the expiration of the primary term of this Lease, to include (1) on the reporting date the number of producing wells and the number of wells not producing but not plugged; (2) the number of wells that were plugged during the previous twelve (12) months, and (3) a map denoting the location of each of these wells on the leased premises.

F. It is understood and agreed that all information provided Lessor herein is proprietary and is to be held in confidence.

16. **Force Majeure.** Lessee shall not be liable for delays or defaults in its performance of any agreement or covenant hereunder due to force majeure. The term "force majeure" shall mean: Any act of God including but not limited to storms, floods, washouts, landslides, and lightning; act of the public enemy; wars, blockades, insurrection or riots; strikes or lockouts; epidemics or quarantine regulations; laws, acts, orders or requests of Federal, State, Municipal or other governments or governmental officers or agents under the color of authority requiring, ordering or directing Lessee to cease drilling, reworking or producing operations; freight embargoes or failures; exhaustion or unavailability or delays in delivery of any product, labor, service or material. The term "force majeure" shall not include lack of markets for production or any other events affecting only the economic or financial aspects of drilling, development or production. For a period of sixty (60) days after termination of an event of force majeure, each and every provision of this Lease that might operate to terminate it or the estate conveyed by it shall be suspended and inoperative and this Lease shall continue in full force, provided, however, that in no event will the primary term be extended unless Lessee has begun the actual drilling of a well prior to the date of the expiration of the primary term.

17. **Releases Required.** Within ninety (90) days after the partial termination of this Lease as provided under any of the terms and provisions of this Lease, Lessee shall deliver to Lessor a plat showing the proration units designated by Lessee, and a fully executed, recordable release properly describing the lands and depths to be retained by Lessee around each producing well. If the lease terminates in its entirety, then Lessee shall deliver a complete, fully executed, recordable release to Lessor within thirty (30) days. If such release complies with the requirements of this section, Lessor shall record such release.

18. **Indemnification.** Lessee, its successors and assigns, agrees to indemnify, defend and hold harmless the parties herein designated Lessor, and each of them, from and against any and all claims, losses, liabilities, fines, costs, expenses (including attorneys fees and expenses) resulting from or arising out of Lessee's ownership of this Lease or in connection with operations of or for Lessee, its agents, contractors, or subcontractors hereunder, regardless of the cause of such claims, losses, liabilities, fines, costs or expenses. This provisions and its indemnities shall survive the termination of this Lease and shall bind and inure to the successors, heirs and assigns of Lessor and Lessee.

19. **No Warranties of Title.** This Lease is made without warranties of any kind, either express or implied. Lessor agrees that Lessee, at its option, after having given Lessor sixty (60) days' written notice, may discharge any tax, mortgage or other lien upon Lessor's interest in said land, either in whole or in part, and in the event lessee does so, it shall be subrogated to such lien with right to enforce same, subject to any defenses of Lessor, and apply royalties accruing hereunder toward satisfying same.

20. **Proportionate Reduction for less than Entire Interest.** It is agreed that if Lessor's interest in the oil and gas minerals in and under any of the leased premises is less than the entire oil and gas mineral estate, then the royalties and all other benefits to accrue or to be paid to Lessor hereunder as to such lands shall be reduced to the proportion thereof which the oil and gas mineral estate of Lessor in such land bears to the entire oil and gas mineral estate. However, Lessor's royalties herein shall not be reduced with respect to the 3% of 8/8ths non-participating royalty interest presently burdening the leased premises.

21. **Compliance with Environmental Laws and Regulations.** Lessee, its successors and assigns, by its acceptance of this Lease, hereby agrees to comply with all applicable laws, rules and regulations and hereby assumes full responsibility for, and agrees to indemnify, defend and hold harmless, Lessor from and against any loss, liability, claim, fine, expense cost (including attorneys fees and expenses) and cause of action caused by or arising out of the violation (or defense of the alleged violation) of any federal, state or local laws, rules or regulations applicable to any waste material, drilling matter fluid or any hazardous substances released or caused to be released by Lessee or Lessee's agents, or independent contractors from the land leased hereunder into the atmosphere or into or upon the land or any water course or body of water, including ground water.

22. **Alteration/Modification.** The terms of this Lease cannot be altered or amended except by a written instrument clearly demonstrating such purpose and effect, and executed by both parties to this Lease. The written instrument shall describe the specific terms or provisions being altered and the proposed modification or change thereto.

23. **Ancillary Rights.** Lessee shall have the right for a period of one (1) year following the expiration of this Lease or the release of any lands covered by this Lease to remove all property and fixtures placed by Lessee on said land, including the right to draw and remove all casing. If not, Lessor shall have the option to either claim the property, in whole or in part, as its own or having the said properties and fixtures removed, in whole or in part, at Lessee's expense. If the property is opted to be removed, additional expenses for surface damages and restoring the land shall be charged to Lessee, provided, however, lessee shall not be relieved of its liability to plug any well so abandoned.

IN WITNESS WHEREOF, this instrument is executed on the date first above written.

LESSOR: EXOK, INC.

ATTEST:

By: *Steven D. Bryant*
Steven D. Bryant, President

David A. M...

Address: 6410-B North Santa Fe
Oklahoma City, OK 73116

Tax ID #: 73-1058740

LESSEE: RANKEN ENERGY CORPORATION

ATTEST:

By: *Randolph L. Coy*
Title: President

Deborah L. Coy

Address: 601 N. Kelly, Ste 103
Edmond, OK 73003

Tax ID #: 73-1278733

CORPORATE ACKNOWLEDGMENT

STATE OF OKLAHOMA)
) §
COUNTY OF OKLAHOMA)

The foregoing instrument was acknowledged before me on this 30th day of March, 1999, by Steven D. Bryant, to me known to be the identical person who subscribed his name as President of EXOK, INC., and acknowledged to me that he executed the same as his free and voluntary act and deed and as the free and voluntary act and deed of such corporation, for the uses and purposes therein set forth. Given under my hand and seal the day and year last above written.

My Commission Expires: 5/9/2000

Marilyn L. Dohnell
Marilyn L. Dohnell, Notary Public


CORPORATE ACKNOWLEDGMENT

STATE OF OKLAHOMA)
) §
COUNTY OF OKLAHOMA)

The foregoing instrument was acknowledged before me on this 29th day of March, 1999, by Randolph L. Coy, to me known to be the identical person who subscribed his name as President of **RANKEN ENERGY CORPORATION** and acknowledged to me that he executed the same as his free and voluntary act and deed and as the free and voluntary act and deed of such corporation, for the uses and purposes therein set forth. Given under my hand and seal the day and year last above written.

My Commission Expires: 7/12/02

Janet J. Reynolds
Notary Public, Janet J. Reynolds





JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

July 30, 2008

CERTIFIED MAIL NO.: 7004 2510 0004 1824 5834

Mr. Alvin Arlian
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, CO 80202

43 047 33483
DWR 12-23-24-28
12S 23E 28

Re: Extended Shut-in and Temporarily Abandoned Requirements for Wells on Fee or State Leases

Dear Mr. Arlian:

Enduring Resources, LLC has eighteen (18) Fee Lease Wells and eleven (11) Mineral Lease Wells (see attachment A) that are currently in non-compliance for extended shut-in and temporary abandonment (SI/TA) status. Wells SI/TA beyond twelve (12) consecutive months require the filing of a Sundry Notice in accordance with R649-3-36-1 for Utah Division of Oil, Gas & Mining ("Division") approval. Wells with five (5) years non-activity or non-productivity shall be plugged, unless the Division grants approval for extended shut-in time upon a showing of good cause by the operator (R649-3-36-1.3.3).

This is a second notice of non-compliance for wells 1 through 14 listed on Attachment A. The Division notified the previous operators, TCC Royalty, Ranken Energy, Mak-J Energy and Houston Exploration, on several occasions by certified mail about these wells non-compliance issues. Several plans to produce or plug were submitted, but no action has been taken to date on these wells. It has also come to the Divisions attention that Enduring no longer holds a valid lease for the DWR wells (wells 1 through 9 on Attachment A). Immediate action is required on these wells. The Division feels that sufficient time has passed to make a decision on these wells.

Please submit your plans to produce or plug these wells. If this is not addressed within 30 days, a Notice of Violation will be issued for these wells. A similar response is required for the other fifteen wells listed in Attachment A.



Page 2
Mr. Arlian
July 30, 2008

For extended SI/TA consideration the operator shall provide the Division with the following:

1. Reasons for SI/TA of the well (R649-3-36-1.1).
2. The length of time the well is expected to be SI/TA (R649-3-36-1.2), and
3. An explanation and supporting data if necessary, for showing the well has integrity, meaning that the casing, cement, equipment condition, static fluid level, pressure, existence or absence of Underground Sources of Drinking Water and other factors do not make the well a risk to public health and safety or the environment (R649-3-36-1.3)

Submitting the information suggested below may help show well integrity and may help qualify your well for extended SI/TA. **Note: As of July 1, 2003, wells in violation of the SI/TA rule R649-3-36 may be subject to full cost bonding (R649-3-1-4.2, 4.3).**

1. Wellbore diagram, and
2. Copy of recent casing pressure test, and
3. Current pressures on the wellbore (tubing pressure, casing pressure, and casing/casing annuli pressure) showing wellbore has integrity, and
4. Fluid level in the wellbore, and
5. An explanation of how the submitted information proves integrity.

If the required information is not received within 30 days of the date of this notice, further actions will be initiated. If you have any questions concerning this matter, please contact me at (801) 538-5281.

Sincerely,



Dustin K. Doucet
Petroleum Engineer

JP:js
Enclosure

cc: Compliance File
Well File
Jim Davis, SITLA

Attachment A

	Well Name	API	Lease Type	Years Inactive
1	DWR 12-23-13-22	4304733345	FEE	7 YEARS 6 MONTHS
2	DWR 12-23-34-16	4304733346	FEE	7 YEARS 3 MONTHS
3	DWR 12-23-41-21	4304733480	FEE	8 YEARS 1 MONTH
4	DWR 12-23-13-28	4304733481	FEE	7 YEARS 8 MONTHS
5	DWR 12-23-24-16	4304733482	FEE	8 YEARS 1 MONTH
6	DWR 12-23-24-28	4304733483	FEE	7 YEARS 8 MONTHS
7	DWR 12-23-31-21	4304733484	FEE	8 YEARS 2 MONTHS
8	DWR 12-23-42-29	4304733487	FEE	7 YEARS 11 MONTHS
9	DWR 12-23-44-16	4304733489	FEE	7 YEARS 8 MONTHS
10	QUEST 11-25-13-21	4304733935	FEE	4 YEARS 6 MONTHS
11	QUEST 11-25-24-10	4304734118	FEE	7 YEARS 0 MONTHS
12	QUEST 11-25-31-28	4304735310	FEE	4 YEARS 4 MONTHS
13	QUEST 11-25-34-21	4304735297	FEE	4 YEARS 4 MONTHS
14	QUEST 11-25-11-27	4304735298	FEE	4 YEARS 5 MONTHS
15	QUEST 11-25-14-22	4304735299	FEE	2 YEARS 9 MONTHS
16	HOSS 9-25-34-20	4304734756	ML-45558	2 YEARS 7 MONTHS
17	BONANZA 9-24-22-36	4304735860	ML-46527	2 YEARS 6 MONTHS
18	BONANZA 9-24-11-36	4304735861	ML-46527	1 YEAR 5 MONTHS
19	BONANZA 9-25-13-20	4304735929	ML-45558	2 YEARS 11 MONTHS
20	RAINBOW 11-24-31-16	4304736184	ML-47080	1 YEAR 1 MONTH
21	SOUTHAM CYN 10-25-21-32	4304736421	ML 47065	1 YEAR 10 MONTHS
22	AGENCY DRAW 12-21-31-36	4304736424	ML 47086	2 YEARS 1 MONTH
23	BONANZA 9-24-32-22	4304736753	FEE	2 YEARS 6 MONTHS
24	ARCHY BENCH 12-23-22-16	4304736800	ML-48957	2 YEARS 0 MONTHS
25	ARCHY BENCH 11-24-24-32	4304736819	ML-49762	1 YEAR 4 MONTHS
26	ASPHALT WASH 11-24-42-16	4304736875	ML47080	2 YEARS 2 MONTHS
27	SOUTHAM CYN 9-24-23-36	4304736880	FEE	1 YEARS 1 MONTH
28	SOUTHAM CYN 10-25-11-6	4304736933	FEE	1 YEAR 3 MONTHS
29	BUCK CYN 12-21-43-16	4304737091	ML-47085	2 YEARS 9 MONTHS

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
		7. UNIT or CA AGREEMENT NAME: N/A
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC		9. API NUMBER: 4304733483
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202	PHONE NUMBER: (303) 350-5114	10. FIELD AND POOL, OR WILDCAT: Oil Springs
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246' FSL - 2032' FWL COUNTY: Uintah QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 28 12S 23E S STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well Status Report</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This well had 5 psig SITP and 265 psig SICP in August 2008.

Enduring is requesting a 30 day extension to finish up an evaluation of the Wasatch potential in this well bore.

COPY SENT TO OPERATOR

Date: 1.28.2009

Initials: KS

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE	DATE <u>8/29/2008</u>

RECEIVED
SEP 04 2008
DIV. OF OIL, GAS & MINING

(This space for State use only)

**APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING**


DATE: 1/27/09
BY: D. Arlian

(See Instructions on Reverse Side)



DWR 12-23-24-28: 8/27/2008 (KB-Grd. 0.0ft)

ftKB (MD) Schematic - Actual



WellName								WellUserID		
DWR 12-23-24-28								UT0810.01		
APICode				County						
430473348300				UINTAH, UT						
Sec	Twn	Rge	Qtr1	Qtr2	Qtr3	XLoc	YLoc	Latitude	Longitude	
28	12S	23E	SE	SW						
Feet From			Line			Feet From			Line	
Engineer			Technician			Pumper				
SpudDate		Comp Date		KB Height		TD Drill Dept		TD Log Dept		TVD
				0		0		0		0

Casing									
Date In	Casing Type	Hole Dia	Size	Wt	Grade	Depth	Jts	Ft	
7/1/2000	. Conducto	17.500	14.000	0.00		32.00	0.00	0.00	
7/2/2000	3. Surface	12.250	8.625	24.00	J-55	321.00	8.00	0.00	
7/14/2000	. Productio	7.785	4.500	11.60	J-55	4091.00	98.00	0.00	

Tubing

Sucker Rods

Formations

Perforations

Upper	Lower	Formation	Date	Status	Gun Sz	Shot/Ft	Phasg
3744	3754		7/22/2000	Open		4	
3965	3973		7/19/2000	Plugged Ba		4	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
		7. UNIT or CA AGREEMENT NAME: N/A
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC		9. API NUMBER: 4304733483
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		10. FIELD AND POOL, OR WILDCAT: Oil Springs
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246' FSL - 2032' FWL		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 28 12S 23E S		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 12/2/2008	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well Status Report</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

DUE TO DWR DEC. 1 WILDLIFE RESTRICTION WELL HAS BEEN SHUT-IN FOR WINTER.

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE	DATE <u>12/2/2008</u>

(This space for State use only)

RECEIVED
DEC 08 2008
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
		7. UNIT or CA AGREEMENT NAME: N/A
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC		9. API NUMBER: 4304733483
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		10. FIELD AND POOL, OR WILDCAT: Oil Springs
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246' FSL - 2032' FWL		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 28 12S 23E S		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 1/2/2009	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well Status Report</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

DUE TO DWR DEC. 1 WILDLIFE RESTRICTION WELL HAS BEEN SHUT-IN FOR WINTER.

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE	DATE <u>1/2/2009</u>

(This space for State use only)

RECEIVED

JAN 05 2009

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME: N/A
2. NAME OF OPERATOR: Enduring Resources, LLC		8. WELL NAME and NUMBER: DWR 12-23-24-28
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		9. API NUMBER: 4304733483
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246' FSL - 2032' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 28 12S 23E S		10. FIELD AND POOL, OR WILDCAT: Oil Springs COUNTY: Uintah STATE: UTAH
5. PHONE NUMBER: (303) 350-5114		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 1/30/2009	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well Status Report</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

DUE TO DWR DEC. 1 TO APR. 1, WILDLIFE RESTRICTION WELL HAS BEEN SHUT-IN FOR WINTER.

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE	DATE <u>1/30/2009</u>

(This space for State use only)

RECEIVED
FEB 03 2009

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
2. NAME OF OPERATOR: Enduring Resources, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246' FSL - 2032' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 28 12S 23E S		8. WELL NAME and NUMBER: DWR 12-23-24-28
PHONE NUMBER: (303) 350-5114		9. API NUMBER: 4304733483
COUNTY: Uintah STATE: UTAH		10. FIELD AND POOL, OR WILDCAT: Oil Springs

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 4/1/2009	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well Status Report</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MONTHLY WELL STATUS REPORT:

This well shall continue to be shut-in for the month of April, 2009.

- Enduring is preparing an "Action Plan" for this and other shut-in wells.
- By May 1, 2009, the Action Plan is to be submitted for the approval of the DOG&M.

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE 	DATE <u>3/30/2009</u>

(This space for State use only)

RECEIVED
APR 02 2009

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047334830000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246 FSL 2032 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 28 Township: 12.0S Range: 23.0E Meridian: S	9. FIELD and POOL or WILDCAT: OIL SPRINGS COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/29/2009	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input checked="" type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: Monthly Status Report

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

5-29-2009 Pursuant to an Action Plan submitted to DOG&M May-2009, this well shall continue to be shut-in while six other wells are being plugged commencing June-2009.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 June 01, 2009

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 5/29/2009

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047334830000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246 FSL 2032 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 28 Township: 12.0S Range: 23.0E Meridian: S	9. FIELD and POOL or WILDCAT: OIL SPRINGS
	COUNTY: UINTAH
	STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 6/30/2009			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			
	<input checked="" type="checkbox"/> OTHER		OTHER: Monthly Status Report

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

6-30-2009 Pursuant to an Action Plan submitted to and approved by the DOG&M in May-2009, this well shall continue to be shut-in while six other wells are being plugged commencing June-2009.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 June 30, 2009

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 6/30/2009

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047334830000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246 FSL 2032 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 28 Township: 12.0S Range: 23.0E Meridian: S	9. FIELD and POOL or WILDCAT: OIL SPRINGS COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/3/2010	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached is a proposed plugging procedure for this well. 1. Seeding and surface restoration are subject to a DWR right-a-way agreement, and 2. Surface access timing is also limited to the terms of a DWR right-a-way agreement.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: October 21, 2010
 By: *Dark [Signature]*

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 10/13/2010



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047334830000

- 1. Notify the Division at least 24 hours prior to conducting abandonment operations. Please call Dan Jarvis at 801-538-5338.**
- 2. All balanced plugs shall be tagged to ensure that they are at the depth specified.**
- 3. All annuli shall be cemented from a minimum depth of 100' to the surface.**
- 4. Surface reclamation shall be done in accordance with R649-3-34 – Well Site Restoration.**
- 5. All requirements in the Oil and Gas Conservation General Rule R649-3-24 shall apply.**
- 6. If there are any changes to the procedure or the wellbore configuration, notify Dustin Doucet at 801-538-5281 (ofc) or 801-733-0983 (home) prior to continuing with the procedure.**
- 7. All other requirements for notice and reporting in the Oil and Gas Conservation General Rules shall apply.**

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: October 21, 2010
By: Dustin Doucet

Wellbore Diagram

API Well No: 43-047-33483-00-00 Permit No:
 Company Name: ENDURING RESOURCES, LLC
 Location: Sec: 28 T: 12S R: 23E Spot: SESW
 Coordinates: X: 641425 Y: 4400086
 Field Name: OIL SPRINGS
 County Name: Uintah

Well Name/No: DWR 12-23-24-28

String Information

String	Bottom (ft sub)	Diameter (inches)	Weight (lb/ft)	Length (ft)	Capacity (f/cf)
HOL1	32	17.5			
COND	32	14			
HOL2	321	12.25			
SURF	321	8.625	24	321	
HOL3	4091	7.875			
PROD	4091	4.5	11.6	4091	11.459

Plug #4

$90' / (1.15 \times 11.459) = 7.5x \text{ reqd.}$

7.5x reqd. ✓

Conductor: 14 in. @ 32 ft.
 Hole: 17.5 in. @ 32 ft.
 Cement from 321 ft. to surface
 Surface: 8.625 in. @ 321 ft.
 Hole: 12.25 in. @ 321 ft.

350'

Plug #3

$(205x) = 263'$ TOC @ 100'

Cement Information

String	BOC (ft sub)	TOC (ft sub)	Class	Sacks
PROD	4091	0	PM	975
SURF	321	0	PM	230

2060' WSTC

1717'

Plug #2

$(207x)(1.15)(11.459) = 263'$

TOC @ 1717' o.k.

Perforation Information

Top (ft sub)	Bottom (ft sub)	Shts/Ft	No Shts	Dt Squeeze
3744	3973			

Approved by the Utah Division of Oil, Gas and Mining

Date: October 21, 2010

By: Derek Duff

Plug #1

$(307x)(1.15)(11.459) = 395'$

TOC @ 3430' max o.k.

Formation Information

Formation	Depth
WSTC	2060
BMSW	3100
MVRD	3862

± 3100' BMSW

3430'

3744'

Cement from 4091 ft. to surface

Production: 4.5 in. @ 4091 ft.

Hole: 7.875 in. @ 4091 ft.

Hole: Unknown

3862' MVRD

TD: 4497 TVD: PBTD:

DWR #12-23-24-28 Proposed P&A Procedure

8 5/8" @ 321' TOC at Surface
4 1/2" 11.6# @ 4,497' TOC to surface

Open Perfs: 3,744'-54'

PBTD @ 3,825' - CIBP

Prior to MI check deadmen and blow down the well
MIRU, NDWH, NUBOP
POH and check tubing
TIH to 3,825' (top of CIBP)
Spot 30 sacks of cement to cover CIBP and open Perfs (3,744'-54')
POH and WOC and Tag
Add cement if necessary
Roll hole with produced water and corrosion inhibitor
Pressure test casing, if test fails call for orders
POH to 2,060' and spot 20 sacks (100') plug across Wasatch/Green River
interface
POH to 350' and spot 20 sacks (100' plug) across shoe
POH, leaving 3 joints of tubing in the hole
Circulate cement to surface, POH
Cut off wellhead
Top off cement in long string and annulus with 1" tubing if necessary on
Weld Plate
RDMO

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047334830000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246 FSL 2032 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 28 Township: 12.0S Range: 23.0E Meridian: S	9. FIELD and POOL or WILDCAT: OIL SPRINGS COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 12/16/2010			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Subsequent Plugging Report attached. Winter Wildlife surface restriction. Next year surface shall be re-habbed and re-seeded pursuant to DOG&M and UDWR.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 12/16/2010

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 12/16/2010

DWR 12-23-24-28
Plugging Summary Report

12-13-2010

Install and test rig anchors with Benco. MIRU Western Wellsite. Pre job safety meeting. Blow down well. ND WH. NU BOPE. No tbg in hole. PU 121 jts tbg off trailer and tag CIBP @3820. Break circulation to surface. Mix and pump 35 sks Class G balanced cement plug. TOOH SB tbg. SWI to WOC. SWIFN.


12-14-2010

Pre job safety meeting. TIH and tag TOC @3265'. Load hole with 45 bbls production water with corrosion inhibitor. TOOH 2075 '. Mix and pump 20 sks Class G balanced cement plug. TOOH LD tbg. ND BOPE. TIH to 323'. Mix and pump 25 sks Class G cement to surface. TOOH LD tbg. RD rig. Dig out WH. Cut off WH. Top off with 15 sks Class G cement. SDFN.

12-15-2010

Weld on information plate to csg stub. MO Western Wellsite.

Plugs witnessed by Dave Hackford-DOGM

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL		8. WELL NAME and NUMBER: DWR 12-23-24-28
2. NAME OF OPERATOR: Enduring Resources, LLC		9. API NUMBER: 43047334830000
3. ADDRESS OF OPERATOR: 511-16th Street, Suite 700 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext	9. FIELD and POOL or WILDCAT: OIL SPRINGS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1246 FSL 2032 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 28 Township: 12.0S Range: 23.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/17/2011		<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 50px;" type="text"/>
<input type="checkbox"/> SPUD REPORT Date of Spud:		
<input type="checkbox"/> DRILLING REPORT Report Date:		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
Reseed location as per DWR requirements with following seed mix: 20.3# Fourwing Saltbush, 18.7# Russian Wildrye, 12.4# Siberian Wheatgrass, 12.3# Crested Wheatgrass, 12.2# Western Wheatgrass, 6.2# Indian Ricegrass, 3.5# Wyoming Big Sagebrush, 1# Shadscale Saltbush. Final reclamation complete. Final report.		
		Accepted by the Utah Division of Oil, Gas and Mining
		Date: <u>10/26/2011</u>
		By: <u></u>
NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 10/21/2011



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047334830000

DOGM will conduct an inspection at assure that reclamation is complete.