



Coastal
The Energy People

April 7, 2000

Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, Utah 84078

ATTENTION: Ed Forsman / Wayne Bankert / Greg Darlington

Gentleman,

Enclosed are the original and two copies of the Application for Permit to Drill for the Ute Tribal #12-25, Ute Tribal #9-26 and the Ute Tribal #2-26.

If you have questions or need additional information, please do not hesitate to call me, (435) 781-7022.

RECEIVED

APR 10 2000

DIVISION OF
OIL, GAS AND MINING

Sincerely,

Katy Dow
Environmental Jr. Analyst

Coastal Oil & Gas Corporation

A SUBSIDIARY OF THE COASTAL CORPORATION
1368 S 1200 E • PO BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0136
Expires: November 30, 2000

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 14-20-H62-4679
1b. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator Coastal Oil & Gas Corporation		7. Unit or CA Agreement Name and No.
3a. Address P.O. Box 1148, Vernal, UT 84078	3b. Phone No. (include area code) (435) 781-7023	8. Lease Name and Well No. Ute Tribal #2-26
4. Location of Well (Report location clearly and in accordance with any State requirements)* At surface 1019' FNL & 2063' FEL At proposed prod. zone		9. API Well No.
14. Distance in miles and direction from nearest town or post office* 12.1 Miles Southeast of Ft. Duchesne, UT		10. Field and Pool, or Exploratory Leland Bench
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drg. unit line, if any) 1019'	16. No. of Acres in lease 280	11. Sec., T., R., M., or Blk. and Survey or Area NW/NE Sec. 26, T4S, R1E
17. Spacing Unit dedicated to this well 40	18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Refer to Topo C	12. County or Parish Uintah
19. Proposed Depth 6700'	20. BLM/BIA Bond No. on file U-605382-9	13. State UT
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5077' GR	22. Approximate date work will start* Upon Approval	23. Estimated duration To Be Determined

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature 	Name (Printed/Typed) Cheryl Cameron	Date 4/4/00
-------------------	--	----------------

Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 10/2/00
Title Environmental Analyst	Office RECLAMATION SPECIALIST III	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on Reverse)

43-047-33539

Federal Approval of this
Action is Necessary

RECEIVED
APR 10 2000
DIVISION OF
OIL, GAS AND MINING


T4S, R1E, U.S.B.&M.

COASTAL OIL & GAS CORP.

Well location, UTE TRIBAL #2-26, located as shown in the NW 1/4 NE 1/4 of Section 26, T4S, R1E, U.S.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT THE NORTHWEST CORNER OF SECTION 26, T4S, R1E, U.S.B.&M. TAKEN FROM THE UTELAND BUTTE QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5188 FEET.




CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert J. Kay
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 2-14-00	DATE DRAWN: 3-6-00
PARTY J.F. B.B. D.B. D.COX	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE COASTAL OIL & GAS CORP.	



LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.
- △ = SECTION CORNERS RE-ESTABLISHED.

LATITUDE = 39°06'38"
 LONGITUDE = 109°50'30"

E 1/4 35,
 Set Marked Stone,
 Pile of Stones

Mr. Ferron Secakuka
Ute Tribe
Energy & Minerals Resource Department
PO Box 70
Ft. Duchesne, UT 84026

Mr Charles H Cameron
Bureau of Indian Affairs
Uintah & Ouray Agency
Office of Mineral & Mining
PO Box 130
Ft. Duchesne, UT 84026

Ms. Lisha Cordova
State of Utah
Division of Oil Gas & Mining
1594 West North Temple, Suite 1210
Salt Lake City, UT 84114

UTE TRIBAL #2-26
NW/NE SECTION 26, T4S, R1E
UINTAH COUNTY, UTAH
14-20-H62-4679

ONSHORE ORDER NO. 1
COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

1. **Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
Green River	2026'
Garden Gulch	4767'
Douglas Creek	5417'
Castle Peak	6163'
Total Depth	6500'

RECEIVED

APR 10 2000

DIVISION OF
OIL, GAS AND MINING

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	2026'
Oil/Gas	Garden Gulch	4767"
Oil/Gas	Douglas Creek	5417'
Oil/Gas	Castle Peak	6163'
	Total Depth	6500'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment:** (Schematic Attached)

The BOP stack will consist of one 11" 3000 psi annular BOP 11" 3000 psi double ram, and one 11' drilling spool. The lower ram will contain pipe rams, and the upper ram will contain blind rams.

The choke and kill lines and the choke manifold will have a 3000 psi minimum pressure.

The BOPE and related equipment will meet the requirements of the 3M system.

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Casing and Cement Program.

5. **Drilling Fluids Program:**

Please refer to the attached Mud Program.

6. Evaluation Program

<u>Depth</u>	<u>Log Type</u>
SC-TD	DIL/FDC/CNL

7. Abnormal Conditions:

Maximum anticipated bottomhole pressure approximately equals 2,600 psi (calculated at 0.4 psi/foot @ 6500' TD).

Maximum anticipated surface pressure equals approximately 1,170 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

UTE TRIBAL #2-26
NW/NE SECTION 26, T4S, R1E
UINTAH COUNTY, UTAH
14-20-H62-4679

RECEIVED

APR 10 2000

DIVISION OF
OIL, GAS AND MINING

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. **Existing Roads:**

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

To reach the Ute Tribal #2-26 location - Proceed in a Southerly direction from Ft. Duchesne, Utah approximately 4.0 miles to the junction of this road and an existing road to the south; proceed in a southerly direction approximately 6.1 miles to the junction of this road and an existing road to the south; proceed in a southerly direction approximately 2.0 miles to the junction of this road and an existing road to the east; turn left and proceed in an easterly then southeasterly direction approximately 2.3 miles to the junction of this road and an existing road to the southwest; turn right and proceed in a southwesterly direction approximately 0.2 miles to the beginning of the proposed access road to the southwest; follow road flags in a southwesterly direction approximately 0.2 miles to the proposed location.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. **Planned Access Roads:**

Approximately 0.2 miles of access road is proposed. Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet. Appropriate water control will be installed to control erosion.

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing & Proposed Facilities:**

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

Culvert(s) shall be installed as needed as discussed during the onsite.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Desert Brown, Munsell standard color number 10 YR 6/3.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

The proposed pipeline will leave the well pad in a Northeasterly direction for an approximate distance of 940'. Please refer to Topo Map D.

5. Location and Type of Water Supply:

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. Source of Construction Materials:

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. Methods of Handling Waste Materials:

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural

drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

The plastic reinforced liner will be a minimum of 12 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

8. Ancillary Facilities:

None are anticipated.

9. Well Site Layout: (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. Plans for Reclamation of the Surface:

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

The plastic, nylon reinforced liner shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. **Surface Ownership:**

The wellpad and access road are located on lands owned by the Ute Indian Tribe.

12. **Other Information:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey was conducted by Montgomery Archaeological Consultants.

13. **Lessee's or Operators's Representative & Certification:**

Cheryl Cameron
Environmental Analyst
Coastal Oil & Gas Corporation
P.O. Box 1148
Vernal, UT 84078
(435) 781-7023

Tom Young
Drilling Manager
Coastal Oil & Gas Corporation
9 Greenway Plaza, Suite 2770
Houston, TX 77046
(713) 418-4156

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Cheryl Cameron

4/5/00
Date

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Coastal Oil & Gas Corporation

Well Name & Number: Ute Tribal #2-26

Location: NW/NE Sec. 26, T4S, R1E

Lease Number: 14-20-H62-4679

RECEIVED

APR 10 2000

DIVISION OF
OIL, GAS AND MINING

CULTURAL RESOURCES

See ENVIRONMENTAL ASSESSMENT FOR SNYDER OIL CORPORATION'S LELAND BENCH OIL FIELD, UINTAH COUNTY, UTAH EA JUNE 1995.

PALEONTOLOGICAL RESOURCES

See ENVIRONMENTAL ASSESSMENT FOR SNYDER OIL CORPORATION'S LELAND BENCH OIL FIELD, UINTAH COUNTY, UTAH EA JUNE 1995.

It has been recommended by Uinta Paleontological Associates, Inc. that a paleontological monitor should be on site during all ground disturbing activity in this area. Refer to the attached Paleontological Field Survey Report.

SOILS, WATERSHEDS, AND FLOODPLAINS

See ENVIRONMENTAL ASSESSMENT FOR SNYDER OIL CORPORATION'S LELAND BENCH OIL FIELD, UINTAH COUNTY, UTAH EA JUNE 1995.

WILDLIFE

See ENVIRONMENTAL ASSESSMENT FOR SNYDER OIL CORPORATION'S LELAND BENCH OIL FIELD, UINTAH COUNTY, UTAH EA JUNE 1995.

THREATENED, ENDANGERED, AND OTHER SENSITIVE SPECIES

See ENVIRONMENTAL ASSESSMENT FOR SNYDER OIL CORPORATION'S LELAND BENCH OIL FIELD, UINTAH COUNTY, UTAH EA JUNE 1995.

FERRUGINOUS HAWK: In the event that this well becomes a producing well, it must be equipped with a multi-cylinder engine or hospital muffler to reduce noise levels.

No construction and/or drilling activities within 0.5 miles of any active nest between March 1 and July 15, unless otherwise approved by the AO, and within 0.25 miles at all other times.

Please refer to the addendum to the Legal Plat and location of the nest on Topo 1.

COASTAL OIL & GAS CORP.

UTE TRIBAL #2-26
LOCATED IN UINTAH COUNTY, UTAH
SECTION 26, T4S, R1E, U.S.B.&M.




PHOTO: VIEW OF LOCATION STAKE

CAMERA ANGLE: WESTERLY




PHOTO: VIEW OF BEGINNING OF ROAD

CAMERA ANGLE: SOUTHWESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

3 6 00
MONTH DAY YEAR

PHOTO

TAKEN BY: J.F.

DRAWN BY: J.L.G.


REVISED: 00-00-00

T4S

L E L A N D

23

RECEIVED
APR 10 2000
DIVISION OF
OIL, GAS AND MINING



JEEP

FERRUGINOUS
HAWK NEST

2-26

9-26

R
1
E

LEGEND:

- — — — — EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- — — — — PROPOSED ACCESS
- 1/4 MI. RADIUS
- 1/4 MI. RADIUS

COASTAL OIL & GAS CORP.

**UTE TRIBAL #2-26 & #9-26
SECTION 26, T4S, R1E, U.S.B.&M.**



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC
MAP

3	31	00
MONTH	DAY	YEAR

1
TOPO


SCALE: 1" = 1000'	DRAWN BY: C.G.	REVISED: 4-4-00
-------------------	----------------	-----------------

COASTAL OIL & GAS CORP.

ADDENDUM TO LEGAL PLAT

UTE TRIBAL #2-26 & #9-26
SECTION 26, T4S, R1E, U.S.B.&M.


SCALE: 1" = 400'
DATE: 04-04-00
Drawn By: D.R.B.



RECEIVED

APR 10 2000

DIVISION OF
OIL, GAS AND MINING



LEGEND:

⊙ PROPOSED LOCATION



COASTAL OIL & GAS CORP.

UTE TRIBAL #2-26
SECTION 26, T4S, R1E, U.S.B.&M.
1019' FNL 2063' FEL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1018

TOPOGRAPHIC
MAP

3 MONTH
6 DAY
00 YEAR

SCALE: 1:100,000 DRAWN BY: J.L.G. REVISED: 00-00-00





**PROPOSED LOCATION:
UTE TRIBAL #2-26**

PROPOSED ACCESS 0.2 MI. +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING ROAD

COASTAL OIL & GAS CORP.

**UTE TRIBAL #2-26
SECTION 26, T4S, R1E, U.S.B.&M.
1019' FNL 2063' FEL**



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




**TOPOGRAPHIC
MAP**

3 6 00
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: J.L.G. REVISED: 00-00-00

**B
TOPO**



**PROPOSED LOCATION:
UTE TRIBAL #2-26**

LEGEND:

- | | |
|-------------------|-------------------------|
| ⊗ DISPOSAL WELLS | ⊗ WATER WELLS |
| ● PRODUCING WELLS | ● ABANDONED WELLS |
| ● SHUT IN WELLS | ● TEMPORARILY ABANDONED |

U E L S Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



COASTAL OIL & GAS CORP.


**UTE TRIBAL #2-26
 SECTION 26, T4S, R1E, U.S.B.&M.
 1019' FNL 2063' FEL**

**TOPOGRAPHIC
 MAP**

**3 6 00
 MONTH DAY YEAR**

SCALE: 1" = 2000' DRAWN BY: J.L.G. REVISED: 00-00-00

**C
 TOPO**



APPROXIMATE TOTAL PIPELINE DISTANCE = 940' +/-

LEGEND:

- — — — — EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- PROPOSED ACCESS

COASTAL OIL & GAS CORP.

UTE TRIBAL #2-26
 SECTION 26, T4S, R1E, U.S.B.&M.
 1019' FNL 2063' FEL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC
 MAP

3	6	00
MONTH	DAY	YEAR


SCALE: 1" = 1000' | DRAWN BY: J.L.G. | REVISED: 00-00-00

D
 TOPO

COASTAL OIL & GAS CORP.

LOCATION LAYOUT FOR

UTE TRIBAL #2-26
SECTION 26, T4S, R1E, U.S.B.&M.
1019' FNL 2063' FEL



SCALE: 1" = 50'
DATE: 03-06-00
Drawn By: D.COX

Approx. Top of Cut Slope
Proposed Access Road

F-0.4'
El. 76.6'

Sta. 3+25


F-4.2'
El. 72.8'

F-2.9'
El. 74.1'

RECEIVED


APR 10 2000

DIVISION OF
OIL, GAS AND MINING



NOTE:
Flare Pit is to be located
a min. of 100' from the
Well Head.

Approx. Toe of Fill Slope



NOTES:
Elev. Ungraded Ground At Loc. Stake = 5079.0'
FINISHED GRADE ELEV. AT LOC. STAKE = 5077.0'

FIGURE #1
UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

COASTAL OIL & GAS CORP.

TYPICAL CROSS SECTIONS FOR


UTE TRIBAL #2-26

SECTION 26, T4S, R1E, U.S.B.&M.

1019' FNL 2063' FEL

1" = 20'
X-Section
Scale
1" = 50'


DATE: 03-06-00
Drawn By: D.COX



RECEIVED


APR 10 2000

DIVISION OF
OIL, GAS AND MINING




STA. 3+25


Slope = 1 1/2:1
(Typ.)



STA. 1+50



STA. 0+50



STA. 0+00

FIGURE #2


APPROXIMATE YARDAGES

CUT	
(12") Topsoil Stripping	= 2,410 Cu. Yds.
Remaining Location	= 3,390 Cu. Yds.
TOTAL CUT	= 5,800 CU.YDS.
FILL	= 1,890 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	= 3,810 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,810 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 0 Cu. Yds.

3,000 PSI


BOP STACK



RECEIVED

APR 10 2000


DIVISION OF OIL, GAS AND MINING



COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

COMPANY NAME Coastal Oil & Gas Corporation DATE 4/4/00
 WELL NAME Ute Tribal #2-26 TD 6,500'
 FIELD Leland Bench COUNTY Uintah STATE Utah ELEVATION 5,065' KB
 SURFACE LOCATION NWNE Section 26, T4S-R1E BHL Straight Hole
 OBJECTIVE ZONE(S) Lower Green River Oil
 ADDITIONAL INFO Normally pressured to TD



CASING PROGRAM

	DESIGN FACTORS							
	SIZE	INTERVAL	WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
SURFACE	8-5/8"	0-300'	24#	K-55	STC	>10	>10	>10
PRODUCTION	5-1/2"	0-TD	15.5#	K-55	LTC	SPECIFIED BY PROD DEPT		
TUBING								

CEMENT PROGRAM

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS*	WEIGHT	YIELD
SURFACE	300	Class G + 2% CaCl ₂ + 0.25 lb/sk Flocele	110	50%	15.60	1.19
PRODUCTION	LEAD 4000	Hifill + 0.6% EX-1 + 0.25 lb/sk Flocele + 0.2% FWCA + 10 lb/sk Gilsonite + 16% Gel + 1% HR-7 + 3% Salt	280	25%	11.60	3.12
	TAIL 2500	50/50 POZ + 0.25 lb/sk Flocele + 0.4% Halad-322 + 2% Gel + 0.1% HR-5 + 2% Microbond M +5% Salt	450	25%	14.4	1.24

* or 15% over caliper log

FLOAT EQUIPMENT & CENTRALIZERS


SURFACE	Guide shoe, 1 jt, float collar. Thread lock FE up to and including pin end of FC. Centralize first 3 joints and every other joint to surface.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every other joint to top of pay (+/- 4,000').

RECEIVED

APR 10 2000

DIVISION OF
OIL, GAS AND MINING

WELLHEAD EQUIPMENT



TREE	
TUBING HEAD	11" 3M X 7-1/16" 5M
CASING SPOOL	
CASING SPOOL	
CASING HEAD	8-5/8" SOW X 11" 3M

BIT PROGRAM

INTERVAL	LE	BIT MFG & MODEL	GPM	SER	NZLS	COMMENTS
Surface Hole	11"	Various				
SC - Top of Wasatch	7-7/8"	Various				

GEOLOGICAL DATA

LOGGING:

Depth	Log Type
SC - TD	DIL/FDC/CNL

MUD LOGGER: NA
SAMPLES: NA
CORING: NA
DST: NA

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER LOSS	VISCOSITY	TREATMENT
0-Trona	Air Mist	NA	NA		
300-TD	Air Mist/Aerated Water Water/Mud	NA 8.5-9.5	NC NC - 15 cc's	NA 30-40	KCL, Gel, LCM, Polymer

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.
BOPE: 11" 2M with 2 rams. Test to 2,000 psi prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip.
Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.
Run Totco survey every 500' from surface casing shoe to TD. Maximum allowable hole angle is 5 degrees.

PROJECT ENGINEER: _____
Blaine Yeary

PROJECT MANAGER: _____
Ben Clark

DATE: _____

DATE: _____

RECEIVED
APR 10 2000
DIVISION OF
OIL, GAS AND MINING

PALEONTOLOGICAL FIELD SURVEY REPORT

COASTAL OIL AND GAS CORPORATION

UTE TRIBAL #2-26

SECTION 26, TOWNSHIP 4 SOUTH, RANGE 1 EAST

UINTAH COUNTY, UTAH

March 7, 2000

RECEIVED

APR 10 2000

**DIVISION OF
OIL, GAS AND MINING**

BY

**UINTA PALEONTOLOGICAL ASSOCIATES, INC.
SUE ANN BILBEY, Ph.D. AND EVAN HALL
446 SOUTH 100 WEST
VERNAL, UTAH 84078
435-789-1033**

**PALEONTOLOGY REPORT FOR COASTAL OIL AND GAS CORPORATION
UTE TRIBAL #2-26, Ute Tribal Lands, Uintah County, Utah**


The proposed location for Coastal Oil and Gas Corporation Ute Tribal #2-26 is in the NW 1/4, NE1/4, Section 26, Township 4 South Range 1 East, Uintah County, Utah (Figure 1). It is in Quaternary alluvium deposited on the Eocene Uinta Formation (Rowley, et al. 1985).. An extensive paleontological field survey was done of much of the Leland Bench area, in 1996 for Snyder Oil and Western Geophysical Survey (Uinta Paleontological Associates, 1996).. That survey revealed that a Quaternary alluvial surface predominates on much of Leland Bench..

Bedrock exposed at the well site in the southern portion of Section 26 is part of the Uinta Formation, a late Eocene unit noted for its extensive paleontological resources (Untermann and Untermann, 1969; Rowley, et al, 1985; Hamblin, 1991; Uinta Paleontological Associates, 1996). Significantly this area is just north of the type localities for many of the fossil mammals of the Uintan Mammal Age (i.e., the White River Pocket and Myton Pocket).. The Uinta Formation "C": or upper member (a Type 1 paleontological unit) is primarily light gray to variegated mudstones with interbedded fluvial sandstone units. Based primarily on the types of fossil mammals found on the Leland Bench, the Uinta "C" is the member represented here, unlike earlier assumptions that it is Uinta "B" (Hamblin 1994). As part of a well survey for Snyder Oil, Alden Hamblin identified a critical fossil site on the western edge of this proposed well pad (42UN945v, Figure 2).

The access road is Quaternary alluvium composed of rocky soils and weathered surfaces of the Uinta Formation. Bedrock of light grayish green to reddish gray mudstone and sandstone will be impacted along the proposed route. Scattered turtle fragments were found near the route, but were not found in place.

The well site of Ute Federal #2-26 is in a badland area weathering into a small ephemeral stream drainage. The western portion of the original Snyder site is extremely fossiliferous. Numerous fossils (titanotheres, perissodactyl, artiodactyl as well as numerous turtles) are found in this area which was identified as 42UN945v, and has been enlarged (Figure 3). They seem to be weathering from a grayish green mudstone overlain by a reddish brown fluvial sandstone. The center stake has been moved to the east, so the immediate area of the badlands will not be impacted, or only slightly. At the well site center stake we found fragments of titanotheres teeth that were not in place, but may be indicative of more material in the area.

Recommendations: This site is extremely important paleontologically. Every effort should be made to avoid the western badland area. In addition we recommend that a paleontological monitor should be on site during all ground disturbing activity in this area. Impacted fossils should be moved or collected for future research.



APPROXIMATE TOTAL PIPELINE DISTANCE = 900' +/-

LEGEND:

- EXISTING PIPELINE
- - - PROPOSED PIPELINE
- PROPOSED ACCESS

COASTAL OIL & GAS CORP.

UTE TRIBAL #2-26
 SECTION 26, T4S, R1E, U.S.B.&M.
 1019' FNL 2063' FEL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP
 3 MONTH 6 DAY 00 YEAR
 SCALE: 1" = 1000' DRAWN BY: J.L.G. REVISED: 00-00-00






Figure 2. Looking west to Ute Tribal #2-26. Fossil horizon can be seen in the background.




Figure 3. Mammal teeth and jaw bones at site 42UN945V.

LITERATURE CITED

- Black, C. C. and M. R. Dawson, 1966, A review of late Eocene mammalian fauna from North America: *American Journal of Science*, v. 264, p. 321-349.
- Bryant, B., C. W. Naeser, R. F. Marvin, and H. H. Mehnert, 1989, Upper Cretaceous and Paleogene sedimentary rocks and isotopic ages of Paleogene tuffs, Uinta Basin, Utah: *U. S. Geol. Survey Bull.* 1787-J, 22 pp.
- Cashion, W. B., 1973, Geologic and structure map of the Grand Junction Quadrangle, Colorado and Utah: *U. S. Geol. Survey Map* I-736.
- Franczyk, K. J., J. K. Pitman, and D. J. Nichols, 1990, Sedimentology, mineralogy, and depositional history of some Uppermost Cretaceous Lowermost Tertiary rocks along the Utah Book and Roan Cliffs east of the Green River: *U. S. Geol. Survey Bull.* 1787, 27 pp.
- Hamblin, A. D., 1987, Paleogeography and paleoecology of the Myton Pocket, Uinta Basin, Utah (Uinta Formation - upper Eocene): *Brigham Young University Geology Studies*, v. 34, no. 1, p. 33-60.
- Hamblin, A. H., 1991, Paleontology report for the cultural resources component of the Natural Buttes EA Study Area, Metcalf Archaeological Associates.
- Kay, J. L., 1957, The Eocene vertebrates of the Uinta Basin, Utah: *in* *Geology of the Uinta Mountains*, Intermountain Association of Petroleum Geologists Guidebook, 8th Annual Field Conference, p. 110-114.
- Rowley, P. D., W. R. Hansen, O. Tweto, and P. I. Carrara, 1985, Geologic Map of the Vernal 1° x 2° Quadrangle, Colorado, Utah, and Wyoming: *United States Geological Survey Misc. Investigation Series Map* I-1526.
- Savage, D. E. and D. E. Russell, 1983, *Mammalian paleofauna of the world*: Addison-Wesley Publ. Co., 432 pp.
- Stagner, W. L., 1941, The paleogeography of the eastern part of the Uinta Basin during Uinta B (Eocene) Time: *Annals of Carnegie Museum*, v. 28, p. 273-308.
- Uinta Paleontological Associates (Bilbey, Hamblin, Rasmussen, and Hall), 1996, Paleontological field survey for Leland Bench: Snyder Oil Corp. and Western Geophysical, 140 pp.
- Untermann, G. E. and B. R. Untermann, 1968, *Geology of Uintah County: Utah Geologic and Mineralogical Survey Bulletin* 72, 98 pp.

CULTURAL RESOURCE INVENTORY OF
COASTAL OIL & GAS WELL LOCATIONS UTE TRIBAL
2-26, 9-26, 3-25, 4-25, 7-25, 11-25 AND 12-25
IN THE LELAND BENCH AREA,
UINTAH COUNTY, UTAH

Michael S. Wolfe
and
Keith R. Montgomery

CULTURAL RESOURCE INVENTORY OF
COASTAL OIL & GAS WELL LOCATIONS UTE TRIBAL
2-26, 9-26, 3-25, 4-25, 7-25, 11-25 AND 12-25
IN THE LELAND BENCH AREA,
UINTAH COUNTY, UTAH

By:

Michael S. Wolfe
and
Keith R. Montgomery

Prepared For:

Ute Indian Tribe
Energy and Minerals
Resource Department
P.O. Box 70
Ft. Duchesne, UT 84026

Prepared Under Contract With:

Coastal Oil and Gas Corporation
P.O. Box 1148
Vernal, Utah 84078

Prepared By:

Montgomery Archaeological Consultants
P.O. Box 147
Moab, Utah 84532

March 14, 2000

Ute Indian Tribe License No. A00-363

United States Department of Interior (FLPMA)
Permit No. 99-UT-60122

State of Utah Antiquities Project (Survey)
Permit No. U-00-MQ-0023i

ABSTRACT

Cultural resource inventories were conducted by Montgomery Archaeological Consultants (MOAC) in February, 2000, for seven Coastal Oil & Gas well locations, access roads, and pipelines. The project area is located 12 miles south of Randlett, Uintah County, Utah. The proposed wells occur in Coastal Oil and Gas Corporation's Leland Bench Field and include: Ute Tribal Wells 2-26, 9-26, 3-25, 4-25, 7-25, 11-25 and 12-25. A total of 95 acres was inventoried on Ute Tribal lands, Uintah and Ouray Reservation.

The cultural resource inventory resulted in the location of seven previously-recorded sites (42Un1672, 42Un1840, 42Un2231, 42Un2345, 42Un2348, 42Un2349, and 42Un2351), and the documentation of four new archaeological sites (42Un2658, 42Un2659, 42Un2660 and 42Un2661). In addition, one historic isolated find was documented (IF-A). All the newly-recorded archaeological sites (42Un2658, 42Un2659, 42Un2660 and 42Un2661) are evaluated as eligible to the NRHP under Criterion (d) based on their potential for providing information relevant to the research domains of the area. Sites 42Un2658, 42Un2660 and 42Un2661 are classified as prehistoric temporary camps of unknown temporal affiliation. Activities conducted at these sites include possible faunal processing and lithic tool manufacturing. Diagnostic artifacts were limited to scrapers, and an absence of ground stone and hunting implements was noted. All of these sites contain one or more burned rock features which lack surface indications of cultural deposits. Since the sites occur in aeolian deposition on Leland Bench they have good potential for yielding additional diagnostic artifacts and features. In addition, further investigations of the burned rock features could yield morphological, radiocarbon, and subsistence information. Site 42Un2659 is a lithic scatter containing chipped stone tools (bifaces, scrapers, and cores) as well as debitage. The site lies in aeolian soil with potential for additional cultural remains

In conclusion, the cultural resource inventory of Coastal Oil & Gas Corporation's seven Ute Tribal well locations resulted in the location or documentation of six prehistoric sites (42Un2349, 42Un2351, 42Un2658, 42Un2659, 42Un2660 and 42Un2661) which are considered eligible to the NRHP under Criterion (d). It is recommended that these archaeological sites be avoided from well location development. Based on this recommendation, a determination of "no historic properties affected" is proposed for the project pursuant to Section 106, CFR 800.

TABLE OF CONTENTS

ABSTRACT i
TABLE OF CONTENTS ii
LIST OF TABLE ii
LIST OF FIGURES ii
INTRODUCTION 1
PREVIOUS RESEARCH 1
DESCRIPTION OF THE PROJECT AREA 2
 Environment 4
 Cultural Historical Overview 5
SURVEY METHODOLOGY 6
INVENTORY RESULTS 6
 Archaeological Sites 6
 Isolated Find 10
NATIONAL REGISTER OF HISTORIC PLACES EVALUATION 11
MANAGEMENT RECOMMENDATIONS 12
REFERENCES CITED 13
APPENDIX A: Site Location Data 16
APPENDIX B: INTERMOUNTAIN ANTIQUITIES COMPUTER
 SYSTEM (IMACS) SITE FORMS 18

LIST OF TABLE

1. Leland Bench Field Seven Well Locations Descriptions 4

LIST OF FIGURES

1. Inventory Area of Seven Wells in the Leland Bench Area 3
2. Inventory Area of Seven Wells in the Leland Bench Area
 with Cultural resources 17

INTRODUCTION

Cultural resource inventories were conducted by Montgomery Archaeological Consultants (MOAC) in February, 2000 for seven proposed well locations with associated access roads and pipelines. The project area occurs in Coastal Oil and Gas Corporation's Leland Bench Field, Uintah County, Utah. The survey was implemented at the request of Ms. Cheryl Cameron, Coastal Oil & Gas Corporation, Vernal, Utah. The project is situated on Ute Indian land (Uintah & Ouray Reservation).

The objective of the inventories was to locate, document, and evaluate any cultural resources within the project area in order to comply with Section 106 of 36 CFR 800, the National Historic Preservation Act of 1966 (as amended). Also, the inventories were implemented to attain compliance with a number of federal and state mandates, including the National Environmental and Policy Act of 1969, the Archaeological and Historic Conservation Act of 1972, the Archaeological Resources Protection Act of 1979, the American Indian Religious Freedom Act of 1978, and the Utah State Antiquities Act of 1973 (amended 1990).

The fieldwork was conducted on February 23, 24, and 28, 2000, by Keith R. Montgomery, Principal Investigator, and assisted by Michael S. Wolfe, Sharyl Kinnear-Ferris and Mark Bond. The inventory was performed under the auspices of U.S.D.I. (FLPMA) Permit No. 99-UT-60122, State of Utah Antiquities Permit (Survey) No. U-00-MQ-0023i and Ute Indian Tribe License No. A00-363.

PREVIOUS RESEARCH

Prior to the fieldwork, a file search for previous cultural resource inventories and archaeological sites was conducted by MOAC personnel, Sarah Ball, at the Division of State History, Antiquities Section, Salt Lake City. This consultation indicated that numerous archaeological surveys have been completed in the area related to energy exploration. In 1986 and 1987, three well locations and access roads were surveyed by Archaeological-Environmental Research Corporation (AERC) for Conoco Oil (Hauck 1986a, 1986b, 1987a) and Holden Energy Corporation (Hauck 1987b). Also a seismic line corridor was surveyed in 1987 for Arma Geophysical (Hauck 1987c). In 1988, AERC inventories several well locations for Holden Energy Corporation (Hauck 1988a, 1988b, 1988c). During 1994, 1995 and 1996 numerous well locations, gathering systems, and access roads were surveyed for Snyder Oil Corporation by Metcalf Archaeological Consultants (MAC) (Barclay 1994a, 1994b, 1994c, 1994d, 1994e, 1994f, 1996; Metcalf 1995) and by Brigham Young University (Richens 1995). Additional well location

inventories were completed by Senco-Phenix from 1996 to 1998 for Snyder Oil Corporation (Senulis 1996, 1997 and 1998). These inventories have demonstrated a relatively high prehistoric site density on Leland Bench. Most of these sites seem to be oriented to lithic procurement and preliminary processing of lithic material. Numerous features of fire-altered rocks, unaccompanied by ash or charcoal staining, have been recorded. Some of these sites are rather extensive (e.g., 42Un1672, 42Un1840, 42Un2345 and 42Un2351).

Seven archaeological sites have been documented within the current project area. Site 42Un1672 is an extensive lithic scatter first recorded by AERC (Hauck 1988b, 1988c) and later revisited and enlarged by MAC (Barclay 1994d, 1996). This site is evaluated as not eligible to the NRHP. Site 42Un1840 is a low density lithic procurement/temporary camp recorded by Grand River Institute in 1991 (Conners 1991), evaluated as not eligible to the National Register of Historic Places (NRHP). Site 42Un2231 is a small lithic scatter recorded by Brigham Young University (Richens 1995), and is considered eligible to the NRHP. Site 42Un2345 is a low density lithic scatter recorded by MAC (Barclay 1996), and evaluated as not eligible to the NRHP. Site 42Un2348 is a lithic scatter recorded by Senco-Phenix (Senulis 1996), and is considered not eligible to the NRHP. Site 42Un2349 is a temporary camp with fire-cracked rock documented by Senco-Phenix (Senulis 1996), and evaluated as eligible to the NRHP. Site 42Un2351 is a lithic procurement/processing locality and campsite recorded by Senco-Phenix (Senulis 1996), and is evaluated as eligible to the NRHP.

DESCRIPTION OF PROJECT AREA

The project area is located in the Uintah Basin. More specifically, it is located northwest of the Green River and north of Pariette Wash, approximately 12 miles south of Randlett, Uintah County, Utah. The seven proposed well locations occur in Coastal Oil and Gas Corporation's Leland Bench Field and include: Ute Tribal 2-26, 9-26, 3-25, 4-25, 7-25, 11-25 and 12-25 (Figure 1). The project area is situated in Township 4 South, Range 1 East, Sections 23, 24, 25 and 26 (Figure 1). Specific information on the proposed well locations are presented in Table 1.




Figure 1. Inventory Area of Coastal Oil and Gas Corporation's Seven Wells in the Leland Bench Area, Uintah County, UT. USGS 7.5 Uteland Butte, UT1964. Scale 1:24000.

Table 1. Coastal Oil & Gas Corporations Leland Bench Seven Well Locations

Well Location Designation	Legal Location	Location at Surface	Access/Pipeline	Cultural Resources
Ute Tribal 2-26	T4S R1E S26, NW, NW	1019' FNL 2063' FEL	Access/Pipeline 600'	42Un2351
Ute Tribal 9-26	T4S R1E S26, NE, SE	2180' FSL 460' FEL	Access/Pipeline 1200'	42Un1672
Ute Tribal 3-25	T4S R1E S25, NE, NW	549' FNL 2162' FWL	Access/Pipeline 2500'	42Un1840, 42Un2345 42Un2348, 42Un2349, IF-A
Ute Tribal 4-25	T4S R1E S25, NW, NW	509' FNL 593' FWL	Pipeline 2000' Access/Pipeline 1800'	42Un1840, 42Un2231, 42Un2345
Ute Tribal 7-25	T4S R1E S25, SW, NE	1850' FNL 2050' FEL	Access/Pipeline 1100'	42Un2658, 42Un2659, 42Un2660
Ute Tribal 11-25	T4S R1E S25, NE, SW	1950' FSL 1902' FWL	Access/Pipeline 400'	42Un2661
Ute Tribal 12-25	T4S R1E S25, NW, SW	2121' FSL 834' FWL	Access/Pipeline 1300'	42Un1672

Environment

The study area lies within the Uinta Basin physiographic unit, a distinctly bowl-shaped geologic structure (Stokes 1986:231). The entire Uinta Basin ecosystem is within the Green River drainage, considered to be the northernmost extension of the Colorado Plateau. Specifically, the survey area is situated on the deeply dissected uplands of Leland Bench. The geology includes Quaternary alluvial deposits, older alluvial terrace deposits, and rock outcrops of the Eocene Uintah Formation. In addition exposed sections of the Duchesne River Formation occur in the area which are composed of river-deposited soft clay, conglomerate mudstone, and ledgy sandstone. This formation is thought to contain the latest Eocene fauna of North America composed of fossil vertebrates of turtles, artiodactyls, perissodactyls, rodents, carnivores, and crocodile (Ibid:160). The depositional environment in the project area is characterized by exposed sandstone and shale bedrock

alternating with barren clay surfaces and sand fields. The nearest water source is Pariette Draw situated several miles south of Leland Bench which drains southeast into the Green River. The inventory area is also dissected by various intermittent drainages. The elevation of the project area ranges from 4950 to 5250 feet a.s.l. The project occurs within the Upper Sonoran Desert Shrub association. Shadscale and saltbrush communities are found in the alkaline bottoms. Low sagebrush and grasses are found on the terraces and benches. Some areas are barren due to the alkali nature of the soil and high rates of erosion. Modern disturbances include livestock grazing, roads, and oil/gas development.

Cultural-Historical Overview

The cultural-chronological sequence represented in the study area includes the Paleoindian, Archaic, Fremont, and Euro-American stages. The earliest inhabitants of the region are representative of the Paleoindian stage (ca. 12,000-8,000 B.P.). This stage is characterized by the adaptation to terminal Pleistocene environments and characterized by the exploitation of big game fauna. The presence of Paleoindian hunters in the Uinta Basin region is implied by the discovery of Clovis and Folsom fluted points, as well as the later Plano Complex lanceolate projectile points. The Archaic stage (ca. 8,000 B.P. - 1,500 B.P.) is characterized by peoples depending on a foraging subsistence strategy, seasonally exploiting a wide spectrum of plant and animal species in different ecozones. In the Uinta Basin evidence of widespread Early Archaic exploitation is relatively sparse compared to the subsequent Middle and Late Archaic periods. Early Archaic (ca. 6000 to 3000 B.C.) sites in the basin include sand dune sites and rockshelters clustered mainly in the lower White River drainage as well as along the Green River in the Browns Park and Flaming Gorge area (Spangler 1995:373). Projectile points recovered from Uinta Basin contexts include Pinto Series, Humboldt, Elko Series, Northern Side-notched, Hawken Side-notched, Sudden Side-notched and Rocker Base Side-notched points. The Formative stage (A.D. 500-1300) is recognized in the area as the Uinta Fremont, first termed by Marwitt (1970). This stage is characterized by reliance upon domesticated corn and squash, increasing sedentism, and in its later periods, substantial habitation structures, pottery, and bow and arrow weapon technology. Based on the evidence from Caldwell Village, Boundary Village, Deluge Shelter, Mantles Cave and others, the temporal range of the Uinta Fremont appears to be from A.D. 650 to 950.

Archaeological evidence suggests that the Ute appeared in east-central Utah at approximately A.D. 1100 or shortly before the disappearance of Formative-stage peoples (Reed 1994). The archaeological remains of Numic-speaking Ute consist primarily of lithic scatters with low quantities of brown ware ceramics, rock art, and occasional wickiups. The Eastern Ute, comprising the bands living east of the Green River, has been divided into four phases (Reed 1988). The earliest and most tenuous phase is the Chipeta Phase, dated between A.D. 1250 and 1400. Diagnostic artifacts include Desert Side-notched, Cottonwood Triangular, and small corner-notched arrow points and possibly Shoshonean knives. The Canalla phase (ca. A.D. 1400-1650) designates the period between the appearance of well-dated Uncompahgre brown ware ceramics and the adoption of an equestrian lifeway. Diagnostic artifacts include Uncompahgre Brown Ware ceramics,

Desert Side-notched and Cottonwood Triangular points, and Shoshonean knives. The pedestrian hunter and gatherers probably lived in wickiups. Near the end of the phase, some groups may have obtained trade items from Spanish settlements in New Mexico (Horn, Reed, and Chandler 1994:131). The Antero phase (ca. A.D. 1650-1881) represents a shift to a fully equestrian lifestyle and integration of EuroAmerican trade goods into Ute material culture. The introduction of the horse allowed the hunting of bison on the Plains and led to an increase in the importance of raiding for economic gain (Ibid:131). EuroAmerican trade goods became important, and tepees as well as wickiups were inhabited. In 1912, Robert H. Lowie observed conical lodges at Ouray differing from the tipi merely in having a brush cover and was informed that these were used in the old days for a summer habitation (Smith 1974:33).

SURVEY METHODOLOGY

The archaeologists were accompanied to the field by Alvin Ignacio, Oil and Gas Technician, Energy & Minerals Resources Department, Ute Indian Tribe. An intensive pedestrian survey was performed for this project which is considered 100% coverage. At the seven proposed well locations, a 10 acre square was defined, centered on the well pad center stake. The interior of the well locations was examined for cultural resources by the archaeologists walking parallel transects spaced no more than 10 meters apart. A 100-foot wide corridor was surveyed along the access and pipeline corridors, inspected by walking parallel transects along the staked centerline, spaced no more than 10 meters apart. Ground visibility was considered good. A total of 95 acres was inventoried on Ute Tribal lands.

INVENTORY RESULTS

The cultural resource inventory resulted in the location of seven previously-recorded sites (42Un1672, 42Un1840, 42Un2231, 42Un2345, 42Un2348, 42Un2349, and 42Un2351) and the documentation of four new archaeological sites (42Un2658, 42Un2659, 42Un2660 and 42Un2661). In addition, one isolated historic artifact was documented (IF-A), and a previously unrecorded feature was added to Site 42Un1672.

Archaeological Sites

Smithsonian Site No.: 42Un1672
Temporary Site No.: 26-4-I #1
Legal Description: T 4S, R 2E, S. 25
Well Location: Ute Tribal 12-25
NRHP Evaluation: Not Eligible

Description: This is an extensive prehistoric lithic scatter originally recorded by AERC in 1988 (Hauck 1988b, 1988c) and evaluated as not eligible to the NRHP. In 1994 the site was inspected and enlarged to a 467,000 square meter area by MAC (Barclay

1994a, 1994b, 1994c, 1994d, 1994e and 1994f). Several years later it was revisited by MAC who increased the site area to 481,436 square meters (Barclay 1996). Basically the site is a low density lithic scatter containing early stage tools reflecting secondary procurement and lithic testing activities. Numerous inspections at this locality have failed to identify temporal diagnostic artifacts. The site is presently disturbed by several well pads and access roads. During this project a rock concentration (Feature 1) was recorded, located at the base of a steep slope 50 feet northeast of the access road into proposed Ute Tribal 12-25 well location. Approximately 55 alluvial cobbles and fragments, most of which appear fire-reddened are scattered along a residual slope within a 1 by 3 meter area. This feature lacks morphology and cultural deposits (e.g., charcoal or ash). There is no apparent depth potential, therefore the documentation of Feature 1 does not change the eligibility of this site.

Smithsonian Site No.: 42Un1840
Temporary Site No.: None
Legal Description: T 4S, R 1E, S. 24
Well Location: Ute Tribal 4-25 and 3-25
NRHP Evaluation: Not Eligible

Description: This is a lithic procurement locality recorded by Grand River Institute in 1991 (Connors 1991). The site extends 480 by 120 meters along a gravel finger ridge. The source material consists of Quaternary cobbles of chert and quartzite. Cultural materials include about 15 flakes and core fragments. Most of the chipped stone tools are manufactured from chert and consist of a biface, a uniface, a large scraper, a flake tool, as well as two quartzite scraper-on-cores. Located in the northeast portion of the site is a possible deflated hearth. This site is evaluated as not eligible to the NRHP since it is unlikely to yield important information concerning the prehistory of the area.

Smithsonian Site No.: 42Un2231
Temporary Site No.: SOCO 25-1
Legal Description: T 4S, R 1E, S. 25
Well Location: Ute Tribal 4-25
NRHP Evaluation: Not Eligible

Description: This is a prehistoric lithic scatter recorded by Brigham Young University in 1995 (Talbot 1995). This site measures about 75 by 100 meters and is situated on a sandy knoll extending onto the adjacent desert pavement. Cultural materials includes a light scatter of decortication and secondary flakes with two concentrations noted. Chipped stone tools are limited to a quartzite chopper and a chert hammerstone. No temporal diagnostic artifacts were observed. This site is evaluated as not eligible to the NRHP based on the shallow soils and lack of potential for yielding additional information.

Smithsonian Site No.: 42Un2345
Temporary Site No.: Leland #1
Legal Description: T 4S, R 1E, S. 23 and 26
Well Location: Ute Tribal 4-25
NRHP Evaluation: Not Eligible

Description: This is a low density lithic scatter recorded by Metcalf Archaeological Consultants in 1996 (Barclay 1996). The site is associated with a deflated area of desert pavement containing cobbles of quartzite and chert. It consists predominately of lithic debitage, cores, and tested cobbles reflecting casual lithic testing and secondary procurement activities. The site is considered not eligible for NRHP inclusion based on the absence of diagnostic artifacts, features, and lack of depth potential.

Smithsonian Site No.: 42Un2348
Temporary Site No.: LB-1
Legal Description: T 4S, R 1E, S. 25
Well Location: Ute Tribal 3-25
NRHP Evaluation: Not Eligible

Description: This is a prehistoric lithic scatter of unknown temporal affiliation documented by Senco-Phenix in 1996 (Senulis 1996). The site is situated on a residual ridge and measures 70 by 80 meters. Cultural materials consist of about 90 chert secondary flakes and a mano fragment. Three deflated burned rock clusters were identified containing 10 to 15 fire-cracked rocks and lacking cultural deposits. This site is considered not eligible to the NRHP due to its poor physical integrity, the absence of intact features, and minimal potential for buried cultural remains.

Smithsonian Site No.: 42Un2349
Temporary Site No.: LB-2
Legal Description: T 4S, R 1E, Section 25
Well Location: Ute Tribal 3-25
NRHP Evaluation: Eligible

Description: This is a lithic scatter of unknown temporal affiliation documented by Senco-Phenix in 1996 (Senulis 1996). The site is situated in aeolian deposition near the rim of a high ridge, and measures 50 by 50 meters. Cultural materials include lithic debitage, a uniface, and four ground stone fragments. In addition four fire-cracked features were recorded. The site is evaluated as eligible to the NRHP, since potential exists for buried cultural deposits and features which could provide pertinent data to address the research domains of the area. The site is located about 100 feet east of the proposed access road into Ute Tribal 3-25 well location.

Smithsonian Site No.: 42Un2351
Temporary Site No.: LB-4
Legal Description: T 4S, R 1E, S. 26
Well Location: Ute Tribal 2-26
NRHP Evaluation: Eligible

Description: This is an extensive lithic scatter of unknown temporal affiliation documented in 1996 by Senco-Phenix (Senulis 1996). This site is situated on a south-facing bench and extends 500 by 225 meters (2500 sq. meters). Cultural materials consist of 15-25 concentrations of fire-cracked rock, two scrapers, four bifaces, 14+ core/blanks, and approximately 65 pieces of debitage dispersed over a large ridge surrounded by badlands. This site is interpreted as a lithic processing area where selected cobbles were transported to the site, heat treated, broken, and selected for use as cores, blanks, and preforms. The vast majority of the artifacts and debris is heat treated. There is very little evidence of lithic reduction. Based on the potential for buried cultural materials this site is considered eligible to the NRHP. The site is situated 150 feet west of proposed Ute Tribal 2-26 well location.

Smithsonian Site No.: 42Un2658
Temporary Site No.: MOAC 0023-1
Legal Description: T 4S, R 1E, S. 25
Well Location: Ute Tribal 7-25
NRHP Evaluation: Eligible

Description: This is a prehistoric temporary camp of unknown temporal affiliation which reflects possible faunal procurement tasks. The site is situated on the rim of a canyon edge and mesa. Two deflated hearth features (Features 1 and 2) were found on the canyon edge and slope, and a third deflated hearth (Feature 3) occurs in a sand dune. The cultural material is limited to three cobble scrapers. Based on the potential for buried cultural material within the sandy portions of this site, this site is evaluated as eligible for inclusion in the NRHP. The site is located outside of proposed Ute Tribal 7-25, situated about 200 feet southeast of the well pad.

Smithsonian Site No.: 42Un2659
Temporary Site No.: MOAC 0023-2
Legal Description: T 4S, R 1E, S. 25
Well Location: Ute Tribal 7-25
NRHP Evaluation: Eligible

Description: This is a low density lithic scatter of unknown temporal affiliation situated in aeolian deposits on a north slope on Leland Bench. The lithic debitage consists of about 42 decortication and secondary flakes from white/red semi-translucent chert and brown/beige opaque siltstone. Diagnostic artifacts include two biface preforms (Tools 1 and 8), two cores (Tools 4 and 5), and four scrapers (Tools 2, 3, 6, and 7) suggesting this site was utilized for resource processing in addition to lithic reduction. No features were observed. This site is recommended as eligible to the NRHP based on its potential for additional cultural remains. It is located outside of proposed Ute Tribal 7-25 approximately 100 feet north of the well pad and on the south side of a knoll.

Smithsonian Site No.: 42Un2660
Temporary Site No.: MOAC 0023-3
Legal Description: T 4S, R 1E, S. 25
Well Location: Ute Tribal 7-25
NRHP Evaluation: Eligible

Description: This is a small prehistoric temporary camp of unknown temporal affiliation. It is situated on a gently sloping sandy area of Leland Bench, and measures 55 by 25 meters. Cultural materials consist of less than 25 pieces of chert and quartzite debitage and an oval chert scraper (Tool 1). A deflated hearth (Feature 1), represented by a 1 by 1 meter concentration of 12 to 15 oxidized cobbles and fire-broken rock occurs along the north side of the site. This site is recommended as eligible to the NRHP based on the potential for subsurface cultural materials which could provide significant data concerning the prehistory of the area. The site is located 150 feet north of the proposed access road into proposed Ute Tribal 7-25 well location.

Smithsonian Site No.: 42Un2661
Temporary Site No.: MOAC 0023-4
Legal Description: T 4S, R 1E, S. 25
Well Location: Ute Tribal 11-25
NRHP Evaluation: Eligible

Description: This is a prehistoric temporary camp of unknown temporal affiliation situated in a blowout within a sandy area and measuring 20 by 14 meters. This site contains three features consisting of concentrations of oxidized, fire-altered alluvial cobbles and fragments representing deflated hearths (Features 1, 2, and 3). No ash staining or charcoal was observed. A lithic cluster (1 by 0.5 meters) consisting of six primary flakes derived from a gray/pink quartzite, is located adjacent to the site datum. No other lithic debitage or tools were observed. The site is evaluated as eligible for inclusion in the NRHP, since it lies in a sand dune yielding potential for subsurface cultural remains. The site is located 100 feet south of proposed Ute Tribal 11-25 well location.

Isolated Find of Artifacts

Isolated Find A (IF-A) is located in the SE/NE/NW, S. 25, T 4S, R 1E (UTM Zone 12, 599530E / 4440547N). It consists of a hole-in-cap milk can with two punched holes in one end. It measures 4 6/16" by 2 15/16" with a 7/8" cap diameter.

NATIONAL REGISTER OF HISTORIC PLACES EVALUATION

The National Register Criteria for Evaluation of Significance and procedures for nominating cultural resources to the National Register of Historic Places (NRHP) are outlined in 36 CFR 60.4 as follows:

The quality of significance in American history, architecture, archaeology, and culture is present in districts, sites, buildings, structures, and objects of State and local importance that possess integrity of location, design, setting, material, workmanship, feeling, and association, and that they:

- a)...are associated with events that have made a significant contribution to the broad patterns of our history; or
- b)...are associated with the lives of persons significant to our past; or
- c)...embody the distinctive characteristics of a type, period, or method of construction; or that represents the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction; or
- d)...have yielded or may be likely to yield information important in prehistory or history.

The cultural resource inventory resulted in the documentation of four newly recorded archaeological sites (42Un2658, 42Un2659, 42Un2660 and 42Un2661) and one newly recorded isolated find (IF-A). These sites are evaluated as eligible to the NRHP under Criterion (d) based on their potential for providing information relevant to the research domains of the area. Sites 42Un2658, 42Un2660 and 42Un2661 are classified as prehistoric temporary camps of unknown temporal affiliation. Activities conducted at these sites include possible faunal processing and lithic tool manufacturing. Diagnostic artifacts were limited to scrapers, with an absence of ground stone and hunting implements. All of these sites contain one or more burned rock features which lack surface indications of cultural deposits. Since the sites occur in aeolian deposits on Leland Bench they have good potential for yielding additional diagnostic artifacts and features. In addition, further investigations of the burned rock features could yield morphological, radiocarbon, and subsistence information. Site 42Un2659 is a lithic scatter containing chipped stone tools (bifaces, scrapers, and cores) as well as debitage. The site lies in aeolian soil with potential for additional cultural remains.

MANAGEMENT RECOMMENDATIONS

The cultural resource inventory of Coastal Oil & Gas Corporation's seven Ute Tribal well locations resulted in the location or documentation of six prehistoric sites (42Un2349, 42Un2351, 42Un2658, 42Un2659, 42Un2660 and 42Un2661) which are considered eligible to the NRHP under Criterion (d). It is recommended that these archaeological sites be avoided from well location development. Based on this recommendation, a determination of "no historic properties affected" is proposed for the project pursuant to Section 106, CFR 800.

REFERENCES CITED

Barclay, D.

- 1994a Snyder Oil Corporation's Ute #26-3-G Well Pad and Access, Uintah County, Utah. Metcalf Archaeological Consultants. Report No. U-94-MM-655i.
- 1994b Snyder Oil Corporation's Ute #25-3-L Well Pad and Access, Uintah County, Utah. Metcalf Archaeological Consultants. Report No. U-94-MM-655i.
- 1994c Snyder Oil Corporation's Ute #21-4-G Well Pad and Access, Uintah County, Utah. Metcalf Archaeological Consultants. Report No. U-94-MM-655i.
- 1994d Snyder Oil Corporation's Ute #26-4-I Well Pad and Access, Uintah County, Utah. Metcalf Archaeological Consultants. Report No. U-94-MM-655i.
- 1994e Snyder Oil Corporation's Ute #26-5-J Well Pad and Access, Uintah County, Utah. Metcalf Archaeological Consultants. Report No. U-94-MM-655i.
- 1994f Snyder Oil Corporation's Ute #26-5-J Well Pad and Access, Uintah County, Utah. Metcalf Archaeological Consultants. Report No. U-94-MM-655i.
- 1996 Snyder Oil Corporation's Proposed Leland Bench Natural Gas Pipeline Gathering System, Class III Cultural Resource Inventory, Uintah County, Utah. Metcalf Archaeological Consultants. Report No. U-96-MM-0469i.

Burton, D.K.

- 1996 *A History of Uintah County: Scratching the Surface*. Utah Centennial County History Series. Utah State Historical Society and Uintah County Commission.

Connors, C.E.

- 1991 Cultural Resource Inventory for Warren Am. Oil Company Ute Tribal #24-1 Well. Ms. Prepared by Grand River Institute. Report No. U-91-GB-102i.

Callaway, D., J. Janetski, and O. C. Stewart

- 1986 Ute. In *Great Basin*, edited by Warren L. D'Azevedo, pp. 336-367. Handbook of North American Indians, Volume II: Great Basin, edited by William C. Sturtevant, Smithsonian Institution, Washington.

Hauck F.R.

- 1986a Cultural Resource Evaluation of The Pleasant Valley Tribal Unit No. 26-1 Proposed Well Location in the Leland Bench Locality of Uintah County, Utah. Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. U-86-AF-181i.

- Hauck, F.R.
1986b Cultural Resource Evaluation of Access Route Into The Pleasant Valley Tribal Unit No. 26-1 Proposed Well Location in the Leland Bench Locality of Uintah County, Utah. Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. U-86-AF-826i.
- 1987a Cultural Resource Evaluation of a Proposed Well Location in the Leland Bench Locality of Uintah County, Utah. Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. U-87-AF-039i.
- 1987b Cultural Resource Evaluation of a Proposed Well Location and Access Route in the Leland Bench Locality of Uintah County, Utah. Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. U-87-AF-709i.
- 1987c Cultural Resource Evaluation of Two Seismic Line Corridors in the Leland Bench - Pariette Draw Locality of Uintah County, Utah. Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. U-87-AF-737ib.
- 1988a Cultural Resource Evaluation of Two Proposed Wells -- Ute Tribal Units No. 13-1 and 25-1 in the Leland Bench Locality of Uintah County, Utah Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. U-88-AF-272i.
- 1988b Cultural Resource Evaluation of Two Proposed Well --Ute Tribal Units No. 13-1 and 25-1 in the Leland Bench Locality of Uintah (Addendum), Utah. Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. U-88-AF-272i.
- 1988c Final Report on Cultural Resource Evaluation of Proposed Well Ute Tribal Unit No. 25-1 in the Leland Bench Locality of Uintah County, Utah. Archeological-Environmental Research Corporation, Bountiful, Utah. Report No. UT-88-AF-272i.
- Horn, J.C., A.D. Reed, and S.M. Chandler
1994 Grand Resource Area Class I Cultural Resource Inventory. Alpine Archaeological Consultants, Inc. Montrose. Bureau of Land Management, Moab, Utah.
- Metcalf, M.D.
1995 Three Snyder Flowline Routes, Ute Tribal 21-4-G, 22-4-I and 26-3-G, Uintah County, Utah. Report No. U-95-MM-0525i.

- Marwitt, J.P.
1970 Median Village and Fremont Culture Regional Variation. *University of Utah Anthropological Papers* No. 95. Salt Lake City.
- Reed, A.D.
1988 Ute Cultural Chronology. In *Archaeology of the Eastern Ute: A Symposium* edited by Paul R. Nickens, pp 79-101. Colorado Council of Professional Archaeologists Occasional Papers No. 1. Denver.
1994 The Numic Occupation of Western Colorado and Eastern Utah during the Prehistoric and Protohistoric Periods. In *Across the West: Human Population Movement and the Expansion of the Numas*, edited by D.B. Madsen and D. Rhode. University of Utah Press.
- Richens, L.D.
1995 A Cultural Resource Inventory of Snyder Oil Corporation Well Pads and Access Roads on Leland Bench Uintah County, Utah. Ms. prepared by Brigham Young University. Report No. U-95-BC-175i.
- Senulis, J.A.
1996 An Intensive Cultural Resource and Inventory of the Leland Bench 3D Seismic Project, Uintah County, Utah. Ms. prepared by Senco-Phenix. Report No. U-96-SC0454i.
1997 An Intensive Cultural Resource and Inventory of Four Well Pads and Access Roads on the Leland Bench. Ms. prepared by Senco-Phenix. Report No. U-97-SC-307ip.
1998 An Intensive Cultural Resource and Inventory of the Ute tribal #25-k Well Pad and Access Corridor, Uintah County, Utah. Ms. prepared by Senco-Phenix. Report No. U-98-SC-0021i.
- Smith, A.M.
1974 *Ethnography of the Northern Utes*. Papers in Anthropology No. 17. Museum of New Mexico Press.
- Spangler, J.D.
1995 Paradigms and Perspectives: A Class I Overview of Cultural Resources in the Uinta Basin and Tavaputs Plateau.
- Stokes, W.L.
1986 *Geology of Utah*. Utah Museum of Natural History and Utah Geological and Mineral Survey, Salt Lake City.

APPENDIX A: Site Location Data

APPENDIX B:

SITES 42Un2658, 42Un2659, 42Un2660 and 42Un2661
INTERMOUNTAIN ANTIQUITIES COMPUTER SYSTEM (IMACS) SITE FORMS

On File At:

Utah Division of State History
Salt Lake City, Utah

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 04/10/2000

API NO. ASSIGNED: 43-047-33539

WELL NAME: UTE TRIBAL 2-26
 OPERATOR: COASTAL OIL & GAS CORP (N0230)
 CONTACT: CHERYL CAMERON

PHONE NUMBER: 435-781-7023

PROPOSED LOCATION:
 N^WNE 26 040S 010E
 SURFACE: 1019 FNL 2063 FEL
 BOTTOM: 1019 FNL 2063 FEL
 UINTAH
 WINDY RIDGE EAST (753)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 2-Indian
 LEASE NUMBER: 14-20-H62-4679
 SURFACE OWNER: 2-Indian

PROPOSED FORMATION: DGCRK

RECEIVED AND/OR REVIEWED:

Plat
 Bond: Fed[] Ind[2] Sta[] Fee[]
 (No. U-605382-9)

Potash (Y/N)
 Oil Shale (Y/N) *190 - 5 (B)
 Water Permit
 (No. 43-8496)

RDCC Review (Y/N)
 (Date: _____)

Fee Surf Agreement (Y/N)

LOCATION AND SITING: **Enh. Pec. Project*

R649-2-3. Unit Leland Bench
 R649-3-2. General
 Siting: _____
 R649-3-3. Exception
 Drilling Unit
 Board Cause No: 239-1
 Eff Date: 5-12-97
 Siting: Per Unit Agreement / POD

R649-3-11. Directional Drill


COMMENTS: *Blm appr. 9-28-2000 / Unit Oper. chg. in progress per BIA. (Snyder to Coastal)

STIPULATIONS: ① FEDERAL APPROVAL



Serving the Industry, Protecting the Environment

OPERATOR: COASTAL OIL & GAS CORP (N0230)
 FIELD: WINDY RIDGE EAST (753) & UNDESIGNATED (002)
 S EC. 25 & 26, T 4 S, R 1 E,
 COUNTY: UINTAH SPACING: STATE 40 ACRES



PREPARED
 DATE: 20-APR-2000

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0136
Expires: November 30, 2000

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 14-20-H62-4679
1b. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator Coastal Oil & Gas Corporation		7. Unit or CA Agreement Name and No.
3a. Address P.O. Box 1148, Vernal, UT 84078	3b. Phone No. (include area code) (435) 781-7023	8. Lease Name and Well No. Ute Tribal #2-26
4. Location of Well (Report location clearly and in accordance with any State requirements)* At surface 1019' FNL & 2063' FEL At proposed prod. zone		9. API Well No.
14. Distance in miles and direction from nearest town or post office* 12.1 Miles Southeast of Ft. Duchesne, UT		10. Field and Pool, or Exploratory Leland Bench
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drg. unit line, if any) 1019'		11. Sec., T., R., M., or Blk. and Survey or Area NW/NE Sec. 26, T4S, R1E
16. No. of Acres in lease 280		12. County or Parish Uintah
17. Spacing Unit dedicated to this well 40		13. State UT
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Refer to Topo C		19. Proposed Depth 6700'
20. BLM/BIA Bond No. on file U-605382-9		21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5077' GR
22. Approximate date work will start* Upon Approval		23. Estimated duration To Be Determined

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) Cheryl Cameron	Date 4/4/00
-------------------	--	----------------

Title Environmental Analyst	
Approved by (Signature) 	Name (Printed/Typed) Assistant Field Manager Mineral Resources
Date 9/25/00	

NOTICE OF APPROVAL **CONDITIONS OF APPROVAL ATTACHED**

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on Reverse)

RECEIVED
APR 07 2000

DOGMA

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Coastal Oil & Gas Corporation
Well Name & Number: Ute Tribal 2-26
API Number: 43-047-33539
Lease Number: 14-20-H62-4679
Location: NWNE Sec. 26 T. 04S R. 01E
Agreement: 14-20-H62-4730

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production - within five (5) business days after new well begins, or Notice production resumes after well has been off production for more than ninety (90) days.

RECEIVED
OCT 11 2014
OIL & GAS DIVISION

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a **3M** system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the usable water zone, identified at 592 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

Ute Tribal
Surface Management Agency
2013

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

A cement bond log (CBL) will be run from the production casing shoe to the top of the cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

6. Notifications of Operations

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5(d) shall be submitted to the appropriate Field Office within 60 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (1).

RECEIVED
MMS
OIL & GAS
DIVISION

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted on initial meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal Field Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

RECEIVED
OCT 2 1993
BUREAU OF
LAND MANAGEMENT

In the event after-hours approvals are necessary, please contact one of the following individuals:

Ed Forsman (435) 789-7077
Petroleum Engineer

Jerry Kenczka (435) 781-1190
Petroleum Engineer

BLM FAX Machine (435) 781-4410

Ute Tribal
Oil & Gas
Department
1000 1st St
Cortez, CO 81301

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids.

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

11/13/10
01/14/11
1/14/11
C. J. [unclear]

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

Sixty foot wide Rights-Of-Way (ROWs) corridor shall be granted for the following:

-Access road and pipelines in corridor. Coastal will identify and provide maps of each additional pipeline upon construction. The Ute Tribe will be notified of each additional pipeline. Where no pipelines are present in the corridor the road ROW will be 30 feet wide. Where the pipelines do not follow the roads in the corridor the pipeline corridor ROW will be 30 feet wide.

Access roads which shall have constructed travel width limited to 18 feet, except as granted for sharp curves or intersections or where deep cuts are required for road construction. Culverts will be installed or extended where required and diversion ditches will be placed as needed to improve the proposed roads.

The Ute Tribal 2-26 will be monitored during construction of the wellsite and access road by a Paleontologist accompanied by a Tribal Technician.

A raptor nest which was active on March 29, 2000 at the time of the onsite was observed near the Ute Tribal well 2-26. When the nest is active drilling activities will only be allowed for the period of September to January within a half mile radius of the nest. No drilling activities between January 31 and August 31 will be allowed within one half mile of the nest if it is determined to be an active nest.

The Ute Tribe Energy and Mineral Department is to be notified 48 hours in writing in advance of any construction activity. A Tribal Technician is to routinely monitor construction. The Ute Tribal office days are Monday through Thursday. The Ute Tribe Energy and Minerals Department is to be notified in writing of any changes that are made to the original application and ROW. Approved changes will be provided in writing from the Ute Tribe.

Coastal will assure the Ute Tribe that any/all contractors and subcontractors have acquired a current 2000 Tribal Business License and have access permits prior to construction. They will have these permits in vehicles at all times.

Coastal employees and/or authorized personnel (subcontractors) in the field will have applicable APDs and/or ROW permits/authorizations on their person(s) during all phases of construction.

Coastal will implement "Safety and Emergency Plan" and Coastal will ensure its compliance.

All vehicular traffic, personnel movement, construction, and restoration activities shall be confined to the areas examined, as referenced in report, and to the existing roadways and/or evaluated access routes.

All personnel should refrain from collecting artifacts, any paleontological fossils, and from disturbing any significant cultural resources in the area.

COASTAL
L. J. COASTAL
COASTAL ENERGY SERVICES

The Ute Tribe Energy & Mineral Department shall be consulted if cultural remains (including paleontology fossils) from subsurface deposits are exposed or identified during construction or if the need arises to relocate or otherwise alter the location of the construction area. Prior to commencing constructing in the area where cultural resources are exposed the operator must obtain authorization from the BIA and Ute Tribal Department of Cultural Rights and Protection.

Upon completion of the project approved under this Application for Permit to Drill and ROW, the Ute Tribe Energy & Minerals Resources Department will be notified by Coastal Oil and Gas Company so that a Tribal Technician can verify Affidavit of Completions.

Before the site is abandoned, the company will be required to restore the well site and ROW to near their original state. The disturbed areas will be reseeded with desirable perennial vegetation.

Noxious weeds will be controlled on the well site and ROW. If noxious weeds spread from the project area onto adjoining land, the company will also be responsible for their control.

Soil erosion will be mitigated by reseeded all disturbed areas.

Reserve pits will be lined with impervious synthetic liners. Prior to backfilling the reserve pit all fluids will be pumped from the pit into trucks and hauled to approved disposal sites. When the pits are backfilled, the surplus oil and mud etc. will be buried a minimum depth of 3.0 feet below the surface of the soil.

A closed production system will be used. Production fluids will be contained in leak proof tanks. Low profile tanks may be used to minimize problems with irrigation systems. All production fluids will be disposed of at approved disposal sites. Production water, oil, and other by-products will not be applied to roads or well pads for the control of dust or weeds. The indiscriminate dumping of production fluids on roads, well sites or other areas will not be allowed on Tribal Lands.

Surface pipelines will be constructed to lay on the soil surface, and the ROW for the pipeline will not be bladed or cleared of vegetation without site specific authorization from BIA.

Where surface pipelines do not parallel roads but cross country between stations. The line shall either be welded in place at a welding station located at the wellsite or on roads near the flowline ROW and then dragged into place with a suitable piece of equipment. If the flowline doesn't follow existing and proposed new access roads, then traffic shall be restricted along pipeline ROWs so that they will not be used as an access road.

Buried flowlines shall be a minimum of three feet below the surface. After the construction of the pipeline is completed the disturbed area of the ROW shall be contoured to blend into the natural landscape, and it shall be reseeded with desirable vegetation. Between September 15 and November 1 of the year following pipeline construction of the buried line, all disturbed areas shall be reseeded with perennial vegetation according to BIA or Ute Tribe specifications.

Coastal employees, representatives, and subcontractors shall not carry firearms on their person or in their vehicles while working on the Uintah and Ouray Indian Reservation.

COASTAL OIL AND GAS
2013
11/17
COASTAL OIL AND GAS



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Kathleen Clarke
Executive Director

Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

October 2, 2000

Coastal Oil & Gas Corporation
PO Box 1148
Vernal, UT 84078

Re: Ute Tribal 2-26 Well, 1019' FNL, 2063' FEL, NW NE, Sec. 26, T. 4 South, R. 1 East,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33539.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

John R. Baza
Associate Director

er

Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Coastal Oil & Gas Corporation
Well Name & Number Ute Tribal 2-26
API Number: 43-047-33539
Lease: 14-20-H62-4679

Location: NW NE **Sec.** 26 **T.** 4 South **R.** 1 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338
- Contact Robert Krueger at (801) 538-5274.

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: COASTAL OIL & GAS CORP

Well Name: UTE TRIBAL 2-26

Api No. 43-047-33539 LEASE TYPE: INDIAN

Section 26 Township 04S Range 01E County UINTAH

Drilling Contractor BILL MARTIN JR RIG # RATHOLE

SPUDDED:

Date 11/01/2000

Time 12:30 PM

How DRY

Drilling will commence _____

Reported by LARRY

Telephone # 1-435-789-1717

Date 11/02/2000 Signed: CHD

ENTITY ACTION FORM - FORM 6

11-07-00 09:22am From-COASTAL OIL & GAS DOWNSTAIRS SECRETARY +4357894436 T-364 P.02/02 F-262

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	2900	43-047-33539	Ute Tribal 2-26	NW/NE	26	4S	1E	Uintah	11/1/00	11/1/00
WELL 1 COMMENTS: Code K: SPUD @ 12:30 PM on 11/1/00 - M.I.R.U. Bill Jr. Rathole Dr'g. 11-7-00											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.



Signature Cheryl Cameron

Sr. Regulatory Analyst 11/6/00

Title

Date

Phone No. 435 781-7023

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW/NE Sec. 26, T4S, R1E

1019' FNL & 2063' FEL

5. Lease Serial No.

14-20-H62-4679

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal #2-26

9. API Well No.

43-047-33539

10. Field and Pool, or Exploratory Area

Leland Bench

11. County or Parish, State

Uintah Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

Notice of Intent

Subsequent Report

Final Abandonment Notice

Acidize

Alter Casing

Casing Repair

Change Plans

Convert to Injection

Deepen

Fracture Treat

New Construction

Plug and Abandon

Plug Back

Production (Start/Resume)

Reclamation

Recomplete

Temporarily Abandon

Water Disposal

Water Shut-Off

Well Integrity

Other SPUD

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

M.I.R.U. Bill Jr. Rathole Drlg. SPUD @ 12:30 P.M. 11/1/00 Drill 336' of 12 1/4' Hole Run 8 Jts of 8 5/8" 24" ST&C Surface Csg Set @ 326'-Cmt W/ Halliburton 170 SX Prem. Plus W/2% CaCl2 + 1/8#/SK Poly E Flake Displace W/18 Bbl. Water, Good Returns - Circ Approx, 10 Bbl to Pit - Plug Down @ 1:20 P.M. 11/2/00, Float Held, Hole stayed full.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Cheryl Cameron

Title

Sr. Regulatory Analyst

Date 11/6/00

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW/NE Sec. 26, T4S, R1E

1019' FNL & 2063' FEL

5. Lease Serial No.

14-20-H62-4679

6. If Indian, Allottee or Tribe Name

8. Well Name and No.
Ute Tribal #2-26

9. API Well No.

43-047-33539

10. Field and Pool, or Exploratory Area
Leland Bench

11. County or Parish, State

Uintah Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Drilling</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	<u>Summary</u>
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Finished Drlg form 336' to 5,510', Ran 150 Jts of 6 1/2" 15.5#, K-55 LT&C Csg. Set at 6591'
 First Stage: Cmt Csg w/350 SX Hilift, 11.0 PPG Yeild 3.61 Cu. ft/SK 23.88 Gal/SK-Tail w/485 SX
 50/50 POZ 14.3 #/Gal Yeild 1.27 Cu.Ft/SK 5.8 Gal/SK-Displace w/158 Bbl water. Hole Stayed full.
 Bumped Plug w/1850 PSI, Packer Inflated.
 Second Stage: Pump 20 Bbl Lead 144 SX Hilift 11.1# yeilld 3.81, Tail w/47 SX 50/50 POZ 14.3#, 1.27
 Yeild-Displaced w/42 Bbl water circulated 10 Ebls water, No Cmt in returns, Cmt top @ 330'
 Nipple down, Clean Mud Pits

Released Rig @ 12:00 Noon 11/30/00

RECEIVED

DEC 18 2000

DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Cheryl Cameron

Title

Sr. Regulatory Analyst

Date 11/30/00

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: November 30, 2000

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
14-20-H62-4730

1a. Type of Well Oil Well Gas Dry Other
b. Type of Completion: New Work Over Deepen Plug Back Diff. Resvr.
Other _____

6. If Indian, Allottee or Tribe Name
UTE

7. Unit or CA Agreement Name and No.
N/A

8. Lease Name and Well No.
Ute Tribal 2-26

2. Name of Operator
Coastal Oil & Gas Corporation

3. Address **P.O. Box 1148 Vernal, UT 84078** 3a. Phone No. (include area code) **435) 781-7023**

9. API Well No.
43-047-33539

4. Location of Well (Report locations clearly and in accordance with Federal requirements)*

At surface **NW/NE 1019' FNL & 2063' FEL**

10. Field and Pool, or Exploratory
Leland Bench

At top prod. interval reported below **same**

11. Sec., T., R., M., or Block and Survey or Area **Sec. 26, T4S, R1E**

At total depth **same**

12. County or Parish **Uintah** 13. State **UT**

14. Date Spudded **11/01/00** 15. Date T.D. Reached **11/30/00** 16. Date Completed D & A Ready to Prod. **01/06/01**

17. Elevations (DF, RKB, RT, GL)*
5077' GR

18. Total Depth: MD **6610'** 19. Plug Back T.D.: MD **6545'** 20. Depth Bridge Plug Set: MD **TVD**

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
CMLD/NOA/AL - 12-02-00/AL/CA/LO/6.8" 2 1/2" 5" 1-11-01
CBL, CCL, GR - 01-11-01/ISS/COMP Gas Comp. Output - 1-11-01
1/2" 2 1/2" 4" 5" 5 1/2" 5 7/8" 1-11-01
22. Was well cored? No Yes (Submit copy)
Was DST run? No Yes (Submit copy)
Directional Survey? No Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12 1/4"	8 5/8" K-55	24#		326'		170 Prem			
7 7/8"	5 1/2" K-55	15.5#		6591'		1026 mix			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Set (MD)
2 7/8"	6138'							

25. Producing Intervals

26. Perforation Record

A)	Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
B)	Wasatch	6559'	6559'	6243', 6293', 6447', 6448', 6457', 6559'	4"	12	2SPF
C)	Green River	4822'	6457'	6294', 6296', 6298', 6305'	4"	16	4SPF
C)				5950'-5952'	4"	12	4SPF
D)				5712'-5719'	4"	32	4SPF

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and type of Material
6293'-6559'	Frac w/86,438# sand
5950'-5952'	Frac w/21,500# sand - screened off w/5BBLs of flush
5687'-5719'	Frac w/26,500# sand - screened off w/31BBLs left in flush
5390'-5406'	Frac w/31,500# sand - screened off w/18BBLs left in flush

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
01/06/01	01/08/01	24	→	63	31	24			Pumping
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. n/a	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Well Status	
n/a	n/a	n/a	→	63	31	24			Producing

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Well Status	
			→						

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)

Sold, used for fuel

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				Green River Wasatch	2092' 6550'

32. Additional remarks (include plugging procedure):


#26. 5687'-5698' 48 4" holes @ 4SPF, 5390'-5406' 68 4" holes @ 4SPF, 4822'-4836' 60 4" holes @ 4SPF

#27. 4822'-4836' Frac w/43,269# sand & flush w/114BBLs

33. Circle enclosed attachments:

- | | | | |
|--|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verificatio | 5. Core Analysis | 7. Other | |

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Cheryl Cameron Title Senior Regulatory Analyst
 Signature  Date February 23, 2001

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:
6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
7. UNIT or CA AGREEMENT NAME:
8. WELL NAME and NUMBER:
9. API NUMBER:
10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL
OIL WELL GAS WELL OTHER _____
2. NAME OF OPERATOR:
El Paso Production Oil & Gas Company
3. ADDRESS OF OPERATOR:
8 South 1200 East CITY Vernal STATE Utah ZIP 84078
PHONE NUMBER:
435-789-4433



4. LOCATION OF WELL
FOOTAGES AT SURFACE: COUNTY:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Name Change</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.
See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation
NAME (PLEASE PRINT) John T. Elzner TITLE Vice President
SIGNATURE  DATE 06-15-01
El Paso Production Oil & Gas Company
NAME (PLEASE PRINT) John T. Elzner TITLE Vice President
SIGNATURE  DATE 06-15-01

(This space for State use only)

RECEIVED
JUN 19 2001
DIVISION OF
OIL, GAS AND MINING

State of Delaware
Office of the Secretary of State

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

MAR 9 2001

DIVISION OF
OIL, GAS AND MINING



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

0610204 8100

010162788

AUTHENTICATION: 1061007

DATE: 04-03-01

CERTIFICATE OF AMENDMENT

OF

CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:

"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION

David L. Siddall

David L. Siddall
Vice President

Attest:

Margaret E. Roark

Margaret E. Roark, Assistant Secretary

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

JUL 12 2001

**DIVISION OF
OIL, GAS AND MINING**

In Reply Refer To:
3106
UTSL-065841
(UT-924)

JUL 10 2001

NOTICE

El Paso Production Oil & Gas Company : Oil and Gas
Nine Greenway Plaza :
Houston TX 77046-0095 :

Name Change Recognized


Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.



Opolonia L. Abeyta
Acting Chief, Branch of
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
~~State of Utah, DOGM~~, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

1112 copy



United States Department of the Interior
BUREAU OF INDIAN AFFAIRS

Uintah and Ouray Agency
P. O. Box 130
988 South 7500 East
Fort Duchesne, Utah 84026-0130
Phone: (435) 722-4300 Fax: (435) 722-2323

IN REPLY REFER TO:
Minerals and Mining
Phone: (435) 722-4310
Fax: (435) 722-2809

August 16, 2001

El Paso Production Company
Attn: Elizabeth R. Williams
Nine Greenway Plaza
Houston, TX 77046-0995

Dear Mrs. Williams:

We are in receipt of the corporate documentation for the name change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company.

All documents appear to be in order, and the approval is hereby authorized to change all records, including change of operator of certain oil and gas wells, Rights-of-Way, Communitization Agreements, Oil and Gas Leases, Exploration and Development Agreements, etc. from Coastal Oil & Gas Corporation to "El Paso Production Oil and Gas Company".

Approval of this name change is August 16, 2001, but effective on March 9, 2001. If you have any questions, please do not hesitate to contact this office.

Respectfully,

Acting Superintendent

RECEIVED

AUG 22 2001

DIVISION OF
OIL, GAS AND MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
14-20-H62-4905

6. If Indian, Allottee or Tribe Name
UTE

7. If Unit or CA/Agreement, Name and/or No.
14-20-H62-4730

8. Well Name and No.
UTE TRIBAL 2-26

9. API Well No.
43-047-33539

10. Field and Pool, or Exploratory
LELAND BENCH

11. County or Parish, and State
UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
EL PASO PRODUCTION
Contact: CHERYL CAMERON
E-Mail: Cheryl.Cameron@CoastalCorp.com

3a. Address
P.O. BOX 1148
VERNAL, UT 84078

3b. Phone No. (include area code)
Ph: 435.781.7023
Fx: 435.789.4436

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 26 T4S R1E Mer NWNE 1019FNL 2063FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	


13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Any produced water from the subject well will be contained in a water tank and will be hauled by truck to one of the pre-approved disposal sites: RNI, Sec.5, T9S, R22E, NBU #159, Sec.35, T9S, R21E, Ace Oilfield, Sec.2, T6S, R20E, MC&MC, Sec.12, T6S, R19E.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

14. I hereby certify that the foregoing is true and correct.
**Electronic Submission #6613 verified by the BLM Well Information System
For EL PASO PRODUCTION, sent to the Vernal**

Name (Printed/Typed) CHERYL CAMERON Title OPERATIONS

Signature  Date 08/21/2001

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING
1. DJJ
2. CDW

Change of Operator (Well Sold)

X Operator Name Change

The operator of the well(s) listed below has changed, effective:

7/1/2006

FROM: (Old Operator): N1845-El Paso Production O&G Company 1001 Louisiana Street Houston, TX 77002 Phone: 1 (713) 420-2300	TO: (New Operator): N3065-El Paso E&P Company, LP 1001 Louisiana Street Houston, TX 77002 Phone: 1 (713) 420-2131
---	--

WELL NAME	CA No.			Unit:			LELAND BENCH		
	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	
UTE TRIBAL 26-1-C	26	040S	010E	4304731738	12010	Indian	OW	P	
UTE 26-1	26	040S	010E	4304731822	12010	Indian	WI	A	
UTE 25-1	25	040S	010E	4304731848	12010	Indian	OW	P	
UTE TRIBAL 23-1	23	040S	010E	4304731935	12010	Indian	OW	S	
UTE TRIBAL 26-5-J	26	040S	010E	4304732574	12010	Indian	OW	P	
UTE TRIBAL 26-3-G	26	040S	010E	4304732667	12010	Indian	OW	S	
UTE TRIBAL 25-F	25	040S	010E	4304732809	12010	Indian	GW	P	
UTE TRIBAL 2-26	26	040S	010E	4304733539	12010	Indian	OW	P	
UTE TRIBAL 9-26	26	040S	010E	4304733543	12010	Indian	OW	P	

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 7/5/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 7/5/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/30/2006
- Is the new operator registered in the State of Utah: YES Business Number: 2114377-0181
- (R649-9-2) Waste Management Plan has been received on: requested 7/18/06
- Inspections of LA PA state/fee well sites complete on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM not yet BIA not yet
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: not yet
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 7/14/2006

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 7/19/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 7/19/2006
- Bond information entered in RBDMS on: 7/19/2006
- Fee/State wells attached to bond in RBDMS on: 7/19/2006
- Injection Projects to new operator in RBDMS on: 7/19/2006
- Receipt of Acceptance of Drilling Procedures for APD/New on: 7/5/2006

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: 103601420
- Indian well(s) covered by Bond Number: 103601473
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 400JU0708
- The **FORMER** operator has requested a release of liability from their bond on: n/a applicable wells moved

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 7/20/2006

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:
MULTIPLE LEASES

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

1. TYPE OF WELL OIL WELL GAS WELL OTHER _____

8. WELL NAME and NUMBER:
SEE ATTACHED

2. NAME OF OPERATOR:
EL PASO PRODUCTION OIL AND GAS COMPANY N1845

9. API NUMBER:

3. ADDRESS OF OPERATOR:
1339 EL SEGUNDO AVE NE ALBUQUERQUE NM 87113

PHONE NUMBER:
(505) 344-9380

10. FIELD AND POOL, OR WILDCAT:
SEE ATTACHED

4. LOCATION OF WELL
FOOTAGES AT SURFACE: SEE ATTACHED

COUNTY: UINTAH & DUCHESNE

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: <u>CHANGE OF OPERATOR</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

PLEASE BE ADVISED THAT EL PASO PRODUCTION OIL AND GAS COMPANY (CURRENT OPERATOR) HAS TRANSFERRED ITS OPERATORSHIP TO EL PASO E&P COMPANY, L.P. (NEW OPERATOR) EFFECTIVE ~~JUNE 30~~ July 1, 2006 AND THAT EL PASO E&P COMPANY, L.P. IS CONSIDERED TO BE THE NEW OPERATOR OF THE ATTACHED WELL LOCATIONS.

EL PASO E&P COMPANY, L.P. IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASED LANDS. BOND COVERAGE IS PROVIDED BY THE STATE OF UTAH STATEWIDE BLANKET BOND NO. 400JU0705, BUREAU OF LAND MANAGEMENT NATIONWIDE BOND NO. 103601420, AND BUREAU OF INDIAN AFFAIRS NATIONWIDE BOND NO. 103601473.

El Paso E & P Company, L. P. N3065
1001 Louisiana
Houston, TX 77002

William M. Griffin
William M. Griffin, Sr. Vice President

NAME (PLEASE PRINT) CHERYL CAMERON

TITLE AUTHORIZED REGULATORY AGENT

SIGNATURE *Cheryl Cameron*

DATE 6/20/2006

(This space for State use only)

APPROVED 7/19/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician (See Instructions on Reverse Side)

RECEIVED
JUL 05 2006

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

3/1/2008

FROM: (Old Operator): N3065-El Paso E&P Company, LP 1099 18th St, Suite 1900 Denver, CO 80202 Phone: 1 (303) 291-6400	TO: (New Operator): N3460-Finley Resources, Inc. 1308 Lake St, Suite 200 Fort Worth, TX 76102 Phone: 1 (817) 231-8729
--	---

CA No.		Unit:		LELAND BENCH				
WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LIST								

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on 3/10/2008
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 3/10/2008
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 4/28/2008
- Is the new operator registered in the State of Utah: yes Business Number: 6911056-0143
- If **NO**, the operator was contacted on:
- (R649-9-2)Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a
- Reports current for Production/Disposition & Sundries on: _____
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM n/a BIA not yet
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: not yet
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 3/13/2008

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 4/28/2008
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 4/28/2008
- Bond information entered in RBDMS on: n/a
- Fee/State wells attached to bond in RBDMS on: n/a
- Injection Projects to new operator in RBDMS on: _____
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: n/a
- Indian well(s) covered by Bond Number: RLB0011263
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number n/a
- The **FORMER** operator has requested a release of liability from their bond on: n/a
The Division sent response by letter on:

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

		5. LEASE DESIGNATION AND SERIAL NUMBER:
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: Various Leases
2. NAME OF OPERATOR: EL PASO E&P COMPANY, L.P. <i>N 3065</i>		9. API NUMBER: Attached (2 lists)
3. ADDRESS OF OPERATOR: 1099 18TH ST, STE 1900 DENVER CO 80202		PHONE NUMBER: (303) 291-6400
4. LOCATION OF WELL FOOTAGES AT SURFACE:		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
PLEASE BE ADVISED THAT AS A RESULT OF SALE, EL PASO E&P COMPANY, L.P. WILL BE TRANSFERING OPERATORSHIP OF THE ATTACHED REFERENCED WELLS TO FINLEY RESOURCES INC. THE EFFECTIVE DATE OF CHANGE OF OPERATORSHIP WILL BE MARCH 1, 2008.

FINLEY RESOURCES INC *N 3460*
1308 LAKE ST. STE 200
FORT WORTH, TX 76102

COMPANY BOND NUMBER: *RLB 0011263*

NAME: FINLEY RESOURCES INC. TITLE BY: BRENT D TALBOT, PRESIDENT (FINLEY)

SIGNATURE: *B D Talbot*
DATE: *2-28-2008*

NAME (PLEASE PRINT) <u>El Paso E&P Company, L.P.</u>	TITLE <u>Thomas M. Hart, Sr. Vice President</u>
SIGNATURE <i>[Signature]</i>	DATE <u>2/28/2008</u>

(This space for State use only)
APPROVED 4 128108
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
MAR 10 2008
DIV. OF OIL, GAS & MINING

El Paso to Finley Resources
Leland Bench Field (sorted by unit and API #)

well_name	sec	twp	rng	api	entity	l_type	well	stat	unit_name	qtr_qtr	l_num
UTE 26-1	26	040S	010E	4304731822	12010	Indian	WI	I	LELAND BENCH (GRRV) SENE		14-20-H62-4905
UTE TRIBAL 26-1-C	26	040S	010E	4304731738	12010	Indian	OW	P	LELAND BENCH (GRRV) NENE		14-20-H62-4905
UTE 25-1	25	040S	010E	4304731848	12010	Indian	OW	S	LELAND BENCH (GRRV) SWNW		14-20-H62-4904
UTE TRIBAL 23-1	23	040S	010E	4304731935	12010	Indian	OW	S	LELAND BENCH (GRRV) SWSE		14-20-H62-4902
UTE TRIBAL 26-5-J	26	040S	010E	4304732574	12010	Indian	OW	P	LELAND BENCH (GRRV) NWSE		14-20-H62-4905
UTE TRIBAL 26-3-G	26	040S	010E	4304732667	12010	Indian	OW	P	LELAND BENCH (GRRV) SWNE		14-20-H62-4905
UTE TRIBAL 25-F	25	040S	010E	4304732809	12010	Indian	GW	P	LELAND BENCH (GRRV) SENW		14-20-H62-4904
UTE TRIBAL 2-26	26	040S	010E	4304733539	12010	Indian	OW	S	LELAND BENCH (GRRV) NWNE		14-20-H62-4905
UTE TRIBAL 9-26	26	040S	010E	4304733543	12010	Indian	OW	P	LELAND BENCH (GRRV) NESE		14-20-H62-4905