

EOG Resources, Inc.
P.O. 1910
Vernal, UT 84078

September 18, 2003

Utah Division of Oil, Gas, & Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: APPLICATION FOR PERMIT TO DRILL
CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E
UINTAH COUNTY, UTAH
LEASE NO.: U-0284-A
FEDERAL LANDS

Enclosed please find a copy of the Application for Permit to Drill and associated attachments for the referenced well.

Please address further communication regarding this matter (including approval) to:

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Phone: (435)789-4120
Fax: (435)789-1420

Sincerely,



Ed Trotter
Agent
EOG Resources, Inc.

Attachments

RECEIVED
SEP 22 2003
DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

001

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease serial No.

U-0284-A

6. If Indian, Allottee or Tribe name

7. If Unit or CA Agreement, Name and No.

CHAPITA WELLS UNIT

8. Lease Name and Well No.

CHAPITA WELLS UNIT 841-22

9. API Well No.

43-047-35219

10. Field and pool, or Exploratory

NATURAL BUTTES

11. Sec., T., R., M., or BLK. And survey of area

SEC. 22, T9S, R22E, S.L.B.&M.

1a. TYPE OF WORK DRILL REENTER

b. TYPE OF WELL Oil Well Gas Well Other Single Zone Multiple Zone

2. Name of Operator

EOG RESOURCES, INC.

3a. Address

P.O. BOX 1910, VERNAL, UT 84078

3b. Telephone Number: (435)789-4120

4. Location of Well (Report location clearly and in accordance with any State requirements. *)
At surface

1898' FSL & 2365' FWL 4430889Y NE/SW 40.01942
634303X -109.42625

At proposed prod. Zone

14. Distance in miles and direction from nearest town or post office*

17.65 MILES SOUTHEAST OF OURAY, UTAH

12. County or parish

UINTAH

13. State

UTAH

15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. Unit line, if any)

1898'

16. No. of acres in lease

1240

17. Spacing Unit dedicated to this well

18. Distance from proposed location* to nearest well, drilling, completed, or applied for, on this lease, ft.

See Map C

19. Proposed depth

10,325'

20. BLM/BIA Bond No. on file

#NM 2308

21. Elevations (show whether DF, KDB, RT, GL, etc.)

4945.4 FEET GRADED GROUND

22. Approx. date work will start*

UPON APPROVAL

23. Estimated duration

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan
- A Surface Use Plan (if the location is on National Forest System lands, the SUPO shall be filed with the appropriate Forest Service Office.
- Bond to cover the operations unless covered by an existing bond on file (see item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the Authorized officer.

25. Signature

Name (Printed/ Typed)

Ed Trotter

Date

September 18, 2003

Title

Agent

Approved by (Signature)

Name (Printed/ Typed)

BRADLEY G. HILL
ENVIRONMENTAL SCIENTIST III

Date

09-29-03 SEP 22 2003

DIV. OF OIL, GAS & MINING

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.


Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

Federal Approval of this Action is Necessary

RECEIVED

T9S, R22E, S.L.B.&M.



LEGEND:

- = 90° SYMBOL
- = PROPOSED WELL HEAD.
- = SECTION CORNERS LOCATED.

(NAD 27)

LATITUDE = $40^{\circ}01'10.03''$ (40.019453)
 LONGITUDE = $109^{\circ}25'35.01''$ (109.426392)

EOG RESOURCES, INC.


Well location, CWU #841-22, located as shown in the NE 1/4 SW 1/4 of Section 22, T9S, R22E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 20EAM LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert H. Cox
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 05-29-03	DATE DRAWN: 06-11-03
PARTY S.H. D.B. D.COX	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE EOG RESOURCES, INC.	

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River	1,611'
Wasatch	4,685'
Island	7,235'
KMV Price River	7,392'
KMV Price River Middle	8,112'
KMV Price River Lower	8,910'
Bit Trip Segoe	9,255'
Segoe	9,315'
KMV Castlegate	9,515'
KMV Castlegate SS	9,735'
Bit Trip Black Hawk Shale	9,750'
KMV Black Hawk	9,936'

EST. TD: 10,325

Anticipated BHP 4500 PSI

- 3. PRESSURE CONTROL EQUIPMENT:** Intermediate Hole - 3000 PSIG
Production Hole - 5000 PSIG
BOP Schematic Diagrams attached.

4. CASING PROGRAM:

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>RATING FACTOR</u>		
							<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
12 1/4"	0' - 250' +/- KB	250' +/-	9 5/8"	36.0 #	J-55	STC	2020 PSI	3520 PSI	394,000#
8 3/4"	250' - 2700' +/-KB	2700 +/-	7"	23.0 #	J-55	STC	3270 PSI	4360 PSI	313,000#
6 1/4"	2700' - TD +/-KB	10,325' +/-	4 1/2"	11.6 #	N-80	LTC	6350 PSI	7780 PSI	223,000#

All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0-250' Below GL):

Guide Shoe
Insert Baffle
Wooden wiper plug
Centralizers: 1 - 5-10' above shoe, every collar for next 3 joints (4 total).

Intermediate Hole Procedure (250'-2700'):

Float Shoe (PDC drillable)
Float Collar (PDC drillable)
Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

Float Equipment- Production Hole Procedure (2700'-TD):

FS, 1 joint of casing, FC, and balance of casing to surface. Run 11.6#, N-80 burst rating or equivalent marker collars or short casing joints at $\pm 7,392'$ (Top of Price River) and $\pm 4,200'$ (400' above the Wasatch) (alter depth if needed to avoid placing across any potentially-productive intervals). Centralize 5' above shoe on joint #1, top of joint #2, then every 2nd joint to 400' above Island top (50 total). Thread lock FS, top and bottom of FC, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (0-250' below GL):

Air – Air Water Mist

Intermediate Hole Procedure (250-2700'):

Spud – 5000': Circulate fresh water through reserve pit and add Crystal Drill. Sweep with Barazan D and Barolift.

5000' - 9000': Close in pits and add 6 ppb DAP. Add Crystal Drill to keep water clear. Add NaCl water for weight. Sweep with Barazan D and Barolift

9000' – TD: Close in pits and add 6 ppb DAP. Add Crystal Drill to keep water clear. Add barite for weight. Add sea mud for viscosity as needed. Sweep with Barazan D and Barolift

Production Hole Procedure (2700'-TD):

Spud – 5000': Circulate fresh water through reserve pit and add Crystal Drill. Sweep with Barazan D and Barolift.

5000' - 9000': Close in pits and add 6 ppb DAP. Add Crystal Drill to keep water clear. Add NaCl water for weight. Sweep with Barazan D and Barolift

9000' – TD: Close in pits and add 6 ppb DAP. Add Crystal Drill to keep water clear. Add barite for weight. Add sea mud for viscosity as needed. Sweep with Barazan D and Barolift

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

7. VARIANCE REQUESTS:

- A. EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line (Where possible, a straight run blooie line will be used).
- B. EOG Resources, Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).
- C. EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be 75' in length.

8. EVALUATION PROGRAM:

Logs: RST (Reservoir Saturation Tool) Cased logs TD to Surface

9. CEMENT PROGRAM:

Surface Hole Procedure (0-250' Below GL)

Lead: 200 sx. (100% excess volume) Class 'G' cement with 2% S001 (CaCl₂) & 0.25 pps D29 (cellophane flakes), mixed at 15.8 ppg, 1.18 cu. ft./sk., 5.22 gps water.

Top Out: Top out with Class 'G' cement with 2% S1 (CaCl₂) in mix water, 15.8 ppg, 1.15 cu. ft./sk., 4.95 gps via 1" tubing set at 25' if needed.

Intermediate Hole Procedure (250'-2700')

Lead: 150 sks. (50% excess volume) Class 'G' lead cement with 5% D44 (Salt), 12% D20 (Bentonite), 1% D79% (Extender), 0.25% D112 (Fluid Loss Additive), 0.2% D46 (Anti-Foamer) & 0.25 pps D29 (Cellophane flakes) mixed at 11.0 ppg, 3.91 cu.ft./sk., 24.54 gps water.

Tail: 120 sks. (50% excess volume) 59:50 Poz Class "G" cement with 10% D44 (BWOW), 2% D20 mixed at 14.1 ppg, 1.35 cu.ft./sk., 6.24 gps water.

Production Hole Procedure (2700' to TD)

Lead: 120 sks: 35:65 Poz: Class "G" w/ 4% D20 (Bentonite), + 2% D174 + 0.75% D112 + 0.2% D46 + 0.15% D13 + 0.25 pps D29, mixed at 13.0 ppg, 1.74 cu.ft./sk., 9.05 gps water.

Tail: 200 sks: 50:50 Poz: Class "G" w/ 2% D20 (Bentonite), + 0.1% D46 + 0.075% D800 + 0.2% D167 + 0.2% D65 + 35% D66, mixed at 14.1 ppg, 1.71 cu.ft./sk., 7.73 gps water.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

INTERMEDIATE HOLE (250-2700')

Potential Problems: Lost circulation below 1600' and minor amounts of gas may be present.

PRODUCTION HOLE (2700'-TD)

Potential Problems: Sloughing shales and key seat development are possible in the Wasatch Formation. CO₂ contamination in the mud is possible in the Price River (Mesa Verde).

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

3000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
CASING FLANGE IS 11" 3000 PSIG RATED.
BOPE 11" 3000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 3000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 3000 psig BOPE specifications.




5000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 5000 PSIG RATED.
CASING FLANGE IS 11" 5000 PSIG RATED.
BOPE 11" 5000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 5000 psig.
3. Annular preventor will be tested to 50% of working pressure, 2500 psig.
4. Casing will be tested to 0.22 psi/ft. or 2500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 5000 psig BOPE specifications.



**CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL**

Company/Operator: EOG Resources, Inc.
Well Name & Number: Chapita Wells Unit 841-22
Lease Number: U-0284-A
Location: 1898' FSL & 2365' FWL, NE/SW, Sec. 22,
T9S, R22E, S.L.B.&M., Uintah County, Utah
Surface Ownership: Federal

NOTIFICATION REQUIREMENTS

Location Construction - forty-eight (48) hours prior to construction of location and access roads.

Location Completion - prior to moving on the drilling rig.

Spud Notice: - at least twenty-four (24) hours prior to spudding the well.

Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.

BOP and related Equipment Tests - twenty-four (24) hours prior to running casing and tests.

First Production Notice - within five (5) business days after new Well begins or production resumes after Well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

THIRTEEN POINT SURFACE USE PROGRAM

1. EXISTING ROADS

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 17.65 miles southeast of Ouray, Utah - See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. PLANNED ACCESS ROAD

- A. An existing access road will be utilized to service this well. See attached TOPO Map "B".
- B. The access road has a 30 foot ROW w/ 18 foot running surface.
- C. Maximum grade on access road will be 8%.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.

New or reconstructed roads will be centerlined - flagged at time of location staking.

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, drainage, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot Right-of-Way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

3. **LOCATION OF EXISTING WELLS WITHIN A ONE MILE RADIUS OF PROPOSED WELL LOCATION**

- A. Abandoned wells – 7*
- B. Producing wells - 51*
- C. Shut in wells – 1*

(*See attached TOPO map “C” for location)

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

A. **ON WELL PAD**

- 1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, 300 Bbl vertical or 200 Bbl low profile, condensate tank, and attaching piping.
- 2. Gas gathering lines - A 3” gathering line will be buried from dehy to the edge of the location.

B. **OFF WELL PAD**

- 1. Proposed location of attendant off pad flowlines shall be flagged prior to archaeological clearance.
- 2. Protective measures and devices for livestock and wildlife will be taken and/or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery.

The production facilities will be placed on the Southwest side of the location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Carlsbad Canyon.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

5. **LOCATION & TYPE OF WATER SUPPLY**

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/or Target Trucking Inc.'s water source in the SW/SW, Sec. 35, T9S, R22E, Uintah County, Utah (State Water Right #49-1501). Produced water from the Chapita Wells and Stagecoach Units will also be used.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. **SOURCE OF CONSTRUCTION MATERIAL**

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of the location.
- B. All construction material will come from Federal Land.
- C. No mineral materials will be required.

7. **METHODS OF HANDLING WASTE DISPOSAL**

A. **METHODS AND LOCATION**

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
- 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following three locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
- 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.

- B. Water from drilling fluids and recovered during testing operations will be

disposed of by either evaporating in the reserve pit or be removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

On BLM administered land:

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with a plastic liner. A felt liner will also be installed if rock is encountered during pit construction.

8. ANCILLARY FACILITIES

A. No airstrips or camps are planned for this well.

9. WELLSITE LAYOUT

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.
- D. The approved seed mixture for this location is:
 - Gardner Salt Bush – 4 pounds per acre
 - Shad Scale – 3 pounds per acre
 - Hi-Crest Crested Wheat Grass – 2 pounds per acre

The reserve pit will be located on the West side of the location. The flare pit will be located downwind of the prevailing wind direction on the West side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled pit topsoil will be stored separate from the location topsoil North of Corner #5. The stockpiled location topsoil will be stored from West of Corner #6 to the access road. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture for this location and then walked down with a cat.

Access to the well pad will be from the Northeast.

X A diversion ditch shall be constructed on the Southeast side of the location, below the cut slope (from Corners #2 to #8), draining to the Northeast.

X Corners #2, #6, & #8 will be rounded off to minimize excavation.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently mounted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RESTORATION OF SURFACE

A. PRODUCING LOCATION

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

B. DRY HOLE/ABANDONED LOCATION

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP

Access road: Federal

Location: Federal

12. OTHER INFORMATION

A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the AO. Within five working days the AO will inform the operator as to:

-whether the materials appear eligible for the National Register of Historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used.

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

B. As operator, EOG Resources, Inc. will control noxious weeds

along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

Additional Surface Stipulations

X When the location is constructed, the existing Pond (located .75 miles North of the location next to the access road) will be cleaned out.

LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION

PERMITTING AGENT

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Telephone: (435)789-4120
Fax: (435)789-1420

DRILLING OPERATIONS

Donald Presenkowski
EOG Resources, Inc.
P.O. Box 250
Big Piney, WY 83113
Telephone: (307)276-4865

All lease or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approval plan of operations, and any applicable Notice to Lessees. EOG Resources, Inc. is fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

A copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions that presently exist; that the statements made in the Plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this Plan and the terms and conditions under which it is approved.

Please be advised that EOG Resources, Inc. is considered to be the operator of the **Chapita Wells Unit 841-22 Well, located in the NE/SW Section 22, T9S, R22E, Uintah County, Utah; Lease #U-0284-A;** and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is provided under Bond #NM 2308.

9-18-2003
Date


Agent

EOG RESOURCES, INC.
CWU #841-22
SECTION 22, T9S, R22E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.8 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 48.65 MILES.

EOG RESOURCES, INC.

CWU #841-22

LOCATED IN UTAH COUNTY, UTAH
SECTION 22, T9S, R22E, S.1.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHEASTERLY



PHOTO: VIEW OF EXISTING ACCESS

CAMERA ANGLE: NORTHEASTERLY



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS	05	30	03	PHOTO
TAKEN BY: S.H.	MONTH	DAY	YEAR	
DRAWN BY: P.M.	REVISED: 00-00-00			


EOG RESOURCES, INC.

LOCATION LAYOUT FOR

CWU #841-22

SECTION 22, T9S, R22E, S.L.B.&M.


1898' FSL 2365' FWL



SCALE: 1" = 50'
DATE: 06-11-03
Drawn By: D COX

NOTE:
Flare Pit is to be located a min. of 100' from the Well Head.

Approx. Toe of Fill Slope



Elev. Ungraded Ground at Location Stake = 4945.4'
Elev. Graded Ground at Location Stake = 4945.4'


EOG RESOURCES, INC.

TYPICAL CROSS SECTIONS FOR

CWU #841-22





SECTION 22, T9S, R22E, S.L.B.&M.

1898' FSL 2365' FWL



DATE: 06-11-03

Drawn By: D.COX



APPROXIMATE YARDAGES

(6") Topsoil Stripping = 1,140 Cu. Yds.
(For New Construction Only)

Remaining Location = 16,920 Cu. Yds.


TOTAL CUT = 18,060 CU.YDS.

FILL = 920 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION = 17,090 Cu. Yds.

Topsoil & Pit Backfill (1/2 Pit Vol.) = 2,800 Cu. Yds.

EXCESS UNBALANCE (After Rehabilitation) = 14,290 Cu. Yds.



LEGEND:

⊙ PROPOSED LOCATION



EOG RESOURCES, INC.

CWU #841-22
 SECTION 22, T9S, R22E, S.L.B.&M.
 1898' FSL 2365' FWL




Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
 MAP

05	30	03
MONTH	DAY	YEAR



SCALE: 1:100,000 DRAWN BY: P.M. REVISED: 00-00-00



**PROPOSED LOCATION:
CWU #841-23**

LEGEND:

— EXISTING ROAD



EOG RESOURCES, INC.

CWU #841-22
SECTION 22, T9S, R22E, S.L.B.&M.
1898' FSL 2365' FBL




Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC 05 30 03
MAP MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 00-00-00





PROPOSED LOCATION:
CWU #841-23

LEGEND:

- ◊ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ◊ WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

EOG RESOURCES, INC.

CWU #841-22
 SECTION 22, T9S, R22E, S.L.B.&M.
 1898' FSL 2365' FBL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC			05	30	03	C TOPO
MAP			MONTH	DAY	YEAR	
SCALE: 1" = 2000'		DRAWN BY: P.M.		REVISED: 00-00-00		

**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

004

APD RECEIVED: 09/22/2003

API NO. ASSIGNED: 43-047-35219

WELL NAME: CWU 841-22
 OPERATOR: EOG RESOURCES INC (N9550)
 CONTACT: ED TROTTER

PHONE NUMBER: 435-789-4120

PROPOSED LOCATION:

NESW 22 090S 220E
 SURFACE: 1898 FSL 2365 FWL
 BOTTOM: 1898 FSL 2365 FWL
 UINTAH
 NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal
 LEASE NUMBER: U-0284-A
 SURFACE OWNER: 1 - Federal
 PROPOSED FORMATION: BLKHK

LATITUDE: 40.01942
 LONGITUDE: 109.42625

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. NM 2308)
- Potash (Y/N)
- Oil Shale 190-5 (BP or 190-3 or 190-13)
- Water Permit
(No. 49-1501)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)


LOCATION AND SITING:

- ___ R649-2-3.
- Unit CHAPITA WELLS
- ___ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- ___ R649-3-3. Exception
- Drilling Unit
Board Cause No: 179-8
Eff Date: 8-10-99
Siting: Suspends General Siting
- ___ R649-3-11. Directional Drill

COMMENTS:

STIPULATIONS:

1- Federal Approval
2- OIL SHALE



OPERATOR: EOG RESOURCES INC (N9550)

SEC. 22 T.9S, R.22E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

CAUSE: 179-8 / 8-10-1999

Wells


- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED



Utah Oil Gas and Mining



PREPARED BY: DIANA MASON
DATE: 24-SEPTEMBER-2003

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

September 26, 2003

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2003 Plan of Development Chapita Wells Unit,
Uintah County, Utah.

Pursuant to email between Diana Mason, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2003 within the Chapita Wells Unit, Uintah County, Utah.

Api Number	Well	Location
(Proposed PZ Mesaverde)		
43-047-35214	CWU 869-30 Sec 30 T09S R23E 0714 FNL 0559 FWL	
43-047-35221	CWU 863-32 Sec 32 T09S R23E 1064 FSL 1879 FEL	
43-047-35222	CWU 861-32 Sec 32 T09S R23E 1974 FNL 1649 FEL	
43-047-35223	CWU 865-33 Sec 33 T09S R23E 0565 FNL 1908 FWL	
43-047-35224	CWU 866-33 Sec 33 T09S R23E 2062 FNL 2142 FEL	
43-047-35225	CWU 868-33 Sec 33 T09S R23E 0838 FSL 1976 FEL	
43-047-35226	CWU 864-33 Sec 33 T09S R23E 1850 FNL 0751 FWL	
43-047-35227	CWU 856-34 Sec 34 T09S R23E 0481 FSL 0846 FWL	
43-047-35220	CWU 838-23 Sec 23 T09S R22E 1569 FNL 2378 FEL	
43-047-35215	CWU 844-15 Sec 15 T09S R22E 0535 FSL 0779 FWL	
43-047-35218	CWU 846-9 Sec 9 T09S R22E 1535 FNL 0703 FWL	
43-047-35219	CWU 841-22 Sec 22 T09S R22E 1898 FSL 2365 FWL	

Please be advised that these wells are currently outside of the existing Mesaverde Participating Areas within the Chapita Wells Unit.

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Chapita Wells Unit
Division of Oil Gas and Mining
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:9-26-3



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
(801) 538-5340 telephone
(801) 359-3940 fax
(801) 538-7223 TTY
www.nr.utah.gov

Michael O. Leavitt
Governor
Robert L. Morgan
Executive Director
Lowell P. Braxton
Division Director

September 29, 2003

EOG Resources, Inc.
P O Box 1910
Vernal, UT 84078

Re: Chapita Wells Unit 841-22 Well, 1898' FSL, 2365' FWL, NE SW, Sec. 22, T. 9 South,
R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-35219.

Sincerely,

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: EOG Resources, Inc.
Well Name & Number Chapita Wells Unit 841-22
API Number: 43-047-35219
Lease: U-0284-A

Location: NE SW **Sec.** 22 **T.** 9 South **R.** 22 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

5. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

006

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

5. LEASE DESIGNATION AND SERIAL NUMBER:
U-0284-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
CHAPITA WELLS UNIT

8. WELL NAME and NUMBER:
CHAPITA WELLS UNIT 841-22

9. API NUMBER:
4304734219

10. FIELD AND POOL, OR WLD CAT:
NATURAL BUTTES

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL GAS WELL OTHER _____

2. NAME OF OPERATOR:
EOG RESOURCES, INC.

3. ADDRESS OF OPERATOR: P.O. BOX 1910 CITY VERNAL STATE UT ZIP 84078 PHONE NUMBER: (435) 789-4120

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 1898' FSL, 2365' FWL COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESW 22 9S 22E S STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
The attached revised drilling program reflects changes to the casing, float, cement, and mud programs.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) Ed Trotter TITLE Agent
SIGNATURE *Ed Trotter* DATE 11/20/2003

(This space for State use only)

RECEIVED
NOV 21 2003

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River	1,611'
Wasatch	4,685'
Island	7,235'
KMV Price River	7,392'
KMV Price River Middle	8,112'
KMV Price River Lower	8,910'
Bit Trip Segoe	9,255'
Segoe	9,315'
KMV Castlegate	9,515'
KMV Castlegate SS	9,735'
Bit Trip Black Hawk Shale	9,750'
KMV Black Hawk	9,936'

EST. TD: 10,325

Anticipated BHP 4500 PSI

- 3. PRESSURE CONTROL EQUIPMENT:** Intermediate Hole - 3000 PSIG
Production Hole – 5000 PSIG
BOP Schematic Diagrams attached.

4. CASING PROGRAM:

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>RATING FACTOR</u>		
							<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
17 1/2"	0' - 250'+/- KB	250' +/-	13 3/8"	48.0 #	H-40	STC	770 PSI	1730 PSI	322,000#
12 1/4"	250' - 2700'+/-KB	2700+/-	9 5/8"	36.0 #	J-55	STC	2020 PSI	3520 PSI	394,000#
7 7/8"	2700' – TD +/-KB	10,325' +/-	4 1/2"	11.6 #	N-80	LTC	6350 PSI	7780 PSI	223,000#

The 12 1/4" Intermediate hole will be drilled to a total depth of 200' below the base of the Green River lost circulation zone and 9 5/8" casing will be set to that depth. Actual setting depth of the 9 5/8" casing may be less than 2700' in this well.

All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0-250' Below GL):

Guide Shoe

Insert Baffle

Wooden wiper plug

Centralizers: 1 – 5-10' above shoe, every collar for next 3 joints (4 total).

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

Float Equipment (Continued):

Intermediate Hole Procedure (250'-2700'):

Guide Shoe

Insert Float Collar (PDC drillable)

Cents.: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Float Equipment- Production Hole Procedure (2700'-TD):

FS, 1 joint of casing, FC, and balance of casing to surface. Run 11.6#, N-80 burst rating or equivalent marker collars or short casing joints at ± 7,392' (Top of Price River) and ± 4,200' (400' above the Wasatch) (alter depth if needed to avoid placing across any potentially- productive intervals). Centralize 5' above shoe on joint #1, top of joint #2, then every 2nd joint to 400' above Island top (50 total). Thread lock FS, top and bottom of FC, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (0-250' below GL):

Air – Air Water Mist

Intermediate Hole Procedure (250-2700'):

Water (circulate through reserve pit) with Gel/LCM sweeps.

Production Hole Procedure (2700'-TD):

2700' - 4500' Water (circulate through reserve pit) with Gel/LCM sweeps.

4500' - 6900' Close in mud system. "Mud up" with **6.0 ppb** Diammonium Phosphate (DAP). Drill with DAP water, POLYPLUS for viscosity and hole cleaning, adding KLA-GARD B for supplemental inhibition. Also sweep hole periodically w/ Durogel / LCM sweeps to clean the hole and seal loss zones. Add additional LCM as hole dictates. Mud weight and vis as needed, water loss – no control.

6900' - TD Discontinue KLA-GARD B. Utilize POLYPAC-R for fluid loss control. Maintain **5.5 ppb** DAP. **Do not mix caustic or lime.** Maintain 7.5-8.5 pH. Weight up system and add vis as hole conditions require. Run LCM sweep periodically to seal off loss zones or more often as hole dictates. Water loss: 20 cc's maximum. Expect increasing gas shows requiring heavier mud weights from top of Island onward. Treat CO₂ contamination with DESCO CF and OSIL (Oxygen scavenger) if mud properties dictate.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

7. VARIANCE REQUESTS:

- A. EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line (Where possible, a straight run blooie line will be used).
- B. EOG Resources, Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).
- C. EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be 75' in length.

8. EVALUATION PROGRAM:

Logs: RST (Reservoir Saturation Tool) Cased logs TD to Surface

9. CEMENT PROGRAM:

Surface Hole Procedure (0-250' Below GL)

Lead: 300 sks (100% excess volume) Class 'G' cement with 2% S1 (CaCl₂) & 0.25 pps D29 (cellophane flakes), mixed at 15.8 ppg, 1.16 ft³/sk., 4.95 gps water.

Top Out: Top out with Class 'G' cement with 2% S1 (CaCl₂) in mix water, 15.8 ppg, 1.16 ft³/sk., 4.95 gps via 1" tubing set at 25' if needed.

Intermediate Hole Procedure (250'-2700')

Lead: 85 sks: (50% excess volume) Class 'G' lead cement (coverage from 1700-1000') with 5% D44 (Salt), 12% D20 (Bentonite), 1% D79% (Extender), 0.25% D112 (Fluid Loss Additive), 0.2% D46 (Anti-Foamer) & 0.25 pps D29 (Cellophane flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 290 sks: (50% excess volume) Class 'G' cement (coverage from 2700-1700') with 10% D53 (Gypsum), 2% S1 (CaCl₂) & 0.25 pps D29 (Cellophane flakes) mixed at 14.2 ppg, 1.61 ft³/sk., 7.9 gps water.

Production Hole Procedure (2700' to TD)

Lead: 110 sks 35:65 Poz G w/ 4% D20 (Bentonite), 2% D174 (Extender), 0.2% D65 (Dispersant), 0.2% D46 (Antifoam), 0.75% D112 (Fluid Loss Additive), 0.15% D13 (Retarder), 0.25 pps D29 (cello flakes), mixed at 13.0 ppg, 1.73 cu. ft./sk., 9.06 gps water

Tail: 190 sks: 50:50 Poz G w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.15% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 cu. ft./sk., 5.9 gps water.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 841-22
NE/SW, SEC. 22, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

INTERMEDIATE HOLE (250-2700')

Potential Problems: Lost circulation below 1800' and minor amounts of gas may be present.

PRODUCTION HOLE (2700'-TD)

Potential Problems: Sloughing shales and key seat development are possible in the Wasatch Formation. CO₂ contamination in the mud is possible in the Price River (Mesa Verde).

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

3000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
 CASING FLANGE IS 11" 3000 PSIG RATED.
 BOPE 11" 3000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 3000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 3000 psig BOPE specifications.




5000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 5000 PSIG RATED.
 CASING FLANGE IS 11" 5000 PSIG RATED.
 BOPE 11" 5000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 5000 psig.
3. Annular preventor will be tested to 50% of working pressure, 2500 psig.
4. Casing will be tested to 0.22 psi/ft. or 2500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 5000 psig BOPE specifications.



**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

007

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. TYPE OF WORK <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease serial No. U-0284-A
b. TYPE OF WELL <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe name CHAPITA WELLS UNIT
2. Name of Operator EOG RESOURCES, INC.		7. If Unit or CA Agreement, Name and No. CHAPITA WELLS UNIT
3a. Address P.O. BOX 1910, VERNAL, UT 84078		8. Lease Name and Well No. CHAPITA WELLS UNIT 841-22
3b. Telephone Number: (435)789-4120		9. API Well No. 43-047-35219
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 1898' FSL & 2365' FWL NE/SW At proposed prod. Zone		10. Field and pool, or Exploratory NATURAL BUTTES
14. Distance in miles and direction from nearest town or post office* 17.65 MILES SOUTHEAST OF OURAY, UTAH		11. Sec., T., R., M., or BLK. And survey of area SEC. 22, T9S, R22E, S.L.B.&M.
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. Unit line, if any) 1898'		12. County or parish UINTAH
16. No. of acres in lease 1240		13. State UTAH
18. Distance from proposed location* to nearest well, drilling, completed, or applied for, on this lease, ft. See Map C		17. Spacing Unit dedicated to this well
21. Elevations (show whether DF, KDB, RT, GL, etc.) 4945.4 FEET GRADED GROUND		20. BLM/BIA Bond No. on file #NM 2308
22. Approx. date work will start* UPON APPROVAL		23. Estimated duration RECEIVED NOV 24 2003

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form: DIV. OF OIL, GAS & MINING

- | | |
|--|---|
| <ol style="list-style-type: none"> 1. Well plat certified by a registered surveyor. 2. A Drilling Plan 3. A Surface Use Plan (if the location is on National Forest System lands, the SUPO shall be filed with the appropriate Forest Service Office. | <ol style="list-style-type: none"> 4. Bond to cover the operations unless covered by an existing bond on file (see item 20 above). 5. Operator certification. 6. Such other site specific information and/or plans as may be required by the Authorized officer. |
|--|---|

25. Signature	Name (Printed/ Typed) Ed Trotter	Date September 18, 2003
Title Agent		

Approved by (Signature)	Name (Printed/ Typed) EDWIN I FORSMAN	Date 11/18/03
Title Assistant Field Manager Mineral Resources		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

NOTICE OF APPROVAL

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

CONDITIONS OF APPROVAL ATTACHED

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: EOG Resources, Inc.

Well Name & Number: CWU 841-22

Lease Number: U-0284A

API Number: 43-047-35219

Location: NESW Sec. 22 T.9S R. 22E

Agreement: Chapita Wells Unit

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to John Mayers of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 5M system (production hole) and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint. Surface casing setting depths are based on ground level elevations only.

The top of the Wasatch formation has been identified at $\pm 4840'$, the proposed casing/cementing program will not be adequate to protect this resource. As a minimum requirement, the cement behind the production casing must extend to the top of the Wasatch formation.

All casing strings below the conductor shall be pressure tested to 0.22 psi/ft of casing string length or 1500 psi, whichever is greater but not to exceed 70% of the minimum internal yield.

If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

A cement bond log (CBL) will be run from the production casing shoe to top of the cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

Please submit to this office, in LAS format, an electronic copy of all logs run on this well. This submission will replace the requirement for submittal of paper logs to the BLM.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Written notification of such must be submitted to this office not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5(d) shall be submitted to the appropriate Field Office within 60 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (1).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergencies, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries and tested for meter accuracy at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162. "Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874
Petroleum Engineer

Kirk Fleetwood (435) 828-7875
Petroleum Engineer

BLM FAX Machine (435) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: EOG RESOURCES INCWell Name: CWU 841-22Api No: 43-047-35219 Lease Type: FEDERALSection 22 Township 09S Range 22E County UINTAHDrilling Contractor BILL JR'S RIG # AIR**SPUDDED:**Date 02/25/04Time 6:00 PMHow ROTARY**Drilling will commence:** _____Reported by ED TROTTERTelephone # 1-435-789-4120Date 02/26/2004 Signed CHD

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

OPERATOR: EOG Resources, Inc.
ADDRESS: P.O. BOX 250
BIG PINEY, WYOMING 83113

OPERATOR ACCT. NO. 9550
FAX: EARLENE RUSSELL
(801) 359-3940

ENTITY ACTION FORM - FORM 6

T-699 P.01/01 F-459

307276938

From-EOG - BIG PINEY, WY.

Mar-01-04 11:21am

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	LOCATION				COUNTY	SPUD DATE	EFFECTIVE DATE	
					QQ	SEC.	TP	RG				
A	99999	13650	43-047-35219	CHAPITA WELLS UNIT 841-22	NESW	22	9S	22E	UINTAH	2/25/2004	3/3/04	K
<i>BLK HK</i>												
A	99999	14066	43-047-35017	CHAPITA WELLS UNIT 828-15	SWNE	15	9S	22E	UINTAH	2/26/2004	3/3/04	K
<i>BLKHK - NOT unit qtr/qtr</i> CONFIDENTIAL												

ACTIONS CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

Signature _____
Sr. Regulatory Assistant 3/1/2004
Title _____

Phone No. (307) 276-4833

RECEIVED
MAR 01 2004
DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

011

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No. U-0284-A
6. If Indian, Allottee or Tribe Name
7. If Unit or CA/Agreement, Name and/or No. CHAPITA WELLS
8. Well Name and No. CHAPITA WELLS UNIT 841-22
9. API Well No. 43-047-35219
10. Field and Pool, or Exploratory NATURAL BUTTES
11. County or Parish, and State UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
EOG RESOURCES, INC
Contact: ALFREDA SCHULZ
E-Mail: affreda_schulz@eogresources.com

3a. Address
P. O. BOX 250
BIG PINEY, WY 83113

3b. Phone No. (include area code)
Ph: 307.276.4833

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 22 T9S R22E NESW 1898FSL 2365FWL
40.01945 N Lat, 109.42639 W Lon

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc requests authorization for disposal of produced water from the referenced well to any of the following locations.

1. Natural Buttes Unit 21-20B SWD.
2. Ace Disposal.
3. EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
4. RN Industries.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

14. I hereby certify that the foregoing is true and correct.
**Electronic Submission #28381 verified by the BLM Well Information System
For EOG RESOURCES, INC, sent to the Vernal**

Name (Printed/Typed) ALFREDA SCHULZ	Title AUTHORIZED REPRESENTATIVE
Signature (Electronic Submission)	Date 03/01/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____	Title _____	Date _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

RECEIVED

MAR 03 2004

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		7. If Unit or CA/Agreement, Name and/or No. CHAPITA WELLS	
2. Name of Operator EOG RESOURCES, INC		8. Well Name and No. CHAPITA WELLS UNIT 841-22	
3a. Address P. O. BOX 250 BIG PINEY, WY 83113		9. API Well No. 43-047-35219	
3b. Phone No. (include area code) Ph: 307.276.4833		10. Field and Pool, or Exploratory NATURAL BUTTES	
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 22 T9S R22E NESW 1898FSL 2365FWL 40.01945 N Lat, 109.42639 W Lon		11. County or Parish, and State UINTAH COUNTY, UT	

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Well Spud
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc spud a 17 1/2" surface hole at the referenced location 2/25/04 at 6:00 p.m. The contractor was Bill Jr's Air Rig. Ed Trotter, representative for EOG, notified Ed Forsman of the Vernal BLM office and Carol Daniels of the Utah Division of Oil, Gas & Mining of the spud 2/25/04.

14. I hereby certify that the foregoing is true and correct. Electronic Submission #28380 verified by the BLM Well Information System For EOG RESOURCES, INC, sent to the Vernal	
Name (Printed/Typed) ALFREDA SCHULZ	Title SR. REGULATORY ASSISTANT
Signature (Electronic Submission)	Date 03/01/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____	Title _____	Date _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

MAR 03 2004

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: November 30, 2000

012

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
U-0284A

1a. Type of Well Oil Well Gas Well Dry Other
b. Type of Completion New Well Work Over Deepen Plug Back Diff. Resvr.
Other _____

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.
CHAPITA WELLS

2. Name of Operator
EOG RESOURCES, INC

Contact: ALFREDA SCHULZ
E-Mail: alfreda_schulz@eogresources.com

8. Lease Name and Well No.
CHAPITA WELLS UNIT 841-22

3. Address P. O. BOX 250
BIG PINEY, WY 83113

3a. Phone No. (include area code)
Ph: 307.276.4833

9. API Well No.
43-047-35219

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface NESW 1898FSL 2365FWL 40.01945 N Lat, 109.42639 W Lon

At top prod interval reported below NESW 1898FSL 2365FWL 40.01945 N Lat, 109.42639 W Lon

At total depth NESW 1898FSL 2365FWL 40.01945 N Lat, 109.42639 W Lon

10. Field and Pool, or Exploratory
NATURAL BUTTES/MESAVERDE

11. Sec., T., R., M., or Block and Survey
or Area Sec 22 T9S R22E Mer SLB

12. County or Parish
UINTAH

13. State
UT

14. Date Spudded
02/25/2004

15. Date T.D. Reached
03/19/2004

16. Date Completed
 D & A Ready to Prod.
04/07/2004

17. Elevations (DF, KB, RT, GL)*
4960 KB

18. Total Depth: MD 10325
TVD 10320

19. Plug Back T.D.: MD 10283
TVD

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
 RST, CBL

22. Was well cored? No Yes (Submit analysis)
Was DST run? No Yes (Submit analysis)
Directional Survey? No Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
7.875	4.500 P110	11.6		10325		2100			
17.500	13.375 H40	48.0	0	286		250			
12.250	9.625 J55	36.0	0	2319		705			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	10159							

25. Producing Intervals

26. Perforation Record

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	9984	10154	9984 TO 10154			2 SPF/PRODUCING
B)						
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
9984 TO 10154	1314 BBLs GELLED WATER & 192,000# 20/40 SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
04/07/2004	04/12/2004	24	▶	8.0	954.0	32.0			FLows FROM WELL
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
8/64	3100	3300.0	▶	8	954	32		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			▶						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			▶						

RECEIVED

APR 19 2004

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #29474 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

DIV. OF OIL, GAS & MINING

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
MESAVERDE	9984	10154		WASATCH NORTH HORN ISLAND MESAVERDE BUG TOP KMV-MIDDLE PRICE RIVER KMV-LOWER PRICE RIVER PRESSURE PICKS SEGO CASTLEGATE BASE CASTLEGATE BLACK TG 2 BLACKHAWK BLACKHAWK 1	4743 6682 7146 7408 8052 8856 8450 9310 9516 9740 9884 9948 10008

32. Additional remarks (include plugging procedure):

FLOWING THROUGH QUESTAR SALES METER # 5993. TWO (2) 400 BBL TANKS ON LOCATION # 80317V, 80317V.
Perforated the Blackhawk from 9984-86', 10015-17', 10031-31', 10041-43', 10070-71', 10086-87', 10140-42', 10153-54' @ 2 SPF.

33. Circle enclosed attachments:

- 1. Electrical/Mechanical Logs (1 full set req'd)
- 2. Geologic Report
- 3. DST Report
- 4. Directional Survey
- 5. Sundry Notice for plugging and cement verification
- 6. Core Analysis
- 7 Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #29474 Verified by the BLM Well Information System.
For EOG RESOURCES, INC, sent to the Vernal

Name (please print) ALFREDA SCHULZ Title SR. REGULATORY ASSISTANT

Signature (Electronic Submission) Date 04/15/2004

RECEIVED
APR 19 2004

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. **DIV. OF OIL, GAS & MINING**

**** ORIGINAL ** ORIGINAL ****

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

013

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
U-0284A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS

8. Well Name and No.
CHAPITA WELLS 841-22

9. API Well No.
43-047-35219

10. Field and Pool, or Exploratory
NATURAL BUTTES / MESAVERDE

11. County or Parish, and State
UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
EOG RESOURCES, INC

Contact: ALFREDA SCHULZ
E-Mail: alfreda_schulz@eogresources.com

3a. Address
P. O. BOX 250
BIG PINEY, WY 83113

3b. Phone No. (include area code)
Ph: 307.276.4833

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 22 T9S R22E NESW 1898FSL 2365FWL
40.01945 N Lat, 109.42639 W Lon

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc. completed pay in the Mesaverde formation of the referenced well as follows:

- Set 10K composite bridge plug @ 9493'. Perforated Lower Price River/Sego from 9278-80', 9320-23', 9354-56', 9360-62' & 9378-80' w/2 SPF. Fracture stimulated with 2016 bbls gelled water & 66,451# 20/40 sand.
- Set 10K composite bridge plug @ 9254'. Perforated Lower Price River from 9042-45', 9086-88', 9154-56', 9168-70' & 9221-24' w/2 SPF. Fracture stimulated with 1332 bbls gelled water & 54,098# 20/40 sand.
- Set 10K composite bridge plug @ 9015'. Perforated Lower Price/Middle Price River from 8814-16', 8832-33', 8850-51', 8873-74', 8916-19', 8964-66' & 8992-94' w/2 SPF. Fracture stimulated with 1543 bbls gelled water & 62,793# 20/40 sand.
- Set 10K composite bridge plug @ 8667'. Perforated Middle Price River from 8468-70', 8487-89', 8530-33', 8582-84' & 8620-22' w/2 SPF. Fracture stimulated with 2859 bbls gelled water & 122,649#

14. I hereby certify that the foregoing is true and correct.
Electronic Submission #32341 verified by the BLM Well Information System For EOG RESOURCES, INC, sent to the Vernal

Name (Printed/Typed) ALFREDA SCHULZ Title SR. REGULATORY ASSISTANT

Signature (Electronic Submission) Date 07/26/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

RECEIVED
JUL 29 2004

DIV. OF OIL, GAS & MINING

Additional data for EC transaction #32341 that would not fit on the form

32. Additional remarks, continued

20/40 sand. Set 10K composite bridge plug @ 8408'. Drilled out bridge plugs @ 8408', 8667', 9015' & 9254'. Bridge plug over Blackhawk formation left in place. Landed tubing @ 8442'.

5. Returned to sales 7/2/2004 through Questar sales meter #5993.

TEST: 7/16/2004, 466 MCF, 0 BC, 182 BW in 24 hours on a 12/64" choke, FTP 1100, CP 1900 psig.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

014

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU 0284A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
UTU 63013F

8. Well Name and No.
CHAPITA WELLS UNIT 841-22

9. API Well No.
43-047-35219

10. Field and Pool, or Exploratory
NATURAL BUTTES / MESAVERDE

11. County or Parish, and State
UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
EOG RESOURCES, INC

Contact: ALFREDA SCHULZ
E-Mail: alfreda_schulz@eogresources.com

3a. Address
P. O. BOX 250
BIG PINEY, WY 83113

3b. Phone No. (include area code)
Ph: 307.276.4833

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 22 T9S R22E NESW 1898FSL 2365FWL
40.01945 N Lat, 109.42639 W Lon

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc. continued completion in the Mesaverde formation of the referenced well as follows:
Set 10k composite bridge plug @ 9250'. Landed tubing @ 9718'.
TEST: 8/20/2004, 336 MCFD, 15 BC & 84 BW in 24 hours on 12/64" choke, TP 850 PSIG, CP 1400 PSIG.

RECEIVED
SEP 22 2004

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.
Electronic Submission #35568 verified by the BLM Well Information System For EOG RESOURCES, INC, sent to the Vernal

Name (Printed/Typed) ALFREDA SCHULZ Title SR. REGULATORY ASSISTANT

Signature (Electronic Submission) Date 09/20/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
EOG RESOURCES, INC.

3a. Address
P.O. Box 1815 Vernal, UT 84078

3b. Phone No. (include area code)
435-789-0790

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
1898 FSL 2365 FWL (NE/SW) S.L.B.&M SECTION 22, T9S, R22E

5. Lease Serial No.
U-0284-A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNIT

8. Well Name and No.
CHAPITA WELLS UNIT 841-22

9. API Well No.
43-047-35219

10. Field and Pool, or Exploratory Area
NATURAL BUTTES/MESAVERDE

11. County or Parish, State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc respectfully requests permission to recomplete the referenced well opening additional pay in the Mesaverde formation as per the attached procedure.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

**Federal Approval of This
Action Is Necessary**

4-28-06
CWO

Date: 4/16/06
By: [Signature]

14. I hereby certify that the foregoing is true and correct
 Name (Printed/Typed) **Kaylene R. Gardner** Title **Regulatory Assistant**

Signature [Signature] Date **03/27/2006**

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____ Title _____ Date _____
 Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

(Instructions on page 2)

APR 05 2006

DIV. OF OIL, GAS & MINING

**RECOMPLETION
PROGRAM SLICKWATER
CWU 841-22**

CWU 841-22
1898' FSL & 2365' FWL (NEW/SW)
Section 22, T9S, R22E
Uintah County, Utah

March 20, 2006
EOG WI: 50.0% BPO
NRI: 43.5% BPO
API# 43-047-35219
AFE# 302521

WELL DATA:

ELEVATION: 4945' GL KB: 4959' (14' KB)

TOTAL DEPTH: 10325' KB PBSD: 10283' KB (Top of FC)

CASING: 13-3/8" 48#, H-40 set @ 286' KB. Cement to surface - 7 bbls.
9-5/8", 36#, J-55 set @ 2319'. Cemented w/100 sx Hi-Lift & 305 sx RFC 10-2. Top job w/300 sx "G". Circ cmt to surface.
4-1/2", 11.6#, P-110 set @ 10,325'. Cemented w/500 sx 35/65 Pozmix & 1600 sx 50/50 Pozmix. Bumped plug, float held.
2-3/8", 4.7#, N-80 Tbg landed @ 10,159'. 1 joint, XN nipple, then 312 joints.

EXISTING PERFS	SPF/Phasing	INTERVAL	
9984-86', 10015-17', 10031-32', 10041-43', 10070-71', 10086-87', 10140-42', 10153-54'	2/180°	Blackhawk	1

PROPOSED PERFS	SPF/Phasing	INTERVAL	FRAC #
9278-80', 9320-23', 9354-56', 9360-62', 9378-80'	2/180°	Lower Price River/Sego	2
9042-45', 9086-88', 9154-56', 9168-70', 9221-24'	2/180°	Lower Price River	3
8814-16', 8832-33', 8850-51', 8873-74', 8916-19', 8964-66', 8992-94'	2/180°	Middle/Lower Price River	4
8468-70', 8487-89', 8530-33', 8582-84', 8620-22'	2/180°	Middle Price River	5

PROPOSED PERFS	SPF/Phasing	INTERVAL	FRAC #
8300-01', 8306-07', 8353-55', 8375-76', 8381-83', 8388-89', 8396-97', 8409-11', 8423-24'	2/180°	Middle Price River	6
8162-63', 8167-68', 8193-94', 8204-05', 8215-16', 8240-41', 8247-48', 8255-56', 8262-63'	2/180°	Middle Price River	7
7974-76', 7991-93', 8017-18', 8021-22', 8061-62', 8098-100', 8104-05', 8115-16'	2/180°	Upper Price River	8
7745-47', 7796-97', 7812-14', 7825-27', 7849-50', 7862-63', 7884-85', 7904-05', 7919-20'	2/180°	Upper Price River	9

**RECOMPLETION PROGRAM
CWU 841-22**

7430-31', 7465-66', 7482-83', 7502-03', 7525-26', 7543-45', 7555-56', 7566-67', 7614-17'	2/180°	Upper Price River	10
7219-21', 7230-31', 7255-56', 7300-02', 7330-31', 7336-37', 7346-47', 7370-73', 7387-89'	2/180°	Upper Price River	11

PROCEDURE:

1. MIRUSU. NDWH. NU 10M# BOPE. POOH with 2-3/8" tubing. RUWL. Set Weatherford 10K composite bridge plug @ 8450'±. Perforate Middle Price River intervals from 8300'-8424' as shown using a 3-1/8" HSC ported casing gun. RDWL.
2. RU Schlumberger. Frac down casing per attached procedure. RD Schlumberger.
3. RUWL. Set Weatherford 10K composite frac plug @ 8285'±. Perforate Middle Price River intervals from 8162'-8263' as shown. RDWL.
4. RU Schlumberger. Frac down casing per attached procedure. RD Schlumberger.
5. RUWL. Set Weatherford 10K composite frac plug @ 8140'±. Perforate Upper Price River intervals from 7974-8116' as shown. RDWL.
6. RU Schlumberger. Frac down casing per attached procedure. RD Schlumberger.
7. RUWL. Set Weatherford 10K composite frac plug @ 7945'±. Perforate Upper Price River intervals from 7745'-7920' as shown. RDWL.
8. RU Schlumberger. Frac down casing per attached procedure. RD Schlumberger.
9. RUWL. Set Weatherford 10K composite frac plug @ 7650'±. Perforate Upper Price River intervals from 7430'-7617' as shown. RDWL.
10. RU Schlumberger. Frac down casing per attached procedure. RD Schlumberger.
11. RUWL. Set Weatherford 10K composite frac plug @ 7405'±. Perforate Upper Price River intervals from 7219'-7389' as shown. RDWL
12. RU Schlumberger. Frac down casing per attached procedure. RD Schlumberger. Flow back immediately. Following flowback, RIH w/3-7/8" bit & pump off sub. Drill out composite frac plugs. Clean out to PBTD. Land tubing below perfs. ND BOPE. NU 10M psig tree. Drop ball. Pump off bit & sub. Swab/flow test.
13. RDMOSU. Place well on production.

PREPARED BY:

OTTO DICK, COMPLETIONS ENGINEER

REVIEWED BY:

PAUL PENDLETON, AREA PRODUCTION MANAGER

APPROVED BY:

KEN BOEDEKER, DIVISION ENGINEERING MANAGER

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator **EOG Resources, Inc.**

3a. Address
600 17th Street, Suite 1000N, Denver, CO 80202

3b. Phone No. (include area code)
303-262-2812

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**1,898' FSL 2,365' FWL (NESW)
 Sec. 22-T9S-R22E 40.019453 LAT 109.426392 LON**

5. Lease Serial No.
U-0284-A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
Chapita Wells Unit

8. Well Name and No.
Chapita Wells Unit 841-22

9. API Well No.
43-047-35219

10. Field and Pool, or Exploratory Area
Natural Buttes/Mesaverde

11. County or Parish, State
Uintah County, Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The referenced well was recompleted opening additional pay in the Mesaverde formation.


The well was returned to sales 4/4/2006.

14. I hereby certify that the foregoing is true and correct
 Name (Printed/Typed)

Carrie MacDonald

Title **Operations Clerk**

Signature



Date

04/19/2007

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

(Instructions on page 2)

APR 20 2007

DIV. OF OIL, GAS & MINING

PERCY**OPERATIONS SUMMARY REPORT**

WELL NAME:	CWU 841-22	AFE NO:	303952
RIG NAME:	BASIC 1469	WELL ID NO.:	053603
FIELD NAME:	CHAPITA WELLS DEEP	API NO.:	43-047-35219
EVENT NO.:	4	EVENT DESC.:	RECOMPLETE KMV

DATE: 3/15/2006	DSS: 0	DEPTH: 10,320	MUD WT:	CUM COST TO DATE:
------------------------	---------------	----------------------	----------------	--------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
24.00	C	OT		<p>LOCATION DATA</p> <p>1898' FSL & 2365' FWL (NE/SW)</p> <p>SECTION 22, T9S, R22E</p> <p>UINTAH COUNTY, UTAH</p> <p>TRUE RIG #9</p> <p>10,325' MESAVERDE</p> <p>DW/GAS</p> <p>CHAPITA WELLS DEEP PROSPECT</p> <p>LEASE: U-0284-A</p> <p>ELEVATION: 4945' NAT GL, 4945' PREP GL, ' KB (')</p> <p>EOG WI 50%, NRI 43.5%</p> <p>WESTPORT WI 50%</p>

DATE: 3/26/2006	DSS: 0	DEPTH: 10,325	MUD WT:	CUM COST TO DATE: 5,550.00
------------------------	---------------	----------------------	----------------	-----------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
6.50	C	OT		<p>SITP 475 PSIG. SICP 800 PSIG. MIRUSU. KILLED WELL W/80 BBLS TREATED WATER. ND TREE. NU BOPE. POH.</p> <p>HEAVY SCALE ON OUTSIDE OF TUBING @ 7500'± & MODERATE SCALE 8500'±. LIGHT SCALE PRESENT ON</p> <p>BOTTOM 3 STDS. SDFN.</p>

DATE: 3/28/2006	DSS: 0	DEPTH: 10,325	MUD WT:	CUM COST TO DATE: 13,300.00
------------------------	---------------	----------------------	----------------	------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
8.50	C	OT		<p>SICP 1500 PSIG. BLEW WELL DOWN. KILLED WITH 40 BBLS TREATED WATER. RIH W/BIT & SCRAPER TO 9886'.</p> <p>POH.</p> <p>RU CUTTERS WL. SET WEATHERFORD 10K CBP @ 8450'. PERFORATED MPR FROM 8423'-24', 8409'-11', 8396'-97', 8388'-89', 8381'-83', 8375'-76', 8353'-55', 8306'-07' & 8300'-01'. RDWL. PREP TO FRAC. SDFN.</p>

DATE: 3/29/2006	DSS: 0	DEPTH: 10,325	MUD WT:	CUM COST TO DATE: 36,066.00
------------------------	---------------	----------------------	----------------	------------------------------------



OPERATIONS SUMMARY REPORT

WELL NAME: CWU 841-22	AFE NO: 303952
RIG NAME: BASIC 1469	WELL ID NO.: 053603
FIELD NAME: CHAPITA WELLS DEEP	API NO.: 43-047-35219
EVENT NO.: 4	EVENT DESC.: RECOMPLETE KMV

DATE: 3/29/2006	DSS: 0	DEPTH: 10,325	MUD WT:	CUM COST TO DATE: 36,066.00
------------------------	---------------	----------------------	----------------	------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
11.50	C	OT		SICP 464 PSIG. RU SCHLUMBERGER. FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 15827 GAL SLICK WATER PAD, 54439 GAL SLICK WATER WITH 57700# 20/40 SAND @ 1-2.5 PPG. MTP 8506 PSIG. MTR 56.5 BPM. ATP 6293 PSIG. ATR 42.2 BPM. ISIP 2550 PSIG. RD SCHLUMBERGER.
				RUWL. SET 10K CFP AT 8285'. PERFORATED MPR FROM 8162'-63', 8167'-68', 8193'-94', 8204'-05', 8215'-16', 8240'-41', 8247'-48', 8255'-56' & 8262'-63' @ 2 SPF & 180° PHASING. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 10,466 GAL SLICK WATER PAD, 98062 GAL SLICK WATER WITH 110,300# 20/40 SAND @ 1-2.5 PPG. MTP 8462 PSIG. MTR 56.6 BPM. ATP 7255 PSIG. ATR 52.9 BPM. ISIP 2670 PSIG. RD SCHLUMBERGER.
				RUWL SET 10K CFP AT 8140'. PERFORATED UPR FROM 7974'-76', 7991'-93', 8017'-18', 8021'-22', 8061'-62', 8098'-100', 8104'-05' & 8115'-16' @ 2 SPF & 180° PHASING. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 10461 GAL SLICK WATER PAD, 59,595 GAL SLICK WATER WITH 63,800# 20/40 SAND @ 1-2.5 PPG. MTP 8210 PSIG. MTR 57.4 BPM. ATP 7317 PSIG. ATR 55 BPM. ISIP 2670 PSIG. RD SCHLUMBERGER.
				RUWL. SET 10K CFP AT 7945'. PERFORATED UPR FROM 7745'-47', 7796'-97', 7812'-14', 7825'-27', 7849'-50', 7862'-63', 7884'-85', 7904'-05' & 7919'-20' @ 2 SPF & 180° PHASING. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 10,469 GAL SLICK WATER PAD, 60,889 GAL SLICK WATER WITH 68,100# 20/40 SAND @ 1-2.5 PPG. MTP 8198 PSIG. MTR 60.3 BPM. ATP 7300 PSIG. ATR 51.9 BPM. ISIP 2600 PSIG. RD SCHLUMBERGER.
				RUWL. SET 10K CFP AT 7650'. PERFORATED UPR FROM 7219'-21', 7230'-31', 7255'-56', 7300'-02', 7330'-31', 7336'-37', 7346'-47', 7370'-73' & 7387'-89' @ 2 SPF & 180° PHASING. RDWL. SDFN.

DATE: 3/30/2006	DSS: 0	DEPTH: 10,325	MUD WT:	CUM COST TO DATE: 100,017.00
------------------------	---------------	----------------------	----------------	-------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
11.00	C	OT		SICP 2020 PSIG. RU SCHLUMBERGER. FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 10462 GAL SLICK WATER PAD, 54134 GAL SLICK WATER WITH 59,300 # 20/40 SAND @ 1-2.5 PPG. MTP 7958 PSIG. MTR 60.3 BPM. ATP 7220 PSIG. ATR 54.4 BPM. ISIP 2200 PSIG. RD SCHLUMBERGER.
				RUWL SET 10K CFP AT 7414'. PERFORATED UPR FROM 7219'-21', 7230'-31', 7255'-56', 7300'-02', 7330'-31', 7336'-37', 7346'-47', 7370'-73' & 7387'-89' @ 2 SPF & 180° PHASING. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 10,459 GAL SLICK WATER PAD, 113,903 GAL SLICK WATER WITH 106,800# 20/40 SAND @ 1-2.5 PPG. MTP 7333 PSIG. MTR 60.1 BPM. ATP 5840 PSIG. ATR 56.3 BPM. ISIP 2970 PSIG. RD SCHLUMBERGER.
				RUWL SET 10K CBP @ 7180'. RDWL. RIH W/BIT & PUMP OFF SUB TO CBP @ 7180'. SDFN.

DATE: 3/31/2006	DSS:	DEPTH: 10,320	MUD WT:	CUM COST TO DATE: 108,067.00
------------------------	-------------	----------------------	----------------	-------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
8.00	C	OT		SICP 0 PSIG. CLEANED OUT & DRILLED OUT PLUGS @ 7180', 7414', 7650', 7945' & 8140'. POH TO 7100'. SDFN.

DATE: 4/1/2006	DSS:	DEPTH: 10,320	MUD WT:	CUM COST TO DATE: 118,891.00
-----------------------	-------------	----------------------	----------------	-------------------------------------



OPERATIONS SUMMARY REPORT

WELL NAME: CWU 841-22	AFE NO: 303952
RIG NAME: BASIC 1469	WELL ID NO.: 053603
FIELD NAME: CHAPITA WELLS DEEP	API NO.: 43-047-35219
EVENT NO.: 4	EVENT DESC.: RECOMPLETE KMV

DATE: 4/1/2006	DSS:	DEPTH: 10,320	MUD WT:	CUM COST TO DATE: 118,891.00
-----------------------	-------------	----------------------	----------------	-------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
12.00	C	OT		SITP 500 PSIG. SICP 1400 PSIG. CLEANED OUT & DRILLED OUT PLUGS @ 8285' & 8450'. CLEANED OUT TO PBTD @ 10,233'. LANDED TBG AT 7209' KB. ND BOPE. NU TREE. PUMPED OFF BIT & SUB. SDFN.

FLOWED 12 HRS. 18/64" CHOKE. FTP 1000 PSIG. CP 1750 PSIG. 33 BFPH. RECOVERED 434 BLW. 11689 BLWTR.

<u>TUBING DETAIL</u>	<u>LENGTH</u>
PUMP OFF SUB	1.00'
1 JT 2-3/8" 4.7# N80 TBG	32.54'
XN NIPPLE	1.10'
221 JTS 2-3/8" 4.7# N80 TBG	7160.29'
BELOW KB	14.00'
LANDED @	7208.93' KB

DATE: 4/2/2006	DSS:	DEPTH: 10,320	MUD WT:	CUM COST TO DATE: 121,116.00
-----------------------	-------------	----------------------	----------------	-------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
24.00	C	OT		FLOWED 24 HRS. 18/64 CHOKE. FTP 1150 PSIG, CP 1700 PSIG. 32 BFPH. RECOVERED 1156 BBLS, 10967 BLWTR.

DATE: 4/3/2006	DSS:	DEPTH: 10,320	MUD WT:	CUM COST TO DATE: 123,691.00
-----------------------	-------------	----------------------	----------------	-------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
24.00	C	OT		FLOWED 12 HRS. 18/64" CHOKE. FTP 1200 PSIG, CP 2050 PSIG. 28 BFPH. RECOVERED 779 BBLS, 10344 BLWTR.

DATE: 4/4/2006	DSS:	DEPTH: 10,320	MUD WT:	CUM COST TO DATE: 124,766.00
-----------------------	-------------	----------------------	----------------	-------------------------------------

<u>HOURS</u>	<u>PH</u>	<u>OP</u>	<u>ACT</u>	<u>ACTIVITY DESCRIPTION</u>
3.50	C	OT		FLOWED 3.5 HRS. 18/64" CHOKE. FTP 1200 PSIG. CP 2050 PSIG. 28 BFPH. RECOVERED 81 BLW. 10263 BLWTR. RETURNED WELL TO PRODUCTION.