

EOG Resources, Inc.
P.O. 1910
Vernal, UT 84078

February 23, 2004

Utah Division of Oil, Gas, & Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: APPLICATION FOR PERMIT TO DRILL
CHAPITA WELLS UNIT 655-6
NW/SW (Lot 6), SEC. 6, T9S, R23E
UINTAH COUNTY, UTAH
LEASE NO.: U-01304
FEDERAL LANDS

Enclosed please find a copy of the Application for Permit to Drill and associated attachments for the referenced well.

Please address further communication regarding this matter (including approval) to:

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Phone: (435)789-4120
Fax: (435)789-1420

Sincerely,


Ed Trotter
Agent
EOG Resources, Inc.

Attachments

RECEIVED
FEB 26 2004
DIV. OF OIL, GAS & MINING

001

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: DRILL REENTER
1b. Type of Well: Oil Well Gas Well Other Single Zone Multiple Zone

2. Name of Operator
EOG RESOURCES, INC.

3a. Address **P.O. BOX 1815
VERNAL, UT 84078**
3b. Phone No. (Include area code)
(435)789-0790

4. Location of Well (Report location clearly and in accordance with any State requirements. *)
At surface **2084' FSL, 434' FWL** ^{4435874Y} _{638460X} **NW/SW** ^{40.06366} _{-109.37649}
At proposed prod. Zone
10. Field and Pool, or Exploratory
NATURAL BUTTES
11. Sec., T., R., M., or Blk. and Survey or Area
**SEC. 6, T9S, R23E,
S.L.B.&M.**

14. Distance in miles and direction from nearest town or post office*
18 MILES SOUTHEAST OF OURAY, UTAH
12. County or Parish
UINTAH
13. State
UTAH

15. Distance from proposed* location to nearest property or lease line, ft. **434'**
(Also to nearest drig. Unit line, if any)
16. No. of Acres in lease
2451
17. Spacing Unit dedicated to this well
'

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. See Topo Map C
6775'
19. Proposed Depth
6775'
20. BLM/BIA Bond No. on file
NM-2308


21. Elevations (Show whether DF, KDB, RT, GL, etc.)
4866.1 FEET GRADED GROUND
22. Approximate date work will start*
UPON APPROVAL
23. Esti mated duration
45 DAYS

24. Attachments


Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:


- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature  Name (Printed/Typed) **Ed Trotter** Date **February 23, 2004**

Title
Agent

Approved by (Signature)  Name (Printed/Typed) **BRADLEY G. HILL**
Title **ENVIRONMENTAL SCIENTIST III**

**Federal Approval of this
Action is Necessary**



Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of Approval, if any, are attached.


Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

R
22
E

R
23
E

T9S, R23E, S.L.B.&M.



LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 27)
 LATITUDE = 40°03'49.01" (40.063614)
 LONGITUDE = 109°22'35.96" (109.376656)

EOG RESOURCES, INC.


Well location, CWU #655-6, located as shown in the NW 1/4 SW 1/4 of Section 6, T9S, R23E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 20EAM LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Debra H. Johnson
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 01-19-04	DATE DRAWN: 01-21-04
PARTY G.S. M.B. D.COX	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE EOG RESOURCES, INC.	

EIGHT POINT PLAN

CHAPITA WELLS UNIT 655-6
NW/SW (Lot 6), SEC. 6, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River	1,943'
Wasatch	4,979'
Chapita Wells	5,635'
Buck Canyon	6,290'

EST. TD: 6775

Anticipated BHP 2900 PSI

3. PRESSURE CONTROL EQUIPMENT: 3000 PSIG BOP Schematic Diagram attached.

4. CASING PROGRAM:

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>RATING FACTOR</u>		
							<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
12 1/4"	0' - 250'+/-KB	250+/-	9 5/8"	36.0 #	J-55	STC	2020 PSI	3520 PSI	394,000#
7 7/8"	250' - TD +/-KB	6775' +/-	4 1/2"	11.6 #	J-55	LTC	4960 PSI	5350 PSI	162,000#

All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0-250' Below GL):

Guide Shoe

Insert Baffle

Wooden wiper plug

Centralizers: 1 - 5-10' above shoe, every collar for next 3 joints (4 total).

Float Equipment- Production Hole Procedure (250'-TD):

Texas-Pattern shoe, short casing shoe joint ($\pm 20'$), Float Collar, and balance of casing to surface. Run short casing joint (less than 38') at $\pm 3,900'$ (1000' above projected top of Wasatch). Centralize 5' above shoe on joint #1, top of joint #2, then every 4th joint to $\pm 4,500'$ (400' above Wasatch top - 15 total). Thread lock shoe, top and bottom of FC, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (0-250' below GL):

Air - Air Water Mist

EIGHT POINT PLAN

CHAPITA WELLS UNIT 655-6
NW/SW (Lot 6), SEC. 6, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

MUD PROGRAM (Continued):

Production Hole Procedure (250'-TD):

2700' - 4500' Water (circulate through reserve pit) with Gel/LCM sweeps.

4500' - 6900' Close in mud system. "Mud up" with **6.0 ppb** Diammonium Phosphate (DAP). Drill with DAP water, POLYPLUS for viscosity and hole cleaning, adding KLA-GARD B for supplemental inhibition. Also sweep hole periodically w/ Durogel / LCM sweeps to clean the hole and seal loss zones. Add additional LCM as hole dictates. Mud weight and vis as needed, water loss - no control.

6900' - TD Discontinue KLA-GARD B. Utilize POLYPAC-R for fluid loss control. Maintain **5.5 ppb** DAP. **Do not mix caustic or lime.** Maintain 7.5-8.5 pH. Weight up system and add vis as hole conditions require. Run LCM sweep periodically to seal off loss zones or more often as hole dictates. Water loss: 20 cc's maximum. Expect increasing gas shows requiring heavier mud weights from top of Island onward. Treat CO₂ contamination with DESCO CF and OSIL (Oxygen scavenger) if mud properties dictate.

7. VARIANCE REQUESTS:

- A. EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line (Where possible, a straight run blooie line will be used).
- B. EOG Resources, Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).
- C. EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be 75' in length.

8. EVALUATION PROGRAM:

Logs: Schlumberger Platform Express TD - Surface Casing, with Di-pole Sonic from TD to surface in 1 run.

9. CEMENT PROGRAM:

Surface Hole Procedure (0-250' Below GL)

Lead: 200 sks. (100% excess volume) Class 'G' cement with 2% S1 (CaCl₂) & 0.25 pps D29 (cellophane flakes), mixed at 15.8 ppg, 1.15. ft³/sk., 4.95 gps water.

Top Out: Top out with Class 'G' cement with 2% S1 (CaCl₂) in mix water, 15.8 ppg., 1.15. ft³/sk., 4.95 gps via 1" tubing set at 25' if needed.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 655-6
NW/SW (Lot 6), SEC. 6, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

CEMENT PROGRAM (Continued):

Production Hole Procedure (250' to TD)

Lead: 100 sks: Class 'G' lead cement with 5% D44 (Salt), 12% D20 (Bentonite), 1% D79% (Extender), 0.25% D112 (Fluid Loss Additive), 0.2% D46 (Anti-Foamer) & 0.25 pps D29 (Cellophane flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 250 sks: 50:50 Poz G w/ 2% D20 (Bentonite), 10% D44 (Salt), mixed at 14.1 ppg, 1.35 cu. ft./sk., 5.0 gps water. 50:50 Poz G w/ 2% D20 (Bentonite), 10% D44 (Salt), mixed at 14.1 ppg, 1.35 ft³/sk., 5.0 gps water.

10. ABNORMAL CONDITIONS:

PRODUCTION HOLE (250'-TD)

Potential Problems: Lost circulation, asphaltic, black oil flows, large Trona water flows and gas flows may be encountered in the Green River, beginning at $\pm 1,900'$. Other wells in the general area of the CWU 655-06 (all drilled with air/mist or aerated water) reported problems with sloughing formation in the Wasatch while attempting to mud up for logs or to run casing.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

3000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
 CASING FLANGE IS 11" 3000 PSIG RATED.
 BOPE 11" 3000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 3000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 3000 psig BOPE specifications.



**CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL**

Company/Operator: EOG Resources, Inc.
Well Name & Number: Chapita Wells Unit 655-6
Lease Number: U-01304
Location: 2084' FSL & 434' FWL, NW/SW, (Lot 6) Sec. 6,
T9S, R23E, S.L.B.&M., Uintah County, Utah
Surface Ownership: Federal

NOTIFICATION REQUIREMENTS

Location Construction - forty-eight (48) hours prior to construction of location and access roads.

Location Completion - prior to moving on the drilling rig.

Spud Notice: - at least twenty-four (24) hours prior to spudding the well.

Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.

BOP and related Equipment Tests - twenty-four (24) hours prior to running casing and tests.

First Production Notice - within five (5) business days after new Well begins or production resumes after Well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

THIRTEEN POINT SURFACE USE PROGRAM

1. EXISTING ROADS

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 18 miles southeast of Ouray, Utah - See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. PLANNED ACCESS ROAD

- A. The access road will be approximately 0.4 miles in length. See attached TOPO Map "B".
- B. The access road has a 30 foot ROW w/ 18 foot running surface.
- C. Maximum grade on access road will be 8%.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.

New or reconstructed roads will be centerlined - flagged at time of location staking.

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, drainage, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot Right-of-Way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

3. **LOCATION OF EXISTING WELLS WITHIN A ONE MILE RADIUS OF PROPOSED WELL LOCATION**

A. Abandoned wells - 1*

B. Producing wells - 5*

(*See attached TOPO map "C" for location)

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

A. **ON WELL PAD**

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, 300 Bbl vertical or 200 Bbl low profile, condensate tank, and attaching piping.
2. Gas gathering lines - A 4" gathering line will be buried from dehy to the edge of the location.

B. **OFF WELL PAD**

1. Proposed location of attendant off pad flowlines shall be flagged prior to archaeological clearance.
2. A 4" OD steel above ground natural gas pipeline will be laid approximately 1362' from proposed location to a point in the NW/SE of Section 1, T9S, R22E, where it will tie into Questar Pipeline Co.'s existing line. Proposed pipeline crosses Federal lands within the Chapita Wells Unit, thus a Right-of-Way grant will not be required.
3. Proposed pipeline will be a 4" OD steel, welded line laid on the surface.
4. Protective measures and devices for livestock and wildlife will be taken and/or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery.

The production facilities will be placed on the Southeast side of the location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities

required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Carlsbad Canyon.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

5. LOCATION & TYPE OF WATER SUPPLY

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/or Target Trucking Inc.'s water source in the SW/SW, Sec. 35, T9S, R22E, Uintah County, Utah (State Water Right #49-1501). Produced water from the Chapita Wells and Stagecoach Units will also be used.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIAL

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of the location.
- B. All construction material will come from Federal Land.
- C. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
- 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following three locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).

5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit or be removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

On BLM administered land:

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with a plastic liner. A felt liner will also be installed if rock is encountered during pit construction.

8. **ANCILLARY FACILITIES**

- A. No airstrips or camps are planned for this well.

9. **WELLSITE LAYOUT**

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.
- D. The approved seed mixture for this location is:
 - Four Wing Salt Bush – 3 pounds per acre
 - Indian Rice Grass – 2 pounds per acre
 - Needle and Thread Grass – 2 pounds per acre
 - Globe Mallow – 1 pound per acre
 - Hi-Crest Crested Wheat Grass – 1 pound per acre.

The reserve pit will be located on the Northwest corner of the location. The flare pit will be located downwind of the prevailing wind direction on the North side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled pit topsoil will be stored separate from the location topsoil East of Corners B and 5. The stockpiled location topsoil will be stored from West of Corner #1 to Corner #8. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture for this location and then walked down with a cat.

Access to the well pad will be from the.

Corners #2, #6, & #8 will be rounded off to minimize excavation.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently mounted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RESTORATION OF SURFACE

A. PRODUCING LOCATION

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

B. DRY HOLE/ABANDONED LOCATION

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP

Access road: Federal

Location: Federal

12. OTHER INFORMATION

A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the AO. Within five working days the AO will inform the operator as to:

- whether the materials appear eligible for the National Register of Historic Places;
- the mitigation measures the operator will likely have to undertake before the site can be used.
- a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification

from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

Additional Surface Stipulations

X No construction or drilling activities shall be conducted between May 15 and June 20 because of Antelope Stipulations.

X A pond to trap silt will be constructed 100' East of Corner #8 of the location with an 18" culvert in the spillway.

LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION

PERMITTING AGENT

Ed Trotter
P.O. Box 1910
Vernal, UT 84078
Telephone: (435)789-4120
Fax: (435)789-1420

DRILLING OPERATIONS

Donald Presenkowski
EOG Resources, Inc.
P.O. Box 250
Big Piney, WY 83113
Telephone: (307)276-4865

All lease or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approval plan of operations, and any applicable Notice to Lessees. EOG Resources, Inc. is fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.


A copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions that presently exist; that the statements made in the Plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this Plan and the terms and conditions under which it is approved.

Please be advised that EOG Resources, Inc. is considered to be the operator of the **Chapita Wells Unit 655-6 Well, located in the NW/SW (Lot 6) Section 6, T9S, R23E, Uintah County, Utah; Lease #U-01304;** and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is provided under Bond #NM 2308.

2-23-2004
Date


Agent

EOG RESOURCES, INC.
CWU #655-6
SECTION 6, T9S, R23E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; TURN LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; PROCEED IN A SOUTHEASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 2.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN RIGHT AND PROCEED IN AN EASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 0.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 1.3 MILES TO THE BEGINNING OF THE PROPOSED ACCESS ROAD FOR TO THE SOUTHEAST; FOLLOW ROAD FLAGS IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 0.4 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 49.0 MILES.

EOG RESOURCES, INC.

CWU #655-6

LOCATED IN UINTAH COUNTY, UTAH

SECTION 6, T9S, R23E, S.L.B.&M.




PHOTO: VIEW FROM LOCATION STAKE TO CORNER #1

CAMERA ANGLE: SOUTHWESTERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHEASTERLY



- Since 1964 -

E&L S Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com




LOCATION PHOTOS	01	22	04	PHOTO
	MONTH	DAY	YEAR	
TAKEN BY: G.S.	DRAWN BY: P.M.	REVISED: 00-00-00		

SCALE: 1" = 50'
 DATE: 01-21-04
 Drawn By: D.COX


EOG RESOURCES, INC

LOCATION LAYOUT FOR

CWU #655-6
 SECTION 6, T9S, R23E, S.L.B.&M.
 2084' FSL 434' FWL



NOTE:
 Flare Pit is to be located a min. of 100' from the Well Head.



Elev. Ungraded Ground at Location Stake = 4869.8'
 Elev. Graded Ground at Location Stake = 4866.1'

UINTAH ENGINEERING & LAND SURVEYING
 85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017


EOG RESOURCES, INC.

TYPICAL CROSS SECTIONS FOR

CWU #655-6


SECTION 6, T9S, R23E, S.L.B.&M.

2084' FSL 434' FWL



1" = 20'
X-Section Scale
1" = 50'


DATE: 01-21-04
Drawn By: D.COX



APPROXIMATE YARDAGES

(6") Topsoil Stripping	=	1,430 Cu. Yds.
Remaining Location	=	7,500 Cu. Yds.
TOTAL CUT	=	8,930 CU.YDS.
FILL	=	5,550 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	=	3,090 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	3,090 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	0 Cu. Yds.



LEGEND:

○ PROPOSED LOCATION

EOG RESOURCES, INC.


CWU #655-6
 SECTION 6, T9S, R23E, S.L.B.&M.
 2084' FSL 434' FWL

U E L S
 Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC 01 22 04
MAP MONTH DAY YEAR
 SCALE: 1:100,000 DRAWN BY: P.M. REVISED: 00-00-00





LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD




EOG RESOURCES, INC.

CWU #655-6
SECTION 6, T9S, R23E, S.L.B.&M.
2084' FSL 434' FWL

UELS Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP	01	22	04	B TOPO
	MONTH	DAY	YEAR	
SCALE: 1" = 2000'		DRAWN BY: P.M.		REVISED: 00-00-00



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED


EOG RESOURCES, INC.

CWU #655-6
SECTION 6, T9S, R23E, S.L.B.&M.
2084' FSL 434' FWL

U&L
Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC 01 22 04
MAP MONTH DAY YEAR
 SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 00-00-00 **C**
 TOPO



APPROXIMATE TOTAL PIPELINE DISTANCE = 1,362' +/-

LEGEND:

-  PROPOSED ACCESS ROAD
-  EXISTING PIPELINE
-  PROPOSED PIPELINE

EOG RESOURCES, INC.

CWU #655-6
SECTION 6, T9S, R23E, S.L.B.&M.
2084' FSL 434' FWL



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP
01 22 04
MONTH DAY YEAR
SCALE: 1" = 1000' DRAWN BY: P.M. REVISED: 00-00-00



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 02/26/2004

API NO. ASSIGNED: 43-047-35553

WELL NAME: CWU 655-6
OPERATOR: EOG RESOURCES INC (N9550)
CONTACT: ED TROTTER

PHONE NUMBER: 435-789-4120

PROPOSED LOCATION:

NWSW 06 090S 230E
SURFACE: 2084 FSL 0434 FWL
BOTTOM: 2084 FSL 0434 FWL
UINTAH
NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal
LEASE NUMBER: U-01304
SURFACE OWNER: 1 - Federal
PROPOSED FORMATION: WSTC
COALBED METHANE WELL? NO

LATITUDE: 40.06366
LONGITUDE: 109.37649

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. NM-2308)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 49-1501)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)


LOCATION AND SITING:

- R649-2-3.
- Unit CHAPITA WELLS
- R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit
Board Cause No: 17A-P
Eff Date: 8-10-1999
Siting: Suspends General Siting
- R649-3-11. Directional Drill

COMMENTS:

STIPULATIONS:

1- Federal approval




OPERATOR: EOG RESOURCES INC (N9550)

SEC. 6 T.9S, R.23E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

CAUSE: 179-8 / 8-10-1999



Utah Oil Gas and Mining

Wells

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED



PREPARED BY: DIANA WHITNEY
DATE: 27-FEBRUARY-2004

002

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

February 27, 2004

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2004 Plan of Development Chapita Wells Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2004 within the Chapita Wells Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
------	-----------	----------

(Proposed PZ Mesaverde)

43-047-35525	CWU 881-16 Sec 16 T09S R22E 2023 FSL 0766 FEL
43-047-35526	CWU 892-22 Sec 22 T09S R22E 2151 FSL 0707 FEL
43-047-35527	CWU 909-23 Sec 23 T09S R22E 0678 FNL 1995 FWL
43-047-35528	CWU 908-23 Sec 23 T09S R22E 0805 FNL 1277 FEL
43-047-35529	CWU 910-23 Sec 23 T09S R22E 1852 FSL 0575 FEL
43-047-35530	CWU 907-23 Sec 23 T09S R22E 1882 FSL 2025 FWL
43-047-35531	CWU 901-24 Sec 24 T09S R22E 1990 FNL 0482 FWL
43-047-35532	CWU 913-24 Sec 24 T09S R22E 2177 FSL 1930 FWL
43-047-35533	CWU 899-24 Sec 24 T09S R22E 0692 FSL 0333 FWL
43-047-35534	CWU 912-25 Sec 25 T09S R22E 0370 FNL 0381 FEL
43-047-35535	CWU 911-25 Sec 25 T09S R22E 0660 FNL 1971 FWL
43-047-35537	CWU 896-25 Sec 25 T09S R22E 1026 FSL 0502 FWL
43-047-35538	CWU 897-25 Sec 25 T09S R22E 2105 FNL 1142 FWL
43-047-35539	CWU 903-25 Sec 25 T09S R22E 1877 FSL 2060 FWL
43-047-35540	CWU 904-26 Sec 26 T09S R22E 0518 FSL 1624 FEL
43-047-35541	CWU 906-26 Sec 26 T09S R22E 1606 FSL 0711 FEL
43-047-35542	CWU 914-26 Sec 26 T09S R22E 0403 FNL 1458 FWL
43-047-35543	CWU 905-26 Sec 26 T09S R22E 0495 FNL 0468 FEL
43-047-35544	CWU 895-26 Sec 26 T09S R22E 2331 FSL 2129 FEL
43-047-35545	CWU 893-27 Sec 27 T09S R22E 1189 FNL 1172 FEL
43-047-35548	CWU 902-19 Sec 19 T09S R23E 0940 FSL 1097 FWL

page 2

(Proposed PZ Wasatch)

43-047-35536 CWU 652-25 Sec 25 T09S R22E 1956 FSL 1949 FEL
43-047-35547 CWU 651-6 Sec 6 T09S R23E 0820 FNL 0662 FEL
43-047-35553 CWU 655-6 Sec 6 T09S R23E 2084 FSL 0434 FWL
43-047-35554 CWU 653-1 Sec 1 T09S R22E 1827 FSL 0830 FEL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Chapita Wells Unit
Division of Oil Gas and Mining
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:2-27-04



State of Utah

Department of
Natural Resources

Division of
Oil, Gas & Mining

ROBERT L. MORGAN
Executive Director

LOWELL P. BRAXTON
Division Director

MICHAEL O. LEAVITT
Governor

OLENE S. WALKER
Lieutenant Governor

March 1, 2004

EOG Resources, Inc.
P O Box 1815
Vernal, UT 84078

Re: Chapita Wells Unit 655-6 Well, 2084' FSL, 434' FWL, NW SW, Sec. 6,
T. 9 South, R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-35553.

Sincerely,

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: EOG Resources, Inc.

Well Name & Number Chapita Wells Unit 655-6

API Number: 43-047-35553

Lease: U-01304

Location: NW SW **Sec.** 6 **T.** 9 South **R.** 23 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

006

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: DRILL REENTER

1b. Type of Well: Oil Well Gas Well Other Single Zone Multiple Zone

2. Name of Operator
EOG RESOURCES, INC.

3a. Address **P.O. BOX 1815
VERNAL, UT 84078**

3b. Phone No. (Include area code)
(435)789-0790

4. Location of Well (Report location clearly and in accordance with any State requirements. *)

At surface **2084' FSL, 434' FWL** **NW/SW**

At proposed prod. Zone

14. Distance in miles and direction from nearest town or post office*
18 MILES SOUTHEAST OF OURAY, UTAH

5. Lease Serial No.
U-01304

6. If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.
CHAPITA WELLS UNIT

8. Lease Name and Well No.
CHAPITA WELLS UNIT 655-6

9. API Well No.
43-047-35553

10. Field and Pool, or Exploratory
NATURAL BUTTES

11. Sec., T., R., M., or Blk. and Survey or Area
**SEC. 6, T9S, R23E,
S.L.B.&M.**

12. County or Parish **UINTAH** 13. State **UTAH**

15. Distance from proposed* location to nearest property or lease line, ft. **434'**
(Also to nearest drig. Unit line, if any)

16. No. of Acres in lease
2451

17. Spacing Unit dedicated to this well

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. See Topo Map C

19. Proposed Depth
6775'

20. BLM BIA Bond No. on file
NM-2308

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
4866.1 FEET GRADED GROUND

22. Approximate date work will start*
UPON APPROVAL


23. Estimated duration
45 DAYS

24. Attachments

Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:


- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 
Title **Agent**

Name (Printed/Typed)
Ed Trotter

**RECEIVED
AUG 30 2004**

Date
February 23, 2004

Approved by (Signature) 
Title **Assistant Field Manager
Mineral Resources**

Name (Printed/Typed) **EDWIN J FORSMAN**
Office **DIV. OF OIL, GAS & MINING**

Date
8/20/04

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of Approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

NOTICE OF APPROVAL
UDOGM

CONDITIONS OF APPROVAL ATTACHED

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: EOG Resources, Inc.
Well Name & Number: CWU 655-6
Lease Number: U-01304
API Number: 43-047-35553
Location: Lot 6 Sec. 6 T.9S R. 23E
Agreement: Chapita Wells Unit

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to John Mayers of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 5M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint. Surface casing setting depths are based on ground level elevations only.

All casing strings below the conductor shall be pressure tested to 0.22 psi/ft of casing string length or 1500 psi, whichever is greater but not to exceed 70% of the minimum internal yield.

As a minimum requirement, the cement behind to production casing must extend at least 200' above the base of usable water which has been identified at ±1640'

If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

A cement bond log (CBL) will be run from the production casing shoe to top of the cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic

summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

Please submit to this office, in LAS format, an electronic copy of all logs run on this well. This submission will replace the requirement for submittal of paper logs to the BLM.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Written notification of such must be submitted to this office not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared

without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5(d) shall be submitted to the appropriate Field Office within 60 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (1).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergencies, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries and tested for meter accuracy at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well

which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874
Petroleum Engineer

Kirk Fleetwood (435) 828-7875
Petroleum Engineer

BLM FAX Machine (435) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: EOG Resources Inc..

API Number: 43-047-35553

Well Name & Number: CWU 655-6

Lease number: UTU-01304

Location: NWSW Sec, 6 T.9S. R. 23E.

Surface Ownership: BLM

Date NOS Received: 2/9/04

Date APD Received: 2/24/04

Conditions for Approval are in the APD

007

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:
U-01304

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
CHAPITA WELLS UNIT

8. WELL NAME and NUMBER:
CHAPITA WELLS UNIT 655-6

9. API NUMBER:
4304735553

10. FIELD AND POOL, OR WILDCAT:
NATURAL BUTTES

1. TYPE OF WELL OIL WELL GAS WELL OTHER _____

2. NAME OF OPERATOR:
EOG RESOURCES, INC.

3. ADDRESS OF OPERATOR:
P.O. BOX 1910 CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:
(435) 789-4120

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2084' FSL, 434' FWL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 6 9S 23E

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT* (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. requests authorization to change the TD on this well to 7785' and to revise the drilling procedure on the subject well. These changes include changes in the casing, cement, float equipment, and mud program. A revised drilling plan is attached.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 11-09-04
By: [Signature]

Federal Approval of this
Action is Necessary

RECEIVED

NOV 08 2004

DIV. OF OIL, GAS & MINING

COPY SENT TO OPERATOR
Date: 11-10-04
Initials: CHO

NAME (PLEASE PRINT) Ed Trotter

TITLE Agent

SIGNATURE [Signature]

DATE 11/3/2004

(This space for State use only)

EIGHT POINT PLAN

CHAPITA WELLS UNIT 655-6
NW/SW, SEC. 6, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River	1,943'
Wasatch	4,988'
Chapita Wells	5,639'
Buck Canyon	6,300'
North Horn	6,938'
Island	7,375'
KMV Price River	7,586'

EST. TD: 7,785'

Anticipated BHP 3400 PSI

3. PRESSURE CONTROL EQUIPMENT: 3,000 PSI - BOP Schematic Diagram attached.

4. CASING PROGRAM:

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>RATING FACTOR</u>		
							<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
12 1/4"	0' - 500' +/--KB	500' +/-	9 5/8"	36.0#	J-55	STC	2020 PSI	3520 PSI	394,000#
7 7/8"	500' - TD +/--KB	7,785' +/-	4 1/2"	11.6 #	J-55	LTC	4960 PSI	5350 PSI	162,000#

All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0-500' Below GL):

Guide Shoe

Insert Baffle

Wooden wiper plug

Centralizers: 1 - 5-10' above shoe, every collar for next 3 joints (4 total).

Production Hole Procedure (500'-TD):

Texas-Pattern shoe, short casing shoe joint ($\pm 20'$), Float Collar, and balance of casing to surface. Run short casing joint ($< 38'$) at $\pm 3,900'$ (1,000' above projected top of Wasatch). Centralize 5' above shoe on joint #1, top of joint #2, then every 4th joint to $\pm 4,500'$ (400' above Wasatch top - 15 total). Thread lock shoe, top and bottom of FC, and top of 2nd joint.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 655-6 NW/SW, SEC. 6, T9S, R23E, S.L.B.&M. UINTAH COUNTY, UTAH

6. MUD PROGRAM:

Surface Hole Procedure (0-500' below GL):

500' - 1,700': Water (circulate through reserve pit). Anco-Drill sweeps for hole cleaning, Paper sweeps to seal off loss zones. Add LIME to reserve pit to keep clear.

Production Hole Procedure (500'-TD):

1,700' - 4,900': Continue as above as far as possible. Should it become necessary to trip for a bit prior to reaching TD, either slug drill pipe and fill hole with brine or with 9.2 ppg mud (pre-mixed in rig mud tanks) to control gas. Once back on bottom after trip, turn flow back and re-circulate through reserve pit to resume drilling ahead. Stay on as clear of fluid as long as possible. Try to control any fluid losses if drilling on clear fluid with paper LCM. Add LIME and Gyp if needed to control alkalinites.

4,900' - TD: Continue sweeping hole with Anco-Drill for hole cleaning. Again, should it become necessary to trip for a bit prior to reaching TD, either slug drill pipe and fill hole with brine or with 9.2 ppg mud (pre-mixed in rig mud tanks) to control gas. Once back on bottom after trip, turn flow back and re-circulate through reserve pit to resume drilling ahead. Stay on as clear of fluid as long as possible. Increase Anco-Drill sweep frequency as you near TD in preparation to logging and running casing. Be alert at all times while drilling the Wasatch on water for any signs of hole sloughing (i.e. tight connections, fill, etc.). Should sloughing be detected, immediately mud up the hole. If mud-up becomes necessary to log, run casing, for hole sloughing or to control water and gas flows, mix Gel, Anco-Drill and Aqua-Pac if chloride content of mud will allow or SALT GEL and STARCH if chloride content is high. When mudding up, add 6% LCM (mixture of Cedar Fiber, Paper, Cottonseed Hulls and Sawdust) to control losses.

7. VARIANCE REQUESTS:

- A. EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line (Where possible, a straight run blooie line will be used).
- B. EOG Resources, Inc. requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).
- C. EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be 75' in length.

8. EVALUATION PROGRAM:

Logs: Open Hole Logging - Schlumberger Platform Express TD to Surface Casing

EIGHT POINT PLAN

CHAPITA WELLS UNIT 655-6
NW/SW, SEC. 6, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

9. CEMENT PROGRAM:

Surface Hole Procedure (0-500' Below GL)

Lead: 200 sks. (100% excess volume) Class 'G' cement with 2% S1 (CaCl₂) & 0.25 pps D29 (cellophane flakes), mixed at 15.8 ppg, 1.15. ft³/sk., 4.95 gps water.

Top Out: Top out with Class 'G' cement with 2% S1 (CaCl₂) in mix water, 15.8 ppg,, 1.15. ft³/sk., 4.95 gps via 1" tubing set at 25' if needed.

Production Hole Procedure (500' to TD)

Lead: 100 sks: Class 'G' lead cement with 5% D44 (Salt), 12% D20 (Bentonite), 1% D79% (Extender), 0.25% D112 (Fluid Loss Additive), 0.2% D46 (Anti-Foamer) & 0.25 pps D29 (Cellophane flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 250 sks: 50:50 Poz G w/ 2% D20 (Bentonite), 10% D44 (Salt), mixed at 14.1 ppg, 1.35 cu. ft./sk., 5.0 gps water. 50:50 Poz G w/ 2% D20 (Bentonite), 10% D44 (Salt), mixed at 14.1 ppg, 1.35 ft³/sk., 5.0 gps water.

10. ABNORMAL CONDITIONS:

PRODUCTION HOLE (500'-TD)

Potential Problems: Lost circulation, asphaltic, black oil flows, large Trona water flows and gas flows may be encountered in the Green River, beginning at ± 1,900'. Other wells in the general area of the **CWU 655-06** (all drilled with air/mist or aerated water) reported problems with sloughing formation in the Wasatch while attempting to mud up for logs or to run casing.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

3000 PSIG DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
 CASING FLANGE IS 11" 3000 PSIG RATED.
 BOPE 11" 3000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 3000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure-tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 3000 psig BOPE specifications.



DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: EOG RESOURCES INCWell Name: CWU 655-6Api No: 43-047-35553 Lease Type: FEDERALSection 06 Township 09S Range 23E County UINTAHDrilling Contractor PETE MARTIN'S RIG # BUCKET**SPUDDED:**Date 02/28/05Time 11:00 AMHow DRY**Drilling will commence:** _____Reported by DALL COOKTelephone # 1-435-828-3630Date 02/28/2005 Signed CHD

009

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG RESOURCES, INC. Operator Account Number: N 9550
 Address: P.O. BOX 250
city BIG PINEY
state WY zip 83113 Phone Number: (307) 276-3330

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304735553	CHAPITA WELLS UNIT 655-6		NWSW	6	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	14583	2/28/2005			3/3/05	
Comments: <i>PRRV = MURD</i> <i>NO PA</i>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A							
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Kaylena R. Gardner

Name (Please Print)

Kaylena R. Gardner
Signature

Regulatory Assistant

3/1/2005
Date

RECEIVED

MAR 01 2005

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-01304	
2. Name of Operator EOG RESOURCES, INC.		6. If Indian, Allottee or Tribe Name	
3a. Address P.O. BOX 250 BIG PINEY, WY 83113		7. If Unit or CA/Agreement, Name and/or No. CHAPITA WELLS UNI	
3b. Phone No. (include area code) Ph: 307-276-3331 Ext: 4842		8. Well Name and No. CHAPITA WELLS UNIT 655-6	
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 6 T9S R23E NWSW 2084FSL 434FWL 40.06361 N Lat, 109.37666 W Lon		9. API Well No. 43-047-35553	
		10. Field and Pool, or Exploratory NATURAL BUTTES	
		11. County or Parish, and State UINTAH COUNTY, UT	

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc. requests authorization for disposal of produced water from the referenced well to any of the following locations.

1. Natural Buttes Unit 21-20B SWD
2. Ace Disposal
3. RN Industries

EOG Resources, Inc. operates under Nationwide Bond #2308

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED
MAR 04 2005
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct. Electronic Submission #54633 verified by the BLM Well Information System For EOG RESOURCES, INC., sent to the Vernal	
Name (Printed/Typed) KAYLENE R GARDNER	Title REGULATORY ASSISTANT
Signature (Electronic Submission)	Date 03/01/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____	Title _____	Date _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

011

5. Lease Serial No.
U-01304

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNI

8. Well Name and No.
CHAPITA WELLS UNIT 655-06

9. API Well No.
43-047-35553

10. Field and Pool, or Exploratory
NATURAL BUTTES

11. County or Parish, and State
UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
EOG RESOURCES, INC. Contact: KAYLENE R GARDNER
E-Mail: kaylene_gardner@eogresources.com

3a. Address
P.O. BOX 250
BIG PINEY, WY 83113

3b. Phone No. (include area code)
Ph: 307-276-3331 Ext: 4842

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 6 T9S R23E NWSW 2084FSL 434FWL
40.06361 N Lat, 109.37666 W Lon

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Well Spud
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc. spud a 20" surface hole at the referenced location 2/28/2005 at 11:00 a.m. The contractor was Pete Martin's Bucket Rig. Dall Cook, representative for EOG, notified Kirk Fleetwood of the Vernal BLM office and Carol Daniels of the Utah Division of Oil Gas and Mining of the spud 2/28/2005 @ 8:30 a.m.

EOG Resources, Inc. operates under Nationwide Bond #2308

RECEIVED
MAR 04 2005

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.
Electronic Submission #54634 verified by the BLM Well Information System For EOG RESOURCES, INC., sent to the Vernal

Name (Printed/Typed) KAYLENE R GARDNER Title REGULATORY ASSISTANT

Signature (Electronic Submission) Date 03/01/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

6/30/05

Form 3160-5
(April 2004)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

012

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator **EOG RESOURCES, INC.**

3a. Address
P.O. BOX 250 Big Piney WY, 83113

3b. Phone No. (include area code)
307-276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SECTION 6, T9S, R23E NW/SW 2084 FSL 434 FWL 40.063614 LAT 109.376656 LON

5. Lease Serial No.
U-01304

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNIT

8. Well Name and No.
CHAPITA WELLS UNIT 655-6

9. API Well No.
43-047-35553

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other DRILLING
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	OPERATIONS
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Please see the attached well chronology report for drilling operations from 3/10/2005 - 3/24/2005.

RECEIVED
 MAR 28 2005
 DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) **Kaylene R. Gardner** Title **Regulatory Assistant**

Signature *[Signature]* Date **03/24/2005**

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

013

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator **EOG RESOURCES, INC.**

3a. Address
P.O. BOX 250 Big Piney WY, 83113

3b. Phone No. (include area code)
307-276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SECTION 6, T9S, R23E NW/SW 2084 FSL 434 FWL 40.063614 LAT 109.376656 LON

5. Lease Serial No.
U-01304

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNIT

8. Well Name and No.
CHAPITA WELLS UNIT 655-6

9. API Well No.
43-047-35553

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION				
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off	
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity	
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other DRILLING	
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	OPERATIONS	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal		

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Please see the attached well chronology report for completion operations from 3/24/2005 - 4/1/2005.

EOG Resources, Inc. operates under Nationwide Bond #2308

RECEIVED

APR 05 2005

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct
 Name (Printed/Typed) **Kaylene R. Gardner** Title **Regulatory Assistant**

Signature *[Handwritten Signature]* Date **04/01/2005**

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

06:45 07:00 0.25 SET WEAR BUSHING.
 07:00 09:30 2.5 MU BIT, DOG SUB & MTR. PU DCS. TAGGED CMT AT 460'.
 09:30 11:00 1.5 DRILL CEMENT/FLOAT EQUIPMENT 460' - 540'.

 11:00 11:30 0.5 DRILLED 540' - 596', RPM 50+75, 15-20K WOB, 112 FPH.
 11:30 11:45 0.25 INSTALLED ROTATING HEAD RUBBER.
 11:45 12:30 0.75 DRILLED 596' - 689', RPM 50+75, 20K WOB.
 12:30 13:00 0.5 SURVEY AT 609', .25 DEG.
 13:00 17:15 4.25 DRILLED 689' - 1187', RPM 50+75, 20-22K WOB, 117 FPH.
 17:15 17:45 0.5 SURVEY AT 1107', .5 DEG.
 17:45 22:15 4.5 DRILLED 1187' - 1688', RPM 50+75, 20-24K WOB, 111 FPH.
 22:15 22:45 0.5 SURVEY AT 1608', .25 DEG.
 22:45 03:45 5.0 DRILLED 1688' - 2188', RPM 50+75, 20-26K WOB, 100 FPH.
 03:45 04:15 0.5 SURVEY AT 2108', .25 DEG.
 04:15 06:00 1.75 DRILLED 2188' - 2339', RPM 50+75, 20-26K WOB, 86 FPH.

SAFETY MEETING: PU DCS/WERELINE SURVEYS/PU DP/MAKING CONNECTIONS
 TEMP 31 DEG

BGG 760-850U, CG 800-900U, HIGH GAS 6220U AT 2057'
 LITHOLOGY 60% SH, 35% SS, 5% LS

06:00 18.0 SPUD 7 7/8" SURFACE HOLE AT 11:00 HRS, 3/20/05.

03-22-2005 Reported By K. MELDER

Daily Costs: Drilling	Completion	Daily Total
Cum Costs: Drilling	Completion	Well Total
MD 4,579 TVD 4,578 Progress 2,240 Days 2 MW 8.4 Visc 26.0		
Formation :	PBTD : 0.0	Perf : PKR Depth : 0.0

Activity at Report Time: DRILLING

Start	End	Hrs	Activity Description
06:00	09:00	3.0	DRILLED 2339' - 2680', RPM 50+75, 22-26K WOB, 114 FPH.
09:00	09:30	0.5	SURVEY AT 2600', .25 DEG.
09:30	14:30	5.0	DRILLED 2680' - 3176', RPM 50+75, 23-25K WOB, 99 FPH.
14:30	15:00	0.5	SURVEY AT 3096', 1.25 DEG.
15:00	16:30	1.5	DRILLED 3176' - 3301', RPM 50+75, 23-25K WOB, 83 FPH.
16:30	17:00	0.5	SERVICED RIG. FUNCTION TESTED PIPE RAMS.
17:00	21:30	4.5	DRILLED 3301' - 3677', RPM 50+76, 23-25K WOB, 83 FPH, 3-5' FLARE.
21:30	22:00	0.5	SURVEY AT 3597', 2 DEG.
22:00	02:30	4.5	DRILLED 3677' - 4176', RPM 50+76, 23-25K WOB, 111 FPH, 4-6' FLARE.
02:30	03:00	0.5	SURVEY AT 4096', 1.75 DEG.
03:00	06:00	3.0	DRILLED 4176' - 4579', RPM 50+75, 23-25K WOB, 134 FPH.

SAFETY MEETING: LOCK OUT-TAG OUT/PICK DP OUT OF TUBS/FORKLIFT SAFETY
 TEMP 29 DEG

BGG 3500 - 400U, CG 4100-4300U, HIGH GAS 9005U AT 3050
LITHOLOGY 50% SS, 40% SH, 10% LS

03-23-2005 Reported By K. MELDER

Daily Costs: Drilling					Completion			Daily Total			
Cum Costs: Drilling					Completion			Well Total			
MD	6,166	TVD	6,164	Progress	1,407	Days	3	MW	8.5	Visc	26.0
Formation :	PBTD : 0.0				Perf :			PKR Depth : 0.0			

Activity at Report Time: DRILLING

Start	End	Hrs	Activity Description
06:00	07:00	1.0	DRILLED 4579' - 4673, RPM 50+75, 23-25K WOB, 97 FPH.
07:00	07:30	0.5	SURVEY AT 4596', 3 DEG.
07:30	11:00	3.5	DRILLED 4673' - 4954', RPM 60+75, 23-25K WOB, 80 FPH.
11:00	11:30	0.5	SERVICE RIG. FUNCTION TESTED PIPE RAMS. CHANGED OUT ROTATING HEAD RUBBER.
11:30	14:00	2.5	DRILLED 4954' - 5172', RPM 60+75, 23-25K WOB, 87 FPH. CLOSED IN PITS. STARTED MUD UP AT 5000'.
14:00	14:30	0.5	SURVEY AT 5092', MISS-RUN, CLOCK STOPPED.
14:30	15:00	0.5	DRILLED 5072' - 5204', RPM 60+75, 23-25K WOB.
15:00	15:30	0.5	SURVEY AT 5124', 2.25 DEG.
15:30	21:15	5.75	DRILLED 5204' - 5702', RPM 55+75, 23-25K WOB, 87 FPH.
21:15	22:00	0.75	SURVEY AT 5622', 2 DEG. CHECKED CROWN-O-MATIC.
22:00	06:00	8.0	DRILLED 5702' - 6166', RPM 55+75, 23-25K WOB, 58 FPH.

SAFETY MEETING: MAKING CONNECTIONS/TEAM WORK/SPIN CHAIN/TRIP HAZARDS
TEMP 40 DEG

BGG 930-1000U, CG 2100-2700U, HIGH GAS 4890U AT 5702'
LITHOLOGY 55% SH, 40% SS, 5% LS

03-24-2005 Reported By BRUCE TAYLOR

Daily Costs: Drilling					Completion			Daily Total			
Cum Costs: Drilling					Completion			Well Total			
MD	7,148	TVD	7,145	Progress	982	Days	4	MW	9.1	Visc	33.0
Formation :	PBTD : 0.0				Perf :			PKR Depth : 0.0			

Activity at Report Time: DRILLING

Start	End	Hrs	Activity Description
06:00	07:30	1.5	DRILL W/MOTOR, 6166' - 6228', 62', 41.3'/HR, 26/28K WOB, 55/73 RPM.
07:30	08:00	0.5	SURVEY @ 6148', 2 DEG.
08:00	12:30	4.5	DRILL 6228' TO 6507', 279', 62'/HR, 26/28K WOB, 55/73 RPM.
12:30	13:30	1.0	SERVICED RIG. FUNCTION TESTED PIPE RAMS. TIGHTENED U-BOLTS ON DRIVE SHAFTS.
13:30	17:00	3.5	DRILL 6507' TO 6693', 186', 53.1'/HR, 26/28K WOB, 55/73 RPM.
17:00	18:00	1.0	SUREVEY @ 6613', 2 DEG.
18:00	06:00	12.0	DRILL 6683' TO 7148', 465', 38.7'/HR, 26/28K WOB, 55/73 RPM.

SAFETY MEETING: PU PIPE FROM TUBS/MIX CHEMICAL/LOTO/PUMPS
TEMP 33 DEG

FORMATION NORTH HORN TOP @ 6904'

55% SS, 45% SH

BGG 50-700, CG 1500-2200, DTG 5526, HIGH GAS 5490 @ 6200'

03-25-2005 Reported By BRUCE TAYLOR

Daily Costs: Drilling				Completion				Daily Total			
Cum Costs: Drilling				Completion				Well Total			
MD	7,575	TVD	7,575	Progress	427	Days	5	MW	9.3	Visc	34.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		

Activity at Report Time: LD DP

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL W/MOTOR 7148' TO 7442', 294', 39.6'/HR, 26/28K WOB, 55/73 RPM.
13:30	14:00	0.5	SERVICED RIG. FUNCTION TESTED RAMS & HYDRIL.
14:00	18:00	4.0	DRILL 7442' TO 7575', 133', 33.2'/HR, 26/28K WOB, 55/73 RPM.
18:00	19:00	1.0	CIRCULATED BOTTOMS UP.
19:00	03:00	8.0	WIPER TRIP. STRAP OUT OF HOLE TO BHA. TIH. NO CORRECTION.
03:00	04:00	1.0	CIRCULATED BOTTOMS UP. RIG UP LAY DOWN MACHINE. HELD PRE-JOB SAFETY MEETING.
04:00	06:00	2.0	PULL OUT OF HOLE LAYING DOWN DRILL PIPE.

SAFETY MEETING: RIG SERVICE/HORSEPLAY/TRIP/LDDP

TEMP 33 DEG

NOTIFIED KIRK FLEETWOOD W/BLM IN VERNAL INTENT TO RUN/CEMENT PROD CSG AT 10:45 AM, 3/24/05

BGG 500-700, CG 1500-2200, STG 7960, HIGH GAS 7960' @ 7575'

LAST FORMATION: ISLAND @ 7308', 55% SS, 45% SH

03-26-2005 Reported By BRUCE TAYLOR

Daily Costs: Drilling				Completion				Daily Total			
Cum Costs: Drilling				Completion				Well Total			
MD	7,575	TVD	7,575	Progress	0	Days	6	MW	9.3	Visc	34.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		

Activity at Report Time: WO COMPLETION

Start	End	Hrs	Activity Description
06:00	11:00	5.0	FINISHED LD DP, BREAK KELLY, LAY DOWN BHA.
11:00	13:00	2.0	PULLED WEAR BUSHING. RIG UP FRANKS CSG CREW.
13:00	18:00	5.0	RUN 186 JTS 4 1/2", 11.6#, J-55, STC CASING AS FOLLOWS: FLOAT SHOE, 1 JT CASING, FLOAT COLLAR AT 7524', 88 JTS CASING, MARKER JT AT 3946', 97 JTS CASING, PUP JT, CASING HANGER, LANDING JT. LANDED CASING AT 7567' KB. RAN 15 CENTRALIZERS, 1-5' ABOVE SHOE, 1 ON FIRST JT THEN EVERY 4TH JT.
18:00	21:00	3.0	STUCK PIPE 20' OFF BOTTOM, PRESSURED UP TO 1000 PSI & PULLED 140K, PIPE CAME FREE. WASHED 20' TO BOTTOM. CIRCULATED BOTTOMS UP WITH RIG PUMP @ 100 SPM. LAY DOWN 1 JOINT, INSTALLED HANGER JOINT. RIG DOWN CASING CREW. TESTED PACK OFF TO 5000 PSI. RIG UP TO CEMENT THROUGH CASING VALVE.

21:00 00:00 3.0 SAFETY MEETING. RU SCHLUMBERGER. CEMENT WELL AS FOLLOWS: PUMPED 20 BBL MUD FLUSH, 20 BBL H2O SPACER, LEAD W/450 SXS "G" W/+12% D20, 1% D79+ .250% D112, .2% D046, .25 #/SX D029, 5% D044, MIXED AT 11 PPG, YIELD 3.91. TAIL W/850 SXS 50/50 POZ "G" W/+ 2% D020, .1% D046, .2% D167, .2% D065, MIXED AT 14.1 PPG, YIELD 1.29. DROPPED PLUG & DISPLACED W/116 BBL H2O TO BUMP PLUG WITH 2800 PSI @ 23:57 HRS. HAD FULL RETURNS THROUGHOUT JOB. BLED PSI, FLOATS HELD. RD SCHLUMBERGER.

00:00 02:00 2.0 CLEANED MUD TANKS. ND BOPE.

TRUCKS TO START MOVING THIS AM (3/26/05) TO THE CWU 645-01
MOVE 1800 GAL RIG FUEL TO NEXT WELL
TEMP 27 DEG

02:00 22.0 RELEASED RIG AT 02:00 HRS, 3/26/05.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

014

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator **EOG RESOURCES, INC.**

3a. Address
P.O. BOX 250 Big Piney WY, 83113

3b. Phone No. (include area code)
307-276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SECTION 6, T9S, R23E NW/SW 2084 FSL 434 FWL 40.063614 LAT 109.376656 LON

5. Lease Serial No.
U-01304

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNIT

8. Well Name and No.
CHAPITA WELLS UNIT 655-6

9. API Well No.
43-047-35553

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other DRILLING
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	OPERATIONS
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

TD reached 3/24/2005. Completion operations are scheduled to begin on or about 4/09/2005

EOG Resources, Inc. operates under Nationwide Bond #2308

RECEIVED

APR 11 2005


DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct
 Name (Printed/Typed)

Kaylene R. Gardner

Title **Regulatory Assistant**

Signature



Date

04/07/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

015

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator **EOG RESOURCES, INC.**

3a. Address
P.O. BOX 250 Big Piney WY, 83113

3b. Phone No. (include area code)
307-276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SECTION 6, T9S, R23E NW/SW 2084 FSL 434 FWL 40.063614 LAT 109.376656 LON

5. Lease Serial No.
U-01304

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNIT

8. Well Name and No.
CHAPITA WELLS UNIT 655-6

9. API Well No.
43-047-35553

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other DRILLING
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	OPERATIONS
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomplate in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Please see the attached well chronology report for completion operations from 4/4/2005 - 4/15/2005.

EOG Resources, Inc. operates under Nationwide Bond #2308

RECEIVED

APR 18 2005

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct
 Name (Printed/Typed)

Kaylene R. Gardner

Title **Regulatory Assistant**

Signature



Date

04/15/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

WELL CHRONOLOGY REPORT

Report Generated On: 04-15-2005

Well Name	CWU 655-06	Well Type	DEVG	Division	DENVER
Field	CHAPITA WELLS UNIT	API #	43-047-35553	Well Class	COMP
County, State	UINTAH, UT	Spud Date	03-20-2005	Class Date	
Tax Credit	N	TVD / MD	7,575/ 7,575	Property #	054639
Water Depth	0	Last CSG	4.5	Shoe TVD / MD	7,567/ 7,567
KB / GL Elev	4,884/ 4,866				
Location	Section 6, T9S, R23E, NWSW, 2084 FSL & 434 FWL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	50.0	NRI %	42.25

AFE No	302738	AFE Total		DHC / CWC			
Rig Contr	PATTERSON	Rig Name	PATTERSON #779	Start Date	03-10-2004	Release Date	03-26-2005

03-10-2004 Reported By

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA (changed depth) 2084' FSL & 434' FWL (NW/SW) SECTION 6, T9S, R23E UINTAH COUNTY, UTAH PATTERSON #779 OBJECTIVE: 7575' TD WASATCH DW/GAS CHAPITA WELLS UNIT PROSPECT LEASE: U-01304 ELEVATION: 4870' NAT GL, 4866' PREP GL, 4884' KB (18') EOG WI 50%, NRI 42.5%

03-17-2005 Reported By ED TROTTER

Daily Costs: Drilling		Completion		Daily Total							
Cum Costs: Drilling		Completion		Well Total							
MD	530	TVD	530	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

21:00 00:00 3.0 SAFETY MEETING. RU SCHLUMBERGER. CEMENT WELL AS FOLLOWS: PUMPED 20 BBL MUD FLUSH, 20 BBL H2O SPACER, LEAD W/450 SXS "G" W/+12% D20, 1% D79+ .250% D112, .2% D046, .25 #/SX D029, 5% D044, MIXED AT 11 PPG, YIELD 3.91. TAIL W/850 SXS 50/50 POZ "G" W/+ 2% D020, .1% D046, .2% D167, .2% D065, MIXED AT 14.1 PPG, YIELD 1.29. DROPPED PLUG & DISPLACED W/116 BBL H2O TO BUMP PLUG WITH 2800 PSI @ 23:57 HRS. HAD FULL RETURNS THROUGHOUT JOB. BLED PSI, FLOATS HELD. RD SCHLUMBERGER.

00:00 02:00 2.0 CLEANED MUD TANKS. ND BOPE.

TRUCKS TO START MOVING THIS AM (3/26/05) TO THE CWU 645-01
 MOVE 1800 GAL RIG FUEL TO NEXT WELL
 TEMP 27 DEG

02:00 22.0 RELEASED RIG AT 02:00 HRS, 3/26/05.
 CASING POINT COST \$295,476

24.0 LOG TOPS
 WASATCH 4985'
 CHAPITA WELLS 5628'
 BUCK CANYON 6286'
 NORTH HORN 6853'
 ISLAND 7322'

04-13-2005 Reported By SEARLE

DailyCosts: Drilling					Completion			Daily Total			
Cum Costs: Drilling					Completion			Well Total			
MD	7,575	TVD	7,575	Progress	0	Days	7	MW	0.0	Visc	0.0
Formation : WASATCH		PBTD : 7524.0		Perf : 5146-7442		PKR Depth : 0.0					

Activity at Report Time: FRAC WASATCH

Start	End	Hrs	Activity Description
06:30	19:00	12.5	3/29/2005: RU SCHLUMBERGER. RAN RST/CBL/VDL/CCL/GR FROM PBTD TO 300'. CEMENT TOP @ 340'. RD SCHLUMBERGER.

4/5/2005: NU 5M BOPE. PRESSURE TESTED CASING & BOPE TO 4500 PSIG.

4/12/2005: RU CUTTERS WIRELINE. PERFORATED ISLAND FROM 7402'-06' & 7438'-42' @ 3 SPF & 120°. RU SCHLUMBERGER. FRAC DOWN CASING WITH 833 GAL WF30 PRE-PAD, 1672 GAL YF130 PAD, 21,430 GAL YF130 WITH 107,049# 20/40 SAND @ 1-8 PPG. MTP 4459 PSIG. MTR 35 BPM. ATP 3397 PSIG. ATR 33.7 BPM. ISIP 2900 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 7364'. PERFORATED NH/ISLAND FROM 7263'-67' & 7327'-30' @ 3 SPF @ 120° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 833 GAL WF30 PRE-PAD, 1662 GAL YF130 PAD, 12,997 GAL YF130 WITH 62,377# 20/40 SAND @ 1-8 PPG. MTP 4427 PSIG. MTR 32.3 BPM. ATP 3833 PSIG. ATR 23.6 BPM. ISIP 2900 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 7230'. PERFORATED NORTH HORN FROM 7138'-41', 7187'-91' & 7200'-02' @ 3 SPF @ 120° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 829 GAL WF30 PRE-PAD, 1673 GAL YF130 PAD, 20,101 GAL YF130 WITH 96,673# 20/40 SAND @ 1-8 PPG. MTP 4345 PSIG. MTR 39.4 BPM. ATP 3060 PSIG. ATR 36.3 BPM. ISIP 2750 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 6896'. PERFORATED Ba FROM 6636'-39', 6683'-84', 6782'-84' & 6836'-39' @ 3 SPF @ 120° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 828 GAL WF30 PRE-PAD, 1667 GAL YF130 PAD, 13,050 GAL YF130 WITH 63,619# 20/40 SAND @ 1-8 PPG. MTP 3674 PSIG. MTR 31 BPM. ATP 2844 PSIG. ATR 30 BPM. ISIP 2100 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 6300'. PERFORATED Ca FROM 6184'-86', 6200'-04', 6217'-20' & 6250'-52' @ 3 SPF @ 120° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 824 GAL WF30 PRE-PAD, 1687 GAL YF130 PAD, 17,097 GAL YF130 WITH 91,508# 20/40 SAND @ 1-8 PPG. MTP 3561 PSIG. MTR 36.4 BPM. ATP 2482 PSIG. ATR 35.7 BPM. ISIP 1600 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 5950'. PERFORATED Ca FROM 5886'-90', 5903'-07' & 5912'-14' @ 3 SPF @ 120° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 828 GAL WF30 PRE-PAD, 1667 GAL YF130 PAD, 19,021 GAL YF130 WITH 107,517# 20/40 SAND @ 1-8 PPG. MTP 3196 PSIG. MTR 36.9 BPM. ATP 2189 PSIG. ATR 36.1 BPM. ISIP 1850 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 5790'. PERFORATED Ca FROM 5652'-55', 5665'-67', 5731'-33' & 5739'-42' @ 2 SPF @ 180° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 830 GAL WF30 PRE-PAD, 1672 GAL YF130 PAD, 19,689 GAL YF130 WITH 109,250# 20/40 SAND @ 1-8 PPG. MTP 4234 PSIG. MTR 35.6 BPM. ATP 3353 PSIG. ATR 33.4 BPM. ISIP 2150 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 5462'. PERFORATED Tw FROM 5357'-61', 5433'-35' & 5439'-42' @ 2 SPF @ 180° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 826 GAL WF30 PRE-PAD, 1675 GAL YF130 PAD, 18,284 GAL YF130 WITH 123,215# 20/40 SAND @ 1-8 PPG. MTP 3720 PSIG. MTR 35.3 BPM. ATP 3250 PSIG. ATR 34 BPM. ISIP 2800 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE FRAC PLUG @ 5250'. PERFORATED Tw FROM 5146'-48', 5162'-64', 5174'-76', 5196'-98' & 5209'-11' @ 2 SPF @ 180° DEG. RDWL. RU SCHLUMBERGER. FRAC DOWN CASING WITH 838 GAL WF30 PRE-PAD, 3323 GAL YF130 PAD, 24,219 GAL YF130 WITH 130,197# 20/40 SAND @ 1-8 PPG. MTP 4482 PSIG. MTR 36 BPM. ATP 3391 PSIG. ATR 28.8 BPM. ISIP 2400 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K COMPOSITE BRIDGE PLUG @ 5064'. RDWL. SDFN.

04-15-2005		Reported By		SEARLE							
DailyCosts: Drilling				Completion				Daily Total			
Cum Costs: Drilling				Completion				Well Total			
MD	7,575	TVD	7,575	Progress	0	Days	9	MW	0.0	Visc	0.0
Formation : WASATCH			PBTD : 7524.0			Perf : 5146-7442			PKR Depth : 0.0		
Activity at Report Time: CLEAN OUT											
Start	End	Hrs	Activity Description								
07:00	16:00	9.0	SITP 0 PSIG. SICP 1300 PSIG. CLEANED OUT & DRILLED OUT PLUGS @ 5250', 5462', 5790', 5950', 6300', 6896', 7230' & 7364'. CLEANED OUT TO PBTD. POH TO 7300'. FCP 200 PSIG ON 32/64" CHOKE. SIFN. RECOVERED 450 BLW DURING CLEAN OUT. 5177 BLWTR.								

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

016

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
 EOG RESOURCES, INC.

3a. Address
 P.O. BOX 250 Big Piney WY, 83113

3b. Phone No. (include area code)
 307-276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
 SECTION 6, T9S, R23E NW/SW 2084 FSL 434 FWL 40.063614 LAT 109.376656 LON

5. Lease Serial No.
 U-01304

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
 CHAPITA WELLS UNIT

8. Well Name and No.
 CHAPITA WELLS UNIT 655-6

9. API Well No.
 43-047-35553

10. Field and Pool, or Exploratory Area
 NATURAL BUTTES

11. County or Parish, State
 Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other DRILLING
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	OPERATIONS
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BLA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomplate in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

INITIAL PRODUCTION: The referenced well was turned to sales at 11:30 a.m., 4/25/2005 through Questar meter # 6702 on a 12/64" choke. Opening pressure, FTP 1800 psig, CP 2300 psig.


EOG Resources, Inc. operates under Nationwide Bond #2308

14. I hereby certify that the foregoing is true and correct
 Name (Printed/Typed)

Kaylene R. Gardner

Title Regulatory Assistant

Signature



Date

04/26/2005

RECEIVED

APR 28 2005

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: March 31, 2007

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well Oil Well Gas Well Dry Other
 b. Type of Completion: New Well Work Over Deepen Plug Back Diff. Resvr.,
 Other _____

5. Lease Serial No.
U-01304

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.
CHAPITA WELLS UNIT

2. Name of Operator **EOG RESOURCES, INC.**

8. Lease Name and Well No.
CWU 655-06

3. Address **P.O. Box 250
Big Piney, WY 83113**

3a. Phone No. (include area code)
307-276-3331

9. AFI Well No.
43-047-35553

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface **NWSW 2084 FSL 434 FWL 40.06361 LAT 109.376656 LON**

At top prod. interval reported below **SAME**

At total depth **SAME**

10. Field and Pool, or Exploratory
NATURAL BUTTES/WASATC

11. Sec., T., R., M., on Block and
Survey or Area **6, T9S, R23E**

12. County or Parish **UINTAH** 13. State
UT

14. Date Spudded
02/28/2005

15. Date T.D. Reached
03/24/2005

16. Date Completed **04/25/2005**
 D & A Ready to Prod.

17. Elevations (DF, RKB, RT, GL)*
4884 KB

18. Total Depth: MD **7575**
TVD

19. Plug Back T.D.: MD **7524**
TVD

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)

RST/CBL/VDL/CCL/GR

22. Was well cored? No Yes (Submit analysis)
Was DST run? No Yes (Submit report)
Directional Survey? No Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4	9-5/8	J-55	36#	0-540		235			
7-7/8	4-1/2	J-55	11.6#	0-7567		1300			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-3/8	7445							

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) WASATCH	5146	7442	7402-7442		3/SPF	
B)			7263-7330		3/SPF	
C)			7138-7202		3/SPF	
D)			6636-6839		3/SPF	

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
7402-7442	570 BBLs GELLED WATER & 107,049 # 20/40 SAND
7263-7330	369 BBLs GELLED WATER & 62,377 # 20/40 SAND
7138-7202	538 BBLs GELLED WATER & 96,673 # 20/40 SAND
6636-6839	370 BBLs GELLED WATER & 63,619 # 20/40 SAND

RECEIVED

JUN 06 2005

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
04/25/2005	05/01/2005	24	→	19	966	25			OW. OF OIL, GAS & MINING FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. SI	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
12/64	2100	2200	→	19	966	25		PRODUCING GAS WELL	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. SI	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
	SI		→						

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)

SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
WASATCH	5146	7442		WASATCH	4985
				CHAPITA WELLS	5628
				BUCK CANYON	6286
				NORTH HORN	6853
				ISLAND	7322

32. Additional remarks (include plugging procedure):

SEE ATTACHED SHEET.


33. Indicate which items have been attached by placing a check in the appropriate boxes:

- Electrical/Mechanical Logs (1 full set req'd.)
 Geologic Report
 DST Report
 Directional Survey
 Sundry Notice for plugging and cement verification
 Core Analysis
 Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Keylene R. Gardner

Title Regulatory Assistant

Signature 

Date 06/02/2005

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

ADDITIONAL REMARKS (CONTINUED):

TURNED TO SALES THROUGH QUESTAR METER #6702. One 300 bbl tank # 80581V is on location.

27. PERFORATION RECORD

6184-6252	3/ SPF
5886-5914	3/SPF
5652-5742	2/SPF
5357-5442	2/SPF
5146-5211	2/SPF

28. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.

6184-6252	467 BBLS GELLED WATER & 91,508 # 20/40 SAND
5886-5914	512 BBLS GELLED WATER & 107,517 # 20/40 SAND
5652-5742	528 BBLS GELLED WATER & 109,250 # 20/40 SAND
5357-5442	495 BBLS GELLED WATER & 123,215 # 20/40 SAND
5146-5211	674 BBLS GELLED WATER & 130,197 # 20/40 SAND

Perforated the Island from 7402-06' & 7438-42' w/3 SPF.

Perforated the North Horn/Island from 7263-67' & 7327-30' w/3 SPF.

Perforated the North Horn from 7138-41', 7187-91' & 7200-02' w/3 SPF.

Perforated the Ba from 6636-39', 6683-84', 6782-84' & 6836-39' w/3 SPF.

Perforated the Ca from 6184-86', 6200-04', 6217-20' & 6250-52 w/3 SPF.

Perforated the Ca from 5886-90', 5903-07' & 5912-14' w/3 SPF.

Perforated the Ca from 5652-55', 5665-67', 5731-33' & 5739-42' w/2 SPF.

Perforated the Tw from 5357-61', 5433-35' & 5739-42' w/2 SPF.

Perforated the Tw from 5146-48, 5162-64', 5174-76', 5196-98' & 5209-11' w/2 SPF.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM

Operator: EOG RESOURCES Operator Account Number: N 9560
 Address: P.O. BOX 1815
city VERNAL
state UT zip 84078 Phone Number: (435) 781-9111

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-35542	CHAPITA WELLS UNIT 914-26		NENW	26	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
C	14515	13650				4/12/06	
Comments: CHANGE TO PARTICIPATING AREA <i>MVRD</i> PER BLM EFFECTIVE 6/1/2005 <i>-K</i>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-35553	CHAPITA WELLS UNIT 856-6		NWSW	6	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
C	14583	4905				4/12/06	
Comments: CHANGE TO PARTICIPATING AREA <i>WSTC</i> PER BLM EFFECTIVE 2/1/2006 <i>-K</i>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-35579	CHAPITA WELLS UNIT 862-32		SWSW	32	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
C	14678	14091				4/12/06	
Comments: CHANGE TO PARTICIPATING AREA <i>MVRD</i> PER BLM EFFECTIVE 7/1/2005 <i>-K</i>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Kaylene R. Gardner

Name (Please Print)

Signature

Regulatory Assistant

Title

4/10/2006

Date

(5/2000)

RECEIVED

APR 11 2006

DIV. OF OIL, GAS & MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

CERTIFIED MAIL—Return Receipt Requested

FEB 23 2006

EOG Resources, Inc.
Attn: Debbie Spears
600 17th Street, Suite 1100N
Denver, Colorado 80202

Princeton Resources Ltd.
P.O. Box 888
Littleton, CO 80160-0888

Re: 3rd Revision of the
Consolidated Wasatch Formation PA "B-C-D-E"
Chapita Wells Unit
Uintah County, Utah

Gentlemen:

The 3rd Revision of the Consolidated Wasatch Formation PA "B-C-D-E", Chapita Wells Unit, CRS No. UTU63013B, AFS No. 892000905B, is hereby approved effective as of April 1, 2005, pursuant to Section 11 of the Chapita Wells Unit Agreement, Uintah County, Utah.

The 3rd Revision of the Consolidated Wasatch Formation PA "B-C-D-E" results in an addition of 77.69 acres to the participating area for a total of 12,895.82 acres and is based upon the completion of Well No. 655-6, API No. 43-047-35553, located in Lot 6 of Section 6, Township 9 South, Range 23 East, SLM&B, Federal Unit Tract No. 15, Lease No. UTU01304, as being a well capable of producing unitized substances in paying quantities.

Copies of the approved request are being distributed to the appropriate federal agencies and one copy is returned herewith. Please advise all interested parties of the approval of the 3rd Revision of the Consolidated Wasatch Formation PA "B-C-D-E", Chapita Wells Unit, and the effective date.

RECEIVED

FEB 27 2006

U.S. DEPT. OF OIL, GAS & MINING

You have the right to request a State Director Review of our decision as specified in 43 CFR 3165.3. Such request including all supporting documentation, must be filed in writing within twenty (20) business days of this notice to State Director (U-920), Bureau of Land Management, P.O. Box 45155, Salt Lake City, Utah 84145-0155. As stated in the regulations at 43 CFR 3165.3(e), a request for State Director Review does not automatically suspend the decision.

Sincerely,

/s/ Douglas F. Cook

Douglas F. Cook
Chief, Branch of Fluid Minerals

bcc: Division of Oil, Gas & Mining
SITLA
Chapita Wells Unit w/enclosure
MMS - Data Management Division (Attn: James Sykes)
Field Manager - Vernal w/enclosure
Agr. Sec. Chron.
Reading File
Central Files
MCoulthard

UT922:TATHOMPSON:tt:2/23/06