



Enduring Resources

475 17th Street Suite 1500 Denver Colorado 80202
Telephone 303 573-1222 Fax 303 573 0461

January 17, 2006

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, Utah 84114-5801

Attn.: Ms. Diana Whitney

RE: Asphalt Wash #10-23-31-33
Surface Location: NENE Sec. 33-T10S-R23E
725' FNL – 859' FEL
BH Location: NWNE Sec. 33-T10S-R23E
660' FNL – 1,980' FEL
Uintah County, Utah
Lease Serial No.: UTU-073451

Dear Ms. Whitney:

Enclosed is an original application to drill concerning the above-referenced proposed well. This information was also submitted to the Bureau of Land Management.

Enduring Resources, LLC is requesting the Utah Division of Oil, Gas and Mining to hold this application and all future information as confidential.

If any questions arise or additional information is required, please contact me at 303-350-5114.

Very truly yours,

ENDURING RESOURCES, LLC

Alvin R. (Al) Arlian
Landman-Regulatory Specialist

ara
Enclosures:

RECEIVED

JAN 20 2006

DIV. OF OIL, GAS & MINING

ENDURING RESOURCES, LLC

425 Seventeenth Street, Suite 1500

Denver, Colorado 80202

Telephone: 303-573-1222

Facsimile: 303-573-0461

January 17, 2006

State of Utah
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

Attention: Ms. Diana Whitney

**RE: Request for Exception Well Location
Asphalt Wash #10-23-31-33**
Surface Location: NENE Sec. 33-T10S-R23E
725' FNL-859' FEL
BH Location: NWNE Sec. 33-T10S-R23E
660' FNL-1,980' FEL
Uintah County, Utah
Lease Serial No.: UTU-073451

Dear Ms. Whitney:

Enduring Resources, LLC ("ERLLC") is the only leasehold interest owner within 460 feet of any part of the above-referenced proposed well's proposed directional well bore.

1. The subject proposed well will be drilled from the Asphalt Wash #10-23-41-33 pad and the surface locations of the Asphalt Wash 10-23-41-33, Asphalt Wash 10-23-24-42 and Asphalt Wash 10-23-31-33, are each only 25 feet apart.
2. ERLLC is the only leasehold interest owner within the NE of Sec 33, therefore,
 - A. ERLLC grants itself permission to directionally drill the subject well(s), and
 - B. ERLLC also grants itself permission for exception well(s)' surface locations.

In the event there are any other outstanding matters preventing these APD's from being approved, please let me know at your earliest convenience, 303-350-5114 (aarlian@enduringresources.com).

Very truly yours

ENDURING RESOURCES, LLC



Alvin R. (Al) Arlian
Landman-Regulatory Specialist

ara/

RECEIVED

JAN 20 2006

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. MINERAL LEASE NO: UTU-73451	6. SURFACE: Federal
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT OR CA AGREEMENT NAME:	
2. NAME OF OPERATOR: Enduring Resources, LLC		9. WELL NAME and NUMBER: Asphalt Wash 10-23-31-33	
3. ADDRESS OF OPERATOR: 475 17th St., Ste 1500 CITY Denver STATE CO ZIP 80220		PHONE NUMBER: (303) 350-5114	10. FIELD AND POOL, OR WILDCAT: Undesignated Natural Bures
4. LOCATION OF WELL (FOOTAGES) 643183x 4418976y 39.910672 -109.324863 AT SURFACE: 725' FNL - 859' FEL NENE AT PROPOSED PRODUCING ZONE: 660' FNL - 1,980' FEL NWNE 642841x 4418989y 39.910845 -109.328862		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNE 33 10S 23E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 75.7 miles southeasterly from Vernal, UT		12. COUNTY: Uintah	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 725'	16. NUMBER OF ACRES IN LEASE: 600	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 acres	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 25' Surface - 1,220' BHL	19. PROPOSED DEPTH: 7,370	20. BOND DESCRIPTION: RLB0008031	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5141' KB-RT	22. APPROXIMATE DATE WORK WILL START: 4/1/2006	23. ESTIMATED DURATION: 20 days	

24. **PROPOSED CASING AND CEMENTING PROGRAM**

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
20"	14" line pipe	40	3 yards	Ready Mix	
11"	8-5/8" J-55 24#	2,000	Premium Lead	138 sxs	3.50 11.1
			Premium Tail	138 sxs	1.15 15.8
7-7/8"	4-1/2" N-80 11.6#	7,370	Class G	87 sxs	3.91 11.0
			50/50 Poz Class G	852 sxs	1.29 14.1

25. **ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER
 EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER

- COMPLETE DRILLING PLAN
 FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

CONFIDENTIAL

NAME (PLEASE PRINT) Alvin R. (AI) Arlian TITLE Landman - Regulatory Specialist
SIGNATURE [Signature] DATE 1/17/2006

(This space for State use only)

API NUMBER ASSIGNED: 13-047-37633

Approved by the
Utah Division of
Oil & Gas
APPROVAL:
Date: 01-23-06
BY: [Signature]

RECEIVED
JAN 20 2006

DIV. OF OIL, GAS & MINING

Federal Approval of this
Action is Necessary

SELF-CERTIFICATION STATEMENT

The following self-certification statement is provided per federal requirements dated June 15, 1988.

Please be advised that Enduring Resources, LLC is considered to be the operator of the following well.

Asphalt Wash #10-23-31-33

Surface Location: NENE Sec. 33-T10S-R23E

725' FNL – 859' FEL

BH Location: NWNE Sec. 33-T10S-R23E

660' FNL – 1,980' FEL

Uintah County, Utah

Lease Serial No.: UTU-073451

Enduring Resources, LLC is responsible under the terms and conditions of the lease for the operations conducted upon leased lands. Bond coverage is provided by UTB000173.



January 17, 2006

Alvin R. (Al) Arlian
Landman - Regulatory Specialist
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, CO 80202
(303) 350-5114

RECEIVED

JAN 20 2006

DIV. OF OIL, GAS & MINING

Enduring Resources, LLC

Asphalt Wash 10-23-31-33
Surface Loc: NENE Sec. 33-T10S-R23E
BH Loc: NWNE Sec. 33-T10S-R23E
Uintah County, Utah

Lease #: UTU-73451

ONSHORE ORDER 1 - DRILLING PLAN

1. Estimated Tops of Geological Markers:

Formation	Depth (K.B.) TVD
Uinta	Surface
Green River	33'
Wasatch	3103'
Mesaverde	5005'

2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:

Substance	Formation	Depth (K.B.) TVD
	KB-Uinta Elevation: 5141' est.	
Oil / Gas	Green River	33'
Oil /Gas	Wasatch	3103'
Oil /Gas	Mesaverde	5005'
	TD	7370'

An 11" hole will be drilled to approximately 2000 feet. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set.

3. Pressure Control Equipment: (3000 psi schematic attached)

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 3,000 psi casinghead, with 3,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 3,000 psi BOPE
- C. Kelly will be equipped with upper and lower Kelly valves.
- D. Testing Procedure: Annular Preventer

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

4. Proposed Casing & Cementing Program:

A. Casing Program: All New

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Depth Set (MD)
20"	14" O.D.				40' (GL)
11"	8-5/8"	24#	J-55	ST&C	0 – 2016' (KB) est.
7-7/8"	4-1/2"	11.6#	N-80	LT&C	0 – 7370' (KB)

The surface casing will have guide shoe, 1 joint, insert float collar. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints with bowspring centralizers on every other collar (8 centralizers total). Thread lock guide shoe.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

B. Casing Design Parameters:

Depth (MD)	Casing	Collapse(psi)/SF	Burst (psi)/SF	Tension(mlbs)/SF
40' (GL)	14" OD			
2016' (KB)	8-5/8", 24#/ft, J55, STC	1370/1.52(a)	2950/3.28(b)	244/5.81(c)
7370' (KB)	4-1/2", 11.6#/ft, N-80, LTC	6350/1.66 (d)	7780/2.21 (e)	223/3.04 (f)

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus, no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

PROPOSED CEMENTING PROGRAM

Surface Casing (if well will circulate)-Cemented to surface

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
8-5/8"	Lead	1516	Premium cement + 16% gel + 0.25 pps celloflake	138	25%	11.1	3.50
8-5/8"	Tail	500	Premium cement + 2% CaCl ₂ + 0.25 pps celloflake	138	25%	15.8	1.15

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft³/sx) cement will be premium cement w/ 3% CaCl₂ + 0.25 pps celloflake. Volume as required

Surface Casing (if well will not circulate) - Cemented to surface

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
8-5/8"	Lead	500	Premium cement + 2% CaCl ₂ + 0.25 pps celloflake	138	25	15.8	1.15
8-5/8"	Top job	As req.	Premium cement + 3% CaCl ₂ + 0.25 pps celloflake	As Req.		15.8	1.15

Production Casing and Liner - Cemented TD to 300' above base of surface casing

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
4-1/2"	Lead	987	Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender	87	25	11.0	3.3
4-1/2"	Tail	4667	50/50 POZ Class G + 2% gel +1% CaCl ₂ + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam	852	25	14.3	1.56

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of surface casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. **Drilling Fluids (mud) Program:**

Interval (MD)	Mud Weight	Fluid Loss	Viscosity	Mud Type
0' - 2016' (KB)		No cntrl		Air/mist
2000'-3000' (KB)	8.4-8.6	No cntrl	28-36	Water
3000'-7370' (KB)	8.8-9.8	8 - 10 ml	32-42	Water/Gel

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

6. **Evaluation Program:**

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.

Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

7. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No H₂S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 3,832 psi (calculated at 0.52 psi/foot of hole) and maximum anticipated surface pressure equals approximately 2,211 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

8. Anticipated Starting Dates:

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 10 days
- Completion Days - Approximately 10 days
- Anticipate location construction within 30 days of permit issue.

9. Variances:

None anticipated

10. Other:

A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

A measurement while drilling (MWD) system will be used to track and control the directional path of the wellbore.

Enduring Resources, LLC

Asphalt Wash 10-23-31-33
Surface Loc: NENE Sec. 33-T10S-R23E
BH Loc: NENE Sec. 33-T10S-R23E
Uintah County, Utah
Lease #: UTU-73451

Directions to Asphalt Wash 10-23-31-33

Directions to the proposed (**surface**) location are as follows:

FROM THE INTERSECTION OF U.S. HIGHWAY 40 AND 500 EAST STREET IN VERNAL, UTAH PROCEED IN AN EASTERLY THEN SOUTHERLY DIRECTION ALONG U.S. HIGHWAY 40 APPROXIMATELY 3.3 MILES TO THE JUNCTION OF STATE HIGHWAY 45; EXIT RIGHT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 45 APPROXIMATELY 40.5 MILES TO THE JUNCTION OF THE DRAGON ROAD (COUNTY B ROAD 4180). THIS ROAD IS LOCATED APPROXIMATELY 4.8 MILES SOUTH OF BONANZA, UTAH. EXIT LEFT AND PROCEED IN A SOUTHEASTERLY DIRECTION ALONG COUNTY B ROAD 4180 APPROXIMATELY 4.0 MILES TO THE JUNCTION OF THE KINGS WELLS ROAD (COUNTY B ROAD 4190). EXIT RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION ALONG COUNTY B ROAD 4190 APPROXIMATELY 8.7 MILES TO THE JUNCTION OF THE ATCHEE RIDGE ROAD (COUNTY B ROAD 4270). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 4.3 MILES TO THE JUNCTION OF THE LONG DRAW ROAD (COUNTY B ROAD 4260). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHERLY, THEN WESTERLY DIRECTION APPROXIMATELY 4.0 MILES TO THE JUNCTION OF COUNTY B ROAD 4160. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4160 APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THE BITTER CREEK ROAD (COUNTY B ROAD 4120). EXIT LEFT AND PROCEED IN A WESTERLY DIRECTION ALONG COUNTY B ROAD 4120 APPROXIMATELY 1.9 MILES TO THE JUNCTION OF COUNTY B ROAD 4230. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4230 APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THE ATCHEES WASH ROAD (COUNTY B ROAD 4240). EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4240 APPROXIMATELY 7.5 MILES TO THE PROPOSED ACCESS ROAD. FOLLOW ROAD FLAGS IN A NORTHERLY DIRECTION APPROXIMATELY 550 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 75.7 MILES IN A SOUTHEASTERLY DIRECTION.

Enduring Resources, LLC

Asphalt Wash 10-23-31-33
Surface Loc: NENE Sec. 33-T10S-R23E
BH Loc: NWNE Sec. 33-T10S-R23E
Uintah County, Utah

Lease #: UTU-73451

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Directions to the proposed (**surface**) location are as follows:

FROM THE INTERSECTION OF U.S. HIGHWAY 40 AND 500 EAST STREET IN VERNAL, UTAH PROCEED IN AN EASTERLY THEN SOUTHERLY DIRECTION ALONG U.S. HIGHWAY 40 APPROXIMATELY 3.3 MILES TO THE JUNCTION OF STATE HIGHWAY 45; EXIT RIGHT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 45 APPROXIMATELY 40.5 MILES TO THE JUNCTION OF THE DRAGON ROAD (COUNTY B ROAD 4180). THIS ROAD IS LOCATED APPROXIMATELY 4.8 MILES SOUTH OF BONANZA, UTAH. EXIT LEFT AND PROCEED IN A SOUTHEASTERLY DIRECTION ALONG COUNTY B ROAD 4180 APPROXIMATELY 4.0 MILES TO THE JUNCTION OF THE KINGS WELLS ROAD (COUNTY B ROAD 4190). EXIT RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION ALONG COUNTY B ROAD 4190 APPROXIMATELY 8.7 MILES TO THE JUNCTION OF THE ATCHEE RIDGE ROAD (COUNTY B ROAD 4270). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 4.3 MILES TO THE JUNCTION OF THE LONG DRAW ROAD (COUNTY B ROAD 4260). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHERLY, THEN WESTERLY DIRECTION APPROXIMATELY 4.0 MILES TO THE JUNCTION OF COUNTY B ROAD 4160. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4160 APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THE BITTER CREEK ROAD (COUNTY B ROAD 4120). EXIT LEFT AND PROCEED IN A WESTERLY DIRECTION ALONG COUNTY B ROAD 4120 APPROXIMATELY 1.9 MILES TO THE JUNCTION OF COUNTY B ROAD 4230. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4230 APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THE ATCHEES WASH ROAD (COUNTY B ROAD 4240). EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4240 APPROXIMATELY 7.5 MILES TO THE PROPOSED ACCESS ROAD. FOLLOW ROAD FLAGS IN A NORTHERLY DIRECTION APPROXIMATELY 550 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 75.7 MILES IN A SOUTHEASTERLY DIRECTION.

2. **Planned Access Roads:**

The proposed access (all on federal lands) road will be approximately 740 feet of new construction located ON-LEASE and 1,090 feet of new construction OFF-LEASE. Please refer to Topo Map "B" for the takeoff point for the new road construction (*Proposed Access Road*).

The pad is also located on federal lands.

The well pad will be used to drill two other wells:

1. **Asphalt Wash 10-23-42-33, a directional well (SENE Sec. 33), and**
2. **Asphalt Wash 10-23-41-33, a vertical well (NENE Sec. 33)**

An OFF-LEASE 30' wide, access road right-of-way across BLM lands to access this well will be needed and is requested herein. This is the same road accessing other multi-well pads in Sec 33.

The proposed access road will be utilized to transport personnel, equipment and supplies to and from the proposed well site during drilling, completion and production operations. The road will be utilized year round.

The access road will be crowned 2% to 3%, ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet right-of-way. Maximum grade of road is 5% or less. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. No fence crossings, culverts, turnouts, cattle guards or major cuts and fills are required. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: *Surface Operating Standards for Oil and Gas Exploration and Development. 1989.*

The road surface and shoulders will be kept in a safe usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy

conditions. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. Location of Existing Wells within a One-Mile radius (See "Topo" Map "C" attached):

The following wells are wells located within a one (1) mile radius of the proposed location.

- | | | | |
|----|-------|------------------------------|---|
| a. | None: | Water Wells: | |
| b. | None: | Injection Wells: | |
| c. | None: | Producing Wells: | |
| d. | None: | Drilling Wells: | |
| e. | None: | Shut-in Wells: | |
| f. | (1): | Temporarily Abandoned Wells: | (1 – Abandon Location) |
| | | i. | Saddle Tree 13-34 43-047-31782 |
| g. | None: | Disposal Wells: | |
| h. | None: | Abandoned Wells: | |
| i. | None: | Dry Holes: | |
| j. | None: | Observation Wells: | |

4. Location of Existing and/or Proposed Facilities:

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank and be independent of the back cut.

All permanent (on site for six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Inter-Agency Committee

All facilities will be painted within 6 months of installation. The color shall be Carlsbad Canyon (2.5Y 6/2). Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Gas Gathering Pipeline:

- a. 210' BLM (ON-LEASE)
- b. 400' OFF-LEASE

The OFF-LEASE 30 foot wide, surface, 4 inch pipeline right-of-way across BLM lands to sell natural gas from this well is hereby requested adjacent to the access road. This pipeline will provide gas pipeline gathering for all the wells to be drilled on this lease, Lease No. 73451, and any SITLA wells drilled in Section 32. Note: A 630' "trunk surface pipeline" will be laid north of the well to access Section 32.

If the well is capable of economic production, a surface gas gathering line and related equipment shall be installed. The surface gas gathering line shall be in use year round. A total of approximately 610 feet of surface gas gathering pipeline shall be laid on the surface to minimize surface disturbance:

- The pipeline will be 4 inch or less diameter steel surface pipeline,
- shall be laid beside the access road,

The proposed surface pipeline will begin at the well site and be laid along side the access road until ties into the proposed pipeline to the Asphalt Wash 10-23-22-33 Well.

The line will be welded together and pulled from the well site location and tie-in point when practical; however, it may be necessary to utilize the access road for welding of the line. The line will then be boomed off to the side of the road. That portion of the pipeline not located along the road will be laid with as little surface disturbance as practical. The gas meter run will be located within 500 feet of the wellhead. The meter run will be housed. The gas gathering line will be buried or anchored down from the wellhead to the meter.

Upon plugging and abandonment, the gas gathering line will be removed and the disturbed area will be re-contoured and restored as near as practical to the original condition. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

5. Location and Type of Water Supply:

Whenever practical, water will be obtained from Enduring Resources LLC Water Right Number 49-2215. If that source is not feasible, then one of the two following sources shall be used: Target Trucking Water User Claim #43-2195, or by Dalbo Inc. Water User Claim #43-8496.

Water will be hauled to the location over the roads marked on "Topo" Maps "A" and "B."

No water well is to be drilled on this lease.

6 Source of Construction Materials:

Surface and subsoil materials in the immediate area will be utilized for location and access road construction.

Any gravel will be obtained from a commercial source; however, gravel sized rock debris associated with location and access road construction may be used as access road surfacing material.

7. Methods of Handling Waste Materials:

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break or allow discharge of liquids.

The reserve pit will be lined with ¼ felt and a minimum of 16 mm plastic with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the will be disposed of in the pit.

A chemical portable toilet will be furnished with the drilling rig. The toilet will be replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

Garbage, trash and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well.

Produced oil will be stored in an oil tank and then hauled by truck to a crude purchaser facility. Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to an approved disposal site.

8 Ancillary Facilities:

During drilling operations, approximately 20 days, the site will be a manned camp. Three or four additional trailers will be on location to serve as the crews' housing and eating facilities. These will be located on the perimeter of the pad site within the topsoil stockpiles. Refer to Sheet 4.

9. Well Site Layout: (Refer to Sheets #2, #3, and #4)

The attached Location Layout Diagrams described drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s) and surface material stockpiles(s).

Please see the attached diagram for rig orientation and access roads.

The top soil will be windrowed rather than piled. It will be reseeded and track walker at the time the location is constructed. Seeding will be with the determined during the onsite. (Refer to "Seed Mixture for Windrowed Top Soil Will included:" following herein.

The top soil removed from the pit area will be store separately and will not be reseeded until the pit is reclaimed.

All pits shall be fence to the following minimum standards:

- a. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches over the new wire. Total height of the fence shall be at least 42 inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two fence posts shall be no greater than 16 feet.
- e. All wire shall be stretched by, using a stretching device, before it is attached to corner posts.
- f. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.
- g. Location size may change prior to drilling the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling, the location will be re-surveyed and a Form 9 will be submitted.

10. Plans for Surface Reclamation:**Producing Location:**

- a. Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, materials, trash and debris not required for production.
- b. Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 40CFR 3162.7.
- c. Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.
- d. The reserve pit and that portion of the location not needed for production facilities/operations will be re-contoured to the approximated natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.
- e. To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface 3 feet above surrounding round surface to allow the reclaimed pit area to drain effectively.
- f. Upon completion of back filling, leveling and re-contouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

- a. Abandoned well sites, roads and other disturbed areas will be restored as nearly as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions and re-establishment of vegetation as specified.
- b. All disturbed surfaces will be re-contoured to the approximated natural contours with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

Seed Mixture for Windrowed Top Soil Will Included:

The appropriate surface management agency will be contacted for the required seed mixture and dates.

11. Surface Ownership: Location, Access and Pipeline Route:

Wellsite: Bureau of Land management

Access: Bureau of Land management

Pipeline: Bureau of Land management

12. Other Information**On-site Inspection for Location, Access and Pipeline Route:**

The on-site was conducted October 11, 2005

Special Conditions of Approval:

Production Equipment shall be painted Dark Olive Black.

13. Other Information**Wildlife Stipulations:**

Wildlife stipulations and possible activity restrictions will be detailed in the conditions of approval" received with an approved Permit to Drill. Operator will comply with these wildlife stipulations, if any.

Archeology:

A Cultural Resource Inventory Report is being conducted for the well location, access route and pipeline. The report shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust Lands Administration upon its receipt.

Paleontology:

A Paleontology Reconnaissance Report is being conducted for the well location, access route and pipeline. The report shall be submitted to the Division of Oil, gas and Mining and the School and Institutional Trust Lands Administration upon its receipt.

If, during operations, any archaeological or historical sites, or any objects of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites will be suspended and the discovery reported promptly to the surface management agency.

All lease operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, and the approved Plan of Operations and all applicable Notice to Lessees. The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved Application for Permit to Drill will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.




PHOTO VIEW: FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: EASTERLY




PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: NORTHERLY

ENDURING RESOURCES

**Asphalt Wash 10-23-41-33, Asphalt Wash
10-23-42-33 & Asphalt Wash 10-23-31-33
SECTION 33, T10S, R23E, S.L.B.&M.
750' FNL & 857' FEL**

LOCATION PHOTOS

TAKEN BY: K.R.K.

DRAWN BY: T.D.H.

DATE TAKEN: 05-23-05

DATE DRAWN: 06-07-05

REVISED: 10-26-05: J.R.S.

Timberline Land Surveying, Inc.
38 West 100 North Vernal, Utah 84078
(435) 789-1365

**SHEET
1
OF 11**

ENDURING RESOURCE

WELL PAD INTERFERENCE PLAT ASPHALT WASH 10-23-41-33, ASPHALT WASH 10-23-42-33 & ASPHALT WASH 10-23-31-33



SURFACE POSITION FOOTAGES:

Asphalt Wash 10-23-42-33
775' FNL & 856' FEL

Asphalt Wash 10-23-41-33
750' FNL & 857' FEL

Asphalt Wash 10-23-31-33
725' FNL & 859' FEL

BOTTOM HOLE FOOTAGES


Asphalt Wash 10-23-42-33
1980' FNL & 660' FEL

Asphalt Wash 10-23-41-33
VERTICAL

Asphalt Wash 10-23-31-33
660' FNL & 1980' FEL

Basis of bearings is the South line of the SE 1/4 of Section 33 which is taken from Global Positioning Satellite Observations to bear S89°59'44"W.

Basis of elevation is triangulation station JEK 19 ET 1966 which is located at the South 1/4 corner of Section 8, T11S, R23E, S.L.B.&M. The elevation of this triangulation station is marked on the Archy Bench SE 7.5 min. Quadrangle as being 6054'.




RELATIVE COORDINATES		
From Surface Position to Bottom Hole		
WELL	NORTH	EAST
42-33	-1,205'	195'
41-33	VERTICAL	
31-33	66'	-1,221'

LATITUDE & LONGITUDE		
Surface Position - (NAD 83) Autonomous		
WELL	N. LATITUDE	W. LONGITUDE
42-33	39°54'37.96"	109°19'31.85"
41-33	39°54'38.21"	109°19'31.87"
31-33	39°54'38.46"	109°19'31.90"

LATITUDE & LONGITUDE		
Bottom Hole - (NAD 83) Autonomous		
WELL	N. LATITUDE	W. LONGITUDE
42-33	39°54'26.06"	109°19'29.36"
41-33	VERTICAL	
31-33	39°54'39.11"	109°19'46.27"

DURING RESOURCE





CUT SHEET - ASPHALT WASH 10-23-41-33, ASPHALT WASH 10-23-42-33 & ASPHALT WASH 10-23-31-33



Section 33, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE NE		Footage Location: 750' FNL & 857' FEL	
Date Surveyed: 10-20-05	Date Drawn: 10-26-05	Date Last Revision:		Timberline (435) 789-1365 Land Surveying, Inc. 38 WEST 100 NORTH VERNAL, UTAH 84078	
Surveyed By: K.R.K.	Drawn By: J.R.S.	Scale: 1" = 60'			
				SHEET	4
				OF 11	

ENDURING RESOURCE

CROSS SECTIONS - ASPHALT WASH 10-23-41-33, ASPHALT WASH 10-23-42-33 & ASPHALT WASH 10-23-31-33



NOTE:
UNLESS OTHERWISE NOTED
CUT SLOPES ARE AT 1:1
FILL SLOPES ARE AT 1.5:1

Pit overburden is included in pad cut.

REFERENCE POINTS

- 175' SOUTHEASTERLY = 5121.2'
- 225' SOUTHEASTERLY = 5127.4'
- 250' NORTHERLY = 5116.0'
- 300' NORTHERLY = 5114.1'


ESTIMATED EARTHWORK QUANTITIES (No shrink or swell adjustments have been used) (Expressed in Cubic Yards)				
ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	6,670	7,070	Topsoil is not included in Pad Cut	-400
PIT	3,110	3,110		3,110
TOTALS	9,780	7,070	1,680	2,710

Excess Material after Pit Rehabilitation = 1,150 Cu. Yds.

Section 33, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE NE		Footage Location: 750' FNL & 857' FEL	
Date Surveyed: 10-20-05	Date Drawn: 10-26-05	Date Last Revision:		Timberline (435) 789-1365 Land Surveying, Inc. 38 WEST 100 NORTH VERNAL, UTAH 84078	
Surveyed By: K.R.K.	Drawn By: J.R.S.	Scale: 1" = 60'			
				SHEET	5
				OF 11	

DURING RESOURCE


TYPICAL RIG LAYOUT - ASPHALT WASH 10-23-41-33, ASPHALT WASH 10-23-42-33 & ASPHALT WASH 10-23-31-33




Section 33, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE NE		Footage Location: 750' FNL & 857' FEL	
Date Surveyed: 10-20-05	Date Drawn: 10-26-05	Date Last Revision:		Timberline (435) 789-1365 Land Surveying, Inc. 38 WEST 100 NORTH VERNAL, UTAH 84078	
Surveyed By: K.R.K.	Drawn By: J.R.S.	Scale: 1" = 60'			
				SHEET 6 OF 11	

DURING RESOURCE

TYPICAL PRODUCTION LAYOUT – ASPHALT WASH 10-23-41-33,
 ASPHALT WASH 10-23-42-33 & ASPHALT WASH 10-23-31-33



Section 33, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE NE	Footage Location: 750' FNL & 857' FEL
Date Surveyed: 10-20-05	Date Drawn: 10-26-05	Date Last Revision:	Timberline (435) 789-1365 <i>Land Surveying, Inc.</i> 38 WEST 100 NORTH VERNAL, UTAH 84078
Surveyed By: K.R.K.	Drawn By: J.R.S.	Scale: 1" = 60'	
			SHEET 7 OF 11



**Proposed Well Location:
Asphalt Wash 10-23-41-33**

LEGEND

- = PROPOSED WELL LOCATION
- = EXISTING ROAD
- = EXISTING ROAD (TO BE IMPROVED)
- - - - = PROPOSED ACCESS ROAD
- B-5460 = COUNTY ROAD CLASS & NUMBER

TOPOGRAPHIC MAP "A"

SCALE: 1"=10,000'

DRAWN BY: T.D.H.

DATE SURVEYED: 05-23-05

DATE DRAWN: 06-07-05

REVISED: 10-26-05 J.R.S.

ENDURING RESOURCES

**Asphalt Wash 10-23-41-33, Asphalt Wash
10-23-42-33 & Asphalt Wash 10-23-31-33
SECTION 33, T10S, R23E, S.L.B.&M.
750' FNL & 857' FEL**


Timberline Land Surveying, Inc.

38 West 100 North Vernal, Utah 84078
(435) 789-1365

SHEET

8

OF 11



Proposed Well Location:
Asphalt Wash 10-23-41-33

Road Reroute
±330 Feet

Proposed Access Road
±550 Feet

Proposed 10-23-12-34

Proposed 10-23-23-34

Proposed 10-23-13-34

Proposed 10-23-44-34

T10S

T11S

Road Reroute
±950 Feet

PROPOSED ACCESS ROAD			
Segment	Owner	On Lease	Length
1	BLM	No	±950'
2	BLM	No	±140'
3	BLM	Yes	±410'
4	BLM	Yes	±330'
TOTAL			±1,830'

Vernal ± 74.7 Miles

ROCK HOUSE GAS FIELD

LEGEND

- PROPOSED ACCESS ROAD
- = SUBJECT WELL
- = SHARED ACCESS
- = EXISTING ROAD
- = EXISTING ROAD (TO BE IMPROVED)
- (B-5460) = COUNTY ROAD CLASS & NUMBER
- = LEASE LINE AND / OR PROPERTY LINE


ENDURING RESOURCES

Asphalt Wash 10-23-41-33, Asphalt Wash
10-23-42-33 & Asphalt Wash 10-23-31-33
SECTION 33, T10S, R23E, S.L.B.&M.
750' FNL & 857' FEL

TOPOGRAPHIC MAP "B" DATE SURVEYED: 05-23-05
SCALE: 1" = 2000' DRAWN BY: T.D.H. DATE DRAWN: 06-07-05
REVISED: 10-26-05 J.R.S.

Timberline Land Surveying, Inc.
38 West 100 North Vernal, Utah 84078
(435) 789-1385

SHEET
9
OF 11



Proposed Well Location:
Asphalt Wash 10-23-41-33

Proposed Surface Position:
Asphalt Wash 10-23-42-33

Proposed Bottom Hole Location:
Asphalt Wash 10-23-42-33

Rock House

Saddle Tree
Draw 13-34

T10S

T11S

LEGEND

- ⊘ = DISPOSAL WELL
- = PRODUCING WELL
- = SHUT IN WELL
- ⊘ = WATER WELL
- = ABANDONED WELL
- = TEMPORARILY ABANDONED WELL

ENDURING RESOURCES

Asphalt Wash 10-23-42-33
SECTION 33 , T10S, R23E, S.L.B.&M.
Bottom Hole: 1980' FNL & 660' FEL

TOPOGRAPHIC MAP "C"

DATE SURVEYED: 05-23-05

DATE DRAWN: 06-07-05

SCALE: 1" = 2000'


DRAWN BY: T.D.H.

REVISED: 10-26-05 J.R.S.



Timberline Land Surveying, Inc.
 38 West 100 North Vernal, Utah 84078
 (435) 789-1365

SHEET
10a
OF 11



Proposed Well Location:
Asphalt Wash 10-23-41-33

T10S
T11S

LEGEND

- ⊘ = DISPOSAL WELL
- = PRODUCING WELL
- = SHUT IN WELL
- ⊘ = WATER WELL
- = ABANDONED WELL
- = TEMPORARILY ABANDONED WELL


ENDURING RESOURCES

Asphalt Wash 10-23-41-33
SECTION 33 , T10S, R23E, S.L.B.&M.
750' FNL & 857' FEL

TOPOGRAPHIC MAP "C"		DATE SURVEYED: 05-23-05
SCALE: 1" = 2000'		DATE DRAWN: 06-07-05
DRAWN BY: T.D.H.	REVISED: 10-26-05 J.R.S.	

Timberline Land Surveying, Inc.
 38 West 100 North Vernal, Utah 84078
 (435) 789-1365

SHEET
10b
OF 11



LEGEND

- ⊘ = DISPOSAL WELL
- = PRODUCING WELL
- = SHUT IN WELL
- ⊘ = WATER WELL
- = ABANDONED WELL
- = TEMPORARILY ABANDONED WELL

TOPOGRAPHIC MAP "C"

DATE SURVEYED: 05-23-05

DATE DRAWN: 06-07-05

SCALE: 1" = 2000'

DRAWN BY: T.D.H.


REVISED: 10-26-05 J.R.S.

ENDURING RESOURCES

Asphalt Wash 10-23-31-33
SECTION 33 , T10S, R23E, S.L.B.&M.
Bottom Hole: 660' FNL & 1980' FEL

Timberline Land Surveying, Inc.
 38 West 100 North Vernal, Utah 84078
 (435) 789-1365

SHEET
10C
OF 11



Proposed Well Location:
Asphalt Wash 10-23-41-33

Proposed Access Road

PROPOSED PIPELINE

Proposed Pipeline
from Well 22-33

Proposed Well Pad 22-33

Rock House

TIE-IN POINT

Proposed Well Pad 12-34

Proposed Well Pad 32-33

Proposed Pipeline

Proposed Pipeline

Proposed Well Pad 23-33

Proposed Pipeline
Proposed Pipeline

Proposed Well Pad 13-34

Proposed Well Pad 23-34

Proposed Well Pad 44-34

Proposed Well Pad 44-33

Proposed Access
& Pipeline

T10S

T11S

PROPOSED PIPELINE			
Segment	Owner	On Lease	Length
1	BLM	No	±400'
2	BLM	Yes	±210'
TOTAL			±610'

LEGEND

- = OTHER PIPELINE
- = PROPOSED PIPELINE
- = PROPOSED ACCESS ROAD
- = LEASE LINE AND/OR PROPERTY LINE

ENDURING RESOURCES

Asphalt Wash 10-23-41-33, Asphalt Wash 10-23-42-33 & Asphalt Wash 10-23-31-33
SECTION 33 , T10S, R23E, S.L.B.&M.
750' FNL & 857' FEL



TOPOGRAPHIC MAP "D"		DATE SURVEYED: 05-23-05
SCALE: 1" = 1000'	DRAWN BY: T.D.H.	DATE DRAWN: 06-07-05
		REVISED: 10-26-05 J.R.S.

Timberline Land Surveying, Inc.
 38 West 100 North Vernal, Utah 84078
 (435) 789-1365

SHEET
11
 OF 11

3,000 PSI

BOP STACK



**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 01/20/2006

API NO. ASSIGNED: 43-047-37633

WELL NAME: ASPHALT WASH 10-23-31-33
 OPERATOR: ENDURING RESOURCES, LLC (N2750)
 CONTACT: AL ARLIAN

PHONE NUMBER: 303-350-5114

PROPOSED LOCATION:

NWNE

NENE 33 100S 230E
 SURFACE: 0725 FNL 0859 FEL
 BOTTOM: 0660 FNL 1980 FEL
 COUNTY: UINTAH
 LATITUDE: 39.91067 LONGITUDE: -109.3249
 UTM SURF EASTINGS: 643183 NORTHINGS: 4418976
 FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal
 LEASE NUMBER: UTU-73451
 SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: MVRD
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. RLB0008031)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 43-8496)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)

LOCATION AND SITING:

- ___ R649-2-3.
- Unit: _____
- ___ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- ___ R649-3-3. Exception
- ___ Drilling Unit
Board Cause No: _____
Eff Date: _____
Siting: _____
- ___ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1. Federal Approval

2. Spacing GAP

T10S R23E

NATURAL BUTTES FIELD

ROCK HOUSE 10D-32

ROCK HOUSE
9-32-10-23

BHL
9-32-10-23

ASPHALT WASH
10-23-13-33

ASPHALT WASH
10-23-23-33

ASPHALT WASH
10-23-14-33

BHL
10-23-42-33

ASPHALT WASH 10-23-41-33
ASPHALT WASH 10-23-31-33
ASPHALT WASH 10-23-42-33

ASPHALT WASH
10-23-12-34

ASPHALT WASH
10-23-13-34

ATCHEE
WASH 33-9

ASPHALT WASH
10-23-44-33

SADDLE TREE
DRAW B-34

T11S R23E

ROCK HOUSE UNIT

ROCK HOUSE FIELD

OPERATOR: ENDURING RES LLC (N2750)

SEC: 33 T. 10S R. 23E

FIELD: NATURAL BUTTES (630)


COUNTY: UINTAH

SPACING: R649-3-11 / DIRECTIONAL DRILLING

Field Status	
	ABANDONED
	ACTIVE
	COMBINED
	INACTIVE
	PROPOSED
	STORAGE
	TERMINATED

Unit Status	
	EXPLORATORY
	GAS STORAGE
	NF PP OIL
	NF SECONDARY
	PENDING
	PI OIL
	PP GAS
	PP GEOTHERML
	PP OIL
	SECONDARY
	TERMINATED

Wells Status	
	GAS INJECTION
	GAS STORAGE
	LOCATION ABANDONED
	NEW LOCATION
	PLUGGED & ABANDONED
	PRODUCING GAS
	PRODUCING OIL
	SHUT-IN GAS
	SHUT-IN OIL
	TEMP. ABANDONED
	TEST WELL
	WATER INJECTION
	WATER SUPPLY
	WATER DISPOSAL
	DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 23-JANUARY-2006



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

January 23, 2006

Enduring Resources, LLC
475 17th St., Ste. 1500
Denver, CO 80202

Re: Asphalt Wash 10-23-31-33 Well, Surface Location 725' FNL, 859' FEL,
NE NE, Sec. 33, T. 10 South, R. 23 East, Bottom Location 660' FNL,
1980' FEL, NW NE, Sec. 33, T. 10 South, R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-37633.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Enduring Resources, LLC
Well Name & Number Asphalt Wash 10-23-31-33
API Number: 43-047-37633
Lease: UTU-73451

Surface Location: NE NE **Sec.** 33 **T.** 10 South **R.** 23 East
Bottom Location: NW NE **Sec.** 33 **T.** 10 South **R.** 23 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Page 2
43-047-37633
January 23, 2006

6. In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.



Enduring Resources

475 17th Street Suite 1500 Denver Colorado 80202
Telephone 303 573-1222 Fax 303 573 0461

February 10, 2006

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, Utah 84114-5801
Attn.: Ms. Diana Whitney

43-047-37633

RE: Asphalt Wash #10-23-31-33
Surface Location: NENE Sec. 33-T10S-R23E
725' FNL – 859' FEL
BH Location: NWNE Sec. 33-T10S-R23E
660' FNL – 1,980' FEL
Uintah County, Utah
Lease Serial No.: UTU-073451

Dear Ms. Whitney:

Enclosed is an original copy of the ***DIRECTIONAL DRILLING PLAN*** for the above-referenced proposed well. The quarter/quarter on the header of the plan is the surface location.

This information was inadvertently omitted from the APD sent to you earlier. ***This well's BHL AND surface location are both on federal lands.***

Enduring Resources, LLC is requesting the Utah Division of Oil, Gas and Mining to hold this application and all future information as confidential.

If any questions arise or additional information is required, please contact me at 303-350-5114.

Very truly yours,

ENDURING RESOURCES, LLC

Alvin R. (Al) Arlian
Landman-Regulatory Specialist

ara
Enclosures:

RECEIVED
FEB 14 2006
DIV. OF OIL, GAS & MINING



ENDURING RESOURCES
Asphalt Wash 10-23-31-33
NE/NE Sec. 33, T10S, R23E
Uintah County, Utah



CONFIDENTIAL

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.00	0.00	273.09	0.00	0.00	0.00	0.00	0.00	0.00	
2	2098.00	0.00	273.09	2098.00	0.00	0.00	0.00	0.00	0.00	KOP
3	2905.56	32.30	273.09	2863.45	11.97	-221.35	4.00	273.09	221.68	End Build
4	4225.83	32.30	273.09	3979.39	50.05	-925.86	0.00	0.00	927.21	Start Drop
5	5302.57	0.00	273.09	5000.00	66.00	-1221.00	3.00	180.00	1222.78	Start Hold
6	7672.57	0.00	273.09	7370.00	66.00	-1221.00	0.00	273.09	1222.78	TD



RKB Elevation: 5141.00
Ground Elevation: 5125.00

WELL DETAILS

Name	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
Asphalt Wash 10-23-31-33	49.88	-3.56	7143617.65	2250299.93	39°54'38.453N	109°19'31.896W	N/A

FIELD DETAILS

Uintah, Utah
 Utah Central Zone
 U.S.A.
 Geodetic System: US State Plane Coordinate System 1983
 Ellipsoid: GRS 1980
 Zone: Utah, Central Zone
 Magnetic Model: igrf2005
 System Datum: Mean Sea Level
 Local North: True North

SITE DETAILS

NE/NE 33-10S-23E Pad
 Sec. 33, T10S, R23E, Uintah County, Utah
 Site Centre Latitude: 39°54'37.960N
 Longitude: 109°19'31.850W
 Ground Level: 5125.00
 Positional Uncertainty: 0.00

TARGET DETAILS



Name	TVD	+N/-S	+E/-W	Shape
10-23-31-33 Target	7370.00	66.00	-1221.00	Rectangle (400x400)

CASING DETAILS

No.	TVD	MD	Name	Size
1	2000.00	2000.00	9 5/8" Surface	9.625

FORMATION TOP DETAILS

No.	TVDPath	MDPath	Formation
1	33.00	33.00	Green River
2	3103.00	3188.97	Wasatch
3	5005.00	5307.57	Mesaverde



Weatherford International

Planning Report

Company: Enduring Resources Field: Uintah, Utah Site: NE/NE 33-10S-23E Pad Well: Asphalt Wash 10-23-31-33 Wellpath: 1	Date: 2/10/2006 Co-ordinate(NE) Reference: Well: Asphalt Wash 10-23-31-33 Vertical (TVD) Reference: SITE 5141.0 Section (VS) Reference: Well (0.00N,0.00E,273.09Azi) Plan: Plan #1	Time: 09:38:54 Page: 1
--	---	---

Field: Uintah, Utah Utah Central Zone U.S.A. Map System: US State Plane Coordinate System 1983 Geo Datum: GRS 1980 Sys Datum: Mean Sea Level	Map Zone: Utah, Central Zone Coordinate System: Well Centre Geomagnetic Model: igrf2005
---	--

Site: NE/NE 33-10S-23E Pad
 Sec. 33, T10S, R23E, Uintah County, Utah

Site Position:	Northing: 7143567.87 ft	Latitude: 39 54 37.960 N	
From: Geographic	Easting: 2250304.70 ft	Longitude: 109 19 31.850 W	
Position Uncertainty: 0.00 ft		North Reference: True	
Ground Level: 5125.00 ft			

Well: Asphalt Wash 10-23-31-33	Slot Name:
Well Position: +N/-S 49.88 ft	Latitude: 39 54 38.453 N
+E/-W -3.56 ft	Longitude: 109 19 31.896 W
Position Uncertainty: 0.00 ft	
Northing: 7143617.65 ft	
Easting: 2250299.93 ft	

Wellpath: 1	Drilled From: Surface	Tie-on Depth: 0.00 ft	
Current Datum: SITE	Height: 5141.00 ft	Above System Datum: Mean Sea Level	
Magnetic Data: 2/10/2006		Declination: 11.67 deg	
Field Strength: 52893 nT		Mag Dip Angle: 65.97 deg	
Vertical Section: Depth From (TVD)	+N/-S	+E/-W	Direction
ft	ft	ft	deg
0.00	0.00	0.00	273.09

Plan: Plan #1	Date Composed: 2/10/2006
Principal: Yes	Version: 1
	Tied-to: From Surface

Plan Section Information

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg	Target
0.00	0.00	273.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2098.00	0.00	273.09	2098.00	0.00	0.00	0.00	0.00	0.00	0.00	
2905.56	32.30	273.09	2863.45	11.97	-221.35	4.00	4.00	0.00	273.09	
4225.83	32.30	273.09	3979.39	50.05	-925.86	0.00	0.00	0.00	0.00	
5302.57	0.00	273.09	5000.00	66.00	-1221.00	3.00	-3.00	0.00	180.00	
7672.57	0.00	273.09	7370.00	66.00	-1221.00	0.00	0.00	0.00	273.09	10-23-31-33 Target

Section 1 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
0.00	0.00	273.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2000.00	0.00	273.09	2000.00	0.00	0.00	0.00	0.00	0.00	0.00	273.09
2098.00	0.00	273.09	2098.00	0.00	0.00	0.00	0.00	0.00	0.00	273.09

Section 2 : Start Build 4.00

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
2100.00	0.08	273.09	2100.00	0.00	0.00	0.00	4.00	4.00	0.00	0.00
2200.00	4.08	273.09	2199.91	0.20	-3.62	3.63	4.00	4.00	0.00	0.00
2300.00	8.08	273.09	2299.33	0.77	-14.20	14.22	4.00	4.00	0.00	0.00
2400.00	12.08	273.09	2397.77	1.71	-31.67	31.72	4.00	4.00	0.00	0.00
2500.00	16.08	273.09	2494.74	3.02	-55.96	56.04	4.00	4.00	0.00	0.00
2600.00	20.08	273.09	2589.79	4.70	-86.94	87.07	4.00	4.00	0.00	0.00
2700.00	24.08	273.09	2682.43	6.73	-124.47	124.65	4.00	4.00	0.00	0.00
2800.00	28.08	273.09	2772.23	9.10	-168.36	168.61	4.00	4.00	0.00	0.00
2900.00	32.08	273.09	2858.75	11.81	-218.40	218.72	4.00	4.00	0.00	0.00
2905.56	32.30	273.09	2863.45	11.97	-221.35	221.68	4.00	4.00	0.00	0.00

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/NE 33-10S-23E Pad
Well: Asphalt Wash 10-23-31-33
Wellpath: 1

Date: 2/10/2006 **Time:** 09:38:54 **Page:** 2
Co-ordinate(NE) Reference: Well: Asphalt Wash 10-23-31-33
Vertical (TVD) Reference: SITE 5141.0
Section (VS) Reference: Well (0.00N,0.00E,273.09Azi)
Plan: Plan #1

Section 2 : Start Build 4.00

MD	Incl	Azim	TVD	+N/-S	+E/-W	VS	DLS	Build	Turn	TFO
----	------	------	-----	-------	-------	----	-----	-------	------	-----

Section 3 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
3000.00	32.30	273.09	2943.28	14.69	-271.75	272.15	0.00	0.00	0.00	180.00
3100.00	32.30	273.09	3027.80	17.57	-325.11	325.58	0.00	0.00	0.00	180.00
3188.97	32.30	273.09	3103.00	20.14	-372.58	373.13	0.00	0.00	0.00	180.00
3200.00	32.30	273.09	3112.33	20.46	-378.47	379.02	0.00	0.00	0.00	180.00
3300.00	32.30	273.09	3196.85	23.34	-431.83	432.46	0.00	0.00	0.00	180.00
3400.00	32.30	273.09	3281.37	26.23	-485.19	485.90	0.00	0.00	0.00	180.00
3500.00	32.30	273.09	3365.90	29.11	-538.55	539.34	0.00	0.00	0.00	180.00
3600.00	32.30	273.09	3450.42	32.00	-591.91	592.78	0.00	0.00	0.00	180.00
3700.00	32.30	273.09	3534.95	34.88	-645.28	646.22	0.00	0.00	0.00	180.00
3800.00	32.30	273.09	3619.47	37.76	-698.64	699.66	0.00	0.00	0.00	180.00
3900.00	32.30	273.09	3703.99	40.65	-752.00	753.09	0.00	0.00	0.00	180.00
4000.00	32.30	273.09	3788.52	43.53	-805.36	806.53	0.00	0.00	0.00	180.00
4100.00	32.30	273.09	3873.04	46.42	-858.72	859.97	0.00	0.00	0.00	180.00
4200.00	32.30	273.09	3957.57	49.30	-912.08	913.41	0.00	0.00	0.00	180.00
4225.83	32.30	273.09	3979.39	50.05	-925.86	927.21	0.00	0.00	0.00	180.00

Section 4 : Start Drop -3.00

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
4300.00	30.08	273.09	4042.84	52.12	-964.21	965.62	3.00	-3.00	0.00	180.00
4400.00	27.08	273.09	4130.65	54.70	-1011.97	1013.45	3.00	-3.00	0.00	180.00
4500.00	24.08	273.09	4220.84	57.03	-1055.08	1056.62	3.00	-3.00	0.00	180.00
4600.00	21.08	273.09	4313.17	59.10	-1093.41	1095.01	3.00	-3.00	0.00	180.00
4695.40	18.22	273.09	4403.00	60.83	-1125.43	1127.08	3.00	-3.00	0.00	180.00
4700.00	18.08	273.09	4407.38	60.91	-1126.87	1128.51	3.00	-3.00	0.00	180.00
4800.00	15.08	273.09	4503.21	62.45	-1155.35	1157.04	3.00	-3.00	0.00	180.00
4900.00	12.08	273.09	4600.40	63.72	-1178.79	1180.51	3.00	-3.00	0.00	180.00
5000.00	9.08	273.09	4698.69	64.71	-1197.12	1198.86	3.00	-3.00	0.00	180.00
5100.00	6.08	273.09	4797.81	65.42	-1210.28	1212.05	3.00	-3.00	0.00	180.00
5200.00	3.08	273.09	4897.48	65.85	-1218.25	1220.03	3.00	-3.00	0.00	180.00
5300.00	0.08	273.09	4997.43	66.00	-1221.00	1222.78	3.00	-3.00	0.00	180.00
5302.57	0.00	273.09	5000.00	66.00	-1221.00	1222.78	3.00	-3.00	0.00	180.00

Section 5 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
5307.57	0.00	273.09	5005.00	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
5400.00	0.00	273.09	5097.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
5500.00	0.00	273.09	5197.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
5600.00	0.00	273.09	5297.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
5700.00	0.00	273.09	5397.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
5800.00	0.00	273.09	5497.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
5900.00	0.00	273.09	5597.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6000.00	0.00	273.09	5697.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6100.00	0.00	273.09	5797.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6200.00	0.00	273.09	5897.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6300.00	0.00	273.09	5997.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6400.00	0.00	273.09	6097.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6500.00	0.00	273.09	6197.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6600.00	0.00	273.09	6297.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6700.00	0.00	273.09	6397.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6800.00	0.00	273.09	6497.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
6900.00	0.00	273.09	6597.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
7000.00	0.00	273.09	6697.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
7100.00	0.00	273.09	6797.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
7200.00	0.00	273.09	6897.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/NE 33-10S-23E Pad
Well: Asphalt Wash 10-23-31-33
Wellpath: 1

Date: 2/10/2006 **Time:** 09:38:54 **Page:** 3
Co-ordinate(NE) Reference: Well: Asphalt Wash 10-23-31-33
Vertical (TVD) Reference: SITE 5141.0
Section (VS) Reference: Well (0.00N,0.00E,273.09Azi)
Plan: Plan #1

Section 5 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
7300.00	0.00	273.09	6997.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
7400.00	0.00	273.09	7097.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
7500.00	0.00	273.09	7197.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
7600.00	0.00	273.09	7297.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09
7672.57	0.00	273.09	7370.00	66.00	-1221.00	1222.78	0.00	0.00	0.00	273.09

Survey

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	Tool/Comment
2000.00	0.00	273.09	2000.00	0.00	0.00	0.00	0.00	0.00	0.00	9 5/8" Surface
2098.00	0.00	273.09	2098.00	0.00	0.00	0.00	0.00	0.00	0.00	KOP
2100.00	0.08	273.09	2100.00	0.00	0.00	0.00	4.00	4.00	0.00	MWD
2200.00	4.08	273.09	2199.91	0.20	-3.62	3.63	4.00	4.00	0.00	MWD
2300.00	8.08	273.09	2299.33	0.77	-14.20	14.22	4.00	4.00	0.00	MWD
2400.00	12.08	273.09	2397.77	1.71	-31.67	31.72	4.00	4.00	0.00	MWD
2500.00	16.08	273.09	2494.74	3.02	-55.96	56.04	4.00	4.00	0.00	MWD
2600.00	20.08	273.09	2589.79	4.70	-86.94	87.07	4.00	4.00	0.00	MWD
2700.00	24.08	273.09	2682.43	6.73	-124.47	124.65	4.00	4.00	0.00	MWD
2800.00	28.08	273.09	2772.23	9.10	-168.36	168.61	4.00	4.00	0.00	MWD
2900.00	32.08	273.09	2858.75	11.81	-218.40	218.72	4.00	4.00	0.00	MWD
2905.56	32.30	273.09	2863.45	11.97	-221.35	221.68	4.00	4.00	0.00	End Build
3000.00	32.30	273.09	2943.28	14.69	-271.75	272.15	0.00	0.00	0.00	MWD
3100.00	32.30	273.09	3027.80	17.57	-325.11	325.58	0.00	0.00	0.00	MWD
3188.97	32.30	273.09	3103.00	20.14	-372.58	373.13	0.00	0.00	0.00	Wasatch
3200.00	32.30	273.09	3112.33	20.46	-378.47	379.02	0.00	0.00	0.00	MWD
3300.00	32.30	273.09	3196.85	23.34	-431.83	432.46	0.00	0.00	0.00	MWD
3400.00	32.30	273.09	3281.37	26.23	-485.19	485.90	0.00	0.00	0.00	MWD
3500.00	32.30	273.09	3365.90	29.11	-538.55	539.34	0.00	0.00	0.00	MWD
3600.00	32.30	273.09	3450.42	32.00	-591.91	592.78	0.00	0.00	0.00	MWD
3700.00	32.30	273.09	3534.95	34.88	-645.28	646.22	0.00	0.00	0.00	MWD
3800.00	32.30	273.09	3619.47	37.76	-698.64	699.66	0.00	0.00	0.00	MWD
3900.00	32.30	273.09	3703.99	40.65	-752.00	753.09	0.00	0.00	0.00	MWD
4000.00	32.30	273.09	3788.52	43.53	-805.36	806.53	0.00	0.00	0.00	MWD
4100.00	32.30	273.09	3873.04	46.42	-858.72	859.97	0.00	0.00	0.00	MWD
4200.00	32.30	273.09	3957.57	49.30	-912.08	913.41	0.00	0.00	0.00	MWD
4225.83	32.30	273.09	3979.39	50.05	-925.86	927.21	0.00	0.00	0.00	Start Drop
4300.00	30.08	273.09	4042.84	52.12	-964.21	965.62	3.00	-3.00	0.00	MWD
4400.00	27.08	273.09	4130.65	54.70	-1011.97	1013.45	3.00	-3.00	0.00	MWD
4500.00	24.08	273.09	4220.84	57.03	-1055.08	1056.62	3.00	-3.00	0.00	MWD
4600.00	21.08	273.09	4313.17	59.10	-1093.41	1095.01	3.00	-3.00	0.00	MWD
4695.40	18.22	273.09	4403.00	60.83	-1125.43	1127.08	3.00	-3.00	0.00	Entry Point
4700.00	18.08	273.09	4407.38	60.91	-1126.87	1128.51	3.00	-3.00	0.00	MWD
4800.00	15.08	273.09	4503.21	62.45	-1155.35	1157.04	3.00	-3.00	0.00	MWD
4900.00	12.08	273.09	4600.40	63.72	-1178.79	1180.51	3.00	-3.00	0.00	MWD
5000.00	9.08	273.09	4698.69	64.71	-1197.12	1198.86	3.00	-3.00	0.00	MWD
5100.00	6.08	273.09	4797.81	65.42	-1210.28	1212.05	3.00	-3.00	0.00	MWD
5200.00	3.08	273.09	4897.48	65.85	-1218.25	1220.03	3.00	-3.00	0.00	MWD
5300.00	0.08	273.09	4997.43	66.00	-1221.00	1222.78	3.00	-3.00	0.00	MWD
5302.57	0.00	273.09	5000.00	66.00	-1221.00	1222.78	3.00	-3.00	0.00	Start Hold
5307.57	0.00	273.09	5005.00	66.00	-1221.00	1222.78	0.00	0.00	0.00	Mesaverde
5400.00	0.00	273.09	5097.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
5500.00	0.00	273.09	5197.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
5600.00	0.00	273.09	5297.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
5700.00	0.00	273.09	5397.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD

Weatherford International

Planning Report

Company: Enduring Resources	Date: 2/10/2006	Time: 09:38:54	Page: 4
Field: Uintah, Utah	Co-ordinate(NE) Reference: Well: Asphalt Wash 10-23-31-33		
Site: NE/NE 33-10S-23E Pad	Vertical (TVD) Reference: SITE 5141.0		
Well: Asphalt Wash 10-23-31-33	Section (VS) Reference: Well (0.00N,0.00E,273.09Azi)		
Wellpath: 1	Plan: Plan #1		

Survey

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	Tool/Comment
5800.00	0.00	273.09	5497.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
5900.00	0.00	273.09	5597.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6000.00	0.00	273.09	5697.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6100.00	0.00	273.09	5797.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6200.00	0.00	273.09	5897.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6300.00	0.00	273.09	5997.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6400.00	0.00	273.09	6097.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6500.00	0.00	273.09	6197.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6600.00	0.00	273.09	6297.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6700.00	0.00	273.09	6397.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6800.00	0.00	273.09	6497.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
6900.00	0.00	273.09	6597.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7000.00	0.00	273.09	6697.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7100.00	0.00	273.09	6797.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7200.00	0.00	273.09	6897.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7300.00	0.00	273.09	6997.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7400.00	0.00	273.09	7097.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7500.00	0.00	273.09	7197.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7600.00	0.00	273.09	7297.43	66.00	-1221.00	1222.78	0.00	0.00	0.00	MWD
7672.57	0.00	273.09	7370.00	66.00	-1221.00	1222.78	0.00	0.00	0.00	TD

Targets

Name	Description Dip. Dir.	TVD ft	+N/-S ft	+E/-W ft	Map Northing ft	Map Easting ft	← Latitude →			← Longitude →				
							Deg	Min	Sec	Deg	Min	Sec		
10-23-31-33 Target	-Rectangle (400x400)	7370.00	66.00	-1221.00	7143653.95	2249077.68	39	54	39.105	N	109	19	47.566	W
	-Plan hit target													

Casing Points

MD ft	TVD ft	Diameter in	Hole Size in	Name
2000.00	2000.00	9.625	12.250	9 5/8" Surface

Formations

MD ft	TVD ft	Formations	Lithology	Dip Angle deg	Dip Direction deg
33.00	33.00	Green River		0.00	0.00
3188.97	3103.00	Wasatch		0.00	0.00
5307.57	5005.00	Mesaverde		0.00	0.00

Annotation

MD ft	TVD ft	
2098.00	2098.00	SHL (725 FNL & 859 FEL)
2905.56	2863.45	KOP
4225.83	3979.40	End Build
4695.40	4403.00	Start Drop
5302.57	5000.00	Entry Point
7672.57	7370.00	Start Hold
7672.57	7370.00	TD
7672.57	7370.00	PBHL (660 FNL & 1980 FEL)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL GAS WELL OTHER _____

2. NAME OF OPERATOR: **Enduring Resources, LLC**

3. ADDRESS OF OPERATOR: **475 17th Street, Suite 1500** CITY **Denver** STATE **CO** ZIP **80202** PHONE NUMBER: **(303) 350-5719**

4. LOCATION OF WELL: FOOTAGES AT SURFACE: **725' FNL - 859' FEL** COUNTY: **Uintah**
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: **NENE 33 10S 23E S** STATE: **UTAH**

5. LEASE DESIGNATION AND SERIAL NUMBER: **UTU-73451**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: **n/a**

7. UNIT or CA AGREEMENT NAME: **n/a**

8. WELL NAME and NUMBER: **Asphalt Wash 10-23-31-33**

9. API NUMBER: **4304737633**

10. FIELD AND POOL, OR WILDCAT: **Undesignated**

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Request for APD Extension</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 11/23/2007
TO: 11/23/2008

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 12-18-06
By: [Signature]

COPY SENT TO OPERATOR
Date: 12-19-06
Initials: RM

NAME (PLEASE PRINT) Evette Bissett TITLE Regulatory Compliance Assistant
SIGNATURE [Signature] DATE 12/12/2006

(This space for State use only)

RECEIVED
DEC 15 2006
DIV. OF OIL, GAS & MINING

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304737633
Well Name: Asphalt Wash 10-23-31-33
Location: 725' FNL - 859' FEL, NENE, Sec 33, T10S-R23E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No

Gulita Bessie
Signature

12/12/2006
Date

Title: Regulatory Compliance Assistant

Representing: Enduring Resources, LLC

**RECEIVED
DEC 15 2006
DIV. OF OIL, GAS & MINING**

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73451
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
		7. UNIT or CA AGREEMENT NAME: n/a
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: Asphalt Wash 10-23-31-33
2. NAME OF OPERATOR: Enduring Resources, LLC		9. API NUMBER: 4304737633
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		10. FIELD AND POOL, OR WILDCAT: Undesignated
PHONE NUMBER: (303) 350-5719		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 725' FNL - 859' FEL		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 33 10S 23E S		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Request for APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 12/18/2007
TO: 12/18/2008

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: 12-18-07
By: 

COPY SENT TO OPERATOR
Date: 12-18-2007
Initials: _____

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE 	DATE <u>12/14/2007</u>

(This space for State use only)

RECEIVED

DEC 17 2007

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304737633
Well Name: Asphalt Wash 10-23-31-33
Location: 725' FNL - 859' FEL, NENE, Sec 33, T10S-R23E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No



Signature

12/14/2007

Date

Title: Landman - Regulatory Specialist

Representing: Enduring Resources, LLC

RECEIVED

DEC 17 2007

DIV. OF OIL, GAS & MINING



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

CONFIDENTIAL

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73451
2. NAME OF OPERATOR: Enduring Resources, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: n/a
4. LOCATION OF WELL FOOTAGES AT SURFACE: 725' FNL - 859' FEL COUNTY: Uintah		8. WELL NAME and NUMBER: Asphalt Wash 10-23-31-33
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 33 10S 23E S STATE: UTAH		9. API NUMBER: 4304737633
		10. FIELD AND POOL, OR WILDCAT: Undesignated

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Request for APD Extension</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 12/18/2008
TO: 12/18/2009

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: 12-22-08
By: [Signature]

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman</u>
SIGNATURE <u>[Signature]</u>	DATE <u>12/8/2008</u>

(This space for State use only)

COPY SENT TO OPERATOR
Date: 12.30.2008
Initials: KS

(5/2000)

(See Instructions on Reverse Side)

RECEIVED
DEC 18 2008

DIV. OF OIL, GAS & MINING



**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304737633
Well Name: Asphalt Wash 10-23-31-33
Location: 725' FNL - 859' FEL, NENE, Sec 33, T10S-R23E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No


Signature

12/8/2008
Date

Title: Administrative Assistant

Representing: Enduring Resources, LLC

RECEIVED

DEC 18 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73451
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: ASPHALT WASH 10-23-31-33
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047376330000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0725 FNL 0859 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 33 Township: 10.0S Range: 23.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/22/2009	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Request an one-year extension to APD term.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: December 21, 2009

By: 

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 12/18/2009



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047376330000

API: 43047376330000

Well Name: ASPHALT WASH 10-23-31-33

Location: 0725 FNL 0859 FEL QTR NENE SEC 33 TWP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
- Has the approved source of water for drilling changed? Yes No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
- Is bonding still in place, which covers this proposed well? Yes No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Alvin Arlian

Date: 12/18/2009

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

Date: December 21, 2009

By: 

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73451
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: ASPHALT WASH 10-23-31-33
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047376330000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0725 FNL 0859 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 33 Township: 10.0S Range: 23.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 1/23/2011	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Request an one year extension to APD termination date.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: 01/24/2011
By: 

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 1/21/2011



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047376330000

API: 43047376330000

Well Name: ASPHALT WASH 10-23-31-33

Location: 0725 FNL 0859 FEL QTR NENE SEC 33 TWP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No

Signature: Alvin Arlian

Date: 1/21/2011

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	
1. TYPE OF WELL Gas Well	5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73451
2. NAME OF OPERATOR: Enduring Resources, LLC	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 511-16th Street, Suite 700 , Denver, CO, 80202	7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0725 FNL 0859 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 33 Township: 10.0S Range: 23.0E Meridian: S	8. WELL NAME and NUMBER: ASPHALT WASH 10-23-31-33
PHONE NUMBER: 303 350-5114 Ext	9. API NUMBER: 43047376330000
9. FIELD and POOL or WILDCAT: NATURAL BUTTES	COUNTY: UINTAH
	STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 1/23/2012	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Request for an one-year extension to APD expiration date.

Approved by the Utah Division of Oil, Gas and Mining

Date: January 26, 2012

By: 

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A	DATE 1/23/2012	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047376330000

API: 43047376330000

Well Name: ASPHALT WASH 10-23-31-33

Location: 0725 FNL 0859 FEL QTR NENE SEC 33 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No

Signature: Alvin Arlian

Date: 1/23/2012

Title: Landman-Regulatory Representing: ENDURING RESOURCES, LLC

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73451
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: ASPHALT WASH 10-23-31-33	
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047376330000	
3. ADDRESS OF OPERATOR: 511-16th Street, Suite 700 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0725 FNL 0859 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 33 Township: 10.0S Range: 23.0E Meridian: S	COUNTY: UINTAH STATE: UTAH	

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 1/23/2013	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Request for an one-year extension to APD termination date.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: February 19, 2013

By: 

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A	DATE 1/21/2013	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047376330000

API: 43047376330000

Well Name: ASPHALT WASH 10-23-31-33

Location: 0725 FNL 0859 FEL QTR NENE SEC 33 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No

Signature: Alvin Arlian

Date: 1/21/2013

Title: Landman-Regulatory Representing: ENDURING RESOURCES, LLC

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73451
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	2. NAME OF OPERATOR: Enduring Resources, LLC	8. WELL NAME and NUMBER: ASPHALT WASH 10-23-31-33
3. ADDRESS OF OPERATOR: 511-16th Street, Suite 700 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext	9. API NUMBER: 43047376330000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0725 FNL 0859 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 33 Township: 10.0S Range: 23.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES	COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 1/23/2014	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Request for an one-year extension to APD expiration date.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: January 27, 2014

By: 

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A	DATE 1/20/2014	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047376330000

API: 43047376330000

Well Name: ASPHALT WASH 10-23-31-33

Location: 0725 FNL 0859 FEL QTR NENE SEC 33 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 1/23/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No

Signature: Alvin Arlian

Date: 1/20/2014

Title: Landman-Regulatory Representing: ENDURING RESOURCES, LLC



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 24, 2014

Travis Whitham
Enduring Resources, LLC
511-16th Street, Suite 700
Denver, CO 80202

43 047 37633
Asphalt Wash 10-23-31-33
33 105 23E

Re: APDs Rescinded Enduring Resources, LLC, Uintah County


Dear Mr. Whitham:

Enclosed find the list of APDs that you asked to be rescinded. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Mason
Environmental Scientist

cc: Well File
Bureau of Land Management, Vernal

4304737576 BIG PACK 11-21-44-28
4304737579 BIG PACK 11-21-41-33
4304737588 BIG PACK 11-21-42-28
4304737601 ASPHALT WASH 10-23-13-33
4304737603 BIG PACK 11-21-43-33
4304737615 ASPHALT WASH 10-23-41-33
4304737616 ASPHALT WASH 10-23-14-33
4304736237 SOUTHMAN CYN 10-24-11-30
4304737614 ASPHALT WASH 10-23-44-33
4304737632 ASPHALT WASH 10-23-42-33
→ 4304737633 ASPHALT WASH 10-23-31-33
4304739920 ASPHALT WASH 10-23-32-33
4304737637 ASPHALT WASH 10-23-21-33
4304737638 ASPHALT WASH 10-23-11-33
4304737645 E BENCH 11-22-21-20