

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires November 30, 2000

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU-25880
b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator KERR MCGEE OIL & GAS ONSHORE LP		7. If Unit or CA Agreement, Name and No.
3A. Address 1368 SOUTH 1200 EAST VERNAL, UT 84078		8. Lease Name and Well No. BITTER CREEK 1122-6A
3b. Phone No. (include area code) (435) 781-7024		9. API Well No. 43-047-35120
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface NENE 654'FNL, 952'FEL (LOT 1) 629002X At proposed prod. Zone 4417104Y		10. Field and Pool, or Exploratory BITTER CREEK undesignated
11. Sec., T., R., M., or Blk, and Survey or Area SEC 6, T11S, R22E		11. Sec., T., R., M., or Blk, and Survey or Area
14. Distance in miles and direction from nearest town or post office* 39 MILES SOUTHEAST OF OURAY, UTAH		12. County or Parish UINTAH
13. State UTAH		13. State UTAH
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 654'	16. No. of Acres in lease 614.60	17. Spacing Unit dedicated to this well 40.00
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. REFER TO TOPO C	19. Proposed Depth 8570'	20. BLM/BIA Bond No. on file BOND NO. 2971100-2533
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5525'GL	22. Approximate date work will start*	23. Estimated duration

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office. | 6. Such other site specific information and/or plans as may be required by the authorized office. |

25. Signature 	Name (Printed/Typed) SHEILA UPCHEGO	Date 5/10/2006
Title REGULATORY ANALYST		
Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 05-25-06
Title ENVIRONMENTAL MANAGER		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

**Federal Approval of this
Action is Necessary**

RECEIVED
MAY 15 2006


BUREAU OF LAND MANAGEMENT
OFFICE OF OIL, GAS & MINING

T11S, R22E, S.L.B.&M.

Sec. 36

Kerr-McGee Oil & Gas Onshore LP


Well location, BITTER CREEK #1122-6A, located as shown in Lot 1 of Section 6, T11S, R22E, S.L.B.&M. Uintah County, Utah.



LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S89°13'32"E	420.69'
L2	S02°12'23"W	546.05'


BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



SCALE CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM THE ORIGINAL FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



UINTAH ENGINEERING & LAND SURVEYING		
85 SOUTH 200 EAST - VERNAL, UTAH 84078		
(435) 789-1017		
SCALE 1" = 1000'	DATE SURVEYED: 03-16-06	DATE DRAWN: 03-27-06
PARTY T.A. S.M. C.H.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE Kerr-McGee Oil & Gas Onshore LP	

LEGEND:
 L-shaped symbol = 90° SYMBOL
 ● = PROPOSED WELL HEAD.
 ▲ = SECTION CORNERS LOCATED.

(NAD 83)
 LATITUDE = 39°53'41.54" (39.894872)
 LONGITUDE = 109°29'30.39" (109.491775)
 (NAD 27)
 LATITUDE = 39°53'41.66" (39.894906)
 LONGITUDE = 109°29'27.93" (109.491092)

**BITTER CREEK 1122-6A
NE/NE LOT 1, SECTION 6, T11S, R22E
UINTAH COUNTY, UTAH
UTU-25880**

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. Estimated Tops of Important Geologic Markers:

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	935'
Top of Birds Nest Water	1213'
Mahogany	1735'
Wasatch	4004'
Mesaverde	6521'
MVU2	7505'
MVL1	8131'
TD	8570'

2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Water	Green River	935'
	Top of Birds Nest Water	1213'
	Mahogany	1735'
Gas	Wasatch	4004'
	Mesaverde	6521'
Gas	MVU2	7505'
Gas	MVL1	8131'
Water	N/A	
Other Minerals	N/A	

3. Pressure Control Equipment (Schematic Attached)

Please refer to the attached Drilling Program.

4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program.

5. Drilling Fluids Program:

Please refer to the attached Drilling Program.

6. Evaluation Program:

Please refer to the attached Drilling Program.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 8570' TD, approximately equals 5313 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 3428 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.

10. **Other Information:**

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE May 10, 2006
 WELL NAME BITTER CREEK 1122-6A TD 8,570' MD/TVD _____
 FIELD Natural Buttes COUNTY Uintah STATE Utah ELEVATION 5,525' GL KB 5,540'
 SURFACE LOCATION NENE SECTION 6, T11S, R22E 654'FNL, 952'FEL BHL Straight Hole
 Latitude: 39.894872 Longitude: 109.491775
 OBJECTIVE ZONE(S) Wasatch/Mesaverde
 ADDITIONAL INFO Regulatory Agencies: BLM (SURF & MINERALS), UDOGM, Tri-County Health Dept.

GEOLOGICAL FORMATION		MECHANICAL			
LOGS	TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			12-1/4"	9-5/8", 32.3#, H-40, STC	Air mist
Catch water sample, if possible, from 0 to <div style="margin-left: 100px;"> Green River @ 0,935' Top of Birds Nest Water @ 1213' Preset fl GL @ 1,720' MD </div>					
Note: 12.25" surface hole will usually be drilled ±400' below the bottom of lost circulation zone. Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.					
	Mahogany @	1,735'			Water/Fresh Water Mud
Mud logging program TBD Open hole logging program fl TD - surf csg			7-7/8"	4-1/2", 11.6#, I-80 or equivalent LTC casing	8.3-11.0 ppg
	Wasatch @	4,004'			
	Mverde @	6,521'			
	MVU2 @	7,505'			
	MVL1 @	8,131'			
	TD @	8,570'			Max anticipated Mud required 11.0 ppg



**KERR-McGEE OIL & GAS ONSHORE LP
DRILLING PROGRAM**

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
SURFACE	9-5/8"	0 to 1720	32.30	H-40	STC	2270	1370	254000
						0.75*****	1.70	5.22
PRODUCTION	4-1/2"	0 to 8570	11.60	I-80	LTC	7780	6350	201000
						2.58	1.30	2.32

- 1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))
- 2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)
- (Burst Assumptions: TD = 11.0 ppg) .22 psi/ft = gradient for partially evac wellbore
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)
- MASP 3017 psi
- ***** Burst SF is low but csg is much stronger than formation at 2000'. EMW @ 2000' for 2270# is 21.8 ppg or 1.13 psi/ft

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	50		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2	LEAD	1500	NOTE: If well will circulate water to surface, option 2 will be utilized Prem cmt + 16% Gel + 10 pps gilsonite + .25 pps Flocele + 3% salt BWOC	170	35%	11.00	3.82
	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,500'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	380	60%	11.00	3.38
	TAIL	5,070'	50/50 Poz/G + 10% salt + 2% gel + .1% R-3	1420	60%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained
*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & four sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.



DRILLING ENGINEER: _____
Brad Laney

DATE: _____

DRILLING SUPERINTENDENT: _____
Bobby Brown

DATE: _____

5M BOP STACK and CHOKE MANIFOLD SYSTEM



**BITTER CREEK 1122-6A
NE/NE LOT 1, SECTION 6, T11S, R22E
UINTAH COUNTY, UTAH
UTU-25880**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Directions to the proposed location are attached.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

The proposed access road is approximately 300' +/- . Refer to Topo Map D for pipeline placement.

A rights-of-way will be required for the 2-track road. The existing 2-track road is approximately 0.4 +/- miles (needs upgraded) the 2-track road going off lease (UTU-71417) through 1122-6H in Sec 6, T11S, R22E location to connect to the proposed access road going to the 1122-5E access road. Refer to Topo Map B.

The access road will be crowned (2 to 3%), ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe and usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free-flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing or shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches, and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing & Proposed Facilities & Pipelines:**

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The requested color is Carlsbad Canyon (2.5 Y 6/2) as determined during the on-site inspection.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Variances to Best Management Practices (BMP) Requests:

A rights-of-way will be need for the proposed pipeline. Approximately 2950' of 6" and Approximately 3350' +/- of 4" steel pipeline will go off lease onto (Lease #UTU-71417) the 1122-6H in Section 6, T11S, R22E to tie-in at the Bitter Creek Pipeline. The pipeline will be butt-welded together. The pipeline shall be installed on surface within access corridor for the well location. As a Best Management Practice (BMP), the pipeline would be buried within the access road corridor if possible. The construction of pipelines requires the corridor of 30 feet.

This exception to the BMP should be granted by the BLM Authorized Officer because indurated bedrock, such as sandstone, is at or within 2 feet of the surface and the soil has a poor history for successful rehabilitation.

5. **Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec.32, T4S,R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. **Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner is to be used as discussed during on-site inspection. It will be a minimum of 20 mil thick and felt with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec.35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E. (Request is in lieu of filing Form 3160-5, after initial production).

8. **Ancillary Facilities:**

None are anticipated.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **Plans for Reclamation of the Surface:**

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

When the pit is backfilled, the topsoil pile shall be spread on the location up to the rig anchor points. The location will be reshaped to the original contour to the extent possible. The following seed mixture will be used to reclaim the surface for interim reclamation using appropriate reclamation methods. A total of 12 lbs/acre will be used if the seeds are drilled (24 lbs/acre if the seeds are broadcast). The per acre requirements for drilled seeds are:

Crested Wheatgrass	4 lbs.
Needle and Thread Grass	4 lbs
Indian Rice Grass	4 lbs.

The operator shall call BLM for the seed mixture when final reclamation occurs.

11. Surface Ownership:

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435) 781-4400

12. STIPULATIONS:

WILDLIFE STIPULATIONS:

ANTELOPE STIPULATIONS: No drilling or construction from May 15th through June 20th.

13. Other Information:

A Class III Archaeological Survey has been performed and completed on May 2, 2006, the Archaeological Report No. 06-141. The Paleontological Reconnaissance Survey has been performed will be submitted when report becomes available.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance. The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

13. Lessee's or Operators's Representative & Certification:

Sheila Upchego
Regulatory Analyst
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435) 781-7024

Randy Bayne
Drilling Manager
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435)781-7018


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Westport Oil & Gas Company agrees to be responsible under the terms and the conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for the lease activities is being provided by BLM Nationwide Bond #2971100-2533.

I hereby certify that the proposed drill site and access route has been inspected and that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Sheila Upchego

May 10, 2006
Date

Kerr-McGee Oil & Gas Onshore LP
BITTER CREEK #1122-6A
SECTION 6, T11S, R22E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 11.2 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 10.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 2.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN RIGHT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 300' TO THE BEGINNING OF THE PROPOSED ACCESS ROAD FOR THE BITTER CREEK #1122-5E TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 150' THE PROPOSED ACCESS TO THE NORTHWEST; FOLLOW ROAD FLAGS IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.4 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 55.6 MILES.

Kerr-McGee Oil & Gas Onshore LP

BITTER CREEK #1122-6A

LOCATED IN UINTAH COUNTY, UTAH

SECTION 6, T11S, R22E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHEASTERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHWESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS	03	21	06	PHOTO
	MONTH	DAY	YEAR	
TAKEN BY: T.A.	DRAWN BY: LDK		REVISED: 00-00-00	

Kerr-McGee Oil & Gas Onshore LP
BITTER CREEK #1122-6A
 PIPELINE ALIGNMENT
 LOCATED IN UTAH COUNTY, UTAH
 SECTION 6, T11S, R22E, S.L.B.&M.




PHOTO: VIEW OF TIE-IN POINT

CAMERA ANGLE: NORTHWESTERLY




PHOTO: VIEW OF PIPELINE ALIGNMENT


CAMERA ANGLE: NORTHWESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 435-789-1017 uels@uelsinc.com

PIPELINE PHOTOS			03	21	06	PHOTO
			MONTH	DAY	YEAR	
TAKEN BY: T.A.	DRAWN BY: LDK	REVISED: 00-00-00				



**PROPOSED LOCATION:
BITTER CREEK #1122-6A**

**OURAY 21.9 MI. +/-
SEEP RIDGE ROAD 10.7 MI. +/-**

3.2 MI. +/-

SEE TOPO "B"

**T10S
T11S**

**R 21 E
R 22 E**

LEGEND:

○ PROPOSED LOCATION




**Kerr-McGee Oil & Gas Onshore LP
BITTER CREEK #1122-6A
SECTION 6, T11S, R22E, S.L.B.&M.
654' FNL 952' FEL**



**Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813**

TOPOGRAPHIC MAP
03 21 06
MONTH DAY YEAR
SCALE: 1:100,000 DRAWN BY: LDK REVISED: 00-00-00





LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD
- EXISTING 2-TRACK NEEDS UPGRADED




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



Kerr-McGee Oil & Gas Onshore LP
BITTER CREEK #1122-6A
SECTION 6, T11S, R22E, S.L.B.&M.
654' FNL 952' FEL

TOPOGRAPHIC MAP	03	21	06
	MONTH	DAY	YEAR
SCALE: 1" = 2000'	DRAWN BY: LDK		REVISED: 00-00-00





**PROPOSED LOCATION:
BITTER CREEK #1122-6A**

LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ⊗ WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

Kerr-McGee Oil & Gas Onshore LP

**BITTER CREEK #1122-6A
SECTION 6, T11S, R22E, S.L.B.&M.
654' FNL 952' FEL**




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP	03	21	06
	<small>MONTH</small>	<small>DAY</small>	<small>YEAR</small>
SCALE: 1" = 2000'	DRAWN BY: LDK		REVISED: 00-00-00






APPROXIMATE TOTAL 6" PIPELINE DISTANCE = 2,950' +/-

APPROXIMATE TOTAL 4" PIPELINE DISTANCE = 3,350' +/-

LEGEND:

-  PROPOSED ACCESS ROAD
-  EXISTING 2-TRACK NEEDS UPGRADED
-  EXISTING PIPELINE
-  PROPOSED PIPELINE
-  PROPOSED PIPELINE (SERVICING OTHER WELLS)



Kerr-McGee Oil & Gas Onshore LP

BITTER CREEK #1122-6A
SECTION 6, T11S, R22E, S.L.B.&M.
654' FNL 952' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC 03 21 06
MAP MONTH DAY YEAR
 SCALE: 1" = 1000' DRAWN BY: LDK REVISED: 04-21-06C.P.




Kerr-McGee Oil & Gas Onshore LP

FIGURE #1


LOCATION LAYOUT FOR

BITTER CREEK #1122-6A
SECTION 6, T11S, R22E, S.L.B.&M.
654' FNL 952' FEL



SCALE: 1" = 50'
DATE: 03-27-06
Drawn By: C.H.

NOTE:
Flare Pit is to be located
a min. of 100' from the
Well Head.



NOTES:
Existing Road
Elev. Ungraded Ground At Loc. Stake = 5525.3'
FINISHED GRADE ELEV. AT LOC. STAKE = 5523.9'

Proposed Access Road
GRADE
Elev. 23.9'
UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

Kerr-McGee Oil & Gas Onshore LP





FIGURE #2

TYPICAL CROSS SECTIONS FOR

BITTER CREEK #1122-6A
SECTION 6, T11S, R22E, S.L.B.&M.
654' FNL 952' FEL

1" = 20'
X-Section Scale
1" = 50'

DATE: 03-27-06
Drawn By: C.H.



* NOTE:
FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,800 Cu. Yds.
Remaining Location	= 6,710 Cu. Yds.
TOTAL CUT	= 8,510 CU.YDS.
FILL	= 4,570 CU.YDS.

EXCESS MATERIAL	= 3,940 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,940 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 05/15/2006

API NO. ASSIGNED: 43-047-38120

WELL NAME: BITTER CREEK 1122-6A

OPERATOR: KERR-MCGEE OIL & GAS (N2995)

PHONE NUMBER: 435-781-7024

CONTACT: SHEILA UPCHEGO

PROPOSED LOCATION:

NENE 06 110S 220E
 SURFACE: 0654 FNL 0952 FEL
 BOTTOM: 0654 FNL 0952 FEL
 COUNTY: UINTAH
 LATITUDE: 39.89609 LONGITUDE: -109.4910
 UTM SURF EASTINGS: 629008 NORTHINGS: 4417104
 FIELD NAME: UNDESIGNATED (2)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-25880

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: WSMVD
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. 2971100-2533)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 43-8496)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)

LOCATION AND SITING:

- ____ R649-2-3.
- Unit: _____
- ____ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit
Board Cause No: 210-04
Eff Date: 4-12-04
Siting: 400' fr well & 920' fr other wells.
R649-3-2
- ____ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1- Federal Approval

NATURAL BUTTES FIELD

T10S R21E

T11S R22E

CAUSE: 210-04 / 4-12-2004

BITTER CREEK
H22-5A

STATE 4-32
STATE 1022-12M
(RIGSKID)

BITTER CREEK
H22-6C

BITTER CREEK
H22-6B

BITTER CREEK
H22-6A

BITTER CREEK
H22-5B

BITTER CREEK
H22-6H

BITTER CREEK
H22-5G

BITTER CREEK
H22-5E

BITTER CREEK
H22-5H

BITTER CREEK
H22-6L

BITTER CREEK
H22-6F

BITTER CREEK
H22-6J

BITTER CREEK
H22-6I

BITTER CREEK
H22-5I

BITTER CREEK
H22-6G

BITTER CREEK
H22-6P

BITTER CREEK
H22-5M

BITTER CREEK
H22-6O

FIELD


OPERATOR: KERR-MCGEE O&G (N2995)

SEC: 5,6 T. 11S R. 22E

FIELD: UNDESIGNATED (002)

COUNTY: UINTAH

CAUSE: 210-04 / 4-12-2004



Utah Oil Gas and Mining

- Field Status**
- ABANDONED
 - ACTIVE
 - COMBINED
 - INACTIVE
 - PROPOSED
 - STORAGE
 - TERMINATED

- Unit Status**
- EXPLORATORY
 - GAS STORAGE
 - NF PP OIL
 - NF SECONDARY
 - PENDING
 - PI OIL
 - PP GAS
 - PP GEOTHERML
 - PP OIL
 - SECONDARY
 - TERMINATED

- Wells Status**
- ⊕ GAS INJECTION
 - ⊗ GAS STORAGE
 - ⊙ LOCATION ABANDONED
 - ⊕ NEW LOCATION
 - ⊙ PLUGGED & ABANDONED
 - ⊕ PRODUCING GAS
 - ⊙ PRODUCING OIL
 - ⊕ SHUT-IN GAS
 - ⊙ SHUT-IN OIL
 - ⊗ TEMP. ABANDONED
 - ⊙ TEST WELL
 - ⊕ WATER INJECTION
 - ⊙ WATER SUPPLY
 - ⊕ WATER DISPOSAL
 - ⊙ DRILLING



PREPARED BY: DIANA WHITNEY
DATE: 19-MAY-2006



Kerr-McGee Oil & Gas OnShore LP
1999 Broadway, Suite 3700, Denver, Colorado 80202
303-296-3600 • Fax 303-296-3601

May 23, 2006

Ms. Diana Whitney
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, UT 84114-6100

RE: Bitter Creek 1122-6A
T11S-R22E
Section 6: NENE (Lot 1)
654' FNL, 952' FEL
Uintah County, Utah

Dear Ms. Whitney:

Kerr-McGee Oil & Gas Onshore LP, formerly known as Westport Oil and Gas Company, L.P. has submitted a permit to drill the captioned well to test the Wasatch and Mesaverde formations. The well is located at an exception location to Spacing Order 210-4. The well location was moved for topographic reasons. Kerr-McGee owns 100% of the leasehold within 460 feet of the exception location of the offset lands and has no objection to the exception location.

Kerr-McGee requests your approval of this exception location. If you have any questions, call me at 720-264-2618. Thank you for your assistance.

Sincerely,

A handwritten signature in black ink, appearing to read 'W. Chris Latimer', written over a horizontal line.

W. Chris Latimer, CPL
Senior Landman

cc: Raleen Weddle

RECEIVED

MAY 25 2006

DIV. OF OIL, GAS & MINING



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

May 25, 2006

Kerr-McGee Oil & Gas Onshore, LP
1368 S 1200 E
Vernal, UT 84078

Re: Bitter Creek 1122-6A Well, 654' FNL, 952' FEL, NE NE, Sec. 6, T. 11 South,
R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38120.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Kerr-McGee Oil & Gas Onshore LP

Well Name & Number Bitter Creek 1122-6A

API Number: 43-047-38120

Lease: UTU-25880

Location: NE NE **Sec.** 6 **T.** 11 South **R.** 22 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU-25880

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
BITTER CREEK 1122-6A

9. API Well No.
4304738120

10. Field and Pool, or Exploratory Area
UNDESIGNATED

11. County or Parish, State
UINTAH, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
KERR MCGEE OIL AND GAS ONSHORE, LP

3a. Address
1368 SOUTH 1200 EAST, VERNAL, UTAH 84078

3b. Phone No. (include area code)
(435)781-7003

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
**654' FNL, 952' FEL (LOT 1)
NENE, SEC 6-T11S-R22E**

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other APD EXTENSION
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	DOG M
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

THE OPERATOR REQUESTS AUTHORIZATION FOR A ONE YEAR EXTENSION FOR THE SUBJECT WELL LOCATION SO THAT THE DRILLING OPERATIONS MAY BE COMPLETED. THE ORIGINAL APD WAS APPROVED BY THE DIVISION OF OIL, GAS AND MINING BY THE 2006.

Utah Division of
Oil, Gas and Mining

5-3-07
RM

MAY 01 2007

Date: 05-01-07
By: [Signature]

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) RAMEY HOOPES	Title REGULATORY CLERK
Signature <i>Ramey Hoopes</i>	Date April 24, 2007

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
-------------	-------	------

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738120
Well Name: BITTER CREEK 1122-6A
Location: NENE, SEC 6-T11S-R22E
Company Permit Issued to: KERR-MCGEE OIL AND GAS ONSHORE LP
Date Original Permit Issued: 5/25/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No



Signature

4/24/2007

Date

Title: REGULATORY CLERK

Representing: KERR-MCGEE OIL AND GAS ONSHORE I

MAY 01 2007

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

RECEIVED
VERNAL FIELD OFFICE


2006 MAY 11 PM 3:39
PERMIT APPROVED
OMB No. 1004-0136
DEPT. OF THE INTERIOR
BUREAU OF LAND MGMT.
UTU-25880

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		6. If Indian, Allottee or Tribe Name
b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator KERR MCGEE OIL & GAS ONSHORE LP		8. Lease Name and Well No. BITTER CREEK 1122-6A
3A. Address 1368 SOUTH 1200 EAST VERNAL, UT 84078	3b. Phone No. (include area code) (435) 781-7024	9. API Well No. 43-047-38120
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NENE 654'FNL, 952'FEL (LOT 1) At proposed prod. Zone		10. Field and Pool, or Exploratory BITTER CREEK
14. Distance in miles and direction from nearest town or post office* 39 MILES SOUTHEAST OF OURAY, UTAH		11. Sec., T., R., M., or Blk, and Survey or Area SEC 6, T11S, R22E
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 654'	16. No. of Acres in lease 614.60	17. Spacing Unit dedicated to this well 40.00
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. REFER TO TOPO C	19. Proposed Depth 8570'	20. BLM/BIA Bond No. on file BOND NO. 2971100-2533 / WY 2357
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5525'GL	22. Approximate date work will start*	23. Estimated duration WY 2000 291

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office. | 6. Such other site specific information and/or plans as may be required by the authorized office. |

25. Signature 	Name (Printed/Typed) SHEILA UPCHEGO	Date 5/10/2006
Title REGULATORY ANALYST		
Approved by (Signature) 	Name (Printed/Typed) STEVE KERR	Date 6-26-2007
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

RECEIVED
JUL 02 2007

NOTICE OF APPROVAL

UDOGM

06BM1481A

DIV. OF OIL, GAS & MINING

NDS 04/07/2006



**UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE**

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Kerr-McGee Oil & Gas Onshore, LP
Well No: Bitter Creek 1122-6A
API No: 43-047-38120

Location: NENE Lot 1, Sec. 6, T11S, R22E
Lease No: UTU-25880
Agreement: N/A

Title	Name	Office Phone Number	Cell Phone Number
Petroleum Engineer:	Matt Baker	(435) 781-4490	(435) 828-4470
Petroleum Engineer:	Michael Lee	(435) 781-4432	(435) 828-7875
Petroleum Engineer:	James Ashley	(435) 781-4470	(435) 828-7874
Petroleum Engineer:	Ryan Angus	(435) 781-4430	(435) 828-7368
Supervisory Petroleum Technician:	Jamie Sparger	(435) 781-4502	(435) 828-3913
NRS/Enviro Scientist:	Paul Buhler	(435) 781-4475	(435) 828-4029
NRS/Enviro Scientist:	Karl Wright	(435) 781-4484	
NRS/Enviro Scientist:	Holly Villa	(435) 781-4404	
NRS/Enviro Scientist:	Vacant	(435) 781-4476	(435) 828-7381
NRS/Enviro Scientist:	Chuck Macdonald	(435) 781-4441	(435) 828-7481
NRS/Enviro Scientist:	Jannice Cutler	(435) 781-3400	
NRS/Enviro Scientist:	Michael Cutler	(435) 781-3401	
NRS/Enviro Scientist:	Anna Figueroa	(435) 781-3407	
NRS/Enviro Scientist:	Verlyn Pindell	(435) 781-3402	
NRS/Enviro Scientist:	Darren Williams	(435) 781-4447	
NRS/Enviro Scientist:	Nathan Packer	(435) 781-3405	

Fax: (435) 781-4410

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

Surface COAs:

- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.
- During operations, if any vertebrate paleontological resources are discovered, all operations affecting such sites shall be immediately suspended, and all discoveries shall be left intact until authorized to proceed by the Authorized Officer. The appropriate Authorized Officer of the Vernal BLM office shall be notified within 48 hrs of the discovery, and a decision as to the preferred alternative/course of action will be rendered.
- The lessee/operator is given notice that lands in the lease have been identified as containing crucial pronghorn (antelope) habitat. It is requested that the lessee/operator not initiate surface disturbing activities or drilling from May 15 through June 20. A survey may be conducted by a qualified biologist or a BLM representative during this timing period to determine if pronghorn are in the area.
- As discussed on the onsite all fill and excess material will be kept out of the drainages.
- 4 to 6 inches of topsoil shall be stripped from the location and windrowed as shown on the cut sheet. The topsoil shall then be broadcast seeded with the recommended seed mix immediately after it has been windrowed and the seed walked into the soil with a dozer.
- The topsoil from the reserve pit shall be stripped and piled separately near the reserve pit. When the reserve pit is closed, it shall be recontoured and the topsoil respread, and the area shall be seeded in the same manner as the location topsoil.
- Once the location is plugged and abandoned, it shall be recontoured to natural contours, topsoil respread where appropriate, and the entire location seeded with the recommended seed mix. Seeding shall take place by broadcasting the seed and walking it into the soil with a dozer immediately after the dirt work is completed.

DOWNHOLE COAs:

SITE SPECIFIC DOWNHOLE COAs:

- Production casing cement shall be brought up and into the surface casing.
- A cement Bond Log (CBL) shall be run from the production casing shoe to the surface casing shoe.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person

making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- Chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or

data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: KERR-McGEE OIL & GAS ONSHORE, LP

Well Name: BITTER CREEK 1122-6A

Api No: 43-047-38120 Lease Type: FEDERAL

Section 06 Township 11S Range 22E County UINTAH

Drilling Contractor PETE MARTIN DRLG RIG # BUCKET

SPUDDED:

Date 11/18/07

Time 2:30 PM

How DRY

Drilling will Commence: _____

Reported by SHEILA UPCHEGO

Telephone # (435) 781-7024

Date 11/20/07 Signed CHD

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU-25880

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
BITTER CREEK 1122-6A

9. API Well No.
4304738120

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE – Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
KERR-McGEE OIL & GAS ONSHORE LP

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
NE/NE, LOT 1, SEC. 6, T11S, R22E 654'FNL, 952'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other SET SURFACE
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	CSG
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

MIRU BILL MARTIN AIR RIG ON 11/23/2007. DRILLED 12 1/4" SURFACE HOLE TO 1865'. RAN 9 5/8" 41 JTS OF 36# J-55 SURFACE CSG. LEAD CMT W/150 SX HIFILL CLASS G @11.0 PPG 3.82 YIELD. TAILED CMT W/200 SX PREM CLASS G @15.8 PPG 1.15 YIELD. GOOD RETURNS 20 +/- BBL LEAD CMT TO PIT. RAN 200' OF 1" PIPE. CMT W/150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. GOOD CMT TO SURFACE AND FELL BACK. TOP OUT W/125 SX PREM CLASS G @15.8 PPG 1.15 YIELD. GOOD CMT TO SURFACE HOLE STAYED FULL.

WORT.

RECEIVED
DEC 03 2007
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) SHEILA UPCHEGO	Title SENIOR LAND ADMIN SPECIALIST
Signature 	Date November 26, 2007

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
-------------	-------	------

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
KERR-McGEE OIL & GAS ONSHORE LP

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
NE/NE, LOT 1, SEC. 6, T11S, R22E 654'FNL, 952'FEL

5. Lease Serial No.
UTU-25880

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
BITTER CREEK 1122-6A

9. API Well No.
4304738120

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Deepen
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Fracture Treat
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Plug and Abandon
	<input type="checkbox"/> Plug Back
	<input type="checkbox"/> Production (Start/Resume)
	<input type="checkbox"/> Reclamation
	<input type="checkbox"/> Recomplete
	<input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Water Disposal
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Well Integrity
	<input checked="" type="checkbox"/> Other FINAL DRILLING OPERATIONS

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

FINISHED DRILLING FROM 1865' TO 8600' ON 01/14/2008. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/380 SX PREM LITE II @11.3 PPG 3.13 YIELD. TAILED CMT W/1270 SX 50/50 POZ @ 14.3 PPG 1.31 YIELD. DISPLACE W/133 BBLs FRESH EATER + CLAYFIX + ALGICIDE BUMP PLUG W/3000# 500 OVER FLOATS OK HAD GOOD RETURNS W/36 BBLs LEAD CMT TO PIT. FLUSH AND DRAIN STACK LAND HANGER W/60,000# TEST SCALE TO 5000# ND BOPE CLEAN MUD TANKS.

RELEASED PIONEER RIG 41 ON 01/14/2008 AT 2000 HRS.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)
SHEILA UPCHEGO

Title
SENIOR LAND ADMIN SPECIALIST

Signature

Date
January 15, 2008

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Produced by

JAN 28 2008

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

UTU-25880

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NE/NE, LOT 1, SEC. 6, T11S, R22E 654'FNL, 952'FEL

8. Well Name and No.

BITTER CREEK 1122-6A

9. API Well No.

4304738120

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other PRODUCTION START-UP
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 02/09/2008 AT 2:00 PM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

RECEIVED
FEB 25 2008
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

SHEILA UPCHEGO

Title

SENIOR LAND ADMIN SPECIALIST

Signature

Date

February 12, 2008

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Anadarko Petroleum Corporation
 1368 South 1200 East
 Vernal, UT 84078

CHRONOLOGICAL WELL HISTORY

BITTER CREEK 1122-6A

LOCATION NENE, SEC.6, T11S, R22E
 UINTAH COUNTY, UT

DATE	ACTIVITY	PIONEER 41	STATUS
10/30/07	LOCATION STARTED	PIONEER 41	
11/14/07	LOCATION COMPLETED	PIONEER 41	P/L IN, WOBR
11/18/07	SET CONDUCTOR	PIONEER 41	WOAR
11/23/07	SET AIR RIG	PIONEER 41	DRILLING
11/28/07	9-5/8" @ 1825'	PIONEER 41	WORT
12/27/07	TD: 1883' Csg. 9 5/8" @ 1825' MW: 8.4 Move rig f/ State 1021-36E. 100% moved and 10% rigged up @ report time.		SD: 12/XX/07 DSS: 0
12/28/07	TD: 1883' Csg. 9 5/8" @ 1825' MW: 8.4 Finish rig move and RURT @ report time.		SD: 12/XX/07 DSS: 0
12/31/07	TD: 1883' Csg. 9 5/8" @ 1825' MW: 8.4 Rig up and w/o #1 pump. Finish RURT. NU and test BOPE. PUDS and tag cmt. MP#2 engine down. Rig on repair @ report time.		SD: 12/XX/07 DSS: 0
01/02/08	TD: 1883' Csg. 9 5/8" @ 1825' MW: 8.4 Repair MP#2 engine. Drill cmt and FE @ report time.		SD: 1/02/08 DSS: 0
01/03/08	TD: 3340' Csg. 9 5/8" @ 1825' MW: 8.4 Drill FE. Rotary spud @ 0000 hrs 1/2/07. Drill from 1883'-3340'. DA @ report time.		SD: 1/02/08 DOL/DSS:9/1
01/04/07	TD: 5053' Csg. 9 5/8" @ 1825' MW: 8.7 Drill from 3340'-5053'. DA @ report time.		SD: 1/02/08 DOL/DSS:10/2
01/07/08	TD: 7810' Csg. 9 5/8" @ 1825' MW: 11.6 Drill from 5053'- 7810'. DA @ report time.		SD: 1/02/08 DOL/DSS:13/5
01/08/08	TD: 7830' Csg. 9 5/8" @ 1825' MW: 11.6 Drill from 7810'- 7830'. TOOH to shoe for new bit. Inspect blocks. Need to replace same. Replacement blocks coming from Houston. Prepare to unstring and change out blocks.		SD: 1/02/08 DOL/DSS:14/6
01/09/08	TD: 7830' Csg. 9 5/8" @ 1825' MW: 11.6 W/O Replacement blocks from Houston.		SD: 1/02/08 DOL/DSS:15/7
01/10/08	TD: 7830' Csg. 9 5/8" @ 1825' MW: 11.6 Replacement blocks on location @ 1500 hrs. Hang and string up Blocks.		SD: 1/02/08 DOL/DSS:16/8
01/11/08	TD: 7830' Csg. 9 5/8" @ 1825' MW: 11.6		SD: 1/02/08 DOL/DSS:17/9

TOOH and change bit and MM. TIH to 4560'. W&R to 5050'. Lost returns. Build volume and regain returns. W&R to 6350' @ report time.

01/14/08 TD: 8600' Csg. 9 5/8" @ 1825' MW: 11.9 SD: 1/02/08 DOL/DSS:20/12
W&R to 6350'-7100'. Lost 150 bbls of mud. Pull 6 stands, est returns, W&R to 7830'. Drill f/
7830'-8600'. CCH, short trip, and LDDS. Run quad combo to TD. Logging out @ report time.

01/15/08 TD: 8600' Csg. 9 5/8" @ 1825' MW: 11.9 SD: 1/02/08 DOL/DSS:21/13
Finish logging. Run and cmt 4.5" prod csg. Land hanger, ND, clean pits, and rls rig @ 2000 hrs
on 1/14/08. RDRT @ report time.

02/04/08 **MIRU**
Days on Completion: 1
Remarks: (DAY # 1) JSA # 1. RDMO OF STATE 1021 36E, ROAD RIG TO BITTER CREEK
1122-6A, MIRU SERVICE UNIT AND SPOTTED EQUIP., ND/WH, NU/BOP, RU WORKING
FLOOR & TBG EQUIP., TALLY 2-3/8" TBG, PU/ 3-7/8" MILL, RIH W/ 2-3/8" NEW J-55 TBG, EOT
@ 4829.60' , 157 JTS., POOH L/D 3 JTS. SWI. SDFN

02/05/08 **PREP TO FRAC**
Days on Completion: 2
Remarks: (DAY # 2) JSA # 2. NO PRESSURE ON WELL, RIH W/ 2-3/8" TBG W/ TALLY IN
HOLE, TO @ 6752', 7 jts, HOOK UP & CIRC WELL W/ WTR, TOO H W/ STANDING TBG IN
DERRICK, RD/FLOOR & TBG EQUIP. ND/ BOP, NU/ FRAC VALVE, TESTED FRAC VALVE &
CSG TO 7500 PSI. READY TO RIG UP BJ FRAC TO FRAC VALVE, SDFN
(24 HR PLAN) PERF & FRAC IN AM.

02/06/08 **FRAC**
Days on Completion: 3
Remarks: (DAY # 3) SAFETY MEETING W/ BJ FRAC CREW
(STG # 1) MIRU CUTTER WIRELINE, RIH W/ PERF GUNS AND PERF THE M.V. @8220'-
8225' 4 SPF, 8034'-8038' 3 SPF, 7954' - 7958' 2 SPF,. USING 3-3/8" EXP GUNS, 23 gm, 0.36
HOLE, 90* PHS, 40 HOLES. WHP 270 #.
RIG UP BJ, PT SURFACE LINE TO 8500 #, BRK DN PERF 4205# @ 3.5 B/M, INJ -P 4700 #,
INJ -RT 44.9 B/M, ISIP = 2870 #, F.G. = .80 , PMPD 3 BBLs 15 % HCL AHEAD OF
INJ., CALC 40/40 PERF OPEN, PMPED 658.8 BBL SLK WTR & 21000 #
OTTAWA 30/50 SAND, ISIP = 3000 # , F.G. = .81, NPI = 130 , MP = 6490 #, MR = 51.3 B/M,
AP = 5317 # , AR = 46.6 B/M. 16000 # OTTAWA SD. 5000 # TLC SD. 23 GALS OF INFO-150,
29 GALS CLAYTREAT 3C, 21 GALS FRW-14, 116 GAL DVE 40 005.COMMENTS = PT-
SURFACE LINES TO 8000#, LOST ONE PUMP ON PAD, CMT TROUBLE.

(STG # 2) RIH W/ BAKER 8K CBP & PERF GUNS, SET CBP @ 7374', PERF THE M.V. @
7340'-7344', 7228'-7232', 4-SPF, & 7122'-7125', 4-SPF, USING 3-3/8" EXP GUNS, 23 gm, 0.36
HOLE, 90* PHS, 41 HOLES, WHP 330 #.BRK DN PERF @ 3093 # @ 4 B/M, INJ -P 4252 #,
INJ -RT 52 B/M, ISIP = 1815 #, F.G. = .69 , CALC 41/41 PERF OPEN, PMPED 1459.9 BBL
SLK WTR & 53036 # 30/50 OTTAWA SD, ISIP = 2545 #, F.G. = .79 , NPI = 730 , MP =
4222 #, MR = 52.3 B/M, AP = 4009 #, AR = 51.8 B/M. 48036 # 30/50 OTTAWA SD., 5000 #
20/40 TLC, 62 GAL CLAYTREAT 3C, 30 GALS FRW-14, 57 GAL INFLO-150, 107GAL DVE
40 005.
COMMENTS __ GOOD JOB __

(STG # 3) RIH W/ BAKER 8K CBP & PERF GUNS, SET CBP @ 6997', PERF THE M.V.
@6964'-6967', & 6923'-6930' , USING 3-3/8" EXP GUNS, 23gm, 0.36 HOLE, 90* PHS, 4-SPF, 40
HOLES, WHP 210 #.BRK DN PERF @ 4376 # @ 5B/M, INJ -P = 4350 #, INJ -RT 49.5 B/M,
ISIP = 2015 #, F.G. = .73, CALC 40/40 PERF OPEN, PMPED 587.5 BBLs SLK WTR & 19094 #
OTTAWA 30/50 SD, ISIP = 2900 #, F.G. = .86 , NPI = 885 , MP = 4376 #, MR = 49.6 B/M, AP
= 4200 #, AR 48.8 B/M, 14094 # 30/50 OTTAWA SD., 5000 # 20/40 TLC SD. 23 GAL

CLAYTREAT 3C, 13 GAL FRW-14, 20 GAL INFLO-150, 67 GAL DVE 40
005.COMMENTS: LOST PUMP #2, 4-PUMPS ON THIS STG.

(STG # 4) RIH W BAKER 8K CBP & PERF GUNS, SET CBP @ 6418', PERF THE WASATCH @ 6378'-6388', USING 3-3/8" EXP GUNS, 23 gm, 0.36 HOLE, 4-SPF, 40 HOLES. WHP 312 #, BRK DN PERF @ 2750 #, @ 5 B/M, INJ - P 4500 #, INJ -RT 51.4 B/M, ISIP = 1900 #, F.G. = .74, CALC 27/40 PERF OPEN, PMPED 623.8 BBLS SLK WTR, 20458 # OTTAWA 30/50 SD, ISIP = 3000 #, F.G. = .91, NPI = 1100, MP = 4515 #, MR = 51.6 B/P, AP = 4347 #, AR = 50.6 B/M. 15458 # 30/30 OTTAWA SD., 5000 # 20/40 TLC SD., 26 GAL CLAYTREAT 3C, 13 GAL FRW-14, 21 GAL INFLO-14, 72 GAL DVE 40 005.COMMENTS: 5- PUMP ON LINE. GOOD JOB. MISS FIRE SETTING CBP @ 6418'. CHANGE OUT CBP.

(STG # 5) RIH W/ BAKER 8K CBP & PERF GUNS, SET CBP @ 5834', PERF THE WASATCH @ 5797'- 5804' & 5666'- 5669', USING 3-3/8" EZP GUN, 23 gm, 0.36 HOLE, 90* PHS, 4-SPF, 40 HOLES. WHP330 #. BRK DN PERF @ 2601 # @ 5 B/M, INJ -P 3300 #, INJ- RT 50.7 B/M, ISIP = 1670 #, F.G. = .73, CALC 40/40 PERF OPEN, PMPED 1112.5 BBLS SLK WTR & 40423 # SAND, ISIP = 2185 #, F.G. = .82, NPI = 515, MP = 3321 #, MR = 50.6 B/M, AP = 3221 #, AR = 50.1 B/M, 35423 # 30/50 OTTAWA SAND, 5000 # 20/40 TLC SAND. 45 GALS CLAYTREAT 3C, 21 GALS FRW-14, 43 GALS INFLO-150, 93 GALS DVE 40 005.COMMENTS GOOD JOB.

(STG # 6) RIH W/ BAKER 8K CBP & PERF GUNS, SET CBP @ 5559', PERF THE WASATCH @ 5314'-5318', 3-SPF & 5522'-5529', 4-SPF, USING 3-3/8" EXP GUN, 23 gm, 0.36 HOLE, 90* PHS, 40 HOLES, WHP = 345 # BRK DN PERF @ 3752 # @ 5 B/M, INJ - P = 3622 #, INJ - RT = 50 B/M, ISIP = 1550 #, F.G. = .73, CALC 40/40 PERF OPEN, PMPED 831.4 BBLS SLK WTR & 31131 # SAND, ISIP = 1955 #, F.G. = .80, NPI = 405, MP = 3635 #, MR = 52.4 B/M, AP = 3382 #, AR = 51.8 B/M. 26131 # 30/50 OTTAWA SAND, 5000 # 20/40 TLC SAND. 31 GALS CLAYTREAT 3C, 13 GALS FRW-14, 26 GALS INFLO-150, 39 GALS DVE 40 005. COMMENTS: LOST ONE PUMP IN JOB.

(KILL PLUG) RIH W/BAKER 8K CBP, SET CBP @ 5264', POOH, RIG DOWN CUTTER & BJ FRAC. TOTAL FLUID = 5274 BBLS SLK WTR, TOTAL SAND = 185,142 #. TOTAL INFLO-150 = 190 GALS, TOTAL DVE 40 005 = 494 GALS. (SCALE INHIB.) TOTAL CLAYTREAT = 218 GALS, TOTAL FRW-14 = 111 GALS. (24 HR. PLAN , TIH W/ POBS, DRILL OUT CBP)

02/07/08

DRILL CBP'S

Days on Completion: 4

Remarks: (DAY # 4) JSA # 4

NO PRESSURE ON WELL, RD/FLOOR, ND/ FRAC VALVE, NU /BOP, RU / WORKING FLOOR & TBG EQUIP., PU/ 3-7/8" BIT ,POBS, XN-NIPPLE, RIH W/ 2-3/8" NEW J55 TBG. TAG CBP @ 5264', RU/ POWER SWIVEL, PRESSURE TESTED BOP TO 3000# OK, ESTB. CIRC DOWN TBG OUT CSG.(DRLG CBP # 1) 5264' DRILL OUT BAKER 8K CBP IN 30 MIN. 25 # DIFF. RIH TAG. SAND @ 5539', C/O 20' SAND, FCP 25 #. (DRLG CBP # 2) 5559', DRILL OUT BAKER 8K CBP IN 5 MIN. 100 # DIFF. RIH TAGSAND @ 5800', C/O 34' SD. FCP = 125 #.(DRLG CBP # 3) 5834', DRILL OUT BAKER 8K CBP IN 5 MIN, 25 # DIFF. RIH TAGSAND @ 6364', C/O 54' SD. FCP = 125 #. (DRLG CBP # 4) 6418', DRILL OUT BAKER 8K CBP IN 10 MIN. 25 # DIFF. RIH TAG SAND @ 6977', C/O 20' SD. FCP = 150 #. (DRLG CBP # 5) 6997', DRILL OUT BAKER 8K CBP IN 10 MIN. 25 # DIFF. RIH TAG SAND @ 7350', C/O 24' SD. FCP = 175 #. (DRLG CBP # 6) 7374', DRILL OUT BAKER 8K CBP IN 10 MIN, 25 # DIFF. RIH TAG PBD @ 8500', CIRC WELL CLEAN. R/D POWER SWIVEL, POOH LAY DOWN 51 JTS ON PIPE TRAILER, LAND TBG ON HANGER W/ 219 JTS EOT @ 6898.19',

RD/ FLOOR & TBG EQUIP, ND/ BOP, NU/ WH, DROP BALL DN TBG, PUMP OFF THE BIT @ 1900 #, WAIT 30 MIN FOR BIT TO FALL TO BTM. OPEN WELL TO FBT ON 20/64 CHOKE,

FTP 500 #, SICP = 700 #, TURN WELL OVER TO FBC @ 6:00 PM W/ 5,083 BBLs WTR LTR.
RACK EQUIP AND DRAIN PUMP AND LINES. SDFWD. Avg. 8 MIN/ PLUG, @ 152' SAND.
FLOWBACK REPORT: CP 1000#, TP 400#, CK 20/64", 50 BWPH, LOAD REC'D 1859 BBLs,
REMAINING LTR 4173 BBLs

02/08/08 **ON SALES:** 0 MCF, 0 BC, 1200 BW, TP: 400#, CP: 1000#, 20/64 CHK, 0 HRS, LP: 0#.

02/09/08 **WENT ON SALES:** @ 2:00 PM, 1000 MCF, 1100 TBG, 1900 CSG, 20/64 CK, 20 BBWH

02/10/08 **FLOWBACK REPORT:** CP 1600#, TP 1100#, CK 20/64", 12 BWPH, LOAD REC'D 318 BBLs,
REMAINING LTR 2730 BBLs

02/09/08 **ON SALES:** 0 MCF, 0 BC, 480 BW, TP: 1000#, CP: 2000#, 20/64 CHK, 0 HRS, LP: 0#.

02/10/08 **ON SALES:** 444 MCF, 0 BC, 480 BW, TP: 1100#, CP: 1800#, 20/64 CHK, 24 HRS, LP: 200#.

02/11/08 **ON SALES:** 1408 MCF, 0 BC, 288 BW, TP: 1100#, CP: 1600#, 20/64 CHK, 0 HRS, LP: 139#.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: November 30, 2000

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU-025880

1a. Type of Well Oil Well Gas Dry Other
b. Type of Completion: New Work Over Deepen Plug Back Diff. Resvr.
Other _____

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.

2. Name of Operator
KERR-MCGEE OIL & GAS ONSHORE LP

8. Lease Name and Well No.
BITTER CREEK 1122-6A

3. Address **1368 SOUTH 1200 EAST, VERNAL, UTAH 84078**
3a. Phone No. (include area code) **(435) 781-7024**

9. API Well No.
4304738120

4. Location of Well (Report locations clearly and in accordance with Federal requirements)*

At surface **NE/NE LOT 1, 654'FNL, 952'FEL**

10. Field and Pool, or Exploratory
NATURAL BUTTES

At top prod. interval reported below

11. Sec., T., R., M., or Block and Survey or Area **SEC. 6, T11S, R22E**

At total depth

12. County or Parish **UINTAH** 13. State **UTAH**

14. Date Spudded **11/18/07** 15. Date T.D. Reached **01/14/08** 16. Date Completed D & A Ready to Prod. **02/09/08**

17. Elevations (DF, RKB, RT, GL)*
5525'GL

18. Total Depth: MD **8600'** TVD **MD 8500'** TVD **MD 8500'** 20. Depth Bridge Plug Set: MD **MD** TVD **TVD**

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)

22. Was well cored? No Yes (Submit copy)
Was DST run? No Yes (Submit copy)
Directional Survey? No Yes (Submit copy)

CBL-CCL-GR, SD, DSN, ACTR

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
20"	14"	36.7#		40'		28 SX			
12 1/4"	9 5/8"	36#		1865'		625 SX			
7 7/8"	4 1/2"	11.6#		8600'		1650 SX			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Set (MD)
2 3/8"	6898'							

25. Producing Intervals

26. Perforation Record

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) WASATCH	5314'	6388'	5314'-6388'	0.36	120	OPEN
B) MESAVERDE	6923'	8225'	6923'-8225'	0.36	121	OPEN
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and type of Material
5314'-6388'	PMP 2568 BBLs SLICK H2O & 92,012# 30/50 SD
6923'-8225'	PMP 2707 BBLs SLICK H2O & 93,130# 30/50 SD

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
02/09/08	02/18/08	24	→	0	2,324	460			FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg. 1061#	Csg. Press. 1061#	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Well Status	
20/64	SI	382#	→	0	2324	460			PRODUCING GAS WELL

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
02/09/08	02/18/08	24	→	0	2324	460			FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg. 1061#	Csg. Press. 1061#	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Well Status	
20/64	SI	382#	→	0	2324	460			PRODUCING GAS WELL

(See instructions and spaces for additional data on reverse side)

RECEIVED
MAR 17 2008

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)

SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
WASATCH MESAVERDE	4027' 6548'	6548'			

32. Additional remarks (include plugging procedure):

33. Circle enclosed attachments:

- 1. Electrical/Mechanical Logs (1 full set req'd.)
- 2. Geologic Report
- 3. DST Report
- 4. Directional Survey
- 5. Sundry Notice for plugging and cement verification
- 5. Core Analysis
- 7. Other:

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) SHEILA UPCHEGO Title SENIOR LAND ADMIN SPECIALIST
 Signature  Date 03/12/08

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU-25880

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
BITTER CREEK 1122-6A

9. API Well No.
4304738120

10. Field and Pool, or Exploratory Area
NATURAL BUTTES

11. County or Parish, State
UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
KERR-McGEE OIL & GAS ONSHORE LP

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
NE/NE, LOT 1, SEC. 6, T11S, R22E 654'FNL, 952'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other COMMINGLE
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandon <input type="checkbox"/> Temporarily Abandon WASATCH AND
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal MESAVERDE

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

THE OPERATOR REQUESTS AUTHORIZATION TO COMMINGLE THE WASATCH AND MESAVERDE FORMATION. THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 02/09/2008.

COPY SENT TO OPERATOR

Date: 5.28.2008

Initials: KS

RECEIVED

APR 15 2008

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) SHELA UPCHEGO	Title SENIOR LAND ADMIN SPECIALIST
Signature <i>[Handwritten Signature]</i>	Date April 7, 2008

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office Accepted by the Utah Division of Oil, Gas and Mining	Federal Approval Of This Action Is Necessary

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Date: 5/29/08
By: [Handwritten Signature]
* Cause No 210-04