

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT
(highlight changes)

APPLICATION FOR PERMIT TO DRILL			5. MINERAL LEASE NO: UTU-73923	6. SURFACE: Federal
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>			7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>			8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: Enduring Resources, LLC			9. WELL NAME and NUMBER: Rainbow 11-24-13-29	
3. ADDRESS OF OPERATOR: 475 17th St., Ste 1500 <small>CITY</small> Denver <small>STATE</small> CO <small>ZIP</small> 80220		PHONE NUMBER: (303) 350-5719	10. FIELD AND POOL, OR WILDCAT: Undesignated	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 661' FSL - 584' FWL AT PROPOSED PRODUCING ZONE: 1985' FSL - 660' FWL			11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 29 11S 24E	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 28.8 miles Southwest of Bonanza, UT			12. COUNTY: Uintah	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 584'	16. NUMBER OF ACRES IN LEASE: 1240	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 acres		
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1000' +	19. PROPOSED DEPTH: 6,490	20. BOND DESCRIPTION: RLB0008031		
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5905' RT-KB	22. APPROXIMATE DATE WORK WILL START: 10/1/2006	23. ESTIMATED DURATION: 20 days		

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT			
20"	14" line pipe	40	3 yards	Ready Mix		
11"	8-5/8" J-55 24#	2,016	Premium Lead	138 sxs	3.50	11.1
			Premium Tail	138 sxs	1.15	15.8
7-7/8"	4-1/2" N-80 11.6#	6,895	Class G	45 sxs	3.3	11.0
			50/50 Poz Class G	856 sxs	1.56	14.3

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAN OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) Evette Bissett TITLE Regulatory Compliance Assistant
SIGNATURE *Evette Bissett* DATE 7/27/2006

(This space for State use only)

API NUMBER ASSIGNED: 43-047-38417

(11/2001)

Federal Approval of this Action is Necessary

(See Instructions on Reverse Side)

Approved by the
Utah Division of
Oil, Gas and Mining
APPROVAL:


Date: 08-14-06
By: *[Signature]*

RECEIVED
JUL 31 2006

DIV. OF OIL, GAS & MINING

T11S, R24E, S.L.B.&M.

ENDURING RESOURCES



WELL LOCATION, THE RAINBOW 11-24-13-29, THE TOP OF HOLE LOCATED AS SHOWN IN THE SW 1/4 SW 1/4, THE BOTTOM HOLE LOCATED AS SHOWN IN THE NW 1/4 SW 1/4 OF SECTION 29, T11S, R24 E, S.L.B.&M. UINTAH COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. No. 189377

STACY W. STEWART
 REGISTERED LAND SURVEYOR
 REGISTRATION No. 1223
 STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE DRAWN: 03-30-06	SURVEYED BY: J.H.	SHEET 2b OF 11
REVISED: 04-07-06	DRAWN BY: F.T.M.	
NOTES:	SCALE: 1" = 1000'	

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min
QUAD (ARCHY BENCH SE)



Enduring Resources

475 17th Street Suite 1500 Denver Colorado 80202
Telephone 303 573-1222 Fax 303 573 0461

July 27, 2006

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, Utah 84114-5801

Attn.: Ms. Diana Whitney

RE: Enduring Resources, LLC
Rainbow 11-24-13-29
SW-SW 29-11S-24E Surface
NW-SW 29-11S-24E BHL
Federal Lease: UTU-73923
Uintah County, Utah

Dear Ms. Whitney:

Enclosed is one original application to drill concerning the above-referenced proposed well.

Enduring Resources, LLC is requesting the Utah Division of Oil, Gas and Mining to hold this application and all future information as confidential.

If any questions arise or additional information is required, please contact me at 303-350-5719.

Very truly yours,

ENDURING RESOURCES, LLC
Evette Bissett
Regulatory Compliance Assistant

Enclosures

RECEIVED
JUL 31 2006
DIV. OF OIL, GAS & MINING

ENDURING RESOURCES, LLC

425 Seventeenth Street, Suite 1500

Denver, Colorado 80202

Telephone: 303-573-1222

Facsimile: 303-573-0461

July 27, 2006

State of Utah
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

Attention: Ms. Diana Whitney

**RE: Exception Well Location
Rainbow 11-24-13-29
SWSW Section 29-T11S-R24E Surface
NWSW 29-T11S-R24E BHL
661' FSL - 504' FWL Surface
1985' FSL - 660' FWL
Lease Serial No.: UTU-73923
Uintah County, Utah**

Dear Ms. Whitney:

Enduring Resources, LLC ("ERLLC") plans to drill the above-referenced well from a multi-well pad to limit surface impact and drilling on steep slopes.

ERLLC is the only leasehold interest owner within 460 feet of any part of the above-referenced proposed well's proposed well bore, therefore,

A. ERLLC also grants itself permission for an exception well location.

In the event there are any other outstanding matters preventing these APD's from being approved, please let me know at your earliest convenience, 303-350-5719 (ebissett@enduringresources.com).

Very truly yours



ENDURING RESOURCES, LLC
Evette Bissett
Regulatory Compliance Assistant

RECEIVED
JUL 31 2006
DIV. OF OIL, GAS & MINING

**Enduring Resources, LLC
Rainbow 11-24-13-29
SW-SW 29-11S-24E Surface
NW-SW 29-11S-24E BHL
Uintah County, Utah
Federal Lease: UTU-73923**

ONSHORE ORDER 1 - DRILLING PLAN

1. Estimated Tops of Geological Markers:

Formation	Depth (K.B.)
Uinta	Surface
Green River	198
Wasatch	2608
Mesaverde	4105

2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:

Substance	Formation	Depth (K.B.)
	KB-Uinta Elevation: 5905'	
Oil / Gas	Green River	198
Oil /Gas	Wasatch	2608
Oil /Gas	Mesaverde	4105
	Estimated TD	6490
	Estimated MD - TD	6895

An 11" hole will be drilled to approximately 2000 feet. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set.

3. Pressure Control Equipment: (3000 psi schematic attached)

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 3,000 psi casinghead, with 3,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 3,000 psi BOPE
- C. Kelly will be equipped with upper and lower Kelly valves.
- D. Testing Procedure: Annular Preventer

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

4. Proposed Casing & Cementing Program:

A. Casing Program: All New

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Depth Set (MD)
20"	14" O.D.				40' (GL)
11"	8-5/8"	24#	J-55	ST&C	0 – 2,016' (KB) est.
7-7/8"	4-1/2"	11.6#	N-80	LT&C	0 – 6895' (KB)

The surface casing will have guide shoe, 1 joint, insert float collar. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints with bowspring centralizers on every other collar (8 centralizers total). Thread lock guide shoe.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

B. Casing Design Parameters:

Depth (MD)	Casing	Collapse(psi)/SF	Burst (psi)/SF	Tension(mlbs)/SF
40' (GL)	14" OD			
2016' (KB)	8-5/8", 24#/ft, J55, STC	1370/1.52(a)	2950/3.28(b)	244/5.81(c)
6895' (KB)	4-1/2", 11.6#/ft, N-80, LTC	6350/1.77(d)	7780/2.36 (e)	223/3.24(f)

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus, no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

PROPOSED CEMENTING PROGRAM

Surface Casing (if well will circulate)-Cemented to surface

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
8-5/8"	Lead	1516	Premium cement + 16% gel + 0.25 pps celloflake	138	25%	11.1	3.50
8-5/8"	Tail	500	Premium cement + 2% CaCl ₂ + 0.25 pps celloflake	138	25%	15.8	1.15

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft³/sx) cement will be premium cement w/ 3% CaCl₂.+0.25 pps celloflake. Volume as required

Surface Casing (if well will not circulate) - Cemented to surface

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
8-5/8"	Lead	500	Premium cement + 2% CaCl ₂ + 0.25 pps celloflake	138	25	15.8	1.15
8-5/8"	Top job	As req.	Premium cement + 3% CaCl ₂ + 0.25 pps celloflake	As Req.		15.8	1.15

Production Casing and Liner - Cemented TD to 300' above base of surface casing

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
4-1/2"	Lead	492	Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender	45	25	11.0	3.3
4-1/2"	Tail	4687	50/50 POZ Class G + 2% gel + 1% CaCl ₂ + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam	856	25	14.3	1.56

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of surface casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. Drilling Fluids (mud) Program:

Interval (MD)	Mud Weight	Fluid Loss	Viscosity	Mud Type
0' - 2016' (KB)		No cntrl		Air/mist
2000'-3000' (KB)	8.4-8.6	No cntrl	28-36	Water
3000'-6895' (KB)	8.8-9.8	8 - 10 ml	32-42	Water/Gel

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

6. Evaluation Program:

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.

Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

7. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No H₂S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 3585 psi (calculated at 0.52psi/foot of hole) and maximum anticipated surface pressure equals approximately 2069 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

8. Anticipated Starting Dates:

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 10 days
- Completion Days - Approximately 10 days
- Anticipate location construction within 30 days of permit issue.

9. Variances:

None anticipated

10. Other:

A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

Single Shot directional surveys will be dropped every 2000 feet to monitor hole angle.

**Directions to the Well Pad for:
Rainbow 11-24-14-29
Rainbow 11-24-13-29**

Pad Location: SWSW of Sec. 29, T11S, R24E, S.L.B.&M.

Beginning at the city of Bonanza, Utah. Leave the city of Bonanza traveling southerly on state highway 45 for a distance of approximately 11.0 Miles where there is a turn-off to the right. Turn right, leaving state highway 45, and proceed westerly for approximately 1.9 miles where the road forks. Keep to the left and bear southwesterly for approximately 4.9 miles where the road forks again. Keep to the left and proceed southwesterly for approximately 8.7 miles (6.9 + 1.8 on Topo "A") where there is an intersection. Turn right and proceed northerly approximately 0.7 miles to a fork in the road. Turn right and proceed northeasterly for approximately 1.6 miles. Turn left onto proposed access and continue southwesterly for approximately 1,410' (± 0.3 mi.) to the proposed 29 well pad.

Enduring Resources, LLC
Rainbow 11-24-13-29
SW-SW 29-11S-24E Surface
NW-SW 29-11S-24E BHL
Uintah County, Utah

Federal Lease: UTU-73923

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Beginning at the city of Bonanza, Utah. Leave the city of Bonanza traveling southerly on state highway 45 for a distance of approximately 11.0 Miles where there is a turn-off to the right. Turn right, leaving state highway 45, and proceed westerly for approximately 1.9 miles where the road forks. Keep to the left and bear southwesterly for approximately 4.9 miles where the road forks again. Keep to the left and proceed southwesterly for approximately 8.7 miles (6.9 + 1.8 on Topo "A") where there is an intersection. Turn right and proceed northerly approximately 0.7 miles to a fork in the road. Turn right and proceed northeasterly for approximately 1.6 miles. Turn left onto proposed access and continue southwesterly for approximately 1,410' (± 0.3 mi.) to the proposed Rainbow 11-24-14-29 well pad. *(This is a two-well pad.)*

2. Planned Access Roads:

The proposed access road will be approximately 1,410 feet of new construction. Please refer to Topo Map "B" for the takeoff point for the new ON-LEASE road construction.

Access will be using the Oil Springs Gas Field Road into the section 29 then on to the 1,410 feet of new access road (all on-lease). This is the same road use to access the Rockhopper Fed 11-24-23-29. (The new access road is also the same new road to the Rainbow 14-24-14-29, a two-well pad.)

The proposed access road will be utilized to transport personnel, equipment and supplies to and from the proposed well site during drilling, completion and production operations. The road will be utilized year round.

The access road will be crowned 2% to 3%, ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet right-of-way. Maximum grade of road is 5% or less. Graveling or capping the roadbed will be performed as necessary to provided a well constructed, safe road. No fence crossings, culverts, turnouts, cattle guards or major cuts and fills are required. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. **Location of Existing Wells within a One-Mile radius (See "Topo" Map "C" attached):**

The following wells are wells located within a one (1) mile *or greater radius* of the proposed location.

- a. None: Water Wells:
- b. None: Injection Wells:
- c. (1): Producing Wells:
 - 1. Rockhopper 11-24-23-29, NESW Sec 29
- d. (1): Drilling Wells:
 - 1. Archy Benchj 11-24-12-32
- e. None: Shut-in Wells:
- f. None: Temporarily Abandoned Wells:
- g. None: Disposal Wells:
- h. (1): Abandoned Wells:
 - 1. Continental 1, SESW Sec 30
- i. None: Dry Holes:
- j. None: Observation Wells:
- k. (8): Pending (staked) Wells:
 - 1. Enduring Resources has eight other wells staked in this section

4. **Location of Existing and/or Proposed Facilities:**

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank and be independent of the back cut.

All permanent (on site for six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the rocky Mountain Five State Inter-Agency Committee

All facilities will be painted within 6 months of installation. The color shall be Dark Olive Black. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Gas Gathering Pipeline:	ON-LEASE	1,410'	BLM
	OFF-LEASE	-0-	n/a

If the well is capable of economic production, a surface gas gathering line and related equipment shall be installed. The surface gas gathering line shall be in use year round. A total of approximately less than 1,410 feet of surface gas gathering pipeline (4") shall be laid on the surface to minimize surface disturbance:

The proposed pipeline will begin at the well site; be laid on the north side of the access road, easterly, and tie directly into pipeline located next to Oil Springs Gas Field Road (pipeline to the Rockhopper Fed 11-24-23-29 Well).

The meter run will be housed. The gas gathering line will be buried or anchored down from the wellhead to the meter.

Upon plugging and abandonment, the gas gathering line will be removed and the disturbed area will be re-contoured and restored as near as practical to the original condition. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

5. Location and Type of Water Supply:

Whenever practical, water will be obtained from Enduring Resources LLC Water Right Number 49-2215 or Water Right Number 49-2216 (*See Townships of permitted Use below). If those sources are not available, a new water source shall be submitted prior to commencing operations. (These permits have one-year terms and then must be renewed)
*Enduring Water Permits' Townships of Use:

T10S-R22E	T11S-R22E	T12S-R22E
T10S-R23E	T11S-R23E	T12S-R23E
T10S-R24E	<u>T11S-R24E</u>	T12S-R24E

Water will be hauled to the location over the roads marked on "Topo" Maps "A" and "B."

No water well is to be drilled on this lease.

6 Source of Construction Materials:

Surface and subsoil materials in the immediate area will be utilized for location and access road construction.

Any gravel will be obtained from a commercial source; however, gravel sized rock debris associated with location and access road construction may be used as access road surfacing material.

7. Methods of Handling Waste Materials:

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break or allow discharge of liquids.

The reserve pit will be lined with ¼ felt and a minimum of 16 mm plastic with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the will be disposed of in the pit.

A chemical portable toilet will be furnished with the drilling rig. The toilet will be replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

Garbage, trash and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well.

Produced oil will be stored in an oil tank and then hauled by truck to a crude purchaser facility. Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to an approved disposal site.

8. Ancillary Facilities:

During drilling operations, approximately 20 days, the site will be a manned camp. Three or four additional trailers will be on location to serve as the crews' housing and eating facilities. These will be located on the perimeter of the pad site within the topsoil stockpiles. Refer to Sheet 4.

9. Well Site Layout: (Refer to Sheets #2, #3, and #4)

The attached Location Layout Diagrams described drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s) and surface material stockpiles(s).

Please see the attached diagram for rig orientation and access roads.

The top soil will be windrowed rather than piled. It will be reseeded and track walker at the time the location is constructed. Seeding will be with the determined during the onsite. (Refer to "Seed Mixture for Windrowed Top Soil Will included:" following herein.

The top soil removed from the pit area will be store separately and will not be reseeded until the pit is reclaimed.

All pits shall be fence to the following minimum standards:

- a. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches over the new wire. Total height of the fence shall be at least 42 inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two fence posts shall be no greater than 16 feet.
- e. All wire shall be stretched by, using a stretching device, before it is attached to corner posts.
- f. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.
- g. Location size may change prior to drilling the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling, the location will be re-surveyed and a Form 9 will be submitted.

10. Plans for Surface Reclamation:**Producing Location:**

- a. Immediately upon well completion **of the last well to be drilled from this pad**, the location and surrounding area will be cleared of all unused tubing, equipment, materials, trash and debris not required for production.
- b. Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 40CFR 3162.7.
- c. Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.
- d. The reserve pit and that portion of the location not needed for production (**and drilling the other directional wells**) facilities / operations will be re-contoured to the approximated natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.
- e. To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface 3 feet above surrounding round surface to allow the reclaimed pit area to drain effectively.
- f. Upon completion of back filling, leveling and re-contouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

- i. Abandoned well sites, roads and other disturbed areas will be restored as nearly as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions and re-establishment of vegetation as specified.
- ii. All disturbed surfaces will be re-contoured to the approximated natural contours with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

Seed Mixture for Windrowed Top Soil Will Included:

To be provided by the BLM

11. Surface Ownership: Location, Access and Pipeline Route:

Wellsite: Bureau of Land Management

Access: Bureau of Land Management

Pipeline: Bureau of Land Management

12. Other Information**On-site Inspection for Location, Access and Pipeline Route:**

The on-site was conducted on June 29, 2006

Attending were:

1. Melissa Hawk BLM
2. Brandon McDonald BLM
3. Mike Stewart Ponderosa Construction
4. Chris Stewart Tristate
5. Cameron Stewart Tristate
6. Doug Hammond Enduring Resources

Special Conditions of Approval:

None for this well(s).

Archeology:

- a. A Cultural Resource Inventory Report is pending and to be prepared by Montgomery Archaeological Consultants.

Paleontology:

- b. A Paleontology Reconnaissance Report is pending and to be prepared by Intermountain Paleo-Consulting.

If, during operations, any archaeological or historical sites, or any objects of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites will be suspended and the discovery reported promptly to the surface management agency.

13, Lessee's or Operator's Representatives:**Representatives:**

Alvin R. (Al) Arlian
Landman – Regulatory Specialist
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, Colorado 80202
Office Tel: 303-350-5114
Fax Tel: 303-573-0461
aarlian@enduringresources.com

Teme Singleton
Vice President – Operations
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, Colorado 80202
Office Tel: 303-350-5711
Fax Tel: 303-573-0461
tsingleton@enduringresources.com

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his/her/its subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her/its contractor shall contact the BLM office at (435) 781-4400 forty-eight (48) hours prior to construction activities.


The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill-site and access route, that I am familiar with the conditions which presently exist, that the statements made in this plan are, to the best of my knowledge and belief, true and correct, and that the work associated with the operation proposed herein will be performed by Enduring Resources, LLC and its contractors and subcontractors in conformity with this plan and terms and conditions with this plan and the terms and conditions under which it is approved.

Please be advised that Enduring Resources, LLC is considered to be the operator of the Rainbow 11-24-13-29 Well; with a surface location in the SWSW Section 29, Township 11 South, Range 24 East; and with a BHL in the NWSW Section 29, Township 11 South, Range 24 East; Lease #:UTU-73923 Uintah County, Utah; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by BLM Statewide Oil & Gas Lease Bond No. UTB000173 and State of Utah , Division of Oil, Gas & Mining Surety Bond No. RLB0008031

ENDURING RESOURCES, LLC




Alvin (Al) R. Arlian
Landman – Regulatory Specialist


July 27, 2006

ENDURING RESOURCES, LLC

TYPICAL 3,000 p.s.i. BLOWOUT PREVENTER SCHEMATIC



TYPICAL 3,000 p.s.i. CHOKE MANIFOLD SCHEMATIC





ENDURING RESOURCES
Rainbow 11-24-13-29
SW/SW Sec. 29, T11S, R24E
Uintah County, Utah



SECTION DETAILS										
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.00	0.00	3.46	0.00	0.00	0.00	0.00	0.00	0.00	
2	2050.00	0.00	3.46	2050.00	0.00	0.00	0.00	0.00	0.00	KOP
3	2849.17	39.96	3.46	2785.94	267.07	16.15	5.00	3.46	267.56	End Build
4	3976.52	39.96	3.46	3650.07	989.77	59.84	0.00	0.00	991.58	Start Drop
5	4975.48	0.00	3.46	4570.00	1323.61	80.03	4.00	180.00	1326.03	End Drop
6	6895.48	0.00	3.46	6490.00	1323.61	80.03	0.00	3.46	1326.03	TD



RKB Elevation: 5905.0
 Ground Elevation: 5890.2

WELL DETAILS							
Name	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
Rainbow 11-24-13-29	0.00	0.00	7113763.58	2268878.11	39°49'38.950N	109°15'43.120W	N/A

FIELD DETAILS
 Uintah, Utah
 Utah Central Zone
 U.S.A.

Geodetic System: US State Plane Coordinate System 1983
 Ellipsoid: GRS 1980
 Zone: Utah, Central Zone
 Magnetic Model: igr2005

System Datum: Mean Sea Level
 Local North: True North

SITE DETAILS
 SW/SW 29-11S-24E
 Sec. 29, T11S, R24E, Uintah County, Utah
 661 FSL & 584 FWL



Site Centre Latitude: 39°49'38.950N
 Longitude: 109°15'43.120W

Ground Level: 5890.20
 Positional Uncertainty: 0.00
 Convergence: 1.43

TARGET DETAILS				
Name	TVD	+N/-S	+E/-W	Shape
11-24-13-29 Target	6490.00	1323.61	80.03	Rectangle (400x400)

CASING DETAILS				
No.	TVD	MD	Name	Size
1	2000.00	2000.00	9 5/8" Surface	9.625

FORMATION TOP DETAILS			
No.	TVDPath	MDPath	Formation
1	198.00	198.00	Green River
2	2608.00	2632.80	Wasatch
3	4105.00	4501.90	Mesaverde



Vertical Section at 3.46° [1000ft/in]

Created By: Scott Wallace 7/26/06

West(-)/East(+) [500ft/in]

Weatherford International Planning Report

Company: Enduring Resources	Date: 7/26/2006	Time: 12:56:29	Page: 1
Field: Uintah, Utah	Co-ordinate(NE) Reference: Well: Rainbow 11-24-13-29, True North		
Site: SW/SW 29-11S-24E	Vertical (TVD) Reference: SITE 5905.0		
Well: Rainbow 11-24-13-29	Section (VS) Reference: Well (0.00N,0.00E,3.46Azi)		
Wellpath: 1	Plan: Plan #1		

Field: Uintah, Utah Utah Central Zone U.S.A.	Map Zone: Utah, Central Zone
Map System: US State Plane Coordinate System 1983	Coordinate System: Well Centre
Geo Datum: GRS 1980	Geomagnetic Model: igrf2005
Sys Datum: Mean Sea Level	

Site: SW/SW 29-11S-24E
Sec. 29, T11S, R24E, Uintah County, Utah
661 FSL & 584 FWL

Site Position:	Northing: 7113763.58 ft	Latitude: 39 49 38.950 N
From: Geographic	Easting: 2268878.11 ft	Longitude: 109 15 43.120 W
Position Uncertainty: 0.00 ft		North Reference: True
Ground Level: 5890.20 ft		Grid Convergence: 1.43 deg

Well: Rainbow 11-24-13-29	Slot Name:
Well Position: +N/-S 0.00 ft	Northing: 7113763.58 ft
+E/-W 0.00 ft	Easting: 2268878.11 ft
Position Uncertainty: 0.00 ft	Latitude: 39 49 38.950 N
	Longitude: 109 15 43.120 W

Wellpath: 1	Drilled From: Surface	Tie-on Depth: 0.00 ft	Above System Datum: Mean Sea Level
Current Datum: SITE	Height: 5905.00 ft	Declination: 11.57 deg	Mag Dip Angle: 65.90 deg
Magnetic Data: 7/26/2006		+E/-W: ft	Direction: deg
Field Strength: 52813 nT			
Vertical Section: Depth From (TVD) ft	+N/-S ft	ft	deg
6490.00	0.00	0.00	3.46

Plan: Plan #1	Date Composed: 7/26/2006
Principal: Yes	Version: 1
	Tied-to: From Surface

Plan Section Information

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg	Target
0.00	0.00	3.46	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2050.00	0.00	3.46	2050.00	0.00	0.00	0.00	0.00	0.00	0.00	
2849.17	39.96	3.46	2785.94	267.07	16.15	5.00	5.00	0.00	3.46	
3976.52	39.96	3.46	3650.07	989.77	59.84	0.00	0.00	0.00	0.00	
4975.48	0.00	3.46	4570.00	1323.61	80.03	4.00	-4.00	0.00	180.00	
6895.48	0.00	3.46	6490.00	1323.61	80.03	0.00	0.00	0.00	3.46	11-24-13-29 Target

Section 1 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
0.00	0.00	3.46	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2000.00	0.00	3.46	2000.00	0.00	0.00	0.00	0.00	0.00	0.00	3.46
2050.00	0.00	3.46	2050.00	0.00	0.00	0.00	0.00	0.00	0.00	3.46

Section 2 : Start Build 5.00

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
2100.00	2.50	3.46	2099.98	1.09	0.07	1.09	5.00	5.00	0.00	0.00
2200.00	7.50	3.46	2199.57	9.79	0.59	9.80	5.00	5.00	0.00	0.00
2300.00	12.50	3.46	2298.02	27.11	1.64	27.16	5.00	5.00	0.00	0.00
2400.00	17.50	3.46	2394.58	52.94	3.20	53.04	5.00	5.00	0.00	0.00
2500.00	22.50	3.46	2488.52	87.07	5.26	87.23	5.00	5.00	0.00	0.00
2600.00	27.50	3.46	2579.12	129.24	7.81	129.48	5.00	5.00	0.00	0.00
2632.80	29.14	3.46	2608.00	144.77	8.75	145.04	5.00	5.00	0.00	0.00
2700.00	32.50	3.46	2665.70	179.13	10.83	179.46	5.00	5.00	0.00	0.00
2800.00	37.50	3.46	2747.59	236.37	14.29	236.80	5.00	5.00	0.00	0.00
2849.17	39.96	3.46	2785.94	267.07	16.15	267.56	5.00	5.00	0.00	0.00

Weatherford International Planning Report

Company: Enduring Resources Field: Uintah, Utah Site: SW/SW 29-11S-24E Well: Rainbow 11-24-13-29 Wellpath: 1	Date: 7/26/2006 Co-ordinate(NE) Reference: Vertical (TVD) Reference: Section (VS) Reference: Plan:	Time: 12:56:29 Well: Rainbow 11-24-13-29, True North SITE: 5905.0 Well (0.00N,0.00E,3.46Azi): Plan #1	Page: 2
---	---	--	----------------

Section 2 : Start Build 5.00

MD	Incl	Azim	TVD	+N/-S	+E/-W	VS	DLS	Build	Turn	TFO

Section 3 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
2900.00	39.96	3.46	2824.91	299.66	18.12	300.20	0.00	0.00	0.00	0.00
3000.00	39.96	3.46	2901.56	363.76	21.99	364.43	0.00	0.00	0.00	0.00
3100.00	39.96	3.46	2978.21	427.87	25.87	428.65	0.00	0.00	0.00	0.00
3200.00	39.96	3.46	3054.86	491.98	29.75	492.87	0.00	0.00	0.00	0.00
3300.00	39.96	3.46	3131.51	556.08	33.62	557.10	0.00	0.00	0.00	0.00
3400.00	39.96	3.46	3208.16	620.19	37.50	621.32	0.00	0.00	0.00	0.00
3500.00	39.96	3.46	3284.81	684.29	41.37	685.54	0.00	0.00	0.00	0.00
3600.00	39.96	3.46	3361.46	748.40	45.25	749.77	0.00	0.00	0.00	0.00
3700.00	39.96	3.46	3438.11	812.51	49.13	813.99	0.00	0.00	0.00	0.00
3800.00	39.96	3.46	3514.77	876.61	53.00	878.21	0.00	0.00	0.00	0.00
3900.00	39.96	3.46	3591.42	940.72	56.88	942.44	0.00	0.00	0.00	0.00
3976.52	39.96	3.46	3650.07	989.77	59.84	991.58	0.00	0.00	0.00	0.00

Section 4 : Start Drop -4.00

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
4000.00	39.02	3.46	3668.19	1004.68	60.74	1006.51	4.00	-4.00	0.00	-180.00
4100.00	35.02	3.46	3748.02	1064.76	64.38	1066.71	4.00	-4.00	0.00	180.00
4200.00	31.02	3.46	3831.85	1119.15	67.67	1121.19	4.00	-4.00	0.00	180.00
4287.31	27.53	3.46	3908.00	1161.75	70.24	1163.88	4.00	-4.00	0.00	180.00
4300.00	27.02	3.46	3919.28	1167.56	70.59	1169.69	4.00	-4.00	0.00	-180.00
4400.00	23.02	3.46	4009.88	1209.76	73.14	1211.97	4.00	-4.00	0.00	180.00
4500.00	19.02	3.46	4103.20	1245.56	75.31	1247.83	4.00	-4.00	0.00	180.00
4501.90	18.94	3.46	4105.00	1246.18	75.35	1248.45	4.00	-4.00	0.00	-180.00
4600.00	15.02	3.46	4198.80	1274.77	77.07	1277.10	4.00	-4.00	0.00	180.00
4700.00	11.02	3.46	4296.21	1297.25	78.43	1299.62	4.00	-4.00	0.00	180.00
4800.00	7.02	3.46	4394.96	1312.90	79.38	1315.29	4.00	-4.00	0.00	180.00
4900.00	3.02	3.46	4494.55	1321.63	79.91	1324.04	4.00	-4.00	0.00	180.00
4975.48	0.00	3.46	4570.00	1323.61	80.03	1326.03	4.00	-4.00	0.00	-180.00

Section 5 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
5000.00	0.00	3.46	4594.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5100.00	0.00	3.46	4694.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5200.00	0.00	3.46	4794.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5300.00	0.00	3.46	4894.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5400.00	0.00	3.46	4994.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5500.00	0.00	3.46	5094.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5600.00	0.00	3.46	5194.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5700.00	0.00	3.46	5294.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5800.00	0.00	3.46	5394.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
5900.00	0.00	3.46	5494.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6000.00	0.00	3.46	5594.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6100.00	0.00	3.46	5694.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6200.00	0.00	3.46	5794.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6300.00	0.00	3.46	5894.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6400.00	0.00	3.46	5994.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6500.00	0.00	3.46	6094.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6600.00	0.00	3.46	6194.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6700.00	0.00	3.46	6294.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6800.00	0.00	3.46	6394.52	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46
6895.48	0.00	3.46	6490.00	1323.61	80.03	1326.03	0.00	0.00	0.00	3.46

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: SW/SW 29-11S-24E
Well: Rainbow 11-24-13-29
Wellpath: 1

Date: 7/26/2006
Co-ordinate(NE) Reference: Well: Rainbow 11-24-13-29, True North
Vertical (TVD) Reference: SITE 5905.0
Section (VS) Reference: Well (0.00N,0.00E,3.46Azi)
Plan: Plan #1

Page: 3

Survey

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	Tool/Comment
2000.00	0.00	3.46	2000.00	0.00	0.00	0.00	0.00	0.00	0.00	9 5/8" Surface
2050.00	0.00	3.46	2050.00	0.00	0.00	0.00	0.00	0.00	0.00	KOP
2100.00	2.50	3.46	2099.98	1.09	0.07	1.09	5.00	5.00	0.00	MWD
2200.00	7.50	3.46	2199.57	9.79	0.59	9.80	5.00	5.00	0.00	MWD
2300.00	12.50	3.46	2298.02	27.11	1.64	27.16	5.00	5.00	0.00	MWD
2400.00	17.50	3.46	2394.58	52.94	3.20	53.04	5.00	5.00	0.00	MWD
2500.00	22.50	3.46	2488.52	87.07	5.26	87.23	5.00	5.00	0.00	MWD
2600.00	27.50	3.46	2579.12	129.24	7.81	129.48	5.00	5.00	0.00	MWD
2632.80	29.14	3.46	2608.00	144.77	8.75	145.04	5.00	5.00	0.00	Wasatch
2700.00	32.50	3.46	2665.70	179.13	10.83	179.46	5.00	5.00	0.00	MWD
2800.00	37.50	3.46	2747.59	236.37	14.29	236.80	5.00	5.00	0.00	MWD
2849.17	39.96	3.46	2785.94	267.07	16.15	267.56	5.00	5.00	0.00	End Build
2900.00	39.96	3.46	2824.91	299.66	18.12	300.20	0.00	0.00	0.00	MWD
3000.00	39.96	3.46	2901.56	363.76	21.99	364.43	0.00	0.00	0.00	MWD
3100.00	39.96	3.46	2978.21	427.87	25.87	428.65	0.00	0.00	0.00	MWD
3200.00	39.96	3.46	3054.86	491.98	29.75	492.87	0.00	0.00	0.00	MWD
3300.00	39.96	3.46	3131.51	556.08	33.62	557.10	0.00	0.00	0.00	MWD
3400.00	39.96	3.46	3208.16	620.19	37.50	621.32	0.00	0.00	0.00	MWD
3500.00	39.96	3.46	3284.81	684.29	41.37	685.54	0.00	0.00	0.00	MWD
3600.00	39.96	3.46	3361.46	748.40	45.25	749.77	0.00	0.00	0.00	MWD
3700.00	39.96	3.46	3438.11	812.51	49.13	813.99	0.00	0.00	0.00	MWD
3800.00	39.96	3.46	3514.77	876.61	53.00	878.21	0.00	0.00	0.00	MWD
3900.00	39.96	3.46	3591.42	940.72	56.88	942.44	0.00	0.00	0.00	MWD
3976.52	39.96	3.46	3650.07	989.77	59.84	991.58	0.00	0.00	0.00	Start Drop
4000.00	39.02	3.46	3668.19	1004.68	60.74	1006.51	4.00	-4.00	0.00	MWD
4100.00	35.02	3.46	3748.02	1064.76	64.38	1066.71	4.00	-4.00	0.00	MWD
4200.00	31.02	3.46	3831.85	1119.15	67.67	1121.19	4.00	-4.00	0.00	MWD
4287.31	27.53	3.46	3908.00	1161.75	70.24	1163.88	4.00	-4.00	0.00	Entry Point
4300.00	27.02	3.46	3919.28	1167.56	70.59	1169.69	4.00	-4.00	0.00	MWD
4400.00	23.02	3.46	4009.88	1209.76	73.14	1211.97	4.00	-4.00	0.00	MWD
4500.00	19.02	3.46	4103.20	1245.56	75.31	1247.83	4.00	-4.00	0.00	MWD
4501.90	18.94	3.46	4105.00	1246.18	75.35	1248.45	4.00	-4.00	0.00	Mesaverde
4600.00	15.02	3.46	4198.80	1274.77	77.07	1277.10	4.00	-4.00	0.00	MWD
4700.00	11.02	3.46	4296.21	1297.25	78.43	1299.62	4.00	-4.00	0.00	MWD
4800.00	7.02	3.46	4394.96	1312.90	79.38	1315.29	4.00	-4.00	0.00	MWD
4900.00	3.02	3.46	4494.55	1321.63	79.91	1324.04	4.00	-4.00	0.00	MWD
4975.48	0.00	3.46	4570.00	1323.61	80.03	1326.03	4.00	-4.00	0.00	End Drop
5000.00	0.00	3.46	4594.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5100.00	0.00	3.46	4694.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5200.00	0.00	3.46	4794.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5300.00	0.00	3.46	4894.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5400.00	0.00	3.46	4994.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5500.00	0.00	3.46	5094.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5600.00	0.00	3.46	5194.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5700.00	0.00	3.46	5294.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5800.00	0.00	3.46	5394.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
5900.00	0.00	3.46	5494.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6000.00	0.00	3.46	5594.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6100.00	0.00	3.46	5694.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6200.00	0.00	3.46	5794.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6300.00	0.00	3.46	5894.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6400.00	0.00	3.46	5994.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6500.00	0.00	3.46	6094.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6600.00	0.00	3.46	6194.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD

Weatherford International

Planning Report

Company: Enduring Resources Field: Uintah, Utah Site: SW/SW 29-11S-24E Well: Rainbow 11-24-13-29 Wellpath: 1	Date: 7/26/2006 Co-ordinate(N/E) Reference: Vertical (TVD) Reference: Section (VS) Reference: Plan:	Time: 12:56:29 Well: Rainbow 11-24-13-29, True North SITE: 5905.0 Well (0.00N,0.00E,3.46Azi): Plan #1	Page: 4
---	--	--	----------------

Survey

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	Tool/Comment
6700.00	0.00	3.46	6294.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6800.00	0.00	3.46	6394.52	1323.61	80.03	1326.03	0.00	0.00	0.00	MWD
6895.48	0.00	3.46	6490.00	1323.61	80.03	1326.03	0.00	0.00	0.00	11-24-13-29 Target

Targets

Name	Description		TVD ft	+N/-S ft	+E/-W ft	Map Northing ft	Map Easting ft	← Latitude →			← Longitude →				
	Dip.	Dir.						Deg	Min	Sec	Deg	Min	Sec		
11-24-13-29 Target -Rectangle (400x400) -Plan hit target			6490.00	1323.61	80.03	7115088.78	2268924.99	39	49	52.032	N	109	15	42.094	W

Casing Points

MD ft	TVD ft	Diameter in	Hole Size in	Name
2000.00	2000.00	9.625	12.250	9 5/8" Surface

Formations


MD ft	TVD ft	Formations	Lithology	Dip Angle deg	Dip Direction deg
198.00	198.00	Green River		0.00	0.00
2632.80	2608.00	Wasatch		0.00	0.00
4501.90	4105.00	Mesaverde		0.00	0.00

Annotation

MD ft	TVD ft	
2050.00	2050.00	SHL (661 FSL & 584 FWL)
2849.17	2785.94	KOP
3976.52	3650.07	End Build
4287.31	3908.00	Start Drop
4975.48	4570.00	Entry Point
6895.48	6490.00	End Drop
		TD

ENDURING RESOURCES

*WELL PAD INTERFERENCE PLAT
RAINBOW 11-24-14-29 & 11-24-13-29
Section 29, T11S, R24E, S.L.B.&M.*




TOP HOLE FOOTAGES

*RAINBOW 11-24-14-29
661' FSL & 604' FWL
RAINBOW 11-24-13-29
661' FSL & 584' FWL*

BOTTOM HOLE FOOTAGES

*RAINBOW 11-24-14-29
VERTICAL
RAINBOW 11-24-13-29
1985' FSL & 660' FWL*



Note:

Bearings are derived using true North.

*RELATIVE COORDINATES
From top hole to bottom hole*

WELL	NORTH	EAST
14-29	N/A	N/A
13-29	1324'	80'

*LATITUDE & LONGITUDE
Surface position of Wells (NAD 83)*

WELL	LATITUDE	LONGITUDE
14-29	39° 49' 38.95"	109° 15' 42.86"
13-29	39° 49' 38.95"	109° 15' 43.12"

SURVEYED BY: J.H. DATE DRAWN: 04-07-06

DRAWN BY: F.T.M. SCALE: 1" = 60'

NOTES:



Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

SHEET
3
OF 11

ENDURING RESOURCES

RAINBOW 11-24-14-29 & 11-24-13-29

Section 29, T11S, R24E, S.L.B.&M.



WELL HEAD:
UNGRADED = 5890.2'
FIN. GRADE = 5888.9'

Note:
Flare pit is to be located at least 100' from well head.

REFERENCE POINTS

175' NORTHERLY = 5877.4'
225' NORTHERLY = 5880.1'

SURVEYED BY: J.H.	DATE DRAWN: 04-07-06
DRAWN BY: F.T.M.	SCALE: 1" = 60'
NOTES:	





Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

SHEET
4
OF 11

ENDURING RESOURCES

CROSS SECTIONS

RAINBOW 11-24-14-29 & 11-24-13-29



NOTE:
UNLESS OTHERWISE NOTED
CUT SLOPES ARE AT 1:1
FILL SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	10,090	10,090	Topsoil is not included in Pad Cut	0
PIT	5,390	0		5,390
TOTALS	15,480	10,090	1,890	5,390

SURVEYED BY: J.H. DATE DRAWN: 04-07-06
DRAWN BY: F.T.M. SCALE: 1" = 60'
NOTES:


Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

SHEET
5
OF 11

ENDURING RESOURCES

TYPICAL RIG LAYOUT

RAINBOW 11-24-14-29 & 11-24-13-29



FLARE PIT

Note:
Flare pit is to be located at least 100' from well head.

DATA


SURVEYED BY: J.H.	DATE DRAWN: 04-07-06
DRAWN BY: F.T.M.	SCALE: 1" = 60'
NOTES:	

Tri State (435) 781-2501
 Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

ENDURING RESOURCES

PRODUCTION SCHEMATIC

RAINBOW 11-24-14-29 & 11-24-13-29




FLARE PIT

Note:
Flare pit is to be located at least 100' from well head.

SURVEYED BY: J.H.	DATE DRAWN: 04-07-06
DRAWN BY: F.T.M.	SCALE: 1" = 60'
NOTES:	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

SHEET
7
OF 11




Proposed Location
Rainbow 11-24-14-29
Rainbow 11-24-13-29

See Topo "B"


ENDURING RESOURCES

Rainbow 11-24-14-29
Rainbow 11-24-13-29
 Pad Location: SWSW of Sec. 29, T11S, R24E, S.L.B.&M.




Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 : 100,000
 DRAWN BY: mw
 DATE: 07-19-2006


Legend

 Existing Road
 Proposed Access

TOPOGRAPHIC MAP



SHEET
8
 OF 11



ENDURING RESOURCES

Rainbow 11-24-14-29
Rainbow 11-24-13-29

Pad Location: SWSW of Sec. 29, T11S, R24E, S.L.B.&M.




Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 07-19-2006

Legend

- Location
- One-Mile Radius

TOPOGRAPHIC MAP **SHEET**
"C" **10**
OF 11



**Proposed Location
Rainbow 11-24-14-29
Rainbow 11-24-13-29**

**Proposed Gas
Pipeline ±1,410'**

**Pipeline
Tie-in**



ENDURING RESOURCES

**Rainbow 11-24-14-29
Rainbow 11-24-13-29**

Pad Location: SWSW of Sec. 29, T11S, R24E, S.L.B.&M.



**Tri-State
Land Surveying Inc.**
(435) 781-2501

180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: mw

DATE: 07-19-2006

Legend


- Roads
- Proposed Gas Line

TOPOGRAPHIC MAP

"D"

SHEET

11
OF 11



CENTER STAKE

Date Photographed: 04/03/2006


Date Drawn: 07/19/2006

Drawn By: mw

**LOOKING NORTH
ACCESS**


ENDURING RESOURCES
Rainbow 11-24-14-29 & 11-24-13-29
Pad Location:
SWSW of Sec. 29, T11S, R24E, S.L.B.&M.


**Tri-State
Land Surveying Inc.**
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078





NORTH


ENDURING RESOURCES
Rainbow 11-24-14-29 & 11-24-13-29
Pad Location:
SWSW of Sec. 29, T11S, R24E, S.L.B.&M.

Date Photographed: 04/03/2006


Date Drawn: 07/19/2006

Drawn By: mw


Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

EAST





SOUTH


ENDURING RESOURCES
Rainbow 11-24-14-29 & 11-24-13-29
Pad Location:
SWSW of Sec. 29, T11S, R24E, S.L.B.&M.

Date Photographed: 04/03/2006

Date Drawn: 07/19/2006

Drawn By: mw


Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

WEST



**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 07/31/2006

API NO. ASSIGNED: 43-047-38417

WELL NAME: RAINBOW 11-24-13-29

OPERATOR: ENDURING RESOURCES, LLC (N2750)

CONTACT: EVETTE BISSETT

PHONE NUMBER: 303-350-5719

PROPOSED LOCATION:

SWSW 29 110S 240E

SURFACE: 0661 FSL 0584 FWL

BOTTOM: 1985 FSL 0660 FWL

COUNTY: UINTAH

LATITUDE: 39.82764 LONGITUDE: -109.2611

UTM SURF EASTINGS: 648813 NORTHINGS: 4409864

FIELD NAME: UNDESIGNATED (2)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-73923

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: MVRD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. RLB0008031)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 49-2215)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)


LOCATION AND SITING:

- R649-2-3.
Unit: _____
- R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit
Board Cause No: _____
Eff Date: _____
Siting: _____
- R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1. Federal Approval

2. Spacing Slip



OPERATOR: ENDURING RES LLC (N2750)

SEC: 29 T.11S R. 24E

FIELD: UNDESIGNATED (002)


COUNTY: UINTAH

SPACING: R649-3-11 / DIRECTIONAL DRILLING

- Field Status**
- ABANDONED
 - ACTIVE
 - COMBINED
 - INACTIVE
 - PROPOSED
 - STORAGE
 - TERMINATED

- Unit Status**
- EXPLORATORY
 - GAS STORAGE
 - NF PP OIL
 - NF SECONDARY
 - PENDING
 - PI OIL
 - PP GAS
 - PP GEOTHERML
 - PP OIL
 - SECONDARY
 - TERMINATED

- Wells Status**
- GAS INJECTION
 - GAS STORAGE
 - LOCATION ABANDONED
 - NEW LOCATION
 - PLUGGED & ABANDONED
 - PRODUCING GAS
 - PRODUCING OIL
 - SHUT-IN GAS
 - SHUT-IN OIL
 - TEMP. ABANDONED
 - TEST WELL
 - WATER INJECTION
 - WATER SUPPLY
 - WATER DISPOSAL
 - DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 11-AUGUST-2006



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

August 14, 2006

Enduring Resources, LLC
475 17th St., Ste. 1500
Denver, CO 80202

Re: Rainbow 11-24-13-29 Well, Surface Location 661' FSL, 584' FWL, SW SW,
Sec. 29, T. 11 South, R. 24 East, Bottom Location 1985' FSL, 660' FWL,
NW SW, Sec. 29, T. 11 South, R. 24 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38417.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Enduring Resources, LLC
Well Name & Number Rainbow 11-24-13-29
API Number: 43-047-38417
Lease: UTU-73923

Surface Location: SW SW **Sec.** 29 **T.** 11 South **R.** 24 East
Bottom Location: NW SW **Sec.** 29 **T.** 11 South **R.** 24 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

6. In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73923
2. NAME OF OPERATOR: Enduring Resources, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: n/a
4. LOCATION OF WELL FOOTAGES AT SURFACE: 661' FSL - 584' FWL COUNTY: Uintah QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 29 11S 24E S STATE: UTAH		8. WELL NAME and NUMBER: Rainbow 11-24-13-29
PHONE NUMBER: (303) 350-5719		9. API NUMBER: 4304738417
		10. FIELD AND POOL, OR WILDCAT: Undesignated

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Request for APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 8/14/2007
TO: 8/14/2008

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 08-14-07
By: *[Signature]*

NAME (PLEASE PRINT) <u>Evette Bissett</u>	TITLE <u>Regulatory Affairs Assistant</u>
SIGNATURE <i>[Signature]</i>	DATE <u>8/10/2007</u>

(This space for State use only)

COPY SENT TO OPERATOR
Date: 8-15-07
Time: 2 PM

(See Instructions on Reverse Side)

RECEIVED
AUG 14 2007

(5/2000)

DIV. OF OIL, GAS & MINING

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738417
Well Name: Rainbow 11-24-13-29
Location: 661' FSL - 584' FWL, SWSW, Sec 29, T11S-R24E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 8/14/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No

Laura Bissett
Signature

8/10/2007
Date

Title: Regulatory Affairs Assistant

Representing: Enduring Resources, LLC

**RECEIVED
AUG 14 2007**

DIV. OF OIL, GAS & MINING

CONFIDENTIAL

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU-73923

SUNDRY NOTICES AND REPORTS ON WELLS

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
n/a

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

7. UNIT or CA AGREEMENT NAME:
n/a

1. TYPE OF WELL
OIL WELL GAS WELL OTHER _____

8. WELL NAME and NUMBER:
Rainbow 11-24-13-29

2. NAME OF OPERATOR:
Enduring Resources, LLC

9. API NUMBER:
4304738417

3. ADDRESS OF OPERATOR:
475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202

PHONE NUMBER:
(303) 350-5114

10. FIELD AND POOL, OR WILDCAT:
Undesignated

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 661' FSL - 584' FWL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 29 11S 24E S

COUNTY: Uintah
STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Request for APD Extension</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 8/14/2008
TO: 8/14/2009

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 08-13-08
By: [Signature]

NAME (PLEASE PRINT) Alvin R. (Al) Arlian

TITLE Landman

SIGNATURE [Signature]

DATE 7/22/2008

(This space for State use only)

COPY SENT TO OPERATOR
Date: 8-14-2008
Initials: KS

(See Instructions on Reverse Side)

RECEIVED
AUG 13 2008

DIV. OF OIL, GAS & MINING

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738417
Well Name: Rainbow 11-24-13-29
Location: 661' FSL - 584' FWL, SWSW, Sec 29, T11S-R24E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 8/14/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No


Signature

7/22/2008

Date

Title: Administrative Assistant

Representing: Enduring Resources, LLC

RECEIVED

AUG 13 2008

DIV. OF OIL, GAS & MINING

RECEIVED

JUL 3 1 2006

Form 3160-3
(April 2004)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

5. Lease Serial No. UTU-73923	
6. If Indian, Allottee or Tribe Name N/A	
7. If Unit or CA Agreement, Name and No. N/A	
8. Lease Name and Well No. Rainbow 11-24-13-29	
9. API Well No. 43-047-38417	
10. Field and Pool, or Exploratory Undesignated	11. Sec., T. R. M. or Blk. and Survey or Area Sec 29 T11S R24E S.L.B.&M.
12. County or Parish Utah	13. State UT
14. Distance in miles and direction from nearest town or post office* 28.8 miles Southwest of Bonanza, UT	15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 584'
16. No. of acres in lease 1240 1840	17. Spacing Unit dedicated to this well 40 acres
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1000' +	19. Proposed Depth 6490
20. BLM/BIA Bond No. on file BLM - UTB000173	21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5905' RT-KB
22. Approximate date work will start* 10/01/2006	23. Estimated duration 20 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- 1. Well plat certified by a registered surveyor.
- 2. A Drilling Plan.
- 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- 5. Operator certification
- 6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature <i>Evette Bissett</i>	Name (Printed/Typed) Evette Bissett	Date 07/21/2006
--	---	---------------------------

Title
Regulatory Compliance Assistant

Approved by (Signature) <i>Jessy Kevcka</i>	Name (Printed/Typed) Jessy Kevcka	Date MAR 04 2009
--	---	----------------------------

Title
**Assistant Field Manager
Lands & Mineral Resources**
Office
VERNAL FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

06BM 2029A

Entered in AFMSS

Date 11/27/06

RECEIVED

MAR 10 2009

DIV. OF OIL, GAS & MINING

NOTICE OF APPROVAL

NOS 06/01/2006






**UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE**

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Enduring Resources, LLC
Well No: Rainbow 11-24-13-29
API No: 43-047-38417

Location: SWSW, Sec. 29, T11S, R24E
Lease No: UTU-73923
Agreement: N/A

Title	Name	Office Phone Number	Cell Phone Number
Petroleum Engineer:	Matt Baker	(435) 781-4490	(435) 828-4470
Petroleum Engineer:	Michael Lee	(435) 781-4432	(435) 828-7875
Petroleum Engineer:	Ryan Angus	(435) 781-4430	(435) 828-7368
Supervisory Petroleum Technician:	Jamie Sparger	(435) 781-4502	(435) 828-3913
Supervisory NRS:	Karl Wright	(435) 781-4484	
NRS/Enviro Scientist:	Holly Villa	(435) 781-4404	(435) 828-3544
NRS/Enviro Scientist:	James Hereford	(435) 781-3412	(435) 828-3546
NRS/Enviro Scientist:	Chuck Macdonald	(435) 781-4441	(435) 828-7481
NRS/Enviro Scientist:	Dan Emmett	(435) 781-3414	(435) 828-4029
NRS/Enviro Scientist:	Paul Percival	(435) 781-4493	(435) 828-7381
NRS/Enviro Scientist:	Anna Figueroa	(435) 781-3407	(435) 828-3548
NRS/Enviro Scientist:	Verlyn Pindell	(435) 781-3402	(435) 828-3547
NRS/Enviro Scientist:	Nathan Packer	(435) 781-3405	(435) 828-3545
NRS/Enviro Scientist:	David Gordon	(435) 781-4424	
NRS/Enviro Scientist:	Christine Cimiluca	(435) 781-4475	
NRS/Enviro Scientist:	Lori Ford	(435) 781-4406	

Fax: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.
- This proposed well is located within the Resource Development Group (RDG) EIS project. Adhere to applicable COA's approved in Final RDG EIS Record of Decision listed below:
 1. Transportation:
 - All roads will be constructed to Gold Book standard.
 - Limit use of roads by heavy equipment during the periods when the roads are muddy.
 - Operator will perform normal operational winter maintenance: roads will be plowed to allow safe navigation. And if snow is heavy, plows will provide breaks in the snow piled berms to allow free movement of wildlife across all roads.
 2. Noxious Weeds:
 - Power-wash all construction equipment before commencing construction activities in order to eliminate noxious weeds.
 3. Interim Reclamation:

All portions of the well pads and ROWS not utilized for the operation phase of the project will be re-seeded. Post construction seeding applications will continue until determined successful by the BLM.

 - During interim reclamation of the surface, the following seed mixture will be used PLS (Pure Live Seed) formula.

sagebrush (<i>Artemisia tridentate</i>).....	0.5 lbs/acre
galleta grass (<i>Hilaria jamesii</i>)	2 lbs/acre
hycrest crested wheatgrass (<i>Agropyron cristayum/Agropyron desertorum hybrid</i>)	2 lbs/acre

Rates are set for drill seeding; double the rate if broadcasting.

 - Reseeding may be required if initial seeding is not successful.
- Restrictions for placement of surface pipelines:
 - a): Surface pipelines will be placed 5-10 feet outside of the borrow area.
 - b): Surface pipelines will be placed in such a way that they will not wander into the borrow area.
 - c): Pipelines will be buried at all major road and drainage crossings.
- Paint all facilities Yuma green within six months of installation, except those facilities which are required to comply with the Occupational Safety and Health Act (OSHA).

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- A Cement Bond Log (CBL) shall be run from the TD to the top of cement. A field copy of the CBL shall be submitted to the BLM Vernal Field Office for review.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person

making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or

data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73923
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RAINBOW 11-24-13-29
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047384170000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0661 FSL 0584 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 29 Township: 11.0S Range: 24.0E Meridian: S	9. FIELD and POOL or WILDCAT: OIL SPRINGS COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/13/2009	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Request an one-year extension to APD term.

Approved by the Utah Division of Oil, Gas and Mining

Date: August 13, 2009

By:

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 8/12/2009



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047384170000

API: 43047384170000

Well Name: RAINBOW 11-24-13-29

Location: 0661 FSL 0584 FWL QTR SWSW SEC 29 TWNP 110S RNG 240E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 8/14/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
- Has the approved source of water for drilling changed? Yes No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
- Is bonding still in place, which covers this proposed well? Yes No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Alvin Arlian

Date: 8/12/2009

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

Date: August 13, 2009

By: 

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73923
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: ASPHALT
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: RAINBOW 11-24-13-29
2. NAME OF OPERATOR: Enduring Resources, LLC	9. API NUMBER: 43047384170000
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202	PHONE NUMBER: 303 350-5114 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0661 FSL 0584 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 29 Township: 11.0S Range: 24.0E Meridian: S	9. FIELD and POOL or WILDCAT: OIL SPRINGS COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/14/2010	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Request for an one-year extension to APD termination date.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: August 23, 2010

By: 

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A		DATE 8/12/2010



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047384170000

API: 43047384170000

Well Name: RAINBOW 11-24-13-29

Location: 0661 FSL 0584 FWL QTR SWSW SEC 29 TWP 110S RNG 240E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 8/14/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
- Has the approved source of water for drilling changed? Yes No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
- Is bonding still in place, which covers this proposed well? Yes No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Alvin Arlian

Date: 8/12/2010

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

Date: August 23, 2010

By: 



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

July 20, 2011

Al Arlian
Enduring Resources, LLC
475-17th Street, Ste. 1500
Denver, CO 80202

43 047 38417
Rainbow 11-24-13-29
11S 24E 29

Re: APDs Rescinded for Enduring Resources, LLC
Uintah County

Dear Mr. Arlian:

Enclosed find the list of APDs that are being rescinded per your request to Enduring Resources, LLC. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded, effective July 20, 2011.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Mason
Environmental Scientist

cc: Well File
Bureau of Land Management, Vernal

43-047-38383	ARCHY BENCH 11-23-31-29
43-047-38372	SOUTHAM CYN 10-24-14-17
43-047-38089	RAINBOW 11-24-14-17
→ 43-047-38417	RAINBOW 11-24-13-29
43-047-40332	BONANZA 9-24-32-3
43-047-37626	ARCHY BENCH 11-22-42-1
43-047-37075	ASPHALT WASH 11-24-44-9
43-047-40340	BONANZA 9-24-21-3
43-047-38867	ARCHY BENCH 11-22-23-12
43-047-37097	SOUTHAM CYN 11-24-12-4

United States Department of the Interior



BUREAU OF LAND MANAGEMENT

Green River District-Vernal Field Office

170 South 500 East

Vernal, UT 84078

(435) 781-4400 Fax: (435) 781-4410

<http://www.blm.gov/ut/st/en/fo/vernal.html>



MAR 26 2012

IN REPLY REFER TO:
3160 (UTG011)

Alvin R. Arlian
Enduring Resources, LLC
511-16th Street, Suite 700
Denver, CO 80202

43 047 38417

Re: Notice of Expiration
Well No. Rainbow 11-24-13-29
SWSW, Sec. 29, T11S, R24E
Uintah County, Utah
Lease No. UTU-73923
Asphalt Unit

RECEIVED
APR 04 2012
DIV. OF OIL, GAS & MINING

Dear Mr. Arlian:

The Application for Permit to Drill (APD) for the above-referenced well was approved on March 4, 2009. No extension request of the original APD was received in our office. According to our records, no known activity has transpired at the approved location. In view of the foregoing, this office is notifying you that the approval of the referenced application has expired. If you intend to drill at this location in the future, a new Application for Permit to Drill must be submitted.

This office requires a letter confirming that no surface disturbance has been made for this drill site. Any surface disturbance associated with the approved location of this well is to be rehabilitated. A schedule for this rehabilitation must be submitted to this office. Your cooperation in this matter is appreciated.

If you have any questions regarding this matter, please contact Cindy Severson at (435) 781-4455.

Sincerely,

Jerry Kenczka
Assistant Field Manager
Lands & Mineral Resources

cc: UDOGM