

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: ML-47045	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: EOG Resources, Inc.				9. WELL NAME and NUMBER: East Chapita 58-16	
3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY Vernal STATE UT ZIP 84078			PHONE NUMBER: (435) 781-9111	10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Mesaverd/Wasatch	
4. LOCATION OF WELL (FOOTAGES) 642227x 44334434 40.041121 AT SURFACE: 773 FNL 2166 FWL (NENW) 40.041083 LAT 109.333622 LON AT PROPOSED PRODUCING ZONE: Same				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 16 9S 23E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 55.2 Miles Southeast of Ouray, Utah				12. COUNTY: Uintah	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 773	16. NUMBER OF ACRES IN LEASE: 640		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40		
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 2690	19. PROPOSED DEPTH: 9,150		20. BOND DESCRIPTION: NM 2308		
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 4943 GR	22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION: 45 DAYS		

24. **PROPOSED CASING AND CEMENTING PROGRAM**


SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
17-1/2	13-3/8	H-40	48#	45	See Attached Eight Point Plan
12-1/4	9-5/8	J-55	36#	2,300	See Attached Eight Point Plan
7-7/8	4-1/2	N-80	11.6#	9,150	See Attached Eight Point Plan

25. **ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) **Kaylene R. Gardner** TITLE **Sr. Regulatory Assistant**


SIGNATURE  DATE **3/16/2007**


(This space for State use only)

**Approved by the
Utah Division of
Oil, Gas and Mining**

RECEIVED
MAR 19 2007
DIV. OF OIL, GAS & MINING

API NUMBER ASSIGNED: **43-047-39152**

APPROVAL: 

Date: **04-24-07**
By: 

(11/2001) (See Instructions on Reverse Side)

T9S, R23E, S.L.B.&M.

EOG RESOURCES, INC.


Well location, EAST CHAPITA #58-16, located as shown in the NE 1/4 NW 1/4 of Section 16, T9S, R23E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 58 EAM (1965) LOCATED IN THE NE 1/4 OF SECTION 30, T9S, R23E, S.L.B.&M. TAKEN FROM THE RED WASH SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5132 FEET.

BASIS OF BEARINGS



BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE SURVEY WAS MADE FROM FIELD NOTES OF ACTUAL SURVEYING MADE BY ME OR UNDER MY SUPERVISION AND THAT THE RESULTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



LEGEND:

- └ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)
 LATITUDE = 40°02'27.90" (40.041083)
 LONGITUDE = 109°20'01.04" (109.333622)
 (NAD 27)
 LATITUDE = 40°02'28.02" (40.041117)
 LONGITUDE = 109°19'58.59" (109.332942)

UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 08-29-06	DATE DRAWN: 08-29-06
PARTY G.S. B.C. S.L.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE EOG RESOURCES, INC.	

STATE OF UTAH)

) ss

COUNTY OF UINTAH)

VERIFICATION

Kaylene R. Gardner, of lawful age, being first duly sworn upon oath, deposes and says:

She is the Sr. Regulatory Assistant of EOG Resources, Inc., of Vernal, Utah. EOG Resources, Inc. is the operator of the following described well:


EAST CHAPITA 58-16
773' FNL – 2166' FWL (NENW)
SECTION 16, T9S, R23E
UINTAH COUNTY, UTAH

EOG Resources, Inc., is the only owner in the well and/or of all contiguous oil and gas leases or drilling units overlying the pool.

On the 16th day of March, 2007 she placed in the United States mail, with postage prepaid, a copy of the attached Application for Commingling in one wellbore for the subject well.


Said envelope which contained these instruments was addressed to the Utah Division of Oil, Gas & Mining.

Further affiant saith not.



Kaylene R. Gardner
Sr. Regulatory Assistant

Subscribed and sworn before me this 16th day of March, 2007.


CARLA R WHITE
Notary Public
State of Utah
My Comm. Expires Apr 15, 2008
147 East Main Vernal UT 84078

My Commission Expires
4-15-2008



Notary Public

Vernal Utah

R 23 E

9

HBP
UTU-67868

ECW 58-16

T
9
S

CWU 1-16
HBP
ML 47045

16

CWU 29-16

 EAST CHAPITA 58-16



Denver Division

EXHIBIT "A"

EAST CHAPITA 58-16
Commingling Application
Uintah County, Utah

Scale: 1"=1000'	D:\utah\Commingling\page_EC58-16_commingled.dwg WELL	Author	Mar 06, 2007 - 1:07pm
--------------------	---	--------	--------------------------

TLM

EIGHT POINT PLAN

EAST CHAPITA 58-16
NE/NW, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,714		Shale	
Wasatch	4,659	Primary	Sandstone	Gas
Chapita Wells	5,224	Primary	Sandstone	Gas
Buck Canyon	5,920	Primary	Sandstone	Gas
North Horn	6,515	Primary	Sandstone	Gas
KMV Price River	6,881	Primary	Sandstone	Gas
KMV Price River Middle	7,661	Primary	Sandstone	Gas
KMV Price River Lower	8,527	Primary	Sandstone	Gas
Sego	8,940		Sandstone	
TD	9,150			

Estimated TD: **9,150' or 200'± below Sego top**

Anticipated BHP: 4,995 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
 BOP schematic diagrams attached.

4. CASING PROGRAM:

CASING	Hole Size	Length	Size	WEIGHT	Grade	Thread	Rating Collapse	Factor Burst	Tensile
Conductor	17 ½"	0 – 45'	13 ¾"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 ¼"	0 – 2,300' KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production	7-7/8"	Surface – TD	4-½"	11.6#	N-80	LTC	6350 PSI	7780 Psi	223,000#

Note: 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

EIGHT POINT PLAN

EAST CHAPITA 58-16
NE/NW, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0'- 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

EIGHT POINT PLAN

EAST CHAPITA 58-16
NE/NW, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: 207 sks Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

Lead: 135 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 880 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9 gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

EIGHT POINT PLAN

EAST CHAPITA 58-16
NE/NW, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:


- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

EOG RESOURCES 11" 5,000 PSI W.P. BOP CONFIGURATION



**EOG RESOURCES CHOKE MANIFOLD CONFIGURATION
W/ 5,000 PSI WP VALVES**

PAGE 2 OF 2



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, **whichever is greater.**
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.



**EAST CHAPITA 58-16
NENW, Section 16, T9S, R23E
Uintah County, Utah**

SURFACE USE PLAN

NOTIFICATION REQUIREMENTS

- Location Construction: Forty-eight (48) hours prior to construction of location and access roads.
- Location Completion: Prior to moving on the drilling rig.
- Spud Notice: At least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing: Twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and related Equipment Tests: Twenty-four (24) hours prior to running casing and tests.
- First Production Notice: Within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

The well pad is approximately 325 feet long with a 246-foot width, containing 1.84 acres more or less. The well access road is approximately 528 feet long with a 30-foot right-of-way, disturbing approximately 0.36 acre. New surface disturbance associated with access road and the well pad is estimated to be approximately 2.20 acres. The pipeline is approximately 1169 feet long with a 40-foot right-of-way, disturbing approximately 1.07 acres.

1. EXISTING ROADS:

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 55.2 miles south of Myton, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary.

2. PLANNED ACCESS ROAD:

- A. The access road will be approximately 528' in length. See attached Topo Map "B".
- B. The access road has a 30 foot ROW w/18 foot running surface.
- C. Maximum grade of the new access road will be 8 percent.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.

New or reconstructed roads will be centerlined – flagged at time of location staking.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation or debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around then avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

Traveling off the 30 foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:

See attached TOPO map "C" for the location of wells within a one-mile radius.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

A. On Well Pad

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400 BBL vertical tanks and attaching piping.
2. Gas gathering lines – A 4" gathering line will be buried from dehy to the edge of the location.

B. Off Well Pad

1. Proposed location of attendant off pad flowlines shall be flagged prior to archaeological clearance.
2. The length of the new proposed pipeline is 1169' x 40', containing 1.07 acres more or less. The proposed pipeline leaves the eastern edge of the well pad turning and proceeding in an westerly direction for an approximate distance of 1169'. The pipe will tie into an existing pipeline in the NENW of Section 16, T9S, R23E (ML 47045). Pipe will be 4" NOM, 0.156 wall, Grade X42, Zap-Lok, electric weld with a 35 mil X-Tru coating.
3. Proposed pipeline will be a 4" OD steel, welded line laid on the surface
4. Protective measures and devices for livestock and wildlife will be taken and /or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All existing facilities will be painted with Carlsbad Canyon.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

5. LOCATION AND TYPE OF WATER SUPPLY:

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/ or Target Trucking Inc.'s water source in the SW/SW. Sec 35, T9S, R22E Uintah County, Utah (State Water Right # 49-1501, and/or Bonanza Power Plant water source in Sec 26, T8S, R23E Uintah County, UT (State Water Right # 49-225(A31368)). Water will be hauled by a licensed trucking company.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIALS:

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL:

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
- 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following three locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
- 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.

- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit or by removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with felt and a 16 millimeter plastic liner.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

8. ANCILLARY FACILITIES:

None anticipated.

9. WELL SITE LAYOUT:

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the south corner of the location. The flare pit will be located on the south side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled pit topsoil will be stored separate from the location topsoil south of Corner #5. The stockpiled location topsoil will be stored between corner #6 and the access road. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the west.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently counted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RECLAMATION OF THE SURFACE:

A. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

B. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the UDOGM will attach the appropriated surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP:

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

State of Utah

12. OTHER INFORMATION:

A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:

- Whether the materials appear eligible for the National Register of Historic Places;
- The mitigation measures the operator will likely have to undertake before the site can be used.
- A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities.
- C. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.
- D. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Utah State lands after the conclusion of drilling operations or at any other time without Utah State authorization. However, if Utah State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (Utah State does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

13. LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

PERMITTING AGENT

Kaylene R. Gardner
EOG Resources, Inc.
P.O. Box 1815
Vernal, Ut 84078
(435) 781-9111

DRILLING OPERATIONS


Donald Presenkowski
EOG Resources, Inc.
P.O. Box 250
Big Piney, WY 83113
307-276-4865

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the East Chapita 58-16 Well, located in the NENW, of Section 16, T9S, R23E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

March 16, 2007

Date



Kaylene R. Gardner, Sr. Regulatory Assistant

EOG RESOURCES, INC.
EAST CHAPITA #58-16
 LOCATED IN UINTAH COUNTY, UTAH
 SECTION 16, T9S, R23E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHEASTERLY



UELS Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

08 31 06
 MONTH DAY YEAR

PHOTO

TAKEN BY: GS.

DRAWN BY: C.P.

REVISED: 00-00-00


EOG RESOURCES, INC.
EAST CHAPITA #58-16
SECTION 16, T9S, R23E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 6.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.6 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE #48-16 TO THE NORTHWEST; FOLLOW ROAD FLAGS IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE #57-16 TO THE NORTHWEST; FOLLOW ROAD FLAGS IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.35 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.1 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 55.2 MILES.


EOG RESOURCES, INC.

LOCATION LAYOUT FOR
 EAST CHAPITA #58-16
 SECTION 16, T9S, R23E, S.L.B.&M.
 773' FNL 2166' FWL











SCALE: 1" = 50'
 DATE: 08-29-06
 Drawn By: S.L.

NOTE:
 Flare Pit is to be located
 a min. of 100' from the
 Well Head.



Total Pit Capacity
 W/2' Of Freeboard
 = 12,250 Bbls. ±
 Total Pit Volume
 = 3,320 Cu. Yds.

RESERVE PITS
 (12' Deep)
 SLOPE = 1-1/2 : 1



NOTE:
 Earthwork Calculations Require
 a Fill of 2.9' @ the Location
 Stake For Balance. All Fill is
 to be Compacted to a Minimum
 of 95% of the Maximum Dry
 Density Obtained by AASHTO
 Method t-99.



CONSTRUCT
 DIVERSION
 DITCH

Proposed Access
 Road

Round Corners
 as needed

Existing
 Drainage

CATWALK

PIPE RACKS

DOG HOUSE

RIG

WATER

PUMP

MUD SHED

HOPPER

POWER

TOOLS

FUEL

TRASH

TRAILER

TOILET

FUEL

STORAGE
 TANK

Sta. 1+50

F-1.0'
 El. 45.2'

Sta. 0+50

Sta. 0+00

Approx.
 Toe of
 Fill Slope

NOTES:

Elev. Ungraded Ground At Loc. Stake = 4943.3'
 FINISHED GRADE ELEV. AT LOC. STAKE = 4946.2'

FIGURE #1


EOG RESOURCES, INC.

FIGURE #2

TYPICAL CROSS SECTIONS FOR
 EAST CHAPITA #58-16
 SECTION 16, T9S, R23E, S.L.B.&M.
 773' FNL 2166' FWL

X-Section Scale
 1" = 20'
 1" = 50'

DATE: 08-29-06
 Drawn By: S.L.




* NOTE:
 FILL QUANTITY INCLUDES
 5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,600 Cu. Yds.
Remaining Location	= 6,140 Cu. Yds.
TOTAL CUT	= 7,740 CU.YDS.
FILL	= 4,480 CU.YDS.

EXCESS MATERIAL	= 3,260 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,260 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 0 Cu. Yds.



LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD

EOG RESOURCES, INC.

EAST CHAPITA #58-16
SECTION 16, T9S, R23E, S.L.B.&M.
773' FNL 2166' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP **08 31 06**
MONTH DAY YEAR


SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00



T9S

R
23
E

**PROPOSED LOCATION:
EAST CHAPITA #58-16**



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

EOG RESOURCES, INC.

**EAST CHAPITA #58-16
SECTION 16, T9S, R23E, S.L.B.&M.
773' FNL 2166' FWL**



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




**TOPOGRAPHIC
MAP**

08 31 06
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 1,169' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)



EOG RESOURCES, INC.

EAST CHAPITA #58-16
SECTION 16, T9S, R23E, S.L.B.&M.
773' FNL 2166' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP 08 31 06
 MONTH DAY YEAR
 SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00



**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 03/19/2007

API NO. ASSIGNED: 43-047-39152

WELL NAME: E CHAPITA 58-16
 OPERATOR: EOG RESOURCES INC (N9550)
 CONTACT: KAYLENE GARDNER

PHONE NUMBER: 435-781-9111

PROPOSED LOCATION:

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	DKG	4/18/07
Geology		
Surface		

NENW 16 090S 230E
 SURFACE: 0773 FNL 2166 FWL
 BOTTOM: 0773 FNL 2166 FWL
 COUNTY: UINTAH
 LATITUDE: 40.04112 LONGITUDE: -109.3329
 UTM SURF EASTINGS: 642227 NORTHINGS: 4433443
 FIELD NAME: NATURAL BUTTES (630)

LEASE TYPE: 3 - State
 LEASE NUMBER: ML-47045
 SURFACE OWNER: 3 - State

PROPOSED FORMATION: WSMVD
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[] Ind[] Sta[] Fee[]
(No. 6196017)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 49-1501)
- RDCC Review (Y/N)
(Date:)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)
(Wasatch Mesa Verde)

LOCATION AND SITING:

- R649-2-3.
- Unit: _____
- R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit
- Board Cause No: _____
- Eff Date: _____
- Siting: _____
- R649-3-11. Directional Drill

COMMENTS: Resite (3-6-07)

- STIPULATIONS:
- 1- Spacing Strip
 - 2- Cement strip #3 (4 1/2" production, 2100' MD)
 - 3- Surface Csg Cont strip
 - 4- Commingle
 - 5- STATEMENT OF BASIS

T9S R23E

NATURAL BUTTES FIELD

E CHAPITA 18-17

E CHAPITA 57-16

E CHAPITA 58-16

E CHAPITA 60-16

E CHAPITA 30-16

E CHAPITA 47-16

E CHAPITA 48-16

CWU 1

CWU 29

16

E CHAPITA 31-16

E CHAPITA 800-16

E CHAPITA 49-16
COG STATE 33-16

E CHAPITA 7-16

E CHAPITA 15-17

E CHAPITA 50-16

E CHAPITA 8-16

E CHAPITA 6-16

E CHAPITA 818-16

CHAPITA WELLS UNIT

OPERATOR: EOG RESOURCES INC (N9550)

SEC: 16 T.9S R. 23E

FIELD: NATURAL BUTTES (630)


COUNTY: UINTAH

SPACING: R649-3-2 / GENERAL SITING

- Field Status**
- ABANDONED
 - ACTIVE
 - COMBINED
 - INACTIVE
 - PROPOSED
 - STORAGE
 - TERMINATED

- Unit Status**
- EXPLORATORY
 - GAS STORAGE
 - NF PP OIL
 - NF SECONDARY
 - PENDING
 - PI OIL
 - PP GAS
 - PP GEOTHERML
 - PP OIL
 - SECONDARY
 - TERMINATED

- Wells Status**
- GAS INJECTION
 - GAS STORAGE
 - LOCATION ABANDONED
 - NEW LOCATION
 - PLUGGED & ABANDONED
 - PRODUCING GAS
 - PRODUCING OIL
 - SHUT-IN GAS
 - SHUT-IN OIL
 - TEMP. ABANDONED
 - TEST WELL
 - WATER INJECTION
 - WATER SUPPLY
 - WATER DISPOSAL
 - DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA MASON
DATE: 27-MARCH-2007

Application for Permit to Drill

Statement of Basis

3/26/2007

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
295	43-047-39152-00-00		GW	S	No
Operator	EOG RESOURCES INC	Surface Owner-APD			
Well Name	E CHAPITA 58-16	Unit			
Field	UNDESIGNATED	Type of Work			
Location	NENW 16 9S 23E S 773 FNL 2166 FWL GPS Coord (UTM) 642227E 4433443N				

Geologic Statement of Basis

EOG proposes to set 45 feet of conductor and 2,300 feet of surface casing cemented to the surface. The base of the moderately saline water is estimated at approximately 1,000 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location. The surface formation at this location is the Uinta Formation. The Uinta Formation is made up of discontinuous sands interbedded with shales and are not expected to produce prolific aquifers. The proposed surface casing should adequately protect any near surface aquifers.

Brad Hill
APD Evaluator

3/26/2007
Date / Time

Surface Statement of Basis

The general area is within the Coyote Wash Drainage. This drainage is a major drainage beginning near the Utah-Colorado border to the east and joining the White River approximately 6 miles to the southwest. The drainage consists of several significant side drainages. The drainage is dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. The topography is characterized by rolling hills, frequently divided by gentle to deep draws, which flow into Coyote Wash. The draws are often rimmed with steep side hills with exposed sand stone bedrock cliffs. Vernal, Utah is approximately 35 air miles and 55 road miles to the northwest. The area is accessed by Utah State, Uintah County and oilfield development Roads to within 0.1 miles of the location where a new road will be constructed.

The proposed East Chapita 58-16 gas well is on a narrow flat with broken terrain surrounded on 3 sides with low elevation ridges, which have exposed sandstone rock outcrops. A small drainage to the north is proposed to be diverted around the location.

Both the surface and minerals for this location are owned by SITLA. Jim Davis of SITLA attended the pre-site visit and had no concerns regarding the proposed location.

Ben Williams represented the Utah Division of Wildlife Resources. Mr. Williams stated the area is classified as critical yearlong habitat for antelope. He however recommended no stipulations for this species as the loss of forage from this location is not significant and water not forage is the factor limiting the herd population in the area. No other wildlife is expected to be affected. He gave Byron Tolman, representing EOG Resources, and Mr. Davis a copy of his evaluation and a DWR recommended seed mix to use when re-vegetating the area.

The location appears to be the best site for constructing and operating a well in the immediate area.

Floyd Bartlett
Onsite Evaluator

3/6/2007
Date / Time

Application for Permit to Drill

Statement of Basis

3/26/2007

Utah Division of Oil, Gas and Mining

Page 2

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator EOG RESOURCES INC
Well Name E CHAPITA 58-16
API Number 43-047-39152-0 **APD No** 295 **Field/Unit** UNDESIGNATED
Location: 1/4,1/4 NENW **Sec** 16 **Tw** 9S **Rng** 23E 773 FNL 2166 FWL
GPS Coord (UTM) 642221 4433446 **Surface Owner**

Participants

Floyd Bartlett (DOGM), Jim Davis (SITLA), Byron Tolman (Agent for EOG Resources) and Ben Williams (UDWR).

Regional/Local Setting & Topography

The general area is within the Coyote Wash Drainage. This drainage is a major drainage beginning near the Utah-Colorado border to the east and joining the White River approximately 6 miles to the southwest. The drainage consists of several significant side drainages. The drainage is dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. The topography is characterized by rolling hills, frequently divided by gentle to deep draws, which flow into Coyote Wash. The draws are often rimmed with steep side hills with exposed sand stone bedrock cliffs. Vernal, Utah is approximately 35 air miles and 55 road miles to the northwest. The area is accessed by Utah State, Uintah County and oilfield development Roads to within 0.1 miles of the location where a new road will be constructed.

The proposed East Chapita 58-16 gas well is on a narrow flat with broken terrain surrounded on 3 sides with low elevation ridges, which have exposed sandstone rock outcrops. Drainage to the north is proposed to be diverted around the location.

Both the surface and minerals for this location are owned by SITLA. Jim Davis of SITLA attended the pre-site visit and had no concerns regarding the proposed location.

Surface Use Plan

Current Surface Use

Grazing
Wildlife Habitat
Recreational

New Road

Miles	Well Pad	Src Const Material	Surface Formation
0.1	Width 261 Length 325	Onsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetland N

Flora / Fauna

Barren. Halogeton, shadscale, dead big sagebrush

Antelope, coyote, small mammals and birds. Winter domestic sheep grazing

Soil Type and Characteristics

Medium deep sandy loam with some surface rock.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required Y

To the north east around the location.

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? Y

Paleo Potential Observed? N

Cultural Survey Run? Y

Cultural Resources? N

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	300 to 1320	10
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0

Final Score 25 1 **Sensitivity Level**

Characteristics / Requirements

The reserve pit is proposed on the southeast portion of the location within an area of cut. Dimensions are 75' x 147' x 12' deep. A liner is required. EOG customarily uses a 16 mil liner with an appropriate thickness of sub-felt to cushion the liner.

Closed Loop Mud Required? N

Liner Required? Y

Liner Thickness 16

Pit Underlayment Required? Y

Other Observations / Comments

ATV's were used to access the site.

Floyd Bartlett
Evaluator

3/6/2007
Date / Time

Casing Schematic

Surface

12 7/8" 18 1/2"

BHP $0.052(9150)10.5 = 4996 \text{ psi}$
anticipate 4995 psi

GM $.12(9150) = 1098$
 $4996 - 1098 = 3898 \text{ psi, MASP}$

BOPE 5M ✓

9-5/8"
MW 8.4
Frac 19.3

Burst 3520
70% 2464 psi

Max P @ surf. shoe
 $.22(6850) = 1507$
 $4996 - 1507 = 3489 \text{ psi}$

Test to 2464 psi ✓

stop prod. cont. ✓

Adequate DWD 4/18/07

4-1/2"
MW 10.5

Uinta

TOC @ 800' $1000' \text{ BMSW}$
* St. A

1714' Green River

1888' TOC w/0% w/o

Surface
2300. MD

* propose TOC @ 2100'
✓ o.k. → stop

TOC @ 3879.

4659' Wasatch

5224' Chapita Wells

5920' Buck Canyon

6515' North Horn

6881' KMV Price River

7661' KMV Price River Middle

8527' KMV Price River Lower

8940' Sejo

Production
9150. MD

Well name:	2007-04 EOG E Chapita 58-16		
Operator:	EOG Resources Inc.		
String type:	Surface	Project ID:	43-047-39152
Location:	Uintah County		

Design parameters:

Collapse

Mud weight: 8.400 ppg
 Design is based on evacuated pipe.

Burst

Max anticipated surface pressure: 2,024 psi
 Internal gradient: 0.120 psi/ft
 Calculated BHP: 2,300 psi

No backup mud specified.

Minimum design factors:

Collapse:

Design factor: 1.125

Burst:

Design factor: 1.00

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.80 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.50 (B)

Tension is based on buoyed weight.
 Neutral point: 2,014 ft

Environment:

H2S considered? No
 Surface temperature: 75 °F
 Bottom hole temperature: 107 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 290 ft

Cement top: 800 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 9,150 ft
 Next mud weight: 10.500 ppg
 Next setting BHP: 4,991 psi
 Fracture mud wt: 19.250 ppg
 Fracture depth: 2,300 ft
 Injection pressure: 2,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2300	9.625	36.00	J-55	ST&C	2300	2300	8.796	998.2

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1003	2020	2.013	2300	3520	1.53	72	394	5.43 J

Prepared by: Helen Sadik-Macdonald
 Div of Oil, Gas & Minerals

Phone: 801-538-5357
 FAX: 801-359-3940

Date: April 11, 2007
 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	2007-04 EOG E Chapita 58-16		
Operator:	EOG Resources Inc.		
String type:	Production	Project ID:	43-047-39152
Location:	Uintah County		

Design parameters:

Collapse

Mud weight: 10.500 ppg
 Design is based on evacuated pipe.

Burst

Max anticipated surface pressure: 2,978 psi
 Internal gradient: 0.220 psi/ft
 Calculated BHP 4,991 psi

No backup mud specified.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.80 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.50 (B)

Tension is based on buoyed weight.
 Neutral point: 7,714 ft

Environment:

H2S considered? No
 Surface temperature: 75 °F
 Bottom hole temperature: 203 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 1,500 ft

Cement top: 3,879 ft

Non-directional string.

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	9150	4.5	11.60	N-80	LT&C	9150	9150	3.875	798.5

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4991	6350	1.272	4991	7780	1.56	89	223	2.49 J

Prepared by: Helen Sadik-Macdonald
 Div of Oil, Gas & Minerals

Phone: 801-538-5357
 FAX: 801-359-3940

Date: April 11, 2007
 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9150 ft, a mud weight of 10.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

From: <Kaylene_Gardner@eogresources.com>
To: "Dustin Doucet" <dustindoucet@utah.gov>
Date: 4/18/2007 5:54 PM
Subject: Re: Commingling APD..more
Attachments: ECW 60-16.doc; ECW 58-16.doc; ECW 57-16.doc

The commingling information is within the Drilling plan - I attached a copy for your reference.

Kaylene Gardner
EOG/Vernal
435-781-9111 Office

"Dustin Doucet" <dustindoucet@utah.gov>
04/18/2007 04:46 PM

To
<Kaylene_Gardner@eogresources.com>
cc

Subject
Commingling APD..more

Kaylene,

I need the same info mentioned below on a couple more APD's... the E Chapita 57-16 and 58-16. Thanks.

Dustin

Dustin K. Doucet
Petroleum Engineer
Utah Division of Oil, Gas and Mining
Oil and Gas Program
1594 West North Temple, Suite 1210
Salt Lake City, UT 84116

Phone: (801) 538-5281
fax: (801) 359-3940
email: dustindoucet@utah.gov

>>> Dustin Doucet 4/18/2007 3:35 PM >>>
Kaylene,

I was just reviewing the E Chapita 60-16 well and had everything except the commingling request (i.e. had the plat and affidavit, but nothing requesting commingling and how you propose to do that). If you could send that portion to me I will include it in the APD and sign off on it.
thanks.

Dustin

Dustin K. Doucet
Petroleum Engineer
Utah Division of Oil, Gas and Mining
Oil and Gas Program
1594 West North Temple, Suite 1210
Salt Lake City, UT 84116

Phone: (801) 538-5281
fax: (801) 359-3940
email: dustindoucet@utah.gov

EIGHT POINT PLAN**east chapita 58-16****NE/NW, SEC. 16, T9S, R23E, S.L.B.&M.****UINTAH COUNTY, UTAH****1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:**

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,714		Shale	
Wasatch	4,659	Primary	Sandstone	Gas
Chapita Wells	5,224	Primary	Sandstone	Gas
Buck Canyon	5,920	Primary	Sandstone	Gas
North Horn	6,515	Primary	Sandstone	Gas
KMV Price River	6,881	Primary	Sandstone	Gas
KMV Price River Middle	7,661	Primary	Sandstone	Gas
KMV Price River Lower	8,527	Primary	Sandstone	Gas
Sego	8,940		Sandstone	
TD	9,150			

Estimated TD: **9,150' or 200'± below Sego top****Anticipated BHP: 4,995 Psig**

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

EOG Resources, Inc. requests authorization for commingling of production from the Wasatch, and Mesaverde formations in the referenced wellbore. In the event allocation of production is necessary, the allocation will be based on proportionate net pay as calculated from cased hole logs. Production from the Wasatch, and Mesaverde formations will be commingled in the wellbore and produced through open ended 2-3/8" tubing landed below all perforations in the 4-1/2" production casing.

Attached is a map showing the location of all wells on contiguous oil and gas leases or drilling units and an affidavit showing that this application has been provided to owners of all contiguous oil and gas leases or drilling units overlying the pool.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

EIGHT POINT PLAN**east chapita 58-16**
NE/NW, SEC. 16, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH**4. CASING PROGRAM:**

<u>CASING</u>	<u>Hole Size</u>	<u>Length</u>	<u>Size</u>	<u>WEIGHT</u>	<u>Grade</u>	<u>Thread</u>	<u>Rating Collapse</u>	<u>Factor Burst</u>	<u>Tensile</u>
Conductor	17 1/2"	0 – 45'	13 3/8"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 1/4"	0 – 2,300' KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production	7-7/8"	Surface – TD	4-1/2"	11.6#	N-80	LTC	6350 PSI	7780 Psi	223,000#

Note: 12-1/4" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

5. Float Equipment:**Surface Hole Procedure (0'- 2300'±)**

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-1/2", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM**Surface Hole Procedure (Surface - 2300'±):**

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

EIGHT POINT PLAN**east chapita 58-16**
NE/NW, SEC. 16, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

9. CEMENT PROGRAM:**Surface Hole Procedure (Surface - 2300'±):**

Lead: 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: 207 sks Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

EIGHT POINT PLAN

east chapita 58-16
NE/NW, SEC. 16, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

Production Hole Procedure (2300'± - TD)

Lead: 135 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 880 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

(Attachment: BOP Schematic Diagram)

From: Ed Bonner
To: Mason, Diana
Date: 4/23/2007 3:38 PM
Subject: Well Clearance

CC: Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

Bill Barrett Corporation

Peters Point State 8-2D-13-16 (API 43 007 31280)

EnCana Oil & Gas (USA) Inc

Middle Mountain State 36-12-29-24 (API 43 037 31855)

EOG Resources, Inc

East Chapita 60-16 (API 43 047 39150)

East Chapita 57-16 (API 43 047 39151)

East Chapita 58-16 (API 43 047 39152)

Kerr McGee Oil & Gas Onshore LP

NBU 1021-13N (API 43 047 39107)

NBU 1021-13H (API 43 047 39108)

NBU 1021-16D (API 43 047 39109)

NBU 1022-19P (API 43 047 39139)

If you have any questions regarding this matter please give me a call.



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

April 24, 2007

EOG Resources, Inc
1060 East Highway 40
Vernal, UT 84078

Re: East Chapita 58-16 Well, 773' FNL, 2166' FWL, NE NW, Sec. 16, T. 9 South,
R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Administrative approval for commingling the production from the Wasatch formation and the Mesaverde formation in this well is hereby granted. Appropriate information has been submitted to DOGM in accordance with R649-3-22. No written objections from owners were received by DOGM.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39152.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
SITLA

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
7. Surface casing shall be cemented to the surface.
8. Cement volume for the 4 1/2" production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 2100' MD as indicated in the submitted drilling plan.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: EOG RESOURCES INC

Well Name: E CHAPITA 58-16

Api No: 43-047-39152 Lease Type: STATE

Section 16 Township 09S Range 23E County UINTAH

Drilling Contractor ROCKY MOUNTAIN DRLG RIG # RATHOLE

SPUDDED:

Date 04/08/08

Time 2:15 PM

How DRY

Drilling will Commence: _____

Reported by JERRY BARNES

Telephone # (435) 828-1720

Date 04/09/08 Signed CHD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: East Chapita 58-16
2. NAME OF OPERATOR: EOG Resources, Inc.		9. API NUMBER: 43-047-39152
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202	PHONE NUMBER: (303) 824-5526	10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch/Mesaverde
4. LOCATION OF WELL FOOTAGES AT SURFACE: 773' FNL & 2166' FWL 40.041083 LAT 109.333622 LON COUNTY: Uintah		
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 16 9S 23E S STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well spud</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well spud on 4/8/2008.

NAME (PLEASE PRINT) <u>Mary A. Maestas</u>	TITLE <u>Regulatory Assistant</u>
SIGNATURE	DATE <u>4/11/2008</u>

(This space for State use only)

RECEIVED
APR 17 2008

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc. Operator Account Number: N 9550
 Address: 600 17th St., Suite 1000N
city Denver
state CO zip 80202 Phone Number: (303) 824-5526

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39152	East Chapita 58-16		NENW	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	16785	4/8/2008		4/28/08		
Comments: <u>Wasatch/Mesaverde well</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39203	East Chapita 56-16		SWNW	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	16786	4/10/2008		4/28/08		
Comments: <u>Wasatch/Mesaverde well</u>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39205	East Chapita 63-35		SENE	35	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	16787	4/10/2008		4/28/08		
Comments: <u>Wasatch/Mesaverde well</u>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mary A. Maestas

Name (Please Print)

Mary A. Maestas

Signature

Regulatory Assistant

4/11/2008

Date

RECEIVED Title

APR 24 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: EOG Resources, Inc.		8. WELL NAME and NUMBER: East Chapita 58-16
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202	PHONE NUMBER: (303) 824-5526	9. API NUMBER: 43-047-39152
4. LOCATION OF WELL FOOTAGES AT SURFACE: 773' FNL & 2166' FWL 40.041083 LAT 109.333622 LON		10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch/Mesaverde
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 16 9S 23E S		COUNTY: Uintah
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input checked="" type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well was turned to sales on 5/21/2008. Please see the attached operations summary report for drilling and completion operations performed on the subject well.

NAME (PLEASE PRINT) <u>Mary A. Maestas</u>	TITLE <u>Regulatory Assistant</u>
SIGNATURE <u>Mary A. Maestas</u>	DATE <u>5/22/2008</u>

(This space for State use only)

RECEIVED
MAY 27 2008

WELL CHRONOLOGY REPORT

Report Generated On: 05-22-2008

Well Name	ECW 058-16	Well Type	DEVG	Division	DENVER
Field	CHAPITA DEEP	API #	43-047-39152	Well Class	COMP
County, State	UINTAH, UT	Spud Date	04-22-2008	Class Date	
Tax Credit	N	TVD / MD	9,150/ 9,150	Property #	059618
Water Depth	0	Last CSG	0.0	Shoe TVD / MD	0/ 0
KB / GL Elev	4,962/ 4,946				
Location	Section 16, T9S, R23E, NENW, 773 FNL & 2166 FWL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	81.0

AFE No	304176	AFE Total	2,020,100	DHC / CWC	880,700/ 1,139,400
Rig Contr	TRUE	Rig Name	TRUE #31	Start Date	06-08-2007
06-08-2007	Reported By	SHARON CAUDILL			
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA
			773' FNL & 2166' FWL (NE/NW)
			SECTION 16, T9S, R23E
			UINTAH COUNTY, UTAH
			LAT 40.041083, LONG 109.333622 (NAD 83)
			LAT 40.041117, LONG 109.332942 (NAD 27)
			TRUE #31
			OBJECTIVE: 9150' TD, MESAVERDE
			DW/GAS
			EAST CHAPITA PROSPECT
			DD&A: CHAPITA DEEP
			NATURAL BUTTES FIELD
			LEASE: ML-47045
			ELEVATION: 4943.3' NAT GL, 4946.2' PREP GL (DUE TO ROUNDING THE PREP GL IS 4946'), 4962' KB (16')
			EOG WI 100%, NRI 81%

03-03-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$38,000	Completion	\$0	Daily Total	\$38,000						
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	CONSTRUCTION OF LOCATION WILL START TODAY.

03-04-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	DRILLING ROCK OUT.

03-05-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	DRILLING OUT ROCK.

03-06-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	DRILLING OUT ROCK.

03-07-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	SHOOT MONDAY.

03-10-2008 Reported By TERRY CSERE

TOP JOB # 3: MIXED & PUMPED 50 SX (10 BBLs) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. NO RETURNS. WOC 15 MINUTES.

TOP JOB # 4: MIXED & PUMPED 50 SX (10 BBLs) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. HOLE FILLED & STOOD FULL. RDMO HALLIBURTON CEMENTERS.

PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.

ASPEN DRILLING TOOK SURVEYS WHILE DRILLING @ 510'-1.0?, 997'-0.5?, 1508'-0.75?, 2017'-2.0?.

CONDUCTOR LEVEL RECORD: PS= 89.9 OPS= 89.9 VDS= 89.9 MS= 89.9.
 9 5/8 CASING LEVEL RECORD: PS= 90.0 OPS= 90.0 VDS= 89.9 MS= 89.9.

DANNY FARNSWORTH NOTIFIED ROOSEVELT OFFICE W/UDOGM OF THE SURFACE CASING & CEMENT JOB ON 4/12/2008 @ 9:00 A.M.

04-22-2008		Reported By		PAT CLARK							
Daily Costs: Drilling		\$21,717		Completion		\$0		Daily Total		\$21,717	
Cum Costs: Drilling		\$278,865		Completion		\$0		Well Total		\$278,865	
MD	2,478	TVD	2,478	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		
Activity at Report Time: RURT											
Start	End	Hrs	Activity Description								
06:00	06:00	24.0	MOVE RIG 1/2 MILE TO ECW 58-16 W/WESTROC TRUCKING. 6 BED TRUCKS, 1 HAUL TRUCK, 1 FORKLIFT, 1 CRANE. RELEASED TRUCKS AND CRANE @ 16:00. DERRICK IN AIR @ 18:00. SAFETY MEETINGS - W/WESTROC, MOVING RIG, PPE, LOCATION BOUNDARIES. RIG 75% RIGGED UP, ETA SPUD - 4/22/08 @ MIDNIGHT. NOTIFIED\JAMIE SPARGER\VERNAL BLM\BOP TEST\4-21-08\09:00.								

04-23-2008		Reported By		PAT CLARK							
Daily Costs: Drilling		\$28,842		Completion		\$819		Daily Total		\$29,661	
Cum Costs: Drilling		\$307,707		Completion		\$819		Well Total		\$308,526	
MD	2,585	TVD	2,585	Progress	97	Days	1	MW	8.6	Visc	26.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		
Activity at Report Time: DRILLING @ 2585 / CHANGE ROT. HEAD											
Start	End	Hrs	Activity Description								
06:00	13:00	7.0	RURT. 5 MEN, 7 HOURS. CUT AND SLIP DRILL LINE.								
13:00	14:00	1.0	NU BOPE. RIG ON DAYWORK @ 13:00 HRS, 4/22/08.								
14:00	17:00	3.0	TESTED PIPE RAMS, BLIND RAMS, HCR, CHOKE VALVE, CHOKE LINE & MANIFOLD, KILL LINE VALVES TO 5000 PSI FOR 10 MINUTES. TESTED UPPER & LOWER KELLY COCKS, FLOOR & INSIDE BOP TO 5000 PSI FOR 10 MINUTES. TESTED ANNULAR PREVENTER TO 2500 PSI FOR 10 MINUTES. TESTED CASING TO 1500 PSI FOR 30 MINUTES. NO BLM REP ON LOCATION TO WITNESS TEST.								

17:00 20:00 3.0 HSM. R/U WEATHERFORD TRS. P/U BHA AND DP. TAG CEMENT @ 2425'. R/D TRS.
 20:00 21:30 1.5 DRILL CEMENT/FLOAT EQUIP. FC @ 2433', GS @ 2478'. DRILL 10' TO 2488'.
 21:30 22:00 0.5 OTHER - FIT TEST TO 246 PSI FOR 10.5 EMW.
 22:00 00:00 2.0 DRILL 2488' - 2585'. WOB 10 - 15K, RPM 60/67, SPP 800 PSI, DP 350 PSI, ROP 49 FPH.
 ROTATING HEAD FAILED.
 00:00 01:00 1.0 TOH TO CHANGE ROT HEAD.
 01:00 06:00 5.0 REMOVE OLD ROT HEAD, INSTALL NEW.

FULL CREWS, NO ACCIDENTS.
 SAFETY MEETINGS - TRI[PPING, X/O ROT HEAD.
 FUEL - 2000 GALS, USED - 1100 GALS.
 UNMANNED ML UNIT - 2 DAYS.

06:00 06:00 24.0 SPUD 7 7/8" HOLE AT 22:00 HRS, 4/22/08.

04-24-2008 **Reported By** PAT CLARK

Daily Costs: Drilling	\$57,587	Completion	\$0	Daily Total	\$57,587
Cum Costs: Drilling	\$365,294	Completion	\$819	Well Total	\$366,113

MD 4,975 **TVD** 4,975 **Progress** 2,390 **Days** 2 **MW** 8.6 **Visc** 27.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 4975'

Start	End	Hrs	Activity Description
06:00	07:30	1.5	TIH.
07:30	09:00	1.5	DRILL 2585' - 2695'. WOB 12-15K, RPM 60/67, SPP 850 PSI, DP 250 PSI, ROP 74 FPH.
09:00	09:30	0.5	SURVEY @ 2620' - 2 DEG.
09:30	13:30	4.0	DRILL 2695' - 3135'. SAME PARAMETERS, ROP 110 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM, FUNCTION PIPE RAMS.
14:00	18:30	4.5	DRILL 3135' - 3704'. SAME PARAMETERS, ROP 126 FPH.
18:30	19:00	0.5	SURVEY @ 3629' - 2 DEG.
19:00	03:00	8.0	DRILL 3704' - 4685'. SAME PARAMETERS, ROP 123 FPH.
03:00	03:30	0.5	SURVEY @ 4610' - 1.75 DEG.
03:30	06:00	2.5	DRILL 4685' - 4975'. SAME PARAMETERS, ROP 116 FPH.

FULL CREWS, NO ACCIDENTS, BOP DRILL BOTH TOURS.
 SAFETY MEETINGS - FRAYED SNUB LINES, ATTITUDE.
 FUEL - 6766 GALS, DEL - 4500 GALS.
 CURRENT FORMATION - WASATCH.
 CURRENT MW - 9.2 PPG, VIS - 30 SPQ.
 UNMANNED ML UNIT - 2 DAYS.

04-25-2008 **Reported By** PAT CLARK

Daily Costs: Drilling	\$41,145	Completion	\$0	Daily Total	\$41,145
Cum Costs: Drilling	\$406,440	Completion	\$819	Well Total	\$407,259

MD 6,775 **TVD** 6,775 **Progress** 1,800 **Days** 3 **MW** 9.5 **Visc** 30.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 6775'

Start	End	Hrs	Activity Description
06:00	15:00	9.0	DRILL 4975' - 5658'. WOB 15-19K, RPM 60-68/67, SPP 1200 PSI, DP 300 PSI, ROP 76 FPH.
15:00	15:30	0.5	RIG SERVICE. CHECK COM, FUNCTION ANNULAR.
15:30	06:00	14.5	DRILL 5658' - 6775'. SAME PARAMETERS, ROP 77 FPH. FULL CREWS, NO ACCIDENTS, BOP DRILLS BOTH TOURS. SAFETY MEETINGS - FORKLIFT, BOP DRILLS. FUEL - 5438 GALS, USED - 1328 GALS. CURRENT FORMATION - NORTH HORN. CURRENT MW - 9.7 PPG, VIS - 31 SPQ. UNMANNED ML UNIT - 3 DAYS.

04-26-2008	Reported By	PAT CLARK									
Daily Costs: Drilling	\$43,432	Completion	\$0	Daily Total	\$43,432						
Cum Costs: Drilling	\$450,098	Completion	\$819	Well Total	\$450,917						
MD	7,840	TVD	7,840	Progress	1,264	Days	4	MW	10.0	Visc	30.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							
Activity at Report Time: DRILLING @ 7840'											

Start	End	Hrs	Activity Description
06:00	10:00	4.0	DRILL 6775' - 6974'. WOB 15-20K, RPM 55-65/67, SPP 1450 PSI, DP 150 PSI, ROP 50 FPH.
10:00	10:30	0.5	RIG SERVICE. CHECK COM.
10:30	13:30	3.0	DROP SURVEY, PUMP PILL, TOH.
13:30	16:00	2.5	L/D REAMERS, MM, BIT. P/U NEW MM, BIT, TIH. FILL PIPE @ 3500'.
16:00	06:00	14.0	DRILL 6974' - 7840'. WOB 12-18K, RPM 60/67, SPP 1600 PSI, DP 350 PSI, ROP 62 FPH. FULL CREWS, NO ACCIDENTS. SAFETY MEETINGS - MAN BASKET, FRAYED SNUB LINES. FUEL - 3466 GALS, USED - 1972 GALS. CURRENT FORMATION - KMV PRICE RIVER MIDDLE. CURRENT MW - 10 PPG, VIS - 32 SPQ. UNMANNED ML UNIT - 4 DAYS.

04-27-2008	Reported By	PAT CLARK									
Daily Costs: Drilling	\$30,913	Completion	\$0	Daily Total	\$30,913						
Cum Costs: Drilling	\$481,011	Completion	\$819	Well Total	\$481,830						
MD	8,750	TVD	8,750	Progress	910	Days	5	MW	10.0	Visc	33.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							
Activity at Report Time: DRILLING @ 8750'											

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 7840' - 8278'. WOB 15-19K, RPM 60/67, SPP 1650 PSI, DP 300 PSI, ROP 58 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM, FUNCTION PIPE RAMS.
14:00	06:00	16.0	DRILL 8278' - 8750'. SAME PARAMETERS, ROP 30 FPH. FULL CREWS, NO ACCIDENTS, BOP DRILLS BOTH TOURS. SAFETY MEETINGS - GRINDING WHEELS, RIGHT TOOL FOR THE JOB. FUEL - 2701 GALS, USED - 765 GALS. CURRENT FORMATION - KMV PRICE RIVER LOWER. CURRENT MW - 10.4 PPG, VIS - 34 SPQ.

UNMANNED ML UNIT - 5 DAYS.

04-28-2008 Reported By PAT CLARK

Daily Costs: Drilling	\$33,859	Completion	\$0	Daily Total	\$33,859
Cum Costs: Drilling	\$514,871	Completion	\$819	Well Total	\$515,690

MD 9,150 TVD 9,150 Progress 400 Days 6 MW 10.4 Visc 34.0

Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: R/U TO RUN 4 1/2" CSG

Start	End	Hrs	Activity Description
06:00	20:00	14.0	DRILL 8750' - 9150' TD. WOB 15-20K, RPM 60/67, SPP 1750 PSI, DP 350 PSI, ROP 29 FPH. REACHED TD @ 20:00 HRS, 4/27/08.
20:00	20:30	0.5	CIRCULATE AND CONDITION F/SHORT TRIP.
20:30	21:30	1.0	SHORT TRIP 23 STANDS.
21:30	23:00	1.5	CIRCULATE AND CONDITION TO LDDP. R/U WEATHERFORD TRS. PUMP PILL.
23:00	05:30	6.5	LDDP, BHA. R/D TRS. PULL WEAR BUSHING.
05:30	06:00	0.5	R/U TO RUN 4 1/2" CSG.

FULL CREWS, NO ACCIDENTS, FUNCTION BLIND RAMS.

SAFETY MEETINGS - MAN BASKET, LDDP, RUN CSG.

FUEL - 1675 GALS, USED- 1026 GALS.

CURRENT MW - 10.7 PPG, VIS - 36 SPQ.

UNMANNED ML UNIT - 5 DAYS, RELEASED 4-27-08.

04-29-2008 Reported By PAT CLARK

Daily Costs: Drilling	\$61,383	Completion	\$146,883	Daily Total	\$208,266
Cum Costs: Drilling	\$576,254	Completion	\$147,702	Well Total	\$723,956

MD 9,150 TVD 9,150 Progress 0 Days 7 MW 10.6 Visc 35.0

Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: RDRT/WO COMPLETION

Start	End	Hrs	Activity Description
06:00	11:30	5.5	HSM. RUN 4 1/2", 11.6#, N-80, LTC CASING AS FOLLOWS: FLOAT SHOE, 1 JT CSG, FLOAT COLLAR, 64 JTS CSG, MARKER JOINT @ 6488', 56 JTS CSG, MJ @ 4217', 104 JTS CSG (225 TOTAL). LANDED AT 9132' KB, FC AT 9088'. P/U JT # 226, TAG BOTTOM @ 9150'. L/D JT # 226, P/U LANDING JT, CASING HANGER AND PUP, LAND IN CASING HEAD W/69,000#. R/D WEATHERFORD TRS.
11:30	14:30	3.0	HSM, R/U SCHLUMBERGER. PRESSURE TEST LINES TO 5000 PSI, CEMENT WELL AS FOLLOWS: PUMP 20 BBLs MUD FLUSH, 20 BBLs FRESH WATER, MIX AND PUMP 255 SX(135 BBLs, 760 CU/FT) LEAD G CEMENT @ 11.5 PPG, 2.98 YLD, H2O 18.227 GAL/SK + 10% D020 + .2% D046 + .2% D167 + .5% D065 + .125 LB/SK D130. MIX AND PUMP 1475 SX (339 BBLs, 1903 CU/FT) TAIL 50/50 POZ G CEMENT @ 14.1 PPG, 1.29 YLD, H2O 5.963 GAL/SK + 2% D020 + .1% D046 + .2% D065 + .2% D167 + .1% D013. WASH UP TO PIT, DROP TOP PLUG AND DISPLACE W/142 BBLs H2O W/2 GALS/1000 L064. FULL RETURNS. MAX PRESSURE 2400 PSI, BUMP PLUG TO 3400 PSI. BLED BACK 2 BBLs, FLOAT HELD. R/D SCHLUMBERGER.
14:30	17:00	2.5	PACK OFF AND TEST CASING HEAD. NDBOP, CLEAN MUD TANKS.

FULL CREWS, NO ACCIDENTS.

SAFETY MEETINGS - L/D DP, RUN CSG, CEMENTING.

FUEL - 850 GALS, USED - 825 GALS
 CAMP MOVED TO ECW 60-16.
 WESTROC TRUCKING TO MOVE RIG 1.1 MILES TO ECW 60-16 @ 07:00.
 TRANSFER 9 JTS 4 1/2", 11.6#, N-80, LTC CSG (361.61' TOL) TO ECW 60-16.
 TRANSFER 2 MJ 4 1/2", 11.6#, HCP-110, LTC CSG (21.30' TOL) TO ECW 60-16.
 TRANSFER 850 GALS DIESEL @ \$3.91/GAL TO ECW 60-16.

17:00 06:00 13.0 RDRT.

06:00 06:00 24.0 RIG RELEASED @ 17:00 HRS, 4/28/08.
 CASING POINT COST \$576,255

05-04-2008 Reported By MCCURDY

Daily Costs: Drilling \$0 **Completion** \$45,236 **Daily Total** \$45,236
Cum Costs: Drilling \$576,254 **Completion** \$192,938 **Well Total** \$769,192

MD 9,150 **TVD** 9,150 **Progress** 0 **Days** 8 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0 Perf :** **PKR Depth : 0.0**

Activity at Report Time: WO COMPLETION

Start End Hrs Activity Description

06:00 06:00 24.0 2-MAY-2008 MIRU SCHLUMBERGER. LOG WITH RST/CBL/CCL/VDL/GR FROM PBTD TO 480' EST CEMENT TOP @ 750'. RD SCHLUMBERGER.

NU 10M FRAC TREE. PRESSURE TESTED FRAC TREE & CASING TO 6500 PSIG. WO COMPLETION.

05-15-2008 Reported By CARLSON

Daily Costs: Drilling \$0 **Completion** \$443 **Daily Total** \$443
Cum Costs: Drilling \$576,254 **Completion** \$193,381 **Well Total** \$769,635

MD 9,150 **TVD** 9,150 **Progress** 0 **Days** 9 **MW** 0.0 **Visc** 0.0

Formation : MESA VERDE **PBTD : 0.0 Perf :** 8751-8924 **PKR Depth : 0.0**

Activity at Report Time: FRAC

Start End Hrs Activity Description

06:00 06:00 24.0 PERFORATE LPR FROM 8751'-52', 8758'-59', 8784'-85', 8796'-97', 8810'-11', 8826'-27', 8858'-60', 8882'-83', 8896'-98', 8923'-24' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 5207 GAL YF116 ST+ PAD, 34153 GAL YF116 ST+ WITH 89900 # 20/40 SAND @ 1-4 PPG. MTP 7303 PSIG. MTR 54.5 BPM. ATP 5079 PSIG. ATR 44.9 BPM. ISIP (SCREEN OUT) PSIG. RD SCHLUMBERGER. FLOW WELL ON 24/64 CK FOR 2 HOURS AND 45 MINUTES. SAND TO SURFACE IN 1 HOUR AND 10 MINUTES. RECOVERED 230 BBLs FLUID. SWIFN

05-16-2008 Reported By CARLSON

Daily Costs: Drilling \$0 **Completion** \$8,808 **Daily Total** \$8,808
Cum Costs: Drilling \$576,254 **Completion** \$202,189 **Well Total** \$778,444

MD 9,150 **TVD** 9,150 **Progress** 0 **Days** 10 **MW** 0.0 **Visc** 0.0

Formation : MESA VERDE **PBTD : 0.0 Perf :** 7696-8924 **PKR Depth : 0.0**

Activity at Report Time: FRAC

Start End Hrs Activity Description

06:00 06:00 24.0 SICP 1945 PSIG. RUWL. SET 10K CFP @ 8720' & PERFORATE LPR FROM 8495'-96', 8527'-28', 8561'-62', 8602'-03', 8609'-10', 8614'-15', 8625'-26', 8636'-37', 8660'-61', 8677'-78', 8693'-94' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 9930 GAL YF116 ST+ PAD 38059 GAL YF116 ST+ WITH 107800# 20/40 SAND @ 1-4 PPG. MTP 6222 PSIG. MTR 51.8 BPM. ATP 5114 PSIG. ATR 48.2 BPM. ISIP 3000 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K CFP @ 8460' & PERFORATE MPR FROM 8273'-74', 8290'-91', 8299'-8300', 8306'-07', 8329'-30', 8353'-54', 8368'-69', 8373'-74', 8396'-97', 8416'-17', 8426'-27', 8444'-45' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 11088 GAL YF116 ST+ PAD, 21896 GAL YF116 ST+ WITH 33800 # 20/40 SAND @ 1-2 PPG. MTP 6560 PSIG. MTR 45.3 BPM. ATP 5816 PSIG. ATR 23.9 BPM. ISIP 3700 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K CFP AT 8250' & PERFORATE MPR FROM 8060'-61', 8067'-68', 8073'-74', 8090'-91', 8120'-21', 8129'-30', 8137'-38', 8149'-50', 8168'-69', 8186'-87', 8211'-12', 8228'-29' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 4151 GAL YF116 ST+ PAD, 45231 GAL YF116 ST+ WITH 126300# 20/40 SAND @ 1-4 PPG. MTP 6583 PSIG. MTR 48.5 BPM. ATP 5938 PSIG. ATR 29.1 BPM. ISIP 3300 PSIG. RD SCHLUMBERGER.

RUWL. SET 10K CFP AT 8030'. PERFORATE MPR FROM 7849'-50', 7858'-59', 7871'-72', 7885'-86', 7893'-94', 7906'-07', 7950'-51', 7958'-59', 7975'-76', 7994'-95'.N 8006'-07', 8016'-17' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 4164 GAL YF116ST+ PAD, 58262 GAL YF116ST+ WITH 145300# 20/40 SAND @ 1-4 PPG. MTP 6427 PSIG. MTR 53.4 BPM. ATP 5264 PSIG. ATR 46.7 BPM. ISIP 3800 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP @ 7830' & PERFORATE MPR FROM 7696'-97', 7710'-11', 7719'-20', 7728'-29', 7751'-53', 7766'-67', 7775'-76', 7781'-82', 7795'-96', 7803'-04', 7811'-12' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 4147 GAL YF116 ST+ PAD 47468 GAL YF116 ST+ WITH 134900# 20/40 SAND @ 1-5 PPG. MTP 6125 PSIG. MTR 51.8 BPM. ATP 4619 PSIG. ATR 48 BPM. ISIP 2800 PSIG. RD SCHLUMBERGER

SWIFN

05-17-2008		Reported By		CARLSON	
Daily Costs: Drilling	\$0	Completion	\$420,087	Daily Total	\$420,087
Cum Costs: Drilling	\$576,254	Completion	\$622,276	Well Total	\$1,198,531
MD	9,150	TVD	9,150	Progress	0
Formation : MESA VERDE, WASATCH		PBTD : 0.0		Perf : 5180-8924	
				Days	11
				MW	0.0
				Visc	0.0
				PKR Depth : 0.0	

Activity at Report Time: PREP TO MIRUSU

Start **End** **Hrs** **Activity Description**
 06:00 06:00 24.0 SICP 1780 PSIG RUWL SET 6K CFP @ 7670' & PERFORATE UPR FROM 7383'-84', 7393'-94', 7401'-02', 7475'-77', 7540'-41', 7569'-70', 7578'-79', 7583'-84', 7602'-03', 7646'-47', 7651'-52' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 3119 GAL YF116 ST+ PAD, 39882 GAL YF116 ST+ WITH 112500# 20/40 SAND @ 1-5 PPG. MTP 5747 PSIG. MTR 52 BPM. ATP 4512 PSIG. ATR 45.7 BPM. ISIP 2700 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP @ 7310' & PERFORATE UPR FROM 7015'-17', 7045'-46', 7057'-58', 7087'-88', 7095'-96', 7144'-45', 7183'-84', 7227'-28', 7235'-36', 7273'-74', 7282'-83' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 3095 GAL YF116 ST+ PAD 50638 GAL YF116 ST+ WITH 140400 # 20/40 SAND @ 1-5 PPG. MTP 5689 PSIG. MTR 51.7 BPM. ATP 4249 PSIG. ATR 47.6 BPM. ISIP 2330 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP @ 6984' & PERFORATE NH/UPR FROM 6747'-48', 6775'-76', 6808'-09', 6866'-68', 6874'-75', 6900'-01', 6909'-11', 6916'-17', 6947'-48', 6962'-63' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 3104 GAL YF116 ST+ PAD, 40221 GAL YF116 ST+ WITH 114700# 20/40 SAND @ 1-5 PPG. MTP 5850 PSIG. MTR 51.5 BPM. ATP 4281 PSIG. ATR 45.6 BPM. ISIP 2750 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP @ 6715' & PERFORATE NH FROM 6439'-40', 6451'-52', 6467'-68', 6514'-15', 6550'-51', 6588'-89', 6628'-31', 6643'-45', 6698'-99' @ 3 SPF @ 120? PHASING. RDWL. .RU SCHLUMBERGER, FRAC DOWN CASING WITH 3105 GAL YF116 ST+ PAD 41430 GAL YF116 ST+ WITH 110100# 20/40 SAND @ 1-5 PPG. MTP 6000 PSIG. MTR 53.8 BPM. ATP 4621 PSIG. ATR 45.9 BPM. ISIP 2680 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP @ 6300' & PERFORATE Ba FROM 5955'-56', 5965'-66', 5997'-98', 6045'-46', 6069'-70', 6087'-88', 6092'-93', 6146'-47', 6189'-90', 6212'-13', 6261'-62', 6273'-74' @ 3 SPF @ 120? PHASING. RDWL,RU SCHLUMBERGER, FRAC DOWN CASING WITH 3114 GAL YF116 ST+ PAD, 39378 GAL YF116 ST+ WITH 100700# 20/40 SAND @ 1-4 PPG. MTP 5036 PSIG. MTR 51.7 BPM. ATP 4122 PSIG. ATR 47 BPM. ISIP 1740 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP @ 5380' & PERFORATE Ca FROM 5303'-06', 5314'-17', 5324'-27', 5332'-35' @ 3 SPF @ 120? PHASING. RDWL,RU SCHLUMBERGER, FRAC DOWN CASING WITH 3108 GAL YF116 ST+ PAD 38380 GAL YF116 ST+ WITH 97700# 20/40 SAND @ 1-4 PPG. MTP 3874 PSIG. MTR 41.1 BPM. ATP 3456 PSIG. ATR 37.3 BPM. ISIP 2600 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CFP @ 5225' & PERFORATE Pp FROM 5180'-82', 5194'-96', 5200'-04', 5208'-12' @ 3 SPF @ 120? PHASING. RDWL,RU SCHLUMBERGER, FRAC DOWN CASING WITH 3111 GAL YF116 ST+ PAD, 38550 GAL YF116 ST+ WITH 96900# 20/40 SAND @ 1-4 PPG. MTP 4058 PSIG. MTR 41.8 BPM. ATP 3261 PSIG. ATR 38.4 BPM. ISIP 2400 PSIG. RD SCHLUMBERGER.

RUWL. SET 6K CBP AT 5086'. RDWL. SDFN.

05-20-2008		Reported By		HAL IVIE							
Daily Costs: Drilling		\$0		Completion		\$33,312		Daily Total		\$33,312	
Cum Costs: Drilling		\$576,254		Completion		\$655,588		Well Total		\$1,231,843	
MD	9,150	TVD	9,150	Progress	0	Days	12	MW	0.0	Visc	0.0
Formation : MESA VERDE, WASATCH			PBTD : 0.0			Perf : 5180-8924			PKR Depth : 0.0		
Activity at Report Time: CLEAN OUT AFTER FRAC											
Start	End	Hrs	Activity Description								
06:00	16:00	10.0	MIRU ROYAL WELL SERVICE. ND FRAC TREE. NU BOP. RIH W/ BIT & PUMP OFF SUB TO 5086'. RU TO DRILL OUT PLUGS. SDFN.								

05-21-2008		Reported By		HAL IVIE							
Daily Costs: Drilling		\$0		Completion		\$51,384		Daily Total		\$51,384	
Cum Costs: Drilling		\$576,254		Completion		\$706,972		Well Total		\$1,283,227	
MD	9,150	TVD	9,150	Progress	0	Days	13	MW	0.0	Visc	0.0
Formation : MESA VERDE, WASATCH			PBTD : 9088.0			Perf : 5180-8924			PKR Depth : 0.0		
Activity at Report Time: FLOW TEST											
Start	End	Hrs	Activity Description								
06:00	06:00	24.0	SICP 0 PSIG. CLEANED OUT & DRILLED OUT PLUGS @ 5086', 5225', 5380', 6300', 6715', 6984', 7310', 7670', 7830', 8030', 8250', 8460', 8720', RIH. CLEANED OUT TO PBTD @ 9088' LANDED TBG AT 7362 KB. ND BOPE. NU TREE. PUMPED OFF BIT & SUB. RDMOSU.								

FLOWED 13 HRS. 24/64" CHOKE. FTP 1200 PSIG. CP 1450 PSIG. 95 BFPH. RECOVERED 1246 BLW. 14244 BLWTR.

TUBING DETAIL LENGTH

PUMP OFF SUB 1.00'
 1 JT 2-3/8 4.7# N-80 TBG 32.34'
 XN NIPPLE 1.10'
 227 JTS 2-3/8 4.7# N-80 TBG 7311.42'
 BELOW KB 16.00'
 LANDED @ 7361.86' KB

05-22-2008 **Reported By** HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$9,838	Daily Total	\$9,838
Cum Costs: Drilling	\$576,254	Completion	\$716,810	Well Total	\$1,293,065
MD	9,150	TVD	9,150	Progress	0
		Days	14	MW	0.0
Visc					0.0
Formation : MESA VERDE, WASATCH	PBTD : 9088.0	Perf : 5180-8924		PKR Depth : 0.0	

Activity at Report Time: FLOW TEST TO SALES-INITIAL PRODUCTION-FIRST GAS SALES

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 23 HRS. 24/64" CHOKE. FTP 1150 PSIG. CP 1350 PSIG. 59 BFPH. RECOVERED 1429 BLW. 12815 BLWTR. 538 MCFD RATE. SI 1 HR TO RU BRECO SEPARATOR.

INITIAL PRODUCTION: TURNED TO GAS SALES. SITP 1150 & SICP 1400 PSIG. TURNED WELL TO QUESTAR SALES AT 12:15 PM, 5/21/08. FLOWING 348 MCFD RATE ON 20/64" POS CK. STATIC 332.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: EOG Resources, Inc.		8. WELL NAME and NUMBER: East Chapita 58-16
3. ADDRESS OF OPERATOR: 1060 E. Hwy 40 Vernal UT 84078		9. API NUMBER: 43-047-39152
PHONE NUMBER: (435) 781-9111		10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch/Mesaverde
4. LOCATION OF WELL FOOTAGES AT SURFACE: 773' FNL & 2166' FWL 40.041083 LAT 109.333622 LON		COUNTY: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 16 9S 23E S		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Site Facility Diagram</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached please find a site facility diagram.


Accepted by the
Utah Division of
Oil, Gas and Mining
for Record Only

NAME (PLEASE PRINT) <u>Kaylene R. Gardner</u>	TITLE <u>Lead Regulatory Assistant</u>
SIGNATURE	DATE <u>6/5/2008</u>

(This space for State use only)

RECEIVED
JUN 09 2008
DIV. OF OIL, GAS & MINING

Geogresources Site Facility Diagram



Well Name: EAST CHAPITA 58-16
 1/4 1/4:NE/NW Sec:16 T:9S R:23E
 County:UINTAH State:UTAH
 Lease: ML-47045

Site facility diagrams & site security plans are located at the Vernal office in Vernal, Utah. The office is located at 1060 East Hwy 40 and normal business hours are 7:00 a.m. to 4:30 p.m. Mon -Thurs and 7:00 a.m. to 1:00 p.m. Fridays.

Valve	Production Phase	Sales Phase	Water Drain
PV	O	SC	SC
LV	SC	O	SC
WD	SC	SC	O

DATED 6/5/2008

Abbreviations

AM= Allocation Meter
 AR = Access Road
 CHT = Chemical Tank
 COMP = Compressor
 CON = Condensor
 CT = Condensate Tank
 DL = Dump Line
 EP = Electrical Panel
 ET = Emergency Tank
 FW = Firewall
 LACT = LACT Unit
 LH = Line Heater
 LV = Load Valve
 MAN = Manifold
 MB = Methanol Bath
 O = Open
 PL = Production Line
 PP = Power Pole
 PT = Propane Tank
 PU = Pumping Unit
 PV = Production Valve
 PW = Produced Water
 RL = Recycle Line
 RP = Recycle Pump
 RV = Recycle Valve
 SC = Sealed Closed
 SGS = Sales Gas Scrubber
 SL = Sales Line
 SM = Sales Meter
 SO = Sealed Open
 SP = Separator
 SV = Sales Valve
 T = Treater
 TP = Trace Pump
 WD = Water Drain
 WDP = Water Disposal Pump
 WFP = Water Flood Pump
 WH = Wellhead


----- = Buried Line
 _____ = Unburied Line

◁ = Meter Display

□ = Meter Tube

○ = Production Valve

× = Valve



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-47045

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:
East Chapita 58-16

9. API NUMBER:
43-047-39152

10. FIELD AND POOL, OR WILDCAT
Natural Buttes/Wasatch/Mesaverde

11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:
NENW 16 9S 23E S

12. COUNTY
Uintah

13. STATE
UTAH

1a. TYPE OF WELL: OIL WELL GAS WELL DRY OTHER _____

b. TYPE OF WORK: NEW WELL HORIZ. LATS. DEEP-EN RE-ENTRY DIFF. RESVR. OTHER _____

2. NAME OF OPERATOR:
EOG Resources, Inc.

3. ADDRESS OF OPERATOR: **600 17th St., Suite 1000N** CITY **Denver** STATE **CO** ZIP **80229** PHONE NUMBER: **(303) 824-5526**

4. LOCATION OF WELL (FOOTAGES)
AT SURFACE: **773' FNL & 2166' FWL 40.041083 LAT 109.333622 LON**
AT TOP PRODUCING INTERVAL REPORTED BELOW: **Same**
AT TOTAL DEPTH: **Same**

14. DATE SPURRED: **4/8/2008** 15. DATE T.D. REACHED: **4/27/2008** 16. DATE COMPLETED: **5/21/2008** ABANDONED READY TO PRODUCE

17. ELEVATIONS (DF, RKB, RT, GL):
4943' NAT GL

18. TOTAL DEPTH: MD **9,150** TVD _____ 19. PLUG BACK T.D.: MD **9,088** TVD _____ 20. IF MULTIPLE COMPLETIONS, HOW MANY? * _____ 21. DEPTH BRIDGE MD _____ TVD _____ PLUG SET: _____

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)
RST/CBL/CCL/VDL/GR Temp.

23. WAS WELL CORED? NO YES (Submit analysis)
WAS DST RUN? NO YES (Submit report)
DIRECTIONAL SURVEY? NO YES (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12-1/4"	9-5/8 J-55	36.0	0	2,478		800			
7-7/8"	4-1/2 N-80	11.6	0	9,132		1730			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-3/8"	7,362							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Wasatch/Mesaverde	5,180	8,924			8,751 8,924		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(B)					8,495 8,694		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)					8,273 8,445		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)					8,060 8,229		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD **5180 - 8924**

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
8751-8924	39,360 GALS GELLED WATER & 89,900# 20/40 SAND
8495-8694	47,989 GALS GELLED WATER & 107,800# 20/40 SAND
8273-8445	32,984 GALS GELLED WATER & 33,800# 20/40 SAND

29. ENCLOSED ATTACHMENTS:

- ELECTRICAL/MECHANICAL LOGS GEOLOGIC REPORT DST REPORT DIRECTIONAL SURVEY
 SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION CORE ANALYSIS OTHER: _____

30. WELL STATUS:
Producing

RECEIVED

JUN 24 2008

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 5/21/2008		TEST DATE: 5/29/2008		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL - BBL: 20	GAS - MCF: 842	WATER - BBL: 836	PROD. METHOD: FLOWS
CHOKE SIZE: 24/64"	TBG. PRESS. 850	CSG. PRESS. 1,850	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL: 20	GAS - MCF: 842	WATER - BBL: 836	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Wasatch/Mesaverde	5,180	8,924		Green River	1,777
				Mahogany	2,418
				Uteland Butte	4,563
				Wasatch	4,683
				Chapita Wells	5,282
				Buck Canyon	5,936
				Price River	6,894
				Middle Price River	7,666
				Lower Price River	8,430
				Sego	8,968

34. FORMATION (Log) MARKERS:

35. ADDITIONAL REMARKS (Include plugging procedure)

See attached page for additional information.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Mary A. Maestas TITLE Regulatory Assistant
 SIGNATURE *Mary A. Maestas* DATE 6/20/2008

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
 1594 West North Temple, Suite 1210
 Box 145801
 Salt Lake City, Utah 84114-5801

Phone: 801-538-5340
 Fax: 801-359-3940

East Chapita 58-16 - ADDITIONAL REMARKS (CONTINUED):

26. PERFORATION RECORD

7849-8017	3/spf
7696-7812	3/spf
7383-7652	3/spf
7015-7283	3/spf
6747-6963	3/spf
6439-6699	3/spf
5955-6274	3/spf
5303-5335	3/spf
5180-5212	3/spf

27. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.

8060-8229	49,382 GALS GELLED WATER & 126,300# 20/40 SAND
7849-8017	62,426 GALS GELLED WATER & 145,300# 20/40 SAND
7696-7812	51,615 GALS GELLED WATER & 134,900# 20/40 SAND
7383-7652	43,001 GALS GELLED WATER & 112,500# 20/40 SAND
7015-7283	53,733 GALS GELLED WATER & 140,400# 20/40 SAND
6747-6963	43,325 GALS GELLED WATER & 114,700# 20/40 SAND
6439-6699	44,535 GALS GELLED WATER & 110,100# 20/40 SAND
5955-6274	42,492 GALS GELLED WATER & 100,700# 20/40 SAND
5303-5335	41,488 GALS GELLED WATER & 97,700# 20/40 SAND
5180-5212	41,661 GALS GELLED WATER & 96,900# 20/40 SAND

Perforated the Lower Price River from 8751-52', 8758-59', 8784-85', 8796-97', 8810-11', 8826-27', 8858-60', 8882-83', 8896-98' & 8923-24' w/ 3 spf.

Perforated the Lower Price River from 8495-96', 8527-28', 8561-62', 8602-03', 8609-10', 8614-15', 8625-26', 8636-37', 8660-61', 8677-78' & 8693-94' w/ 3 spf.

Perforated the Middle Price River from 8273-74', 8290-91', 8299-8300', 8306-07', 8329-30', 8353-54', 8368-69', 8373-74', 8396-97', 8416-17', 8426-27' & 8444-45' w/ 3 spf.

Perforated the Middle Price River from 8060-61', 8067-68', 8073-74', 8090-91', 8120-21', 8129-30', 8137-38', 8149-50', 8168-69', 8186-87', 8211-12' & 8228-29' w/ 3 spf.

Perforated the Middle Price River from 7849-50', 7858-59', 7871-72', 7885-86', 7893-94', 7906-07', 7950-51', 7958-59', 7975-76', 7994-95', 8006-07' & 8016-17' w/ 3 spf.

Perforated the Middle Price River from 7696-97', 7710-11', 7719-20', 7728-29', 7751-53', 7766-67', 7775-76', 7781-82', 7795-96', 7803-04' & 7811-12' w/ 3 spf.

Perforated the Upper Price River from 7383-84', 7393-94', 7401-02', 7475-77', 7540-41', 7569-70', 7578-79', 7583-84', 7602-03', 7646-47' & 7651-52' w/ 3 spf.

Perforated the Upper Price River from 7015-17', 7045-46', 7057-58', 7087-88', 7095-96', 7144-45', 7183-84', 7227-28', 7235-36', 7273-74' & 7282-83' w/ 3 spf.

Perforated the North Horn/Upper Price River from 6747-48', 6775-76', 6808-09', 6866-68', 6874-75', 6900-01', 6909-11', 6916-17', 6947-48' & 6962-63' w/ 3 spf.

Perforated the North Horn from 6439-40', 6451-52', 6467-68', 6514-15', 6550-51', 6588-89', 6628-31', 6643-45' & 6698-99' w/ 3 spf.

Perforated the Ba from 5955-56', 5965-66', 5997-98', 6045-46', 6069-70', 6087-88', 6092-93', 6146-47', 6189-90', 6212-13', 6261-62' & 6273-74' w/ 3 spf.

Perforated the Ca from 5303-06', 5314-17', 5324-27' & 5332-35' w/ 3 spf.

Perforated the Pp from 5180-82', 5194-96', 5200-04' & 5208-12' w/ 3 spf.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-47045

SUNDRY NOTICES AND REPORTS ON WELLS

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

7. UNIT or CA AGREEMENT NAME:

1. TYPE OF WELL
OIL WELL GAS WELL OTHER _____

8. WELL NAME and NUMBER:
East Chapita 58-16

2. NAME OF OPERATOR:
EOG Resources, Inc.

9. API NUMBER:
43-047-39152

3. ADDRESS OF OPERATOR:
1060 East Highway 40 Vernal UT 84078

PHONE NUMBER:
(435) 781-9145

10. FIELD AND POOL, OR WILDCAT:
Natural Buttes/Wasatch/Mesaverde

4. LOCATION OF WELL
FOOTAGES AT SURFACE: **773' FNL & 2166' FWL 40.041083 LAT 109.333622 LON**
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: **NENW 16 9S 23E S**

COUNTY: **Uintah**
STATE: **UTAH**

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input checked="" type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

All material, debris, trash, and junk was removed from the location. The reserve pit was reclaimed. Stockpiled topsoil was spread over the pit area and broadcast seeded with the prescribed seed mixture. The seeded area was then walked down with a cat. Interim reclamation was completed on 7/18/2008.

NAME (PLEASE PRINT) Mickenzie Thacker TITLE Operations Clerk
SIGNATURE *Mickenzie Thacker* DATE 2/4/2009

(This space for State use only)

RECEIVED
FEB 09 2009
DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47045	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
7. UNIT or CA AGREEMENT NAME:	
8. WELL NAME and NUMBER: E CHAPITA 58-16	
9. API NUMBER: 43047391520000	
9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
COUNTY: UINTAH	
STATE: UTAH	

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL Gas Well	
2. NAME OF OPERATOR: EOG Resources, Inc.	
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1000 N , Denver, CO, 80202	
PHONE NUMBER: 435 781-9111 Ext	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0773 FNL 2166 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 16 Township: 09.0S Range: 23.0E Meridian: S	

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/9/2012	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <input type="text" value="Measurement variance propd"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. respectfully requests authorization to measure and allocate produced gas, condensate and water production as per the attached proposal.

Approved by the Utah Division of Oil, Gas and Mining
Date: May 11, 2012
By: *D. K. Quist*

NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A	DATE 4/9/2012	



Sales Gas meter building:
All gas going to sales will be measured at this point.
Run gas for lease consumption will also be measured at this point.


Gas lift meter building:
All gas going to gas lift is measured at this point.

East Chapita 47-16 location,
central facility for Section 16
All official measurement of
gas, oil, and water will occur
on this location

ECWU
47-16

R1000









*EOG Resources, Inc.
1060 E Hwy 40
Vernal, Utah 84078*

FedEx
7933 4391 7041

March 14, 2012

Division of Natural Resources
Utah Division of Oil, Gas, and Mining
Attn: Dustin Doucet, Randy Thackery
1594 West North Temple, Suite 1210
Salt Lake City, UT 84116

RE: Central Facility - Gathering System
Hydrocarbon Measurement Proposal
Section 16 T9S R23E
Uintah County, Utah

Gentlemen:

EOG Resources has submitted a proposal to the School and Institutional Trust Land Administration (SITLA) to install a Central Production Facility / Gathering System for Lease ML-47045. The facility will be located in the SWNE of Section 16, Township 09 South, Range 23 East, on an expanded East Chapita Wells (ECW) 47-16 well location. As you are aware, we have been producing a couple of the wells (ECW 103-16 and ECW 106-16) in section 16 utilizing gas lift operations to enhance production from the wells and have been encouraged with the results of that operation. Based on that fact, we intend to incorporate gas compression into Central Production Facility where we can process the gas, compress it and then send dry gas back to the wells for enhanced recovery via gas lift operations. All of the gas that we use for gas lift operations will be pulled out of the gathering system prior to the measurement point at the Central Facility. We believe that by moving our operations to a central facility, we can reduce air emissions, lower our operating costs (eliminating water hauling by pumping the water to the Coyote disposal facility located in Section 16), enhance our production and ultimately extend the life of the wells. At this time, we intend to measure all production from Lease ML-47045 at the central facility except for the production from ECW 59-16 well which will be measured on location utilizing the existing orifice meter for gas measurement and tank gauging for condensate and water measurement. Currently, the ECW 59-16 well is the only well in Section 16 that is located north of Coyote Wash and we would have to cross the wash to bring the well into the central facility. Eventually, as we continue to develop the lease we would bring the ECW 59-16 well into the central facility. At this time, we intend to leave the existing separator / dehydrator units on location in order to test our wells.

Therefore, EOG Resources would like to propose the following methods to measure the gas, condensate and water production from the aforementioned lease (except for the ECW 59-16) and



EOG Resources, Inc.
1060 E Hwy 40
Vernal, Utah 84078

the methods that we would like to use to measure and allocate production back to the remaining producing wells in the lease.

Gas Measurement – all gas leaving the lease from the central facility will be measured using an electronic flow meter (EFM) with orifice plate that is compliant with American Gas Association No. 3 (AGA) standards and State of Utah Regulations (R649-2-8). This meter will be calibrated on a quarterly basis.

Allocation Method – In an effort to reduce emissions, we intend to produce the wells directly into the gathering system. At least initially, we intend to leave the existing Separator / Dehydrator unit in place and utilize the existing EFM to test the wells on a quarterly basis. This will allow us to allocate production back to the individual wells based on well tests. Each well test will be run for a minimum of 24 hours. Therefore, we propose to allocate gas production to each well by totalizing the results of the well tests for every well and then utilize the results of each individual well to determine a percentage of the total that each well contributes to the total. We will take that percentage for each well and multiply it times the total production that is measured leaving the lease at the central facility on a daily basis. That gas volume will be allocated back to each well and will be reported on a monthly basis.

Gas Lift Operations – Every well in the lease will be evaluated on a case by case basis as to the viability to add gas lift operations to the well. We would like to propose, that for each well that we decide to convert to gas lift or the wells where we have already installed gas lift operations, to measure the injected gas via an EFM (orifice or v-cone) meter at the well site. Therefore, for each well that has had gas lift installed, the volume used for the percentage calculation for allocation to each well will be determined by subtracting the injected volume (per 24 hour period) from the produced volume that was determined during the well test for each well.

Oil / Condensate / Water Measurement – all condensate produced will be sold at the central facility via a Lease Automatic Custody Transfer (LACT) meter. The LACT meter will be proven on a quarterly basis. All water produced will be measured by a master (turbine) meter at the central facility prior to entering the pipeline that goes to the Coyote Saltwater Disposal Facility that is located within the lease boundary.

Allocation Method – We intend to install turbine meters on the dumps in the existing Separator / Dehydrator unit at each well so that we can accurately measure the condensate and water production from each well during the well tests. Therefore, we propose to allocate condensate and water production to each well by totalizing the results of the well tests for every well and then utilize the results of each individual well to determine a percentage of the total that each well contributes to the total. We will take that condensate percentage from each well and multiply it times the total condensate sold at the central facility per month for the allocated condensate production for each well and take the water percentage from each well and multiply it times water volume that is measured per month via the master meter that is located at the central facility for the allocated water production for each well. Those condensate and water volumes will be allocated back to each well and will be reported on a monthly basis.



EOG Resources, Inc.
1060 E Hwy 40
Vernal, Utah 84078

I look forward to hearing from you soon regarding our proposal. If you need any other information from me, I can be reached at (435) 781-9100 (office) or (435) 828-8236 (cell).

Sincerely,

A handwritten signature in black ink, appearing to read "Ed Forsman".

Ed Forsman
Production Engineering Advisor
EOG Resources – Vernal Operations

cc: Ted Kelly – Big Piney Office
Jim Schaefer – Denver Office
Denver file

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG RESOURCES Operator Account Number: N 9550
 Address: 600 17th St., Ste. 1000N
city Denver
state CO zip 80202 Phone Number: (303) 824-5590

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39152	EAST CHAPITA 58-16		NENW	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
D	16785	18940	4/8/2008			3/12/2013	
Comments:							
3/12/13							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-38988	EAST CHAPITA 31-16		NWSW	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
D	16820	18940	4/26/2008			3/12/2013	
Comments:							
3/12/13							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39060	EAST CHAPITA 48-16		SENE	16	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
D	16863	18940	5/13/2008			3/12/2013	
Comments:							
3/12/13							

RECEIVED

MAR 11 2013

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Vail Nazzaro

Name (Please Print)

Vail Nazzaro
Signature

Senior Regulatory Assistant

Title

3/8/2013

Date