

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER


FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007


| | |
|--|--|
| 5. Lease Serial No. U-011336 | |
| 6. If Indian, Allottee or Tribe Name | |
| 7. If Unit or CA Agreement, Name and No. Natural Buttes Unit | |
| 8. Lease Name and Well No. Natural Buttes Unit 630-01E | |
| 9. API Well No. 4304739298 | |
| 10. Field and Pool, or Exploratory Natural Buttes/Wasatch/Mesaverde | |
| 11. Sec., T. R. M. or Blk. and Survey or Area Section 1, T10S, R22E S.L.B.&M | |
| 12. County or Parish Uintah | 13. State UT |
| 14. Distance in miles and direction from nearest town or post office* 54.4 Miles South of Vernal, UT | |
| 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 763 Lease Line | 16. No. of acres in lease 523 |
| 17. Spacing Unit dedicated to this well Suspended | |
| 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1580 | 19. Proposed Depth 6967 |
| 20. BLM/BIA Bond No. on file NM 2308 | |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5112 GL | 22. Approximate date work will start* |
| | 23. Estimated duration 45 Days |

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the BLM.

| | | |
|--|---|---------------------------|
| 25. Signature  | Name (Printed Typed) Kaylene R. Gardner | Date 05/07/2007 |
| Title Sr. Regulatory Assistant | | |

| | | |
|--|--|-------------------------|
| Approved by (Signature)  | Name (Printed Typed) BRADLEY G. HILL | Date 05-14-07 |
| Title ENVIRONMENTAL MANAGER | | |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

**Federal Approval of this
Action is Necessary**

RECEIVED

MAY 10 2007

DIV. OF OIL, GAS & MINING

T10S, R22E, S.L.B.&M.

R
22
E

R
23
E

EOG RESOURCES, INC.

Well location, NBU #630-1E, located as shown in the NE 1/4 SE 1/4 of Section 1, T10S, R22E, S.L.B.&M., Uintah County, Utah.

T9S
T10S

WEST - 5280.00' (G.L.O.)

N00°16'W - 2679.60' (G.L.O.)

N00°22'W - 2667.72' (G.L.O.)

N00°01'55"W - 2623.25' (Meas.)

S00°08'58"W - 2644.56' (Meas.)

LOT 4

LOT 3

LOT 2

LOT 1

1991 Alum. Cap,
0.5' High, Pile of
Stones, Steel Post

1991 Alum. Cap,
0.4' High, Pile
of Stones

NBU #630-1E
Elev. Ungraded Ground = 5112'

763'

1844'

1991 Alum. Cap,
0.4' High, Pile of
Stones, Steel Post

1991 Alum. Cap,
0.3' High, Pile of
Stones, Steel Post

S89°55'57"W - 2640.76' (Meas.)

N89°42'21"W - 2640.44' (Meas.)


1991 Brass Cap, 0.2'
Above 1.5' High Pile
of Stones

BASIS OF ELEVATION

BENCH MARK (20EAM) LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.


BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS CONDUCTED UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)
LATITUDE = 39°58'32.60" (39.975722)
LONGITUDE = 109°22'53.52" (109.381533)
(NAD 27)
LATITUDE = 39°58'32.72" (39.975756)
LONGITUDE = 109°22'51.07" (109.380853)

UINTAH ENGINEERING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

| | | |
|-------------------------|-----------------------------|-------------------------|
| SCALE 1" = 1000' | DATE SURVEYED: 03-07-07 | DATE DRAWN: 03-09-07 |
| PARTY G.S. C.R. L.K. | REFERENCES G.L.O. PLAT | |
| WEATHER COOL | FILE EOG RESOURCES, INC. | |

EIGHT POINT PLAN

NATURAL BUTTES UNIT 630-01E
NE/SE, SEC. 1, T10S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0'- 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

EIGHT POINT PLAN

NATURAL BUTTES UNIT 630-01E
NE/SE, SEC. 1, T10S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: 207 sks Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

Lead: 105 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 585 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9 gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

EIGHT POINT PLAN

NATURAL BUTTES UNIT 630-01E
NE/SE, SEC. 1, T10S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:


- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

EOG RESOURCES 11" 5,000 PSI W.P. BOP CONFIGURATION



EOG RESOURCES CHOKE MANIFOLD CONFIGURATION
W/ 5,000 PSI WP VALVES

PAGE 2 OF 2



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, whichever is greater.
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.



**Natural Buttes Unit 630-01E
NESE, Section 1, T10S, R22E
Uintah County, Utah**

SURFACE USE PLAN

The well pad is approximately 375 feet long with a 261-foot width, containing 2.25 acres more or less. The well access road is approximately 180 feet long with a 40-foot right-of-way, disturbing approximately 0.17 acre. New surface disturbance associated with access road and the well pad is estimated to be approximately 2.42 acres. The pipeline is approximately 283 feet long with a 20-foot right-of-way, disturbing approximately 0.12 acre.

1. EXISTING ROADS:

- A. See attached Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 54.4 miles south of Vernal, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary.

2. PLANNED ACCESS ROAD:

- A. The access road will be approximately 180' in length; **one (1) armored low water crossings will be installed** . See attached Topo B.
- B. The access road has a 40-foot ROW w/18 foot running surface.
- C. Maximum grade of the new access road will be 8 percent.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.

- I. A 40-foot permanent right-of-way is requested. No surfacing material will used.
- J. No additional storage areas will be needed for storing equipment, stockpiling, or vehicle parking.

All travel will be confined to existing access road rights-of-way.

New or reconstructed roads will be centerlined – flagged at time of location staking. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction.

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed, safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 40-foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing; nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

Traveling off the 40-foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

The entire length of the road is located within Federal Lease # U-011336, thus an off lease right-of-way is not required.

3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:

See attached TOPO map "C" for the location of wells within a one-mile radius.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

A. On Well Pad

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400-bbl vertical tanks and attaching piping.

2. Gas gathering lines – A 4" gathering line will be buried from dehy to the edge of the location.

B. Off Well Pad

1. Proposed pipeline will transport natural gas.
2. The pipeline will be a permanent feeder line.
3. The length of the proposed pipeline is 283' x 40'. The proposed pipeline leaves the southern edge of the well pad (Lease U-011336) proceeding in an easterly direction for an approximate distance of 283' tying into an existing pipeline in the NESE of Section 1, T9S, R22E. Pipe will be 4" NOM, 0.156 wall, Grade X42, Zap-Lock, electric weld with a 35 mil X-Tru coating.
4. Proposed pipeline will be a 4" OD steel, zap-lok line laid on the surface
5. Proposed pipeline will be laid on surface.
6. A 20-foot permanent pipeline right-of-way is requested. A 40-foot temporary pipeline right-of-way for construction purposes is requested, the temporary right-of-way will be utilized for a 10-day period.
7. The proposed pipeline route begins in the NESE of Section 1, T9S, R22E, proceeding easterly for 283'. The entire length of the proposed pipeline is located within Federal Lease U-011336 thus a pipeline right-of-way is not required.
8. Pipeline will be coupled using the Zap lock method. No additional off-pad facilities will be required.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All facilities will be painted with Carlsbad Canyon.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

5. LOCATION AND TYPE OF WATER SUPPLY:

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/or Bonanza Power Plant water source in Sec 26, T8S, R23E Uintah County, UT (State Water Right # 49-225(A31368)). Water will be hauled by a licensed trucking company.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIALS:

- A. All construction material for this pipeline will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL:

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
 - 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
 - 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
 - 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, CWU 550-30N SWD or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
 - 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit or by removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with felt and a 16-millimeter plastic liner and sufficient bedding (i.e. weed free straw, or hay; felt; polyswell or soil) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation

hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well. Furthermore, extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will not be used, produced, stored, transported, or disposed of in association with the drilling, testing or completion of the well.

8. ANCILLARY FACILITIES:

None anticipated.

9. WELL SITE LAYOUT:

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the north corner of the location. The flare pit will be located downwind of the prevailing wind direction on the west side of the location, a minimum of 100 feet from the wellhead and 30 feet from the reserve pit fence.

The stockpiled pit topsoil (first six inches) will be stored separate from the location topsoil north of corner #5. The location topsoil will be stockpiled in a location providing easy access for interim reclamation and protection from existing topography. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the north

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)

- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently counted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RECLAMATION OF THE SURFACE:

A. Interim Reclamation (Producing Location)

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours – See attached Figure #3. The reserve pit will be reclaimed within 90 days from the date of the well completion, or as soon as environmental conditions allow. Before any dirt takes place, the reserve pit must be completely dry and free of all foreign obstacles.

The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

| Seed Mixture | Drilled Rate (lbs./acre PLS*) |
|---------------------|--|
| HyCrest Wheatgrass | 9.0 |
| Prostrate kochia | 3.0 |

*Pure live seed (PLS) formula: percent of purity of seed mixture times percent germination of seed mixture equals portion of seed mixture that is PLS.

B. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriated surface rehabilitation conditions of approval.

| Seed Mixture | Drilled Rate (lbs./acre PLS*) |
|------------------------|--|
| Wyoming Big Sage | 3.0 |
| Indian Ricegrass | 3.0 |
| Needle and Threadgrass | 3.0 |
| HyCrest Wheatgrass | 1.0 |
| Winterfat | 1.0 |

*Pure live seed (PLS) formula: percent of purity of seed mixture times percent germination of seed mixture equals portion of seed mixture that is PLS.

11. SURFACE OWNERSHIP:

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

Bureau of Land Management

12. OTHER INFORMATION:

A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:

- Whether the materials appear eligible for the National Register of Historic Places;

- The mitigation measures the operator will likely have to undertake before the site can be used.
- A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways-for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)
- D. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

A cultural resources survey will be conducted and submitted by Montgomery Archaeological Consultants. A paleontological survey will be conducted and submitted by Intermountain Paleo.

LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

PERMITTING AGENT

Kaylene R. Gardner
EOG Resources, Inc.
P.O. Box 1815
Vernal, Ut 84078
(435) 781-9111

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.


The operator or his/her contractor shall contact the BLM office at (435) 781-4400 forty-eight (48) hours prior to construction activities.

CERTIFICATION:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the Natural Buttes Unit 630-01E well, located in the NESE, of Section 1, T10S, R22E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

May 7, 2007
Date


Kaylene R. Gardner, Sr. Regulatory Assistant

Onsite Date: April 18, 2007

EOG RESOURCES, INC.

NBU #630-1E

LOCATED IN UINTAH COUNTY, UTAH
SECTION 1, T10S, R22E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHEASTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHEASTERLY



Since 1964

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

03 07 07
MONTH DAY YEAR

PHOTO

TAKEN BY: GS.

DRAWN BY: C.P.

REVISED: 00-00-00

EOG RESOURCES, INC.
NBU #630-1E
SECTION 1, T10S, R22E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 1.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 5.1 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE #631-1E TO THE EAST; FOLLOW ROAD FLAGS IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTH; FOLLOW ROAD FLAGS IN A SOUTHERLY DIRECTION APPROXIMATELY 180' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 54.4 MILES.

EOG RESOURCES, INC.

LOCATION LAYOUT FOR

NBU #630-1E

SECTION 1, T10S, R22E, S.L.B.&M.

1844' FSL 763' FEL

FIGURE #1

Proposed Access Road


F-8.5'
El. 101.8'

SCALE: 1" = 50'
DATE: 03-09-07
Drawn By: L.K.

Sta. 3+75

F-5.8'
El. 104.5'

Round Corner
as needed




NOTE:
Flare Pit is to
be located a min.
of 100' from the
Well Head.

Existing
Drainage

Topsoil Stockpile

Pit Topsoil



C-10.7'
El. 111.0'
(btm. pit)

Reserve Pit Backfill
& Spoils Stockpile

15' WIDE BENCH

RESERVE PITS
(10' Deep)


Total Pit Capacity
W/2' of Freeboard
= 12,820 Bbls.±
Total Pit Volume
= 3,560 Cu. Yds

C-1.2'
El. 111.5'

C-2.0'
El. 112.3'

Sta. 1+75

C-1.4'
El. 111.7'



Sta. 0+50

C-15.6'
El. 115.9'
(btm. pit)

20' WIDE BENCH

C-6.8'
El. 117.1'

C-7.6'
El. 117.9'

Sta. 0+00

C-5.3'
El. 115.6'

STORAGE
TANK

Approx.
Top of
Cut Slope

Elev. Ungraded Ground at Location Stake = 5112.3'
Elev. Graded Ground at Location Stake = 5110.3'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 798-1017

EOG RESOURCES, INC.

TYPICAL CROSS SECTIONS FOR

NBU #630-1E

SECTION 1, T10S, R22E, S.L.B.&M.


1844' FSL 763' FEL

FIGURE #2

1" = 20'
X-Section
Scale
1" = 50'

DATE: 03-09-07

Drawn By: L.K.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

| | | |
|------------------------|----------|-----------------------|
| (6") Topsoil Stripping | = | 2,180 Cu. Yds. |
| Remaining Location | = | 11,120 Cu. Yds. |
| TOTAL CUT | = | 13,300 CU.YDS. |
| FILL | = | 9,330 CU.YDS. |

| | | |
|---|---|----------------|
| EXCESS MATERIAL | = | 3,970 Cu. Yds. |
| Topsoil & Pit Backfill (1/2 Pit Vol.) | = | 3,970 Cu. Yds. |
| EXCESS UNBALANCE (After Interim Rehabilitation) | = | 0 Cu. Yds. |

EOG RESOURCES, INC.
PRODUCTION FACILITY LAYOUT FOR



NBU #630-1E
SECTION 1, T10S, R22E, S.L.B.&M.
1844' FSL 763' FEL

FIGURE #3




Access
Road

SCALE: 1" = 50'
DATE: 03-09-07
Drawn By: L.K.



 RE-HABED AREA



SEE TOPO "B"

**PROPOSED LOCATION:
NBU #630-1E**

**R
22
E** **R
23
E**

LEGEND:

 PROPOSED LOCATION

EOG RESOURCES, INC.

**NBU #630-1E
SECTION 1, T10S, R22E, S.L.B.&M.
1844' FSL 763' FEL**



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**


03 07 07
MONTH DAY YEAR

SCALE: 1:100,000

DRAWN BY: C.P.

REVISED: 00-00-00

A
TOPO



LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD

EOG RESOURCES, INC.


NBU #630-1E
SECTION 1, T10S, R22E, S.L.B.&M.
1844' FSL 763' FEL



UELS
Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP
 03 07 07
 MONTH DAY YEAR
 SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00

B
TOPO



APPROXIMATE TOTAL PIPELINE DISTANCE = 283' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)

EOG RESOURCES, INC.

NBU #630-1E
SECTION 1, T10S, R22E, S.L.B.&M.
1844' FSL 763' FEL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP
03 07 07
MONTH DAY YEAR
SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00



**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 05/10/2007

API NO. ASSIGNED: 43-047-39298

WELL NAME: NBU 630-01E
 OPERATOR: EOG RESOURCES INC (N9550)
 CONTACT: KAYLENE GARDNER

PHONE NUMBER: 435-781-9111

PROPOSED LOCATION:

NESE 01 100S 220E
 SURFACE: 1844 FSL 0763 FEL
 BOTTOM: 1844 FSL 0763 FEL
 COUNTY: UINTAH
 LATITUDE: 39.97581 LONGITUDE: -109.3810
 UTM SURF EASTINGS: 638253 NORTHINGS: 4426117
 FIELD NAME: NATURAL BUTTES (630)

| INSPECT LOCATN BY: / / | | |
|------------------------|----------|------|
| Tech Review | Initials | Date |
| Engineering | | |
| Geology | | |
| Surface | | |

LEASE TYPE: 1 - Federal
 LEASE NUMBER: U-011336
 SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: WSMVD
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. NM 2308)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 49-225)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)

LOCATION AND SITING:

- R649-2-3.
- Unit: NATURAL BUTTES *OK*
- R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit
Board Cause No: 173-14
Eff Date: 12-2-1999
Siting: 460' fr ubdrgs unit comm. Tract
- R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1- Federal Approval
2- OIL SHALE



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

May 14, 2007

EOG Resources, Inc.
1060 East Highway 40
Vernal, UT 84078

Re: Natural Buttes Unit 630-01E Well, 1844' FSL, 763' FEL, NE SE, Sec. 1,
T. 10 South, R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39298.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal Office

Operator: EOG Resources, Inc.
Well Name & Number Natural Buttes Unit 630-01E
API Number: 43-047-39298
Lease: U-011336

Location: NE SE Sec. 1 T. 10 South R. 22 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division with 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office
(801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

5. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|---|--|--|
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| 2. NAME OF OPERATOR: EOG Resources, Inc. | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY Vernal STATE UT ZIP 84078 | | 7. UNIT or CA AGREEMENT NAME: Natural Buttes Unit |
| PHONE NUMBER: (435) 781-9111 | | 8. WELL NAME and NUMBER: Natural Buttes Unit 630-01E |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FSL & 763' FEL 39.975722 LAT 109.381533 LON | | 9. API NUMBER: 43-047-39298 |
| QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 1 10S 22E S.L.B. & M. | | 10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Mesaverde |
| COUNTY: UINTAH | | |
| STATE: UTAH | | |


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|---|---|---|
| <input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: APD EXTENSION REQUEST |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. respectfully requests the APD for the referenced well be extended for one year.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 05-20-08
By: 

COPY SENT TO OPERATOR
Date: 5-21-2008
Initials: KS

| | |
|--|--|
| NAME (PLEASE PRINT) <u>Kaylene R. Gardner</u> | TITLE <u>Lead Regulatory Assistant</u> |
| SIGNATURE  | DATE <u>5/19/2008</u> |

(This space for State use only)

RECEIVED
MAY 16 2008



**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-39298
Well Name: Natural Buttes Unit 630-01E
Location: 1844 FSL 763 FEL (NESE), Section 1, T10S, R22E S.L.B.&M.
Company Permit Issued to: EOG Resources, Inc.
Date Original Permit Issued: 5/14/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No


Signature

5/9/2008
Date

Title: Lead Regulatory Assistant

Representing: EOG Resources, Inc.

RECEIVED

MAY 16 2008

DIV. OF OIL, GAS & MINING

RECEIVED
VERNAL FIELD OFFICE

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

2007 MAY -8 PM 4:17

APPLICATION FOR PERMIT TO DRILL OR REENTER
DEPT. OF THE INTERIOR
BUREAU OF LAND MGMT

| | | | |
|--|---------------------------------------|---|--|
| 1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER | | 5. Lease Serial No. U-011336 | |
| 1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone | | 6. If Indian, Allottee or Tribe Name | |
| 2. Name of Operator EOG RESOURCES, INC | | 7. If Unit or CA Agreement, Name and No. Natural Buttes Unit | |
| 3a. Address 1060 East Highway 40 Vernal, UT 84078 | | 8. Lease Name and Well No. Natural Buttes Unit 630-01E | |
| 3b. Phone No. (include area code) 435-781-9111 | | 9. API Well No. 43 047 39298 | |
| 4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface 1844 FSL & 763 FEL (NESE) 39.975722 Lat 109.381533 Lon At proposed prod. zone Same | | 10. Field and Pool, or Exploratory Natural Buttes/Wasatch/Mesaverde | |
| 14. Distance in miles and direction from nearest town or post office* 54.4 Miles South of Vernal, UT | | 11. Sec., T, R, M. or Blk. and Survey or Area Section 1, T10S, R22E S.L.B.&M | |
| 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 763 Lease Line | 16. No. of acres in lease 523 | 17. Spacing Unit dedicated to this well Suspended | |
| 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1580 | 19. Proposed Depth 6967 | 20. BLM/BIA Bond No. on file NM 2308 | |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5112 GL | 22. Approximate date work will start* | 23. Estimated duration 45 Days | |

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

| | | |
|-----------------------------------|--|--------------------|
| 25. Signature | Name (Printed Typed) Kaylene R. Gardner | Date 05/07/2007 |
| Title Sr. Regulatory Assistant | | |

| | | |
|---|--------------------------------------|---------------------|
| Approved by (Signature) | Name (Printed Typed) TERRY KENZEL | Date OCT 24 2008 |
| Title Assistant Field Manager Lands & Mineral Resources | Office VERNAL FIELD OFFICE | |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

NOTICE OF APPROVAL

UDOGM

RECEIVED

OCT 29 2008

DIV. OF OIL, GAS & MINING

NOS 3/26/07
07PP16717



**UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE**



170 South 500 East

VERNAL, UT 84078

(435) 781-4400

CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

| | | | |
|-----------------|------------------------------------|-------------------|---------------------------------|
| Company: | EOG Resources, Inc. | Location: | NESE, Sec. 1, T10S, R22E |
| Well No: | Natural Buttes Unit 630-01E | Lease No: | UTU-011336 |
| API No: | 43-047-39298 | Agreement: | Natural Buttes Unit |

| Title | Name | Office Phone Number | Cell Phone Number |
|-----------------------------------|-----------------|----------------------------|--------------------------|
| Petroleum Engineer: | Matt Baker | (435) 781-4490 | (435) 828-4470 |
| Petroleum Engineer: | Michael Lee | (435) 781-4432 | (435) 828-7875 |
| Petroleum Engineer: | Ryan Angus | (435) 781-4430 | (435) 828-7368 |
| Supervisory Petroleum Technician: | Jamie Sparger | (435) 781-4502 | (435) 828-3913 |
| Supervisory NRS: | Karl Wright | (435) 781-4484 | (435) 828-7381 |
| NRS/Enviro Scientist: | Holly Villa | (435) 781-4404 | (435) 828-3544 |
| NRS/Enviro Scientist: | James Hereford | (435) 781-3412 | |
| NRS/Enviro Scientist: | Chuck Macdonald | (435) 781-4441 | (435) 828-7481 |
| NRS/Enviro Scientist: | Dan Emmett | (435) 781-3414 | |
| NRS/Enviro Scientist: | Paul Percival | (435) 781-4493 | |
| NRS/Enviro Scientist: | Michael Cutler | (435) 781-3401 | (435) 828-3546 |
| NRS/Enviro Scientist: | Anna Figueroa | (435) 781-3407 | (435) 828-3548 |
| NRS/Enviro Scientist: | Verlyn Pindell | (435) 781-3402 | (435) 828-3547 |
| NRS/Enviro Scientist: | Nathan Packer | (435) 781-3405 | (435) 828-3545 |

Fax: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

| | | |
|---|---|--|
| Location Construction (Notify Environmental Scientist) | - | Forty-Eight (48) hours prior to construction of location and access roads. |
| Location Completion (Notify Environmental Scientist) | - | Prior to moving on the drilling rig. |
| Spud Notice (Notify Petroleum Engineer) | - | Twenty-Four (24) hours prior to spudding the well. |
| Casing String & Cementing (Notify Supv. Petroleum Tech.) | - | Twenty-Four (24) hours prior to running casing and cementing all casing strings. |
| BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.) | - | Twenty-Four (24) hours prior to initiating pressure tests. |
| First Production Notice (Notify Petroleum Engineer) | - | Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days. |

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

SITE SPECIFIC COAs:

- Prevent fill and stock piles from entering drainages.
- The access road shall be crowned and ditched. Flat-bladed roads are not allowed.
- The authorized officer may prohibit surface disturbing activities during severe winter, wet, or muddy conditions to minimize watershed damage. This limitation does not apply to operation and maintenance of producing wells.
- No vehicle travel, construction or routine maintenance activities shall be performed during periods when the soil is too wet to adequately support vehicles and/or construction equipment. If such equipment creates ruts in excess of four inches deep, the soil shall be deemed too wet to adequately support construction equipment.
- If additional erosion occurs during the life of this project, more culverts, low water crossings, berms, wing ditches, or gravel (from a private or commercial source) etc. shall be installed to control the erosion. Low-water crossings and culverts shall be appropriately constructed to avoid sedimentation of drainage ways and other water resources.
- Bury pipelines at all low water crossings.
- The pit liner is to be cut 5 feet below ground surface or at the level of the cuttings, whichever is deeper, and the excess liner material is to be disposed of at an authorized disposal site.
- Permission to clear all wildlife stipulations will only be approved by the BLM authorized officer during the specific timing for the species potentially affected by this action.

***DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

SITE SPECIFIC DOWNHOLE COAs:

- A surface casing shoe integrity test shall be performed.
- A variance is granted for Onshore Order #2-Drilling Operations III. E. “blooie line discharge 100 feet from well bore and securely anchored”. Blooie line can be 75 feet.
- Poduction casing cement shall be at a minimum 200 feet inside the surface casing. A CBL shall be run from TD to top of cement and a field copy shall be sent to this field office.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller’s log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**

- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Wellogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.

- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.

- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

| | | |
|--|--|---|
| SUNDRY NOTICES AND REPORTS ON WELLS | | 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 7. UNIT or CA AGREEMENT NAME: Natural Buttes Unit |
| 2. NAME OF OPERATOR: EOG Resources, Inc. | | 8. WELL NAME and NUMBER: Natural Buttes Unit 630-01E |
| 3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY Vernal STATE UT ZIP 84078 | | 9. API NUMBER: 43-047-39298 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FSL & 763' FEL 39.975722 LAT 109.381533 LON | | 10. FIELD AND POOL, OR WLDCAT: Natural Buttes/Mesaverde |
| QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 1 10S 22E S.L.B. & M. | | COUNTY: UINTAH STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|---|---|---|
| <input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: <u>APD EXTENSION REQUEST</u> |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
EOG Resources, Inc. respectfully requests the APD for the referenced well be extended for one year.

Approved by the
Utah Division of
Oil, Gas and Mining

COPY SENT TO OPERATOR
Date: 5-12-2009
Initials: KS

Date: 05-11-09
By: [Signature]

| | |
|--|-------------------------------|
| NAME (PLEASE PRINT) <u>Mickenzie Thacker</u> | TITLE <u>Operations Clerk</u> |
| SIGNATURE <u>[Signature]</u> | DATE <u>5/5/2009</u> |

(This space for State use only)

RECEIVED
MAY 06 2009

DIV. OF OIL, GAS & MINING

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-39298
Well Name: Natural Buttes Unit 630-01E
Location: 1844 FSL 763 FEL (NESE), Section 1, T10S, R22E S.L.B.&M.
Company Permit Issued to: EOG Resources, Inc.
Date Original Permit Issued: 5/14/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes No

Has the approved source of water for drilling changed? Yes No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

Is bonding still in place, which covers this proposed well? Yes No

Michael Thayer
Signature

5/5/2009
Date

Title: Operations Clerk

Representing: EOG Resources, Inc.

RECEIVED
MAY 06 2009

DIV. OF OIL, GAS & MINING

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

X Change of Operator (Well Sold)
 Operator Name Change

Designation of Agent/Operator
 Merger

ROUTING

| |
|--------|
| 1. DJJ |
| 2. CDW |

The operator of the well(s) listed below has changed, effective: **1/1/2010**

| | |
|---|---|
| FROM: (Old Operator): N9550-EOG Resources 1060 E Hwy 40 Vernal, UT 84078 Phone: 1-(435) 781-9111 | TO: (New Operator): N2995-Kerr-McGee Oil & Gas Onshore., LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024 |
|---|---|

| WELL NAME(S) | CA No. | SEC | TWN | RNG | API NO | ENTITY NO | LEASE TYPE | WELL TYPE | WELL STATUS |
|-------------------|--------|-----|-----|-----|--------|-----------|------------|-----------|-------------|
| SEE ATTACHED LIST | | | | | | | | | |

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 12/24/2009
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 12/24/2009
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- (R649-9-2) Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM not yet BIA n/a
- Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: not yet
- Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: n/a

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 1/31/2010
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 1/31/2010
- Bond information entered in RBDMS on: 1/31/2010
- Fee/State wells attached to bond in RBDMS on: 1/31/2010
- Injection Projects to new operator in RBDMS on: n/a

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: WYB000291
- Indian well(s) covered by Bond Number: n/a
- (R649-3-1) The **NEW** operator of any state or fee well(s) listed covered by Bond Number 22013542
- The **FORMER** operator has requested a release of liability from their bond on: n/a

COMMENTS:

EOG transferred all their leases and permits in NBU to Kerr-McGee effective January 1, 2010

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
Multiple Leases

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2.

1. Type of Well

Oil Well Gas Well Other

7. If Unit of CA/Agreement, Name and/or No.
Natural Buttes

8. Well Name and No.
Multiple Wells

2. Name of Operator
EOG Resources, Inc

9. API Well No.
See Attached

3a. Address
1060 EAST HIGHWAY 40, VERNAL, UT 84078

3b. Phone No. (include area code)
435-781-9145

10. Field and Pool or Exploratory Area
Natural Buttes

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
See Attached

11. Country or Parish, State
Utah, Utah

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|--|---|---|--|---|
| <input checked="" type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other <u>Change of Operator</u> |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon | |
| | <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc. has assigned all of its right, title and interest in the wells described in the attached list ("the Subject Wells") to Kerr-McGee Oil & Gas Onshore LP and will relinquish and transfer operatorship of all of the Subject Wells to Kerr-McGee Oil & Gas Onshore LP on January 1, 2010.

As of January 1, 2010, Kerr-McGee Oil & Gas Onshore LP will be considered to be the operator of each of the Subject Wells and will be responsible under the terms and conditions of the applicable lease for the operations conducted upon the leased lands. Bond coverage is provided under Kerr-McGee Oil & Gas Onshore LP's Nationwide BLM Bond No. WYB-000291.

Kerr-McGee Oil & Gas Onshore LP
1099 18th Street, Suite 1800
Denver, CO 80202-1918

APPROVED* 1/13/10 except
Earlene Russell (1)
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

By: Michael A. Nixon Date: 12/17/2009
Michael A. Nixon
Agent and Attorney-in-Fact

14. I hereby certify that the foregoing is true and correct.

Name (Printed/Typed)
J. Michael Schween

Title Agent and Attorney-in-Fact

Signature

Date 12/17/2009

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

RECEIVED

Approved by

DEC 24 2009

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(1)

| Lease | API # | Well Name | Footages | T | R | Sec. | QQ | PROPOSED TD | APD Sub'd |
|--------------|-------------------------|--|---------------------|-----|-----|------|------|-------------|-----------|
| UTU-0581 | 43-047-40216 | Natural Buttes Unit 419-29E | 859 FNL - 2338 FWL | 9S | 21E | 29 | NENW | 6,640 | 6-26-08 |
| UTU-0581 | 43-047-50127 | Natural Buttes Unit 420-29E | 471 FNL - 2012 FEL | 9S | 21E | 29 | NWNE | 6,673 | 9-11-08 |
| UTU-01791 | 43-047-40225 | Natural Buttes Unit 430-8E | 882 FSL - 514 FWL | 10S | 21E | 8 | SWSW | 6,201 | 7-3-08 |
| UTU-01791 | 43-047-40074 | Natural Buttes Unit 432-9E | 864 FSL - 686 FWL | 10S | 21E | 9 | SWSW | 5,984 | 5-8-08 |
| UTU-010954-A | 43-047-39732 | Natural Buttes Unit 512-35E | 722 FNL - 1988 FWL | 9S | 22E | 35 | NENW | 7,412 | 10-19-07 |
| UTU-0149076 | 43-047-35688 | Natural Buttes Unit 540-24E | 521 FSL - 750 FEL | 9S | 21E | 24 | SESE | 9,800 | 8-6-04 |
| UTU-010954 | 43-047-39306 | Natural Buttes Unit 603-35E | 1047 FNL - 679 FEL | 9S | 22E | 35 | NENE | 7,257 | 5-14-07 |
| UTU-010954-A | 43-047-39302 | Natural Buttes Unit 604-35E | 1139 FNL - 1826 FEL | 9S | 22E | 35 | NWNE | 7,330 | 5-11-07 |
| UTU-010954 | 43-047-50275 | Natural Buttes Unit 605-35E | 1799 FNL - 2165 FEL | 9S | 22E | 35 | SWNE | 7,290 | 1-29-09 |
| UTU-010954-A | 43-047-39292 | Natural Buttes Unit 627-35E | 1970 FNL - 1847 FWL | 9S | 22E | 35 | SENW | 7,275 | 5-7-07 |
| UTU-6774 | 43-047-50028 | Natural Buttes Unit 672-25E | 1980 FNL - 660 FWL | 10S | 20E | 25 | SWNW | 6,032 | 2-5-08 |
| UTU-6774 | 43-047-50036 | Natural Buttes Unit 675-25E | 1977 FNL - 2110 FEL | 10S | 20E | 25 | SWNE | 6,035 | 3-14-08 |
| UTU-6774 | 43-047-50031 | Natural Buttes Unit 676-25E | 1978 FNL - 923 FEL | 10S | 20E | 25 | SENE | 6,100 | 2-12-08 |
| UTU-4476 | 43-047-40416 | Natural Buttes Unit 677-26E | 839 FNL - 1133 FWL | 10S | 20E | 26 | NWNW | 6,157 | 11-14-08 |
| UTU-4476 | 43-047-40220 | Natural Buttes Unit 678-26E | 1960' FNL - 481 FWL | 10S | 20E | 26 | SWNW | 6,254 | 7-3-08 |
| UTU-4476 | 43-047-40305 | Natural Buttes Unit 680-26E | 799 FNL - 1923 FEL | 10S | 20E | 26 | NWNE | 6,242 | 8-1-08 |
| UTU-01791 | 43-047-40417 | Natural Buttes Unit 692-6E | 661 FSL - 1840 FWL | 10S | 21E | 6 | SESW | 6,484 | 11-14-08 |
| UTU-472 | 43-047-40268 | Natural Buttes Unit 701-26E | 2215 FNL - 1770 FEL | 10S | 22E | 26 | SWNE | 7,023 | 7-24-08 |
| UTU-472 | 43-047-40240 | Natural Buttes Unit 702-26E | 2130 FSL - 1903 FEL | 10S | 22E | 26 | NWSE | 7,003 | 7-14-08 |
| UTU-472 | 43-047-40241 | Natural Buttes Unit 703-26E | 1836 FSL - 797 FEL | 10S | 22E | 26 | NESE | 6,991 | 7-14-08 |
| UTU-472 | 43-047-40267 | Natural Buttes Unit 704-26E | 785 FSL - 1806 FEL | 10S | 22E | 26 | SWSE | 6,998 | 7-24-08 |
| UTU-472 | 43-047-40374 | Natural Buttes Unit 705-26E | 552 FSL - 475 FEL | 10S | 22E | 26 | SESE | 6,957 | 9-22-08 |
| UTU-037167 | 43-047-40243 | Natural Buttes Unit 710-35E | 600 FNL - 1967 FWL | 10S | 22E | 35 | NENW | 6,984 | 7-14-08 |
| UTU-037167 | 43-047-40418 | Natural Buttes Unit 712-35E | 2160 FNL - 1923 FWL | 10S | 22E | 35 | SENW | 6,938 | 11-14-08 |
| UTU-037167 | 43-047-40242 | Natural Buttes Unit 713-35E | 739 FSL - 702 FEL | 10S | 22E | 35 | NENE | 6,902 | 7-14-08 |
| UTU-037167 | 43-047-40270 | Natural Buttes Unit 714-35E | 1957 FNL - 1881 FEL | 10S | 22E | 35 | SWNE | 6,933 | 7-24-08 |
| UTU-037167 | 43-047-40269 | Natural Buttes Unit 715-35E | 1684 FNL - 1042 FEL | 10S | 22E | 35 | SENE | 6,921 | 7-24-08 |
| UTU-0577-A | 43-047-50262 | Natural Buttes Unit 716-26E | 660 FNL - 1980 FEL | 9S | 20E | 26 | NWNE | 7,184 | 1-19-09 |
| UTU-0577-A | 43-047-40264 | Natural Buttes Unit 717-26E | 2084 FNL - 1978 FEL | 9S | 20E | 26 | SWNE | 7,180 | 7-24-08 |
| UTU-0577-A | 43-047-40210 | Natural Buttes Unit 718-26E | 2009 FNL - 557 FEL | 9S | 20E | 26 | SENE | 7,201 | 6-26-08 |
| UTU-0577-A | 43-047-50116 | Natural Buttes Unit 719-26E | 2088 FSL - 2171 FEL | 9S | 20E | 26 | NWSE | 7,164 | 9-11-08 |
| UTU-0577-A | 43-047-40265 | Natural Buttes Unit 720-26E | 1916 FSL - 685 FEL | 9S | 20E | 26 | NESE | 7,175 | 7-24-08 |
| UTU-0577-A | 43-047-50115 | Natural Buttes Unit 721-26E | 624 FSL - 1828 FEL | 9S | 20E | 26 | SWSE | 7,167 | 9-11-08 |
| UTU-0577-A | 43-047-40209 | Natural Buttes Unit 722-26E | 676 FSL - 849 FEL | 9S | 20E | 26 | SESE | 7,175 | 6-26-08 |
| UTU-0582 | 43-047-40212 | Natural Buttes Unit 723-35E | 668 FNL - 1985 FEL | 9S | 20E | 35 | NWNE | 7,093 | 7-2-08 |
| UTU-0582 | 43-047-40215 | Natural Buttes Unit 724-35E | 758 FNL 781 FEL | 9S | 20E | 35 | NENE | 7,097 | 7-2-08 |
| UTU-0582 | 43-047-40214 | Natural Buttes Unit 725-35E | 1884 FNL - 2179 FEL | 9S | 20E | 35 | SWNE | 7,074 | 6-26-08 |
| UTU-0582 | 43-047-40211 | Natural Buttes Unit 726-35E | 1966 FNL - 515 FEL | 9S | 20E | 35 | SENE | 7,084 | 6-26-08 |
| UTU-460 | 43-047-50274 | Natural Buttes Unit 727-35E | 2049 FSL - 1745 FEL | 9S | 20E | 35 | NWSE | 7,031 | 1-29-09 |
| UTU-460 | 43-047-40458 | Natural Buttes Unit 728-35E | 852 FSL - 1937 FEL | 9S | 20E | 35 | SWSE | 7,017 | 12-19-08 |

RECEIVED

DEC 24 2008

DIV. OF OIL, GAS & MINING

(1)

| Lease | API # | Well Name | Footages | T | R | Sec. | QQ | PROPOSED TD | APD Sub'd |
|----------------|-------------------------|--|---------------------|-----|-----|------|--------------|-------------|-----------|
| UTU-460 | 43-047-40213 | Natural Buttes Unit 729-35E | 554 FSL - 504 FEL | 9S | 20E | 35 | SESE | 7,036 | 6-26-08 |
| UTU-0581 | 43-047-40218 | Natural Buttes Unit 737-30E | 1948 FSL - 1071 FWL | 9S | 21E | 30 | NWSW (Lot 3) | 6,756 | 7-2-08 |
| UTU-0581 | 43-047-50468 | Natural Buttes Unit 738-30E | 1947 FSL - 2465 FWL | 9S | 21E | 30 | NESW | 6,759 | 6-8-09 |
| UTU-0581 | 43-047-40219 | Natural Buttes Unit 739-30E | 814 FSL - 2147 FWL | 9S | 21E | 30 | SESW | 6,750 | 7-2-08 |
| UTU-0581 | 43-047-50118 | Natural Buttes Unit 740-30E | 512 FSL - 780 FWL | 9S | 21E | 30 | SWSW (Lot 4) | 6,809 | 9-11-08 |
| UTU-0581 | 43-047-50128 | Natural Buttes Unit 741-30E | 661 FSL - 1980 FEL | 9S | 21E | 30 | SWSE | 6,729 | 9-11-08 |
| UTU-0581 | 43-047-40183 | Natural Buttes Unit 742-30E | 497 FSL - 618 FEL | 9S | 21E | 30 | SESE | 6,737 | 6-26-08 |
| UTU-01791 | 43-047-40222 | Natural Buttes Unit 756-6E | 1840 FSL - 2317 FWL | 10S | 21E | 6 | NESW | 6,496 | 7-3-08 |
| UTU-0129384 | 43-047-50238 | Natural Buttes Unit 757-26E | 798 FNL - 850 FEL | 10S | 21E | 26 | NENE | 6,488 | 7-14-08 |
| UTU-0129384 | 43-047-40239 | Natural Buttes Unit 758-27E | 749 FNL - 664 FEL | 10S | 21E | 27 | NENE | 5,530 | 7-14-08 |
| UTU-0581 | 43-047-40217 | Natural Buttes Unit 759-29E | 1979 FNL - 2034 FWL | 9S | 21E | 29 | SESW | 6,644 | 7-2-08 |
| UTU-01197-A-ST | 43-047-50683 | Natural Buttes Unit 634-12EX | 623 FNL - 672 FEL | 10S | 22E | 12 | NENE | 7,128 | 8-23-09 |
| ML-3140.5 | 43-047-50042 | Natural Buttes Unit 733-36E | 775 FNL - 2134 FEL | 9S | 20E | 36 | NWNE | 7,050 | 4-14-08 |
| UTU-01480-ST | 43-047-50053 | Natural Buttes Unit 744-31E | 2515 FSL - 2533 FWL | 9S | 21E | 31 | NESW | 6,989 | 6-5-08 |
| ML-22446 | 43-047-50059 | Natural Buttes Unit 749-31E | 955 FSL - 489 FEL | 9S | 21E | 31 | SESE (LOT 8) | 6,901 | 6-25-08 |
| ML-3142 | 43-047-50062 | Natural Buttes Unit 750-32E | 1091 FNL - 1615 FWL | 9S | 21E | 32 | NENW | 6,635 | 7-2-08 |
| ML-3142 | 43-047-50055 | Natural Buttes Unit 753-32E | 478 FNL - 2066 FEL | 9S | 21E | 32 | NWNE | 6,562 | 6-5-08 |

RECEIVED

DEC 24 2009

DIV. OF OIL, GAS & MINING

RECEIVED

DEC 24 2000

PERMITTED WELL LIST

DIV. OF OIL, GAS & MINING

| <u>Well Name</u> | <u>API #</u> | <u>Lease #</u> | <u>QQ</u> | <u>Sec</u> | <u>T</u> | <u>R</u> |
|--|-------------------------|----------------|--------------|------------|----------|----------|
| Natural Buttes Unit 320-6E | 43-047-40224 | UTU01791 | (Lot 6) NWSW | 6 | 10S | 21E |
| Natural Buttes Unit 375-13E | 43-047-50029 | UTU4485 | SWSW | 13 | 10S | 20E |
| Natural Buttes Unit 377-9E | 43-047-40073 | UTU01791 | NWNW | 9 | 10S | 21E |
| Natural Buttes Unit 425-4E | 43-047-39427 | UTU01393B | NWSW | 4 | 10S | 21E |
| Natural Buttes Unit 440-1E | 43-047-39857 | UTU02270A | NWSE | 1 | 10S | 20E |
| Natural Buttes Unit 441-12E | 43-047-39418 | UTU02270A | SENE | 12 | 10S | 20E |
| Natural Buttes Unit 495-31E | 43-047-50037 | ML22446 | (Lot 6) NWSW | 31 | 9S | 21E |
| Natural Buttes Unit 498-13E | 43-047-37684 | UTU4485 | NESE | 13 | 10S | 20E |
| Natural Buttes Unit 507-7E | 43-047-40048 | UTU02270A | SESW | 7 | 10S | 21E |
| Natural Buttes Unit 515-25E | 43-047-50033 | UTU6774 | NWNE | 25 | 10S | 20E |
| Natural Buttes Unit 517-6E | 43-047-40223 | UTU01791 | (Lot 7) SWSW | 6 | 10S | 21E |
| Natural Buttes Unit 531-8E | 43-047-40050 | UTU01791 | NESW | 8 | 10S | 21E |
| (1) Natural Buttes Unit 532-12E | 43-047-35200 | UTU02270A | SWNE | 12 | 10S | 20E |
| Natural Buttes Unit 606-35E | 43-047-39797 | UTU010954A | NWNW | 35 | 9S | 22E |
| Natural Buttes Unit 607-35E | 43-047-39307 | UTU010954A | SWNW | 35 | 9S | 22E |
| Natural Buttes Unit 609-23E | 43-047-39318 | UTU01393B | SENE | 23 | 10S | 22E |
| Natural Buttes Unit 610-23E | 43-047-39317 | UTU01393B | NESE | 23 | 10S | 22E |
| Natural Buttes Unit 612-23E | 43-047-39314 | UTU01393B | SWSE | 23 | 10S | 22E |
| Natural Buttes Unit 616-5E | 43-047-39304 | UTU01393B | SWNE | 5 | 10S | 21E |
| Natural Buttes Unit 619-4E | 43-047-39446 | UTU01393B | SESW | 4 | 10S | 21E |
| Natural Buttes Unit 620-30E | 43-047-39309 | ML22793 | (Lot 2) SWNW | 30 | 10S | 21E |
| Natural Buttes Unit 628-1E | 43-047-39311 | UTU01198B | SESW | 1 | 10S | 22E |
| Natural Buttes Unit 629-1E | 43-047-39312 | UTU01198B | NWSE | 1 | 10S | 22E |
| Natural Buttes Unit 630-1E | 43-047-39298 | UTU01198B | NESE | 1 | 10S | 22E |
| Natural Buttes Unit 631-1E | 43-047-39297 | UTU01198B | SESE | 1 | 10S | 22E |
| Natural Buttes Unit 649-26E | 43-047-39870 | UTU472 | NWNE | 26 | 10S | 22E |
| Natural Buttes Unit 651-26E | 43-047-39871 | UTU472 | SENE | 26 | 10S | 22E |
| Natural Buttes Unit 652-6E | 43-047-39859 | UTU01791 | SWSE | 6 | 10S | 21E |
| Natural Buttes Unit 656-1E | 43-047-39868 | UTU01791 | NWNE | 1 | 10S | 20E |
| (1) Natural Buttes Unit 657-1E | 43-047-39856 | UTU01791 | (Lot 1) NENE | 1 | 10S | 20E |
| Natural Buttes Unit 659-1E | 43-047-39855 | UTU01791 | SENE | 1 | 10S | 20E |
| Natural Buttes Unit 669-29E | 43-047-50030 | U01207ST | SWNE | 29 | 9S | 22E |

| <u>Well Name</u> | <u>API #</u> | <u>Lease #</u> | <u>QQ</u> | <u>Sec</u> | <u>T</u> | <u>R</u> |
|--|-------------------------|----------------|--------------|------------|----------|----------|
| Natural Buttes Unit 673-25E | 43-047-50034 | UTU6774 | SENW | 25 | 10S | 20E |
| Natural Buttes Unit 674-25E | 43-047-50035 | UTU6774 | NENE | 25 | 10S | 20E |
| Natural Buttes Unit 679-26E | 43-047-40221 | UTU4476 | SENW | 26 | 10S | 20E |
| Natural Buttes Unit 681-26E | 43-047-40330 | UTU4476 | NENE | 26 | 10S | 20E |
| Natural Buttes Unit 682-9E | 43-047-40075 | UTU01791 | NENW | 9 | 10S | 21E |
| Natural Buttes Unit 683-9E | 43-047-40072 | UTU01791 | NESW | 9 | 10S | 21E |
| Natural Buttes Unit 730-36E | 43-047-50061 | ML3140.5 | NWNW | 36 | 9S | 20E |
| (1) Natural Buttes Unit 731-36E | 43-047-50061 | ML3140.5 | NENW | 36 | 9S | 20E |
| Natural Buttes Unit 732-36E | 43-047-50060 | ML3140.5 | SWNW | 36 | 9S | 20E |
| Natural Buttes Unit 734-36E | 43-047-50065 | ML3140.5 | NENE | 36 | 9S | 20E |
| Natural Buttes Unit 735-36E | 43-047-50039 | ML3140.5 | SWNE | 36 | 9S | 20E |
| Natural Buttes Unit 736-36E | 43-047-50063 | ML3140.5 | SENE | 36 | 9S | 20E |
| Natural Buttes Unit 743-31E | 43-047-50040 | UTU01480AST | (Lot 3) NWSW | 31 | 9S | 21E |
| Natural Buttes Unit 745-31E | 43-047-50041 | ML224446 | Lot 4 | 31 | 9S | 21E |
| Natural Buttes Unit 746-31E | 43-047-50090 | UTU01480ST | NWSE | 31 | 9S | 21E |
| Natural Buttes Unit 747-31E | 43-047-50049 | UTU01480ST | NESE | 31 | 9S | 21E |
| Natural Buttes Unit 748-31E | 43-047-50050 | ML22446 | (Lot 7) SWSE | 31 | 9S | 21E |
| Natural Buttes Unit 751-32E | 43-047-50056 | ML3412 | SWNW | 32 | 9S | 21E |
| Natural Buttes Unit 752-32E | 43-047-50051 | ML3412 | SENW | 32 | 9S | 21E |
| Natural Buttes Unit 754-32E | 43-047-50092 | ML3412 | SWNE | 32 | 9S | 21E |
| Natural Buttes Unit 755-32E | 43-047-50054 | ML3412 | SENE | 32 | 9S | 21E |
| Natural Buttes Unit 761-5E | 43-047-50108 | UTU01393B | NWSE | 5 | 10S | 21E |

RECEIVED

DEC 14 2010

DIV. OF OIL, GAS & MINING

| | |
|---|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
|---|---|

| | |
|--|--|
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
|--|--|

| | |
|------------------------------------|--|
| 1. TYPE OF WELL Gas Well | 8. WELL NAME and NUMBER: NBU 630-01E |
|------------------------------------|--|

| | |
|---|---|
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | 9. API NUMBER: 43047392980000 |
|---|---|

| | | |
|---|--|--|
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | PHONE NUMBER: 720 929-6007 Ext | 9. FIELD and POOL or WILDCAT: NATURAL BUTTES |
|---|--|--|

| | |
|---|---|
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844 FSL 0763 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | COUNTY: UINTAH STATE: UTAH |
|---|---|

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|---|---|---|
| <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 5/14/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.

Approved by the Utah Division of Oil, Gas and Mining

Date: May 10, 2010

By:

| | | |
|--|-------------------------------------|------------------------------------|
| NAME (PLEASE PRINT) Danielle Piernot | PHONE NUMBER 720 929-6156 | TITLE Regulatory Analyst |
| SIGNATURE N/A | DATE 5/6/2010 | |



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047392980000

API: 43047392980000

Well Name: NBU 630-01E

Location: 1844 FSL 0763 FEL QTR NESE SEC 01 TWP 100S RNG 220E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 5/14/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
- Has the approved source of water for drilling changed? Yes No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
- Is bonding still in place, which covers this proposed well? Yes No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Danielle Piernot

Date: 5/6/2010

Title: Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date: May 10, 2010

By: 

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

SEP 28 2010

FORM APPROVED
OMB NO. 1004-0135
Expires: July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

BLM

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

| | | |
|--|---|--|
| 1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other | | 5. Lease Serial No. UTU011336 |
| 2. Name of Operator KERR MCGEE OIL & GAS ONSHORE | | 6. If Indian, Allottee or Tribe Name |
| Contact: GINA T BECKER Mail: gina.becker@anadarko.com | | 7. If Unit or CA/Agreement, Name and/or No. UTU63047A |
| 3a. Address 1368 SOUTH 1200 EAST VERNAL, UT 84078 | 3b. Phone No. (include area code) Ph: 720-929-6086 Fx: 720-929-7086 | 8. Well Name and No. NBU 630-01E |
| 4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 1 T10S R22E NESE 1844FSL 763FEL | | 9. API Well No. 43-047-39298-00-X1 |
| | | 10. Field and Pool, or Exploratory NATURAL BUTTES |
| | | 11. County or Parish, and State UINTAH COUNTY, UT |

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION |
|--|--|
| <input checked="" type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize |
| <input type="checkbox"/> Subsequent Report | <input type="checkbox"/> Deepen |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Fracture Treat |
| | <input type="checkbox"/> Production (Start/Resume) |
| | <input type="checkbox"/> Alter Casing |
| | <input type="checkbox"/> New Construction |
| | <input type="checkbox"/> Reclamation |
| | <input type="checkbox"/> Casing Repair |
| | <input type="checkbox"/> Plug and Abandon |
| | <input type="checkbox"/> Recomplete |
| | <input type="checkbox"/> Change Plans |
| | <input type="checkbox"/> Temporarily Abandon |
| | <input type="checkbox"/> Convert to Injection |
| | <input type="checkbox"/> Plug Back |
| | <input type="checkbox"/> Water Disposal |
| | <input type="checkbox"/> Water Shut-Off |
| | <input type="checkbox"/> Well Integrity |
| | <input checked="" type="checkbox"/> Other Change to Original PD |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Kerr-McGee Oil & Gas Onshore, L.P. would like to apply for a APD extension. Nothing has changed since the original approval (October 24, 2008).

RECEIVED

JAN 20 2011

DIV. OF OIL, GAS & MINING

CONDITIONS OF APPROVAL ATTACHED

| |
|---------------------|
| VERNAL FIELD OFFICE |
| ENG. <u>GTD</u> |
| GEOL. _____ |
| E.S. _____ |
| PET. _____ |
| RECL. _____ |

14. I hereby certify that the foregoing is true and correct.

**Electronic Submission #93636 verified by the BLM Well Information System
For KERR MCGEE OIL & GAS ONSHORE L, sent to the Vernal
Committed to AFMSS for processing by GAIL JENKINS on 10/01/2010 (11GXJ0025SE)**

| | |
|------------------------------------|-----------------------------|
| Name (Printed/Typed) GINA T BECKER | Title REGULATORY ANALYST II |
| Signature (Electronic Submission) | Date 09/28/2010 |

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Acting Assistant Field Manager
Lands & Mineral Resources

| | | |
|---|--------|---------------------|
| Approved By <u>[Signature]</u> | Title | NOV 18 2011 Date |
| Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. | Office | VERNAL FIELD OFFICE |

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UDOGM

** BLM REVISED **

CONDITIONS OF APPROVAL

Kerr McGee Oil and Gas Onshore LP.

Notice of Intent APD Extension

Lease: UTU-11336
Well: NBU 630-01E
Location: NESE Sec 1-T10S-R22E

An extension for the referenced APD is granted with the following conditions:

1. The extension and APD shall expire on 10/24/12.
2. No other extension shall be granted.

If you have any other questions concerning this matter, please contact Carey Doyle of this office at (435) 781-3406.

| | |
|--|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
| 1. TYPE OF WELL Gas Well | 8. WELL NAME and NUMBER: NBU 630-01E |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | 9. API NUMBER: 43047392980000 |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | PHONE NUMBER: 720 929-6515 Ext |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844 FSL 0763 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | 9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|--|---|---|
| <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 5/14/2011 | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input checked="" type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.

Approved by the Utah Division of Oil, Gas and Mining

Date: 04/14/2011

By:

| | | |
|---|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Gina Becker | PHONE NUMBER 720 929-6086 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 4/7/2011 | |



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047392980000

API: 43047392980000

Well Name: NBU 630-01E

Location: 1844 FSL 0763 FEL QTR NESE SEC 01 TWNP 100S RNG 220E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 5/14/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No

Signature: Gina Becker

Date: 4/7/2011

Title: Regulatory Analyst II **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

| | |
|--|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
| 1. TYPE OF WELL Gas Well | 8. WELL NAME and NUMBER: NBU 1022-114BS |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | 9. API NUMBER: 43047392980000 |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | PHONE NUMBER: 720 929-6514 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | 9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|--|---|--|
| <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 1/15/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR <input checked="" type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The operator is requesting the approval of the following changes to the originally approved APD: 1. Change the Well Name = from Natural Buttes Unit 630-01E to NBU 1022-114BS 2. Surface & Bottom Hole Location Change (New Plat is Attached) a. From = 1844? FSL/ 763? FEL To = 1832? FSL/ 908? FEL 3. Proposed Total Depth (New Drilling Program Attached) 4. Surface Hole Size and Casing Grade (New Wellbore Diagram Attached) 5. Change to a Directional Well (Directional Drilling Survey Attached) 6. Surface Use Plan of Operation (Updated Plan Attached) 7. Updated Topo?s & Directions (Attached) Please let me know if you need any other documentation. Thank you!

**Approved by the
 Utah Division of
 Oil, Gas and Mining**

Date: January 09, 2012

By:

| | | |
|---|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Gina Becker | PHONE NUMBER 720 929-6086 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 1/6/2012 | |

**Kerr-McGee Oil & Gas Onshore, LP
WELL PAD – NBU 1022-1I
WELLS – NBU 1022-1I4BS, NBU 1022-1I1CS,
NBU 1022-1I4CS, NBU 1022-1I1BS &
NBU 1022-1H4CS
Section 1, T10S, R22E, S.L.B.&M.**

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly, then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Fidlar Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge at the White River. Exit left and proceed in a southeasterly direction along the Fidlar Road approximately 4.4 miles to the intersection of the Seven Sisters Road (County B Road 3420). Exit right and proceed in a southeasterly, then southerly direction along the Seven Sisters Road approximately 3.9 miles to a proposed access road to the southeast. Follow road flags in a southeasterly direction approximately 1,000 feet to a second proposed access road to the southeast. Follow road flags in a southeasterly direction approximately 75 feet to the proposed well pad.

Total distance from Vernal, Utah to the proposed well location is approximately 46.4 miles in a southerly direction.

Kerr-McGee Oil & Gas Onshore. L.P.**NBU 1022-114BS**

Surface: 1832 FSL / 908 FEL NESE
 BHL: 1914 FSL / 530 FEL NESE

Section 1 T10S R22E

Uintah County, Utah
 Mineral Lease: UTU-011336

ONSHORE ORDER NO. 1**DRILLING PROGRAM**

1. & 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

| <u>Formation</u> | <u>Depth</u> | <u>Resource</u> |
|------------------|--------------|-----------------|
| Uinta | 0 - Surface | |
| Green River | 1121 | |
| Birds Nest | 1385 | Water |
| Mahogany | 1747 | Water |
| Wasatch | 4151 | Gas |
| Mesaverde | 6314 | Gas |
| MVU2 | 7284 | Gas |
| MVL1 | 7855 | Gas |
| TVD | 8485 | |
| TD | 8517 | |

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

6. **Evaluation Program:**

Please refer to the attached Drilling Program

7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8485' TVD, approximately equals

$$\frac{5,430 \text{ psi}}{0.64 \text{ psi/ft}} = \text{actual bottomhole gradient}$$

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,552 psi (bottom hole pressure
 minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press. (MASP) = (Pore Pressure at next csg point -
 (0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program.
 Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. **Other Information:**

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

| | | | | | |
|-------------------|---|------------------------|---------|-----------------|-------------|
| COMPANY NAME | KERR-McGEE OIL & GAS ONSHORE LP | | DATE | October 6, 2011 | |
| WELL NAME | NBU 1022-1I4BS | | TD | 8,485' TVD | 8,517' MD |
| FIELD | Natural Buttes | COUNTY | Uintah | STATE | Utah |
| SURFACE LOCATION | NESE | 1832 FSL | 908 FEL | Sec 1 | T 10S R 22E |
| | Latitude: 39.975694 | Longitude: -109.382051 | | NAD 83 | |
| BTM HOLE LOCATION | NESE | 1914 FSL | 530 FEL | Sec 1 | T 10S R 22E |
| | Latitude: 39.975913 | Longitude: -109.380702 | | NAD 83 | |
| OBJECTIVE ZONE(S) | Wasatch/Mesaverde | | | | |
| ADDITIONAL INFO | Regulatory Agencies: BLM (Minerals), BLM (Surface), UDOGM Tri-County Health Dept. | | | | |





KERR-McGEE OIL & GAS ONSHORE LP
DRILLING PROGRAM

CASING PROGRAM

| | SIZE | INTERVAL | WT. | GR. | CPLG. | DESIGN FACTORS | | | |
|------------|--------|-----------------|-------|-------|-------|----------------|----------|---------|---------|
| | | | | | | BURST | LTC | | DQX |
| | | | | | | | COLLAPSE | TENSION | |
| CONDUCTOR | 14" | 0-40' | | | | | | | |
| SURFACE | 8-5/8" | 0 to 2,200 | 28.00 | IJ-55 | LTC | 3,390 | 1,880 | 348,000 | N/A |
| | | | | | | 2.46 | 1.83 | 6.45 | N/A |
| PRODUCTION | 4-1/2" | 0 to 5,000 | 11.60 | I-80 | DQX | 7,780 | 6,350 | 223,000 | 267,035 |
| | | | | | | 1.11 | 1.15 | 3.34 | |
| | 4-1/2" | 5,000 to 8,517' | 11.60 | I-80 | LTC | 1.11 | 1.15 | 6.76 | |

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe
 Fracture at surface shoe with 0.1 psi/ft gas gradient above
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

| | | FT. OF FILL | DESCRIPTION | SACKS | EXCESS | WEIGHT | YIELD | |
|---|------|----------------------|--|--|---------|--------|-------|------|
| SURFACE | LEAD | 500' | Premium cmt + 2% CaCl + 0.25 pps flocele | 180 | 60% | 15.80 | 1.15 | |
| | | Option 1 | | | | | | |
| | | TOP OUT CMT (6 jobs) | 1,200' | 20 gals sodium silicate + Premium cmt + 2% CaCl + 0.25 pps flocele | 270 | 0% | 15.80 | 1.15 |
| NOTE: If well will circulate water to surface, option 2 will be utilized | | | | | | | | |
| SURFACE | LEAD | 1,700' | 65/35 Poz + 6% Gel + 10 pps gilsonite + 0.25 pps Flocele + 3% salt BWOW | 160 | 35% | 11.00 | 3.82 | |
| | | TAIL | 500' | Premium cmt + 2% CaCl + 0.25 pps flocele | 150 | 35% | 15.80 | 1.15 |
| | | TOP OUT CMT | as required | Premium cmt + 2% CaCl | as req. | | 15.80 | 1.15 |
| PRODUCTION | LEAD | 3,647' | Premium Lite II +0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender | 270 | 20% | 11.00 | 3.38 | |
| | | TAIL | 4,870' | 50/50 Poz/G + 10% salt + 2% gel + 0.1% R-3 | 1,150 | 35% | 14.30 | 1.31 |

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

| | |
|------------|--|
| SURFACE | Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe |
| PRODUCTION | Float shoe, 1 jt, float collar. No centralizers will be used. |

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Nick Spence / Danny Showers / Chad Loesel


DATE:

DRILLING SUPERINTENDENT:

Kenny Gathings / Lovel Young

DATE:


EXHIBIT A NBU 1022-114BS





SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



Site: NBU 1022-11 PAD
 Well: NBU 1022-114BS
 Wellbore: OH
 Design: PLAN #1 PRELIMINARY



| WELL DETAILS: NBU 1022-114BS | | | | | | | | |
|---|---------|-------------|------------|------------------|-------------------|------------------|-------------------|------------------------|
| GL 5105 & KB 4 @ 5109.00ft (ASSUMED) | | | | | | | | |
| +N/-S | +E/-W | Northing | Easting | Latitude | Longitude | | | |
| 0.00 | 0.00 | 14521322.41 | 2093898.55 | 39° 58' 32.624 N | 109° 22' 52.932 W | | | |
| DESIGN TARGET DETAILS | | | | | | | | |
| Name | TVD | +N/-S | +E/-W | Northing | Easting | Latitude | Longitude | Shape |
| PBHL | 8485.00 | 79.40 | 378.02 | 14521408.66 | 2094275.06 | 39° 58' 33.409 N | 109° 22' 48.076 W | Circle (Radius: 25.00) |
| - plan hits target center | | | | | | | | |



| SECTION DETAILS | | | | | | | | | |
|-----------------|-------|-------|---------|-------|--------|------|--------|--------|---------------------|
| MD | Inc | Azi | TVD | +N/-S | +E/-W | Dleg | TFace | VSect | |
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 300.00 | 0.00 | 0.00 | 300.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 813.03 | 10.26 | 78.14 | 810.29 | 9.42 | 44.84 | 2.00 | 78.14 | 45.81 | |
| 2430.41 | 10.26 | 78.14 | 2401.81 | 68.64 | 326.78 | 0.00 | 0.00 | 333.91 | |
| 3016.73 | 0.00 | 0.00 | 2985.00 | 79.40 | 378.02 | 1.75 | 180.00 | 386.27 | |
| 8516.73 | 0.00 | 0.00 | 8485.00 | 79.40 | 378.02 | 0.00 | 0.00 | 386.27 | PBHL_NBU 1022-114BS |

| PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N | | FORMATION TOP DETAILS | | |
|---|--|--|---|---|
| Geodetic System: Universal Transverse Mercator (US Survey Feet) Datum: NAD 1927 (NADCON CONUS) Ellipsoid: Clarke 1866 Zone: Zone 12N (114 W to 108 W) Location: SECTION 1 T10S R22E System Datum: Mean Sea Level | | TVDPath 1121.00 4151.00 6314.00 | MDPath 1128.79 4182.73 6345.73 | Formation GREEN RIVER WASASTCH MESAVERDE |

| CASING DETAILS | | | |
|----------------|---------|--------|-------|
| TVD | MD | Name | Size |
| 2197.00 | 2222.27 | 8 5/8" | 8.625 |

REC



US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

NBU 1022-1I PAD

NBU 1022-1I4BS

OH

Plan: PLAN #1 PRELIMINARY

Standard Planning Report

18 August, 2011





SDI
Planning Report



| | | | |
|------------------|------------------------------------|-------------------------------------|---|
| Database: | EDM5000-RobertS-Local | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Company: | US ROCKIES REGION PLANNING | TVD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | MD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Site: | NBU 1022-11 PAD | North Reference: | True |
| Well: | NBU 1022-114BS | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | OH | | |
| Design: | PLAN #1 PRELIMINARY | | |

| | | | |
|--------------------|--|----------------------|----------------|
| Project | UTAH - UTM (feet), NAD27, Zone 12N | | |
| Map System: | Universal Transverse Mercator (US Survey Feet) | System Datum: | Mean Sea Level |
| Geo Datum: | NAD 1927 (NADCON CONUS) | | |
| Map Zone: | Zone 12N (114 W to 108 W) | | |

| | | | | | |
|------------------------------|--------------------------------------|---------------------|--------------------|--------------------------|-------------------|
| Site | NBU 1022-11 PAD, SECTION 1 T10S R22E | | | | |
| Site Position: | | Northing: | 14,521,314.05 usft | Latitude: | 39° 58' 32.549 N |
| From: | Lat/Long | Easting: | 2,093,859.18 usft | Longitude: | 109° 22' 53.440 W |
| Position Uncertainty: | 0.00 ft | Slot Radius: | 13.200 in | Grid Convergence: | 1.04 ° |

| | | | | | | |
|-----------------------------|----------------------------------|----------|----------------------------|--------------------|----------------------|-------------------|
| Well | NBU 1022-114BS, 1832 FSL 908 FEL | | | | | |
| Well Position | +N/-S | 7.65 ft | Northing: | 14,521,322.42 usft | Latitude: | 39° 58' 32.624 N |
| | +E/-W | 39.51 ft | Easting: | 2,093,898.54 usft | Longitude: | 109° 22' 52.932 W |
| Position Uncertainty | | 0.00 ft | Wellhead Elevation: | | Ground Level: | 5,105.00 ft |

| | | | | | |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| Wellbore | OH | | | | |
| Magnetics | Model Name | Sample Date | Declination (°) | Dip Angle (°) | Field Strength (nT) |
| | IGRF2010 | 08/18/11 | 11.00 | 65.87 | 52,314 |

| | | | | |
|--------------------------|------------------------------|-------------------|----------------------|----------------------|
| Design | PLAN #1 PRELIMINARY | | | |
| Audit Notes: | | | | |
| Version: | Phase: | PLAN | Tie On Depth: | 0.00 |
| Vertical Section: | Depth From (TVD) (ft) | +N/-S (ft) | +E/-W (ft) | Direction (°) |
| | 0.00 | 0.00 | 0.00 | 78.14 |

| Plan Sections | | | | | | | | | | |
|----------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|----------------------|---------------------|---------|-------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | TFO (°) | Target |
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 300.00 | 0.00 | 0.00 | 300.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 813.03 | 10.26 | 78.14 | 810.29 | 9.42 | 44.84 | 2.00 | 2.00 | 0.00 | 78.14 | |
| 2,430.41 | 10.26 | 78.14 | 2,401.81 | 68.64 | 326.78 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 3,016.73 | 0.00 | 0.00 | 2,985.00 | 79.40 | 378.02 | 1.75 | -1.75 | 0.00 | 180.00 | |
| 8,516.73 | 0.00 | 0.00 | 8,485.00 | 79.40 | 378.02 | 0.00 | 0.00 | 0.00 | 0.00 | PBHL_NBU 1022-114 |



SDI
Planning Report



| | | | |
|------------------|------------------------------------|-------------------------------------|---|
| Database: | EDM5000-RobertS-Local | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Company: | US ROCKIES REGION PLANNING | TVD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | MD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Site: | NBU 1022-11 PAD | North Reference: | True |
| Well: | NBU 1022-114BS | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | OH | | |
| Design: | PLAN #1 PRELIMINARY | | |

| Planned Survey | | | | | | | | | | |
|---|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|--|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | |
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 100.00 | 0.00 | 0.00 | 100.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 200.00 | 0.00 | 0.00 | 200.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 300.00 | 0.00 | 0.00 | 300.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| Start Build 2.00 | | | | | | | | | | |
| 400.00 | 2.00 | 78.14 | 399.98 | 0.36 | 1.71 | 1.75 | 2.00 | 2.00 | 0.00 | |
| 500.00 | 4.00 | 78.14 | 499.84 | 1.43 | 6.83 | 6.98 | 2.00 | 2.00 | 0.00 | |
| 600.00 | 6.00 | 78.14 | 599.45 | 3.23 | 15.36 | 15.69 | 2.00 | 2.00 | 0.00 | |
| 700.00 | 8.00 | 78.14 | 698.70 | 5.73 | 27.28 | 27.88 | 2.00 | 2.00 | 0.00 | |
| 800.00 | 10.00 | 78.14 | 797.47 | 8.95 | 42.59 | 43.52 | 2.00 | 2.00 | 0.00 | |
| 813.03 | 10.26 | 78.14 | 810.29 | 9.42 | 44.84 | 45.81 | 2.00 | 2.00 | 0.00 | |
| Start 1617.38 hold at 813.03 MD | | | | | | | | | | |
| 900.00 | 10.26 | 78.14 | 895.87 | 12.60 | 60.00 | 61.31 | 0.00 | 0.00 | 0.00 | |
| 1,000.00 | 10.26 | 78.14 | 994.27 | 16.26 | 77.43 | 79.12 | 0.00 | 0.00 | 0.00 | |
| 1,100.00 | 10.26 | 78.14 | 1,092.67 | 19.93 | 94.86 | 96.93 | 0.00 | 0.00 | 0.00 | |
| 1,128.79 | 10.26 | 78.14 | 1,121.00 | 20.98 | 99.88 | 102.06 | 0.00 | 0.00 | 0.00 | |
| GREEN RIVER | | | | | | | | | | |
| 1,200.00 | 10.26 | 78.14 | 1,191.07 | 23.59 | 112.29 | 114.74 | 0.00 | 0.00 | 0.00 | |
| 1,300.00 | 10.26 | 78.14 | 1,289.47 | 27.25 | 129.73 | 132.56 | 0.00 | 0.00 | 0.00 | |
| 1,400.00 | 10.26 | 78.14 | 1,387.88 | 30.91 | 147.16 | 150.37 | 0.00 | 0.00 | 0.00 | |
| 1,500.00 | 10.26 | 78.14 | 1,486.28 | 34.57 | 164.59 | 168.18 | 0.00 | 0.00 | 0.00 | |
| 1,600.00 | 10.26 | 78.14 | 1,584.68 | 38.23 | 182.02 | 185.99 | 0.00 | 0.00 | 0.00 | |
| 1,700.00 | 10.26 | 78.14 | 1,683.08 | 41.89 | 199.45 | 203.81 | 0.00 | 0.00 | 0.00 | |
| 1,800.00 | 10.26 | 78.14 | 1,781.48 | 45.56 | 216.89 | 221.62 | 0.00 | 0.00 | 0.00 | |
| 1,900.00 | 10.26 | 78.14 | 1,879.88 | 49.22 | 234.32 | 239.43 | 0.00 | 0.00 | 0.00 | |
| 2,000.00 | 10.26 | 78.14 | 1,978.28 | 52.88 | 251.75 | 257.24 | 0.00 | 0.00 | 0.00 | |
| 2,100.00 | 10.26 | 78.14 | 2,076.68 | 56.54 | 269.18 | 275.06 | 0.00 | 0.00 | 0.00 | |
| 2,200.00 | 10.26 | 78.14 | 2,175.08 | 60.20 | 286.61 | 292.87 | 0.00 | 0.00 | 0.00 | |
| 2,222.27 | 10.26 | 78.14 | 2,197.00 | 61.02 | 290.50 | 296.84 | 0.00 | 0.00 | 0.00 | |
| 8 5/8" | | | | | | | | | | |
| 2,300.00 | 10.26 | 78.14 | 2,273.48 | 63.86 | 304.05 | 310.68 | 0.00 | 0.00 | 0.00 | |
| 2,400.00 | 10.26 | 78.14 | 2,371.88 | 67.53 | 321.48 | 328.49 | 0.00 | 0.00 | 0.00 | |
| 2,430.41 | 10.26 | 78.14 | 2,401.81 | 68.64 | 326.78 | 333.91 | 0.00 | 0.00 | 0.00 | |
| Start Drop -1.75 | | | | | | | | | | |
| 2,500.00 | 9.04 | 78.14 | 2,470.41 | 71.04 | 338.20 | 345.58 | 1.75 | -1.75 | 0.00 | |
| 2,600.00 | 7.29 | 78.14 | 2,569.39 | 73.96 | 352.10 | 359.78 | 1.75 | -1.75 | 0.00 | |
| 2,700.00 | 5.54 | 78.14 | 2,668.76 | 76.26 | 363.04 | 370.96 | 1.75 | -1.75 | 0.00 | |
| 2,800.00 | 3.79 | 78.14 | 2,768.43 | 77.93 | 371.00 | 379.10 | 1.75 | -1.75 | 0.00 | |
| 2,900.00 | 2.04 | 78.14 | 2,868.29 | 78.97 | 375.98 | 384.19 | 1.75 | -1.75 | 0.00 | |
| 3,000.00 | 0.29 | 78.14 | 2,968.27 | 79.39 | 377.98 | 386.23 | 1.75 | -1.75 | 0.00 | |
| 3,016.73 | 0.00 | 0.00 | 2,985.00 | 79.40 | 378.02 | 386.27 | 1.75 | -1.75 | 0.00 | |
| Start 5500.00 hold at 3016.73 MD | | | | | | | | | | |
| 3,100.00 | 0.00 | 0.00 | 3,068.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,200.00 | 0.00 | 0.00 | 3,168.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,300.00 | 0.00 | 0.00 | 3,268.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,400.00 | 0.00 | 0.00 | 3,368.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,500.00 | 0.00 | 0.00 | 3,468.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,600.00 | 0.00 | 0.00 | 3,568.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,700.00 | 0.00 | 0.00 | 3,668.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,800.00 | 0.00 | 0.00 | 3,768.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 3,900.00 | 0.00 | 0.00 | 3,868.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |



SDI
Planning Report



| | | | |
|------------------|------------------------------------|-------------------------------------|---|
| Database: | EDM5000-RobertS-Local | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Company: | US ROCKIES REGION PLANNING | TVD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | MD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Site: | NBU 1022-11 PAD | North Reference: | True |
| Well: | NBU 1022-114BS | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | OH | | |
| Design: | PLAN #1 PRELIMINARY | | |

| Planned Survey | | | | | | | | | | |
|----------------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|--|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | |
| 4,000.00 | 0.00 | 0.00 | 3,968.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,100.00 | 0.00 | 0.00 | 4,068.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,182.73 | 0.00 | 0.00 | 4,151.00 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| WASASTCH | | | | | | | | | | |
| 4,200.00 | 0.00 | 0.00 | 4,168.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,300.00 | 0.00 | 0.00 | 4,268.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,400.00 | 0.00 | 0.00 | 4,368.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,500.00 | 0.00 | 0.00 | 4,468.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,600.00 | 0.00 | 0.00 | 4,568.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,700.00 | 0.00 | 0.00 | 4,668.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,800.00 | 0.00 | 0.00 | 4,768.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 4,900.00 | 0.00 | 0.00 | 4,868.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,000.00 | 0.00 | 0.00 | 4,968.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,100.00 | 0.00 | 0.00 | 5,068.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,200.00 | 0.00 | 0.00 | 5,168.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,300.00 | 0.00 | 0.00 | 5,268.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,400.00 | 0.00 | 0.00 | 5,368.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,500.00 | 0.00 | 0.00 | 5,468.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,600.00 | 0.00 | 0.00 | 5,568.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,700.00 | 0.00 | 0.00 | 5,668.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,800.00 | 0.00 | 0.00 | 5,768.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 5,900.00 | 0.00 | 0.00 | 5,868.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,000.00 | 0.00 | 0.00 | 5,968.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,100.00 | 0.00 | 0.00 | 6,068.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,200.00 | 0.00 | 0.00 | 6,168.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,300.00 | 0.00 | 0.00 | 6,268.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,345.73 | 0.00 | 0.00 | 6,314.00 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| MESAVERDE | | | | | | | | | | |
| 6,400.00 | 0.00 | 0.00 | 6,368.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,500.00 | 0.00 | 0.00 | 6,468.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,600.00 | 0.00 | 0.00 | 6,568.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,700.00 | 0.00 | 0.00 | 6,668.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,800.00 | 0.00 | 0.00 | 6,768.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 6,900.00 | 0.00 | 0.00 | 6,868.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,000.00 | 0.00 | 0.00 | 6,968.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,100.00 | 0.00 | 0.00 | 7,068.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,200.00 | 0.00 | 0.00 | 7,168.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,300.00 | 0.00 | 0.00 | 7,268.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,400.00 | 0.00 | 0.00 | 7,368.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,500.00 | 0.00 | 0.00 | 7,468.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,600.00 | 0.00 | 0.00 | 7,568.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,700.00 | 0.00 | 0.00 | 7,668.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,800.00 | 0.00 | 0.00 | 7,768.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 7,900.00 | 0.00 | 0.00 | 7,868.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 8,000.00 | 0.00 | 0.00 | 7,968.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 8,100.00 | 0.00 | 0.00 | 8,068.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 8,200.00 | 0.00 | 0.00 | 8,168.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 8,300.00 | 0.00 | 0.00 | 8,268.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 8,400.00 | 0.00 | 0.00 | 8,368.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 8,500.00 | 0.00 | 0.00 | 8,468.27 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| 8,516.73 | 0.00 | 0.00 | 8,485.00 | 79.40 | 378.02 | 386.27 | 0.00 | 0.00 | 0.00 | |
| PBHL_NBU 1022-114BS | | | | | | | | | | |



SDI
Planning Report



| | | | |
|------------------|------------------------------------|-------------------------------------|---|
| Database: | EDM5000-RobertS-Local | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Company: | US ROCKIES REGION PLANNING | TVD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | MD Reference: | GL 5105 & KB 4 @ 5109.00ft (ASSUMED) |
| Site: | NBU 1022-11 PAD | North Reference: | True |
| Well: | NBU 1022-114BS | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | OH | | |
| Design: | PLAN #1 PRELIMINARY | | |

| Planned Survey | | | | | | | | | |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |

| Design Targets | | | | | | | | | |
|---|---------------|--------------|----------|------------|------------|-----------------|----------------|------------------|-------------------|
| Target Name | Dip Angle (°) | Dip Dir. (°) | TVD (ft) | +N/-S (ft) | +E/-W (ft) | Northing (usft) | Easting (usft) | Latitude | Longitude |
| PBHL_NBU 1022-114BS - hit/miss target - Shape - plan hits target center - Circle (radius 25.00) | 0.00 | 0.00 | 8,485.00 | 79.40 | 378.02 | 14,521,408.67 | 2,094,275.06 | 39° 58' 33.409 N | 109° 22' 48.076 W |

| Casing Points | | | | | |
|---------------------|---------------------|--------|----------------------|--------------------|--|
| Measured Depth (ft) | Vertical Depth (ft) | Name | Casing Diameter (in) | Hole Diameter (in) | |
| 2,222.27 | 2,197.00 | 8 5/8" | 8.625 | 11.000 | |

| Formations | | | | | |
|---------------------|---------------------|-------------|-----------|---------|-------------------|
| Measured Depth (ft) | Vertical Depth (ft) | Name | Lithology | Dip (°) | Dip Direction (°) |
| 1,128.79 | 1,121.00 | GREEN RIVER | | | |
| 4,182.73 | 4,151.00 | WASASTCH | | | |
| 6,345.73 | 6,314.00 | MESAVERDE | | | |

| Plan Annotations | | | | |
|---------------------|---------------------|------------|------------|----------------------------------|
| Measured Depth (ft) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Comment |
| 300.00 | 300.00 | 0.00 | 0.00 | Start Build 2.00 |
| 813.03 | 810.29 | 9.42 | 44.84 | Start 1617.38 hold at 813.03 MD |
| 2,430.41 | 2,401.81 | 68.64 | 326.78 | Start Drop -1.75 |
| 3,016.73 | 2,985.00 | 79.40 | 378.02 | Start 5500.00 hold at 3016.73 MD |
| 8,516.73 | 8,485.00 | 79.40 | 378.02 | TD at 8516.73 |

NBU 1022-1H4CS / 1022-111BS / 1022-111CS
 1022-114BS / 1022-114CS

NBU 1022-11 Pad
 Surface Use Plan of Operations
 1 of 14

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 1022-11 Pad

| <u>API #</u> | <u>NBU 1022-1H4CS</u> | | |
|--------------|-----------------------------|------|-----|
| | Surface: 1824 FSL / 947 FEL | NESE | Lot |
| | BHL: 2410 FNL / 492 FEL | SENE | Lot |

| <u>API #</u> | <u>NBU 1022-111BS</u> | | |
|--------------|-----------------------------|------|-----|
| | Surface: 1826 FSL / 937 FEL | NESE | Lot |
| | BHL: 2576 FSL / 492 FEL | NESE | Lot |

| <u>API #</u> | <u>NBU 1022-111CS</u> | | |
|--------------|-----------------------------|------|-----|
| | Surface: 1830 FSL / 918 FEL | NESE | Lot |
| | BHL: 2243 FSL / 492 FEL | NESE | Lot |

| <u>API #4304739298</u> | <u>NBU 1022-114BS (fka NBU 630-01E)</u> | | |
|------------------------|---|------|-----|
| | Surface: 1832 FSL / 908 FEL | NESE | Lot |
| | BHL: 1914 FSL / 530 FEL | NESE | Lot |

| <u>API #</u> | <u>NBU 1022-114CS</u> | | |
|--------------|-----------------------------|------|-----|
| | Surface: 1828 FSL / 928 FEL | NESE | Lot |
| | BHL: 1579 FSL / 492 FEL | NESE | Lot |

An Application for Permit to Drill (APD) was approved by the BLM on October 24, 2008 for the NBU 630-01E well location. A Sundry Notice under separate cover will be submitted to change the location and the well name to the NBU 1022-114BS.

This Surface Use Plan of Operations (SUPO) or 13-point plan provides site-specific information for the above-referenced wells.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

A. Existing Roads:

Existing roads consist of county and improved/unimproved access roads (two-tracks). In accordance with Onshore Order #1, Kerr-McGee will, in accordance with BMPs, improve or maintain existing roads in a condition that is the same as or better than before operations began. New or reconstructed proposed access roads are discussed in Section B.

The existing roads will be maintained in a safe and usable condition. Maintenance for existing roads will continue until final abandonment and reclamation of well pads and/or other facilities, as applicable. Road maintenance will include, but is not limited to, blading, ditching, and/or culvert installation and cleanout. To ensure safe operating conditions, gravel surfacing will be performed where excessive rutting or erosion may occur. Dust control will be performed as necessary to ensure safe operating conditions.

10/10/2011

RECEIVED: Jan. 06, 2012

Roads, gathering lines and electrical distribution lines will occupy common disturbance corridors where possible. Where available, roadways will be used as the staging area and working space for installation of gathering lines. All disturbances located in the same corridor will overlap each other to the maximum extent possible, while maintaining safe and sound construction and installation practices. Unless otherwise approved or requested in site specific documents, in no case will the maximum disturbance widths of the access road and utility corridors exceed the widths specified in Part D of this document.

Please refer to Topo B, for existing roads.

B. New or Reconstructed Access Roads:

All new or reconstructed roads will be located, designed, and maintained to meet the standards of the BLM. BMPs. Described in the BLM's Surface Operating Standards for Oil and Gas Exploration and Development, 4th Edition (Gold Book) (USDI and USDA, 2007) and/or BLM Manual Section 9113 (1985) will be considered in consultation with the BLM in the design, construction, improvement and maintenance of all new or reconstructed roads. If a new road would cross a water of the United States, Kerr-McGee will adhere to the requirements of applicable Nationwide Permits of the Department of Army Corps of Engineers.

Each new well pad or pad expansion may require construction of a new access road and/or de-commissioning of an older road. Plans, routes, and distances for new roads and road improvements are provided in design packages, exhibits and maps for a project. Project-specific maps are submitted to depict the locations of existing, proposed, and/or decommissioned and include the locations for supporting structures, including, but not limited to, culverts, bridges, low water crossings, range infrastructure, and haul routes, as per OSO 1. Designs for cuts and fills, including spoils source and storage areas, are provided with the road designs, as necessary.

Where safety objectives can be met. As applicable, Kerr-McGee may use unimproved and/or two-track roads for lease operations, to lessen total disturbance.

Road designs will be based on the road safety requirements, traffic characteristics, environmental conditions, and the vehicles the road is intended to carry. Generally, newly constructed unpaved lease roads will be crowned and ditched with the running surfaces of the roads approximately 12-18 feet wide and a total road corridor width not to exceed 45 feet, except where noted in the road design for a specific project. Maximum grade will generally not exceed 8%. Borrow ditches will be back sloped 3:1 or less. Construction BMPs will be employed to control onsite and offsite erosion.

Where topography would direct storm water runoff to an access road or well pad, drainage ditches or other common drainage control facilities, such as V- or wing-ditches, will be constructed to divert surface water runoff. Drainage features, including culverts, will be constructed or installed prior to commencing other operations, including drilling or facilities placement. Riprap will be placed at the inlet and outlet at the culvert(s), as necessary.

Prior to construction, new access road(s) will be staked according to the requirements of OSO 1. Construction activity will not be conducted using frozen or saturated materials or during periods when significant watershed damage (e.g. rutting, extensive sheet soil erosion, formation of rills/gullies, etc.) is likely to occur. Vegetative debris will not be placed in or under fill embankments.

New road maintenance will include, but is not limited to, blading, ditching, culvert installation and cleanout, gravel surfacing where excessive rutting or erosion may occur and dust control, as necessary to ensure safe operating

10/10/2011

NBU 1022-1H4CS / 1022-111BS / 1022-111CS
1022-114BS / 1022-114CS

NBU 1022-11 Pad
Surface Use Plan of Operations
3 of 14

conditions. All vehicular traffic, personnel movement, construction/restoration operations will be confined to the approved area and to existing roadways and/or access routes.

Snow removal will be conducted on an as-needed basis to accommodate safe travel. Snow removal will occur as necessary throughout the year, as will necessary drainage ditch construction. Removed snow may be stored on permitted well pads to reduce hauling distances and/or at the aerial extent of approved disturbance boundaries to facilitate snow removal for the remainder of the season.

If a county road crossing or encroachment permit is needed, it will be obtained prior to construction.

The following segments are "on-lease"

±1,075' (0.2 miles) – Section 1 T10S R22E (SE/4) – On-lease UTU011336, new access road from the edge of the pad to the existing road. This road will be used concurrently with the NBU 1022-1P Pad. Please refer to Topo B.

C. Location of Existing Wells:

Division of Oil, Gas and Mining (UDOGM) records show no drilled locations on this pad and was verified on October 6, 2011. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (Kerr-McGee).

Should the well(s) prove productive, production facilities will be installed on the disturbed portion of each well pad. A berm will be constructed completely around production components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will generally be constructed of compacted subsoil or corrugated metal, and will hold the capacity of the largest tank and have sufficient freeboard to accommodate a 25 year rainfall event. This includes pumping units. Aboveground structures constructed or installed onsite for 6 months or longer, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with the BLM (typically Shadow Gray). A production facility layout is provided as part of a project-specific APD, ROW or NOS submission.

GAS GATHERING

Please refer to Exhibit A and Topo D- Pad and Pipeline Detail.

The gas gathering pipeline material: Steel line pipe. Surface = Bare pipe. Buried = Coated with fusion bonded epoxy coating (or equivalent).

Kerr-McGee proposes to install gas gathering lines to tie into a previously approved buried gas pipeline covered under ROW UTU-88692. The total of this proposed gas gathering from the meter to the approved 16" gas pipeline is ±1,550' and the individual segments are broken up as follows:

The following segments are "onlease", no ROW needed.

±410' (0.1 miles) – Section 1 T10S R22E (NE/4 SE/4) – On-lease UTU011336, BLM surface, New 6" buried gas gathering pipeline from the meter to the edge of the pad. Please refer to Topo D2 - Pad and Pipeline Detail.

10/10/2011

RECEIVED: Jan. 06, 2012

NBU 1022-1H4CS / 1022-1I1BS / 1022-1I1CS
1022-1I4BS / 1022-1I4CS

NBU 1022-1I Pad
Surface Use Plan of Operations
4 of 14

- ±95' (0.02 miles) – Section 1 T10S R22E (NE/4 SE/4) – On-lease UTU011336, BLM surface, New 6" buried gas gathering pipeline from the edge of the pad to the proposed 8" buried pipeline at the NBU 1022-1P Pad intersection. Please refer to Exhibit A, Line 10.
- ±1,045' (0.2 miles) – Section 1 T10S R22E (SE/4) – On-lease UTU011336, BLM surface, New 8" buried gas gathering pipeline from the NBU 1022-1P Pad intersection to the tie-in at the previously approved 16" gas gathering pipeline. Please refer to Exhibit A, Line 8. This pipeline will be used concurrently with the NBU 1022-1P Pad.

Kerr-McGee proposes to install liquid gathering lines to tie into a previously approved buried liquid pipeline covered under ROW UTU-88691. The total of this proposed liquid gathering from the separator to the approved liquid pipeline is ±1,550' and the individual segments are broken up as follows:

The following segments are "onlease", no ROW needed.

- ±410' (0.1 miles) – Section 1 T10S R22E (NE/4 SE/4) – On-lease UTU011336, BLM surface, New 6" buried liquid gathering pipeline from the separator to the edge of the pad. Please refer to Topo D2 - Pad and Pipeline Detail.
- ±95' (0.02 miles) – Section 1 T10S R22E (NE/4 SE/4) – On-lease UTU011336, BLM surface, New 6" buried liquid gathering pipeline from the edge of the pad to the NBU 1022-1P Pad intersection. Please refer to Exhibit B, Line 10.
- ±1,045' (0.2 miles) – Section 1 T10S R22E (SE/4) – On-lease UTU011336, BLM surface, New 6" buried liquid gathering pipeline from the NBU 1022-1P Pad intersection to the tie-in at the previously approved liquid gathering pipeline. Please refer to Exhibit B, Line 8. This pipeline will be used concurrently with the NBU 1022-1P Pad.

Pipeline Gathering Construction

Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee. Gas gathering pipeline(s), gas lift, or liquids pipelines may be constructed to lie on the surface or be buried. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. The area of disturbance during construction from the edge of road or well pad will typically be 30' in width. Where pipelines run cross country, the width of disturbance will typically be 45 ft for buried lines and 30 ft for surface lines. In addition, Kerr-McGee requests for a permanent 30' disturbance width that will be maintained for the portion adjacent to the road. The need for the 30' permanent disturbance width is for maintenance and repairs. Cross country permanent disturbance width also are required to be 30ft.

Above-ground installation will generally not require clearing of vegetation or blading of the surface, except where safety considerations necessitate earthwork. In some surface pipeline installation instances pipe cannot be constructed where it will lay. In these cases where an above-ground pipeline is constructed parallel and adjacent to a road, it will be welded/fused on the road and then lifted from the road to the pipeline route. In other cases where a pipeline route is not parallel and adjacent to a road (cross-country between sites), it will be welded/fused in place at a well pad, access road, or designated work area and pulled between connection locations with a suitable piece of equipment.

Buried pipelines will generally be installed parallel and adjacent to existing and/or newly constructed roads and within the permitted disturbance corridor. Buried pipelines may vary from 2 inches (typically fuel gas lines) to 24 inches (typically transportation lines) in diameter, but 6 to 16 inches is typical for a buried gas line. The diameter of liquids pipelines may vary from 2 inches to 12 inches, but 6 inches is the typical diameter. Gas lift lines may vary from 2 to 12 inches in diameter, but 6-inch diameter pipes are generally used for gas lift. If two or more pipelines are present (gas gathering, gas lift, and fluids), they will share a common trench where possible.

10/10/2011

RECEIVED: Jan. 06, 2012

NBU 1022-1H4CS / 1022-111BS / 1022-111CS
1022-114BS / 1022-114CS

NBU 1022-11 Pad
Surface Use Plan of Operations
5 of 14

Typically, to install a buried pipeline, topsoil will be removed, windrowed and placed on the non-working side of the route for later reclamation. Because working room is limited, the spoil may be spread out across the working side and construction will take place on the spoil. The working side of the corridor will be used for pipe stringing, bending, welding and equipment travel. Small areas on the working side displaying ruts or uneven ground will be groomed to facilitate the safe passage of equipment. After the pipelines are installed, spoil will be placed back into the trench, and the topsoil will be redistributed over the disturbed corridor prior to final reclamation. Typical depth of the trench will be 6 feet, but depths may vary according to site-specific conditions (presence of bedrock, etc.). The proposed trench width for the pipeline would range from 18-48 inches.

The pipeline will be welded along the proposed route and lowered into place. Trenching equipment will cut through the soil or into the bedrock and create good backfill, eliminating the need to remove large rocks. The proposed buried pipeline will be visually and radiographically inspected and the entire pipeline will be pneumatically or hydrostatically tested before being placed into service. Routine vehicle traffic will be prevented from using pipeline routes as travel ways by posting signs at the route's intersection with an access road.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

If pipelines or roads encounter a drainage that could be subject to flooding or surface water during extreme precipitation events, Kerr-McGee will apply all applicable Army Corps mandates as well as the BLM's Hydraulic Considerations for Pipeline Crossings of Stream Channels (BLM Technical Note 423, April 2007). In addition, all stream and drainage

crossings will be evaluated to determine the need for stream alteration permits from the State of Utah Division of Water Rights and if necessary, required permits will be secured. Similarly, where a road or pipeline crossing exists the pipe will be butt welded and buried to a depth between 24 and 48 inches or more. Dirt roads will be cut and restored to a condition equivalent to the existing condition. All Uintah County road encroachment and crossing permits, where applicable, will be obtained prior to crossing construction. In no case will pressure testing of pipelines result in discharge of liquids to the surface. Pipeline signs will be installed along the route to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves and lateral T's will be installed at various locations for production integrity and safety purposes.

Upon completion of the proposed buried pipeline, the entire area of disturbance will be reclaimed to the standards proposed in the Green River District Reclamation Guidelines. Please refer to section J for more details regarding final reclamation.

When no longer deemed necessary by the operator, Kerr-McGee or its successor will consult with the BLM, Vernal Field Office before terminating of the use of the pipeline(s).

The Anadarko Completions Transportation System (ACTS) information:

Please refer to Exhibit C for ACTs Lines

Kerr-McGee will use either a closed loop drilling system that will require one pit and one storage area to be constructed on the drilling pad or a traditional drilling operation with one pit. The storage area will be used to contain only the de-watered drill cuttings and will be lined and reclaimed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit is lined and will be used for the wells drilled on the pad or used as part of our Anadarko Completions Transportation (ACTS) system which is discussed in more detail below. Using the

10/10/2011

RECEIVED: Jan. 06, 2012

NBU 1022-1H4CS / 1022-1I1BS / 1022-1I1CS
1022-1I4BS / 1022-1I4CS

NBU 1022-1I Pad
Surface Use Plan of Operations
6 of 14

closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completion pit.

If Kerr-McGee does not use a closed loop system, it will construct a drilling reserve pit to contain drill cuttings and for use in completion operations. Depending on the location of the pit, its relation to future drilling locations, the reserve/completion pit will be utilized for the completion of the wells on that pad and/or be used as part of our ACTS system.

Kerr-McGee will use ACTS to optimize the completion processes for multiple pads across the project area which may include up to a section of development. ACTS will facilitate management of frac fluids by utilizing existing reserve pits and temporary, surface-laid aluminum liquids transfer lines between frac locations. The pit will be refurbished as follows when a traditional drill pit is used: mix and pile up drill cuttings with dry dirt, bury the original liner in the pit, walk bottom of pit with cat. Kerr-McGee will reline the pit with a 30 mil liner and double felt padding. The refurbished pit will be the same size or smaller as specified in the originally approved ROW/APD. The pit refurb will be done in a normal procedure and there will be no modification to the pit.

All four sides of the completions pit will be fenced in according to standard pit fencing procedures. Netting will be installed over all pits.

The collected hydrocarbons will be treated and sold at approved sales facilities. A loading rack with drip containment will also be installed where water trucks would unload and load to prevent damage caused from pulling hoses in and out of the pit .

ACTS will require temporarily laying multiple 6" aluminum water transfer lines on the surface between either existing or refurbished reserve pits. Please see the attached ACTS exhibit C for placement of the proposed temporary lines. The temporary aluminum transfer lines will be utilized to transport frac fluid being injected and/or recovered during the completion process and will be laid adjacent to existing access roads or pipeline corridors. Upon completion of the frac operation, the liquids transfer lines will be flushed with fresh water and purged with compressed air. The contents of the transfer lines will be flushed into a water truck for delivery to another ACTS location or a reserve pit.

The volume of frac fluid transported through a water transfer line will vary, but volume is projected to be approximately 1.75 bbls per 50-foot joint. Although the maximum working pressure is 125 psig, the liquids transfer lines will be operated at a pressure of approximately 30 to 40 psig. Kerr-McGee requests to keep the netted pit open for one year from first production of the first produced well on the pad. During this time the surrounding well location completion fluids may be recycled in this pit and utilized for other frac jobs in the area. After one year Kerr-McGee will backfill the pit and reclaim. If the pit is not needed for an entire year it will be backfilled and reclaimed earlier. Kerr-McGee understands that due to the temporary nature of this system, BLM considers this a casual use situation; therefore, no permanent ROW or temporary use plan will need to be issued by the BLM.

E. Location and Types of Water Supply:

Water for drilling and completion operations will be obtained from the following sources:

| | | |
|------------------|-------------------|------------------------------------|
| Permit # 49-2307 | JD Field Services | Green River- Section 15, T2N, R22E |
| Permit # 49-2321 | R.N. Industries | White River- Section 2, T10S, R24E |
| Permit # 49-2319 | R.N. Industries | White River- Various Sources |
| Permit # 49-2320 | R.N. Industries | Green River- Section 33, T8S, R23E |

Water will be hauled to location over the roads marked on Maps A and B.

10/10/2011

RECEIVED: Jan. 06, 2012

No water well is to be drilled on this lease.

F. Construction Materials:

Construction operations will typically be completed with native materials found on location. Construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source (described in site-specific documents). No construction materials will be removed from federal lands without prior approval from the BLM. A source location other than an on-location construction site will be designated either via a map or narrative within the project specific materials provided to the BLM.

G. Methods for Handling Waste:

All wastes subject to regulation will be handled in compliance with applicable laws to minimize the potential for leaks or spills to the environment. Kerr-McGee also maintains a Spill Control and Countermeasure Plan, which includes notification requirements, including the BLM, for all reportable spills of oil, produced liquids, and hazardous materials.

Any accidental release, such as a leak or spill in excess of the reportable quantity, as established by 40 CFR Part 117.3, will be reported as per the requirements of CERCLA, Section 102 B. If a release involves petroleum hydrocarbons or produced liquids, Kerr-McGee will comply with the notification requirements of NTL-3A. Drill cuttings and/or drilling fluids will be contained in the reserve/frac pit whether a closed loop system is used or not. Cuttings will be buried in pit(s) upon closure. Unless specifically approved by the BLM, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface precipitation runoff into the pit (via appropriate placement of subsoil storage areas and/or construction of berms, ditches, etc). Should unexpected liquid petroleum hydrocarbons (crude oil or condensate) be encountered during drilling, completions or well testing, liquid petroleum hydrocarbons will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by the BLM. Should timely removal not be feasible, the pit will be netted as soon as practical. Similarly, hydrocarbon removal will take place prior to the closure of the pit, unless authorization is provided for disposal via alternate pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with an impermeable liner. The liner will be a synthetic material 30 mil or thicker. The bottom and side walls of the pit will be void of any sharp rocks that could puncture the liner. The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. After evaporation and when dry, the reserve pit liners will be cut off, ripped and/or folded back (as safety considerations allow) as near to the mud surface as possible and buried on location or hauled to a landfill prior to backfilling the pit with a minimum of five feet of soil material.

Where necessary and if conditions (freeboard, etc.) allow, produced liquids from newly completed wells may be temporarily disposed of into pits for a period not to exceed 90 days as per Onshore Order Number 7 (OSO 7). Subsequently, permanent approved produced water disposal methods will be employed in accordance with OSO 7 and/or as described in a Water Management Plan (WMP). Otherwise, fluids disposal locations and associated haul routes, for ROW consideration, are typically depicted on Topo A of individual projects. Revisions to the water source or method of transportation will be subject to written approval from the BLM.

10/10/2011

RECEIVED: Jan. 06, 2012

Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after one year from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse (trash and other solid waste including cans, paper, cable, etc.) generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility. Immediately after removal of the drilling rig, all debris and other waste materials not contained within trash receptacles will be collected and removed from the well location.

For the protection of livestock and wildlife, all open pits (excluding flare pits) will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet. Siphons, catchments, and absorbent pads will be installed to keep hydrocarbons produced by the drilling rig or other equipment on location from entering the reserve pit. Hydrocarbons, contaminated pads, and/or soils will be disposed of in accordance with state and federal requirements.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Materials Management

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Hazardous materials may be contained in some grease or lubricants, solvents, acids, paint, and herbicides, among others as defined above. Kerr-McGee maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances that are used during the course of construction, drilling, completion, and production operations for this project. The transport, use, storage and handling of hazardous materials will follow procedures specified by federal and state regulations. Transportation of hazardous materials to the well location is regulated by the Department of Transportation (DOT) under 49 CFR, Parts 171-180. DOT regulations pertain to the packing, container handling, labeling, vehicle placarding, and other safety aspects.

10/10/2011

RECEIVED: Jan. 06, 2012

NBU 1022-1H4CS / 1022-111BS / 1022-111CS
1022-114BS / 1022-114CS

NBU 1022-11 Pad
Surface Use Plan of Operations
9 of 14

Potentially hazardous materials used in the development or operation of wells will be kept in limited quantities on well sites and at the production facilities for short periods of time. Chemicals meeting the criteria for being an acutely hazardous material/substance or meet the quantities criteria per BLM Instruction Memorandum No. 93-344 will not be used.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities (crude oil/condensate, produced water). They may also be kept in limited quantities on drilling sites (barite, diesel fuel, cement, cottonseed hulls etc.) for short periods of time during drilling or completion activities.

Fluids disposal and pipeline/haul routes are depicted on Topo Map A.

Any produced water separated from recoverable condensate from the proposed well will be contained in a water tank and will then be transported by pipeline and/or truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E
NBU #159 in Sec. 35 T9S R21E
Ace Oilfield in Sec. 2 T6S R20E
MC&MC in Sec. 12 T6S R19E
Pipeline Facility in Sec. 36 T9S R20E
Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E
Bonanza Evaporation Pond in Sec. 2 T10S R23E

Or to one of the following Kerr-McGee active Salt Water Disposal (SWD) wells:

NBU 159 SWD in Sec. 35 T9S R21E
CIGE 112D SWD in Sec. 19 T9S R21E
CIGE 114 SWD in Sec. 34 T9S R21E
NBU 921-34K SWD in Sec. 34 T9S R21E
NBU 921-33F SWD in Sec. 34 T9S R21E

H. Ancillary Facilities:

No additional ancillary facilities are planned for this location.

I. Well Site Layout:

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit (for closed loop or non-closed loop operations), access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable. Site-specific conditions may require slight deviation in actual equipment depending on whether a closed loop system is used. Surface distance may be less if using closed loop. But in either case, the area of disturbance will not exceed the maximum disturbance outlined in the attached exhibits.

For the protection of livestock and wildlife, all open pits and cellars will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

10/10/2011

RECEIVED: Jan. 06, 2012

Each well will utilize either a centralized tank battery, centralized fluids management system, or have tanks installed on its pad. Production/ Produced Liquid tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks will be kept reasonably free from surface accumulations of liquid hydrocarbons. The tanks are not to be used for disposal of liquids from additional sources without prior approval of BLM.

J. Plans for Surface Reclamation:

The surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. Interim reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but is not limited to the re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

Interim Reclamation

Interim reclamation may include pit evaporation, fluid removal, pit solidification, re-contouring, ripping, spreading top soil, seeding, and/or weed control. Interim reclamation will be performed in accordance with OSO 1, or written notification will be provided to the BLM for approval. Where feasible, drilling locations, reserve pits, or access routes not utilized for production operations will be re-contoured to a natural appearance.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit. Disposal of pit fluids and linings is discussed in Section G.

Final Reclamation

Final reclamation will be performed for unproductive wells and after the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by Kerr-McGee. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. The BLM will be notified prior to commencement of reclamation operations. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring the site to the approximate contour that existed prior to pad construction, final grading will be conducted over the entire surface of the well site and access road. The area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers, where practical. The surface soil material will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep, where practical. The entire area will be uniformly covered with the depressions constructed perpendicular to the natural flow of water.

Reclamation of roads will be performed at the discretion of the BLM. All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded in accordance with the seeding specifications of the BLM.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to the BLM.

Measures Common to Interim and Final Reclamation

Soil preparation will be conducted using a disk for areas in need of more soil preparation following site preparation. This will provide primary soil tillage to a depth no greater than 6 inches. Prior to reseeding, compacted areas will be scarified by ripping or chiseling to loosen compacted soils, promote water infiltration, and improve soil aeration and root penetration.

Seeding will occur year-round as conditions allow and will typically be accomplished through the use of a no-till rangeland style seed drill with a “picker box” in order to seed “fluffy” seed. Where drill seeding is not the preferred method, seed will be broadcast and then raked into the ground at double the rate of drill seeding. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for

re-vegetation. The seed mixes will be selected from a list provided by or approved by the BLM, or a specific seed mix will be proposed by Kerr-McGee to the BLM and used after its approval. The selected specific seed mix for each well location and road segment will be utilized while performing interim and final reclamation for each project. All seed will be certified and tags will be maintained by Kerr-McGee. Every effort will be made to obtain “cheat grass free seed”.

Seed Mix to be used for Well Site, Access Road, and Pipeline (as applicable):

| Shadescale Mix | Pure Live Seed lbs/acre |
|------------------|-------------------------|
| Indian Ricegrass | 3 |
| Sandberg | 0.75 |
| Bottlebrush | 1 |
| Great Basin | 0.5 |
| Crested | 1.5 |
| Winterfat | 0.25 |
| Shadscale | 1.5 |
| Four-wing | 0.75 |
| Forage Kochia | 0.25 |
| Total | 9.5 |

Additional soil amendments and/or stabilization may be required on sites with poor soils and/or excessive erosion potential. Where severe erosion can become a problem and/or the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. Slopes will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to: erosion control blankets, hydro-mulch, and/or bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage. Soil amendments such as "Sustain" (an organic fertilizer that will be applied at the rate 1,800 – 2,100 lbs/acre with seed) may also be dry broadcast or applied with hydro-seeding equipment.

Weed Control

All weed management will be done in accordance with the Vernal BLM Surface Disturbance Weed Policy. Noxious weeds will be controlled, as applicable, on project areas. Monitoring and management of noxious and/or invasive weeds of concern will be completed annually until the project is deemed successfully reclaimed by the surface management agency and/or owner according to the Anadarko Integrated Weed Management Plan. Noxious weed infestations will be mapped using a GPS unit and submitted to the BLM with information required in the Vernal BLM Surface Disturbance Weed Policy. If herbicide is to be applied it will be done according to an approved Pesticide Use Permit (PUP), inclusive of applicable locations. All pesticide applications will be recorded using a Pesticide Application Record (PAR) and will be submitted along with a Pesticide Use Report (PUR) annually prior to Dec. 31.

Monitoring

Monitoring of reclaimed project areas will be completed annually during the growing season and actions to ensure reclamation success will be taken as needed. During the first two growing seasons an ocular methodology will be used to determine the success of the reclamation activities. During the 3rd growing season a 200 point line intercept (quantitative) methodology will be used to obtain basal cover. The goal is to have the reclaimed area reach 30% basal cover when compared to the reference site. If after three growing seasons the area has not reached 30% basal cover, additional reclamation activities may be necessary. Monitoring will continue until the reclaimed area reaches 75% basal cover of desirable vegetation when compared to the reference site. (Green River District Reclamation Guidelines)

All monitoring reports will be submitted electronically to the Vernal BLM in the form of a geo-database no later than March 1st of the calendar year following the data collection.

K. Surface/Mineral Ownership:

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435)781-4400

L. Other Information:

Cultural and Paleontological Resources

All personnel are strictly prohibited from collecting artifacts, any paleontological specimens or fossils, and from disturbing any significant cultural resources in the area. If artifacts, fossils, or any culturally sensitive materials are exposed or identified in the area of construction, all construction operations that would affect the newly discovered resource will cease, and Kerr-McGee will provide immediate notification to the BLM.

Resource Reports:

A Class I literature survey was completed in May 2011 by Montgomery Archaeological Consultants, Inc (MOAC). For additional details please refer to report MOAC 11-145.

A paleontological reconnaissance survey was completed in June, 2010 and July, 2011 by SWCA Environmental Consultants. For additional details please refer to reports UT11-14314-27, UT11-14314-32 and UT11-14314-33.

Biological field survey was completed in May and June of 2011 by Grasslands Consulting, Inc (GCI). For additional details please refer to reports GCI-514 and GCI 559.

Proposed Action Annual Emissions Tables:

| Table 1: Proposed Action Annual Emissions (tons/year)¹ | | | |
|--|--------------------|-------------------|--------------|
| Pollutant | Development | Production | Total |
| NOx | 3.8 | 0.12 | 3.92 |
| CO | 2.2 | 0.11 | 2.31 |
| VOC | 0.1 | 4.9 | 5 |
| SO ₂ | 0.005 | 0.0043 | 0.0093 |
| PM ₁₀ | 1.7 | 0.11 | 1.81 |
| PM _{2.5} | 0.4 | 0.025 | 0.425 |
| Benzene | 2.2E-03 | 0.044 | 0.046 |
| Toluene | 1.6E-03 | 0.103 | 0.105 |
| Ethylbenzene | 3.4E-04 | 0.005 | 0.005 |
| Xylene | 1.1E-03 | 0.076 | 0.077 |
| n-Hexane | 1.7E-04 | 0.145 | 0.145 |
| Formaldehyde | 1.3E-02 | 8.64E-05 | 1.31E-02 |

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

| Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison | | | |
|---|--|---|--|
| Species | Proposed Action Production Emissions (ton/yr) | WRAP Phase III 2012 Uintah Basin Emission Inventory^a (ton/yr) | Percentage of Proposed Action to WRAP Phase III |
| NOx | 19.6 | 16,547 | 0.12% |
| VOC | 25 | 127,495 | 0.02% |

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Uintah Basin Data

NBU 1022-1H4CS / 1022-1I1BS / 1022-1I1CS
1022-1I4BS / 1022-1I4CS

NBU 1022-1I Pad
Surface Use Plan of Operations
14 of 14

M. Lessee's or Operators' Representative & Certification:

Gina T. Becker
Regulatory Analyst II
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6086

Tommy Thompson
General Manager, Drilling
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.


Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.


I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.


Gina T. Becker

October 10, 2011
Date



CROSS SECTION A-A'



CROSS SECTION B-B'

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-11


WELL PAD - CROSS SECTIONS
NBU 1022-114BS,
NBU 1022-111CS, NBU 1022-114CS,
NBU 1022-111BS & NBU 1022-114CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., UINTAH COUNTY, UTAH



CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365



Scale: 1"=100'

Date: 5/13/11

SHEET NO:

REVISED:


8

8 OF 17

| WELL NAME | SURFACE POSITION | | | | | BOTTOM HOLE | | | | |
|----------------|------------------|----------------|---------------|----------------|-----------------------|---------------|----------------|---------------|----------------|-----------------------|
| | NAD83 | | NAD27 | | FOOTAGES | NAD83 | | NAD27 | | FOOTAGES |
| | LATITUDE | LONGITUDE | LATITUDE | LONGITUDE | | LATITUDE | LONGITUDE | LATITUDE | LONGITUDE | |
| NBU 1022-114BS | 39°58'32.500" | 109°22'55.383" | 39°58'32.623" | 109°22'52.933" | 1832' FSL 908' FEL | 39°58'33.287" | 109°22'50.526" | 39°58'33.410" | 109°22'48.077" | 1914' FSL 530' FEL |
| NBU 1022-111CS | 39°58'32.482" | 109°22'55.509" | 39°58'32.605" | 109°22'53.060" | 1830' FSL 918' FEL | 39°58'36.535" | 109°22'50.021" | 39°58'36.658" | 109°22'47.572" | 2243' FSL 492' FEL |
| NBU 1022-114CS | 39°58'32.464" | 109°22'55.636" | 39°58'32.587" | 109°22'53.187" | 1828' FSL 928' FEL | 39°58'29.975" | 109°22'50.055" | 39°58'30.098" | 109°22'47.606" | 1579' FSL 492' FEL |
| NBU 1022-111BS | 39°58'32.443" | 109°22'55.762" | 39°58'32.566" | 109°22'53.313" | 1826' FSL 937' FEL | 39°58'39.825" | 109°22'50.005" | 39°58'39.948" | 109°22'47.556" | 2576' FSL 492' FEL |
| NBU 1022-1H4CS | 39°58'32.425" | 109°22'55.888" | 39°58'32.548" | 109°22'53.439" | 1824' FSL 947' FEL | 39°58'43.027" | 109°22'50.022" | 39°58'43.150" | 109°22'47.573" | 2410' FSL 492' FEL |

RELATIVE COORDINATES - From Surface Position to Bottom Hole

| WELL NAME | NORTH | EAST | WELL NAME | NORTH | EAST | WELL NAME | NORTH | EAST | WELL NAME | NORTH | EAST |
|----------------|----------|--------|----------------|--------|--------|----------------|---------|--------|----------------|--------|--------|
| NBU 1022-114BS | 80.0' | 378.1' | NBU 1022-111CS | 410.6' | 426.9' | NBU 1022-114CS | -251.6' | 434.8' | NBU 1022-111BS | 747.6' | 447.6' |
| NBU 1022-1H4CS | 1,073.5' | 455.8' | | | | | | | | | |



Kerr-McGee Oil & Gas Onshore, LP
 1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-11

WELL PAD INTERFERENCE PLAT
 WELLS - NBU 1022-114BS,
 NBU 1022-111CS, NBU 1022-114CS,
 NBU 1022-111BS & NBU 1022-1H4CS
 LOCATED IN SECTION 1, T10S, R22E,
 S.L.B.&M., UINTAH COUNTY, UTAH.


609

CONSULTING, LLC
 2155 North Main Street
 Sheridan WY 82801
 Phone 307-674-0609
 Fax 307-674-0182

TIMBERLINE (435) 789-1365
 ENGINEERING & LAND SURVEYING, INC.
 209 NORTH 300 WEST - VERNAL, UTAH 84078

| | | |
|----------------------------|-------------------|-----------------------|
| DATE SURVEYED: 02-11-11 | SURVEYED BY: R.Y. | SHEET NO: 6 |
| DATE DRAWN: 02-24-11 | DRAWN BY: E.M.S. | |
| SCALE: 1" = 60' | | 6 OF 17 |

PLEASE NOTE: LOCATIONS OF PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.



WELL PAD - NBU 1022-11 DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 5107.2'
 FINISHED GRADE ELEVATION = 5105.4'
 CUT SLOPES = 1.5:1
 FILL SLOPES = 1.5:1
 TOTAL WELL PAD AREA = 3.66 ACRES
 TOTAL DISTURBANCE AREA = 5.19 ACRES
 SHRINKAGE FACTOR = 1.10
 SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP
 1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-11
 WELL PAD - LOCATION LAYOUT
 NBU 1022-114BS,
 NBU 1022-111CS, NBU 1022-114CS,
 NBU 1022-111BS & NBU 1022-1H4CS
 LOCATED IN SECTION 1, T10S, R22E,
 S.L.B.&M., UINTAH COUNTY, UTAH



CONSULTING, LLC
 2155 North Main Street
 Sheridan, WY 82801
 Phone 307-674-0609
 Fax 307-674-0182

WELL PAD QUANTITIES

TOTAL CUT FOR WELL PAD = 15,705 C.Y.
 TOTAL FILL FOR WELL PAD = 7,037 C.Y.
 TOPSOIL @ 6" DEPTH = 2,954 C.Y.
 EXCESS MATERIAL = 8,668 C.Y.

RESERVE PIT QUANTITIES

TOTAL CUT FOR RESERVE PIT
 +/- 11,020 C.Y.
 RESERVE PIT CAPACITY (2' OF FREEBOARD)
 +/- 42,290 BARRELS

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE




HORIZONTAL 0 30' 60' 1" = 60'
 2' CONTOURS

SCALE: 1"=60' DATE: 5/13/11 SHEET NO:
 REVISED: APF 12/7/11 **7** 7 OF 17

TIMBERLINE (435) 789-1365
 ENGINEERING & LAND SURVEYING, INC.
 209 NORTH 300 WEST - VERNAL, UTAH 84078

PLEASE NOTE: LOCATIONS OF PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.



WELL PAD - NBU 1022-11 (CLOSED LOOP) DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 5107.2'
 FINISHED GRADE ELEVATION = 5105.4'
 CUT SLOPES = 1.5:1
 FILL SLOPES = 1.5:1
 TOTAL WELL PAD AREA = 3.66 ACRES
 TOTAL DISTURBANCE AREA = 5.19 ACRES
 SHRINKAGE FACTOR = 1.10
 SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP
 1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-11
 WELL PAD - LOCATION LAYOUT
 NBU 1022-114BS,
 NBU 1022-111CS, NBU 1022-114CS,
 NBU 1022-111BS & NBU 1022-1H4CS
 LOCATED IN SECTION 1, T10S, R22E,
 S.L.B.&M., UINTAH COUNTY, UTAH



CONSULTING, LLC
 2155 North Main Street
 Sheridan, WY 82801
 Phone 307-674-0609
 Fax 307-674-0182

WELL PAD QUANTITIES

TOTAL CUT FOR WELL PAD = 15,705 C.Y.
 TOTAL FILL FOR WELL PAD = 7,037 C.Y.
 TOPSOIL @ 6" DEPTH = 2,954 C.Y.
 EXCESS MATERIAL = 8,668 C.Y.

COMPLETIONS PIT QUANTITIES

TOTAL CUT FOR COMPLETIONS PIT
 +/- 8,870 C.Y.
 COMPLETIONS PIT CAPACITY
 (2' OF FREEBOARD)
 +/- 33,770 BARRELS

WELL PAD LEGEND


- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE



HORIZONTAL 0 30' 60' 1" = 60'
 2' CONTOURS

SCALE: 1"=60' DATE: 10/5/11 SHEET NO:
 REVISED: APF 12/7/11 **7B** 7B OF 17

TIMBERLINE (435) 789-1365
 ENGINEERING & LAND SURVEYING, INC.
 209 NORTH 300 WEST - VERNAL, UTAH 84078



PLEASE NOTE: LOCATIONS OF FACILITIES AND PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-11

WELL PAD - FACILITIES DIAGRAM
NBU 1022-114BS,
NBU 1022-111CS, NBU 1022-114CS,
NBU 1022-111BS & NBU 1022-1H4CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., UINTAH COUNTY, UTAH



CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PPL — PROPOSED PIPELINE
- EPL — EXISTING PIPELINE



HORIZONTAL 1" = 60'

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

Scale: 1"=60' Date: 5/13/11
REVISED:

SHEET NO:
9 9 OF 17




PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: SOUTHEASTERLY

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-11


LOCATION PHOTOS
NBU 1022-1I4BS,
NBU 1022-1I1CS, NBU 1022-1I4CS,
NBU 1022-1I1BS & NBU 1022-1H4CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., Uintah County, Utah.



CONSULTING, LLC
2155 North Main Street
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

| | | |
|--------------------------------|-----------------------|------------------------|
| DATE PHOTOS TAKEN: 02-11-11 | PHOTOS TAKEN BY: R.Y. | SHEET NO: 10 |
| DATE DRAWN: 02-23-11 | DRAWN BY: E.M.S. | |
| Date Last Revised: | | 10 OF 17 |



NBU 1022-114BS
 NBU 1022-111CS
 NBU 1022-114CS
 NBU 1022-111BS
 NBU 1022-1H4CS

Legend

- Proposed Well Location
- Natural Buttes Unit Boundary
- Access Route - Proposed

Distance From Well Pad - NBU 1022-11 To Unit Boundary: ±908ft

Kerr-McGee Oil & Gas Onshore, LP
 1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-11


TOPO A
 NBU 1022-114BS,
 NBU 1022-111CS, NBU 1022-114CS,
 NBU 1022-111BS & NBU 1022-1H4CS
 LOCATED IN SECTION 1, T10S, R22E,
 S.L.B.&M., UINTAH COUNTY, UTAH



CONSULTING, LLC
 2155 North Main Street
 Sheridan, WY 82801
 Phone (307) 674-0609
 Fax (307) 674-0182



| | | |
|------------------|-------------------|-----------|
| Scale: 1:100,000 | NAD83 USP Central | Sheet No: |
| Drawn: TL | Date: 13 May 2011 | 11 |
| Revised: | Date: | |



**NBU 1022-114BS
NBU 1022-111CS
NBU 1022-114CS
NBU 1022-111BS
NBU 1022-1H4CS**

±46.2mi to Vernal

±75ft

±1,000ft

Legend

- Well - Proposed
- Well - Existing
- Well Pad
- Road - Proposed
- Road - Existing
- County Road
- Bureau of Land Management
- State
- Indian Reservation
- Private

Total Proposed Road Length: ±1,075ft


Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-11

TOPO B
NBU 1022-114BS,
NBU 1022-111CS, NBU 1022-114CS,
NBU 1022-111BS & NBU 1022-1H4CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH

CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182

| | | |
|---------------------|-------------------|--|
| Scale: 1" = 2,000ft | NAD83 USP Central | Sheet No: <b style="font-size: 2em;">12 |
| Drawn: TL | Date: 13 May 2011 | 12 of 17 |
| Revised: | Date: | |



NBU 1022-114BS
NBU 1022-111CS
NBU 1022-114CS
NBU 1022-111BS
NBU 1022-1H4CS

| Proposed Well | Nearest Well Bore | Footage |
|----------------|-------------------|---------|
| NBU 1022-1I4BS | BONANZA 1023-6L | 1,336ft |
| NBU 1022-1I1CS | NBU 1022-1H | 1,184ft |
| NBU 1022-1I4CS | BONANZA 1023-6M | 1,221ft |
| NBU 1022-1I1BS | NBU 1022-1H | 852ft |
| NBU 1022-1H4CS | NBU 1022-1H | 528ft |

Legend

- Well - Proposed
- Bottom Hole - Proposed
- Well Pad
- Well Path
- Bottom Hole - Existing
- Well - 1 Mile Radius
- Producing
- Temporarily-Abandoned
- ★ Active
- Shut-In
- ⊙ Spudded (Drilling commenced; Not yet completed)
- ▲ Approved permit (APD); not yet spudded
- Plugged and Abandoned
- New Permit (Not yet approved or drilled)
- ⊕ Inactive
- ⊗ Location Abandoned
- ⊗ Dry hole marker, buried
- ⊗ Drilling Operations Suspended
- ⊗ Returned APD (Unapproved)

Kerr-McGee Oil & Gas Onshore, LP
 1099 18th Street, Denver, Colorado 80202


WELL PAD - NBU 1022-11

TOPO C
NBU 1022-114BS,
NBU 1022-111CS, NBU 1022-114CS,
NBU 1022-111BS & NBU 1022-1H4CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., UINTAH COUNTY, UTAH

609
CONSULTING, LLC
 2155 North Main Street
 Sheridan, WY 82801
 Phone (307) 674-0609
 Fax (307) 674-0182



| | | |
|---------------------|-------------------|-----------------------|
| Scale: 1" = 2,000ft | NAD83 USP Central | Sheet No: |
| Drawn: TL | Date: 13 May 2011 | 13 13 of 17 |
| Revised: | Date: | |



**NBU 1022-114BS
NBU 1022-111CS
NBU 1022-114CS
NBU 1022-111BS
NBU 1022-1H4CS**

**Tie-In Points
Proposed Pipelines**

±1,140ft

| Proposed Liquid Pipeline | Length |
|---|-----------------|
| Buried 6" (Max.) (Meter House to Edge of Pad) | ±410ft |
| Buried 6" (Max.) (Edge of Pad to 1P Intersection) | ±95ft |
| Buried 6" (Max.) (1P Intersection to Proposed Pipeline ROW In Progress) | ±1,045ft |
| TOTAL PROPOSED BURIED LIQUID PIPELINE = | ±1,550ft |

| Proposed Gas Pipeline | Length |
|--|-----------------|
| Buried 6" (Meter House to Edge of Pad) | ±410ft |
| Buried 6" (Edge of Pad to 1P Intersection) | ±95ft |
| Buried 8" (1P Intersection to Proposed Pipeline ROW In Progress) | ±1,045ft |
| TOTAL PROPOSED BURIED GAS PIPELINE = | ±1,550ft |

Legend

- Well - Proposed
- Well Pad
- - - Gas Pipeline - Proposed
- - - Liquid Pipeline - Proposed
- - - Road - Proposed
- Bureau of Land Management
- Well - Existing
- - - Gas Pipeline - To Be Upgraded
- - - Liquid Pipeline - Existing
- - - Road - Existing
- Indian Reservation
- - - Gas Pipeline - Existing
- State
- Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-11

TOPO D
NBU 1022-114BS,
NBU 1022-111CS, NBU 1022-114CS,
NBU 1022-111BS & NBU 1022-1H4CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., UINTAH COUNTY, UTAH


609

CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182



| | | |
|---------------------|-------------------|-----------|
| Scale: 1" = 2,000ft | NAD83 USP Central | Sheet No: |
| Drawn: TL | Date: 13 May 2011 | 14 |
| Revised: | Date: | |

14 of 17



T10S T10S
R22E R23E

NBU 1022-1I4BS
NBU 1022-1I1CS
NBU 1022-1I4CS
NBU 1022-1I1BS
NBU 1022-1H4CS

| Proposed Liquid Pipeline | Length |
|---|-----------------|
| Buried 6" (Max.) (Meter House to Edge of Pad) | ±410ft |
| Buried 6" (Max.) (Edge of Pad to 1P Intersection) | ±95ft |
| Buried 6" (Max.) (1P Intersection to Proposed Pipeline ROW In Progress) | ±1,045ft |
| TOTAL PROPOSED BURIED LIQUID PIPELINE = | ±1,550ft |

| Proposed Gas Pipeline | Length |
|--|-----------------|
| Buried 6" (Meter House to Edge of Pad) | ±410ft |
| Buried 6" (Edge of Pad to 1P Intersection) | ±95ft |
| Buried 8" (1P Intersection to Proposed 16" Pipeline ROW In Progress) | ±1,045ft |
| TOTAL PROPOSED BURIED GAS PIPELINE = | ±1,550ft |

Legend

- Well - Proposed
- Well - Existing
- Well Pad
- - - Gas Pipeline - Proposed
- - - Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- - - Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private


Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-1I
TOPO D2 (PAD & PIPELINE DETAIL)
NBU 1022-1I4BS,
NBU 1022-1I1CS, NBU 1022-1I4CS,
NBU 1022-1I1BS & NBU 1022-1H4CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH

609
CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182



| | | |
|-------------------|-------------------|--------------------|
| Scale: 1" = 500ft | NAD83 USP Central | Sheet No: |
| Drawn: TL | Date: 13 May 2011 | 15 15 of 17 |
| Revised: | Date: | |



**NBU 1022-114BS
NBU 1022-111CS
NBU 1022-114CS
NBU 1022-111BS
NBU 1022-1H4CS**

| Proposed Well | Distance To Nearest Lease Boundary |
|----------------|------------------------------------|
| NBU 1022-114BS | 530ft |
| NBU 1022-111CS | 492ft |
| NBU 1022-114CS | 492ft |
| NBU 1022-111BS | 492ft |
| NBU 1022-1H4CS | 492ft |

Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- ▭ Lease Boundary
- Gas Pipeline - Proposed
- Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-11

TOPO E
NBU 1022-114BS,
NBU 1022-111CS, NBU 1022-114CS,
NBU 1022-111BS & NBU 1022-1H4CS
LOCATED IN SECTION 1, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH

CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182

| | | |
|---------------------|-------------------|--------------------|
| Scale: 1" = 2,000ft | NAD83 USP Central | Sheet No: |
| Drawn: TL | Date: 13 May 2011 | 16 16 of 17 |
| Revised: | Date: | |



Joseph D. Johnson
1099 18TH STREET STE. 1800 • DENVER, CO
80202
720-929-6708 • FAX 720-929-7708
E-MAIL: JOE.JOHNSON@ANADARKO.COM

September 28, 2011

Ms. Diana Mason
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11
NBU 1022-114BS
T10S-R22E
Section I: NESE/NESE
Surface: 1832' FSL, 908' FEL
Bottom Hole: 1914' FSL, 530' FEL
Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.

- Kerr-McGee's NBU 1022-114BS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

A handwritten signature in blue ink, appearing to read 'Joe D. Johnson', with a horizontal line underneath.

Joseph D. Johnson
Landman

| | |
|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS | |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | |
| 1. TYPE OF WELL Gas Well | 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | 8. WELL NAME and NUMBER: NBU 1022-114BS |
| PHONE NUMBER: 720 929-6511 | 9. API NUMBER: 43047392980000 |
| 9. FIELD and POOL or WILDCAT: NATURAL BUTTES | COUNTY: UINTAH |
| | STATE: UTAH |


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|--|---|---|
| <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 5/11/2012 | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input checked="" type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: May 21, 2012
By: 

| | | |
|---|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Gina Becker | PHONE NUMBER 720 929-6086 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 5/11/2012 | |



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047392980000

API: 43047392980000

Well Name: NBU 1022-114BS

Location: 1832 FSL 0908 FEL QTR NESE SEC 01 TWP 100S RNG 220E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 5/14/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No

Signature: Gina Becker

Date: 5/11/2012

Title: Regulatory Analyst II Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.

BLM - Vernal Field Office - Notification Form

Operator KERR-McGEE OIL & GAS Rig Name/# BUCKET RIG
Submitted By CARA MAHLER Phone Number 720.929.6029
Well Name/Number NBU 1022-114BS
Qtr/Qtr NESE Section 1 Township 10S Range 22E
Lease Serial Number UTU011336
API Number 4304739298

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 07/27/2012 13:00 HRS AM PM

Casing – Please report time casing run starts, not cementing times.

- Surface Casing
- Intermediate Casing
- Production Casing
- Liner
- Other

Date/Time 08/16/2012 08:00 HRS AM PM

BOPE

- Initial BOPE test at surface casing point
- BOPE test at intermediate casing point
- 30 day BOPE test
- Other

RECEIVED
JUL 28 2012
DIV. OF OIL, GAS & MINING

Date/Time _____ AM PM

Remarks ESTIMATED DATE AND TIME. PLEASE CONTACT KENNY GATHINGS AT 435.828.0986 OR LOVEL YOUNG AT 435.781.7051

| | |
|---|--|
| <p>STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING</p> | <p>FORM 9</p> |
| <p>SUNDRY NOTICES AND REPORTS ON WELLS</p> <p>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</p> | |
| <p>1. TYPE OF WELL Gas Well</p> | <p>5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336</p> |
| <p>2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.</p> | <p>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</p> |
| <p>3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779</p> | <p>7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES</p> |
| <p>4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S</p> | <p>8. WELL NAME and NUMBER: NBU 1022-114BS</p> |
| <p>PHONE NUMBER: 720 929-6511</p> | <p>9. API NUMBER: 43047392980000</p> |
| | <p>9. FIELD and POOL or WILDCAT: NATURAL BUTTES</p> |
| | <p>COUNTY: UINTAH</p> |
| | <p>STATE: UTAH</p> |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|--|--|---|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 7/27/2012 | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU TRIPLE A BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'.
RAN 14" 36.7# SCHEDULE 10 CONDUCTOR PIPE. CEMENT WITH 28
SACKS READY MIX. SPUD WELL LOCATION ON JULY 27, 2012 AT 09:00
HRS.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 August 01, 2012

| | | |
|---|-------------------------------------|------------------------------------|
| NAME (PLEASE PRINT) Jaime Scharnowske | PHONE NUMBER 720 929-6304 | TITLE Regulatory Analyst |
| SIGNATURE N/A | DATE 8/1/2012 | |

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR McGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: P.O. Box 173779
city DENVER
state CO zip 80217 Phone Number: (720) 929-6304

Well 1

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|--|-----------------------|-------------------|-----------|-----|-----|----------------------------------|--------|
| 4304739298 | NBU 1022-114BS | | NESE | 1 | 10S | 22E | UINTAH |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | | Entity Assignment Effective Date | |
| B | 99999 | 2900 | 7/27/2012 | | | 8/20/2012 | |
| Comments: MIRU TRIPLE A BUCKET RIG. <i>WSMVD</i> SPUD WELL LOCATION ON 7/27/2012 AT 09:00 HRS. <i>BHL:</i> | | | | | | | |

Well 2

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|--|-----------------------|-------------------|-----------|-----|-----|----------------------------------|--------|
| 4304752369 | NBU 1022-111CS | | NESE | 1 | 10S | 22E | UINTAH |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | | Entity Assignment Effective Date | |
| B | 99999 | 2900 | 7/27/2012 | | | 8/20/2012 | |
| Comments: MIRU TRIPLE A BUCKET RIG. <i>WSMVD</i> SPUD WELL LOCATION ON 7/27/2012 AT 11:30 HRS. <i>BHL: ne se</i> | | | | | | | |

Well 3

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|--|-----------------------|-------------------|-----------|-----|-----|----------------------------------|--------|
| 4304752364 | NBU 1022-114CS | | NESE | 1 | 10S | 22E | UINTAH |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | | Entity Assignment Effective Date | |
| B | 99999 | 2900 | 7/27/2012 | | | 8/20/2012 | |
| Comments: MIRU TRIPLE A BUCKET RIG. <i>WSMVD</i> SPUD WELL LOCATION ON 7/27/2012 AT 14:00 HRS. <i>BHL: ne se</i> | | | | | | | |

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

JAIME SCHARNOWSKE

Name (Please Print)

Jaime Scharnowske

Signature

REGULATORY ANALYST

8/2/2012

Title

Date

RECEIVED

AUG 06 2012

| | |
|--|---------------|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 |
| 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 | |
| SUNDRY NOTICES AND REPORTS ON WELLS | |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | |
| 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: | |
| 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES | |
| 8. WELL NAME and NUMBER: NBU 1022-114BS | |
| 9. API NUMBER: 43047392980000 | |
| 9. FIELD and POOL or WILDCAT: NATURAL BUTTES | |
| 1. TYPE OF WELL Gas Well | |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 PHONE NUMBER: 720 929-6511 | |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | |
| COUNTY: UINTAH | |
| STATE: UTAH | |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|--|--|---|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/3/2012 | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No Activity for the month of September 2012. Well TD at 2,339.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY
 October 05, 2012**

| | | |
|---|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Lindsey Frazier | PHONE NUMBER 720 929-6857 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 10/3/2012 | |

| | |
|--|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 5.LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
| 1. TYPE OF WELL Gas Well | 8. WELL NAME and NUMBER: NBU 1022-114BS |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | 9. API NUMBER: 43047392980000 |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | PHONE NUMBER: 720 929-6511 9. FIELD and POOL or WILDCAT: NATURAL BUTTES |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | COUNTY: UINTAH STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|--|---|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 11/5/2012 | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width:100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No Activity for the month of October 2012. Well TD at 2,339.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 November 05, 2012

| | | |
|---|-------------------------------------|------------------------------------|
| NAME (PLEASE PRINT) Jaime Scharnowske | PHONE NUMBER 720 929-6304 | TITLE Regulatory Analyst |
| SIGNATURE N/A | DATE 11/5/2012 | |

| | |
|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 |
| 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 | |
| SUNDRY NOTICES AND REPORTS ON WELLS | |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | |
| 1. TYPE OF WELL Gas Well | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | 8. WELL NAME and NUMBER: NBU 1022-114BS |
| PHONE NUMBER: 720 929-6511 | 9. API NUMBER: 43047392980000 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | 9. FIELD and POOL or WILDCAT: NATURAL BUTTES |
| | COUNTY: UINTAH |
| | STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|--|--|---|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/4/2012 | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No Activity for the month of November 2012. Well TD at 2,350.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 December 05, 2012

| | | |
|---|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Lindsey Frazier | PHONE NUMBER 720 929-6857 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 12/4/2012 | |

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# XTREME 12
Submitted By DALTON KING Phone Number 435- 828-0985
Well Name/Number NBU 1022-1I4BS
Qtr/Qtr NE/SE Section 1 Township 10 S Range 22E
Lease Serial Number UTU 33433
API Number 43-047-39298

Casing – Time casing run starts, not cementing times.

- Production Casing
- Other

Date/Time _____ AM PM

BOPE

- Initial BOPE test at surface casing point
- Other

Date/Time 12/11/2012 01:00 AM PM

RECEIVED
DEC 13 2012

DIV. OF OIL, GAS & MINING

Rig Move

Location To: NBU 1022-1I4BS

Date/Time 12/10/2012 08:00 AM PM

Remarks TIME IS ESTIMATED

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# XTREME 12
Submitted By DALTON KING Phone Number 435- 828-0985
Well Name/Number NBU 1022-1I4BS
Qtr/Qtr NE/SE Section 1 Township 10 S Range 22E
Lease Serial Number UTU 011336
API Number 43-047-39298

Casing – Time casing run starts, not cementing times.

- Production Casing
 Other

Date/Time 12/15/2012 00:30 AM PM

BOPE

- Initial BOPE test at surface casing point
 Other

RECEIVED

DEC 13 2012

DIV. OF OIL, GAS & MINING

Date/Time _____ AM PM

Rig Move

Location To: NBU 1022-1I1CS

Date/Time 12/15/2012 13:00 AM PM

Remarks TIME IS ESTIMATED

| | |
|---|---------------|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 |
| 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 | |
| 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: | |
| 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES | |
| 8. WELL NAME and NUMBER: NBU 1022-114BS | |
| 9. API NUMBER: 43047392980000 | |
| 9. FIELD and POOL or WILDCAT: NATURAL BUTTES | |
| COUNTY: UINTAH | |
| STATE: UTAH | |

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | |
|---|--|
| 1. TYPE OF WELL Gas Well | 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | PHONE NUMBER: 720 929-6511 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | |

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|--|---|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/16/2012 | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

FINISHED DRILLING TO 8,555' ON 12/14/2012. CEMENTED PRODUCTION CASING. RELEASED XTC 12 RIG ON 12/16/2012. DETAILS OF CASING AND CEMENT WILL BE INCLUDED WITH THE WELL COMPLETION REPORT. WELL IS WAITING ON FINAL COMPLETION ACTIVITIES

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 December 28, 2012

| | | |
|---|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Lindsey Frazier | PHONE NUMBER 720 929-6857 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 12/17/2012 | |

| | |
|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
| 1. TYPE OF WELL Gas Well | 8. WELL NAME and NUMBER: NBU 1022-114BS |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | 9. API NUMBER: 43047392980000 |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 | PHONE NUMBER: 720 929-6511 9. FIELD and POOL or WILDCAT: NATURAL BUTTES |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | COUNTY: UINTAH STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|--|---|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 2/4/2013 | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No Activity for the month of January 2013. Well TD at 8,555

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 February 13, 2013

| | | |
|--|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Laura Abrams | PHONE NUMBER 720 929-6356 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 2/4/2013 | |

| | |
|--|---------------|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | FORM 9 |
| 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 | |
| SUNDRY NOTICES AND REPORTS ON WELLS | |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | |
| 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: | |
| 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES | |
| 1. TYPE OF WELL Gas Well | |
| 8. WELL NAME and NUMBER: NBU 1022-114BS | |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. | |
| 9. API NUMBER: 43047392980000 | |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 PHONE NUMBER: 720 929-6511 | |
| 9. FIELD and POOL or WILDCAT: NATURAL BUTTES | |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | |
| COUNTY: UINTAH | |
| STATE: UTAH | |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|--|---|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/4/2013 | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Started completing the well. Well TD at 8,555

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY
 March 04, 2013**

| | | |
|--|-------------------------------------|---------------------------------------|
| NAME (PLEASE PRINT) Laura Abrams | PHONE NUMBER 720 929-6356 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 3/4/2013 | |

| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
|--|--|--|
| SUNDRY NOTICES AND REPORTS ON WELLS | | 5. LEASE DESIGNATION AND SERIAL NUMBER: U-011336 |
| Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| | | 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES |
| 1. TYPE OF WELL Gas Well | 8. WELL NAME and NUMBER: NBU 1022-114BS | |
| 2. NAME OF OPERATOR: ANADARKO E&P COMPANY LP | 9. API NUMBER: 43047392980000 | |
| 3. ADDRESS OF OPERATOR: PO Box 173779 , Denver, CO, 80217 | PHONE NUMBER: 720 929-6515 Ext | 9. FIELD and POOL or WILDCAT: NATURAL BUTTES |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 0908 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 01 Township: 10.0S Range: 22.0E Meridian: S | COUNTY: UINTAH | |
| | STATE: UTAH | |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/5/2013 | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER | |
| | <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. | | |
| <p>The following well was placed on production on 3/5/2013. The chronological well history will be submitted with the well completion report.</p> | | |
| <p>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 11, 2013</p> | | |
| NAME (PLEASE PRINT) Laura Abrams | PHONE NUMBER 720 929-6356 | TITLE Regulatory Analyst II |
| SIGNATURE N/A | DATE 3/8/2013 | |

RECEIVED
APR 09 2013

Form 3160-4
(August 2007)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU011336

| | | | | | |
|---|--|---|--|--|--|
| 1a. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other | | | 6. If Indian, Allottee or Tribe Name | | |
| b. Type of Completion <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr. Other _____ | | | 7. Unit or CA Agreement Name and No. UTU63047A | | |
| 2. Name of Operator KERR-MCGEE OIL&GAS ONSHORE | | | 8. Lease Name and Well No. NBU 1022-114BS | | |
| 3. Address 1099 18TH STREET STE 600 DENVER, CO 80202 | | | 9. API Well No. 43-047-39298 | | |
| 4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface NESE 1832FSL 908FEL 39.975694 N Lat, 109.382051 W Lon At top prod interval reported below NESE 1928FSL 539FEL At total depth NESE 1915FSL 523FEL | | | 10. Field and Pool, or Exploratory NATURAL BUTTES | | |
| 14. Date Spudded 07/27/2012 | | | 15. Date T.D. Reached 12/14/2012 | | |
| 16. Date Completed <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod. 03/05/2013 | | | 17. Elevations (DF, KB, RT, GL)* 5120 KB | | |
| 18. Total Depth: MD 8555 TVD 8524 | | 19. Plug Back T.D.: MD 8490 TVD 8459 | | 20. Depth Bridge Plug Set: MD TVD | |
| 21. Type Electric & Other Mechanical Logs Run (Submit copy of each) CBL/GR/CCL/TEMP | | | 22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit analysis) | | |

23. Casing and Liner Record (Report all strings set in well)

| Hole Size | Size/Grade | Wt. (#/ft.) | Top (MD) | Bottom (MD) | Stage Cementer Depth | No. of Sk. & Type of Cement | Slurry Vol. (BBL) | Cement Top* | Amount Pulled |
|-----------|-------------|-------------|----------|-------------|----------------------|-----------------------------|-------------------|-------------|---------------|
| 20.000 | 14.000 STL | 36.7 | 0 | 40 | | 28 | | | |
| 11.000 | 8.625 IJ-55 | 28.0 | 0 | 2320 | | 1175 | | 0 | |
| 7.875 | 4.500 I-80 | 11.6 | 0 | 8537 | | 1380 | | 620 | |
| | | | | | | | | | |
| | | | | | | | | | |

24. Tubing Record

| Size | Depth Set (MD) | Packer Depth (MD) | Size | Depth Set (MD) | Packer Depth (MD) | Size | Depth Set (MD) | Packer Depth (MD) |
|-------|----------------|-------------------|------|----------------|-------------------|------|----------------|-------------------|
| 2.375 | 7950 | | | | | | | |

25. Producing Intervals

| Formation | Top | Bottom | Perforated Interval | Size | No. Holes | Perf. Status |
|--------------|------|--------|---------------------|-------|-----------|--------------|
| A) MESAVERDE | 6596 | 8478 | 6596 TO 8478 | 0.360 | 170 | OPEN |
| B) | | | | | | |
| C) | | | | | | |
| D) | | | | | | |

26. Perforation Record

| Depth Interval | Amount and Type of Material |
|----------------|--|
| 6596 TO 8478 | PUMP 7409 BBLs SLICK H2O & 151,464 LBS 30/50 OTTAWA SAND |
| | |
| | |

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

| Depth Interval | Amount and Type of Material |
|----------------|-----------------------------|
| | |
| | |

28. Production - Interval A

| Date First Produced | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|---------------------|-------------------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| 03/05/2013 | 03/09/2013 | 24 | ▶ | 0.0 | 1812.0 | 0.0 | | | FLOWS FROM WELL |
| Choke Size | Tbg. Press. Flwg. | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio | Well Status | |
| 20/64 | SI 1238 | 1855.0 | ▶ | 0 | 1812 | 0 | | PGW | |

28a. Production - Interval B

| Date First Produced | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|---------------------|-------------------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| | | | ▶ | | | | | | |
| Choke Size | Tbg. Press. Flwg. | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio | Well Status | |
| | | | ▶ | | | | | | |

(See Instructions and spaces for additional data on reverse side)
ELECTRONIC SUBMISSION #203277 VERIFIED BY THE BLM WELL INFORMATION SYSTEM
**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

28b. Production - Interval C

| | | | | | | | | | |
|---------------------|----------------------|--------------|----------------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| Date First Produced | Test Date | Hours Tested | Test Production → | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate → | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio | Well Status | |

28c. Production - Interval D

| | | | | | | | | | |
|---------------------|----------------------|--------------|----------------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| Date First Produced | Test Date | Hours Tested | Test Production → | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate → | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio | Well Status | |

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

| Formation | Top | Bottom | Descriptions, Contents, etc. | Name | Top |
|-----------|-----|--------|------------------------------|-------------|-------------|
| | | | | | Meas. Depth |
| | | | | GREEN RIVER | 1288 |
| | | | | BIRD'S NEST | 1566 |
| | | | | MAHOGANY | 1895 |
| | | | | WASATCH | 4192 |
| | | | | MESAVERDE | 6291 |

32. Additional remarks (include plugging procedure):

The first 210 ft of the surface hole was drilled with a 12 ? in bit. The remainder of surface hole was drilled with an 11 in bit. DQX csg was run from surface to 5030 ft; LTC csg was run from 5030 ft to 8,537 ft. Attached is the chronological well history, perforation report and final survey.

33. Circle enclosed attachments:

- 1. Electrical/Mechanical Logs (1 full set req'd.)
- 2. Geologic Report
- 3. DST Report
- 4. Directional Survey
- 5. Sundry Notice for plugging and cement verification
- 6. Core Analysis
- 7 Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #203277 Verified by the BLM Well Information System.
For KERR-MCGEE OIL&GAS ONSHORE, LP, sent to the Vernal**

Name (please print) LUKE URBAN Title SR REGULATORY SPECIALIST

Signature _____ (Electronic Submission) Date 04/04/2013

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**US ROCKIES REGION
Operation Summary Report**

Well: NBU 1022-114BS RED Spud Date: 9/3/2012
 Project: UTAH-UINTAH Site: NBU 1022-11 PAD Rig Name No: PROPETRO 12/12, XTC 12/12
 Event: DRILLING Start Date: 8/2/2012 End Date: 12/15/2012
 Active Datum: RKB @5,120.00usft (above Mean Sea Level) UWI: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|----------|----------------|---------------|--------|------|----------|-----|----------------|---|
| 9/2/2012 | 18:00 - 0:00 | 6.00 | DRLSUR | 01 | E | P | | HELD SAFETY MEETING WITH PRO PETRO AND NOV. FINISH RIGGING DOWN AND PREP FOR RIG MOVE FINISH MOVING PRO PETRO EQUIPMENT TO NEW LOCATION.RIG DOWN NOV CLOSED LOOP SYSTEM. |
| 9/3/2012 | 0:00 - 6:00 | 6.00 | DRLSUR | 01 | E | P | | HELD SAFETY MEETING WITH PRO PETRO AND NOV . FINISH RIGGING DOWN AND PREP FOR RIG MOVE FINISH MOVING PRO PETRO EQUIPMENT TO NEW LOCATION.RIG DOWN NOV CLOSED LOOP SYSTEM. |
| | 6:00 - 11:00 | 5.00 | DRLSUR | 01 | A | P | | MOVE RIG 4.7 MILES TO THE NBU 1022-011 PAD |
| | 11:00 - 18:30 | 7.50 | DRLSUR | 01 | B | P | | RIG UP PRE MIX TANK, FRAC TANKS, AND ALL CLOSED LOOP SYSTEM.INSTALL HOSES FILL MUD TANKS AND CHECK FOR LEAKS. BACK IN RIG RAISE DERRICK PREP RIG TO SPUD WELL. |
| | 19:00 - 20:30 | 1.50 | DRLSUR | 02 | B | P | | SPUD DRILL 12.25" HOLE 44 ft TO 210 ft (166 FT, 111 FPH). WOB 5-15 Kips. GPM 491. PSI ON/OFF 750/500. SURFACE RPM 55, MOTOR 83, TOTAL RPM 138. UP/DOWN/ ROT 20/20/20 K. DRAG 0 Kips . CIRCULATE CLOSED LOOP SYSTEM DRILL DOWN TO 210 ft W/6 in COLLARS. NOV ON LINE NO HOLE ISSUES. |
| | 20:30 - 22:30 | 2.00 | DRLSUR | 06 | A | P | | TRIP OUT OF HOLE PICK UP DIRECTIONAL ASSEMBLY 11" BIT AND MUD MOTOR ORIENT MOTOR TO EM TOOLS AND TRIP IN HOLE |
| | 22:30 - 0:00 | 1.50 | DRLSUR | 02 | B | P | | DRILL 11" SURFACE HOLE F/ 210' / 460' 250' @166' FPH WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 860/720. ROTARY RPM 48, MOTOR RPM 83, TOTAL RPM 131. UP/DOWN/ ROTATE 50/43/45 K. DRAG 5 K. CIRCULATE CLOSED LOOP SYSTEM NOV ON LINE WITH 8.6# WATER. RUNNING VOLUME OVER BOTH SHAKERS. 170 API SCREENS ON SHAKERS. NO HOLE ISSUES. Current Position: 1.04' high, 1.1' left of proposalSlide Footage: 30' = 6.6% Rotating Footage: 425' = 93.4% |

**US ROCKIES REGION
Operation Summary Report**

Well: NBU 1022-114BS RED Spud Date: 9/3/2012
 Project: UTAH-UINTAH Site: NBU 1022-11 PAD Rig Name No: PROPETRO 12/12, XTC 12/12
 Event: DRILLING Start Date: 8/2/2012 End Date: 12/15/2012
 Active Datum: RKB @5,120.00usft (above Mean Sea Level) UWI: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|----------|----------------|---------------|--------|------|----------|-----|----------------|--|
| 9/4/2012 | 0:00 - 5:00 | 5.00 | DRLSUR | 02 | B | P | | DRILL 11" SURFACE HOLE F/460' TO 1180' 720' @144' FPH WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 950/790. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROTATE 61/49/55 K. DRAG 6 K. CIRCULATE CLOSED LOOP SYSTEM NOV ON LINE WITH 8.6# WATER. RUNNING VOLUME OVER BOTH SHAKERS. 170 API SCREENS ON SHAKERS. |
| | 5:00 - 12:00 | 7.00 | DRLSUR | 02 | B | P | | DRILL 11" SURFACE HOLE F / 1180' TO 1600' 420' @60' FPH WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1000/890. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROTATE 65/51/60 K. DRAG 5 K. CIRCULATE CLOSED LOOP SYSTEM NOV ON LINE WITH 8.6# WATER. RUNNING VOLUME OVER BOTH SHAKERS. 170 API SCREENS ON SHAKERS. |
| | 12:00 - 14:00 | 2.00 | DRLSUR | 22 | F | Z | | LOST CIRC@1500' DRILLING WITH AIR MIST. NOV RUN RIG OUT OF DRILLING WATER. SHUT DOWN AND FILL PITS AND UPRIGHTS WITH WATER.FROM HOLE. AIR ON HOLE @1500 CFM. |
| | 14:00 - 22:30 | 8.50 | DRLSUR | 02 | B | P | | DRILL 11" SURFACE HOLE F / 1600' TO 2339' 739' @86' FPH WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 970/1070. ROTARY RPM 65, MOTOR RPM 83, TOTAL RPM 148. UP/DOWN/ ROTATE 80/62/70 K. DRAG 10 K. CIRCULATE CLOSED LOOP SYSTEM NOV ON LINE WITH 8.6# WATER. RUNNING VOLUME OVER BOTH SHAKERS. 170 API SCREENS ON SHAKERS. LOST CIRC@1500' DRILLING WITH AIR MIST. |
| | 22:30 - 0:00 | 1.50 | DRLSUR | 05 | C | P | | Current Position: 9.4' low, 3.8' left of proposalSlide Footage: 243' = 10.5% Rotating Footage: 2056' = 89.5% CIRCULATE AND CONDITION MUD PRIOR TO LDDS |

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-114BS RED

Spud Date: 9/3/2012

Project: UTAH-UINTAH

Site: NBU 1022-11 PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 8/2/2012

End Date: 12/15/2012

Active Datum: RKB @5,120.00usft (above Mean Sea Level)

UWI: NE/SE/010/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|----------|----------------|---------------|--------|------|----------|-----|----------------|---|
| 9/5/2012 | 0:00 - 0:30 | 0.50 | DRLSUR | 05 | C | P | | <p>CIRCULATE AND CONDITION MUD PRIOR TO LDDS TOOH LAYING DOWN, L/D MWD TOOLS, DIRECTIONAL MONELS, MUD MOTOR, AND 11" BIT RIG UP AND RUN 52 JOINTS 8.625" J55 28# SURFACE CASING SHOE AT 2304.83' BAFFLE AT 2358.83' NO PROBLEMS GETTING TO BOTTOM RUN 200' 1" PIPE AND RIG DOWN MOVE RIG OFF WELL. HELD S/M WITH PRO PETRO CMENERS RIG UP,PRESSURE TEST LINES TO 2000 PSI. PUMP 130 BBLs OF WATER AHEAD. CATCH PSI. PUMP 20 BBLs OF 8.3# GEL WATER AHEAD. MIX AND PUMP (300 SX) 61.4 BBLs OF 15.8# 1.15 YD 5 GAL/SK PREMIUM CEMENT W/ 2% CALC. DROP PLUG ON FLY. DISPLACE W/ 140 BBLs OF H2O. NO CIRC THROUGH OUT. FINAL LIFT OF 270 PSI AT 4 BBL/MIN. BUMP PLUG WITH 600 PSI FOR 5 MIN. FLOAT HELD. MIX AND PUMP (150 SX) 30.7 BBLs OF SAME TAIL CEMENT W/ 4% CALC. DOWN 1" . NO CEMENT TO SURFACE. SHUT DOWN AND CLEAN TRUCK.. WAIT 1.5 HOURS MIX AND PUMP (150 SX) 30.7 BBLs OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE. SHUT DOWN AND CLEAN TRUCK. WAIT 1.5 HOURS MIX AND PUMP (150 SX) 30.7 BBLs OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE. NO SHUT DOWN AND CLEAN TRUCK.WAIT 1.5 HOURS MIX AND PUMP (150 SX) 30.7 BBLs OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE. WAIT 1.5 HOURS MIX AND PUMP (100 SX) 20.4 BBLs OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE CLEAN TRUCK. WAIT 1.5 HOURS MIX AND PUMP (175 SX) 35.8 BBLs OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE CEMENT TO SURFACE RIG DOWN SAME. RELEASE RIG @ 13:30 9-5-2012</p> |
| | 0:30 - 3:30 | 3.00 | DRLSUR | 06 | A | P | | |
| | 3:30 - 7:00 | 3.50 | DRLSUR | 12 | C | P | | |
| | 7:00 - 13:30 | 6.50 | DRLSUR | 12 | E | P | | |

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-114BS RED Spud Date: 9/3/2012
 Project: UTAH-UINTAH Site: NBU 1022-11 PAD Rig Name No: PROPETRO 12/12, XTC 12/12
 Event: DRILLING Start Date: 8/2/2012 End Date: 12/15/2012
 Active Datum: RKB @5,120.00usft (above Mean Sea Level) UVM: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------------|----------------|---------------|--------|------|----------|-----|----------------|--|
| 12/9/2012 | 12:00 - 0:00 | 12.00 | DRLPRC | 01 | E | P | | <p>RIG DOWN ON THE OLD LOCATION RIGGED DOWN THE FLOOR, LAID OVER THE DERRICK, WELDED UP AND INSPECTED A BRACE IN THE DERRICK, WELDED STIRRING LINES IN THE RIG PIT, FINISHED CLEANING RIG PITS, MOVED 7 LOADS TO THE NEW LOCATION (BASKETS, CEMENT BINS, SOME MATTING BOARDS), TRANSFERRED MUD TO THE NEW LOCATION, MOVED CAMPS TO THE NEW LOCATION. CONTINUED RIGGING DOWN BOILER, PITS PUMPS, DOGHOSE AND DOING MISC. MAINTENANCE</p> <p>R.W. JONES 1 TRUCK 1 PUSHER MOUNTAIN WEST: 2 TRUCKS, 1-1 TON, 5 PERSONEL</p> <p>JD: 6 WATER TRUCKS, 1 BED TRUCK</p> |
| 12/10/2012 | 0:00 - 7:00 | 7.00 | MIRU | 01 | E | P | | <p>EXTREME: 6 MOB HANDS WAIT ON DAYLIGHT TO MOVE / RIG DOWN WATER LINES, PUMPS, PITS, ELECTRIC LINES, PASON LINES, WORK ON THE RIG</p> |
| | 7:00 - 15:00 | 8.00 | MIRU | 01 | A | P | | <p>WE HELD A SAFETY MEETING WITH R.W. JONES TRUCKING, LOADED OUT ALL REMAINING EQUIPMENT MOVED 4.8 MILES AND SET IN ALL OF THE RIG EQUIPMENT. TRUCKS ARRIVED @ 07:00 / LEFT @ 15:00 RW JONES: 10 TRUCKS, 2 FORKLIFTS, 2 PUSHERS, 2 FLAGGERS, 2 SWAMPERS. JD : BACK HOE, TRENCHER, 3 HANDS EXTREME : 6 MOB HANDS</p> |
| | 15:00 - 0:00 | 9.00 | MIRU | 01 | B | P | | <p>HOOKED UP THE ELECTRIC LINES, RAISED THE DOGHOUSE, RAISED THE DERRICK, HOOKED UP THE WATER LINES, FLOW LINES, PUMPS, PITS, STEAM LINES, AND PAYSON LINES. WE COULD NOT SCOPE THE DERRICK UP YET THERE WAS A PROBLEM WITH THE E-STOP. STILL TROUBLE SHOOTING AT THIS POINT AND CONTINUING TO RIG UP.</p> |
| 12/11/2012 | 0:00 - 3:00 | 3.00 | MIRU | 01 | B | P | | <p>RIG UP THE FLARE LINES, FLOW LINES, AND STEAM LINES</p> |
| | 3:00 - 9:30 | 6.50 | MIRU | 08 | A | Z | | <p>***FAILURE: RIG EQUIPMENT - (DRAW WORKS) THE E-STOP WOULD NOT RELEASE THE BRAKES SO WE COULD SCOPE THE DERRICK UP. TROUBLE SHOOTING THE PROBLEM.</p> |
| | 9:30 - 12:00 | 2.50 | MIRU | 01 | B | P | | <p>SCOPE UP THE DERRICK AND RIG UP THE FLOOR, FINISH NU BOP</p> |

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-114BS RED

Spud Date: 9/3/2012

Project: UTAH-UINTAH

Site: NBU 1022-11 PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 8/2/2012

End Date: 12/15/2012

Active Datum: RKB @5,120.00usft (above Mean Sea Level)

UWI: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------------|----------------|---------------|--------|------|----------|-----|----------------|--|
| 12/12/2012 | 12:00 - 19:00 | 7.00 | PRPSPD | 15 | A | P | | HOLD SAFETY MEETING. TEST TOP DRIVE VALVE, I-BOP VALVE, FLOOR VALVE, DART VALVE, PIPE AND BLIND RAMS, INSIDE AND OUTSIDE KILL LINE VALVES INSIDE OUTSIDE CHOKE LINE VALVE, HCR VALVE, CHOKE LINE, CHOKE MANIFOLD VALVES AND CHOKES TO 5000 PSI FOR 10 MINUTES AND 250 PSI FOR 5 MINUTES. TEST ANNULAR TO 2500 PSI FOR 10 MIN AND 250 PSI FOR 5 MINUTES. TESTING CASING TO 1500 PSI FOR 30 MINUTES. |
| | 19:00 - 22:00 | 3.00 | PRPSPD | 06 | A | P | | PICK UP AND SCRIBE THE BHA THEN TRIP WITH THE HEAVY WEIGHT DRILL PIPE. |
| | 22:00 - 23:00 | 1.00 | PRPSPD | 09 | A | P | | CUT AND SLIP 30' OF DRILLING LINE. |
| | 23:00 - 0:00 | 1.00 | PRPSPD | 06 | A | P | | TRIP IN THE HOLE TAG CEMENT @ 2222' |
| | 0:00 - 2:00 | 2.00 | DRLPRC | 02 | B | P | | DRILLING THE SHOE TRACK |
| | 2:00 - 6:00 | 4.00 | DRLPRC | 02 | B | P | | DRILL SLIDE F/ 2350' - 2957' (607' @ 151.7'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 65, MUD MOTOR RPM 108. STROKES PER MINUTE 115 GALLONS PER MINUTE 517. OFF/ON PSI 1100/1500. DIFFERENTIAL 400. TORQUE HIGH/LOW . OFF BOTTOM TORQUE STRING WEIGHT UP/DOWN/ROT 85/65/75. DRAG 10 K. SLID 62' @ 74.6'/HR. SLIDE 24% ROTATE 76% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 8.7 VIS 33. ///// DRILLING WITH FLOWZAN MUD CHEM ///// PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 35 BBL. FLUID FOR HOLE VOLUME (ADD 65 BBLs OF DRILL WATER TO PITS FOR VOLUME) LOST 30 BBL. TO SEEPAGE (5 BBL. /HR.) NO FLARE BIT POSITION: 5' LEFT 5' LOW OF PLAN LINE |

**US ROCKIES REGION
Operation Summary Report**

Well: NBU 1022-114BS RED Spud Date: 9/3/2012
 Project: UTAH-UINTAH Site: NBU 1022-11 PAD Rig Name No: PROPETRO 12/12, XTC 12/12
 Event: DRILLING Start Date: 8/2/2012 End Date: 12/15/2012
 Active Datum: RKB @5,120.00usft (above Mean Sea Level) UWM: NE/SE/010/S/22/E/110/0/26/PM/S1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------|----------------|---------------|--------|------|----------|-----|----------------|---|
| | 6:00 - 13:30 | 7.50 | DRLPRV | 02 | B | P | | DRILL SLIDE F/ 2957' - 4116' (1059' @ 141.2'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 65, MUD MOTOR RPM 108. STROKES PER MINUTE 115 GALLONS PER MINUTE 517. OFF/ON PSI 1200/1600. DIFFERENTIAL 400. TORQUE HIGH/LOW . OFF BOTTOM TORQUE STRING WEIGHT UP/DOWN/ROT 100/80/90. DRAG 10 K. SLID 52' @ 62.4'/HR. SLIDE 12.82% ROTATE 87.18% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 8.7 VIS 33. ///// DRILLING WITH FLOWZAN MUD CHEM ///// PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 60 BBL. FLUID FOR HOLE VOLUME (ADD 160 BBL. OF DRILL WATER TO PITS FOR VOLUME) LOST 100 BBL. TO SEEPAGE (14 BBL. /HR.) NO FLARE BIT POSITION: 3966': 15'N 1'E OF TARGET CENTER RIG SERVICE |
| | 13:30 - 14:00 | 0.50 | DRLPRC | 07 | A | P | | |
| | 14:00 - 17:30 | 3.50 | DRLPRV | 02 | B | P | | DRILL SLIDE F/ 4116' - 4458' (342' @ 97.7'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 65, MUD MOTOR RPM 108. STROKES PER MINUTE 115 GALLONS PER MINUTE 517. OFF/ON PSI 1200/1600. DIFFERENTIAL 400. TORQUE HIGH/LOW . OFF BOTTOM TORQUE STRING WEIGHT UP/DOWN/ROT 100/80/90. DRAG 10 K. SLID 52' @ 62.4'/HR. SLIDE 12.82% ROTATE 87.18% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 8.7 VIS 33. ///// DRILLING WITH FLOWZAN MUD CHEM ///// PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 20 BBL. FLUID FOR HOLE VOLUME (ADD 0 BBL. OF DRILL WATER TO PITS FOR VOLUME) LOST 30 BBL. TO SEEPAGE (8 BBL. /HR.) NO FLARE BIT POSITION: 4320': 14' N 1'E OF TARGET CENTER RIG SERVICE |
| | 17:30 - 18:00 | 0.50 | DRLPRV | 07 | A | P | | |

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-114BS RED Spud Date: 9/3/2012
 Project: UTAH-UJINTAH Site: NBU 1022-11 PAD Rig Name No: PROPETRO 12/12, XTC 12/12
 Event: DRILLING Start Date: 8/2/2012 End Date: 12/15/2012
 Active Datum: RKB @5,120.00usft (above Mean Sea Level) UWM: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------------|----------------|---------------|--------|------|----------|-----|----------------|--|
| | 18:00 - 0:00 | 6.00 | DRLPRV | | | | | DRILL SLIDE F/ 4458' - 5609' (1151' @ 191.3'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 65, MUD MOTOR RPM 108. STROKES PER MINUTE 115 GALLONS PER MINUTE 517. OFF/ON PSI 1200/1600. DIFFERENTIAL 400. TORQUE HIGH/LOW . OFF BOTTOM TORQUE STRING WEIGHT UP/DOWN/ROT 120/100/110. DRAG 10 K. SLID 0' @ 0'/HR. SLIDE 0% ROTATE 100% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 8.9 VIS 33. ///// DRILLING WITH FLOWZAN MUD CHEM ///// PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 70 BBL. FLUID FOR HOLE VOLUME (ADD 160 BBL. OF DRILL WATER TO PITS FOR VOLUME) LOST 125 BBL. TO SEEPAGE (21 BBL. /HR.) NO FLARE BIT POSITION: 5559': 12' N 9'W OF TARGET CENTER |
| 12/13/2012 | 0:00 - 6:00 | 6.00 | DRLPRV | 02 | B | P | | DRILL SLIDE F/ 5609' - 6189' (580' @ 96.6'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 65, MUD MOTOR RPM 108. STROKES PER MINUTE 115 GALLONS PER MINUTE 517. OFF/ON PSI 1450/1950. DIFFERENTIAL 400. TORQUE HIGH/LOW .11000/7000 OFF BOTTOM TORQUE 5500 STRING WEIGHT UP/DOWN/ROT 130/105/115. DRAG 15 K. SLID 50' @ 54.9'/HR. SLIDE 15% ROTATE 85% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 8.8 VIS 33. ///// DRILLING WITH FLOWZAN MUD CHEM ///// PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 35 BBL. FLUID FOR HOLE VOLUME (ADD 90 BBL. OF DRILL WATER TO PITS FOR VOLUME) LOST 55 BBL. TO SEEPAGE (9 BBL. /HR.) NO FLARE BIT POSITION: : 13' N 10'W OF TARGET CENTER /// TORQUE VALUES ARE NOT CORRECT DUE TO A PROBLEM ON THE RIG |

US ROCKIES REGION
Operation Summary Report

| | | | |
|--|--|---|--|
| Well: NBU 1022-114BS RED | | Spud Date: 9/3/2012 | |
| Project: UTAH-UINTAH | | Site: NBU 1022-11 PAD | Rig Name No: PROPETRO 12/12, XTC 12/12 |
| Event: DRILLING | | Start Date: 8/2/2012 | End Date: 12/15/2012 |
| Active Datum: RKB @5,120.00usft (above Mean Sea Level) | | UWM: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0 | |

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------|----------------|---------------|--------|------|----------|-----|----------------|---|
| | 6:00 - 17:30 | 11.50 | DRLPRV | 02 | B | P | | DRILL SLIDE F/ 6189' - 7430'(1241' @ 107.9'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 65, MUD MOTOR RPM 108. STROKES PER MINUTE 115 GALLONS PER MINUTE 517. OFF/ON PSI 1550/2100. DIFFERENTIAL 550. TORQUE HIGH/LOW .11000/6000 OFF BOTTOM TORQUE 5000 STRING WEIGHT UP/DOWN/ROT 140/120/130. DRAG 10 K. SLID 33' @ 44'/HR. SLIDE 6.52% ROTATE 93.48% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 8.8 VIS 33. ///// DRILLING WITH FLOWZAN MUD CHEM ///// PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 75 BBL. FLUID FOR HOLE VOLUME (ADD 180 BBL. OF DRILL WATER TO PITS FOR VOLUME) LOST 65 BBL. TO SEEPAGE (6 BBL. /HR.) NO FLARE BIT POSITION: 7335' 18' N 9'W OF TARGET CENTER /// TORQUE VALUES ARE NOT CORRECT DUE TO A PROBLEM ON THE RIG RIG SERVICE |
| | 17:30 - 18:00 | 0.50 | DRLPRV | 07 | A | P | | |

**US ROCKIES REGION
Operation Summary Report**

| | | | |
|--|--|---|--|
| Well: NBU 1022-1I4BS RED | | Spud Date: 9/3/2012 | |
| Project: UTAH-UINTAH | | Site: NBU 1022-1I PAD | Rig Name No: PROPETRO 12/12, XTC 12/12 |
| Event: DRILLING | | Start Date: 8/2/2012 | End Date: 12/15/2012 |
| Active Datum: RKB @5,120.00usft (above Mean Sea Level) | | UWI: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0 | |

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------------|----------------|---------------|--------|------|----------|-----|----------------|---|
| | 18:00 - 0:00 | 6.00 | DRLPRV | 02 | B | P | | DRILL SLIDE F/ 7430' - 8003' (573' @ 95.5'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 65, MUD MOTOR RPM 108. STROKES PER MINUTE 115 GALLONS PER MINUTE 517. OFF/ON PSI 1700/2000. DIFFERENTIAL 300. TORQUE HIGH/LOW .11000/6000 OFF BOTTOM TORQUE 5000 STRING WEIGHT UP/DOWN/ROT 145/135/140. DRAG 5 K. SLID 0' @ 0'/HR. SLIDE 0% ROTATE 100% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 8.8 VIS 33. ///// DRILLING WITH FLOWZAN MUD CHEM ///// PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 35 BBL. FLUID FOR HOLE VOLUME (ADD 90 BBL OF DRILL WATER TO PITS FOR VOLUME) LOST 65 BBL. TO SEEPAGE (11 BBL. /HR.) NO FLARE BIT POSITION: 8219' 11'N 1'E OF TARGET CENTER /// TORQUE VALUES ARE NOT CORRECT DUE TO A PROBLEM ON THE RIG |
| 12/14/2012 | 0:00 - 7:30 | 7.50 | DRLPRV | 02 | B | P | | DRILL SLIDE F/ 8003' - 8555' (552' @ 73.6'/HR) WEIGHT ON BIT 18-24 K. AVERAGE WEIGHT ON BIT 22 K. ROTARY RPM 50, MUD MOTOR RPM 90. STROKES PER MINUTE 95 GALLONS PER MINUTE 428. OFF/ON PSI 2500/2900. DIFFERENTIAL 400. TORQUE HIGH/LOW 10000/6000 OFF BOTTOM TORQUE 5000 STRING WEIGHT UP/DOWN/ROT 145/130/135. DRAG 10 K. SLID 0' @ 0'/HR. SLIDE 0% ROTATE 100% NOV RUNNING 1 CENTRIFUGES ON DEWATER. WT 11.9 VIS 43. PUMP LCM SWEEPS TO HELP WITH LOSSES. USED 35 BBL. FLUID FOR HOLE VOLUME (ADD 100 BBL OF DRILL WATER TO PITS FOR VOLUME) LOST 40 BBL. TO SEEPAGE (5 BBL. /HR.) 5-15' FLARE FOR 1 HPOUR BIT POSITION: 8555' 3'N 6'E OF TARGET CENTER /// TORQUE VALUES ARE NOT CORRECT DUE TO A PROBLEM ON THE RIG |

US ROCKIES REGION
Operation Summary Report

| | | | |
|--|--|--|--|
| Well: NBU 1022-114BS RED | | Spud Date: 9/3/2012 | |
| Project: UTAH-UINTAH | | Site: NBU 1022-11 PAD | Rig Name No: PROPETRO 12/12, XTC 12/12 |
| Event: DRILLING | | Start Date: 8/2/2012 | End Date: 12/15/2012 |
| Active Datum: RKB @5,120.00usft (above Mean Sea Level) | | UWI: NE/SE/010/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0 | |

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------------|----------------|---------------|--------|------|----------|-----|----------------|--|
| | 7:30 - 9:30 | 2.00 | DRLPRV | 05 | C | P | | CIRCULATE AND CONDITION FOR THE WIPER TRIP |
| | 9:30 - 16:30 | 7.00 | DRLPRV | 06 | E | P | | TRIPPED OUT OF THE HOLE TO THE CASING SHOE. TIGHT @ 6150', 5950', 5200', 4298', 3946', 3200', 2808' |
| | 16:30 - 22:00 | 5.50 | DRLPRV | 06 | E | P | | FILLED THE PIPE AND TRIPPED BACK IN THE HOLE. HAD TO WASH THROUGH ONE BRIDGE AT 6105' 6' OF FILL ON BOTTOM |
| | 22:00 - 0:00 | 2.00 | DRLPRV | 05 | C | P | | CIRCULATE AND CONDITION PRIOR TO TRIPPING OUT FOR CASING. |
| 12/15/2012 | 0:00 - 8:00 | 8.00 | DRLPRV | 06 | A | P | | 15' FLARE ON BOTTOMS UP TRIP OUT TO RUN CASING AND LAYED DOWN THE DIRECTION BHA |
| | 8:00 - 8:30 | 0.50 | DRLPRV | 14 | B | P | | PULLED THE WEAR BUSHING |
| | 8:30 - 17:00 | 8.50 | CSGPRO | 12 | C | P | | HELD A SAFETY MEETING WITH KIMZEY CASING CREW RAN 194 TOTAL JTS. OF CASING (79 JOINTS OF 4.5"/11.6# / I-80/ LTC + 1 MARKER) + (113 JTS. OF 4.5"/ 11.6# / I-80/ DQX) + (1-DQX CROSS OVER). LANDED @ 8536.95', FLOAT COLLAR @ 8489.7', MESA VERDE MARKER @ 6307.82', CROSS OVER JT. @ 5007.88'. WE HAD TO WASH 1 SMALL BRIDGE @ 8525' |
| | 17:00 - 18:30 | 1.50 | CSGPRO | 05 | D | P | | CIRCULATED CASING ON BOTTOM 80 STROKES 360 GPM 800PSI |
| | 18:30 - 22:00 | 3.50 | CSGPRO | 12 | E | P | | 15' FLARE ON BOTTOMS UP SAFETY MEETING WITH BJ PRESSURE TEST TO 4850 PSI. DROPPED THE BOTTOM PLUG, PUMP 25 BBLS OF FRESH WATER. PUMP 160 BBLS (455 SX) OF PREMIUM LITE II LEAD CEMENT, 12.5 PPG 1.98 YLD, .05 LB/SACK OF STATIC FREE + .4%BWOC R-3 +.25 LBS/SACK CELLO FLAKE + 5 LBS/SACK KOL-SEAL + .4% BWOC FL-52 + .2%BWOC SODIUM METASILICATE + 6% BWOC BENTONITE + 100.1%FRESH WATER . FOLLOWED BY 217 BBLS (925 SX) OF 14.3# 1.32 YD 5.91 GAL/SK. POZ 50/50 TAIL CEMENT + 2% BWOC BENTONITE + .005 LB/SACK STATIC FREE + 10% BWOW SODIUM CHLORIDE + .55%BWOC R-3 + .002GPS FP-6L + .75 BWOC SODIUM METASILICATE 58.8% FRESH WATER . SHUT DOWN AND FLUSH LINES. DROP PLUG AND DISPLACE W/ 132 BBLS OF FRESH WATER TREATED WITH CLAYFIX AND MAGNACIDE. LOST RETURNS AT THE START OF DISPLACEMENT, 0 BBLS OF WATER AND NO CEMENT TO SURFACE. LIFT PSI OF 2500 / BUMP PLUG 3200 PSI. . PRESSURE HELD 5 MINS. FLOAT HELD. FLOW BACK 1.5 BBLS. EST. TOC FOR LEAD 500', EST TOC FOR TAIL 3670'. RIG DOWN CEMENTERS. |
| | 22:00 - 23:00 | 1.00 | CSGPRO | 14 | A | P | | SET THE PACK OFF AND NIPPLE DOWN THE BOP |
| | 23:00 - 0:00 | 1.00 | RDMO | 01 | E | P | | DOWN AND PREP TO SKID RIG RIG RELEASED AT 00:00 |

1 General

1.1 Customer Information

| | |
|----------------|-------------------|
| Company | US ROCKIES REGION |
| Representative | |
| Address | |

1.2 Well/Wellbore Information

| | | | |
|--------------|--|---------------|--|
| Well | NBU 1022-114BS RED | Wellbore No. | OH |
| Well Name | NBU 1022-114BS | Wellbore Name | NBU 1022-114BS |
| Report No. | 1 | Report Date | 2/20/2013 |
| Project | UTAH-UINTAH | Site | NBU 1022-11 PAD |
| Rig Name/No. | | Event | COMPLETION |
| Start Date | 2/20/2013 | End Date | 3/5/2013 |
| Spud Date | 9/3/2012 | Active Datum | RKB @5,120.00usft (above Mean Sea Level) |
| UWI | NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0 | | |

1.3 General

| | | | | | |
|---------------------|--|-----------------|--|------------|--|
| Contractor | | Job Method | | Supervisor | |
| Perforated Assembly | | Conveyed Method | | | |

1.4 Initial Conditions

| | | | |
|-------------------|---------|--------------------|--|
| Fluid Type | | Fluid Density | |
| Surface Press | | Estimate Res Press | |
| TVD Fluid Top | | Fluid Head | |
| Hydrostatic Press | | Press Difference | |
| Balance Cond | NEUTRAL | | |

1.5 Summary

| | | | |
|------------------|-------------------------------|--------------------------|-------------------|
| Gross Interval | 6,596.0 (usft)-8,478.0 (usft) | Start Date/Time | 2/27/2013 12:00AM |
| No. of Intervals | 41 | End Date/Time | 2/27/2013 12:00AM |
| Total Shots | 170 | Net Perforation Interval | 50.00 (usft) |
| Avg Shot Density | 3.40 (shot/ft) | Final Surface Pressure | |
| | | Final Press Date | |

2 Intervals

2.1 Perforated Interval

| Date | Formation/Reservoir | CCL@ (usft) | CCL-T S (usft) | MD Top (usft) | MD Base (usft) | Shot Density (shot/ft) | Misfires/Add. Shot | Diameter (in) | Carr Type /Stage No | Carr Size (in) | Phasing (") | Charge Desc /Charge Manufacturer | Charge Weight (gram) | Reason | Misrun |
|-------------------|---------------------|-------------|----------------|---------------|----------------|------------------------|--------------------|---------------|---------------------|----------------|-------------|----------------------------------|----------------------|----------------|--------|
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,596.0 | 6,604.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |

2.1 Perforated Interval (Continued)

| Date | Formation/ Reservoir | CCL@ (usft) | CCL-T S (usft) | MD Top (usft) | MD Base (usft) | Shot Density (shot/ft) | Misfires/ Add. Shot | Diamete r (in) | Carr Type /Stage No | Carr. Size (in) | Phasing (°) | Charge Desc /Charge Manufacturer | Charge Weight (gram) | Reason | Misrun |
|----------------------|-------------------------|----------------|----------------------|------------------|-------------------|------------------------------|------------------------|----------------------|---------------------|-----------------------|----------------|-------------------------------------|----------------------------|----------------|--------|
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,674.0 | 6,675.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,683.0 | 6,684.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,722.0 | 6,723.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,777.0 | 6,778.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,819.0 | 6,820.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,863.0 | 6,864.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,874.0 | 6,875.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,917.0 | 6,918.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 6,940.0 | 6,941.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,044.0 | 7,045.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,120.0 | 7,121.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,127.0 | 7,128.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,226.0 | 7,227.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,315.0 | 7,317.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,333.0 | 7,334.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,345.0 | 7,346.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,364.0 | 7,365.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,420.0 | 7,421.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,487.0 | 7,488.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,512.0 | 7,513.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,544.0 | 7,545.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |

2.1 Perforated Interval (Continued)

| Date | Formation/ Reservoir | CCL@ (usft) | CCL-T S (usft) | MD Top (usft) | MD Base (usft) | Shot Density (shot/ft) | Misfires/ Add. Shot | Diamete r (in) | Carr Type /Stage No | Carr. Size (in) | Phasing (°) | Charge Desc /Charge Manufacturer | Charge Weight (gram) | Reason | Misrun |
|----------------------|-------------------------|----------------|----------------------|------------------|-------------------|------------------------------|------------------------|----------------------|---------------------|-----------------------|----------------|-------------------------------------|----------------------------|----------------|--------|
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,575.0 | 7,576.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,597.0 | 7,598.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,617.0 | 7,618.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,632.0 | 7,633.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,650.0 | 7,651.0 | 3.00 | | 0.360 | EXP/ | 3.375 | 120.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,695.0 | 7,696.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,736.0 | 7,737.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,770.0 | 7,771.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,799.0 | 7,800.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,824.0 | 7,825.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,872.0 | 7,873.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,893.0 | 7,894.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 7,933.0 | 7,934.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 8,030.0 | 8,031.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 8,057.0 | 8,058.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 8,306.0 | 8,307.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 8,367.0 | 8,368.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 8,466.0 | 8,467.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |
| 2/27/2013 12:00AM | MESAVERDE/ | | | 8,476.0 | 8,478.0 | 4.00 | | 0.360 | EXP/ | 3.375 | 90.00 | | 23.00 | PRODUCTIO N | |

3 Plots

**US ROCKIES REGION
Operation Summary Report**

Well: NBU 1022-114BS RED

Spud Date: 9/3/2012

Project: UTAH-UINTAH

Site: NBU 1022-11 PAD

Rig Name No: SWABBCO 6/6

Event: COMPLETION

Start Date: 2/20/2013

End Date: 3/5/2013

Active Datum: RKB @5,120.00usft (above Mean Sea Level)

UWI: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|-----------|----------------|---------------|--------|------|----------|-----|----------------|---|
| 1/25/2013 | - | | | | | | | |
| 2/20/2013 | 7:30 - 7:45 | 0.25 | SUBSPR | 48 | | P | | HELD SAFETY MEETING: HIGH PRESSURE |
| | 7:45 - 9:00 | 1.25 | SUBSPR | 33 | C | P | | FILL SURFACE CSG. MIRU CAMERON QUICK TEST. PRESSURE TEST CSG & FRAC VALVES 1ST PSI TEST T/ 7000 PSI. HELD FOR 15 MIN LOST 46 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI. PRESSURE TEST 8 5/8 X 4 1/2 TO 583 PSI HELD FOR 5 MIN LOST -48 PSI, BLEED PSI OFF, REINSTALLED POP OFF SWFN |
| 2/22/2013 | 9:00 - 14:00 | 5.00 | SUBSPR | 37 | | P | | PERF STG 1) PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF AS PER PERF DESIGN. POOH. SWFW |
| 2/26/2013 | 6:30 - 7:00 | 0.50 | FRAC | 48 | | P | | JSA-SAFETY MEETING |
| | 7:00 - 17:30 | 10.50 | FRAC | 36 | B | P | | PRESSURE TEST SURFACE LINE TO 8032#, LOST 16 # IN 15 MIN, (90 MIN TO TEST) 1. REFER TO STIMULATION PJR FOR FLUID, SAND AND CHEMICAL VOLUME, ALL STAGES WERE PERFORATED ACCORDING TO PERF RECORD IN OPEN WELL, ALL STAGES WERE STIMULATED TO VENDOR POST JOB REPORT. START FRAC @ 8:12 AM, (FRAC STG #1) WHP = 1617 #, BRK DN PERFS = 4210#, @ 4.8 BPM, ISIP = 2560#, FG = 0.74, FINAL ISIP = 2476#, FINAL FG = 0.73, STG #2 = TRY BREAKDOWN W/ PRESSURE UP TO 6800#, WORK W/ NO BRK DN, RIH W/ WIRELINESET DN @ 7956' BOTTOM 2 PERF COVER W/ SAND, HOW FRAC BLUE WELL THE GROUND VALVE ON RED WAS LEAKING, RIH W/ DUMP BAILER DUMP ACID ON TOP PERF, (FRAC STG #2) WHP = 1474#, BRK DN PERFS = PRESSURE UP 6734#, COULD NOT PUMP INTO PERF, CALL DENVER SKIP STG #2, SET CBP ABOVE MOVE TO STG #3. SET CBP 7835' BOOTM PERF 7824 TO 7825' (FRAC STG #3) WHP = 658#, BRK DN PERFS = 5816#, @ 4.8 BPM, ISIP = 3037 #, F.G = 0.83, FINAIL ISIP = 2193#, FINIAL F.G. = 0.72, SW JSA-SAFETY MEETING |
| 2/27/2013 | 6:30 - 7:00 | 0.50 | FRAC | 48 | | P | | |

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-114BS RED Spud Date: 9/3/2012
 Project: UTAH-UINTAH Site: NBU 1022-11 PAD Rig Name No: SWABBCO 6/6
 Event: COMPLETION Start Date: 2/20/2013 End Date: 3/5/2013
 Active Datum: RKB @5,120.00usft (above Mean Sea Level) UVM: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|-----------|----------------|---------------|--------|------|----------|-----|----------------|--|
| | 7:00 - 17:30 | 10.50 | FRAC | 36 | B | P | | <p>1.REFER TO STIMULATION PJR FOR FLUID, SAND AND CHEMICAL VOLUME, ALL STAGES WERE PERFORATED ACCORDING TO PERF RECORD IN OPEN WELL, ALL STAGES WERE STIMULATED TO VENDOR POST JOB REPORT.</p> <p>(FRAC STG #4) WHP = 1365#, BRK DN PERFS = 2791#, @ 5.3 BPM, ISIP = 1635#, FG = 0.65 , FINAL ISIP = 2139#, FINAL FG = 0.72 ,</p> <p>(FRAC STG #5) WHP = 1514#, BRK DN PERFS = 2573#, @ = 4.7 BPM, ISIP = 1926#, F G = 0.70 , FINAL ISIP = 2139#, FINAL F G = 0.73 ,</p> <p>(FRAC STG #6) WHP = 875#, BRK DN PERFS = 2254 #, @ 5.1 BPM, ISIP = 1518 #, F G = 0.65 , FINAL ISIP = 2372 #, FINAL F G = 0.78 , SW HSM, RIGGING DOWN, PINCH POINTS</p> |
| 2/28/2013 | 6:45 - 7:00 | 0.25 | FRAC | 48 | | P | | (FRAC STG #7) WHP = 1,093#, BRK DN PERFS = 2,219#, @ 4.8 BPM, ISIP = 1,459#, F G = 0.65 , FINAL ISIP = 2,035#, FINAL F G = 0.74 , |
| | 7:00 - 15:30 | 8.50 | FRAC | 36 | B | P | | (FRAC STG #8) WHP = 1,255#, BRK DN PERFS = 2,370#, @ 5.1 BPM, ISIP = 1,531#, F G = 0.67 , FINAL ISIP = 2,100#, FINAL F G = 0.76 , |
| | | | | | | | | (KILL PLUG) P/U RIH W/ HALIBURTON 8K CBP, SET FOR TOP KILL @ =6,546' R/D WIRELINE AND FRAC CREW, SHUT WELL IN, [PLUG SET, BLED WELL OFF COULD NOT SHEAR PLUG, PULLED OUT OF ROPE SOCKET] |
| 3/1/2013 | 7:00 - 7:30 | 0.50 | DRLOUT | 48 | | P | | TOTAL FLUID PUMP'D =7,409 BBLS TOTAL SAND PUMP'D =151,464# ROAD RIG |
| | 7:30 - 17:00 | 9.50 | DRLOUT | 44 | C | P | | ROAD RIG FROM NBU 921-26J PAD TO LOC, MIRU,PU FISHING TOOLS, TIH TO 6358' EOT, 200 JTS, SWIFN |
| 3/4/2013 | 7:00 - 7:30 | 0.50 | DRLOUT | 48 | | P | | FISHING |
| | 7:30 - 17:00 | 9.50 | DRLOUT | 44 | C | P | | BREAK CIRC, TRY TO LATCH FISH, 4' SAND ON FISH, WASH DWN , LATCH FISH, CIRC SAND OUT, JAR FISH, POOH WITH FISH, LD FISH, PU POBS, SN, BIT, TIH TAG PLUG #1, TEST BOP'S, 3000#, MILL 5 PLUGS.,7551', 238 JTS EOT SWIFN |
| 3/5/2013 | 7:00 - 7:30 | 0.50 | DRLOUT | 48 | | P | | MILLING |

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-114BS RED

Spud Date: 9/3/2012

Project: UTAH-UJINTAH

Site: NBU 1022-11 PAD

Rig Name No: SWABBCO 6/6

Event: COMPLETION

Start Date: 2/20/2013

End Date: 3/5/2013

Active Datum: RKB @5,120.00usft (above Mean Sea Level)

UWI: NE/SE/0/10/S/22/E/1/0/0/26/PM/S/1832/E/0/908/0/0

| Date | Time Start-End | Duration (hr) | Phase | Code | Sub Code | P/U | MD From (usft) | Operation |
|------|----------------|---------------|--------|------|----------|-----|----------------|--|
| | 7:30 - 12:00 | 4.50 | DRLOUT | 44 | C | P | | <p>MILL 3 CBP'S, 252 JTS, 8088', C/O 12' SAND, TO PBT, 266 JTS, 8490', POOH TO 7950.31', 250 JTS, LAND TBG, ND BOP'S, NUWH, POBS, 1500#, PRESSURE TEST FLOW LINE 3000#, RDMO TO NBU 1022-111CS</p> <p>TURNED TO PROD 12:00 NOON</p> <p>PLUG# 1 6564' 10' SAND 5 MIN 30# KICK PLUG# 2 6634' 10' SAND 5 MIN 20# KICK PLUG# 3 6898 30' SAND 5 MIN 50# KICK PLUG# 4 7158' 15' SAND 5 MIN 500# KICK PLUG# 5 7451' 20' SAND 5 MIN 200# KICK PLUG# 6 7681' 10' SAND 5 MIN 100# KICK PLUG# 7 7862' 30' SAND 5 MIN 50# KICK PLUG# 8 8088' 40' SAND 5 MIN 100# KICK</p> <p>PBT 8490' BTM PERF 8478'</p> <p>TBG 250 JTS 7932.28' KB 15.00' HANGER 4.125" .83' SN 1.875" 2.20' EOT 7950.31'</p> <p>FRAC WTR 7,408 BBLS RCVD 2,200 BBLS LTR 5,208 BBLS</p> <p>WELL TURNED TO SALES @ 1300 HR ON 3/5/2013. 2.7 MCFD, 1560 BWPD, FCP 1650#, FTP 1353#, 20/64" CK.</p> |
| | 12:00 - 12:00 | 0.00 | DRLOUT | 51 | | | | |

Project: UTAH - UTM (feet), NAD27, Zone 12N
 Site: UINTAH_NBU 1022-11 PAD
 Well: NBU 1022-114BS
 Wellbore: Wellbore #1
 Design: NBU 1022-114BS (wp01)
 Latitude: 39.976729
 Longitude: -109.381370
 GL: 5105.00
 KB: 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12)

| FORMATION TOP DETAILS | | | |
|-----------------------|---------|---------|-----------------|
| | TVDPath | MDPath | Formation |
| | 1117.00 | 1122.70 | GREEN RIVER |
| | 1381.00 | 1391.07 | BIRDS NEST |
| | 1836.00 | 1853.65 | MAHOGANY MARKER |
| | 4147.00 | 4177.81 | WASATCH |
| | 4747.00 | 4777.81 | INTERCEPT |
| | 6317.00 | 6347.83 | MESAVERDE |
| | 8505.00 | 8535.86 | SEGO |



| WELL DETAILS: NBU 1022-114BS | | | | | |
|------------------------------|-------------|-----------------------|-----------|-------------|-----------|
| | | Ground Level: 5105.00 | | | |
| +N/-S | +E/-W | Northing | Easting | Latitude | Longitude |
| 0.00 | 14520322.41 | 2093698.55 | 39.975729 | -109.381370 | |

| CASING DETAILS | | | |
|----------------|---------|--------|-------|
| TVD | MD | Name | Size |
| 2284.98 | 2308.83 | 8-5/8" | 8-5/8 |

Azimuths to True North
 Magnetic North: 10.84°
 Magnetic Field
 Strength: 52190.6nT
 Dip Angle: 65.83°
 Date: 11/12/2012
 Model: IGRF2010

| DESIGN TARGET DETAILS | | | | | | | | | |
|-----------------------------|---------|--------|--------|-------------|------------|-----------|-------------|------------------------|--|
| Name | TVD | +N/-S | +E/-W | Northing | Easting | Latitude | Longitude | Shape | |
| NBU 1022-114BS DRILLERS TGT | 3067.00 | 105.55 | 369.45 | 14521434.65 | 2094266.02 | 39.976019 | -109.380052 | Circle (Radius: 15.00) | |
| INTERCEPT NBU 1022-114BS | 4747.00 | 97.53 | 372.08 | 14521426.68 | 2094268.79 | 39.975997 | -109.380042 | Point | |
| NBU 1022-114BS 25' CYL. | 8505.00 | 79.40 | 378.02 | 14521408.68 | 2094275.06 | 39.975947 | -109.380021 | Circle (Radius: 25.00) | |

| SECTION DETAILS | | | | | | | | |
|-----------------|-------|--------|---------|--------|--------|------|--------|--------|
| MD | Inc | Azi | TVD | +N/-S | +E/-W | Dleg | TFace | VSect |
| 2285.00 | 10.64 | 77.40 | 2261.56 | 84.73 | 276.34 | 0.00 | 0.00 | 287.85 |
| 2535.00 | 10.64 | 77.40 | 2507.26 | 94.80 | 321.39 | 0.00 | 0.00 | 334.01 |
| 3067.00 | 0.00 | 0.00 | 3036.21 | 105.55 | 369.45 | 2.00 | 180.00 | 383.26 |
| 3163.94 | 0.29 | 161.86 | 3133.15 | 105.31 | 369.53 | 0.30 | 161.86 | 383.29 |
| 8535.86 | 0.29 | 161.86 | 8505.00 | 79.40 | 378.02 | 0.00 | 0.00 | 386.27 |



US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

UINTAH_NBU 1022-1I PAD

NBU 1022-1I4BS

Wellbore #1

Design: NBU 1022-1I4BS ACTUAL

Standard Survey Report

19 December, 2012

Anadarko Petroleum Corp

Survey Report

| | | | |
|------------------|------------------------------------|-------------------------------------|--|
| Company: | US ROCKIES REGION PLANNING | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | TVD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Site: | UINTAH_NBU 1022-11 PAD | MD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Well: | NBU 1022-114BS | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | NBU 1022-114BS ACTUAL | Database: | edmp |

| | | | |
|--------------------|--|----------------------|----------------|
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | | |
| Map System: | Universal Transverse Mercator (US Survey Feet) | System Datum: | Mean Sea Level |
| Geo Datum: | NAD 1927 (NADCON CONUS) | | |
| Map Zone: | Zone 12N (114 W to 108 W) | | |

| | | | | | |
|------------------------------|---|---------------------|--------------------|--------------------------|-------------|
| Site: | UINTAH_NBU 1022-11 PAD, Sec.1-T10S-R22E | | | | |
| Site Position: | | Northing: | 14,521,322.42 usft | Latitude: | 39.975729 |
| From: | Lat/Long | Easting: | 2,093,898.54 usft | Longitude: | -109.381370 |
| Position Uncertainty: | 0.00 ft | Slot Radius: | 13-3/16 " | Grid Convergence: | 1.04 ° |

| | | | | | | |
|-----------------------------|----------------|---------|----------------------------|--------------------|----------------------|-------------|
| Well: | NBU 1022-114BS | | | | | |
| Well Position | +N/-S | 0.00 ft | Northing: | 14,521,322.42 usft | Latitude: | 39.975729 |
| | +E/-W | 0.00 ft | Easting: | 2,093,898.54 usft | Longitude: | -109.381370 |
| Position Uncertainty | | 0.00 ft | Wellhead Elevation: | ft | Ground Level: | 5,105.00 ft |

| | | | | | |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| Wellbore: | Wellbore #1 | | | | |
| Magnetics | Model Name | Sample Date | Declination (°) | Dip Angle (°) | Field Strength (nT) |
| | IGRF2010 | 11/12/2012 | 10.84 | 65.83 | 52,191 |

| | | | | | |
|--------------------------|-----------------------|------------------------------|-------------------|----------------------|----------------------|
| Design: | NBU 1022-114BS ACTUAL | | | | |
| Audit Notes: | | | | | |
| Version: | 1.0 | Phase: | ACTUAL | Tie On Depth: | 11.00 |
| Vertical Section: | | Depth From (TVD) (ft) | +N/-S (ft) | +E/-W (ft) | Direction (°) |
| | | 11.00 | 0.00 | 0.00 | 77.86 |

| | | | | | |
|-----------------------|-----------------|--------------------------|------------------|--------------------|--|
| Survey Program | Date 12/19/2012 | | | | |
| From (ft) | To (ft) | Survey (Wellbore) | Tool Name | Description | |
| 184.00 | 2,285.00 | Survey #1 (Wellbore #1) | MWD | MWD - STANDARD | |
| 2,375.00 | 8,555.00 | Survey #2 (Wellbore #1) | MWD | MWD - STANDARD | |

| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-------------------------|------------------------|-----------------------|
| 11.00 | 0.00 | 0.00 | 11.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 184.00 | 0.53 | 293.52 | 184.00 | 0.32 | -0.73 | -0.65 | 0.31 | 0.31 | 0.00 |
| 269.00 | 0.79 | 58.68 | 268.99 | 0.78 | -0.59 | -0.42 | 1.39 | 0.31 | 147.25 |
| 351.00 | 2.02 | 68.35 | 350.97 | 1.61 | 1.23 | 1.54 | 1.52 | 1.50 | 11.79 |
| 441.00 | 2.46 | 71.25 | 440.90 | 2.81 | 4.54 | 5.03 | 0.50 | 0.49 | 3.22 |
| 531.00 | 3.61 | 70.81 | 530.77 | 4.37 | 9.04 | 9.76 | 1.28 | 1.28 | -0.49 |
| 621.00 | 5.19 | 71.51 | 620.50 | 6.59 | 15.58 | 16.62 | 1.76 | 1.76 | 0.78 |
| 711.00 | 6.33 | 78.10 | 710.05 | 8.90 | 24.29 | 25.62 | 1.46 | 1.27 | 7.32 |
| 801.00 | 7.47 | 79.51 | 799.40 | 10.99 | 34.90 | 36.43 | 1.28 | 1.27 | 1.57 |
| 891.00 | 8.62 | 78.19 | 888.51 | 13.44 | 47.26 | 49.03 | 1.29 | 1.28 | -1.47 |

Anadarko Petroleum Corp

Survey Report

| | | | |
|------------------|------------------------------------|-------------------------------------|--|
| Company: | US ROCKIES REGION PLANNING | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | TVD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Site: | UJINTAH_NBU 1022-11 PAD | MD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Well: | NBU 1022-114BS | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | NBU 1022-114BS ACTUAL | Database: | edmp |

Survey

| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
|-------------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-------------------------|------------------------|-----------------------|
| 981.00 | 9.15 | 75.29 | 977.43 | 16.63 | 60.78 | 62.92 | 0.77 | 0.59 | -3.22 |
| 1,071.00 | 10.29 | 76.08 | 1,066.14 | 20.39 | 75.50 | 78.10 | 1.28 | 1.27 | 0.88 |
| 1,161.00 | 10.29 | 74.15 | 1,154.69 | 24.51 | 91.04 | 94.16 | 0.38 | 0.00 | -2.14 |
| 1,251.00 | 10.55 | 73.79 | 1,243.20 | 29.01 | 106.68 | 110.40 | 0.30 | 0.29 | -0.40 |
| 1,341.00 | 10.29 | 74.41 | 1,331.72 | 33.47 | 122.34 | 126.64 | 0.31 | -0.29 | 0.69 |
| 1,431.00 | 9.94 | 73.27 | 1,420.32 | 37.87 | 137.52 | 142.41 | 0.45 | -0.39 | -1.27 |
| 1,521.00 | 10.20 | 76.08 | 1,508.93 | 42.02 | 152.69 | 158.12 | 0.62 | 0.29 | 3.12 |
| 1,611.00 | 11.17 | 73.18 | 1,597.37 | 46.46 | 168.77 | 174.77 | 1.23 | 1.08 | -3.22 |
| 1,701.00 | 10.82 | 70.02 | 1,685.72 | 51.87 | 185.06 | 191.83 | 0.77 | -0.39 | -3.51 |
| 1,791.00 | 9.83 | 67.29 | 1,774.26 | 57.72 | 200.08 | 207.75 | 1.23 | -1.10 | -3.03 |
| 1,881.00 | 9.67 | 66.85 | 1,862.96 | 63.66 | 214.12 | 222.72 | 0.20 | -0.18 | -0.49 |
| 1,971.00 | 9.06 | 69.31 | 1,951.76 | 69.13 | 227.70 | 237.15 | 0.81 | -0.68 | 2.73 |
| 2,061.00 | 8.98 | 68.77 | 2,040.65 | 74.18 | 240.88 | 251.09 | 0.13 | -0.09 | -0.60 |
| 2,151.00 | 9.15 | 71.86 | 2,129.53 | 78.95 | 254.22 | 265.14 | 0.57 | 0.19 | 3.43 |
| 2,241.00 | 10.02 | 76.78 | 2,218.27 | 82.97 | 268.65 | 280.09 | 1.33 | 0.97 | 5.47 |
| 2,285.00 | 10.64 | 77.40 | 2,261.56 | 84.73 | 276.34 | 287.98 | 1.43 | 1.41 | 1.41 |
| TIE ON | | | | | | | | | |
| 2,375.00 | 10.51 | 75.08 | 2,350.03 | 88.66 | 292.38 | 304.48 | 0.49 | -0.14 | -2.58 |
| FIRST MWD SURVEY | | | | | | | | | |
| 2,465.00 | 9.83 | 73.53 | 2,438.62 | 92.95 | 307.68 | 320.34 | 0.81 | -0.76 | -1.72 |
| 2,554.00 | 8.98 | 74.26 | 2,526.42 | 96.99 | 321.65 | 334.85 | 0.96 | -0.96 | 0.82 |
| 2,643.00 | 8.00 | 73.74 | 2,614.44 | 100.61 | 334.28 | 347.96 | 1.10 | -1.10 | -0.58 |
| 2,731.00 | 6.44 | 78.99 | 2,701.74 | 103.26 | 345.00 | 359.00 | 1.92 | -1.77 | 5.97 |
| 2,819.00 | 5.13 | 79.61 | 2,789.29 | 104.92 | 353.72 | 367.87 | 1.49 | -1.49 | 0.70 |
| 2,907.00 | 3.88 | 87.49 | 2,877.02 | 105.76 | 360.56 | 374.74 | 1.58 | -1.42 | 8.95 |
| 2,995.00 | 2.63 | 87.49 | 2,964.88 | 105.98 | 365.55 | 379.67 | 1.42 | -1.42 | 0.00 |
| 3,083.00 | 1.44 | 96.11 | 3,052.82 | 105.95 | 368.67 | 382.71 | 1.39 | -1.35 | 9.80 |
| 3,172.00 | 1.31 | 96.86 | 3,141.79 | 105.71 | 370.79 | 384.73 | 0.15 | -0.15 | 0.84 |
| 3,260.00 | 1.44 | 101.86 | 3,229.77 | 105.36 | 372.87 | 386.69 | 0.20 | 0.15 | 5.68 |
| 3,349.00 | 1.00 | 140.11 | 3,318.75 | 104.53 | 374.47 | 388.07 | 1.01 | -0.49 | 42.98 |
| 3,437.00 | 1.19 | 155.99 | 3,406.73 | 103.11 | 375.33 | 388.62 | 0.40 | 0.22 | 18.05 |
| 3,525.00 | 1.25 | 159.99 | 3,494.71 | 101.37 | 376.03 | 388.94 | 0.12 | 0.07 | 4.55 |
| 3,614.00 | 1.25 | 158.24 | 3,583.69 | 99.56 | 376.72 | 389.24 | 0.04 | 0.00 | -1.97 |
| 3,700.00 | 1.38 | 163.11 | 3,669.67 | 97.70 | 377.37 | 389.48 | 0.20 | 0.15 | 5.66 |
| 3,789.00 | 1.38 | 163.36 | 3,758.64 | 95.64 | 377.99 | 389.65 | 0.01 | 0.00 | 0.28 |
| 3,879.00 | 0.50 | 82.99 | 3,848.63 | 94.65 | 378.69 | 390.13 | 1.54 | -0.98 | -89.30 |
| 3,966.00 | 0.44 | 126.74 | 3,935.63 | 94.50 | 379.33 | 390.72 | 0.41 | -0.07 | 50.29 |
| 4,056.00 | 0.56 | 152.86 | 4,025.63 | 93.90 | 379.81 | 391.07 | 0.28 | 0.13 | 29.02 |
| 4,143.00 | 0.56 | 145.11 | 4,112.62 | 93.17 | 380.25 | 391.34 | 0.09 | 0.00 | -8.91 |
| 4,232.00 | 0.31 | 282.24 | 4,201.62 | 92.87 | 380.26 | 391.29 | 0.92 | -0.28 | 154.08 |
| 4,320.00 | 1.06 | 303.61 | 4,289.62 | 93.37 | 379.35 | 390.50 | 0.89 | 0.85 | 24.28 |
| 4,408.00 | 1.00 | 306.74 | 4,377.60 | 94.28 | 378.06 | 389.43 | 0.09 | -0.07 | 3.56 |
| 4,497.00 | 0.94 | 295.74 | 4,466.59 | 95.06 | 376.78 | 388.34 | 0.22 | -0.07 | -12.36 |

Anadarko Petroleum Corp

Survey Report

| | | | |
|------------------|------------------------------------|-------------------------------------|--|
| Company: | US ROCKIES REGION PLANNING | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | TVD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Site: | UINTAH_NBU 1022-11 PAD | MD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Well: | NBU 1022-114BS | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | NBU 1022-114BS ACTUAL | Database: | edmp |

| Survey | | | | | | | | | | |
|---------------------------|--------------------|----------------|---------------------------|---------------|---------------|-----------------------------|-------------------------------|------------------------------|-----------------------------|--|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) | |
| 4,586.00 | 0.88 | 287.36 | 4,555.58 | 95.58 | 375.47 | 387.17 | 0.16 | -0.07 | -9.42 | |
| 4,674.00 | 0.75 | 288.86 | 4,643.57 | 95.97 | 374.28 | 386.09 | 0.15 | -0.15 | 1.70 | |
| 4,763.00 | 0.50 | 284.11 | 4,732.56 | 96.25 | 373.35 | 385.24 | 0.29 | -0.28 | -5.34 | |
| 4,852.00 | 0.56 | 259.11 | 4,821.56 | 96.27 | 372.55 | 384.46 | 0.27 | 0.07 | -28.09 | |
| 4,942.00 | 0.44 | 227.99 | 4,911.56 | 95.95 | 371.86 | 383.72 | 0.32 | -0.13 | -34.58 | |
| 5,031.00 | 0.51 | 230.57 | 5,000.55 | 95.47 | 371.30 | 383.07 | 0.08 | 0.08 | 2.90 | |
| 5,119.00 | 0.56 | 229.24 | 5,088.55 | 94.94 | 370.67 | 382.35 | 0.06 | 0.06 | -1.51 | |
| 5,207.00 | 0.31 | 225.49 | 5,176.55 | 94.49 | 370.18 | 381.77 | 0.29 | -0.28 | -4.26 | |
| 5,296.00 | 0.44 | 196.86 | 5,265.55 | 94.00 | 369.90 | 381.40 | 0.25 | 0.15 | -32.17 | |
| 5,384.00 | 0.50 | 192.45 | 5,353.54 | 93.30 | 369.72 | 381.08 | 0.08 | 0.07 | -5.01 | |
| 5,470.00 | 0.50 | 182.99 | 5,439.54 | 92.56 | 369.62 | 380.82 | 0.10 | 0.00 | -11.00 | |
| 5,559.00 | 0.88 | 186.74 | 5,528.53 | 91.49 | 369.52 | 380.50 | 0.43 | 0.43 | 4.21 | |
| 5,649.00 | 0.88 | 175.86 | 5,618.52 | 90.12 | 369.49 | 380.18 | 0.19 | 0.00 | -12.09 | |
| 5,738.00 | 0.50 | 228.24 | 5,707.52 | 89.18 | 369.25 | 379.75 | 0.78 | -0.43 | 58.85 | |
| 5,827.00 | 0.50 | 346.74 | 5,796.51 | 89.30 | 368.87 | 379.40 | 0.97 | 0.00 | 133.15 | |
| 5,916.00 | 0.50 | 2.86 | 5,885.51 | 90.06 | 368.80 | 379.49 | 0.16 | 0.00 | 18.11 | |
| 6,005.00 | 0.94 | 357.24 | 5,974.50 | 91.18 | 368.79 | 379.71 | 0.50 | 0.49 | -6.31 | |
| 6,095.00 | 0.75 | 359.99 | 6,064.49 | 92.50 | 368.75 | 379.96 | 0.22 | -0.21 | 3.06 | |
| 6,184.00 | 0.69 | 353.49 | 6,153.49 | 93.62 | 368.69 | 380.13 | 0.11 | -0.07 | -7.30 | |
| 6,273.00 | 0.56 | 354.99 | 6,242.48 | 94.59 | 368.59 | 380.24 | 0.15 | -0.15 | 1.69 | |
| 6,361.00 | 0.50 | 6.11 | 6,330.48 | 95.40 | 368.59 | 380.41 | 0.14 | -0.07 | 12.64 | |
| 6,449.00 | 0.33 | 17.92 | 6,418.48 | 96.02 | 368.71 | 380.66 | 0.22 | -0.19 | 13.42 | |
| 6,535.00 | 0.06 | 74.49 | 6,504.48 | 96.27 | 368.83 | 380.83 | 0.35 | -0.31 | 65.78 | |
| 6,624.00 | 0.13 | 129.61 | 6,593.47 | 96.21 | 368.96 | 380.94 | 0.12 | 0.08 | 61.93 | |
| 6,713.00 | 0.31 | 148.11 | 6,682.47 | 95.95 | 369.16 | 381.08 | 0.21 | 0.20 | 20.79 | |
| 6,800.00 | 0.44 | 160.36 | 6,769.47 | 95.43 | 369.40 | 381.21 | 0.17 | 0.15 | 14.08 | |
| 6,890.00 | 0.63 | 340.99 | 6,859.47 | 95.57 | 369.35 | 381.19 | 1.19 | 0.21 | -199.30 | |
| 6,979.00 | 0.25 | 324.99 | 6,948.47 | 96.19 | 369.08 | 381.06 | 0.44 | -0.43 | -17.98 | |
| 7,068.00 | 0.13 | 175.36 | 7,037.47 | 96.25 | 368.98 | 380.97 | 0.41 | -0.13 | -168.12 | |
| 7,158.00 | 0.31 | 155.74 | 7,127.47 | 95.93 | 369.09 | 381.01 | 0.21 | 0.20 | -21.80 | |
| 7,247.00 | 0.75 | 4.49 | 7,216.47 | 96.29 | 369.23 | 381.22 | 1.16 | 0.49 | -169.94 | |
| 7,335.00 | 0.63 | 4.49 | 7,304.46 | 97.35 | 369.31 | 381.53 | 0.14 | -0.14 | 0.00 | |
| 7,424.00 | 0.38 | 22.86 | 7,393.46 | 98.11 | 369.47 | 381.84 | 0.33 | -0.28 | 20.64 | |
| 7,511.00 | 0.25 | 52.24 | 7,480.45 | 98.49 | 369.73 | 382.17 | 0.23 | -0.15 | 33.77 | |
| 7,600.00 | 0.25 | 90.36 | 7,569.45 | 98.61 | 370.08 | 382.54 | 0.18 | 0.00 | 42.83 | |
| 7,688.00 | 0.31 | 110.49 | 7,657.45 | 98.52 | 370.49 | 382.93 | 0.13 | 0.07 | 22.88 | |
| 7,776.00 | 0.69 | 111.36 | 7,745.45 | 98.25 | 371.21 | 383.57 | 0.43 | 0.43 | 0.99 | |
| 7,863.00 | 0.75 | 120.11 | 7,832.44 | 97.77 | 372.19 | 384.43 | 0.14 | 0.07 | 10.06 | |
| 7,953.00 | 1.19 | 133.86 | 7,922.43 | 96.83 | 373.37 | 385.38 | 0.55 | 0.49 | 15.28 | |
| 8,040.00 | 1.75 | 137.99 | 8,009.40 | 95.21 | 374.91 | 386.55 | 0.65 | 0.64 | 4.75 | |
| 8,130.00 | 1.75 | 140.99 | 8,099.36 | 93.12 | 376.70 | 387.86 | 0.10 | 0.00 | 3.33 | |
| 8,219.00 | 1.94 | 144.86 | 8,188.31 | 90.84 | 378.42 | 389.06 | 0.26 | 0.21 | 4.35 | |
| 8,308.00 | 1.63 | 138.99 | 8,277.27 | 88.65 | 380.12 | 390.26 | 0.40 | -0.35 | -6.60 | |
| 8,398.00 | 1.38 | 134.24 | 8,367.24 | 86.93 | 381.73 | 391.48 | 0.31 | -0.28 | -5.28 | |

Anadarko Petroleum Corp

Survey Report

| | | | |
|------------------|------------------------------------|-------------------------------------|--|
| Company: | US ROCKIES REGION PLANNING | Local Co-ordinate Reference: | Well NBU 1022-114BS |
| Project: | UTAH - UTM (feet), NAD27, Zone 12N | TVD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Site: | UINTAH_NBU 1022-11 PAD | MD Reference: | 15' RKB + 5105' GL @ 5120.00ft (Xtreme 12) |
| Well: | NBU 1022-114BS | North Reference: | True |
| Wellbore: | Wellbore #1 | Survey Calculation Method: | Minimum Curvature |
| Design: | NBU 1022-114BS ACTUAL | Database: | edmp |

Survey

| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N-S (ft) | +E-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
|-------------------------|-----------------|-------------|---------------------|-----------|-----------|-----------------------|-------------------------|------------------------|-----------------------|
| 8,505.00 | 2.11 | 150.55 | 8,474.19 | 84.31 | 383.63 | 392.78 | 0.82 | 0.68 | 15.24 |
| LAST MWD SURVEY | | | | | | | | | |
| 8,555.00 | 2.11 | 150.55 | 8,524.15 | 82.71 | 384.53 | 393.33 | 0.00 | 0.00 | 0.00 |
| PROJECTION TO TD | | | | | | | | | |

Design Annotations

| Measured Depth (ft) | Vertical Depth (ft) | Local Coordinates | | Comment |
|---------------------|---------------------|-------------------|-----------|------------------|
| | | +N-S (ft) | +E-W (ft) | |
| 2,285.00 | 2,261.56 | 84.73 | 276.34 | TIE ON |
| 2,375.00 | 2,350.03 | 88.66 | 292.38 | FIRST MWD SURVEY |
| 8,505.00 | 8,474.19 | 84.31 | 383.63 | LAST MWD SURVEY |
| 8,555.00 | 8,524.15 | 82.71 | 384.53 | PROJECTION TO TD |

| | | |
|-------------------|--------------------|-------------|
| Checked By: _____ | Approved By: _____ | Date: _____ |
|-------------------|--------------------|-------------|