

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. <b>U-0285A</b>
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator <b>EOG RESOURCES, INC</b>		7. If Unit or CA Agreement, Name and No. <b>Chapita Wells Unit</b>
3a. Address <b>1060 EAST HIGHWAY 40 VERNAL, UT 84078</b>		8. Lease Name and Well No. <b>Chapita Wells Unit 1290-25</b>
3b. Phone No. (include area code) <b>435-781-9111</b>		9. API Well No. <b>43-047-39471</b>
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface <b>637650 142' FNL &amp; 2478' FEL (NWNE) 40.013886 LAT 109.387750 LON</b> At proposed prod. zone <b>Same 4430340Y 40.013942 -109.387164</b>		10. Field and Pool, or Exploratory <b>Natural Buttes/Mesaverde</b>
14. Distance in miles and direction from nearest town or post office* <b>50.5 miles south of Vernal, Utah</b>		11. Sec., T. R. M. or Blk. and Survey or Area <b>Sec. 25-T9S-R22E, S.L.B.&amp;M.</b>
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) <b>142' Lease line</b>	16. No. of acres in lease <b>1800</b>	17. Spacing Unit dedicated to this well <b>Suspended</b>
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. <b>950'</b>	19. Proposed Depth <b>9280'</b>	20. BLM/BIA Bond No. on file <b>NM2308</b>
21. Elevations (Show whether DF, KDB, RT, GL, etc.) <b>5048'</b>	22. Approximate date work will start*	23. Estimated duration <b>45 days</b>

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature	Name (Printed/Typed) <b>Mary A. Maestas</b>	Date <b>08/02/2007</b>
Title <b>Regulatory Assistant</b>		
Approved by (Signature)	Name (Printed/Typed) <b>BRADLEY G. HILL</b>	Date <b>08-09-07</b>
Title <b>ENVIRONMENTAL MANAGER</b>		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.


\*(Instructions on page 2)

**Federal Approval of this  
Action is Necessary**

**RECEIVED  
AUG 06 2007**

**DIV. OF OIL, GAS & MINING**

T9S, R22E, S.L.B.&M.



EOG RESOURCES, INC.


Well location, CWU #1290-25, located as shown in the NW 1/4 NE 1/4 of Section 25, T9S, R22E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION


BENCH MARK 20EAM LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



LEGEND:

- $\perp$  = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)  
 LATITUDE =  $40^{\circ}00'49.99''$  (40.013886)  
 LONGITUDE =  $109^{\circ}23'15.90''$  (109.387750)  
 (NAD 27)  
 LATITUDE =  $40^{\circ}00'50.11''$  (40.013919)  
 LONGITUDE =  $109^{\circ}23'13.45''$  (109.387069)

UNTAH ENGINEERING & LAND SURVEYING  
 85 SOUTH 200 EAST - VERNAL, UTAH 84078  
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 08-04-06	DATE DRAWN: 08-08-06
PARTY G.S. J.R. C.H.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE EOG RESOURCES, INC.	

**EIGHT POINT PLAN**

**CHAPITA WELLS UNIT 1290-25**  
**NW/NE, SEC. 25, T9S, R22E, S.L.B.&M..**  
**UINTAH COUNTY, UTAH**

**1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:**

<b>FORMATION</b>	<b>DEPTH (KB)</b>
Green River FM	1,579'
Wasatch	4,647'
Chapita Wells	5,212'
Buck Canyon	5,887'
North Horn	6,618'
KMV Price River	6,910'
KMV Price River Middle	7,785'
KMV Price River Lower	8,558'
Sego	9,080'

Estimated TD: **9,280' or 200'± below Sego top**

**Anticipated BHP: 5,066 Psig**

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

**3. PRESSURE CONTROL EQUIPMENT:**

Production Hole – 5000 Psig  
BOP schematic diagrams attached.

**4. CASING PROGRAM:**

	<b><u>HOLE SIZE</u></b>	<b><u>INTERVAL</u></b>	<b><u>SIZE</u></b>	<b><u>WEIGHT</u></b>	<b><u>GRADE</u></b>	<b><u>THREAD</u></b>	<b><u>RATING FACTOR</u></b>		
							<b><u>COLLAPSE</u></b>	<b><u>BURST</u></b>	<b><u>TENSILE</u></b>
<b>Conductor:</b>	17 ½"	0' – 45'	13 ⅜"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
<b>Surface</b>	12-1/4"	45' – 2,300'KB±	9-⅝"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
<b>Production:</b>	7-7/8"	2,300'± – TD	4-½"	11.6#	N-80	LTC	6350 PSI	7780 Psi	223,000#

**Note:** 12-1/4" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone. **All casing will be new or inspected.**

**5. Float Equipment:**

**Surface Hole Procedure (0' - 2300'±)**

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5<sup>th</sup> joint to surface. (15 total)

**EIGHT POINT PLAN**

**CHAPITA WELLS UNIT 1290-25**  
**NW/NE, SEC. 25, T9S, R22E, S.L.B.&M.**  
**UINTAH COUNTY, UTAH**

**Float Equipment: (Cont'd)**

**Production Hole Procedure (2300'± - TD):**

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-1/2", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2<sup>nd</sup> joint.

**6. MUD PROGRAM**

**Surface Hole Procedure (Surface - 2300'±):**

Air/air mist or aerated water.

**Production Hole Procedure (2300'± - TD):** Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

**2300'± - TD** A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

**7. VARIANCE REQUESTS:**

**Reference:** Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

**8. EVALUATION PROGRAM:**

**Logs:** Mud log from base of surface casing to TD.  
**Cased-hole Logs:** Cased-hole logs will be run in lieu of open-hole logs consisting of the following:  
**Cement Bond / Casing Collar Locator and Pulsed Neutron**

**EIGHT POINT PLAN**

**CHAPITA WELLS UNIT 1290-25**  
**NW/NE, SEC. 25, T9S, R22E, S.L.B.&M..**  
**UINTAH COUNTY, UTAH**

**9. CEMENT PROGRAM:**

**Surface Hole Procedure (Surface - 2300'±):**

**Lead:** Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl<sub>2</sub>, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft<sup>3</sup>/sk. yield, 23 gps water.

**Tail:** Class "G" cement with 2% CaCl<sub>2</sub>, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft<sup>3</sup>/sk., 5.2 gps water.

**Top Out:** As necessary with Class "G" cement with 2% CaCl<sub>2</sub>, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft<sup>3</sup>/sk., 5.2 gps water.

**Note:** Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

**Production Hole Procedure (2300'± - TD)**

**Lead:** 128 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft<sup>3</sup>/sk., 24.5 gps water.

**Tail:** 910 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft<sup>3</sup>/sk., 5.9 gps water.

**Note:** The above number of sacks is based on gauge-hole calculation.  
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.  
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.  
**Final Cement volumes will be based upon gauge-hole plus 45% excess.**

**10. ABNORMAL CONDITIONS:**

**Surface Hole (Surface - 2300'±):**

Lost circulation

**Production Hole (2300'± - TD):**

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

**EIGHT POINT PLAN**

**CHAPITA WELLS UNIT 1290-25**  
**NW/NE, SEC. 25, T9S, R22E, S.L.B.&M.**  
**UINTAH COUNTY, UTAH**

**11. STANDARD REQUIRED EQUIPMENT:**


- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

**12. HAZARDOUS CHEMICALS:**

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

**EOG RESOURCES 11" 5,000 PSI W.P. BOP CONFIGURATION**



**EOG RESOURCES CHOKE MANIFOLD CONFIGURATION  
W/ 5,000 PSI WP VALVES**

PAGE 2 OF 2



**Testing Procedure:**

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.  
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, whichever is greater.
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.



***Chapita Wells Unit 1290-25  
NWNE, Section 25, T9S, R22E  
Uintah County, Utah***

***SURFACE USE PLAN***

The well pad is approximately 325 feet long with a 246-foot width, containing 1.84 acres more or less. The well access road is approximately 1056 feet long with a 40-foot right-of-way, disturbing approximately .97 acre. New surface disturbance associated with access road and the well pad is estimated to be approximately 2.81 acres. The pipeline is approximately 1370 feet long with a 40-foot right-of-way, disturbing approximately 1.26 acres.

***1. EXISTING ROADS:***

- A. See attached Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 50.5 miles south of Vernal, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary.

***2. PLANNED ACCESS ROAD:***

- A. The access road will be approximately 1056' in length, with culverts installed as construction dictates. See attached Topo B.
- B. The access road has a 40-foot ROW w/18 foot running surface.
- C. Maximum grade of the new access road will be 8 percent.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.

- I. A 40-foot permanent right-of-way is requested. No surfacing material will be used.
- J. No additional storage areas will be needed for storing equipment, stockpiling, or vehicle parking.

All travel will be confined to existing access road rights-of-way.

New or reconstructed roads will be centerlined – flagged at time of location staking. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction.

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed, safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 40-foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the roadbed block the drainages. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

Traveling off the 40-foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

**An off-lease right-of-way is not required. The entire length of the proposed access road is located within Federal Lease # U-0285A.**

**3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:**

See attached TOPO map "C" for the location of wells within a one-mile radius.

**4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:**

**A. On Well Pad**

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400-bbl vertical tanks and attaching piping.
2. Gas gathering lines – A 4” gathering line will be buried from dehy to the edge of the location.

**B. Off Well Pad**

1. Proposed pipeline will transport natural gas.
2. The pipeline will be a permanent feeder line.
3. The length of the proposed pipeline is 1370' x 40'. The proposed pipeline leaves the western edge of the well pad (Lease U-0285A) proceeding in an easterly direction for an approximate distance of 1370' tying into a proposed pipeline for the Chapita Wells Unit 931-25 located in the NWNE of Section 25, T9S, R22E (Lease U-0285A). Pipe will be 4” NOM, 0.156 wall, Grade X42, Zap-Lock, electric weld with a 35 mil X-Tru coating.
4. Proposed pipeline will be a 4” OD steel, zap-lok line laid on the surface
5. Proposed pipeline will be laid on surface.
6. An off-lease right-of-way is not required. The entire length of the proposed pipeline is located within Federal Lease # U-0285A.
7. The proposed pipeline route begins in the NWNE of Section 25, T9S, R22E, proceeding easterly for an approximate distance of 1370' to the NWNE of Section 25, T9S, R22E.
8. Pipeline will be coupled using the Zap lock method. No additional off-pad facilities will be required.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All facilities will be painted with Carlsbad Canyon or Covert Green.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

**5. LOCATION AND TYPE OF WATER SUPPLY:**

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/or Bonanza Power Plant water source in Sec 26, T8S, R23E, Uintah County, UT

(State Water Right # 49-225(A31368)). Water will be hauled by a licensed trucking company.

- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

**6. SOURCE OF CONSTRUCTION MATERIALS:**

- A. All construction material for this pipeline will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

**7. METHODS OF HANDLING WASTE DISPOSAL:**

**A. METHODS AND LOCATION**

- 1. Cuttings will be confined in the reserve pit.
  - 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
  - 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
  - 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, CWU 550-30N SWD or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
  - 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit, through natural or artificial methods, or removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with felt, and a 16-millimeter plastic liner. Sufficient bedding (i.e. weed free straw, or hay; felt; polyswell or soil) will be used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it

in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well. Furthermore, extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will not be used, produced, stored, transported, or disposed of in association with the drilling, testing or completion of the well.

**8. ANCILLARY FACILITIES:**

None anticipated.

**9. WELL SITE LAYOUT:**

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the southeast corner of the location. The flare pit will be located downwind of the prevailing wind direction on the south side of the location, a minimum of 100 feet from the wellhead and 30 feet from the reserve pit fence.

The stockpiled pit topsoil (first six inches) will be stored separate from the location topsoil west of pit corner B. The stockpiled location topsoil will be stored in a location providing easy access for interim reclamation and protect of the topsoil. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the east.

The corners of the well pad will be rounded off as needed to minimize excavation.

**FENCING REQUIREMENTS:**

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently counted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

**10. PLANS FOR RECLAMATION OF THE SURFACE:**

**A. Interim Reclamation (Producing Location)**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours – See attached Figure #3. The reserve pit will be reclaimed within 90 days from the date of the well completion, or as soon as environmental conditions allow. Before any dirt takes place, the reserve pit must be completely dry and free of all foreign obstacles.

The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

<b>Seed Mixture</b>	<b>Drilled Rate (lbs./acre PLS*)</b>
HyCrest Wheatgrass	6.0
Needle and Threadgrass	6.0

\*Pure live seed (PLS) formula: percent of purity of seed mixture times percent germination of seed mixture equals portion of seed mixture that is PLS.

**B. Dry Hole/Abandoned Location**

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriated surface rehabilitation conditions of approval.

<b>Seed Mixture</b>	<b>Drilled Rate (lbs./acre PLS*)</b>
Wyoming Big Sage	3.0
Shadscale	3.0
Needle and Threadgrass	3.0
HyCrest Wheatgrass	1.0
Scarlet Globe Mallow	1.0

\*Pure live seed (PLS) formula: percent of purity of seed mixture times percent germination of seed mixture equals portion of seed mixture that is PLS.

**11. SURFACE OWNERSHIP:**

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

**Bureau of Land Management**

**12. OTHER INFORMATION:**

- A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:
- Whether the materials appear eligible for the National Register of Historic Places;
  - The mitigation measures the operator will likely have to undertake before the site can be used.
  - A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)
- D. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to

Drill” will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

A cultural resources survey was conducted and submitted by Montgomery Archaeological Consultants on 9/19/2006. A paleontological survey was conducted and submitted by Intermountain Paleo on 10/6/2006.

**Additional Surface Stipulations:**

None.

***LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:***

**PERMITTING AGENT**

Mary A. Maestas  
EOG Resources, Inc.  
P.O. Box 1815  
Vernal, UT 84078  
(435) 781-9111

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

The operator or his/her contractor shall contact the BLM office at (435) 781-4400 forty-eight (48) hours prior to construction activities.


**CERTIFICATION:**

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the Chapita Wells Unit 1290-25 Well, located in the NWNE, of Section 25, T9S, R22E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

August 2, 2007


Date

  
Mary A. Maestas, Regulatory Assistant

EOG RESOURCES, INC.

LOCATION LAYOUT FOR


CWU #1290-25  
SECTION 25, T9S, R22E, S.L.B.&M.  
142' FNL 2478' FEL



SCALE: 1" = 50'  
DATE: 08-08-06  
Drawn By: C.H.

NOTE:

Flare Pit is to be located a min. of 100' from the Well Head.



NOTES:

Elev. Ungraded Ground At Loc. Stake = 5048.0'  
FINISHED GRADE ELEV. AT LOC. STAKE = 5045.4'

FIGURE #1

EOG RESOURCES, INC.


FIGURE #2

TYPICAL CROSS SECTIONS FOR

CWU #1290-25  
SECTION 25, T9S, R22E, S.L.B.&M.  
142' FNL 2478' FEL

1" = 20'  
X-Section  
Scale  
1" = 50'

DATE: 08-08-06  
Drawn By: C.H.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

\* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,610 Cu. Yds.
Remaining Location	= 7,430 Cu. Yds.
<b>TOTAL CUT</b>	<b>= 9,040 CU.YDS.</b>
<b>FILL</b>	<b>= 5,770 CU.YDS.</b>

EXCESS MATERIAL	= 3,270 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,270 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 788-1017

# EOG RESOURCES, INC.

## CWU #1290-25

LOCATED IN UINTAH COUNTY, UTAH  
SECTION 25, T9S, R22E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTH



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS


CAMERA ANGLE: NORTHWESTERLY



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

<b>LOCATION PHOTOS</b>			<b>08</b>	<b>10</b>	<b>06</b>	<b>PHOTO</b>
			MONTH	DAY	YEAR	
TAKEN BY: J.R.	DRAWN BY: A.A.	REVISED: 00-00-00				

Since 1964



**PROPOSED LOCATION:  
CWU #1290-25**

**T9S  
T10S**

**LEGEND:**

 **PROPOSED LOCATION**




**EOG RESOURCES, INC.**

**CWU #1290-25  
SECTION 25, T9S, R22E, S.L.B.&M.  
142' FNL 2478' FEL**

**UEIS** **Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC MAP** **08 10 06**  
MONTH DAY YEAR  
SCALE: 1:100,000 DRAWN BY: A. A. REVISED: 00-00-00 **A TOPO**





**PROPOSED LOCATION:  
CWU #1290-25**

**R  
22  
E**

**R  
23  
E**

**T9S**

**LEGEND:**

- ∅ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED



**EOG RESOURCES, INC.**


**CWU #1290-25  
SECTION 25, T9S, R22E, S.L.B.&M.  
142' FNL 2478' FEL**



**Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC MAP** 08 10 06  
MONTH DAY YEAR  
SCALE: 1" = 2000' DRAWN BY: A. A. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 1370' +/-

**LEGEND:**

-  PROPOSED ACCESS ROAD
-  EXISTING PIPELINE
-  PROPOSED PIPELINE
-  PROPOSED PIPELINE (SERVICING OTHER WELLS)

**EOG RESOURCES, INC.**

**CWU #1290-25**  
**SECTION 25, T9S, R22E, S.L.B.&M.**  
**142' FNL 2478' FEL**



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**TOPOGRAPHIC**  
**MAP**

<b>08</b>	<b>10</b>	<b>06</b>
MONTH	DAY	YEAR

SCALE: 1" = 1000' DRAWN BY: A.A. REVISED: 00-00-00

**D**  
**TOPO**

**WORKSHEET  
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 08/06/2007

API NO. ASSIGNED: 43-047-39471

WELL NAME: CWU 1290-25  
 OPERATOR: EOG RESOURCES INC ( N9550 )  
 CONTACT: MARY MAESTAS

PHONE NUMBER: 435-781-9111

PROPOSED LOCATION:

NWNE 25 090S 220E  
 SURFACE: 0142 FNL 2478 FEL  
 BOTTOM: 0142 FNL 2478 FEL  
 COUNTY: UINTAH  
 LATITUDE: 40.01394 LONGITUDE: -109.3872  
 UTM SURF EASTINGS: 637650 NORTHINGS: 4430340  
 FIELD NAME: NATURAL BUTTES ( 630 )

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal  
 LEASE NUMBER: U-0285A  
 SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: MVRD  
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]  
(No. NM2308 )
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit  
(No. 49-225 )
- RDCC Review (Y/N)  
(Date: \_\_\_\_\_ )
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)

LOCATION AND SITING:


- R649-2-3.
- Unit: CHAPITA WELLS *OK*
- R649-3-2. General  
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit  
Board Cause No: 179-8  
Eff Date: 8-10-1999  
Siting: Suspends General Siting
- R649-3-11. Directional Drill

COMMENTS: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

STIPULATIONS: 1-Federal Approval  
2-OIL SHALE  
 \_\_\_\_\_  
 \_\_\_\_\_

T9S R22E

T9S R23E




CAUSE: 179-8 / 8-10-1999  
**CHAPITA WELLS UNIT**  
**NATURAL BUTTES FIELD**

OPERATOR: EOG RESOURCES INC (N9550)  
 SEC: 24,25 T.9S R. 22E  
 FIELD: NATURAL BUTTES (630)  
 COUNTY: UINTAH  
 CAUSE: 179-8 / 8-10-1999

- Field Status**
- ABANDONED
  - ACTIVE
  - COMBINED
  - INACTIVE
  - PROPOSED
  - STORAGE
  - TERMINATED

- Unit Status**
- EXPLORATORY
  - GAS STORAGE
  - NF PP OIL
  - NF SECONDARY
  - PENDING
  - PI OIL
  - PP GAS
  - PP GEOTHERML
  - PP OIL
  - SECONDARY
  - TERMINATED

- Wells Status**
- GAS INJECTION
  - GAS STORAGE
  - LOCATION ABANDONED
  - NEW LOCATION
  - PLUGGED & ABANDONED
  - PRODUCING GAS
  - PRODUCING OIL
  - SHUT-IN GAS
  - SHUT-IN OIL
  - TEMP. ABANDONED
  - TEST WELL
  - WATER INJECTION
  - WATER SUPPLY
  - WATER DISPOSAL
  - DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA MASON  
 DATE: 8-AUGUST-2007



JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil Gas and Mining

JOHN R. BAZA  
Division Director

August 9, 2007

EOG Resources, Inc.  
1060 East Highway 40  
Vernal, UT 84078

Re: Chapita Wells Unit 1290-25 Well, 142' FNL, 2478' FEL, NW NE, Sec. 25, T. 9 South,  
R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39471.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Uintah County Assessor  
Bureau of Land Management, Vernal Office

**Operator:** EOG Resources, Inc.  
**Well Name & Number** Chapita Wells Unit 1290-25  
**API Number:** 43-047-39471  
**Lease:** U-0285A

**Location:** NW NE                      **Sec.** 25                      **T.** 9 South                      **R.** 22 East

### Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office      (801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>U-0285-A</b>
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME: <b>Chapita Wells Unit</b>
2. NAME OF OPERATOR: <b>EOG Resources, Inc.</b>		8. WELL NAME and NUMBER: <b>Chapita Wells Unit 1290-25</b>
3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY <b>Vernal</b> STATE <b>UT</b> ZIP <b>84078</b>		9. API NUMBER: <b>43-047-39471</b>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>142' FNL &amp; 2478' FEL 40.013886 LAT 109.387750 LON</b> QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NWNE 25 9S 22E S</b>		10. FIELD AND POOL, OR WILDCAT: <b>Natural Buttes/Mesaverde</b> COUNTY: <b>Uintah</b> STATE: <b>UTAH</b>

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start: _____  <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <b>APD Extension</b>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

**EOG Resources, Inc. requests the APD for the referenced well be extended for one year.**

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 08-04-08

By: *[Signature]*

COPY SENT TO OPERATOR

Date: 8.5.2008

Initials: KS

NAME (PLEASE PRINT) <u>Kaylene R. Gardner</u>	TITLE <u>Lead Regulatory Assistant</u>
SIGNATURE <u><i>[Signature]</i></u>	DATE <u>7/30/2008</u>

(This space for State use only)

RECEIVED

AUG - 1 2008

DIV. OF OIL, GAS & MINING

**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 43-047-39471  
**Well Name:** CHAPITA WELLS UNIT 1290-25  
**Location:** 142 FNL - 2478 FEL (NWNE), SECTION 25, T9S, R22E S.L.B.&M  
**Company Permit Issued to:** EOG RESOURCES, INC.  
**Date Original Permit Issued:** 8/9/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes  No

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes  No


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes  No

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes  No

Has the approved source of water for drilling changed? Yes  No

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes  No

Is bonding still in place, which covers this proposed well? Yes  No

  
Signature

7/30/2008

Date

Title: Lead Regulatory Assistant

Representing: EOG Resources, Inc.

RECEIVED

AUG - 1 2008

DIV. OF OIL, GAS & MINING

RECEIVED  
VERNAL FIELD OFFICE

2007 AUG -3 PH 12:20

FORM APPROVED  
OMB No. 1004-0137  
Expires March 31, 2007

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
BUREAU OF LAND MGMT.

APPLICATION FOR PERMIT TO DRILL OR REENTER

5a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7. If Unit or CA Agreement, Name and No. <b>Chapita Wells Unit</b>
5b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		8. Lease Name and Well No. <b>Chapita Wells Unit 1290-25</b>
2. Name of Operator <b>EOG RESOURCES, INC</b>		9. API Well No. <b>43 0A7 39A71</b>
3a. Address <b>1060 EAST HIGHWAY 40 VERNAL, UT 84078</b>	3b. Phone No. (include area code) <b>435-781-9111</b>	10. Field and Pool, or Exploratory <b>Natural Buttes/Mesaverde</b>
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface <b>142' FNL &amp; 2478' FEL (NWNE) 40.013886 LAT 109.387750 LON</b> At proposed prod. zone <b>Same</b>		11. Sec., T. R. M. or Blk. and Survey or Area <b>Sec. 25-T9S-R22E, S.L.B.&amp;M.</b>
14. Distance in miles and direction from nearest town or post office* <b>50.5 miles south of Vernal, Utah</b>		12. County or Parish <b>Uintah County</b>
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) <b>142' Lease line</b>		17. Spacing Unit dedicated to this well <b>Suspended</b>
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. <b>950'</b>		20. BLM/BIA Bond No. on file <b>NM2308</b>
21. Elevations (Show whether DF, KDB, RT, GL, etc.) <b>5048'</b>		23. Estimated duration <b>45 days</b>

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, must be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the BLM.

25. Signature <i>Mary A. Maestas</i>	Name (Printed/Typed) <b>Mary A. Maestas</b>	Date <b>08/02/2007</b>
Title <b>Regulatory Assistant</b>		
Approved by (Signature) <i>Jerry Lewicki</i>	Name (Printed/Typed) <b>Jerry Lewicki</b>	Date <b>7-21-2008</b>
Title <b>Assistant Field Manager Lands &amp; Mineral Resources</b>		
Office <b>VERNAL FIELD OFFICE</b>		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

**CONDITIONS OF APPROVAL ATTACHED**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on page 2)

UDOGM

NOTICE OF APPROVAL  
RECEIVED  
AUG 04 2008

DIV. OF OIL, GAS & MINING

NOS 8/28/06  
06 BM 2550A




**UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE**

**170 South 500 East**

**VERNAL, UT 84078**

**(435) 781-4400**



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

<b>Company:</b>	<b>EOG Resources, Inc.</b>	<b>Location:</b>	<b>NWNE, Sec. 25, T9S, R22E</b>
<b>Well No:</b>	<b>Chapita Wells Unit 1290-25</b>	<b>Lease No:</b>	<b>UTU-0285A</b>
<b>API No:</b>	<b>43-047-39471</b>	<b>Agreement:</b>	<b>Chapita Wells Unit</b>

<b>Title</b>	<b>Name</b>	<b>Office Phone Number</b>	<b>Cell Phone Number</b>
Petroleum Engineer:	Matt Baker	(435) 781-4490	(435) 828-4470
Petroleum Engineer:	Michael Lee	(435) 781-4432	(435) 828-7875
Petroleum Engineer:	James Ashley	(435) 781-4470	(435) 828-7874
Petroleum Engineer:	Ryan Angus	(435) 781-4430	(435) 828-7368
Supervisory Petroleum Technician:	Jamie Sparger	(435) 781-4502	(435) 828-3913
Supervisory NRS:	Karl Wright	(435) 781-4484	(435) 828-7381
NRS/Enviro Scientist:	Holly Villa	(435) 781-4404	(435) 828-3544
NRS/Enviro Scientist:	James Hereford	(435) 781-3412	
NRS/Enviro Scientist:	Chuck Macdonald	(435) 781-4441	(435) 828-7481
NRS/Enviro Scientist:	Dan Emmett	(435) 781-3414	
NRS/Enviro Scientist:	Paul Percival	(435) 781-4493	
NRS/Enviro Scientist:	Michael Cutler	(435) 781-3401	(435) 828-3546
NRS/Enviro Scientist:	Anna Figueroa	(435) 781-3407	(435) 828-3548
NRS/Enviro Scientist:	Verlyn Pindell	(435) 781-3402	(435) 828-3547
NRS/Enviro Scientist:	Darren Williams	(435) 781-4447	(435) 828-4029
NRS/Enviro Scientist:	Nathan Packer	(435) 781-3405	(435) 828-3545

**Fax: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	- Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	- Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)***

- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

**SITE SPECIFIC COAs:**

- Bury pipeline at all low water crossings.
- Permission from an authorized BLM representative will be required if construction or other operations occur during wet conditions that would lead to excessive rutting.
- Permission to clear all wildlife stipulations will only be approved by the BLM wildlife biologist during the specific timing for the species potentially affected by this action.

Culverts and gravel may be installed as needed

***DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)***

**SITE SPECIFIC DOWNHOLE COAs:**

- Production casing cement shall be brought up and into the surface casing. The minimum cement top is 200 ft above the surface casing shoe. COA specification is consistent with operators performance standard stated in APD.
- A variance is granted for Onshore Order #2 Drilling Operations III. E. "Blooie line discharge 100 feet from well bore and securely anchored" Blooie line can be 75 feet.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.

- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT\_VN\_Wellogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

## **OPERATING REQUIREMENT REMINDERS:**

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location (¼¼, Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.

- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.

- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

# DIVISION OF OIL, GAS AND MINING

## **SPUDDING INFORMATION**

Name of Company: EOG RESOURCES INC

Well Name: CWU 1290-25

Api No: 43-047-39471 Lease Type: FEDERAL

Section 25 Township 09S Range 22E County UINTAH

Drilling Contractor ROCKY MOUNTAIN DRILLING RIG # RATHOLE

## **SPUDDED:**

Date 11/04/08

Time 9:30 AM

How DRY

**Drilling will Commence:** \_\_\_\_\_

Reported by JERRY BARNES

Telephone # (435) 828-1720

Date 11/04/08 Signed CHD

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: EOG RESOURCES Operator Account Number: N 9550  
 Address: 1060 East Highway 40  
city VERNAL  
state UT zip 84078 Phone Number: (435) 781-9145

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39471	CHAPITA WELLS UNIT 1290-25		NWNE	25	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>AB</i>	99999	<i>13650</i>	11/4/2008		<i>11/10/08</i>		
Comments: <u>MESAVERDE</u>							

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39512	CHAPITA WELLS UNIT 1335-15		NWNE	15	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>AB</i>	99999	<i>13650</i>	11/6/2008		<i>11/10/08</i>		
Comments: <u>MESAVERDE</u> <i>PRCV=</i>							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39886	CHAPITA WELLS UNIT 1370-30		NWSE	30	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>AB</i>	99999	<i>13650</i>	11/6/2008		<i>11/10/08</i>		
Comments: <u>MESAVERDE</u>							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mickenzie Thacker

Name (Please Print)

*Mickenzie Thacker*

Signature

Operations Clerk

11/7/2008

Title

Date

(5/2000)

**RECEIVED**

NOV 10 2008

DIV. OF OIL, GAS & MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*

5. Lease Serial No.  
UTU0285A

6. If Indian, Allottee or Tribe Name

**SUBMIT IN TRIPLICATE - Other instructions on reverse side.**

7. If Unit or CA/Agreement, Name and/or No.  
CHAPITA WELLS

8. Well Name and No.  
CHAPITA WELLS UNIT 1290-25

9. API Well No.  
43-047-39471

10. Field and Pool, or Exploratory  
NATURAL BUTTES

11. County or Parish, and State  
UINTAH COUNTY, UT

1. Type of Well  
 Oil Well  Gas Well  Other

2. Name of Operator  
EOG RESOURCES, INC. Contact: MICKENZIE THACKER  
E-Mail: MICKENZIE\_THACKER@EOGRESOURCES.COM

3a. Address  
1060 E. HWY 40  
VERNAL, UT 84078

3b. Phone No. (include area code)  
Ph: 435-781-9145

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
Sec 25 T9S R22E NWNE 142FNL 2478FEL  
40.01389 N Lat, 109.38775 W Lon

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION				
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off	
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity	
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Well Spud	
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon		
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal		

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The referenced well was spud on 11/4/2008.

14. I hereby certify that the foregoing is true and correct.  
**Electronic Submission #64552 verified by the BLM Well Information System  
For EOG RESOURCES, INC., sent to the Vernal**

Name (Printed/Typed) MICKENZIE THACKER Title OPERATIONS CLERK

Signature  Date 11/07/2008

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved By \_\_\_\_\_ Title \_\_\_\_\_ Date \_\_\_\_\_

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office \_\_\_\_\_

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\***

**RECEIVED**

**NOV 12 2008**

**DIV. OF OIL, GAS & MINING**

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*

5. Lease Serial No.  
UTU0285A

6. If Indian, Allottee or Tribe Name

**SUBMIT IN TRIPLICATE - Other instructions on reverse side.**

7. If Unit or CA/Agreement, Name and/or No.  
CHAPITA WELLS

8. Well Name and No.  
CHAPITA WELLS UNIT 1290-25

9. API Well No.  
43-047-39471

10. Field and Pool, or Exploratory  
NATURAL BUTTES

11. County or Parish, and State  
UINTAH COUNTY, UT

1. Type of Well  
 Oil Well  Gas Well  Other

2. Name of Operator  
EOG RESOURCES, INC. Contact: MARY A. MAESTAS  
E-Mail: mary\_maestas@eogresources.com

3a. Address  
600 17TH STREET SUITE 1000N  
DENVER, CO 80202

3b. Phone No. (include area code)  
Ph: 303-824-5526

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
Sec 25 T9S R22E NWNE 142FNL 2478FEL  
40.01389 N Lat, 109.38775 W Lon

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Production Start-up
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamatation, have been completed, and the operator has determined that the site is ready for final inspection.)

The referenced well was turned to sales on 2/1/2009. Please see the attached operations summary report for drilling and completion operations performed on the subject well.


14. I hereby certify that the foregoing is true and correct.

**Electronic Submission #66844 verified by the BLM Well Information System  
For EOG RESOURCES, INC., sent to the Vernal**

Name (Printed/Typed) MARY A. MAESTAS

Title REGULATORY ASSISTANT

Signature



Date 02/02/2009

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved By \_\_\_\_\_

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**RECEIVED**

**\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED FEB 09 2009**

## WELL CHRONOLOGY REPORT

Report Generated On: 02-02-2009

<b>Well Name</b>	CWU 1290-25	<b>Well Type</b>	DEVG	<b>Division</b>	DENVER
<b>Field</b>	CHAPITA DEEP	<b>API #</b>	43-047-39471	<b>Well Class</b>	COMP
<b>County, State</b>	UINTAH, UT	<b>Spud Date</b>	12-20-2008	<b>Class Date</b>	
<b>Tax Credit</b>	N	<b>TVD / MD</b>	9,280/ 9,280	<b>Property #</b>	059659
<b>Water Depth</b>	0	<b>Last CSG</b>	0.0	<b>Shoe TVD / MD</b>	0/ 0
<b>KB / GL Elev</b>	5,058/ 5,045				
<b>Location</b>	Section 25, T9S, R22E, NWNE, 142 FNL & 2478 FEL				

<b>Event No</b>	1.0	<b>Description</b>	DRILL & COMPLETE		
<b>Operator</b>	BOG RESOURCES, INC	<b>WI %</b>	55.686	<b>NRI %</b>	47.671

<b>AFE No</b>	304217	<b>AFE Total</b>	1,822,900	<b>DHC / CWC</b>	880,700/ 942,200
<b>Rig Contr</b>	ELENBURG	<b>Rig Name</b>	ELENBURG #29	<b>Start Date</b>	09-05-2007
<b>09-05-2007</b>	<b>Reported By</b>	SHARON CAUDILL			
<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Daily Total</b>	\$0
<b>Cum Costs: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Well Total</b>	\$0
<b>MD</b>	0	<b>TVD</b>	0	<b>Progress</b>	0
<b>Days</b>	0	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>	<b>PKR Depth : 0.0</b>	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA
			142' FNL & 2478' FEL (NW/NE)
			SECTION 25, T9S, R22E
			UINTAH COUNTY, UTAH
			LAT 40.013886, LONG 109.387750 (NAD 83)
			LAT 40.013919, LONG 109.387069 (NAD 27)
			ELENBURG #29
			OBJECTIVE: 9280' TD, MESAVERDE
			DW/GAS
			CHAPITA WELLS DEEP PROSPECT
			DD&A: CHAPITA DEEP
			NATURAL BUTTES FIELD
			LEASE: U-0285-A
			ELEVATION: 5048.0' NAT GL, 5045.4' PREP GL (DUE TO ROUNDING PREP GL WILL BE 5045') 5058' KB (13')
			BOG WI 55.6856%, NRI 47.67131%

10-24-2008      Reported By      TERRY CSERE

<b>DailyCosts: Drilling</b>	\$75,000	<b>Completion</b>	\$0	<b>Daily Total</b>	\$75,000						
<b>Cum Costs: Drilling</b>	\$75,000	<b>Completion</b>	\$0	<b>Well Total</b>	\$75,000						
<b>MD</b>	0	<b>TVD</b>	0	<b>Progress</b>	0	<b>Days</b>	0	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>	<b>PKR Depth : 0.0</b>							

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION STARTED.

10-27-2008 Reported By TERRY CSERE

<b>DailyCosts: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Daily Total</b>	\$0						
<b>Cum Costs: Drilling</b>	\$75,000	<b>Completion</b>	\$0	<b>Well Total</b>	\$75,000						
<b>MD</b>	0	<b>TVD</b>	0	<b>Progress</b>	0	<b>Days</b>	0	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>	<b>PKR Depth : 0.0</b>							

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 25% COMPLETE.

10-28-2008 Reported By TERRY CSERE

<b>DailyCosts: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Daily Total</b>	\$0						
<b>Cum Costs: Drilling</b>	\$75,000	<b>Completion</b>	\$0	<b>Well Total</b>	\$75,000						
<b>MD</b>	0	<b>TVD</b>	0	<b>Progress</b>	0	<b>Days</b>	0	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>	<b>PKR Depth : 0.0</b>							

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	ROCKED OUT.

10-29-2008 Reported By TERRY CSERE

<b>DailyCosts: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Daily Total</b>	\$0						
<b>Cum Costs: Drilling</b>	\$75,000	<b>Completion</b>	\$0	<b>Well Total</b>	\$75,000						
<b>MD</b>	0	<b>TVD</b>	0	<b>Progress</b>	0	<b>Days</b>	0	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>	<b>PKR Depth : 0.0</b>							

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	ROCKED OUT.

10-30-2008 Reported By TERRY CSERE

<b>DailyCosts: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Daily Total</b>	\$0						
<b>Cum Costs: Drilling</b>	\$75,000	<b>Completion</b>	\$0	<b>Well Total</b>	\$75,000						
<b>MD</b>	0	<b>TVD</b>	0	<b>Progress</b>	0	<b>Days</b>	0	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>	<b>PKR Depth : 0.0</b>							

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	DRILLING ROCK. SHOOTING SATURDAY.

10-31-2008 Reported By TERRY CSERE



11-07-2008 Reported By BRIAN ROW

DailyCosts: Drilling \$0 Completion \$0 Daily Total \$0  
 Cum Costs: Drilling \$75,000 Completion \$0 Well Total \$75,000

MD 60 TVD 60 Progress 0 Days 0 MW 0.0 Visc 0.0  
 Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: WORT

Start End Hrs Activity Description

11-11-2008 Reported By BRIAN ROW

DailyCosts: Drilling \$243,602 Completion \$0 Daily Total \$243,602  
 Cum Costs: Drilling \$318,602 Completion \$0 Well Total \$318,602

MD 2,322 TVD 2,322 Progress 0 Days 0 MW 0.0 Visc 0.0  
 Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: WORT

Start End Hrs Activity Description

06:00 06:00 24.0 MIRU CRAIG'S AIR RIG #3 ON 11/05/08. DRILLED 12-1/4" HOLE TO 2309' G.L. (2322' K.B.). ENCOUNTERED WATER @ 907'. FLUID DRILLED HOLE FROM 917' TO T.D. W/PARTIAL RETURNS. RAN 58 JTS (2299.74') OF 9-5/8", 36.0#, J-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 8 CENTRALIZERS SPACED MIDDLE OF SHOE JOINT AND EVERY COLLAR TILL GONE. LANDED @ 2312' KB. RAN 200' OF 1" PIPE DOWN BACK SIDE.RDMO CRAIGS RIG 3

MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 1500 PSIG. PUMPED 184 BBLS FRESH WATER & 20 BBLS GELLED WATER FLUSH AHEAD OF CEMENT. MIXED & PUMPED 250 SX (182 BBLS) OF PREMIUM LEAD CEMENT W/0.2% VARSET, 2% CALSEAL, & 2% EX-1. MIXED LEAD CEMENT @ 10.5 PPG W/YIELD OF 4.1 CF/SX.

TAILED IN W/300 SX (63 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED TAIL CEMENT TO 15.6 PPG W/YIELD OF 1.18 CFS. DISPLACED CEMENT W/174 BBLS FRESH WATER. BUMPED PLUG W/1100# @ 6:32 A.M, 11-09-2008. CHECKED FLOAT, FLOAT HELD. SHUT IN CASING VALVE. BROKE CIRCULATION 55 BBLS INTO LEAD CEMENT. LOST RETURNS 108 BBLS INTO DISPLACEMENT. REGAINED WEAK RETURNS 140 BBLS INTO DISPLACEMENT. LOST RETURNS 158 BBLS INTO DISPLACEMENT. NO CEMENT TO SURFACE.

TOP JOB #1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 100 SX (21 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. NO RETURNS. WOC 3 HRS 56 MINUTES.

TOP JOB #2: MIXED & PUMPED 100 SX (21 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. NO RETURNS. WOC 2 HRS 15 MINUTES.

TOP JOB #3: MIXED & PUMPED 50 SX (10.3 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. HOLE FILLED AND STOOD FULL. RDMO HALLIBURTON CEMENTERS.

PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.

CRAIGS RIG #3 TOOK SURVEYS WHILE DRILLING HOLE @ 1218'-1.0 DEGREE & 2298'-2.5 DEGREE.

CONDUCTOR LEVEL RECORD: PS= 89.7 OPS= 89.9 VDS= 90.0 MS= 90.0.

9 5/8 CASING LEVEL RECORD: PS= 89.8 OPS= 90.0 VDS= 89.9 MS= 90.0.

BRIAN ROW EMAILED NOTIFICATION TO BLM OF THE SURFACE CASING & CEMENT JOB ON 11/7/2008 @ 11:05 A.M.

<b>12-20-2008</b>	<b>Reported By</b>	DUANE C WINKLER									
<b>DailyCosts: Drilling</b>	\$50,256	<b>Completion</b>	\$0	<b>Daily Total</b>	\$50,256						
<b>Cum Costs: Drilling</b>	\$368,858	<b>Completion</b>	\$0	<b>Well Total</b>	\$368,858						
<b>MD</b>	2,458	<b>TVD</b>	2,458	<b>Progress</b>	136	<b>Days</b>	1	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>			<b>Perf :</b>	<b>PKR Depth : 0.0</b>						
<b>Activity at Report Time:</b> DRILLING @ 2458'											

Start	End	Hrs	Activity Description
06:00	07:00	1.0	RDRT
07:00	07:30	0.5	THIRD PARTY SAFETY MEETING
07:30	15:30	8.0	MOVE RIG AND RURT
15:30	19:30	4.0	NIPPLE UP BOPE. DAY WORK STARTED 12/19/2008 @ 15:30 HRS.
19:30	22:00	2.5	TEST BOPS/DIVERTER, TEST ALL VALVES ON CHOKE MANIFOLD, CHOKE LINE AND KILL LINE TESTED RAMS AND HYDRIL AND CASING, ALL 5K EQUIPMENT TO 5,000 HIGH AND 250 LOW, HYDRIL 2,500 HIGH AND 250 LOW, CASING TO 1,500, ALL TESTED.
22:00	04:00	6.0	INSTALL WEAR BUSHING, TRIP IN HOLE WITH BIT, TAG CMT @ 2272'
04:00	04:30	0.5	DRILLING CEMENT, FLOAT COLLAR, CEMENT, FLOAT SHOE AND 10' NEW 7.875 OH
04:30	05:00	0.5	FIT TEST, PRESSURE WITH WATER TO 350 PSIG, EMW 11.2
05:00	05:30	0.5	DEVATION SURVEY 2277' @ 2.75 DEGREE.
05:30	06:00	0.5	DRILLED 2322' TO 2458' (136') ROP 136, MW 8.8, VIS 29, GPM 430, NO LOSS/GAIN.

EMAILED BLM VERNAL JAMIE SPARGER ON 12/19/2008 RIG MOVE TO 1290-25 @ 0730 AND BOPE TEST 1400 HRS, TRANSFERED FROM CWU 1370-30 TO CWU 1290-25 3 JTS 4.5 N80 X 11.6 X LTC CASING (128.31') AND 8227 GLS DIESEL, RIG MOVE WAS 1.2 MILES

NO ACCIDENTS / INCIDENTS

NO RIG REPAIRS:

FULL CREWS

SAFETY MEETING # 1 THIRD PARTY SAFETY MEETING

SAFETY MEETING # 2 RIG UP EQUIPMENT

FUEL ON HAND 8227 GLS,

TEST CROWN-O-MATIC, BOP DRILL

UNMANNED LOGGER DAY 1

06:00 SPUD 7 7/8" HOLE AT W/ROTARY TOOLS 05:00 HRS, 12/20/08.

<b>12-21-2008</b>	<b>Reported By</b>	DUANE C WINKLER									
<b>DailyCosts: Drilling</b>	\$42,134	<b>Completion</b>	\$0	<b>Daily Total</b>	\$42,134						
<b>Cum Costs: Drilling</b>	\$411,264	<b>Completion</b>	\$0	<b>Well Total</b>	\$411,264						
<b>MD</b>	5,224	<b>TVD</b>	5,224	<b>Progress</b>	2,766	<b>Days</b>	2	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>			<b>Perf :</b>	<b>PKR Depth : 0.0</b>						
<b>Activity at Report Time:</b> DRILLING @ 5224'											

Start	End	Hrs	Activity Description
06:00	09:30	3.5	DRILLED 2458' TO 3050', (592'), ROP 169, MW 8.8, VIS 30, GPM 430, NO LOSS/GAIN
09:30	10:00	0.5	DEVATION SURVEY 3003' @ 2.5 DEGREE

10:00	15:30	5.5	DRILLED 3050' TO 3728', (678'), ROP 123, MW 9.0, VIS 31, GPM 430, NO LOSS/GAIN
15:30	16:30	1.0	SERVICE RIG
16:30	22:00	5.5	DRILLED 3728' TO 4544', (816), ROP 148, MW 9.4, VIS 32, GPM 430, NO LOSS/GAIN
22:00	22:30	0.5	DEVIATION SURVEY 4499' @ 2 DEGREE
22:30	06:00	7.5	DRILLED 4544' TO 5224', (680'), ROP 90, MW 9.8, VIS 35, GPM 430, NO LOSS/GAIN.

NO ACCIDENTS / INCIDENTS  
 NO RIG REPAIRS  
 FULL CREWS  
 SAFETY MEETING # 1 CONNECTIONS  
 SAFETY MEETING # 2 FORKLIFT  
 FUEL ON HAND 9729 GLS, USED 1628 GLS  
 TEST CROWN-O-MATIC, BOP DRILL  
 UNMANNED LOGGER DAY 2

---

<b>12-22-2008</b>	<b>Reported By</b>	DUANE C WINKLER									
<b>DailyCosts: Drilling</b>	\$26,859	<b>Completion</b>	\$0	<b>Daily Total</b>	\$26,859						
<b>Cum Costs: Drilling</b>	\$438,198	<b>Completion</b>	\$0	<b>Well Total</b>	\$438,198						
<b>MD</b>	6,560	<b>TVD</b>	6,560	<b>Progress</b>	1,336	<b>Days</b>	3	<b>MW</b>	9.6	<b>Visc</b>	35.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>		<b>PKR Depth : 0.0</b>						
<b>Activity at Report Time: DRILLING @ 6560'</b>											

Start	End	Hrs	Activity Description
06:00	15:00	9.0	DRILLED 5224' TO 5904', (680'), ROP 75, MW 9.7, VIS 35, GPM 430 NO LOSS/GAIN
15:00	15:30	0.5	SERVICE RIG
15:30	06:00	14.5	DRILLED 5904', TO 6560', (656'), ROP 45, MW 10.0, VIS 34, GPM 430, NO LOSS/GAIN

NO ACCIDENTS / INCIDENTS  
 NO RIG REPAIRS  
 FULL CREWS  
 SAFETY MEETING # 1 CHANGING OIL  
 SAFETY MEETING # 2 FORKLIFT  
 FUEL ON HAND 8319 GLS, USED 1409 GLS  
 TEST CROWN-O-MATIC, BOP DRILL  
 UNMANNED LOGGER DAY 3

---

<b>12-23-2008</b>	<b>Reported By</b>	DUANE C WINKLER									
<b>DailyCosts: Drilling</b>	\$27,957	<b>Completion</b>	\$0	<b>Daily Total</b>	\$27,957						
<b>Cum Costs: Drilling</b>	\$466,156	<b>Completion</b>	\$0	<b>Well Total</b>	\$466,156						
<b>MD</b>	7,764	<b>TVD</b>	7,764	<b>Progress</b>	1,204	<b>Days</b>	4	<b>MW</b>	10.1	<b>Visc</b>	33.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>		<b>PKR Depth : 0.0</b>						
<b>Activity at Report Time: DRILLING @ 7764'</b>											

Start	End	Hrs	Activity Description
06:00	16:00	10.0	DRILLED 6560' TO 7129', (569'), ROP 56, MW 10.3, VIS 35, GPM 430, NO LOSS/GAIN
16:00	16:30	0.5	SERVICE RIG
16:30	06:00	13.5	DRILLED 7129' TO 7764', (635'), ROP 47, MW 10.9, VIS 35, GPM 430, NO LOSS/GAIN

NO ACCIDENTS / INCIDENTS  
 NO RIG REPAIRS  
 FULL CREWS  
 SAFETY MEETING # 1 ICY ROADS  
 SAFETY MEETING # 2 CLEANING  
 FUEL ON HAND 6815 GLS, USED 1504 GLS  
 TEST CROWN-O-MATIC, BOP DRILL  
 UNMANNED LOGGER DAY 4

**12-24-2008**      **Reported By**      D. WINKLER / J. SCHLENKER

<b>DailyCosts: Drilling</b>	\$38,576	<b>Completion</b>	\$6,019	<b>Daily Total</b>	\$44,595
<b>Cum Costs: Drilling</b>	\$504,732	<b>Completion</b>	\$6,019	<b>Well Total</b>	\$510,751

**MD**      8,716      **TVD**      8,716      **Progress**      952      **Days**      4      **MW**      11.1      **Visc**      35.0

**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

**Activity at Report Time:** DRILLING @ 8716'

Start	End	Hrs	Activity Description
06:00	14:30	8.5	DRILL 7764' - 8172' (408') ROP 48, WOB 22, SPP 2000/2200, MW 11.1, VIS 37.
14:30	15:00	0.5	SERVICE RIG.
15:00	06:00	15.0	DRILL 8172' - 8716' (544') ROP 36.26, WOB 20/22.5, SPP 2100/2300, MW 11.5, VIS 34, SMALL FLARE,

BG GAS 1000 U, NO MUD GAINS OR LOSSES.  
 ROTATING WT 177,000, UP 183,000, DN 166,000.  
 FUEL ON HAND 4971 GAL, USED 1844 GAL.  
 NO ACCIDENTS OR INCIDENTS REPORTED.  
 NO RIG REPAIRS.  
 FULL CREWS.  
 SAFETY MEETINGS; BOP DRILL & OPERATING THE BOOM & FOCUS.  
 TEST CROWN-O-MATIC  
 UNMANNED LOGGER DAY 5 (STARTED 12/20/08).  
 BOILER OPERATING 24 HRS.

**12-25-2008**      **Reported By**      JIM SCHLENKER

<b>DailyCosts: Drilling</b>	\$28,134	<b>Completion</b>	\$0	<b>Daily Total</b>	\$28,134
<b>Cum Costs: Drilling</b>	\$532,867	<b>Completion</b>	\$6,019	<b>Well Total</b>	\$538,886

**MD**      9,280      **TVD**      9,280      **Progress**      564      **Days**      6      **MW**      11.5      **Visc**      34.0

**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

**Activity at Report Time:** LD DP

Start	End	Hrs	Activity Description
06:00	16:30	10.5	DRILL 8716' - 9170' (454') ROP 43.2, WOB 22, SPP 2200/2400, MW 11.5, VIS 35.
16:30	17:00	0.5	SERVICE RIG.
17:00	19:30	2.5	DRILL 9170' - 9280' (110') ROP 44, WOB 20/22, SPP 2250/2500, MW 11.6, VIS 35. REACHED TD AT 19:30 HRS, 12/24/2008.
19:30	20:00	0.5	CIRCULATE.
20:00	20:30	0.5	PUMP PILL, 275 BBL, 13.1, EMW ON BOTTOM 12.2, DROP SURVEY.

20:30 22:30 2.0 TOO H, WELL STARTED TO FLOW, MIXED PILL.  
 22:30 23:00 0.5 PUMP 100 BBL PILL 13.4 @ 7000', EMW ON BOTTOM =12.4.  
 23:00 00:30 1.5 TOO H TO 5200'.  
 00:30 02:00 1.5 CIRCULATE OUT GAS/CONDENSATE LEFT ON TOP OF HEAVY PILL WITH 11.6 MUD, KILLED FLARE, HOLE STABLE.  
 02:00 06:00 4.0 CONTINUE TOO H LDDP. CSG CREW TO ARRIVE @ 07:00.  
 FUEL ON HAND 3441 GAL, USED 1530 GAL.  
 NO ACCIDENTS OR INCIDENTS REPORTED.  
 NO RIG REPAIRS.  
 FULL CREWS.  
 SAFETY MEETINGS; DRAINING HOSES, BOP DRILL & DANGERS OF FREEZING VALVES.  
 TEST CROWN-O-MATIC.  
 UNMANNED LOGGER DAY 6 (STARTED 12/20/08).  
 BOILER OPERATING 24 HRS.

<b>12-26-2008</b>	<b>Reported By</b>	JIM SCHLENKER									
<b>Daily Costs: Drilling</b>	\$58,731	<b>Completion</b>	\$214,673	<b>Daily Total</b>	\$273,405						
<b>Cum Costs: Drilling</b>	\$591,599	<b>Completion</b>	\$220,692	<b>Well Total</b>	\$812,291						
<b>MD</b>	9,280	<b>TVD</b>	9,280	<b>Progress</b>	0	<b>Days</b>	7	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>			<b>Perf :</b>	<b>PKR Depth : 0.0</b>						

Activity at Report Time: RDRT/WO COMPLETION

Start	End	Hrs	Activity Description
06:00	06:30	0.5	PULL ROTATING RUBBER. LOST CIRCULATION WHILE FILLING HOLE - 100 BBLS MUD LOSS.
06:30	07:30	1.0	CONTINUE TOO H WITH BHA, FILLING HOLE WITH PIT WATER.
07:30	08:30	1.0	PULL WEAR BUSHING.
08:30	09:00	0.5	INSTALL CUSTION SUB & SPEAR TO RUN CSG, SAFETY MTG WITH CALIBER CSG CREW & ALL RIG PERSONNEL, RU CALIBER HYD TONGS.
09:00	19:00	10.0	RUN 4.5" N-80 11.6# CASING AS FOLLOWS; TOTAL OF 2220 JT'S (218 FULL JT'S + 2 MARKER JT'S) FLOAT SHOE LANDED @ 9279.5', 1 JNT CASING, FLOAT COLLAR @ 9235' (TOP), 64 JNT'S CASING, 1 MARKER JT @ 6512' - 6533', 53 JT'S CASING, MARKER JT 4245' - 4267', 100 JTS CSG, INSTALL BOW SPRING CENTRALIZERS, 5' ABOVE SHOE, TOP OF 2nd JT. THEN EVERY 3RD. JT. TO 6260' FOR A TOTAL OF 25. THREAD LOCK SHOE, 1ST JT, FLOAT COLLAR & 2ND JT. TAG HARD BOTTOM @ 9280', REMOVE ROTATING RUBBER, LD TAG JNT, MAKE UP FLUTED MANDRAL HANGER & LANDING JT, LAND CASING W/ STRING WT 90,000#, FMC ON SITE TO SUPERVISE LANDING.
19:00	20:30	1.5	SAFETY MEETING/JSA WITH SCHLUMBERGER & ALL RIG PERSONNEL, RU CEMENTING EQUIP.
20:30	23:30	3.0	CEMENT W/ SCHLUMBERGER, TEST LINES TO 5000 PSI, DROP BOTTOM PLUG, PUMP 20 BBLS CHEMICAL WASH AND 20 BBLS WATER SPACER. MIXED AND PUMPED 820 SKS 35:65 POZ G, (289 BBLS) W/5% D020 (EXTENDER), 2% D174 (EXPANDING CE), .75% D112 (FLUID LOSS), .2% D046 (ANTIFOAM), .3% D013 (RETARDER), .2% D065 (DISPERSANT), .250 lb/sk BLEND D129 (LOST CIRC). (YIELD 1.98) AT 12.5 PPG WITH 10.899 GPS H2O.  PUMPED TAIL 1520 SKS 50:50 POZ G (349 BBLS) W/2% D020 (EXTENDER), .1% D046 (ANTIFOAM), .2% D167 (FLUID LOSS), .2% D065 (DISPERSANT), .1% D013 (RETARDER), (YIELD 1.29) AT 14.1 PPG WITH 5.979 GPS H2O. (OBSERVED RETURN TO SURFACE THE "CEMNET" THEN CEMENT TO TO SURFACE - APROX 50 BBLS DURING THE END OF PUMPING TAIL AND DURING DISPLACEMENT OF TOP PLUG - ESTIMATED 80 BBLS OF CEMENT BY-PASSED TO PIT.)  DROPPED TOP PLUG @ 22:52, DISPLACED TO FLOAT COLLAR WITH 140 BBL OF FRESH WATER, AVG MIX AND DISPLACEMENT RATE 5 BPM. FINAL PUMP PRESSURE 2500 PSI. BUMPED PLUG @ 23:18 WITH 3400 PSI, BLED OFF PRESSURE, 1.5 BBL FLOW BACK, FLOATS HELD.

WAIT ON CEMENT & RD CEMENTING EQUIP, SCHLUMBERGER OFF LOCATION @ 12:30.

23:30 01:30 2.0 SET PACKOFF & TEST W/ 5000 PSI WITH FMC.  
UN-LOCK BOP.  
01:30 05:00 3.5 ND & CLEAN TANKS, RDRT FOR RIG MOVE TO CWU 1358-24 (2 MI), HOWCROFT TRUCKS EXPECTED @ 08:00.

FUEL ON HAND 1124 GAL, USED 2317 GAL.  
NO ACCIDENTS OR INCIDENTS REPORTED.  
NO RIG REPAIRS.  
FULL CREWS.  
SAFETY MEETINGS; RUNNING CASING & CEMENTING.  
TEST CROWN-O-MATIC.  
UNMANNED LOGGER DAY (STARTED 12/20/08).  
BOILER OPERATING 24 HRS.  
MUD LOST 100 BBLS.  
SENT 500 BBLS OF 11.6# MUD TO MUD PLANT.

05:00 RIG RELEASED @ 05:00 HRS, 12/26/2008.  
CASING POINT COST \$558,908

---

<b>01-01-2009</b>	<b>Reported By</b>	SEARLE									
<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$44,191	<b>Daily Total</b>	\$44,191						
<b>Cum Costs: Drilling</b>	\$591,599	<b>Completion</b>	\$264,883	<b>Well Total</b>	\$856,482						
<b>MD</b>	9,280	<b>TVD</b>	9,280	<b>Progress</b>	0	<b>Days</b>	8	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation : MESAVERDE</b>		<b>PBTD : 9235.0</b>		<b>Perf :</b>		<b>PKR Depth : 0.0</b>					
<b>Activity at Report Time: PREP FOR FRACS</b>											
<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>								
06:00	06:00	24.0	MIRU SCHLUMBERGER. LOG WITH RST/CBL/CCL/VDL/GR FROM PBTD TO 200'. EST CEMENT TOP @ 350'. RD SCHLUMBERGER.								

---

<b>01-24-2009</b>	<b>Reported By</b>	MCCURDY									
<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$1,228	<b>Daily Total</b>	\$1,228						
<b>Cum Costs: Drilling</b>	\$591,599	<b>Completion</b>	\$266,111	<b>Well Total</b>	\$857,710						
<b>MD</b>	9,280	<b>TVD</b>	9,280	<b>Progress</b>	0	<b>Days</b>	9	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation : MESAVERDE</b>		<b>PBTD : 9235.0</b>		<b>Perf :</b>		<b>PKR Depth : 0.0</b>					
<b>Activity at Report Time: WO COMPLETION</b>											
<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>								
06:00	06:00	24.0	NU 10M FRAC TREE. PRESSURE TESTED FRAC TREE & CASING TO 6500 PSIG. WO COMPLETION.								

---

<b>01-27-2009</b>	<b>Reported By</b>	KERN									
<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$49,600	<b>Daily Total</b>	\$49,600						
<b>Cum Costs: Drilling</b>	\$591,599	<b>Completion</b>	\$315,711	<b>Well Total</b>	\$907,310						
<b>MD</b>	9,280	<b>TVD</b>	9,280	<b>Progress</b>	0	<b>Days</b>	10	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation : MESAVERDE</b>		<b>PBTD : 9235.0</b>		<b>Perf : 8011'-8969'</b>		<b>PKR Depth : 0.0</b>					
<b>Activity at Report Time: FRAC</b>											

Start	End	Hrs	Activity Description
06:00	06:00	24.0	RU CUTTERS WIRELINE & PERFORATE LPR FROM 8779'-80', 8792'-93', 8805'-06', 8840'-41', 8848'-49', 8875'-76', 8889'-90', 8896'-97', 8903'-04', 8912'-13', 8967'-69' @ 3 SPF @ 120° PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/165 GAL GYPTRON T-106, 6306 GAL LINEAR DELTA 200 W/1# & 1.5# 20/40 SAND, 31821 GAL DELTA 200 W/121000 # 20/40 SAND @ 1-5 PPG. MTP 5787 PSIG. MTR 50.6 BPM. ATP 4521 PSIG. ATR 43.7 BPM. ISIP 3069 PSIG. RD HALLIBURTON.
			RUWL. SET 6K CFP AT 8700'. PERFORATE M/LPR FROM 8443'-44', 8488'-89', 8494'-95', 8509'-10', 8516'-17', 8523'-24', 8550'-51', 8574'-75', 8587'-88', 8620'-21', 8630'-31', 8666'-67' @ 3 SPF @ 120° PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/165 GAL GYPTRON T-106, 6478 GAL LINEAR DELTA 200 W/1# & 1.5# 20/40 SAND, 33944 GAL DELTA 200 W/124600# 20/40 SAND @ 1-5 PPG. MTP 6243 PSIG. MTR 50.9 BPM. ATP 5090 PSIG. ATR 48.1 BPM. ISIP 4215 PSIG. RD HALLIBURTON.
			RUWL. SET 6K CFP AT 8420'. PERFORATE MPR FROM 8253'-54', 8267'-68', 8277'-78', 8292'-93', 8311'-12', 8336'-37', 8341'-42', 8351'-52', 8358'-59', 8363'-64', 8371'-72', 8400'-01' @ 3 SPF @ 120° PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/165 GAL GYPTRON T-106, 6354 GAL LINEAR DELTA 200 W/1# & 1.5# 20/40 SAND, 47455 GAL DELTA 200 W/176000# 20/40 SAND @ 1-5 PPG. MTP 5860 PSIG. MTR 50.3 BPM. ATP 4428 PSIG. ATR 45.5 BPM. ISIP 2873 PSIG. RD HALLIBURTON.
			RUWL. SET 6K CFP AT 8235'. PERFORATE MPR FROM 8011'-13', 8030'-31', 8038'-39', 8047'-48', 8077'-78', 8121'-22', 8127'-28', 8134'-35', 8164'-65', 8195'-96', 8206'-07', @ 3 SPF @ 120° PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/165 GAL GYPTRON T-106, 6320 GAL LINEAR DELTA 200 W/1# & 1.5# 20/40 SAND, 44406 GAL DELTA 200 W/164800# 20/40 SAND @ 1-5 PPG. MTP 4712 PSIG. MTR 51.6 BPM. ATP 4066 PSIG. ATR 47.4 BPM. ISIP 2409 PSIG. RD HALLIBURTON. SDFN.

01-28-2009		Reported By	KERN	
<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$359,318	<b>Daily Total</b> \$359,318
<b>Cum Costs: Drilling</b>	\$591,599	<b>Completion</b>	\$675,029	<b>Well Total</b> \$1,266,628
<b>MD</b>	9,280	<b>TVD</b>	9,280	<b>Progress</b> 0
		<b>Days</b>	11	<b>MW</b> 0.0
<b>Formation : MESAVERDE</b>		<b>PBTD : 9235.0</b>	<b>Perf : 6920'-8969'</b>	<b>PKR Depth : 0.0</b>

Activity at Report Time: WAIT FOR SERVICE RIG TO DRILL OUT PLUGS

Start	End	Hrs	Activity Description
06:00	06:00	24.0	RUWL SET 6K CFP AT 7985'. PERFORATE MPR FROM 7778'-79', 7784'-85', 7792'-93', 7814'-15', 7822'-23', 7835'-36', 7854'-55', 7904'-05', 7910'-11', 7915'-16', 7943'-44', 7964'-65' @ 3 SPF @ 120° PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/ 165 GAL GYPTRON T-106, 6498 GAL LINEAR DELTA 200 1# & 1.5#, 40374 GAL DELTA 200 W/ 149100 # 20/40 SAND @ 1-5 PPG. MTP 4985 PSIG. MTR 50.7 BPM. ATP 4377 PSIG. ATR 49.4 BPM. ISIP 2419 PSIG. RD HALLIBURTON.
			RUWL SET 6K CFP AT 7750'. PERFORATE UPR FROM 7551'-53', 7573'-74', 7590'-91', 7622'-23', 7630'-31', 7641'-42', 7665'-66', 7670'-71', 7714'-15', 7720'-21', 7730'-31' @ 3 SPF @ 120° PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/ 165 GAL GYPTRON T-106, 6403 GAL LINEAR DELTA 200 1# & 1.5#, 28825 GAL DELTA 200 W/ 110000 # 20/40 SAND @ 1-5 PPG. MTP 4646 PSIG. MTR 51.4 BPM. ATP 3594 PSIG. ATR 49.3 BPM. ISIP 2566 PSIG. RD HALLIBURTON.
			RUWL SET 6K CFP AT 7495'. PERFORATE UPR FROM 7187'-88', 7191'-92', 7228'-29', 7236'-37', 7325'-26', 7336'-37', 7377'-78', 7416'-17', 7428'-29', 7448'-49', 7458'-59', 7474'-75' @ 3 SPF @ 120° PHASING RDWL. RU HALLIBURTON, FRAC DOWN CASING W/ 165 GAL GYPTRON T-106, 6413 GAL LINEAR DELTA 200 1# & 1.5#, 53529 GAL DELTA 200 W/ 199900 # 20/40 SAND @ 1-5 PPG. MTP 4459 PSIG. MTR 50.9 BPM. ATP 3623 PSIG. ATR 50.2 BPM. ISIP 2338 PSIG. RD HALLIBURTON.
			RUWL SET 6K CFP AT 7160'. PERFORATE UPR FROM 6920'-21', 6926'-27', 6948'-49', 6956'-57', 6963'-64', 7016'-17', 7020'-21', 7043'-44', 7075'-76', 7084'-85', 7093'-94', 7140'-41' @ 3 SPF @ 120° PHASING RDWL. RU HALLIBURTON, FRAC DOWN CASING W/ 165 GAL GYPTRON T-106, 6449 GAL LINEAR DELTA 200 1# & 1.5#, 45011 GAL DELTA 200 W/ 180500 # 20/40 SAND @ 1-5 PPG. MTP 4577 PSIG. MTR 51 BPM. ATP 3538 PSIG. ATR 49.9 BPM. ISIP 2167 PSIG. RD HALLIBURTON.

RUWL. SET 6K CBP AT 6803'. RDMO CUTTERS WIRELINE.

**01-30-2009**      **Reported By**      POWELL

**Daily Costs: Drilling**      \$0      **Completion**      \$7,314      **Daily Total**      \$7,314

**Cum Costs: Drilling**      \$591,599      **Completion**      \$682,343      **Well Total**      \$1,273,942

**MD**      9,280      **TVD**      9,280      **Progress**      0      **Days**      12      **MW**      0.0      **Visc**      0.0

**Formation :** MESAVERDE      **PBTD :** 9235.0      **Perf :** 6920'-8969'      **PKR Depth :** 0.0

**Activity at Report Time:** CLEAN OUT AFTER FRAC

Start	End	Hrs	Activity Description
07:00	17:00	10.0	MIRUSU. ND TREE. NU BOPE. RIH W/ BIT & PUMP OFF SUB TO 6803'. RU TO DRILL OUT PLUGS. SDFN.

**01-31-2009**      **Reported By**      POWELL

**Daily Costs: Drilling**      \$0      **Completion**      \$9,010      **Daily Total**      \$9,010

**Cum Costs: Drilling**      \$591,599      **Completion**      \$691,353      **Well Total**      \$1,282,952

**MD**      9,280      **TVD**      9,280      **Progress**      0      **Days**      13      **MW**      0.0      **Visc**      0.0

**Formation :** MESAVERDE      **PBTD :** 9235.0      **Perf :** 6920'-8969'      **PKR Depth :** 0.0

**Activity at Report Time:** CLEAN OUT AFTER FRAC

Start	End	Hrs	Activity Description
07:00	18:00	11.0	PUMPED 16 BW. TUBING PRESSURED UP. POH. PUMP OFF SUB WAS PLUGGED OFF WITH RUST. RIH W/NEW PUMP OFF SUB . CLEANED OUT & DRILLED OUT PLUGS @ 6803', 7160', 7495', 7750', 7985' & 8235'. POH. SDFN.

**02-01-2009**      **Reported By**      POWELL

**Daily Costs: Drilling**      \$0      **Completion**      \$8,934      **Daily Total**      \$8,934

**Cum Costs: Drilling**      \$591,599      **Completion**      \$700,287      **Well Total**      \$1,291,886

**MD**      9,280      **TVD**      9,280      **Progress**      0      **Days**      14      **MW**      0.0      **Visc**      0.0

**Formation :** MESAVERDE      **PBTD :** 9235.0      **Perf :** 6920'-8969'      **PKR Depth :** 0.0

**Activity at Report Time:** FLOW TEST

Start	End	Hrs	Activity Description
07:00	15:00	8.0	SICP 1500 PSIG. RIH . CLEANED OUT & DRILLED OUT PLUGS @ 8420' & 8700'. RIH. CLEANED OUT TO PBTD @ 9235'. LANDED TBG AT 7783' KB. ND BOPE. NU TREE. PUMPED OFF BIT & SUB. RDMOSU.

FLOWED 16 HRS. 24/64 CHOKE. FTP 1600 PSIG. CP 2000 PSIG. 60 BFPH. RECOVERED 1071 BLW. 9111 BLWTR.

TUBING DETAIL    LENGTH

PUMP OFF SUB    1.00'

1 JT 2-3/8" 4.7# L-80 TBG    31.75'

XN NIPPLE    1.10'

244 JTS 2-3/8" 4.7# L-80 TBG    7737.40'

BELOW KB    12.00'

LANDED @    7783.25' KB

**02-02-2009**      **Reported By**      POWELL

**Daily Costs: Drilling**      \$0      **Completion**      \$1,850      **Daily Total**      \$1,850

**Cum Costs: Drilling**      \$591,599      **Completion**      \$702,137      **Well Total**      \$1,293,736

**MD** 9,280 **TVD** 9,280 **Progress** 0 **Days** 15 **MW** 0.0 **Visc** 0.0  
**Formation :** MESAVERDE **PBTD :** 9235.0 **Perf :** 6920'-8969' **PKR Depth :** 0.0

**Activity at Report Time:** FLOW TEST TO SALES

Start	End	Hrs	Activity Description
06:00	06:00	24.0	INITIAL PRODUCTION. OPENING PRESSURE: TP 1600 PSIG & CP 2000 PSIG. TURNED WELL OVER TO QUESTAR SALES AT 11:00 HRS, 2/1/09. FLOWED 1235 MCFD RATE ON 20/64" CHOKE. STATIC 238. QGM METER #8075. TEST UNIT.

RU BRECO TEST UNIT. FLOWED 22 HRS. 20/64 CHOKE. FTP 1700 PSIG. CP 2200 PSIG. 34 BFPH. RECOVERED 932 BLW. 8179 BLWTR. 1291 MCFD RATE. FLOW THROUGH TEST UNIT TO SALES.

---

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**WELL COMPLETION OR RECOMPLETION REPORT AND LOG**

5. Lease Serial No.  
UTU0285A

1a. Type of Well  Oil Well  Gas Well  Dry  Other  
 b. Type of Completion  New Well  Work Over  Deepen  Plug Back  Diff. Resvr.  
 Other \_\_\_\_\_

2. Name of Operator **EOG RESOURCES, INC.** Contact: **MARY A. MAESTAS**  
 E-Mail: **mary\_maestas@eogresources.com**

3. Address **600 17TH STREET SUITE 1000N DENVER, CO 80202** 3a. Phone No. (include area code)  
**Ph: 303-824-5526**

4. Location of Well (Report location clearly and in accordance with Federal requirements)\*  
 At surface **NWNE 142FNL 2478FEL 40.01389 N Lat, 109.38775 W Lon**  
 At top prod interval reported below **NWNE 142FNL 2478FEL 40.01389 N Lat, 109.38775 W Lon**  
 At total depth **NWNE 142FNL 2478FEL 40.01389 N Lat, 109.38775 W Lon**

6. If Indian, Allottee or Tribe Name \_\_\_\_\_  
 7. Unit or CA Agreement Name and No.  
**CHAPITA WELLS**

8. Lease Name and Well No.  
**CHAPITA WELLS UNIT 1290-25**

9. API Well No.  
**43-047-39471**

10. Field and Pool, or Exploratory  
**NATURAL BUTTES**

11. Sec., T., R., M., or Block and Survey or Area  
**Sec 25 T9S R22E Mer SLB**

12. County or Parish  
**UINTAH** 13. State  
**UT**

14. Date Spudded  
**11/04/2008** 15. Date T.D. Reached  
**12/24/2008** 16. Date Completed  
 D & A  Ready to Prod.  
**02/01/2009**

17. Elevations (DF, KB, RT, GL)\*  
**5048 GL**

18. Total Depth: **MD 9280** 19. Plug Back T.D.: **MD 9235** 20. Depth Bridge Plug Set: **MD TVD**

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)  
**RST/CBL/CCL/VDL/GR** 22. Was well cored?  No  Yes (Submit analysis)  
 Was DST run?  No  Yes (Submit analysis)  
 Directional Survey?  No  Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)  
**press Temp**

Hole Size	Size/Grade	Wt. (#ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12.250	9.625 J-55	36.0	0	2312		800		0	
7.875	4.500 N-80	11.6	0	9280		2340		350	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	7783							

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	6920	8969	8779 TO 8969		3	
B)			8443 TO 8667		3	
C)			8253 TO 8401		3	
D)			8011 TO 8207		3	

26. Perforation Record **6920**

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
8779 TO 8969	38,292 GALS GELLED WATER & 121,000# 20/40 SAND
8443 TO 8667	40,587 GALS GELLED WATER & 124,600# 20/40 SAND
8253 TO 8401	53,974 GALS GELLED WATER & 176,000# 20/40 SAND
8011 TO 8207	50,891 GALS GELLED WATER & 164,800# 20/40 SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
02/01/2009	02/13/2009	24	→	20.0	648.0	330.0			FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
12/64"	SI 1500	2100.0	→	20	648	330		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
	SI		→						

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #67676 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

**\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\***

**RECEIVED**

**MAR 03 2009**

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

29. Disposition of Gas(Sold, used for fuel, vented, etc.)  
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
MESAVERDE	6920	8969		GREEN RIVER BIRDS NEST MAHOGANY UTELAND BUTTE WASATCH CHAPITA WELLS BUCK CANYON PRICE RIVER	1585 1779 2293 4518 4633 5222 5907 6914

32. Additional remarks (include plugging procedure):  
Please see the attached page for detailed perforation and additional formation marker information.

33. Circle enclosed attachments:

- 1. Electrical/Mechanical Logs (1 full set req'd.)
- 2. Geologic Report
- 3. DST Report
- 4. Directional Survey
- 5. Sundry Notice for plugging and cement verification
- 6. Core Analysis
- 7 Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #67676 Verified by the BLM Well Information System.  
For EOG RESOURCES, INC., sent to the Vernal**

Name (please print) MARY A. MAESTAS Title REGULATORY ASSISTANT

Signature  Date 02/27/2009

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Chapita Wells Unit 1290-25 - ADDITIONAL REMARKS (CONTINUED):**

**26. PERFORATION RECORD**

7778-7965	3/spf
7551-7731	3/spf
7187-7475	3/spf
6920-7141	3/spf

**27. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.**

7778-7965	47,037 GALS GELLED WATER & 149,100# 20/40 SAND
7551-7731	35,393 GALS GELLED WATER & 110,000# 20/40 SAND
7187-7475	60,107 GALS GELLED WATER & 199,900# 20/40 SAND
6920-7141	51,625 GALS GELLED WATER & 180,500# 20/40 SAND

Perforated the Lower Price River from 8779-80', 8792-93', 8805-06', 8840-41', 8848-49', 8875-76', 8889-90', 8896-97', 8903-04', 8912-13', 8967-69' w/ 3 spf.

Perforated the Middle/Lower Price River from 8443-44', 8488-89', 8494-95', 8509-10', 8516-17', 8523-24', 8550-51', 8574-75', 8587-88', 8620-21', 8630-31', 8666-67' w/ 3 spf.

Perforated the Middle Price River from 8253-54', 8267-68', 8277-78', 8292-93', 8311-12', 8336-37', 8341-42', 8351-52', 8358-59', 8363-64', 8371-72', 8400-01' w/ 3 spf.

Perforated the Middle Price River from 8011-13', 8030-31', 8038-39', 8047-48', 8077-78', 8121-22', 8127-28', 8134-35', 8164-65', 8195-96', 8206-07' w/ 3 spf.

Perforated the Middle Price River from 7778-79', 7784-85', 7792-93', 7814-15', 7822-23', 7835-36', 7854-55', 7904-05', 7910-11', 7915-16', 7943-44', 7964-65' w/ 3 spf.

Perforated the Upper Price River from 7551-53', 7573-74', 7590-91', 7622-23', 7630-31', 7641-42', 7665-66', 7670-71', 7714-15', 7720-21', 7730-31' w/ 3 spf.

Perforated the Upper Price River from 7187-88', 7191-92', 7228-29', 7236-37', 7325-26', 7336-37', 7377-78', 7416-17', 7428-29', 7448-49', 7458-59', 7474-75' w/ 3 spf.

Perforated the Upper Price River from 6920-21', 6926-27', 6948-49', 6956-57', 6963-64', 7016-17', 7020-21', 7043-44', 7075-76', 7084-85', 7093-94', 7140-41' w/ 3 spf.

**32. FORMATION (LOG) MARKERS**

Middle Price River	7785
Lower Price River	8585
Sego	9096

**REPORT OF WATER ENCOUNTERED DURING DRILLING**

Well name and number: CWU 1290-25

API number: 4304739471

Well Location: QQ NWNE Section 25 Township 9S Range 22E County UINTAH

Well operator: EOG

Address: 1060 E HWY 40

city VERNAL state UT zip 84078

Phone: (435) 781-9111

Drilling contractor: CRAIGS ROUSTABOUT SERVICE

Address: PO BOX 41

city JENSEN state UT zip 84035

Phone: (435) 781-1366

Water encountered (attach additional pages as needed):

DEPTH		VOLUME (FLOW RATE OR HEAD)	QUALITY (FRESH OR SALTY)
FROM	TO		
907	915	NO FLOW	NOT KNOWN

Formation tops:            1 \_\_\_\_\_            2 \_\_\_\_\_            3 \_\_\_\_\_  
 (Top to Bottom)            4 \_\_\_\_\_            5 \_\_\_\_\_            6 \_\_\_\_\_  
                                      7 \_\_\_\_\_            8 \_\_\_\_\_            9 \_\_\_\_\_  
                                      10 \_\_\_\_\_            11 \_\_\_\_\_            12 \_\_\_\_\_

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I hereby certify that this report is true and complete to the best of my knowledge.

NAME (PLEASE PRINT) Mary A. Maestas

TITLE Regulatory Assistant

SIGNATURE *Mary A. Maestas*

DATE 2/27/2009

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	<b>FORM 9</b>  <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> U-0285A
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>  <b>7. UNIT or CA AGREEMENT NAME:</b> CHAPITA WELLS
<b>1. TYPE OF WELL</b> Gas Well	<b>8. WELL NAME and NUMBER:</b> CWU 1290-25
<b>2. NAME OF OPERATOR:</b> EOG Resources, Inc.	<b>9. API NUMBER:</b> 43047394710000
<b>3. ADDRESS OF OPERATOR:</b> 1060 East Highway 40 , Vernal, UT, 84078	<b>PHONE NUMBER:</b> 435 781-9111 Ext
<b>4. LOCATION OF WELL FOOTAGES AT SURFACE:</b> 0142 FNL 2478 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNE Section: 25 Township: 09.0S Range: 22.0E Meridian: S	<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES  <b>COUNTY:</b> UINTAH  <b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/1/2009	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: Pit Closure

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The reserve pit on the referenced location was closed on 7/1/2009 as per the APD procedure.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 July 08, 2009

<b>NAME (PLEASE PRINT)</b> Mickenzie Thacker	<b>PHONE NUMBER</b> 435 781-9145	<b>TITLE</b> Operations Clerk
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/8/2009	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	<b>FORM 9</b>  <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> U-0285A
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>  <b>7. UNIT or CA AGREEMENT NAME:</b> CHAPITA WELLS
<b>1. TYPE OF WELL</b> Gas Well	<b>8. WELL NAME and NUMBER:</b> CWU 1290-25
<b>2. NAME OF OPERATOR:</b> EOG Resources, Inc.	<b>9. API NUMBER:</b> 43047394710000
<b>3. ADDRESS OF OPERATOR:</b> 1060 East Highway 40 , Vernal, UT, 84078	<b>PHONE NUMBER:</b> 435 781-9111 Ext
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0142 FNL 2478 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNE Section: 25 Township: 09.0S Range: 22.0E Meridian: S	<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES  <b>COUNTY:</b> UINTAH  <b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 2/4/2011  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input checked="" type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. respectfully requests authorization to temporarily abandon the referenced well while the pad well to the location (Chapita Wells Unit 1503-25D, Chapita Wells Unit 1504-25D, Chapita Wells Unit 1505-25D, Chapita Wells Unit 1506-25D, Chapita Wells Unit 1507-25D and Chapita Wells Unit 1508-25D) are drilled and completed.

**Accepted by the  
Utah Division of  
Oil, Gas and Mining**

Date: 02/10/2011  
By: *Derek Quist*

<b>NAME (PLEASE PRINT)</b> Mickenzie Gates	<b>PHONE NUMBER</b> 435 781-9145	<b>TITLE</b> Operations Clerk
<b>SIGNATURE</b> N/A		<b>DATE</b> 2/4/2011