

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 20G0005609
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name Ute
2. Name of Operator Newfield Production Company		7. If Unit or CA Agreement, Name and No. N/A
3a. Address Route #3 Box 3630, Myton UT 84052		8. Lease Name and Well No. Ute Tribal 7-23-4-1
3b. Phone No. (include area code) (435) 646-3721		9. API Well No. 43-047-39634
4. Location of Well (Report location clearly and in accordance with any State requirements,*) At surface SW/NE 2314' FNL 2233' FEL 588485X 40.121395 At proposed prod. zone 44415384 - 109.961582		10. Field and Pool, or Exploratory Monument Butte
14. Distance in miles and direction from nearest town or post office* Approximately 12.0 miles southeast of Myton, Utah		11. Sec., T., R., M., or Blk. and Survey or Area SW/NE Sec. 23, T4S R1W
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) Approx. 326' file, NA' file/unit	16. No. of Acres in lease NA	12. County or Parish Uintah
17. Spacing Unit dedicated to this well 40 Acres	13. State UT	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. NA	19. Proposed Depth 6950'	20. BLM/BIA Bond No. on file B002792
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5048' GL	22. Approximate date work will start* 4th Quarter 2007	23. Estimated duration Approximately seven (7) days from spud to rig release.

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.


25. Signature <i>Mandie Crozier</i>	Name (Printed/Typed) Mandie Crozier	Date 8/13/07
Title Regulatory Specialist		
Approved by Signature <i>Bradley G. Hill</i>	Name (Printed/Typed) BRADLEY G. HILL	Date 01-14-08
Title Office	Office ENVIRONMENTAL MANAGER	

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

Federal Approval of this
Action is Necessary





T4S, R1W, U.S.B.&M.

NEWFIELD PRODUCTION COMPANY

S89°59'W - 79.97 (G.L.O.) 2643.16' (Measured)
 S89°59'W G.L.O. (Basis of Bearings)

WELL LOCATION, WELL 7-23-4-1,
 LOCATED AS SHOWN IN THE SW 1/4 NE
 1/4 OF SECTION 23,
 U.S.B.&M. UINTAH COUNTY, UTAH.



WELL LOCATION:
WELL 7-23-4-1
 ELEV. UNGRADED GROUND = 5047.7'

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
 PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
 MADE BY ME OR UNDER MY SUPERVISION AND THAT
 THE SAME ARE TRUE AND CORRECT TO THE BEST OF
 MY KNOWLEDGE AND BELIEF. No.189377

Stacy W. Stewart
 STACY W. STEWART
 REGISTERED LAND SURVEYOR
 REGISTRATION No. 189377
 STATE OF UTAH

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV;
 U.S.G.S. 7-1/2 min QUAD (PARIETTE DRAW SW)

WELL 7-23-4-1
 (Surface Location) NAD 83
 LATITUDE = 40° 07' 17.61"
 LONGITUDE = 109° 57' 43.46"

TRI STATE LAND SURVEYING & CONSULTING	
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078 (435) 781-2501	
DATE SURVEYED: 06-22-07	SURVEYED BY: C.M.
DATE DRAWN: 06-26-07	DRAWN BY: F.T.M.
REVISED:	SCALE: 1" = 1000'

MEMORANDUM
of
EASEMENT, RIGHT-OF-WAY
and
SURFACE USE AGREEMENT

This Easement and Surface Use Agreement ("Agreement") is entered into this 5th day of November 2007 by and between, **Henderson Ranches, LLC, Wayne and Moreen Henderson, Lance and Julie Henderson, Tommy Henderson, and Billie Henderson**, whose address is R.R. 3, Box 3671, Myton, Utah 84052 ("Surface Owner," whether one or more), and NEWFIELD PRODUCTION COMPANY, a Texas corporation ("NEWFIELD"), with offices at 1401 Seventeenth Street, Suite 1000, Denver, Colorado 80202, covering certain lands, (the "Lands") situated in Uintah County, Utah described as follows:

Township 4 South, Range 1 West
Section 23: SWNE (7-23-4-1)
Uintah County, Utah

(limited to approximately 10 acres around the well bore)

For and in consideration of the sum of ten dollars (\$10.00), and other valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the undersigned hereby agree to the terms and provisions set forth as follows:

1. Compensation for Well: Release of All Claims

NEWFIELD shall pay to Surface Owner the sum as set forth in and according to the terms of that certain Letter Agreement for Easement, Right-of Way and Surface Use by and between Surface Owner and NEWFIELD, dated November 5, 2007, as full payment and satisfaction for any and all detriment, depreciation, injury or damage of any nature to the Lands or growing crops thereon that may occur as a result of NEWFIELD's drilling or completion operations or its continuing activities for the production or transportation of oil, gas, or other hydrocarbons or products associated with the foregoing including, but not limited to, surface use, access, pipelines, gathering lines, pipeline interconnections, and any and all other reasonable or customary uses of land related to said operations or activities.

2. Grant of Right of Way and Easement

Surface Owner hereby grants, bargains, leases, assigns, and conveys to NEWFIELD an easement and right-of-way for the purpose of construction, using and maintaining access roads, locations for surface equipment and subsurface gathering lines for each well drilled upon the Lands, pipelines, and pipeline interconnections for two years from date of this agreement and so long thereafter as NEWFIELD's oil and gas leases remain in effect.


This Agreement shall be binding upon the respective heirs, executors, administrators, successors, and assigns of the undersigned.


These Parties hereto have executed this document effective as of the day first above written.


NEWFIELD PRODUCTION COMPANY


By: 
Gary D. Packer, President

SURFACE OWNER

By: 
Wayne Henderson, Henderson Ranches. LLC


By: 
Wayne Henderson

By: 
Lance Henderson

By: 
Tommy Henderson

By: 
Moreen Henderson

By: 
Julie Henderson

By: 
Billie Henderson

NEWFIELD PRODUCTION COMPANY
UTE TRIBAL 7-23-4-1
SW/NE SECTION 23 T4S, R1W
UINTAH COUNTY, UTAH

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta	0' – 2,800'
Green River	2,800'
TD	6,950'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation (Oil) 2,800' – 6,950'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM**

a. **Casing Design: Ute Tribal 7-23-4-1**

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	300'	24.0	J-55	STC	2,950	1,370	244,000
						17.53	14.35	33.89
Prod casing 5-1/2"	0'	6,950'	15.5	J-55	LTC	4,810	4,040	217,000
						2.18	1.83	2.01

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. **Cementing Design: Ute Tribal 7-23-4-1**

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	300'	Class G w/ 2% CaCl	138	30%	15.8	1.17
			161			
Prod casing Lead	4,950'	Prem Lite II w/ 10% gel + 3% KCl	342	30%	11.0	3.26
			1115			
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363	30%	14.3	1.24
			451			

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

Waiting On Cement: A minimum of four (4) hours shall elapse prior to attempting any pressure testing of the BOP equipment which would subject the surface casing cement to pressure, and a minimum of six (6) hours shall elapse before drilling out of the wiper plug, cement, or shoe is begun. WOC time shall be recorded in the Driller's Log. Compressive Strength shall be a minimum of 500 psi prior to drilling out.

The Vernal BLM Office shall be notified, with sufficient lead time, in order to have a BLM representative on location while running all casing strings and cementing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

The production casing cementing program shall be conducted as approved to protect and/or isolate all usable water zones, potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals.

As a minimum, usable water zones shall be isolated and/or protected by having a cement top for the production casing at least 200 feet above the base of the usable water. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

Top plugs shall be used to reduce contamination of cement by displacement fluid. A bottom plug or other acceptable technique, such as a suitable preflush fluid, inner string cement method, etc., shall be utilized to help isolate the cement from contamination by the mud being displaced ahead of the cement slurry.

All casing strings below the conductor shall be pressure tested to 0.22 psi per foot of casing string length or to 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield. If pressure declines more than 10% in 30 minutes, corrective action shall be taken.

A Form 3160-5, "Sundry Notices and Reports on Wells" shall be filed with the Vernal Office Manager within 30 days after the work is completed. This report must include the following information:

Setting of each string of casing showing the size, grade, weight of casing set, depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of the cementing tools used, casing test method and results, and the date of the work done. Spud date will be shown on the first reports submitted.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The Company's Class 2M minimum specifications for pressure control equipment for a standard Monument Butte development well are as follows:

A 2000 psi WP hydraulic BOP stack consisting of two ram preventers (double or two singles) and either an annular preventer or a rotating head. If no annular preventer is used, ram blocks will be changed to match the outside diameter of casing and the stack will be retested prior to running any casing string.

Connections - All components on the stack and choke and kill lines shall have either flanged, studded, clamp hub or equivalent proprietary connections except control line outlets and pressure gauges.

Choke Manifold - The minimum equipment requirements are shown in **Exhibit C**. The choke manifold shall be located at least 5 feet from the BOP stack, outside the substructure.

Pressure Monitoring - A means of monitoring the inlet pressure of the choke manifold shall be provided. The capability to isolate this outlet shall be provided.

Drillstring Control Devices - An upper and lower kelly valve, drillstring safety valve including correct closing handle, and an inside BOP shall be provided. The safety valve and inside BOP shall have connections or crossovers to fit all tubulars with OD to allow adequate clearance for running in the hole. All drillstring valves shall be rated to the required BOP WP.

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system, and individual components shall be operable as designed.

Function test of the BOP equipment shall be made daily. All required BOP tests and/or drills shall be recorded in the Driller's report.

Chart recorders will be used for all pressure tests. Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to BLM representatives upon request.

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

From surface to ± 3200 feet will be drilled with either fresh water or an air/mist system, depending on the drilling contractor's preference. From about 3200 feet, or in the case of the air/mist system when hole conditions dictate, to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite.

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will visually monitor pit levels and flow from the well during drilling operations.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. TESTING, LOGGING AND CORING PROGRAMS:

a. Logging Program:

(the log types run may change at the discretion of the geologist)

FDC/CNL/GR/DLL: TD - 3,200'

CBL: A cement bond log will be run from TD to the cement top of the production casing.
A field copy will be submitted to the Vernal BLM Office.

- b. **Cores:** As deemed necessary.
- c. **Drill Stem Tests:** No DSTs are planned in the Green River.

Drill stem tests, if they are run, will adhere to the following requirements: Initial opening of the drill stem test tools shall be restricted to daylight hours unless specific approval to start during other hours is obtained from the Authorized Officer (AO). However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vapor-proof for safe operations). Packers can be released but tripping shall not begin before daylight, unless prior approval is obtained from the AO. Closed chamber DSTs may be performed day or night.

Some means of reverse circulation shall be provided in case of flow to the surface showing evidence of hydrocarbons.

Separation equipment required for the anticipated recovery shall be properly installed before a test starts.

If a DST is performed, all engines within 100 feet of the wellbore that are required to be operational during the test shall have spark arresters or water-cooled exhausts.

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

a. **Drilling Activity**

Anticipated Commencement Date:	Upon approval of the site specific APD.
Drilling Days:	Approximately 7 days.
Completion Days:	Approximately 10 - 14 days.

b. **Notification of Operations**

The Vernal BLM office will be notified at least 24 hours **prior** to the commencement of spudding the well (to be followed with a Sundry Notice, Form 3160-5), of initiating pressure tests of the blowout preventer and related equipment, and running casing and cementing of all casing strings. Notification will be made during regular work hours (7:45 a.m.-4:30 p.m., Monday - Friday except holidays).

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the appropriate regulations, Onshore Orders, or BLM policy.

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in suspended status without

prior approval from the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given to the BLM before resumption of operations.

Daily drilling and completion reports shall be submitted to the Vernal BLM Office on a weekly basis.

Whether the well is completed as a dry hole or a producer, the "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. One copy of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the Authorized Officer (AO).

A completion rig will be used for completion operations after the wells are stimulated to run the production tubing. All conditions of this approved plan will be applicable during all operations conducted with the completion rig.

Operator shall report production data to the MMS pursuant to 30 CFR 216.5 using form MMS/3160. In accordance with Onshore Oil and Gas Order No. 1, a well will be reported on form 3160-6, "Monthly Report of Operations," starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report will be filed with the Vernal BLM Office.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated, or the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever occurs first; and for gas wells, as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated, or the date on which gas is measured through permanent metering facilities, whichever occurs first.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by written communication not later than 5 days following the date when the well is placed on production.

Pursuant to Onshore Order No. 7, with the approval of the AO, produced water may be temporarily disposed of into unlined pits for a period of up to 90 days. During this period, an application for approval of the permanent disposal method must be submitted to the AO.

Pursuant to NTL-4A, lessees or operators are authorized to vent/flare gas during the initial well evaluation tests, not to exceed 30 days or the production of 50 MMCF of gas, whichever occurs first. An application must be filed with the AO and approval received for any venting/flaring of gas beyond the initial 30 days or authorized test period.

A schematic facilities diagram, as required by 43 CFR 3162.7-5(b.9.d), shall be submitted to the Vernal BLM Office within 60 days of installation or first production, whichever occurs first. All site security regulations, as specified in Onshore Oil & Gas Order No. 3, shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5(b.4).

Well abandonment operations shall not be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval

will be obtained from the AO. A "Subsequent Report of Abandonment", Form 3160-5, will be filed with the Authorized Officer within 30 days following completion of the well for abandonment. This report will indicate placement of the plugs and current status of the surface restoration. Final Abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO, or the appropriate surface managing agency.

Pursuant to Onshore Oil and Gas Order No. 1, lessees and operators have the responsibility to see that their exploration, development, production, and construction operations are conducted in a manner which conforms with applicable Federal laws and regulations and with the State and local laws, to the extent to which they are applicable, to operations on Federal or Indian lands.

NEWFIELD PRODUCTION COMPANY
UTE TRIBAL 7-23-4-1
SW/NE SECTION 23 T4S, R1W
UINTAH COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site Ute Tribal 7-23-4-1 located in the SW¼ NE¼ Section 23, T4S, R1W, S.L.B. & M., Uintah County, Utah:

Proceed in a southwesterly direction out of Myton, Utah approximately 3.0 miles to it's junction with an existing road to the east; continue easterly and then southeasterly approximately 3.2 miles to it's junction with an existing road to the east; proceed easterly and then southeasterly approximately 3.2 miles to it's junction with an existing road to the east; proceed easterly approximately 1.6 ± to it's junction with an existing road to the north; proceed northerly approximately 0.6 miles ± to it's junction with the beginning of the proposed access road to the northeast; proceed northeasterly along the proposed access road approximately 860' to it's junction with an existing section of access road; proceed northeasterly approximately 730' ± to it's junction with the proposed access road to the southeast; proceed southeasterly along the proposed access road approximately 610' ± to the proposed well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

Approximately 1,470' of access road is proposed. See attached Topographic Map "B".

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to **EXHIBIT B**.

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck for drilling purposes from the following water sources:

Johnson Water District
Water Right: 43-10136

Neil Moon Pond
Water Right: 43-11787

Maurice Harvey Pond
Water Right: 47-1358

Newfield Collector Well
Water Right: 41-3530 (A30414DV, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve

pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. **ANCILLARY FACILITIES:**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) **Producing Location**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) **Dry Hole Abandoned Location**

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** Henderson Ranches LLC, Duchesne County, Utah.

12. **OTHER ADDITIONAL INFORMATION:**

Newfield Production Company requests 1,470' of disturbed area be granted to allow for construction of the planned access road. Refer to **Topographic Map "B"**. For the planned access road a temporary width of 60' will be needed for construction purposes with a permanent width of 30' and a running surface of 18'. The construction phase of the planned access road will last approximately (5) days. The planned access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%. There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road. There are no fences encountered along this proposed road. There will be no new gates or cattle guards required. All construction material for this access road will be borrowed material accumulated during construction of the access road.

Newfield Production Company requests 2,160' of disturbed area be granted to allow for construction of the proposed gas lines. It is proposed that the disturbed area will temporarily be 50' wide to allow for construction of a 6" gas gathering line, and a 3" poly fuel gas line, with a permanent width of 30' upon completion of the proposed gas lines. The construction phase of the proposed gas lines will last approximately (5) days. Both lines will tie in to the existing pipeline infrastructure. Refer to **Topographic Map "C."**

Newfield Production Company requests 5,000' of disturbed area be granted to allow for construction of the proposed water lines. It is proposed that the disturbed area will temporarily be 50' wide to allow for construction of a buried 3" steel water injection line and a buried 3" poly water return line and 30' wide upon completion of the proposed water lines. Refer to **Topographic Map "C."**

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.

- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

The Archaeological Report for the proposed location is attached.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the Ute Tribal 7-23-4-1, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Ute Tribal 7-23-4-1 Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office as well as the Ute Tribe Energy and Mineral Department shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Name: Kim Kettle
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #7-23-4-1, SW/NE Section 23, T4S, R1W, Uintah County, Utah and is responsible under the terms

and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by US Specialty Insurance #B002792.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


8/13/07
Date


Mandie Crozier
Regulatory Specialist
Newfield Production Company

NEWFIELD PRODUCTION COMPANY

WELL 7-23-4-1

Section 23, T4S, R1W, U.S.B.&M.



WELL HEAD:
UNGRADED =
FIN. GRADE =

Note:
Flare pit is to be
located a minimum
of 80' from well
head.

REFERENCE POINTS

- 210' SOUTHEASTERLY = 5047.0'
- 260' SOUTHEASTERLY = 5045.7'
- 170' SOUTHWESTERLY = 5049.2'
- 220' SOUTHWESTERLY = 5049.0'





SURVEYED BY: C.M.	SCALE: 1" = 50'
DRAWN BY: F.T.M.	DATE: 06-26-07

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD PRODUCTION COMPANY

CROSS SECTIONS

WELL 7-23-4-1



NOTE:
UNLESS OTHERWISE NOTED
ALL CUT/FILL SLOPES ARE
AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	600	600	Topsoil is not included in Pad Cut	0
PIT	640	0		640
TOTALS	1,240	600	930	640

SURVEYED BY: C.M.

SCALE: 1" = 50'

DRAWN BY: F.T.M.

DATE: 06-26-07

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501


NEWFIELD PRODUCTION COMPANY

TYPICAL RIG LAYOUT

WELL 7-23-4-1

PROPOSED ACCESS ROAD (Max. 6% Grade)

PREVAILING WIND




SURVEYED BY: C.M.

SCALE: 1" = 50'

DRAWN BY: F.T.M.

DATE: 06-26-07

Tri State (435) 781-2501
 Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078



NEWFIELD
Exploration Company

Well 7-23-4-1
SEC. 23, T4S, R1W, U.S.B.&M.




Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 = 100,000
DRAWN BY: mw
DATE: 06-26-2007

Legend

- Existing Road
- Proposed Access

TOPOGRAPHIC MAP
"A"



NEWFIELD
Exploration Company

Well 7-23-4-1
SEC. 23, T4S, R1W, U.S.B.&M.




Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 06-26-2007

Legend

Existing Road
Proposed Access

TOPOGRAPHIC MAP
"B"



NEWFIELD
Exploration Company

Well 7-23-4-1
SEC. 23, T4S, R1W, U.S.B.&M.


Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 06-26-2007

Legend

- Roads
- Proposed Gas Line
- Proposed Water Line

TOPOGRAPHIC MAP
"C"




- Newfield Wells**
- Location
 - ◐ Surface Spud
 - ⊕ Drilling
 - ▨ Waiting on Completion
 - ▤ Producing Oil Well
 - ▥ Producing Gas Well; GAB
 - ▧ Water Injection Well
 - ▩ Dry Hole
 - Temporarily Abandoned
 - Plugged & Abandoned
 - ▬ Shut In
 - ▭ Water Source Well
 - ▮ Water Disposal Well
 - ⊠ Injection Stations
- Unit Outlines**
- ▭

NEWFIELD
 ROCKY MOUNTAINS

Exhibit A
 Darken & Ulrich Counties

Alpine Plaza Building
 1431 17th Street, Suite 100
 Denver, Colorado 80202 USA
 Phone: (303) 425-8822

01/24/10 007



 **NEWFIELD**
Exploration Company

Well 7-23-4-1
SEC. 23, T4S, R1W, U.S.B&M.



 **Tri-State**
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 06-26-2007

Legend

- Location
- One-Mile Radius

Exhibit "B"

2-M SYSTEM
Blowout Prevention Equipment Systems




EXHIBIT C

Exhibit "D"

CULTURAL RESOURCE INVENTORY OF
NEWFIELD EXPLORATION'S PROPOSED WELL LOCATIONS
#7-19-4-1, #9-20-4-1, #15-20-4-1, AND #7-23-4-1
(T4S, R1W, SECTIONS 19, 20, AND 23)
DUCHESNE AND UINTAH COUNTIES, UTAH

By:

Jacki A. Montgomery

Prepared For:

Utah Division of State History
Salt Lake City

Prepared Under Contract With:

Newfield Exploration Company
Rt. 3 Box 3630
Myton, UT 84052

Submitted By:

Montgomery Archaeological Consultants, Inc.
P.O. Box 219
Moab, Utah 84532

MOAC Report No. 07-297

August 16, 2007

United States Department of Interior (FLPMA)
Permit No. 07-UT-60122

State of Utah Public Lands Policy
Archaeological Survey Permit No. 117

State of Utah Antiquities Project (Survey)
Permit No. U-07-MQ-1004p

**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 09/14/2007

API NO. ASSIGNED: 43-047-39634

WELL NAME: UTE TRIBAL 7-23-4-1
 OPERATOR: NEWFIELD PRODUCTION (N2695)
 CONTACT: MANDIE CROZIER

PHONE NUMBER: 435-646-3721

PROPOSED LOCATION:

SWNE 23 040S 010W
 SURFACE: 2314 FNL 2233 FEL
 BOTTOM: 2314 FNL 2233 FEL
 COUNTY: UINTAH
 LATITUDE: 40.12140 LONGITUDE: -109.9616
 UTM SURF EASTINGS: 588485 NORTHINGS: 4441538
 FIELD NAME: MONUMENT BUTTE (105)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 2 - Indian
 LEASE NUMBER: 20G0005609
 SURFACE OWNER: 4 - Fee

PROPOSED FORMATION: GRRV
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:


- Plat
- Bond: Fed[] Ind[2] Sta[] Fee[]
(No. B002792)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 43-10136)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)

LOCATION AND SITING:

- ___ R649-2-3.
- Unit: _____
- ___ R649-3-2. General
- Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- ___ Drilling Unit
- Board Cause No: _____
- Eff Date: _____
- Siting: _____
- ___ R649-3-11. Directional Drill

COMMENTS: Needs Permit (Rec'd 10/16/07)

STIPULATIONS: 1- Federal Approval
2- Spacing Waiver
3. SOB



OPERATOR: NEWFIELD PROD CO (N2695)
SEC: 23 T.4S R. 1W
FIELD: MONUMENT BUTTE (105)
COUNTY: DUCHESNE
SPACING: R649-3-3 / EXCEPTION LOCATION



- Field Status**
- ABANDONED
 - ACTIVE
 - COMBINED
 - INACTIVE
 - PROPOSED
 - STORAGE
 - TERMINATED

- Unit Status**
- EXPLORATORY
 - GAS STORAGE
 - NF PP OIL
 - NF SECONDARY
 - PENDING
 - PI OIL
 - PP GAS
 - PP GEOTHERML
 - PP OIL
 - SECONDARY
 - TERMINATED

- Wells Status**
- ✂ GAS INJECTION
 - ✂ GAS STORAGE
 - ✂ LOCATION ABANDONED
 - ✂ NEW LOCATION
 - ✂ PLUGGED & ABANDONED
 - ✂ PRODUCING GAS
 - ✂ PRODUCING OIL
 - ✂ SHUT-IN GAS
 - ✂ SHUT-IN OIL
 - ✂ TEMP. ABANDONED
 - ✂ TEST WELL
 - ✂ WATER INJECTION
 - ✂ WATER SUPPLY
 - ✂ WATER DISPOSAL
 - ✂ DRILLING



PREPARED BY: DIANA MASON
 DATE: 14-SEPTEMBER-2007

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

10/23/2007

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
572	43-047-39634-00-00		OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY	Surface Owner-APD			
Well Name	UTE TRIBAL 7-23-4-1	Unit			
Field	MONUMENT BUTTE	Type of Work			
Location	SWNE 23 4S 1W U 2314 FNL 2233 FEL	GPS Coord (UTM) 588485E 4441538N			

Geologic Statement of Basis

The Ute Tribe owns the mineral rights for the proposed well. The BLM will be the agency responsible for evaluating and approving the drilling, casing and cement programs.

Brad Hill
APD Evaluator

10/23/2007
Date / Time

Surface Statement of Basis

The proposed location is approximately 12 road miles southeast of Myton, UT in a sub-drainage of Pleasant Valley Wash which drains into the Pariette Draw drainage of Duchesne County. Both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 13 miles downstream from the location. Broad flats in Pleasant Valley frequently used for agriculture characterize the area. Flats are intersected by drainages with gentle to moderate side slopes. Access is by State and County and planned oil field development roads. Fourteen hundred and seventy feet of new construction across Henderson's private land will be required to reach the location.

The proposed Ute Tribal 7-23-4-1 oil well location is in Pleasant Valley on a non-irrigated site with nearby sprinkler irrigated fields. It is on a gentle greasewood covered flat with a very gentle slope to the east. Immediately east of the location is a pivot sprinkled alfalfa field. The reserve pit is planned on the edge of this field. Overall topography is essentially flat except for a slight rise about 200 yards west of the location. An area with riparian type vegetation (mostly salt grass) is located to the south. Location corner 8 should be rounded to miss this area. Also the portion of the topsoil stockpile shown for this area should be relocated. The location is outside the normal drilling window being moved about 330 to miss the alfalfa field. No draws intersect the location and no diversions will be required.

Henderson Ranches, LLC own the surface of the location. A Surface Use Agreement has not been reached with the Hendersons, however Mr. Wayne Henderson was contacted by Charles MacDonald of the BLM and gave permission to conduct the pre-site visit. Mr. Henderson was aware of the site selected and stated he would not attend the visit. The minerals are owned by the United States Government and held in trust for the Ute Indian Tribe. Michael Cutler of the BLM represented the Ute Indian Tribe. He had no additional concerns regarding the proposal not covered in the APD.

The location appears to be a suitable site for drilling and operating a well.

Floyd Bartlett
Onsite Evaluator

10/16/2007
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

10/23/2007

Page 2

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name UTE TRIBAL 7-23-4-1
API Number 43-047-39634-0 **APD No** 572 **Field/Unit** MONUMENT BUTTE
Location: 1/4,1/4 SWNE **Sec** 23 **Tw** 4S **Rng** 1W 2314 FNL 2233 FEL
GPS Coord (UTM) 588505 4441562 **Surface Owner**

Participants

Floyd Bartlett (DOGM), Kim Swasey (Newfield), Mike Cutler (BLM).

Regional/Local Setting & Topography

The proposed location is approximately 12 road miles southeast of Myton, UT in a sub-drainage of Pleasant Valley Wash which drains into the Pariette Draw drainage of Duchesne County. Both of these draws contain perennial streams somewhat consisting of irrigation runoff and seepage. Pariette Draw runs into the Green River approximately 6 miles downstream from Ouray, Utah and about 13 miles downstream from the location. Broad flats in Pleasant Valley frequently used for agriculture characterize the area. Flats are intersected by drainages with gentle to moderate side slopes. Access is by State and County and planned oil field development roads. Fourteen hundred and seventy feet of new construction across Henderson's private land will be required to reach the location.

The proposed Ute Tribal 7-23-4-1 oil well location is in Pleasant Valley on a non-irrigated site with nearby sprinkler irrigated fields. It is on a gentle greasewood covered flat with a very gentle slope to the east. Immediately east of the location is a pivot sprinkled alfalfa field. The reserve pit is planned on the edge of this field. Overall topography is essentially flat except for a slight rise about 200 yards west of the location. An area with riparian type vegetation (mostly salt grass) is located to the south. Location corner 8 should be rounded to miss this area. Also the portion of the topsoil stockpile shown for this area should be relocated. The location is outside the normal drilling window being moved about 330 to miss the alfalfa field. No draws intersect the location and no diversions will be required.

Surface Use Plan

Current Surface Use

Grazing
Wildlife Habitat

New Road

Miles	Well Pad	Src Const Material	Surface Formation
0.3	Width 199 Length 290	Onsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetland Y

Riparian type vegetation on one corner of location. Vegetation is mostly salt grass. Corner 8 to be rounded.

Flora / Fauna

Cattle, deer, prairie dogs, small mammals and birds.

Deseret shrub type consisting of greasewood, cheatgrass, mat saltbrush, and spring annuals.

Soil Type and Characteristics

Deep sandy clay loam.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diverson Required N

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? N

Paleo Potential Observed? N

Cultural Survey Run? Y

Cultural Resources? N

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet)	<25 or recharge area	20
Distance to Surface Water (feet)	300 to 1000	2
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	300 to 1320	10
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0

Final Score 47 1 **Sensitivity Level**

Characteristics / Requirements

40' x 80' x 8' deep located in an area of cut on the northeast side of the location. A pit liner is required. Newfield commonly uses a 16 mil liner.

Closed Loop Mud Required? N

Liner Required? Y

Liner Thickness 16

Pit Underlayment Required? Y

Other Observations / Comments

Floyd Bartlett
Evaluator

10/16/2007
Date / Time



RECEIVED
OCT 04 2007
DIV. OF OIL, GAS & MINING

October 1, 2007

State of Utah, Division of Oil, Gas & Mining
ATTN: Diana Mason
PO Box 145801
Salt Lake City, UT 84114-5801

43-047-39634

RE: Exception Location
Ute Tribal 7-23-4-1
T4S R1W, Section 23: SW/4NE/4
2314'FNL 2233' FEL
Uintah County, Utah

Dear Ms. Mason;

This letter is a revision of my previous letter dated September 27, 2007. Pursuant to Rule 649-3-3 of the Oil & Gas Rules and Regulations of the State of Utah, Newfield Production Company ("NPC") hereby requests an exception location for the drilling of the captioned well. The proposed drillsite for this well is located 143' south and 44' west of the drilling window required by Rule R649-3-2, which requires a well to be located in the center of a forty (40) acre quarter-quarter section, or a substantially equivalent lot or tract, with a tolerance of two hundred (200) feet in any direction from the center.

The attached plat depicts the proposed location and illustrates the deviation from the drilling window. The requested location has been chosen to accommodate the surface owner.

Please note the drillsite and all surrounding acreage within a four hundred sixty (460') foot radius is owned by NPC and The Ute Indian Tribe. You will find a copy of The Ute Indian Tribe's consent to this exception location attached to this letter.

If you have any questions or require further information, please do not hesitate to contact the undersigned at 303-382-4444 or by email at reveland@newfield.com. Your consideration of this matter is greatly appreciated.

Sincerely,

Roxann Eveland

Roxann Eveland
Land Associate

Attachment



UTE INDIAN TRIBE

Energy and Minerals Department

P.O. Box 70
988 South 7500 East
Fort Duchesne, Utah 84026

September 17, 2007

Phone: 435-725-4950
Fax: 435-725-4970
Email: energy_minerals@utetribe.com

Mr. Gil Hunt, Director, Oil & Gas
Utah Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

Re: Newfield Production Company Exception Locations – Monument Buttes

Gentleman:

Due to topographic or environmental situations, Newfield has had to stake certain obligation wells for 2007 in areas that require an exception location approval from the Utah Division of Oil, Gas & Mining along with Tribal concurrence for same.

Attached are twelve (12) letters, along with accompanying support data, from Newfield to the Tribe requesting Tribal consent for twelve (12) exception locations. The twelve (12) exception locations requiring Tribal consent are as follows: Ute Tribal 10-21-4-1, 9-20-4-1, 8-25-4-1, 6-25-4-1, 2-1-5-1, 4-1-5-1, 3-1-5-1, 7-19-4-1, 7-23-4-1, 16-35-4-1, 4-8-5-2 and the 2-7-5-2.

Pursuant to Tribal Business Committee Resolution 06-217 dated October 25, 2006, the Tribe entered into an Exploration and Development Agreement with Newfield Production Company effective February 23, 2007. Under this contract, Newfield is required to drill twelve (12) wells per year in order to meet its contractual obligations with the Tribe.

By this letter, the Tribe hereby consents to Newfield's proposed exception locations and requests that your Agency approve same.

Thank you for your consideration in this matter. If you have any questions or need any additional information, please contact Mr. Lynn Becker, Director, Energy and Minerals Department at 435-725-4972.

Curtis Cesspooch
Chairman, Tribal Business Committee

Cc: Dinah Peltier-BIA

William Stringer-BLM

Kelly Donohoue-Newfield

RECEIVED

OCT 04 2007

DIV. OF OIL, GAS & MINING



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah
DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil Gas and Mining

JOHN R. BAZA
Division Director

January 14, 2008

Newfield Production Company
Rt. #3, Box 3630
Myton, UT 84052

Re: Ute Tribal 7-23-4-1 Well, 2314' FNL, 2233' FEL, SW NE, Sec. 23, T. 4 South,
R. 1 West, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39634.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal Office

Operator: Newfield Production Company

Well Name & Number Ute Tribal 7-23-4-1

API Number: 43-047-39634

Lease: 2OG0005609

Location: SW NE Sec. 23 T. 4 South R. 1 West

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 (801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

RECEIVED
 VERNAL FIELD OFFICE
 SEP 12 2007

Form 3160-3
 (September 2001)

UNITED STATES
 DEPARTMENT OF THE INTERIOR
 BUREAU OF LAND MANAGEMENT

DEPT. OF THE INTERIOR
 BUREAU OF LAND MGMT.

FORM APPROVED
 OMB No. 1004-0136
 Expires January 31, 2004

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 20G0005609
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name Ute
2. Name of Operator Newfield Production Company		7. If Unit or CA Agreement, Name and No. N/A
3a. Address Route #3 Box 3630, Myton UT 84052	3b. Phone No. (include area code) (435) 646-3721	8. Lease Name and Well No. Ute Tribal 7-23-4-1
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SW/NE 2314' FNL 2233' FEL At proposed prod. zone		9. API Well No. 43 0A7 3963A
14. Distance in miles and direction from nearest town or post office* Approximatley 12.0 miles southeast of Myton, Utah		10. Field and Pool, or Exploratory Monument Butte
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) Approx. 326' f/lse, NA' f/unit	16. No. of Acres in lease NA	11. Sec., T., R., M., or Blk. and Survey or Area SW/NE Sec. 23, T4S R1W
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. NA	19. Proposed Depth 6950'	12. County or Parish Uintah
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5048' GL	22. Approximate date work will start* 4th Quarter 2007	13. State UT
23. Estimated duration Approximately seven (7) days from spud to rig release.		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) Mandie Crozier	Date 8/13/07
Title Regulatory Specialist		
Approved by (Signature) 	Name (Printed/Typed) Terry Kenicka	Date 4-18-2008
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

RECEIVED
 APR 24 2008
 DIV. OF OIL, GAS & MINING



**UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE**

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Newfield Production Company
Well No: Ute Tribal 7-23-4-1
API No: 43-047-39634

Location: SWNE, Sec 23, T4S, R1E
Lease No: 2OG0005609
Agreement: N/A

Title	Name	Office Phone Number	Cell Phone Number
Petroleum Engineer:	Matt Baker	(435) 781-4490	(435) 828-4470
Petroleum Engineer:	Michael Lee	(435) 781-4432	(435) 828-7875
Petroleum Engineer:	James Ashley	(435) 781-4470	(435) 828-7874
Petroleum Engineer:	Ryan Angus	(435) 781-4430	(435) 828-7368
Supervisory Petroleum Technician:	Jamie Sparger	(435) 781-4502	(435) 828-3913
NRS/Enviro Scientist:		(435) 781-4475	(435) 828-4029
NRS/Enviro Scientist:	Karl Wright	(435) 781-4484	(435) 828-7381
NRS/Enviro Scientist:	Holly Villa	(435) 781-4404	(435) 828-3544
NRS/Enviro Scientist:		(435) 781-4476	
NRS/Enviro Scientist:	Chuck Macdonald	(435) 781-4441	(435) 828-7482
NRS/Enviro Scientist:		(435) 781-3400	(435) 828-3544
NRS/Enviro Scientist:	Michael Cutler	(435) 781-3401	(435) 828-3546
NRS/Enviro Scientist:	Anna Figueroa	(435) 781-3407	(435) 828-3548
NRS/Enviro Scientist:	Verlyn Pindell	(435) 781-3402	(435) 828-3547
NRS/Enviro Scientist:	Darren Williams	(435) 781-4447	(435) 828-4029
NRS/Enviro Scientist:	Nathan Packer	(435) 781-3405	(435) 828-3545

Fax: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Construction Activity	-	The Ute Tribe Energy & Minerals Dept. shall be notified in writing 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion	-	Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM
 CONDITIONS OF APPROVAL (COAs)**

Specific Surface COAs

- Adhere to all private surface agreements.
- All traffic related to this action will be restricted to approved routes. Cross-country vehicle travel will not be allowed.
- Pipelines will be buried at all major drainage crossings.
- Prevent fill and stock piles from entering drainages.
- Any hydrocarbons in the reserve pit will be removed **immediately** upon well completion; in accordance with Monument Butte SOP. Pits must be free of oil and other liquid and solid wastes prior to filling.
- Monument Butte SOP, Section 9.2 - Pit Fencing Minimum Standards - will be strictly adhered to. To include 9.2.2.3 - Corner posts will be cemented and/or braced in such a manner as to keep fence tight at all times.
- If Uinta Basin hookless cactus or other special status plants are found, construction will cease and the AO will be notified to determine the appropriate mitigation.

Interim Reclamation:

The topsoil from the reserve pit shall be stripped and piled separately near the reserve pit. When the reserve pit is closed, it shall be recontoured and the topsoil respread, and the area shall be **seeded using a rangeland drill**. Seeding depth as per AO, or seed distributor. If portions of the site are too steep (>40%), or rocky, that portion may be broadcast seeded. If broadcasting seed, the seed shall be walked into the soil with a dozer immediately after the seeding is completed, or covered by soil using a drag chain. Seeding shall occur in the fall (August 1st until snow or ground is frozen) with the following seed mix:

Seed mix (or landowners designated seed mix):

Common name	Latin name	lbs/acre	Recommended seed planting depth
Squirreltail grass	<i>Elymus elymoides</i>	3.0	¼ - ½"
Siberian wheatgrass	<i>Agropyron fragile</i>	1.0	½"
Shadscale saltbush	<i>Atriplex confertifolia</i>	0.50	½"
Four-wing saltbush	<i>Atriplex canescens</i>	0.50	½"
Gardner's saltbush	<i>Atriplex gardneri</i>	0.50	½"
Scarlet globemallow	<i>Sphaeralcea coccinea</i>	0.10	⅛ - ¼"
Forage Kochia	<i>Kochia prostrates</i>	0.10	⅛ - ¼"

- All pounds are pure live seed.
- All seed and mulch will be certified weed free.
- Rates are set for drill seeding; double rate if broadcasting.
- Reseeding may be required if initial seeding is not successful.

Final reclamation:

Once the location is plugged and abandoned, the well location, access, and any disturbed areas shall be recontoured to natural topography, topsoil shall be respread, and the entire location shall be seeded following guidelines in the seed mix bullet statement above. Final seed mix: same as interim.

- Noxious and/or invasive weeds will be controlled along access roads, pipelines, well sites, and all other applicable facilities. Any noxious and/or invasive weeds outbreak, directly attributed to the activities of the Operator, will be the responsibility of the Operator to control.
- The topsoil from the reserve pit shall be stripped and piled separately near the reserve pit. When the reserve pit is closed, it shall be recontoured and the topsoil respread, and the area shall be seeded in the same manner as the location topsoil.
- Once the location is plugged and abandoned, it shall be recontoured to natural topology, topsoil shall be respread, and the entire location shall be seeded with a seed mix recommended by the AO (see above). Seed application will follow all guidelines in the interim seed mix bullet statement above.
- All well facilities not regulated by OSHA will be painted Carlsbad Canyon.
- Notify the Authorized Officer 48 hours prior to surface disturbing activities.

DOWNHOLE CONDITIONS OF APPROVAL

SITE SPECIFIC DOWNHOLE CONDITIONS OF APPROVAL

- Logging: Run gamma ray and electric logs from TD to surface casing.
- Ute Tribal 7-23-4-1, Revised
- Logging: Run gamma ray and electric logs from TD to surface casing.
- Variances Granted:
- See attached sheet.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB

or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid,

and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: Newfield Production Company

Well Name: Ute Tribal 7-23-4-1

API No: 43-047-39634 Lease Type: Federal/Fee

Section 23 Township 04S Range 01W County Uintah

Drilling Contractor Ross Rig Rig # 21

SPUDDED:

Date 5-02-08

Time 8:30 PM

How Dry

Drilling will Commence: _____

Reported by Troy

Telephone # 435-823-6012

Date 5-05-08 Signed RM

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR: NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630
MYTON, UT 84052

OPERATOR ACCT. NO. N2695

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION				SPUD DATE	EFFECTIVE DATE	
					Q2	SC	TP	RG			COUNTY
A	99999	16842	4304736244	FEDERAL 6-30-8-18	SENW	30	8S	18E	UINTAH	4/30/2008	5/8/08
WELL 1 COMMENTS: <i>GRRV</i>											
A	99999	16843	4301333854	STATE 16-16-9-16	SESE	16	9S	16E	DUCHESNE	4/30/2008	5/8/08
WELL 1 COMMENTS: <i>GRRV</i>											
A	99999	16844	4301333234	FEDERAL 15-20-9-17	SWSE	20	9S	17E	DUCHESNE	5/1/2008	5/8/08
WELL 1 COMMENTS: <i>GRRV</i>											
B	99999	14844	4304734287	SUNDANCE FED 14-31-8-18	NESW SESW	31	8S	18E	UINTAH	5/3/2008	5/8/08
WELL 1 COMMENTS: <i>GRRV</i> <i>BHL = SESW</i>											
A	99999	16845	4301333233	FEDERAL 14-20-9-17	SESW	20	9S	17E	DUCHESNE	5/5/2008	5/8/08
WELL 5 COMMENTS: <i>GRRV</i>											
A	99999	16846	4304739634	UTE TRIBAL 7-23-4-1	SWNE	23	4S	1W	DUCHESNE UINTAH	5/2/2008	5/8/08
WELL 5 COMMENTS: <i>GRRV</i>											

ACTION CODES (See instructions on back of form)
 A - new entity for new well (single well only)
 B - well is existing entity (group or unit well)
 C - from one existing entity to another existing entity
 D - well from one existing entity to a new entity
 E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED
MAY 08 2008

DIV. OF OIL, GAS & MINING

Jerry Park
 Signature: _____
 Production Clerk: _____
 Date: 05/08/08

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
 NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630
 Myton, UT 84052

3b. Phone (include are code)
 435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
 Section 23 T4S R1W

5. Lease Serial No.
 UTE TRIBE EDA 20G0005609

6. If Indian, Allottee or Tribe Name.
UTE TRIBAL 7-23-4-1

7. If Unit or CA/Agreement, Name and/or

8. Well Name and No.
 UTE TRIBAL 7-23-4-1

9. API Well No.
 4304739634

10. Field and Pool, or Exploratory Area
 MONUMENT BUTTE

11. County or Parish, State
 Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Spud Notice _____
	<input type="checkbox"/> Convert to	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	_____

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 5/2/08 MIRU Ross #21. Spud well @ 8:30am. Drill 310' of 12 1/4" hole with air mist. TIH w/7 jt's 85/8" j-55 24# csgn. set @ 317.115kb. On 4/15/08 cement with 160 sks of class "G" w/ 3% CaCL2 + 1/4# sk Cello-Flake mixed @15.8 ppg>1.17 cf/sk yeild. Returned 3 bbls cement to pit. Woc.

I hereby certify that the foregoing is true and correct (Printed/ Typed)
 Jay Burton
 Signature *Jay E. Burton*

Title
 Drilling Foreman

Date
 05/08/2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____
 Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title _____ Date _____
 Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED

MAY 12 2008

DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 317.15

LAST CASING 8 5/8" SET AT 317.15'
 DATUM 12' KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 310 LOGGER _____
 HOLE SIZE 12 1/4

OPERATOR NewField Production Company
 WELL Ute Tribal 7-23-4-1
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # Ross # 21

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		Shoe Joint 41.87'					
		WHI - 92 csg head			8rd	A	0.95
7	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	306.25
		GUIDE shoe			8rd	A	0.9
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING			307.15
TOTAL LENGTH OF STRING		307.15	7	LESS CUT OFF PIECE			2
LESS NON CSG. ITEMS		1.85		PLUS DATUM TO T/CUT OFF CSG			12
PLUS FULL JTS. LEFT OUT		0		CASING SET DEPTH			317.15
TOTAL		305.3	7	} COMPARE			
TOTAL CSG. DEL. (W/O THRDS)		305.3	7				
TIMING		1ST STAGE		GOOD CIRC THRU JOB			yes
BEGIN RUN CSG.		Spud		Bbls CMT CIRC TO SURFACE			3
CSG. IN HOLE				RECIPROCATED PIPE FOR			THRU FT STROKE
BEGIN CIRC		11:00 AM		BUMPED PLUG TO			didn't bump 127 PSI
BEGIN PUMP CMT		11:10 AM					
BEGIN DSPL. CMT		11:22 AM					
PLUG DOWN		11:29 AM					

CEMENT USED		160 SKS	CEMENT COMPANY-	B. J.
STAGE	# SX	CEMENT TYPE & ADDITIVES		
1	160	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield		

CENTRALIZER & SCRATCHER PLACEMENT	SHOW MAKE & SPACING
Centralizers - Middle first, top second & third for 3	

COMPANY REPRESENTATIVE Jay Burton DATE 5/7/2008

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630
Myton, UT 84052

3b. Phone (include are code)
435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Section 23 T4S R1W

5. Lease Serial No.
UTE TRIBE EDA 20G0005609
6. If Indian, Allottee or Tribe Name.
7. If Unit or CA/Agreement, Name and/or
8. Well Name and No.
UTE TRIBAL 7-23-4-1
9. API Well No.
4304739634
10. Field and Pool, or Exploratory Area
MONUMENT BUTTE
11. County or Parish, State
UINTAH, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Weekly Status Report
	<input type="checkbox"/> Convert to	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 5/14/08 MIRU Patterson # 155. Set all equipment. Pressure test Kelly, TIW, Choke manifold, & Bop's to 2,000 psi. Test 8.625 csgn to 1,500 psi. Vernal BLM field, & Roosevelt DOGM office was notified of test. PU BHA and tag cement @ 275'. Drill out cement & shoe. Drill a 7.875 hole with fresh water to a depth of 6850'. Lay down drill string & BHA. Open hole log w/ Dig/SP/GR log's TD to surface. PU & TIH with Guide shoe, shoe jt, float collar, 167 jt's of 5.5 J-55, 15.5# csgn. Set @ 6826.69' / KB. Cement with 375 sks cement mixed @ 11.0 ppg & 3.49 yld. Then 475 sks cement mixed @ 14.4 ppg & 1.24 yld. Returned 52 bbls of cement to reserve pit. Nipple down Bop's. Drop slips @ 118,000 #'s tension. Release rig @ 12:30 AM on 5/22/08.

I hereby certify that the foregoing is true and correct (Printed/ Typed)

Melvin Zufelt

Signature

Title

Drilling Supervisor

Date

05/22/2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Office

Date

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED
MAY 27 2008

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

5 1/2" CASING SET AT 6826.69

Flt cllr @ 5765.51'

LAST CASING 8 5/8" SET # 317

OPERATOR Newfield Production Company

DATUM 12' KB

WELL Ute Tribal 7-23-4-1

DATUM TO CUT OFF CASING 12'

FIELD/PROSPECT Monument Butte

DATUM TO BRADENHEAD FLANGE _____

CONTRACTOR & RIG # Patterson #155

TD DRILLER 6850 Loggers 6835

HOLE SIZE 7 7/8"

LOG OF CASING STRING:							
PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		Landing Jt					14
		Short jt 4782' (6.97)					
166	5 1/2"	ETC LT & C casing	15.5#	J-55	8rd	A	6790.01
		Float collar					0.6
1	5 1/2"	ETC LT&C csg	15.5#	J-55	8rd	A	41.43
		GUIDE shoe			8rd	A	0.65
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING			6846.69
TOTAL LENGTH OF STRING		6846.69	167	LESS CUT OFF PIECE			32
LESS NON CSG. ITEMS		15.25		PLUS DATUM TO T/CUT OFF CSG			12
PLUS FULL JTS. LEFT OUT		298.72	7	CASING SET DEPTH			6826.69
TOTAL		7130.16	174	} COMPARE			
TOTAL CSG. DEL. (W/O THRDS)		7130.16	174				
TIMING		1ST STAGE	2nd STAGE				
BEGIN RUN CSG.		9:00 AM	5/21/2008	GOOD CIRC THRU JOB			YES
CSG. IN HOLE		3:00 PM	5/21/2008	Bbls CMT CIRC TO SURFACE			52
BEGIN CIRC		3:15 PM	5/21/2008	RECIPROCATED PIPE FOR			THRUSTROKE NA
BEGIN PUMP CMT		5:56 PM	5/21/2008	DID BACK PRES. VALVE HOLD ?			YES
BEGIN DSPL. CMT		6:55 PM	5/21/2008	BUMPED PLUG TO			1750 PSI
PLUG DOWN		7:18 PM	5/21/2008				
CEMENT USED		CEMENT COMPANY- B. J.					
STAGE	# SX	CEMENT TYPE & ADDITIVES					
1	375	Premlite II w/ 10% gel + 3 % KCL, 3#s /sk CSE + 2# sk/kolseal + 1/2#s/sk Cello Flake					
		mixed @ 11.0 ppg W / 3.43 cf/sk yield					
2	475	50/50 poz W/ 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM mixed @ 14.4 ppg W/ 1.24 YLD					
CENTRALIZER & SCRATCHER PLACEMENT			SHOW MAKE & SPACING				
Centralizers - Middle first, top second & third. Then every third collar for a total of 20.							

COMPANY REPRESENTATIVE Jay Burton

DATE 5/21/2008

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTE TRIBE EDA 20G0005609

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

1. TYPE OF WELL: OIL WELL GAS WELL OTHER

8. WELL NAME and NUMBER:
UTE TRIBAL 7-23-4-1

2. NAME OF OPERATOR:
NEWFIELD PRODUCTION COMPANY

9. API NUMBER:
4304739634

3. ADDRESS OF OPERATOR:
Route 3 Box 3630 CITY Myton STATE UT ZIP 84052

PHONE NUMBER
435.646.3721

10. FIELD AND POOL, OR WILDCAT:
MONUMENT BUTTE

4. LOCATION OF WELL:

FOOTAGES AT SURFACE:

COUNTY: UINTAH

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: , 23, T4S, R1W

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 07/15/2008	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above subject well was completed on 06-18-08, attached is a daily completion status report.

NAME (PLEASE PRINT) Jentry Park

TITLE Production Clerk

SIGNATURE 

DATE 07/15/2008

(This space for State use only)

RECEIVED

JUL 28 2008

DIV. OF OIL, GAS & MINING

Daily Activity Report

Format For Sundry

UTE TRIBAL 7-23-4-1

4/1/2008 To 8/30/2008

6/5/2008 Day: 1

Completion

Rigless on 6/4/2008 - Install 5M frac head. NU 6" 5M Cameron BOP. RU H/O truck & pressure test casing, blind rams, frac head & casing valves to 4500 psi. RU Perforators LLC WLT w/ mast & run CBL under pressure. WLTD @ 6730' & cement top @ 110'. PU & RIH w/ 22' perf gun. Tagged cement @ 6730'. Tried to work perf gun down. Work down to 6733'. Unable to get deep enough to perf BS CARB zone @ 6748- 6770'. Decision was made to drill out cement. RD WL. 161 BWTR. SIFN.

6/7/2008 Day: 2

Completion

Rigless on 6/6/2008 - Move in Western rig #1. Location was really muddy. Chain up rig. Tried to spot in to WH, Unable to get back to WH. NPC Backhoe came in to do dirt work on location. Move rig & equipment out of the way. Location will be ready on Monday AM. 161 BWTR. SIFN.

6/10/2008 Day: 3

Completion

Western #1 on 6/9/2008 - MIRUSU. ND Cameron BOP's & frac head. Instal 3K production tbg head & Scheafer BOP's. RU 4-3/4" Smith rock bit & bit sub. Unload tbg onto racks. Tally, pickup & TIH w/ new 2-7/8, J-55, 6.5# tbg to tag cement @ 6763'. RU pump, tanks & swivel. C/O to PBDT @ 6784'. TOOH w/ 2 jts tbg. Lost pad on rig in mud. Will rig down in morning & repair pad. SIFN.

6/11/2008 Day: 4

Completion

Western #1 on 6/10/2008 - RD rig. Haul rock in & build pad. RU rig. TOOH w/ tbg. RD Schaffer BOP's & production head. Instal frac head & Cameron BOP's. Test head & BOP's to 4500 psi. RU Perforators LLC. WLT & lubricator. RIH w/ 22' & 8', 14' perf guns & perforate BLS sds @ 6748-70', 6720-28', 6696-6710' w/ 3-1/8" Slick Guns (19 gram, .49"HE, 120°) w/ 4 spf for total of 176 holes. RU BJ Sevices "Ram Head" frac flange & frac BLS sds, stage #1 down casing w/ 79,783#'s of 20/40 sand in 818 bbls of Lightning 17 frac fluid. Perfs broke down @ 2995 psi. Pump 30 gals of Techna Hib chemical. Treated @ ave pressure of 3168 w/ ave rate of 24.3 bpm w/ 6 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 3730. 979 bbls EWTR. Leave pressure on well. SIFN.

6/12/2008 Day: 5

Completion

Western #1 on 6/11/2008 - RU Perforators LLC. WLT & lubricator. RIH w/ Weatherford 5-1/2" (6K) composite flow through frac plug & 10' perf guns. Set plug @ 6630'. Perforate CP4 sds @ 6524-34' w/ 4 spf for total of 40 holes. RU BJ & perfs won't break down. RIH & spot 10 gals of 15% HCL acid on perfs. RU BJ & frac stage #2 w/ 24,578#'s of 20/40 sand in 392 bbls of Lightning 17 frac fluid. Open well w/ 1840 psi on casing. Perfs broke down @ 3306 psi. Pump 30 gals of Techna Hib chemical. Treated @ ave pressure of 2179 w/ ave rate of 23.5 bpm w/ 6.5 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 2290. 1371 bbls EWTR. Leave pressure on well. RU WLT. RIH w/ frac plug & 20' & 9' perf guns. Set plug @ 6470'. Perforate CP2 sds @ 6384-6404' & CP1 sds @ 6357-66' w/ 4 spf for total of 116 holes. RU BJ & frac stage #3 w/ 90,277#'s of 20/40 sand in 731 bbls

of Lightning 17 frac fluid. Open well w/ 1800 psi on casing. Perfs broke down @ 2392 psi. Pump 30 gals of Techna Hib chemical. Treated @ ave pressure of 1741 w/ ave rate of 26.4 bpm w/ 8 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 1990. 2102 bbls EWTR. Leave pressure on well. RU WLT. RIH w/ frac plug & 14', 10', 24', 10' perf guns. Set plug @ 6150'. Perforate A3 sds @ 6036-50' & A1 sds @ 6014-24', 5986-6010', 5974-84' w/ 4 spf for total of 232 holes (in 4 runs due to breaking down). RU BJ & frac stage #4 w/ 175,568#'s of 20/40 sand in 1233 bbls of Lightning 17 frac fluid. Open well w/ 1518 psi on casing. Perfs broke down @ 1625 psi. Pump 30 gals of Techna Hib chemical. Treated @ ave pressure of 1840 w/ ave rate of 26.2 bpm w/ 8 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 2100. 3335 bbls EWTR. Leave pressure on well. RU WLT. RIH w/ frac plug & 8' perf gun. Set plug @ 5730'. Perforate D3 sds @ 5620-28' w/ 4 spf for total of 32 holes. RU BJ & perfs won't break down. RIH & spot 10 gals of 15% HCL acid on perfs (in 2 runs due to misfire). RU BJ & frac stage #5 w/ 19,840#'s of 20/40 sand in 323 bbls of Lightning 17 frac fluid. Open well w/ 1623 psi on casing. Perfs broke down @ 2882 psi. Pump 30 gals of Techna Hib chemical. Treated @ ave pressure of 2028 w/ ave rate of 26.1 bpm w/ 6.5 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 1785. 3658 bbls EWTR. Leave pressure on well. SIFN.

6/13/2008 Day: 6

Completion

Western #1 on 6/12/2008 - RU WLT. RIH w/ frac plug & 8', 10' perf guns. Set plug @ 5560'. Perforate D1 sds @ 5486-94' & DS3 sds @ 5416-26' w/ 4 spf for total of 72 holes. RU BJ & frac stage #6 w/ 50,407#'s of 20/40 sand in 469 bbls of Lightning 17 frac fluid. Open well w/ 230 psi on casing. Perfs broke down @ 750 psi. Pump 30 gals of Techna Hib chemical. Treated @ ave pressure of 1773 w/ ave rate of 26 bpm w/ 8 ppg of sand. Spot 12 bbls of 15% HCL acid in flush for next stage. ISIP was 2300. 4127 bbls EWTR. Leave pressure on well. RU WLT. RIH w/ frac plug & 20' perf gun. Set plug @ 5100'. Perforate GB4 sds @ 4974-94' w/ 4 spf for total of 80 holes. RU BJ & frac stage #7 w/ 84,170#'s of 20/40 sand in 701 bbls of Lightning 17 frac fluid. Open well w/ 1655 psi on casing. Perfs broke down @ 2266 psi. Pump 30 gals of Techna Hib chemical. Treated @ ave pressure of 1772 w/ ave rate of 26.3 bpm w/ 8 ppg of sand. ISIP was 1900. Flow well back. Well flowed for 7 hours & turned to oil & gas w/ 600 bbls rec'd. SIFN.

6/14/2008 Day: 7

Completion

Western #1 on 6/13/2008 - Open well w/ 640 psi on casing. Well flowing 425 psi w/ 20/64 choke. RU PSI WLT & lubricator. RIH w/ Weatherford 5-1/2" solid composite plug (6K). Set plug @ 4900'. RD WLT. RD Cameron BOP's & frac head. Instal production tbg head & Schaffer BOP's. RU 4-3/4" Chomp mill & x-over sub. TIH w/ tbg to tag plug @ 4900'. RU swivel, pump & tanks. W/ 120 bbls rec'd. SIFN.

6/17/2008 Day: 8

Completion

Western #1 on 6/16/2008 - Open well w/ 0 psi on casing. Drlg out plug @ 4900'. TIH w/ tbg to tag plug @ 5100'. Drlg out plug #1. TIH w/ tbg to tag plug @ 5560'. Drlg out plug #2. TIH w/ tbg to tag plug @ 5730'. Drlg out plug #3. TIH w/ tbg to tag plug @ 6150'. Drlg out plug #4. TIH w/ tbg to tag plug @ 6470'. Drlg out plug #5. TIH w/ tbg to tag sand @ 6591'. C/O to plug @ 6630'. Drlg out plug #6. TIH w/ tbg to tag sand @ 6640'. C/O to PBD @ 6784'. LD 2 jts tbg. RU swab equipment. EOT @ 6725'. Made 1 swab run & well flowed back 120 bbls. SIFN.

6/18/2008 Day: 9

Completion

Western #1 on 6/17/2008 - Bleed pressure off well. Flowing oil steadily. Bleed off to production tks. Circ hole W/ clean production wtr---stays flowing steady. RU & circ hole W/ 180 bbls 10# brine wtr. Estimated wtr loss of 75 bbls during both circulations. Well static. TIH W/ tbg. Tag PBD @ 6784' (no new fill). LD excess tbg. TOH W/ tbg--LD bit. TIH W/ BHA & production tbg as follows: 2 7/8 bullplug/collar, 4 jts tbg, 2 7/8 nipple, "Collar sized" gas anchor, 1 jt tbg, SN, 2 jts tbg, new CDI 5 1/2" TA (45K) & 205 jts 2 7/8 8rd 6.5# J-55 tbg. ND BOP. Set TA @ 6455' W/ SN @ 6520' & EOT @ 6685'. Land tbg W/ 16,000# tension. NU wellhead. Flush tbg W/ 60 bbls brine wtr (returned 50 bbls). PU & TIH W/ pump and "A" grade rod string to 1700'. PU polished rod & SIFN W/ est 4188 BWTR.

6/19/2008 Day: 10

Completion

Western #1 on 6/18/2008 - Con't PU & TIH W/ pump and "A" grade rod string f/ 1700' (complete as follows): new CDI 2 1/2" X 1 3/4" X 20' pump, 1 5/8" X 21K shear cplg, 6-1 1/2" weight rods, 20-3/4" scraped rods, 135-3/4" plain rods, 98-7/8" scraped rods, 1-8', 1-6', 1-4' & 1-2' X 7/8" pony rods and 1 1/2" X 26' polished rod. Seat pump & RU pumping unit. Fill tbg W/ 2 BW. Pressure test tbg & pump to 200 psi. Stroke pump up W/ unit to 800 psi. Good pump action. RD MOSU. Est 4188 BWTR. Place well on production @ 11:30 AM 6/18/2008 W/ 86" SL @ 5 SPM. FINAL REPORT!!

Pertinent Files: Go to File List

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WORK

OIL WELL [X] GAS WELL [] DRY [] Other []

1b. TYPE OF WELL

NEW WELL [X] WORK OVER [] DEEPEN [] PLUG BACK [] DIFF RESVR. [] Other []

2. NAME OF OPERATOR

Newfield Exploration Company

3. ADDRESS AND TELEPHONE NO.

1401 17th St. Suite 1000 Denver, CO 80202

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.*)

At Surface 2314' FNL & 2233' FEL (SW/NE) Sec. 23, T4S, R1W
At top prod. Interval reported below

At total depth

14. API NO. 43-047-39634 DATE ISSUED 01/14/08

12. COUNTY OR PARISH Uintah 13. STATE UT

15. DATE SPUDDED 05/02/08 16. DATE T.D. REACHED 05/19/08 17. DATE COMPL. (Ready to prod.) 06/18/08 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 5048'GL 5060'KB 19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD 6850' 21. PLUG BACK T.D., MD & TVD 6784' 22. IF MULTIPLE COMPL., HOW MANY* 23. INTERVALS DRILLED BY -----> 23. INTERVALS ROTARY TOOLS X 23. INTERVALS CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)* Green River 4974'-6770' 25. WAS DIRECTIONAL SURVEY MADE No

26. TYPE ELECTRIC AND OTHER LOGS RUN Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log 27. WAS WELL CORED No

Table with 6 columns: CASING SIZE/GRADE, WEIGHT, LB./FT., DEPTH SET (MD), HOLE SIZE, TOP OF CEMENT, CEMENTING RECORD, AMOUNT PULLED. Rows include 8-5/8" - J-55 and 5-1/2" - J-55.

Table with 8 columns: SIZE, TOP (MD), BOTTOM (MD), SACKS CEMENT*, SCREEN (MD), SIZE, DEPTH SET (MD), PACKER SET (MD). Rows include 2-7/8" and 6685'.

Table with 6 columns: INTERVAL, SIZE, SPF/NUMBER, DEPTH INTERVAL (MD), AMOUNT AND KIND OF MATERIAL USED. Rows include (BLS) 6748'-70', 6720'-28', 6696'-6710' and (CP4) 6524'-34'.

Table with 8 columns: DATE FIRST PRODUCTION, PRODUCTION METHOD, WELL STATUS, DATE OF TEST, HOURS TESTED, CHOKER SIZE, PROD'N. FOR TEST PERIOD, OIL--BBL., GAS--MCF., WATER--BBL., GAS-OIL RATIO. Includes 'RECEIVED' stamp and date AUG 04 2008.

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Used for Fuel TEST WITNESSED BY AUG 04 2008

35. LIST OF ATTACHMENTS DIV. OF OIL, GAS & MINING

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records. SIGNED Jentri Park TITLE Production Tech DATE 8/1/2008

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	GEOLOGIC MARKERS	
				NAME	TOP
				MEAS. DEPTH	TRUE VERT. DEPTH
			<p style="text-align: center;">Well Name Ute Tribal 7-23-4-1W</p>	Garden Gulch Mkr	4467'
				Garden Gulch 1	4654'
				Garden Gulch 2	4773'
				Point 3 Mkr	5076'
				X Mkr	5284'
				Y-Mkr	5325'
				Douglas Creek Mkr	5462'
				BiCarbonate Mkr	5757'
				B Limestone Mkr	5896'
				Castle Peak	6299'
			Basal Carbonate	6693	
			Wasatch	NDE	
			Total Depth (LOGGERS)	6835'	

NEWFIELD



Well Name: Ute Tribal 7-23-4-1
 LOCATION: S23, T4S, R1E
 COUNTY/STATE: Uintah
 API: 43-047-39634

Spud Date: 5-2-08
 TD: 6850'
 CSG: 5-21-08
 POP: 6-18-08

DATE	HRS	Oil (bbls)	Water (bbls)	Recovered Water (bbls)	Gas (mcf)	Casing Pressure (psi)	SPM	Comments
6/18/2008				4190				POP @ 11:30 A.M. w/ 86" SL @ 5 SPM. 4190 Total water to recover.
6/19/2008	23	0	125	4065		35	4 1/2	
6/20/2008	24	0	84	3981		165	4 1/2	
6/21/2008	24	98	173	3808	73	100	4 1/2	
6/22/2008	24	188	159	3649	79	180	4 1/2	
6/23/2008	24	228	161	3488	40	85	4 1/2	
6/24/2008	18	126	53	3435	47	115	5	Clutched for oil sale.
6/25/2008	24	205	70	3365	53	70	4 1/2	
6/26/2008	23	272	33	3332	101	85	4 1/2	clutched 1 hour for Oil sale
6/27/2008	24	237	20	3312	89	85	4 1/2	
6/28/2008	24	227	30	3282	80	85	4 1/2	
6/29/2008	24	197	22	3260	67	60	4 1/2	
6/30/2008	24	145	30	3230	60	60	4 1/2	
7/1/2008	24	149	17	3213	47	65	4 1/2	
7/2/2008	24	95	13	3200	40	65	4 1/2	
7/3/2008	24	146	2	3198	25	50	4 1/2	
7/4/2008	24	128	13	3185	35	60	4 3/4	
7/5/2008	24	121	13	3172	38	60	4 1/2	
7/6/2008	24	112	12	3160	38	60	4 1/2	
7/7/2008	24	103	12	3148		40	4 1/2	
7/8/2008	24	100	30	3118	39	40	4 1/2	
7/9/2008	24	113	10	3108	30	25	4 1/2	
7/10/2008	24	118	12	3096	62	30	4 1/2	
7/11/2008	24	113	10	3086	50	40	4 1/2	
7/12/2008	24	116	10	3076	67	45	4 1/2	
7/13/2008	24	119	13	3063	58	35	4 1/2	
7/14/2008	24	133	13	3050	45	40	4 1/2	
7/15/2008	24	114	12	3038	52	45	4 1/2	
7/16/2008	24	125	12	3026	71	55	4 1/2	
7/17/2008	24	112	12	3014	73	55	4 1/2	
7/18/2008				3014				
7/19/2008				3014				
		3940	1176		1459			

105376