

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU0281
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator EOG RESOURCES, INC. Contact: MARY A. MAESTAS E-Mail: mary_maestas@eogresources.com		7. If Unit or CA Agreement, Name and No. CHAPITA WELLS UNI
3a. Address 600 17TH STREET SUITE 1000N DENVER, CO 80202		8. Lease Name and Well No. CHAPITA WELLS UNIT 749-12
3b. Phone No. (include area code) Ph: 303-824-5526		9. API Well No. 43-047-39931
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface NESE 1699FSL 821FEL 40.04804 N Lat, 109.38185 W Lon At proposed prod. zone NESE 1699FSL 821FEL 40.04804 N Lat, 109.38185 W Lon		10. Field and Pool, or Exploratory NATURAL BUTTES/WASATCH
14. Distance in miles and direction from nearest town or post office* 38.3 MILES SOUTH OF VERNAL, UT		11. Sec., T., R., M., or Blk. and Survey or Area Sec 12 T9S R22E Mer SLB
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 821'	16. No. of Acres in Lease 2558.00	12. County or Parish UINTAH COUNTY
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1470'	19. Proposed Depth 7380 MD	13. State UT
21. Elevations (Show whether DF, KB, RT, GL, etc.) 4821 GL	22. Approximate date work will start	17. Spacing Unit dedicated to this well
		20. BLM/BIA Bond No. on file NM2308
		23. Estimated duration 45 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission) 	Name (Printed/Typed) MARY A. MAESTAS Ph: 303-824-5526	Date 01/25/2008
Title REGULATORY ASSISTANT		
Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 01-31-08
Title ENVIRONMENTAL MANAGER		

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #58276 verified by the BLM Well Information System
For EOG RESOURCES, INC., sent to the Vernal

RECEIVED

JAN 28 2008

DIV. OF OIL, GAS & MINING

Federal Approval of this
Action is Necessary

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

6380894
44341394
40.048081
-109.381214

T9S, R22E, S.L.B.&M.

R
22
E

EOG RESOURCES, INC.


Well location, CWU #749-12, located as shown in the NE 1/4 SE 1/4 of Section 12, T9S, R22E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION



BENCH MARK 20EAM LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME, OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



CWU #749-12
Elev. Graded Ground = 4821'

(NAD 83)
LATITUDE = 40°02'52.96" (40.048044)
LONGITUDE = 109°22'54.66" (109.381850)
(NAD 27)
LATITUDE = 40°02'53.09" (40.048081)
LONGITUDE = 109°22'52.21" (109.381169)

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.
- △ = SECTION CORNERS RE-ESTABLISHED.
(Not Set On Ground)

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 10-25-07	DATE DRAWN: 12-10-07
PARTY C.R. C.P. L.K.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE EOG RESOURCES, INC.	

EIGHT POINT PLAN

CHAPITA WELLS UNIT 749-12
NE/SE, SEC. 12, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,840		Shale	
Wasatch	4,835	Primary	Sandstone	Gas
Chapita Wells	5,395	Primary	Sandstone	Gas
Buck Canyon	6,101	Primary	Sandstone	Gas
North Horn	6,733	Primary	Sandstone	Gas
KMV Price River	7,190		Sandstone	
TD	7,380			

Estimated TD: 7,380' or 200'± below Segro top

Anticipated BHP: 4,030 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
 BOP schematic diagrams attached.

4. CASING PROGRAM:

CASING	Hole Size	Length	Size	WEIGHT	Grade	Thread	Rating Collapse	Factor Burst	Tensile
Conductor	17 1/2"	0 – 45'	13 3/8"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 1/4"	0 – 2,300' KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production	7-7/8"	Surface – TD	4-1/2"	11.6#	N-80	LTC	6350 PSI	7780 Psi	233,000#

Note: 12-1/4" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 749-12 NE/SE, SEC. 12, T9S, R22E, S.L.B.&M.. UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

EIGHT POINT PLAN

CHAPITA WELLS UNIT 749-12
NE/SE, SEC. 12, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: 207 sks Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

Lead: 146 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 530 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 749-12
NE/SE, SEC. 12, T9S, R22E, S.L.B.&M.
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:


- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

EOG RESOURCES 11" 5,000 PSI W.P. BOP CONFIGURATION



EOG RESOURCES CHOKE MANIFOLD CONFIGURATION
W/ 5,000 PSI WP VALVES

PAGE 2 OF 2



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, whichever is greater.
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.



**Chapita Wells Unit 749-12
NESE, Section 12, T9S, R22E
Uintah County, Utah**

SURFACE USE PLAN

The well pad is approximately 375 feet long with a 261-foot width, containing 2.25 acres more or less. The well access road is approximately 100 feet long with a 40-foot right-of-way, disturbing approximately .09 acre. New surface disturbance associated with the well pad and access road is estimated to be 2.34 acres.

1. EXISTING ROADS:

- A. See attached Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 38.3 miles south of Vernal, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary.

2. PLANNED ACCESS ROAD:

- A. The access road will be approximately 100' in length.
- B. The access road has a 40-foot ROW w/18 foot running surface.
- C. Maximum grade of the new access road will be 8 percent.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.
- I. A 40-foot permanent right-of-way is requested. No surfacing material will be used.

- J. No additional storage areas will be needed for storing equipment, stockpiling, or vehicle parking.

All travel will be confined to existing access road rights-of-way.

New or reconstructed roads will be centerlined – flagged at time of location staking. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction.

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 40-foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the roadbed block the drainages. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

Traveling off the 40-foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

An off-lease right-of-way is not required. The entire length of the proposed access road is located within Federal Lease # U-0281. The portion of the existing road not needed for production will be reclaimed.

3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:

See attached TOPO map "C" for the location of wells within a one-mile radius.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

A. On Well Pad

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400-bbl vertical tanks and attaching piping.
2. Gas gathering lines – A 4” gathering line will be buried from dehy to the edge of the location.

B. Off Well Pad

1. No new off-pad pipeline will be required. The existing pipeline for the Chapita Wells Unit 979-12 will be used to transport gas from the proposed location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All facilities will be painted with Carlsbad Canyon or Covert Green.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

5. LOCATION AND TYPE OF WATER SUPPLY:

- A. Water supply will be Bonanza Power Plant water source in Sec 26, T8S, R23E, Uintah County, UT (State Water Right # 49-225(A31368)). Water will be hauled by a licensed trucking company.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIALS:

- A. All construction material for this pipeline will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL:

A. METHODS AND LOCATION

1. Cuttings will be confined in the reserve pit.
2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.

3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, CWU 550-30N SWD, CWU 2-29 SWD, Red Wash Evaporation ponds 1, 2, 3 or 4 or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit, through natural or artificial methods, or removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with felt, and a 16-millimeter plastic liner. Sufficient bedding (i.e. weed free straw, or hay; felt; polyswell or soil) will be used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well. Furthermore, extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will not be used, produced, stored, transported, or disposed of in association with the drilling, testing or completion of the well.

8. ANCILLARY FACILITIES:

None anticipated.

9. WELL SITE LAYOUT:

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the southeast corner of the location. The flare pit will be located downwind of the prevailing wind direction on the south side of the location, a minimum of 100 feet from the wellhead and 30 feet from the reserve pit fence.

The stockpiled pit topsoil (first six inches) will be stored separate from the location topsoil west of pit corner B. The stockpiled location topsoil will be stored in a location providing easy access for interim reclamation and protection of the topsoil. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the northwest.

The corners of the well pad will be rounded off as needed to minimize excavation.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently counted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RECLAMATION OF THE SURFACE:

A. Interim Reclamation (Producing Location)

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of the well completion, or as soon as environmental conditions allow. Before any dirt takes place, the reserve pit must be completely dry and free of all foreign obstacles.

The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

Seed Mixture	Drilled Rate (lbs./acre PLS*)
HyCrest Wheatgrass	9.0
Prostrate Kochia	3.0

*Pure live seed (PLS) formula: percent of purity of seed mixture times percent germination of seed mixture equals portion of seed mixture that is PLS.

B. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriated surface rehabilitation conditions of approval.

Seed Mixture	Drilled Rate (lbs./acre PLS*)
Fourwing Saltbush	3.0
Shadscale	3.0
Indian Ricegrass	2.0
HyCrest Wheatgrass	1.0

*Pure live seed (PLS) formula: percent of purity of seed mixture times percent germination of seed mixture equals portion of seed mixture that is PLS.

11. SURFACE OWNERSHIP:

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

Bureau of Land Management

12. OTHER INFORMATION:

- A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:
- Whether the materials appear eligible for the National Register of Historic Places;
 - The mitigation measures the operator will likely have to undertake before the site can be used.
 - A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for

mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)
- D. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

A cultural resources survey was conducted and will be submitted by Montgomery Archaeological Consultants. A paleontological survey was conducted and will be submitted by Intermountain Paleo.

Additional Surface Stipulations:

None.

LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

PERMITTING AGENT

Mary A. Maestas
EOG Resources, Inc.
1060 East Highway 40
Vernal, UT 84078
(435) 781-9111

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.


The operator or his/her contractor shall contact the BLM office at (435) 781-4400 forty-eight (48) hours prior to construction activities.

CERTIFICATION:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the Chapita Wells Unit 749-12 Well, located in the NESE, of Section 12, T9S, R22E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

January 25, 2008
Date



Mary A. Maestas, Regulatory Assistant

EOG RESOURCES, INC
CWU #749-12
SECTION 12, T9S, R22E, S.L.B.&M.

PROCEED IN AN EASTERLY, THEN SOUTHERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 3.9 MILES TO THE JUNCTION OF STATE HIGHWAY 45; EXIT RIGHT AND PROCEED IN A SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 19.2 MILES ON STATE HIGHWAY 45 TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE WEST; TURN RIGHT AND PROCEED IN A WESTERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 8.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN LEFT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 1.6 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN SOUTHERLY, THEN EASTERLY DIRECTION APPROXIMATELY 2.3 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTHEAST; FOLLOW ROAD FLAGS IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 100' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 38.3 MILES.



EOG RESOURCES, INC.

LOCATION LAYOUT FOR

CWU #749-12
SECTION 12, T9S, R22E, S.L.B.&M.
1699' FSL 821' FEL

FIGURE #1

SCALE: 1" = 60'
 DATE: 12-10-07
 DRAWN BY: L.K.
 REVISED: 01-22-08



NOTE:
 Flare Pit is to be located a min. of 100' from the Well Head.

Elev. Ungraded Ground at #749-12 Location Stake = 4821.2'
 Elev. Graded Ground at #749-12 Location Stake = 4820.6'

UINTAH ENGINEERING & LAND SURVEYING
 85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

EOG RESOURCES, INC.

FIGURE #2


TYPICAL CROSS SECTIONS FOR

CWU #749-12
SECTION 12, T9S, R22E, S.L.B.&M.
1699' FSL 821' FEL



1" = 40'
X-Section
Scale
1" = 100'

DATE: 12-10-07
DRAWN BY: L.K.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,110 Cu. Yds.
(New Construction Only)	
Remaining Location	= 13,600 Cu. Yds.
TOTAL CUT	= 14,710 CU.YDS.
FILL	= 490 CU.YDS.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

EXCESS MATERIAL	= 14,220 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,130 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 11,090 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

EOG RESOURCES, INC.

PRODUCTION FACILITY LAYOUT FOR

CWU #749-12

SECTION 12, T9S, R22E, S.L.B.&M.


1699' FSL 821' FEL

FIGURE #3



SCALE: 1" = 60'

DATE: 12-10-07

DRAWN BY: L.K.



Access Road



 RE-HABED AREA

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

EOG RESOURCES, INC.

CWU #749-12

LOCATED IN UINTAH COUNTY, UTAH
SECTION 12, T9S, R22E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHEASTERLY



PHOTO: VIEW OF EXISTING ACCESS

CAMERA ANGLE: SOUTHWESTERLY



UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


10 26 07
MONTH DAY YEAR

PHOTO

TAKEN BY: C.R.

DRAWN BY: C.P.

REVISED: 00-00-00



LEGEND:

● PROPOSED LOCATION

EOG RESOURCES, INC.


CWU #749-12
 SECTION 12, T9S, R22E, S.L.B.&M.
 1699' FSL 821' FEL

UEIS Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP 10 26 07
 MONTH DAY YEAR
 SCALE: 1:100,000 DRAWN BY: C.P. REVISED: 00-00-00





LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD



EOG RESOURCES, INC.

CWU #749-12
 SECTION 12, T9S, R22E, S.L.B.&M.
 1699' FSL 821' FEL




Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP

10	26	07
MONTH	DAY	YEAR



SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00



**PROPOSED LOCATION:
CWU #749-12**

LEGEND:

- ◌ DISPOSAL WELLS
- PRODUCING WELLS
- ◐ SHUT IN WELLS
- ◌ WATER WELLS
- ◌ ABANDONED WELLS
- ◌ TEMPORARILY ABANDONED

EOG RESOURCES, INC.

**CWU #749-12
SECTION 12, T9S, R22E, S.L.B.&M.
1699' FSL 821' FEL**



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



**TOPOGRAPHIC
MAP**

10 26 07
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00



**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 01/28/2008

API NO. ASSIGNED: 43-047-39931

WELL NAME: CWU 749-12
 OPERATOR: EOG RESOURCES, INC. (N9550)
 CONTACT: MARY MAESTAS

PHONE NUMBER: 303-824-5526

PROPOSED LOCATION:

NESE 12 090S 220E
 SURFACE: 1699 FSL 0821 FEL
 BOTTOM: 1699 FSL 0821 FEL
 COUNTY: UINTAH
 LATITUDE: 40.04808 LONGITUDE: -109.3812
 UTM SURF EASTINGS: 638089 NORTHINGS: 4434139
 FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal
 LEASE NUMBER: UTU0281
 SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: WSTC
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:


- Plat
- Bond: Fed[1] Ind[] Sta[] Fee[]
(No. NM 2308)
- Potash (Y/N)
- Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit
(No. 49-225)
- RDCC Review (Y/N)
(Date: _____)
- Fee Surf Agreement (Y/N)
- Intent to Commingle (Y/N)

LOCATION AND SITING:

- R649-2-3.
- Unit: CHAPITA WELLS
- R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit
Board Cause No: 179-8
Eff Date: 8-10-1999
Siting: Successors of the O'Connell
- R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1- EOG Operator
2- OIL SURVE



NATURAL BUTTES FIELD
CHAPITA WELLS UNIT
 CAUSE: 179-08 / 8-10-1999

OPERATOR: EOG RESOURCES INC (N9550)
 SEC: 11,12 T.9S R. 22E
 FIELD: NATURAL BUTTES (630)
 COUNTY: UINTAH
 CAUSE: 179-08 / 8-10-1999

Field Status	Unit Status
ABANDONED	EXPLORATORY
ACTIVE	GAS STORAGE
COMBINED	NF PP OIL
INACTIVE	NF SECONDARY
PROPOSED	PENDING
STORAGE	PI OIL
TERMINATED	PP GAS
	PP GEOTHERML
	PP OIL
	SECONDARY
	TERMINATED

Wells Status

	GAS INJECTION
	GAS STORAGE
	LOCATION ABANDONED
	NEW LOCATION
	PLUGGED & ABANDONED
	PRODUCING GAS
	PRODUCING OIL
	SHUT-IN GAS
	SHUT-IN OIL
	TEMP. ABANDONED
	TEST WELL
	WATER INJECTION
	WATER SUPPLY
	WATER DISPOSAL
	DRILLING



PREPARED BY: DIANA MASON
 DATE: 29-JANUARY-2008

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

January 30, 2008

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2008 Plan of Development Chapita Wells Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2008 within the Chapita Wells Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
------	-----------	----------

(Proposed PZ Wasatch)

43-047-39925	CWU 751-11 Sec 11 T09S R22E 0690 FSL 0615 FWL	
43-047-39926	CWU 750-12 Sec 12 T09S R22E 0686 FSL 1040 FWL	
43-047-39931	CWU 749-12 Sec 12 T09S R22E 1699 FSL 0821 FEL	
43-047-39924	CWU 752-10 Sec 10 T09S R22E 0882 FSL 0350 FWL	
43-047-39930	CWU 753-10 Sec 10 T09S R22E 0533 FSL 1825 FEL	
43-047-39932	CWU 764-22 Sec 22 T09S R22E 0445 FSL 1971 FEL	
43-047-39933	CWU 758-25 Sec 25 T09S R22E 2075 FNL 0534 FEL	

(Proposed PZ MesaVerde)

43-047-39928	CWU 1351-27 Sec 27 T09S R22E 1356 FNL 0201 FEL	
43-047-39927	CWU 1386-15 Sec 15 T09S R22E 0238 FNL 2537 FWL	
43-047-39929	CWU 1387-10 Sec 10 T09S R22E 1248 FSL 2157 FWL	

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Chapita Wells Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:1-30-08



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil Gas and Mining

JOHN R. BAZA
Division Director

January 31, 2008

EOG Resources, Inc.
600 17th St., Ste. 1000N
Denver, CO 80202

Re: Chapita Wells Unit 749-12 Well, 1699' FSL, 821' FEL, NE SE, Sec. 12, T. 9 South,
R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39931.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal Office



Operator: EOG Resources, Inc.
Well Name & Number Chapita Wells Unit 749-12
API Number: 43-047-39931
Lease: UTU0281

Location: NE SE **Sec.** 12 **T.** 9 South **R.** 22 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office (801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

RECEIVED

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

JAN 25 2008

APPLICATION FOR PERMIT TO DRILL OR REENTER **BLM**

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU0281
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator EOG RESOURCES INC		7. If Unit or CA Agreement, Name and No. UTU63013AE
Contact: MARY A. MAESTAS E-Mail: mary_maestas@eogresources.com		8. Lease Name and Well No. CWU 749-12
3a. Address 1060 EAST HIGHWAY 40 VERNAL, UT 84078	3b. Phone No. (include area code) Ph: 303-824-5526	9. API Well No. 43 047 39931
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NESE 1699FSL 821FEL 40.04804 N Lat, 109.38185 W Lon At proposed prod. zone NESE 1699FSL 821FEL 40.04804 N Lat, 109.38185 W Lon		10. Field and Pool, or Exploratory NATURAL BUTTES
14. Distance in miles and direction from nearest town or post office* 38.3 MILES SOUTH OF VERNAL, UT		11. Sec., T., R., M., or Blk. and Survey or Area Sec 12 T9S R22E Mer SLB SME: BLM
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 821'	16. No. of Acres in Lease 2557.84	12. County or Parish UINTAH
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1470'	19. Proposed Depth 7380 MD	13. State UT
21. Elevations (Show whether DF, KB, RT, GL, etc.) 4821 GL	22. Approximate date work will start	17. Spacing Unit dedicated to this well
23. Estimated duration 45 DAYS		20. BLM/BIA Bond No. on file NM2308

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature (Electronic Submission)	Name (Printed/Typed) MARY A. MAESTAS Ph: 303-824-5526	Date 01/25/2008
Title REGULATORY ASSISTANT		
Approved by (Signature) <i>[Signature]</i>	Name (Printed/Typed) <i>Jenny Jenkins</i>	Date 4-11-2008
Title Assistant Field Manager Lands & Mineral Resources		
VERNAL FIELD OFFICE		

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #58276 verified by the BLM Well Information System
For EOG RESOURCES INC, sent to the Vernal
Committed to AFMSS for processing by GAIL JENKINS on 01/25/2008 (08GXJ1689AE)

**NOTICE OF APPROVAL
RECEIVED**

APR 18 2008

DIV. OF OIL, GAS & MINING

** BLM REVISED **

UDOGM

08MIC0162AE

NOS. 12/14/2007




**UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE**

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: EOG Resources, Inc.
Well No: CWU 749-12
API No: 43-047-39931

Location: NESE, Sec. 12, T9S, R22E
Lease No: UTU-0281
Agreement: Chapita Wells Unit

Title	Name	Office Phone Number	Cell Phone Number
Petroleum Engineer:	Matt Baker	(435) 781-4490	(435) 828-4470
Petroleum Engineer:	Michael Lee	(435) 781-4432	(435) 828-7875
Petroleum Engineer:	James Ashley	(435) 781-4470	(435) 828-7874
Petroleum Engineer:	Ryan Angus	(435) 781-4430	(435) 828-7368
Supervisory Petroleum Technician:	Jamie Sparger	(435) 781-4502	(435) 828-3913
Supervisory NRS:	Karl Wright	(435) 781-4484	(435) 828-7381
NRS/Enviro Scientist:	Holly Villa	(435) 781-4404	
NRS/Enviro Scientist:		(435) 781-4476	
NRS/Enviro Scientist:	Chuck Macdonald	(435) 781-4441	(435) 828-7481
NRS/Enviro Scientist:	Michael Cutler	(435) 781-3401	(435) 828-3546
NRS/Enviro Scientist:	Anna Figueroa	(435) 781-3407	(435) 828-3548
NRS/Enviro Scientist:	Verlyn Pindell	(435) 781-3402	(435) 828-3547
NRS/Enviro Scientist:	Darren Williams	(435) 781-4447	
NRS/Enviro Scientist:	Nathan Packer	(435) 781-3405	(435) 828-3545

Fax: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

Site Specific COAs:

- Within 90 calendar days of the approval date for this Application for Permit to Drill (APD), the operator/lessee shall submit to the Authorized Officer (AO), on Sundry Notice Form 3160-5, an Interim Surface Reclamation Plan for surface disturbance on well pads, access roads, and pipelines. At a minimum, this will include the reshaping of the pad to the original contour to the extent possible; the re-spreading of the top soil up to the rig anchor points; and, the area reseeded using appropriate reclamation methods. The AO will provide written approval or concurrence within 30 calendar days of receipt. During interim management of the surface, use the following seed mix:
 - 9 lbs HyCrest Wheatgrass and 3 lbs Kochia
- All the culverts will be installed according to the BLM Gold Book.
- The road and well pad will have road base on the surface.
- Bury pipeline at all low water crossings.
- Permission from an authorized BLM representative will be required if construction or other operations occur during wet conditions that will lead to excessive rutting.
- Permission to clear all wildlife stipulations will only be approved by the BLM wildlife biologist during the specific timing for the species potentially affected by this action.
- Culverts and gravel may be installed as needed.
- The unused portions of the old access road will be rehabbed and reseeded with the interim seed mix at interim reclamation.

***DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

SITE SPECIFIC DOWNHOLE COAs:

- Production casing cement shall be brought up and into the surface casing. The minimum cement top is 200 ft above the surface casing shoe.
- COA specification is consistent with operators performance standard stated in APD.
- A variance is granted for Onshore Order #2 Drilling Operations III. E. "Blooie line discharge 100 feet from well bore and securely anchored" Blooie line can be 75 feet.
- All requirements will be adhered to covering air/gas drilling operations as described in Onshore Order #2 III. E. 1. Drilling Operations, Special Drilling Operations, air/gas drilling.
- A Gamma Ray well Log shall be run from the well Total Depth to the surface.
- A copy of the Gamma Ray well Log shall be submitted to the BLM Vernal Field Office.

Covering air/gas drilling operations, requirements will be adhered to covering air/gas drilling operations as described in Onshore Order #2 III. E. 1. Drilling Operations, Special Drilling Operations, air/gas drilling.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.

- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Wellogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.

- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.

- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: EOG RESOURCES INC

Well Name: CWU 749-12

Api No: 43-047-39931 Lease Type: FEDERAL

Section 12 Township 09S Range 22E County UINTAH

Drilling Contractor ROCKY MOUNTAIN DRLG RIG # RATHOLE

SPUDDED:

Date 07/15/08

Time 6:00 PM

How DRY

Drilling will Commence: _____

Reported by JERRY BARNES

Telephone # (435) 828-1720

Date 07/16//08 Signed CHD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc. Operator Account Number: N 9550
Address: 600 17th St., Suite 1000N
city Denver
state CO zip 80202 Phone Number: (303) 824-5526

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39075	Chapita Wells Unit 632-11		SWNE	11	9S	22E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>EA</i>	99999	<i>16982</i>	7/15/2008		<i>7/30/08</i>		
Comments: <u>Mesaverde well</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-39931	Chapita Wells Unit 749-12		NESE	12	9S	22E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>B</i>	99999	<i>4905</i>	7/15/2008		<i>7/30/08</i>		
Comments: <u>Wasatch well</u>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-38509	Chapita Wells Unit 1221-02		SESW	2	9S	22E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>EA</i>	99999	<i>16983</i>	7/16/2008		<i>7/30/08</i>		
Comments: <u>Mesaverde well</u> <i>PRR = MVRD</i>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mary A. Maestas

Name (Please Print)

Mary A. Maestas

Signature

Regulatory Assistant

7/16/2008

Title

Date

RECEIVED

JUL 16 2008

(5/2000)

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU0281

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNI

1. Type of Well
 Oil Well Gas Well Other

8. Well Name and No.
CHAPITA WELLS UNIT 749-12

2. Name of Operator
EOG RESOURCES, INC
Contact: MARY A. MAESTAS
E-Mail: mary_maestas@eogresources.com

9. API Well No.
43-047-39931

3a. Address
600 17TH STREET SUITE 1000N
DENVER, CO 80202

3b. Phone No. (include area code)
Ph: 303-824-5526

10. Field and Pool, or Exploratory
NATURAL BUTTES/WASATCH

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 12 T9S R22E NESE 1699FSL 821FEL
40.04804 N Lat, 109.38185 W Lon

11. County or Parish, and State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Well Spud
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The referenced well spud on 7/15/2008.

14. I hereby certify that the foregoing is true and correct.
Electronic Submission #61466 verified by the BLM Well Information System For EOG RESOURCES, INC, sent to the Vernal

Name (Printed/Typed) MARY A. MAESTAS Title REGULATORY ASSISTANT

Signature  (Electronic Submission) Date 07/16/2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

RECEIVED

JUL 18 2008

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU0281

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

7. If Unit or CA/Agreement, Name and/or No.
CHAPITA WELLS UNI

8. Well Name and No.
CHAPITA WELLS UNIT 749-12

9. API Well No.
43-047-39931

10. Field and Pool, or Exploratory
NATURAL BUTTES

11. County or Parish, and State
UINTAH COUNTY, UT

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
EOG RESOURCES, INC. Contact: MARY A. MAESTAS
E-Mail: mary_maestas@eogresources.com

3a. Address
600 17TH STREET SUITE 1000N
DENVER, CO 80202

3b. Phone No. (include area code)
Ph: 303-824-5526

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec 12 T9S R22E NESE 1699FSL 821FEL
40.04804 N Lat, 109.38185 W Lon

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Production Start-up
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The referenced well was turned to sales on 9/18/2008. Please see the attached operations summary report for drilling and completion operations performed on the subject well.

14. I hereby certify that the foregoing is true and correct.
**Electronic Submission #63212 verified by the BLM Well Information System
For EOG RESOURCES, INC., sent to the Vernal**

Name (Printed/Typed) MARY A. MAESTAS Title REGULATORY ASSISTANT

Signature *Mary A. Maestas* Date 09/19/2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED SEP 23 2008**

DIV. OF OIL, GAS & MINING

WELL CHRONOLOGY REPORT

Report Generated On: 09-19-2008

Well Name	CWU 749-12	Well Type	DEVG	Division	DENVER
Field	CHAPITA WELLS UNIT	API #	43-047-39931	Well Class	ISA
County, State	UINTAH, UT	Spud Date	07-24-2008	Class Date	09-18-2008
Tax Credit	N	TVD / MD	7,380/ 7,380	Property #	062293
Water Depth	0	Last CSG	0.0	Shoe TVD / MD	0/ 0
KB / GL Elev	4,834/ 4,821				
Location	Section 12, T9S, R22E, NESE, 1699 FSL & 821 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	55.124	NRI %	46.807

AFE No	304963	AFE Total	1,304,500	DHC / CWC	694,700/ 609,800						
Rig Contr	ELENBURG	Rig Name	ELENBURG #28	Start Date	02-14-2008	Release Date	07-27-2008				
02-14-2008	Reported By	CINDY VAN RANKEN									
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA 1699' FSL & 821' FEL (NE/SE) SECTION 12, T9S, R22E UINTAH COUNTY, UTAH LAT 40.048081, LONG 109.381169 (NAD 27) LAT 40.048044, LONG 109.381850 (NAD 83) ELENBURG #28 OBJECTIVE: 7380' MD, WASATCH DW/GAS CHAPITA WELLS PROSPECT DD&A: NATURAL BUTTES NATURAL BUTTES FIELD LEASE: UTU-0281 ELEVATION: 4821.2' NAT GL, 4820.6' PREP GL (DUE TO ROUNDING PREP GL WILL BE 4821'), 4834' KB (13') EOG WI 55.1242%, NRI 46.806575%

07-09-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling \$38,000 **Completion** \$0 **Daily Total** \$38,000
Cum Costs: Drilling \$38,000 **Completion** \$0 **Well Total** \$38,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	START LOCATION.

07-10-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$38,000 **Completion** \$0 **Well Total** \$38,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 25% COMPLETE.

07-11-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$38,000 **Completion** \$0 **Well Total** \$38,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 30% COMPLETE.

07-14-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$38,000 **Completion** \$0 **Well Total** \$38,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LINE TODAY.

07-15-2008 **Reported By** TERRY CSERE

Daily Costs: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$38,000 **Completion** \$0 **Well Total** \$38,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: WO BUCKET TRUCK

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE.

07-16-2008 **Reported By** JERRY BARNES

Daily Costs: Drilling	\$80,960	Completion	\$0	Daily Total	\$80,960
Cum Costs: Drilling	\$316,067	Completion	\$0	Well Total	\$316,067
MD	2,582	TVD	2,582	Progress	226
				Days	1
				MW	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: DRILLING @ 2582'

Start	End	Hrs	Activity Description
06:00	06:30	0.5	RIG DOWN.
06:30	07:00	0.5	SAFETY MEETING W/ HOWCROFT TRUCKING & RIG CREWS.
07:00	08:00	1.0	RIG DOWN & MOVE TO CWU 749-12 CLEAR LOCATION @ 08:00.
08:00	11:00	3.0	SET BOP TEST DTO HEAD TO 5000 PSI. W/ FMC, RAISE DERRICK @ 09:00 SPOT TANKS,PUMPS,GROUND SUPPORT, CONT TO RIG UP TRUCKS OFF LOCATION @ 11:00.
11:00	13:00	2.0	CONT. RIG UP.
13:00	18:00	5.0	NIPPLE UP BOP, ROT.HEAD, CHOKE LINE, KILL LINE VALVES, HYD. HOSES, FUNCTION TEST BOP. RIG ON DAY WORK @ 13:00 HRS, 7/23/08.
18:00	21:30	3.5	TEST BOPE AS PER PROGRAM. NOTIFIED BLM REP, JAIME SPARGER VERNAL OFFICE ON 7/22/08 @ 07:30 HRS FOR BOP TEST. INSIDE BOP, SAFETY VALVE, UPPER KELLY COCK 250/5000 PSI 5/10 MIN. HCR, CHOKE LINE, KILL LINE, 250/5000 PSI 5/10 MIN. CHOKE MANIFOLD, 250/5000 PSI 5/10 MIN. PIPE RAMS, BLIND RAMS, 250/5000 PSI 5/10 MIN. ANNULAR, 250/2500 PSI 5/10 MIN. TEST 9 5/8" CASING TO1500 PSI 30 MIN. WITNESS: D.DUNCAN
21:30	01:30	4.0	SET WEAR BUSHING. P/U BHA AND TIH. TAG CEMENT @ 2310'.
01:30	02:30	1.0	DRILL CEMENT, FLOAT EQUIPMENT TO 2356' + 10' OF NEW HOLE TO 2366'. FIT TEST 190 PSI, 9 PPG FLUID = 10.5 EWM. GOOD TEST.
02:30	03:00	0.5	SURVEY @ 2353' = 1/4 DEG.
03:00	06:00	3.0	DRILLING FROM 2366' TO 2582', ROP 72, WOB 10/14, RPM 50, TQ 1200/1750.

MUD LOSS LAST 24 HRS. 0 BBLs.
ACCIDENTS NONE REPORTED.
FUNCTION TEST CROWN-O-MATIC.
SAFETY MEETING: RIG MOVE, TEST BOPE.
CREWS FULL.
FUEL ON HAND: 6842 GALS. USED 694 GALS, 4500 GAL RECIEVED.
FORMATION TOP: WASATCH.
GAS BG.140 U, CONN. 250 U.
LITHOLOGY, SAND/ SHALE.
MUD LOGGER UNMANED ON LOCATION F/ 7/23/08 = 1 DAY.

06:00 06:00 24.0 SPUD 7 7/8" HOLE @ 03:00 HRS, 7/24/08.

07-25-2008	Reported By	MATT WILLIAMS			
Daily Costs: Drilling	\$28,670	Completion	\$0	Daily Total	\$28,670
Cum Costs: Drilling	\$344,737	Completion	\$0	Well Total	\$344,737

MD 5,255 **TVD** 5,255 **Progress** 2,673 **Days** 2 **MW** 9.0 **Visc** 28.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 5255'

Start	End	Hrs	Activity Description
06:00	12:00	6.0	DRILLING FROM 2582' TO 3353', ROP 129, WOB 10/15, RPM 50/60, TQ 1200/2200.
12:00	12:30	0.5	SERVICE RIG.
12:30	22:00	9.5	DRILLING FROM 3353' TO 4530', ROP 124, WOB 10/15, RPM 50/60, TQ 1200/2200.
22:00	23:00	1.0	SURVEY @ 4485' = 2.5 DEGREE.
23:00	06:00	7.0	DRILLING FROM 4485' TO 5255', ROP 110, WOB 12/18, RPM 40/50, TQ1200/2300. MUD LOSS LAST 24 HRS. 0 BBLs. MUD 9.3 / 31 ACCIDENTS NONE REPORTED. FUNCTION TEST CROWN-O-MATIC. SAFETY MEETING: RIG SERVICE, NEW HIRES. CREWS FULL. FUEL ON HAND: 5076 GALS. USED 1766 GALS, 0 GAL RECIEVED. FORMATION TOP: WASATCH. GAS BG.140 U, CONN. 260 U. LITHOLOGY, SAND/ SHALE. MUD LOGGER UNMANED ON LOCATION F/ 7/23/08 = 2 DAYS.

07-26-2008 **Reported By** MATT WILLIAMS

Daily Costs: Drilling \$29,654 **Completion** \$0 **Daily Total** \$29,654
Cum Costs: Drilling \$374,392 **Completion** \$0 **Well Total** \$374,392

MD 6,861 **TVD** 6,861 **Progress** 1,606 **Days** 3 **MW** 9.5 **Visc** 30.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 6861'

Start	End	Hrs	Activity Description
06:00	12:00	6.0	DRILLING FROM 5255' TO 5844', ROP 98, WOB 15/20, RPM 40/50, TQ 1400/2300.
12:00	12:30	0.5	SERVICE RIG
12:30	13:30	1.0	REPAIR SWIVEL MOTOR.
13:30	06:00	16.5	DRILLING FROM 5844' TO 6861', ROP 61.6, WOB 15/22, RPM 40/50, TQ 1400/2400, MWT 9.4, 32 VIS. MUD LOSS LAST 24 HRS. 0 BBLs. MUD WT: 9.4, VIS 32. ACCIDENTS NONE REPORTED. FUNCTION TEST CROWN-O-MATIC. SAFETY MEETING: HOUSEKEEPING, INSPECTING DRAWWORKS. CREWS FULL. FUEL ON HAND: 3608 GALS. USED 1468 GALS, 0 GAL RECIEVED. FORMATION TOP: KMV PRICE RIVER. GAS BG.140 U, CONN. 260 U. LITHOLOGY, SAND/ SHALE. MUD LOGGER UNMANED ON LOCATION F/ 7/23/08 = 3 DAYS.

06:00 18.0

07-27-2008 **Reported By** MATT WILLIAMS

Daily Costs: Drilling	\$43,181	Completion	\$0	Daily Total	\$43,181						
Cum Costs: Drilling	\$417,573	Completion	\$0	Well Total	\$417,573						
MD	7,380	TVD	7,380	Progress	519	Days	4	MW	9.4	Visc	34.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: RUNNING PRODUCTION CSG

Start	End	Hrs	Activity Description
06:00	14:30	8.5	DRILLING FROM 6861' TO 7380', ROP 61, WOB 15/22, RPM 40/50, TQ 1200/2400, MWT 9.3, 35 VIS. REACHED TD @ 14:30 HRS ON 7/26/08.
14:30	16:30	2.0	PUMP SWEEP, CIRCULATE AND COND MUD FOR SHORT TRIP.
16:30	17:30	1.0	SHORT TRIP
17:30	19:00	1.5	CIRCULATE AND COND, DROP SURVEY, SPOT 200 BBL, 11.3 ppg PILL. EMW = 10.
19:00	23:30	4.5	TRIP OUT OF HOLE LAYING DOWN DRILL PIPE.
23:30	00:00	0.5	PULLED ROTATING RUBBER.
00:00	01:30	1.5	L/D BHA. REMOVE SURVEY TOOL = 2 DEGRRES.
01:30	02:30	1.0	PULL WEAR BUSHING, RIG UP CSG CREW.
02:30	06:00	3.5	HOLD PJSM WITH ELENBURG AND T-REX CSG CREW, START RUNNING 4 1/2, N-80, 11.6#, PRODUCTION STRING. MUD LOSS LAST 24 HRS. 0 BBLs. MUD WT: 9.4, VIS 35. ACCIDENTS NONE REPORTED. FUNCTION TEST CROWN-O-MATIC. SAFETY MEETING: PRESSURE WASHING, OPERATING BOOM. CREWS FULL. FUEL ON HAND: 2836 GALS. USED 772 GALS, 0 GAL RECIEVED. FORMATION TOP: KMV PRICE RIVER. GAS BG.40 U, CONN. 160 U. LITHOLOGY, SAND/ SHALE. MUD LOGGER UNMANED ON LOCATION F/ 7/23/08 = 4 DAYS.

07-28-2008 Reported By MATT WILLIAMS

Daily Costs: Drilling	\$56,656	Completion	\$133,846	Daily Total	\$190,502						
Cum Costs: Drilling	\$474,229	Completion	\$133,846	Well Total	\$608,075						
MD	7,380	TVD	7,380	Progress	0	Days	5	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: RDRT

Start	End	Hrs	Activity Description
06:00	12:00	6.0	RUN 4.5 11.6# N-80 CASING 169 JTS. + 1 MARKER JT. AS FOLLOWS FLOAT SHOE, 1 JT.CSG, FLOAT COLLAR, 67 JTS. CSG, 1 MARJER JT, 101 JTS.CSG & HANGER ASSEMBLY. FLOAT SHOE @ 7380', FLOAT COLLAR @ 7333', MARKER JT @ 4414', CENTRALIZERS 5 FT. ABOVE SHOE JT, TOP OF JT.#2 & EVERY 3 TH. JT. TOTAL 10. TAG @ 7380' CIRC. TO LAY DOWN TAG JT.
12:00	12:30	0.5	CIRCULATE & LD TAG JT. PU DOT HANGER, LAND CSG WITH 65,000#
12:30	13:00	0.5	SAFETY MTG W/SCHLUMBERGER & RIG PERSONNEL, RU CEMENTING EQUIP.

13:00 15:00 2.0 RIG UP TEST LINES TO 5000 PSI. DROP BOTTOM PLUG PUMP 20 BBLS CHEM WASH & 20 BBLS WATER SPACER AHEAD OF LEAD AND CEMENT 7380' 4 1/2 N-80 11.6# CSG. LEAD 156 BBLS 295 SKS. G + ADDS. D020 10%EXTENDER D167 .2% FLUID LOSS D046.2% ANTIFOAM D013 .5% RATARDER D065 .5% DISPERSANT D130 .125LB/SK BLEND LOST CIRC. YIELD 2.98 FT3/SK H2O 18.2 GAL/SK@ 11.5.PPG TAIL. 202 BBLS 880 SKS 50/50 POZ G + ADDS. D020 2% EXTENDER D046 .1% ANTIFOAM D167 .2% FLUID LOSS D065 .2% DISPERSANT S001 1% ACCELERATOR. YIELD 1.29 FT3/SK H2O 5.94 GAL/SK @ 14.1 PPG. SHUTDOWN WASH OUT PUMPS & LINES DROP TOP PLUG & DISP. TO FLOAT COLLAR W/FRESH WATER.113 BBLS. AVG. DISP. RATE 8 BPM. FULL RETURNS THROUGH OUT JOB. DROP PLUG @ 14:31 BUMPED PLUG @ 15:05 TO 2870 PSI 1000 PSI OVER LIFT PSI HOLD PRESSURE FOR 1 MIN. 1.5 BBL. BACK, FLOAT HELD @ 15:06 CEMENT IN PLACE.

15:00 16:00 1.0 W/O CEMENT & RIG DOWN SCHLUMBERGER.

16:00 16:30 0.5 REMOVE CEMENT HEAD. LAY DOWN LANDING JT. LAND PACKOFF TEST 5000 PSI. LOOSEN DTO LOCK DOWN BOLTS W/ FMC.

16:30 20:00 3.5 NIPPLE DOWN BOPE AND CLEAN PITS.

20:00 06:00 10.0 RIG DOWN, RIG MAINTENANCE. PREPARE FOR TRUCKS. RIG MOVE @ 07:00 7/28/08 W/ HOWCROFT TRUCKING 2.7 MILES. TO WELL CWU 753-10.

ACCIDENTS NONE REPORTED.
 FUNCTION TEST CROWN-O-MATIC.
 SAFETY MEETING: RUN CSG, RIG MOVE.
 CREWS FULL.
 FUEL ON HAND: 2221 GALS. USED 615 GALS, 0 GAL RECIEVED.
 MUD LOGGER UNMANED ON LOCATION F/ 7/23/08 TO 7/27/08 = 5 DAYS. OFF LOCATION 7/27/08.

****RIG RELEASED @ 20:00 HRS ON 7/27/08.****
 CASING POINT COST \$435,260

08-03-2008		Reported By		SEARLE	
Daily Costs: Drilling	\$0	Completion	\$40,459	Daily Total	\$40,459
Cum Costs: Drilling	\$474,229	Completion	\$174,305	Well Total	\$648,534
MD	7,380	TVD	7,380	Progress	0
Days	6	MW	0.0	Visc	0.0
Formation :	PBTD : 7334.0		Perf :	PKR Depth : 0.0	
Activity at Report Time: PREP FOR FRACS					
Start	End	Hrs	Activity Description		
06:00		18.0	MIRU SCHLUMBERGER. LOG WITH RST/CBL/CCL/VDL/GR FROM PBTD TO 290'. EST CEMENT TOP @ 630'. RD SCHLUMBERGER.		

08-09-2008		Reported By		MCCURDY	
Daily Costs: Drilling	\$0	Completion	\$6,795	Daily Total	\$6,795
Cum Costs: Drilling	\$474,229	Completion	\$181,100	Well Total	\$655,330
MD	7,380	TVD	7,380	Progress	0
Days	6	MW	0.0	Visc	0.0
Formation :	PBTD : 7211.0		Perf :	PKR Depth : 0.0	
Activity at Report Time: WO COMPLETION					
Start	End	Hrs	Activity Description		
06:00	06:00	24.0	NU 10M FRAC TREE. PRESSURE TESTED FRAC TREE & CASING. AT 6100 PSIG, PRESSURE BROKE BACK TO 4100 PSIG @ 1/4 BPM. RU CUTTERS WIRELINE. SET CIBP @ 7211'. RDWL. TESTED CSG TO 6500 PSIG. WO COMPLETION.		

08-14-2008		Reported By		MCCURDY	
Daily Costs: Drilling	\$0	Completion	\$13,785	Daily Total	\$13,785

Cum Costs: Drilling \$474,229 **Completion** \$194,886 **Well Total** \$669,115
MD 7,380 **TVD** 7,380 **Progress** 0 **Days** 7 **MW** 0.0 **Visc** 0.0
Formation : WASATCH **PBTD : 7211.0** **Perf : 6618'-7118** **PKR Depth : 0.0**

Activity at Report Time: FRAC STAGE 3 THROUGH 7

Start **End** **Hrs** **Activity Description**
 06:00 06:00 24.0 MIRU LONE WOLF WIRELINE & PERFORATE NORTH HORN FROM 6944'-45', 6954'-55', 6960'-62', 6968'-69', 6983'-84', 7077'-79', 7082'-84', 7108'-09', 7117'-18' @ 3 SPF @ 120° PHASING. RDWL. MIRU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 2097 GAL YF116 PAD, 46976 GAL YF116ST+ WITH 147400 # 20/40 SAND @ 1-5 PPG. MTP 5689 PSIG. MTR 50.6 BPM. ATP 4274 PSIG. ATR 47.9 BPM. ISIP 3100 PSIG. RD SCHLUMBERGER.

 RUWL SET 6K CFP AT 6915'. PERFORATE NORTH HORN FROM 6618'-19', 6632'-33', 6649'-50', 6718'-19', 6722'-24', 6727'-29', 6762'-63', (6780'-81' MISFIRED), 6896'-98' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 2096 GAL YF116 PAD, 37779 GAL YF116ST+ WITH 109300 # 20/40 SAND @ 1-4 PPG. MTP 6237 PSIG. MTR 50 BPM. ATP 4326 PSIG. ATR 46.7 BPM. ISIP 2250 PSIG. RD SCHLUMBERGER. SWIFN.

08-15-2008 **Reported By** MCCURDY

Daily Costs: Drilling \$0 **Completion** \$207,726 **Daily Total** \$207,726
Cum Costs: Drilling \$474,229 **Completion** \$402,612 **Well Total** \$876,842
MD 7,380 **TVD** 7,380 **Progress** 0 **Days** 8 **MW** 0.0 **Visc** 0.0
Formation : WASATCH **PBTD : 7211.0** **Perf : 5472'-7118** **PKR Depth : 0.0**

Activity at Report Time: PREP TO MIRUSU

Start **End** **Hrs** **Activity Description**
 06:00 06:00 24.0 SICP 980 PSIG. RUWL. SET 6K CFP AT 6596'. PERFORATE Ba FROM 6481'-82', 6498'-99', 6509'-10', 6557'-58', 6566'-68', 6573'-75', 6579'-81' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 2094 GAL YF116 PAD, 37029 GAL YF116ST+ WITH 109100 # 20/40 SAND @ 1-4 PPG. MTP 5259 PSIG. MTR 50 BPM. ATP 4028 PSIG. ATR 47.8 BPM. ISIP 1880 PSIG. RD SCHLUMBERGER.

 RUWL. SET 6K CFP AT 6454'. PERFORATE Ba FROM 6257'-58', 6274'-75', 6284'-85', 6315'-16', 6326'-27', 6348'-49', 6360'-61', 6378'-79', 6391'-92', 6401'-02', 6428'-29', 6432'-33' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 2100 GAL YF116 PAD, 34314 GAL YF116ST+ WITH 99000 # 20/40 SAND @ 1-4 PPG. MTP 6096 PSIG. MTR 50.3 BPM. ATP 3894 PSIG. ATR 46.2 BPM. ISIP 1690 PSIG. RD SCHLUMBERGER.

 RUWL. SET 6K CFP AT 6180'. PERFORATE Ca FROM 5819'-20', 5826'-27', 5862'-63', 5878'-79', 5911'-12', 6006'-07', 6021'-22', 6060'-61', 6072'-73', 6080'-81', 6088'-89', 6153'-54' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH WITH 2091 GAL YF116 PAD, 30367 GAL YF116ST+ WITH 84500 # 20/40 SAND @ 1-4 PPG. MTP 5907 PSIG. MTR 50 BPM. ATP 3574 PSIG. ATR 46.6 BPM. ISIP 2070 PSIG. RD SCHLUMBERGER.

 RUWL. SET 6K CFP AT 5620'. PERFORATE Ca FROM 5559'-61', 5567'-71', 5575'-79' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 2095 GAL YF116 PAD, 37755 GAL YF116ST+ WITH 107600 # 20/40 SAND @ 1-4 PPG. MTP 5080 PSIG. MTR 35.6 BPM. ATP 3010 PSIG. ATR 34.5 BPM. ISIP 2290 PSIG. RD SCHLUMBERGER.

 RUWL. SET 6K CFP AT 5524'. PERFORATE Ca FROM 5472'-74', 5478'-80', 5484'-86', 5488'-90', 5497'-99' @ 3 SPF @ 120° PHASING. RDWL. RU SCHLUMBERGER, FRAC DOWN CASING WITH 2088 GAL YF116 PAD, 38450 GAL YF116ST+ WITH 110580 # 20/40 SAND @ 1-4 PPG. MTP 4105 PSIG. MTR 35.4 BPM. ATP 2704 PSIG. ATR 34.3 BPM. ISIP 2130 PSIG. RD SCHLUMBERGER.

 RUWL. SET 10K CBP AT 5358'. RDWL. SDFN.

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 32/64 CHOKE. FTP- 400 PSIG, CP- 600 PSIG. 22 BFPH. RECOVERED 510 BBLs, 5576 BLWTR.

08-29-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,565	Daily Total	\$2,565
Cum Costs: Drilling	\$474,229	Completion	\$449,318	Well Total	\$923,548

MD	7,380	TVD	7,380	Progress	0	Days	13	MW	0.0	Visc	0.0
Formation : WASATCH	PBTd : 7211.0		Perf : 5472'-7118		PKR Depth : 0.0						

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 32/64" CHOKE. FTP 550 PSIG. CP 600 PSIG. 28 BFPH. RECOVERED 658 BLW. 4918 BLWTR.

08-30-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,565	Daily Total	\$2,565
Cum Costs: Drilling	\$474,229	Completion	\$451,883	Well Total	\$926,113

MD	7,380	TVD	7,380	Progress	0	Days	14	MW	0.0	Visc	0.0
Formation : WASATCH	PBTd : 7211.0		Perf : 5472'-7118		PKR Depth : 0.0						

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 32/64 CHOKE. FTP- 450 PSIG, CP- 650 PSIG. 24 BFPH. RECOVERED 547 BBLs, 4371 BLWTR.

08-31-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,565	Daily Total	\$2,565
Cum Costs: Drilling	\$474,229	Completion	\$454,448	Well Total	\$928,678

MD	7,380	TVD	7,380	Progress	0	Days	15	MW	0.0	Visc	0.0
Formation : WASATCH	PBTd : 7211.0		Perf : 5472'-7118		PKR Depth : 0.0						

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 48/64 CHOKE. FTP- 350 PSIG, CP- 500 PSIG. 11 BFPH. RECOVERED 253 BBLs, 4118 BLWTR.

09-01-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,565	Daily Total	\$2,565
Cum Costs: Drilling	\$474,229	Completion	\$457,013	Well Total	\$931,243

MD	7,380	TVD	7,380	Progress	0	Days	16	MW	0.0	Visc	0.0
Formation : WASATCH	PBTd : 7211.0		Perf : 5472'-7118		PKR Depth : 0.0						

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 48/64 CHOKE. FTP- 350 PSIG, CP- 650 PSIG. 23 BFPH. RECOVERED 547 BBLs, 3571 BLWTR.

09-02-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,565	Daily Total	\$2,565
Cum Costs: Drilling	\$474,229	Completion	\$459,578	Well Total	\$933,808

MD 7,380 TVD 7,380 Progress 0 Days 17 MW 0.0 Visc 0.0

Formation : WASATCH PBTD : 7211.0 Perf : 5472'-7118 PKR Depth : 0.0

Activity at Report Time: WO FACILITIES

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 48/64" CHOKE. FTP 350 PSIG. CP 750 PSIG. 10 BFPH. RECOVERED 237 BLW. 3334 BLWTR. SI. WO FACILITIES .

FINAL COMPLETION DATE: 09/01/08

09-19-2008 Reported By DUANE COOK

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$474,229	Completion	\$459,578	Well Total	\$933,808

MD 7,380 TVD 7,380 Progress 0 Days 18 MW 0.0 Visc 0.0

Formation : WASATCH PBTD : 7211.0 Perf : 5472'-7118 PKR Depth : 0.0

Activity at Report Time: INITIAL PRODUCTION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	INITIAL PRODUCTION - OPENING PRESSURE: TP 1250 PSIG & CP 1700 PSIG. TURNED WELL OVER TO QUESTAR SALES AT 9:30 HRS, 9/18/08. FLOWED 890 MCFD RATE ON 14/64" CHOKE. STATIC 313. QGM METER #7863.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU0281

1a. Type of Well Oil Well Gas Well Dry Other
b. Type of Completion New Well Work Over Deepen Plug Back Diff. Resvr.
Other _____

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.
CHAPITA WELLS

2. Name of Operator
EOG RESOURCES, INC. Contact: MICKENZIE THACKER
E-Mail: MICKENZIE_THACKER@EOGRESOURCES.COM

8. Lease Name and Well No.
CHAPITA WELLS UNIT 749-12

3. Address 1060 E. HWY 40
VERNAL, UT 84078 3a. Phone No. (include area code)
Ph: 435-781-9145

9. API Well No.
43-047-39931

4. Location of Well (Report location clearly and in accordance with Federal requirements)*
At surface NESE 1699FSL 821FEL 40.04804 N Lat, 109.38185 W Lon
At top prod interval reported below NESE 1699FSL 821FEL 40.04804 N Lat, 109.38185 W Lon
At total depth NESE 1699FSL 821FEL 40.04804 N Lat, 109.38185 W Lon

10. Field and Pool, or Exploratory
NATURAL BUTTES

11. Sec., T., R., M., or Block and Survey
or Area Sec 12 T9S R22E Mer SLB

12. County or Parish
UINTAH 13. State
UT

14. Date Spudded
07/15/2008 15. Date T.D. Reached
07/26/2008 16. Date Completed
 D & A Ready to Prod.
09/18/2008

17. Elevations (DF, KB, RT, GL)*
4821 GL

18. Total Depth: MD 7380 TVD 19. Plug Back T.D.: MD 7211 TVD 20. Depth Bridge Plug Set: MD TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
RST/CBL/CCL/VDL/GR 22. Was well cored? No Yes (Submit analysis)
Was DST run? No Yes (Submit analysis)
Directional Survey? No Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12.250	9.625 J-55	36.0	0	2356		627		0	
7.875	4.500 N-80	11.6	0	7380		1175		630	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	6601							

25. Producing Intervals

26. Perforation Record 5472

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) WASTACH	5472	7118	6944 TO 7118		3	
B)			6618 TO 6898		3	
C)			6481 TO 6581		3	
D)			6257 TO 6433		3	

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.


Depth Interval	Amount and Type of Material
6944 TO 7118	49,238 GALS GELLED WATER & 147,400# 20/40 SAND
6618 TO 6898	40,040 GALS GELLED WATER & 109,300# 20/40 SAND
6481 TO 6581	39,123 GALS GELLED WATER & 109,100# 20/40 SAND
6257 TO 6433	36,414 GALS GELLED WATER & 99,000# 20/40 SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
09/18/2008	09/21/2008	24	→	0.0	1010.0	40.0			
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
14/64	1025	1250.0	→	0	1010	40		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						



(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #64066 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)

SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
WASTACH	5472	7118		GREEN RIVER MAHOGANY UTELAND BUTTE WASATCH CHAPITA WELLS BUCK CANYON PRICE RIVER	1866 2488 4701 4830 5410 6101 7187

32. Additional remarks (include plugging procedure):

33. Circle enclosed attachments:

- 1. Electrical/Mechanical Logs (1 full set req'd.)
- 2. Geologic Report
- 3. DST Report
- 4. Directional Survey
- 5. Sundry Notice for plugging and cement verification
- 6. Core Analysis
- 7. Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #64066 Verified by the BLM Well Information System.
For EOG RESOURCES, INC., sent to the Vernal**

Name (please print) MICKENZIE THACKER Title OPERATIONS CLERK

Signature  Date 10/22/2008

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

Chapita Wells Unit 749-12 - ADDITIONAL REMARKS (CONTINUED):

26. PERFORATION RECORD

5819-6154	3/SPF
5559-5579	3/SPF
5472-5499	3/SPF

27. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.

5819-6154	32,458 GALS GELLED WATER & 84,500# 20/40 SAND
5559-5579	39,850 GALS GELLED WATER & 107,600# 20/40 SAND
5472-5499	40,538 GALS GELLED WATER & 110,580# 20/40 SAND

Perforated the North Horn from 6944-45', 6954-55', 6960-62', 6968-69', 6983-84', 7077-79', 7082-84', 7108-09', 7117-18' w/ 3 spf.

Perforated the North Horn from 6618-19', 6632-33', 6649-50', 6718-19', 6722-24', 6727-29', 6762-63', 6896-98' w/ 3 spf.

Perforated the Ba from 6481-82', 6498-99', 6509-10', 6557-58', 6566-68', 6573-75', 6579-81' w/ 3 spf.

Perforated the Ba from 6257-58', 6274-75', 6284-85', 6315-16', 6326-27', 6348-49', 6360-61', 6378-79', 6391-92', 6401-02', 6428-29', 6432-33' w/ 3 spf.

Perforated the Ca from 5819-20', 5826-27', 5862-63', 5878-79', 5911-12', 6006-07', 6021-22', 6060-61', 6072-73', 6080-81', 6088-89', 6153-54' w/ 3 spf.

Perforated the Ca from 5559-61', 5567-71', 5575-79' w/ 3 spf.

Perforated the Ca from 5472-74', 5478-80', 5484-86', 5488-90', 5497-99' w/ 3 spf.

STATE OF UTAH
 DEPARTMENT OF NATURAL RESOURCES
 DIVISION OF OIL, GAS AND MINING

FORM 7

REPORT OF WATER ENCOUNTERED DURING DRILLING

Well name and number: CWU 749-12

API number: 4304739931

Well Location: QQ NESE Section 12 Township 9S Range 22E County UINTAH

Well operator: EOG

Address: 1060 E HWY 40

city VERNAL state UT zip 84078

Phone: (435) 781-9111

Drilling contractor: CRAIGS ROUSTABOUT SERVICE

Address: PO BOX 41

city JENSEN state UT zip 84035

Phone: (435) 781-1366

Water encountered (attach additional pages as needed):

DEPTH		VOLUME (FLOW RATE OR HEAD)	QUALITY (FRESH OR SALTY)
FROM	TO		
1,920	1,930	NO FLOW	NOT KNOWN

Formation tops: 1 _____ 2 _____ 3 _____
 (Top to Bottom) 4 _____ 5 _____ 6 _____
 7 _____ 8 _____ 9 _____
 10 _____ 11 _____ 12 _____

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I hereby certify that this report is true and complete to the best of my knowledge.

NAME (PLEASE PRINT) Mickenzie Thacker

TITLE Operations Clerk

SIGNATURE *Mickenzie Thacker*

DATE 10/21/2008