

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3  
AMENDED REPORT


<b>APPLICATION FOR PERMIT TO DRILL</b>				<b>1. WELL NAME and NUMBER</b> Natural Buttes Unit 642-13E		
<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				<b>3. FIELD OR WILDCAT</b> NATURAL BUTTES		
<b>4. TYPE OF WELL</b> Gas Well      Coalbed Methane Well: NO				<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b> NATURAL BUTTES		
<b>6. NAME OF OPERATOR</b> EOG Resources, Inc.				<b>7. OPERATOR PHONE</b> 435 781-9111		
<b>8. ADDRESS OF OPERATOR</b> 1060 East Highway 40, Vernal, UT, 84078				<b>9. OPERATOR E-MAIL</b> kaylene_gardner@eogresources.com		
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> U-08512-ST		<b>11. MINERAL OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>		<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>		
<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b> S				<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>		
<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b> , , UT				<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>		
<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>		<b>18. INTEND TO COMMINGLE PRODUCTION DOWNSTREAM</b> YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>		<b>19. SLANT</b> VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
<b>20. LOCATION OF WELL</b>	<b>FOOTAGES</b>	<b>QTR-QTR</b>	<b>SECTION</b>	<b>TOWNSHIP</b>	<b>RANGE</b>	<b>MERIDIAN</b>
LOCATION AT SURFACE	1949 FNL 858 FEL	SENE	13	10.0 S	22.0 E	S
Top of Uppermost Producing Zone	1949 FNL 858 FEL	SENE	13	10.0 S	22.0 E	S
At Total Depth	1949 FNL 858 FEL	SENE	13	10.0 S	22.0 E	S
<b>21. COUNTY</b> UINTAH		<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 629		<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 600		
		<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 1020		<b>26. PROPOSED DEPTH</b> MD: 7110 TVD: 7110		
<b>27. ELEVATION - GROUND LEVEL</b> 5314		<b>28. BOND NUMBER</b> 6196017		<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> 49-225 (A31368)		

**ATTACHMENTS**

**VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN	
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER	
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP	
<b>NAME</b> Kaylene Gardner	<b>TITLE</b> Sr. Regulatory Assistant	<b>PHONE</b> 435 781-9111
<b>SIGNATURE</b>	<b>DATE</b> 11/21/2007	<b>EMAIL</b> kaylene_gardner@eogresources.com
<b>API NUMBER ASSIGNED</b> 43047500130000		<b>APPROVAL</b>

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 07-31-08  
By: 



T10S, R22E, S.L.B.&M.

EOG RESOURCES, INC.


Well location, NBU #642-13E, located as shown in the SE 1/4 NE 1/4 of Section 13, T10S, R22E, S.L.B.&M., Uintah County, Utah.

**BASIS OF ELEVATION**

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.



**LEGEND:**

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

(NAD 83)  
 LATITUDE = 39°57'03.00" (39.950833)  
 LONGITUDE = 109°22'55.00" (109.381944)  
 (NAD 27)  
 LATITUDE = 39°57'03.12" (39.950867)  
 LONGITUDE = 109°22'52.55" (109.381265)

W 1/4 Cor. Sec. 24,  
 1991 Alum. Cap, 0.3'  
 High, Pile of Stones

**UINTAH ENGINEERING & LAND SURVEYING**  
 85 SOUTH 200 EAST - VERNAL, UTAH 84078  
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 9-14-07	DATE DRAWN: 01-01-07
PARTY J.M. K.F. S.G.		REFERENCES G.L.O. PLAT
WEATHER COOL	FILE EOG RESOURCES, INC.	

**Proposed Hole, Casing, and Cement**

<b>String</b>	<b>Hole Size</b>	<b>Casing Size</b>	<b>Top (MD)</b>	<b>Bottom (MD)</b>		
Cond	17.5	13.375	0	45		
<b>Pipe</b>	<b>Grade</b>	<b>Length</b>	<b>Weight</b>			
	H-40	45	48.0			
	<b>Cement Interval</b>	<b>Top (MD)</b>	<b>Bottom (MD)</b>			
		0	45			
		<b>Cement Description</b>	<b>Class</b>	<b>Sacks</b>	<b>Yield</b>	<b>Weight</b>
			C	0	0.0	0.0

**Proposed Hole, Casing, and Cement**

<b>String</b>	<b>Hole Size</b>	<b>Casing Size</b>	<b>Top (MD)</b>	<b>Bottom (MD)</b>		
Surf	12.25	9.625	0	2300		
<b>Pipe</b>	<b>Grade</b>	<b>Length</b>	<b>Weight</b>			
	J-55	0	2300.0			
	<b>Cement Interval</b>	<b>Top (MD)</b>	<b>Bottom (MD)</b>			
		0	2300			
		<b>Cement Description</b>	<b>Class</b>	<b>Sacks</b>	<b>Yield</b>	<b>Weight</b>
			G	185	3.82	11.0
			G	207	1.18	15.6

**Proposed Hole, Casing, and Cement**

<b>String</b>	<b>Hole Size</b>	<b>Casing Size</b>	<b>Top (MD)</b>	<b>Bottom (MD)</b>		
Prod	7.875	4.5	0	7110		
<b>Pipe</b>	<b>Grade</b>	<b>Length</b>	<b>Weight</b>			
	N-80	7110	11.6			
	<b>Cement Interval</b>	<b>Top (MD)</b>	<b>Bottom (MD)</b>			
		2100	7110			
		<b>Cement Description</b>	<b>Class</b>	<b>Sacks</b>	<b>Yield</b>	<b>Weight</b>
			G	101	3.91	11.0
			G	618	1.28	14.1

**EIGHT POINT PLAN**

**NATURAL BUTTES UNIT 642-13E**  
**SE/NE, SEC. 13, T10S, R22E, S.L.B.&M.**  
**UINTAH COUNTY, UTAH**

**1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:**

<b>FORMATION</b>	<b>TVD-RKB (ft)</b>	<b>Objective</b>	<b>Lithology</b>	
Green River	1,100		Shale	
Wasatch	4,071	Primary	Sandstone	Gas
Chapita Wells	4,609	Primary	Sandstone	Gas
Buck Canyon	5,264	Primary	Sandstone	Gas
North Horn	5,947	Primary	Sandstone	Gas
KMV Price River	6,324	Primary	Sandstone	Gas
<b>TD</b>	<b>7,110</b>			

Estimated TD: 7,110' or 200'± TD

**Anticipated BHP: 3,882 Psig**

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

**3. PRESSURE CONTROL EQUIPMENT:**

Production Hole – 5000 Psig  
 BOP schematic diagrams attached.

**4. CASING PROGRAM:**

<b>CASING</b>	<b>Hole Size</b>	<b>Length</b>	<b>Size</b>	<b>WEIGHT</b>	<b>Grade</b>	<b>Thread</b>	<b>Rating Collapse</b>	<b>Factor Burst</b>	<b>Tensile</b>
Conductor	17 ½"	0 – 45'	13 ¾"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 ¼"	0' – 2,300' KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production	7-7/8"	Surface – TD	4-½"	11.6#	N-80	LTC	6350 PSI	7780 Psi	233,000#

**Note:** 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

**All casing will be new or inspected.**

## EIGHT POINT PLAN

### NATURAL BUTTES UNIT 642-13E SE/NE, SEC. 13, T10S, R22E, S.L.B.&M.. UINTAH COUNTY, UTAH

#### 5. Float Equipment:

##### Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5<sup>th</sup> joint to surface. (15 total)

##### Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2<sup>nd</sup> joint.

#### 6. MUD PROGRAM

##### Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

**2300'± - TD** A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

#### 7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

**EIGHT POINT PLAN**

**NATURAL BUTTES UNIT 642-13E**  
**SE/NE, SEC. 13, T10S, R22E, S.L.B.&M.**  
**UINTAH COUNTY, UTAH**

**8. EVALUATION PROGRAM:**

**Logs:** Mud log from base of surface casing to TD.  
**Cased-hole Logs:** Cased-hole logs will be run in lieu of open-hole logs consisting of the following:  
**Cement Bond / Casing Collar Locator and Pulsed Neutron**

**9. CEMENT PROGRAM:**

**Surface Hole Procedure (Surface - 2300'±):**

**Lead:** 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl<sub>2</sub>, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft<sup>3</sup>/sk. yield, 23 gps water.

**Tail:** 207 sks Class "G" cement with 2% CaCl<sub>2</sub>, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft<sup>3</sup>/sk., 5.2 gps water.

**Top Out:** As necessary with Class "G" cement with 2% CaCl<sub>2</sub>, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft<sup>3</sup>/sk., 5.2 gps water.

**Note:** Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

**Production Hole Procedure (2300'± - TD)**

**Lead:** 101 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft<sup>3</sup>/sk., 24.5 gps water.

**Tail:** 618 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft<sup>3</sup>/sk., 5.9gps water.

**Note:** The above number of sacks is based on gauge-hole calculation.  
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.  
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

**Final Cement volumes will be based upon gauge-hole plus 45% excess.**

**EIGHT POINT PLAN**

**NATURAL BUTTES UNIT 642-13E**  
**SE/NE, SEC. 13, T10S, R22E, S.L.B.&M.**  
**UINTAH COUNTY, UTAH**

**10. ABNORMAL CONDITIONS:**

**Surface Hole (Surface - 2300'±):**

Lost circulation

**Production Hole (2300'± - TD):**

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

**11. STANDARD REQUIRED EQUIPMENT:**


- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

**12. HAZARDOUS CHEMICALS:**

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.


(Attachment: BOP Schematic Diagram)

**EOG RESOURCES 11" 5,000 PSI W.P. BOP CONFIGURATION**



**EOG RESOURCES CHOKE MANIFOLD CONFIGURATION  
W/ 5,000 PSI WP VALVES**

PAGE 2 OF 2



**Testing Procedure:**

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.  
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, **whichever is greater.**
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.



**Natural Buttes Unit 642-13E  
SWNE, Section 13, T10S, R22E  
Uintah County, Utah**

**SURFACE USE PLAN**

**1. EXISTING ROADS:**

- A. See attached Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 58.2 miles south of Vernal, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary.

**2. PLANNED ACCESS ROAD:**

- A. The access road will be approximately 110' in length. See attached Topo B.
- B. The access road has a 40-foot ROW w/18 foot running surface.
- C. Maximum grade of the new access road will be 8 percent.
- D. No turnouts will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No bridges, or major cuts and fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards, or fences will be required or encountered.
- I. A 40-foot permanent right-of-way is requested. No surfacing material will used.
- J. No additional storage areas will be needed for storing equipment, stockpiling, or vehicle parking.

All travel will be confined to existing access road rights-of-way.

New or reconstructed roads will be centerlined – flagged at time of location staking.

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 40 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

Traveling off the 40 foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

**3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:**

See attached TOPO map "C" for the location of wells within a one-mile radius.

**4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:**

**A. On Well Pad**

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400-bbl vertical tanks and attaching piping.
2. Gas gathering lines – A 4" gathering line will be buried from dehy to the edge of the location.

**B. Off Well Pad**

1. Proposed pipeline will transport natural gas.
2. The pipeline will be a permanent feeder line.
3. The length of the proposed pipeline is 1314' x 40'. The proposed pipeline leaves the western edge of the well pad (Lease U-08512 ST) proceeding in a southerly direction for an approximate distance of 283' tying into an existing pipeline. Pipe

will be 4" NOM, 0.156 wall, Grade X42, Zap-Lock, electric weld with a 35 mil X-Tru coating.

4. Proposed pipeline will be a 4" OD steel, zap-lok line laid on the surface
5. Proposed pipeline will be laid on surface.
6. Pipeline will be coupled using the Zap lock method. No additional off-pad facilities will be required.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All facilities will be painted with Carlsbad Canyon.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

**5. LOCATION AND TYPE OF WATER SUPPLY:**

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/or Bonanza Power Plant water source in Sec 26, T8S, R23E Uintah County, UT (State Water Right # 49-225(A31368)). Water will be hauled by a licensed trucking company.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

**6. SOURCE OF CONSTRUCTION MATERIALS:**

- A. All construction material for this pipeline will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

**7. METHODS OF HANDLING WASTE DISPOSAL:**

**A. METHODS AND LOCATION**

1. Cuttings will be confined in the reserve pit.
2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.

4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, CWU 550-30N SWD, CWU 2-29 SWD, or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
  5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit or by removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with felt and a 16 millimeter plastic liner. Sufficient bedding (i.e. weed free straw, or hay; felt; polyswell or soil) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well. Furthermore, extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will not be used, produced, stored, transported, or disposed of in association with the drilling, testing or completion of the well.

**8. ANCILLARY FACILITIES:**

None anticipated.

**9. WELL SITE LAYOUT:**

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the southeast corner of the location. The flare pit will be located downwind of the prevailing wind direction on the south side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled pit topsoil (first six inches) will be stored separate from the location topsoil. The stockpiled location topsoil will be stored in a location providing easy access for interim reclamation and protection of the topsoil. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the south.

**FENCING REQUIREMENTS:**

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion

of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16-foot gate shall be installed in any fence where a road is regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently counted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

**10. PLANS FOR RECLAMATION OF THE SURFACE:**

**A. Interim Reclamation (Producing Location)**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours – See attached Figure #3. The reserve pit will be reclaimed within 90 days from the date of the well completion, or as soon as environmental conditions allow. Before any dirt takes place, the reserve pit must be completely dry and free of all foreign obstacles.

The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

**B. Dry Hole/Abandoned Location**

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriated surface rehabilitation conditions of approval.

**11. SURFACE OWNERSHIP:**

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

**State of Utah**

**12. OTHER INFORMATION:**

- A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:
- Whether the materials appear eligible for the National Register of Historic Places;
  - The mitigation measures the operator will likely have to undertake before the site can be used.
  - A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application or herbicides or other pesticides or possible hazardous chemicals.
- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)
- D. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to

Drill” will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied, as needed, to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

A cultural resources survey will be conducted and submitted by Montgomery Archaeological Consultants. A paleontology survey will be conducted and submitted by Intermountain Paleontology.

***LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:***

**PERMITTING AGENT**

Kaylene R. Gardner  
EOG Resources, Inc.  
P.O. Box 1815  
Vernal, Ut 84078  
(435) 781-9111

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

**CERTIFICATION:**

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the Natural Buttes Unit 642-13E Well, located in the SENE, of Section 13, T10S, R22E, Uintah County, Utah; State land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

November 15, 2007  
Date

\_\_\_\_\_  
Kaylene R. Gardner, Lead Regulatory Assistant

**EOG RESOURCES, INC.**  
**NBU #642-13E**  
**SECTION 13, T10S, R22E, S.L.B.&M.**

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN SOUTHWESTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 5.1 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 1.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN RIGHT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.1 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE NORTH; FOLLOW ROAD FLAGS IN A NORTHERLY DIRECTION APPROXIMATELY 110' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 58.2 MILES.


T10S, R22E, S.L.B.&M.

EOG RESOURCES, INC.



Well location, NBU #642-13E, located as shown in the SE 1/4 NE 1/4 of Section 13, T10S, R22E, S.L.B.&M., Uintah County, Utah.

**BASIS OF ELEVATION**

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



**BASIS OF BEARINGS**  
BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

(NAD 83)  
LATITUDE = 39°57'03.00" (39.950833)  
LONGITUDE = 109°22'55.00" (109.381944)  
(NAD 27)  
LATITUDE = 39°57'03.12" (39.950867)  
LONGITUDE = 109°22'52.55" (109.381265)

- LEGEND:**
- └─┘ = 90° SYMBOL
  - = PROPOSED WELL HEAD.
  - ▲ = SECTION CORNERS LOCATED.



W 1/4 Cor. Sec. 24,  
1991 Alum. Cap, 0.3'  
High, Pile of Stones

<b>UINTAH ENGINEERING &amp; LAND SURVEYING</b>		
85 SOUTH 200 EAST - VERNAL, UTAH 84078		
(435) 789-1017		
SCALE 1" = 1000'	DATE SURVEYED: 9-14-07	DATE DRAWN: 01-01-07
PARTY J.M. K.F. S.G.		REFERENCES G.L.O. PLAT
WEATHER COOL	FILE EOG RESOURCES, INC.	

**EOG RESOURCES, INC.**


**LOCATION LAYOUT FOR**

NBU #642-13E  
SECTION 13, T10S, R22E, S.L.B.&M.  
1949' FNL 858' FEL



SCALE: 1" = 60'  
DATE: 01-01-07  
DRAWN BY: S.G.

**NOTE:**  
Flare Pit is to be located a min. of 100' from the Well Head.



**NOTES:**

Elev. Ungraded Ground At Loc. Stake = 5313.5'  
FINISHED GRADE ELEV. AT LOC. STAKE = 5308.8'

**UINTAH ENGINEERING & LAND SURVEYING**  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**EOG RESOURCES, INC.**


**TYPICAL CROSS SECTIONS FOR**

NBU #642-13E  
SECTION 13, T10S, R22E, S.L.B.&M.  
1949' FNL 858' FEL

**FIGURE #2**

1" = 40'  
X-Section  
Scale  
1" = 100'

DATE: 01-01-07  
DRAWN BY: S.G.



**NOTE:**  
Topsoil should not be Stripped Below Finished Grade on Substructure Area.

**\* NOTE:**  
FILL QUANTITY INCLUDES 5% FOR COMPACTION

**APPROXIMATE YARDAGES**

(6") Topsoil Stripping	=	2,380 Cu. Yds.
Remaining Location	=	14,270 Cu. Yds.
<b>TOTAL CUT</b>	<b>=</b>	<b>16,650 CU. YDS.</b>
<b>FILL</b>	<b>=</b>	<b>12,260 CU. YDS.</b>

EXCESS MATERIAL	=	4,390 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	4,390 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	=	0 Cu. Yds.


**UINTAH ENGINEERING & LAND SURVEYING**  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**EOG RESOURCES, INC.**  
**PRODUCTION FACILITY LAYOUT FOR**  
NBU #642-13E  
SECTION 13, T10S, R22E, S.L.B.&M.  
1949' FNL 858' FEL

**FIGURE #3**



SCALE: 1" = 60'  
DATE: 01-01-07  
DRAWN BY: S.G.



 RE-HABED AREA

**UINTAH ENGINEERING & LAND SURVEYING**  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

# EOG RESOURCES, INC.

## NBU #642-13E

LOCATED IN UINTAH COUNTY, UTAH  
SECTION 13, T10S, R22E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: EASTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHEASTERLY



**UELS** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


10 26 07  
MONTH DAY YEAR

PHOTO

TAKEN BY: J.M.

DRAWN BY: C.P.

REVISED: 00-00-00



**LEGEND:**

 PROPOSED LOCATION



**EOG RESOURCES, INC.**


NBU #642-13E  
SECTION 13, T10S, R22E, S.L.B.&M.  
1949' FNL 858' FEL



Utah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC** 10 26 07  
**MAP** MONTH DAY YEAR  
SCALE: 1:100,000 DRAWN BY: C.P. REVISED: 00-00-00





**PROPOSED LOCATION:  
NBU #642-13E**

**PROPOSED ACCESS 110' +/-**

**0.1 MI. +/-**

**1.3 MI. +/-**

R	R
22	23
E	E

**LEGEND:**

-  EXISTING ROAD
-  PROPOSED ACCESS ROAD



**EOG RESOURCES, INC.**


NBU #642-13E  
SECTION 13, T10S, R22E, S.L.B.&M.  
1949' FNL 858' FEL



**Utah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC MAP** 10 26 07  
MONTH DAY YEAR  
SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00





**LEGEND:**

- ∅ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ♂ WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED



**EOG RESOURCES, INC.**


NBU #642-13E  
 SECTION 13, T10S, R22E, S.L.B.&M.  
 1949' FNL 858' FEL



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC MAP** 10 26 07  
 MONTH DAY YEAR  
 SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00





**APPROXIMATE TOTAL PIPELINE DISTANCE = 1,314' +/-**

**LEGEND:**

-  PROPOSED ACCESS ROAD
-  EXISTING PIPELINE
-  PROPOSED PIPELINE

**EOG RESOURCES, INC.**

NBU #642-13E  
SECTION 13, T10S, R22E, S.L.B.&M.  
1949' FNL 858' FEL



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC MAP** 10 26 07  
MONTH DAY YEAR  
SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00



**WORKSHEET  
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 11/15/2007

API NO. ASSIGNED: 43-047-50013

WELL NAME: NBU 642-13E

OPERATOR: EOG RESOURCES, INC. ( N9550 )

PHONE NUMBER: 435 781-9111

CONTACT: Kaylene Gardner

PROPOSED LOCATION:

SENE 13 100S 220E  
 SURFACE: 1949 FNL 0858 FEL  
 BOTTOM: 1949 FNL 0858 FEL  
 COUNTY: UINTAH  
 LATITUDE: 39.95089 LONGITUDE: -109.3813  
 UTM SURF EASTINGS: 638280 NORTHINGS: 4423350  
 FIELD NAME: NATURAL BUTTES ( 630 )

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	DKD	1/4/08
Geology		
Surface		

LEASE TYPE: 3 - State  
 LEASE NUMBER: U-08512-ST  
 SURFACE OWNER: 3 - State

PROPOSED FORMATION: NHORN  
 COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:


- Plat
- Bond: Fed[] Ind[] Sta[3] Fee[]  
(No. 6196017 )
- N Potash (Y/N)
- Y Oil Shale 190-5 (B) or 190-3 or 190-13
- Water Permit  
(No. 49-225 (A3) )
- N RDCC Review (Y/N)  
(Date: \_\_\_\_\_ )
- N/A Fee Surf Agreement (Y/N)
- N/A Intent to Commingle (Y/N)

LOCATION AND SITING:

- \_\_\_\_\_ R649-2-3.
- Unit: NATURAL BUTTES *ok*
- \_\_\_\_\_ R649-3-2. General
- Siting: 460' From Qtr/Qtr & 920' Between Wells
- \_\_\_\_\_ R649-3-3. Exception
- Drilling Unit
- Board Cause No: 173-14
- Eff Date: 12-2-1999
- Siting: 460' fr u bdy of uncomm. Tract
- \_\_\_\_\_ R649-3-11. Directional Drill

COMMENTS: Needs Permit (12-04-07)

STIPULATIONS: 1-OIL SHALE  
2-STATEMENT OF BASIS  
3-SURFACE Csg Cnt STEP  
4-Cnt Step #3 (4 1/2" production, 2100' mo)



**NATURAL BUTTES FIELD  
NATURAL BUTTES UNIT**  
CAUSE: 173-14 / 12-2-1999

OPERATOR: EOG RESOURCES INC (N9550)

SEC: 13 T.10S R. 22E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

CAUSE: 173-14 / 12-2-1999

- Field Status**
- ABANDONED
  - ACTIVE
  - COMBINED
  - INACTIVE
  - PROPOSED
  - STORAGE
  - TERMINATED

- Unit Status**
- EXPLORATORY
  - GAS STORAGE
  - NF PP OIL
  - NF SECONDARY
  - PENDING
  - PI OIL
  - PP GAS
  - PP GEOTHERML
  - PP OIL
  - SECONDARY
  - TERMINATED

- Wells Status**
- GAS INJECTION
  - GAS STORAGE
  - LOCATION ABANDONED
  - NEW LOCATION
  - PLUGGED & ABANDONED
  - PRODUCING GAS
  - PRODUCING OIL
  - SHUT-IN GAS
  - SHUT-IN OIL
  - TEMP. ABANDONED
  - TEST WELL
  - WATER INJECTION
  - WATER SUPPLY
  - WATER DISPOSAL
  - DRILLING



OIL, GAS & MINING



PREPARED BY: DIANA MASON  
DATE: 27-NOVEMBER-2007

# Application for Permit to Drill

## Statement of Basis

12/19/2007

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
611	43-047-50013-00-00	SITLA	GW	S	No
<b>Operator</b>	EOG RESOURCES, INC.	<b>Surface Owner-APD</b>			
<b>Well Name</b>	Natural Buttes Unit 642-13E	<b>Unit</b>	NATURAL BUTTES		
<b>Field</b>	NATURAL BUTTES	<b>Type of Work</b>	DRILL		
<b>Location</b>	SENE 13 10S 22E S 1949 FNL 858 FEL	<b>GPS Coord (UTM)</b> 638280E 4423350N			

### Geologic Statement of Basis

EOG proposes to set 2,300' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 4,300'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 13. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought up above the base of the moderately saline ground water to isolate it from fresher waters uphole.

Brad Hill  
APD Evaluator

12/19/2007  
Date / Time

### Surface Statement of Basis

The general area is in the southeast end of the Natural Buttes Unit, and contains the White River and short rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¼ mile to 1 mile. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 35 air miles and 58.1 road miles to the northwest. The area is accessed by Utah State, Uintah County and oilfield development Roads to within 0.1 mile of the location where a new road will be constructed.

The proposed NBU 642-13E gas well location lies longitudinally along the east edge of a flat, which breaks off sharply into a steep draw that begins south of the location. As the draw continues it becomes very steep and is rimmed with sandstone ledges. This draw joins two other draws and runs westerly to the White River. Fill from the location is proposed to spill off the edge of this draw. Byron Tolman, representing EOG, committed to reduce the width of the location on the east so that during construction the toe of the fills not extend beyond the staked corners of 1, 2 and 8. A deep draw also begins near the northwest limits of the location. The location was staked to avoid this draw. When completed, no drainage concerns requiring diversions will exist. The reserve pit is proposed in an area of cut. Due to the formations in the area and the short distance to the River the reserve pit should be double lined with a 20-mil liner and adequately padded. To provide for early detection of potential leaks from the reserve pit, daily monitoring of the pit level and volume needs to occur. The location should be stable and pose no other problems for drilling and operating a well and appears to be the only site available in the immediate area. The White River is not within view of the location.

Both the surface and minerals are owned by SITLA. Ed Bonner and Jim Davis of SITLA were invited to the pre-site evaluation. Neither attended.

Daniel Emmet represented the Utah Division of Wildlife Resources. Mr. Emmet stated the area is classified as crucial yearlong habitat for antelope. He however recommended no stipulations for this species as the loss of forage from this location is not significant and water not forage is the factor limiting the herd population in the area. Also the following statement by the UDWR was emailed to DOGM for consideration in approving the

# Application for Permit to Drill

## Statement of Basis

12/19/2007

Utah Division of Oil, Gas and Mining

Page 2

Permit to Drill. "The White River in Utah is home to one of the more intact native fish assemblages in the Colorado River basin. We regularly see large adult Colorado pikeminnow (*Ptychocheilus lucius*) and all age/size classes of flannelmouth sucker (*Catostomus latipinnis*), bluehead sucker (*Catostomus discobolus*), and roundtail chub (*Gila robusta*). The pikeminnow is an endangered species covered under the ESA and managed through activities funded by the Upper Colorado River Endangered Fish Recovery Program. The remaining three species are state sensitive species covered under a Range-wide Conservation Agreement and Strategy signed by six states and numerous federal and tribal agencies and a State Management Plan for the three species also signed by state, federal, and tribal agencies. We have planned many conservation actions for the three species around the state; however, we have not worried about the White River populations as much because we still see all life stages here. If development is allowed without mitigation for potential impacts to these species, we could see a disruption in this population like we've seen in other streams and rivers across the state. Spills and/or leaks may impact these fish by a number of means, from simply causing a fish kill and harming all individuals that cannot escape the spill to interruption of spawning cues (meaning they may go one or more years depending on the severity of the spill without spawning)."

Mr Emmett gave Byron Tolman, representing EOG Resources a DWR recommended seed mix to use when re-vegetating the area.

The reserve pit is proposed on the southwest portion of the location within an area of cut. Dimensions are 75' x 175' x 12' deep. Due to the formations in the area and the short distance to the River the reserve pit should be double lined with a 20-mil liner and adequately padded. To provide for early detection of potential leaks from the reserve pit, daily monitoring of the pit level and volume needs to occur. EOG is required to notify the Roosevelt Field Office (435-722-3417) at least 24 hours prior to installing the pit liners.

Floyd Bartlett  
Onsite Evaluator

12/4/2007  
Date / Time

### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A double synthetic liner each with a minimum thickness of 20 mils and an appropriate thickness of felt sub-liner to cushion the liners shall be properly installed and maintained in the reserve pit. EOG is required to notify the Roosevelt Field Office (435-722-3417) at least 24 hours prior to installing the pit liners.

# ON-SITE PREDRILL EVALUATION

## Utah Division of Oil, Gas and Mining

**Operator** EOG RESOURCES, INC.  
**Well Name** Natural Buttes Unit 642-13E  
**API Number** 43-013-10497-0      **APD No** 611      **Field/Unit** NATURAL BUTTES  
**Location: 1/4,1/4 SENE**      **Sec** 13      **Tw** 10S      **Rng** 22E      1949 FNL 858 FEL  
**GPS Coord (UTM)**      **Surface Owner**

### Participants

Floyd Bartlett (DOGM), Byron Tolman (Agent for EOG Resources) and Daniel Emmet (UDWR).

### Regional/Local Setting & Topography

The general area is in the southeast end of the Natural Buttes Unit, and contains the White River and short rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¼ mile to 1 mile. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 35 air miles and 58.1 road miles to the northwest. The area is accessed by Utah State, Uintah County and oilfield development Roads to within 0.1 mile of the location where a new road will be constructed.

The proposed NBU 642-13E gas well location lies longitudinally along the east edge of a flat, which breaks off sharply into a steep draw that begins south of the location. As the draw continues it becomes very steep and is rimmed with sandstone ledges. This draw joins two other draws and runs westerly to the White River. Fill from the location is proposed to spill off the edge of this draw. Byron Tolman, representing EOG, committed to reduce the width of the location on the east so that during construction the toe of the fills not extend beyond the staked corners of 1, 2 and 8. A deep draw also begins near the northwest limits of the location. The location was staked to avoid this draw. When completed, no drainage concerns requiring diversions will exist. The reserve pit is proposed in an area of cut. Due to the formations in the area and the short distance to the River the reserve pit should be double lined with a 20-mil liner and adequately padded. To provide for early detection of potential leaks from the reserve pit, daily monitoring of the pit level and volume needs to occur. The location should be stable and pose no other problems for drilling and operating a well and appears to be the only site available in the immediate area. The White River is not within view of the location. Approximately 6 inches of snow covered the area.

Both the surface and minerals are owned by SITLA.

### Surface Use Plan

#### **Current Surface Use**

Grazing  
Recreational  
Wildlife Habitat

#### **New Road**

<b>Miles</b>	<b>Well Pad</b>		<b>Src Const Material</b>	<b>Surface Formation</b>
0.1	<b>Width</b> 361	<b>Length</b> 400	Onsite	UNTA

**Ancillary Facilities** N

### Waste Management Plan Adequate?

### Environmental Parameters

**Affected Floodplains and/or Wetland** N

**Flora / Fauna**

The area was covered with snow. Identifiable vegetation consists of black sagebrush, Gardner saltbrush, greasewood, horsebrush, and broom snakeweed.

Antelope, coyote, small mammals and birds. Winter domestic sheep grazing.

**Soil Type and Characteristics**

Surface soils are a shallow rocky sandy clay loam.

**Erosion Issues** N

**Sedimentation Issues** Y

Fill from the location is proposed to spill off the edge of the location into a draw.

**Site Stability Issues** Y

. Due to the formations in the area and the short distance to the River the reserve pit should be double lined with a 20-mil liner and adequately padded.

**Drainage Diverson Required** N

**Berm Required?** N

**Erosion Sedimentation Control Required?** Y

Reduce the width of the location on the east so that during construction the toe of the fills not extend beyond the staked corners of 1, 2 and 8.

**Paleo Survey Run?** Y    **Paleo Potental Observed?** N    **Cultural Survey Run?** Y    **Cultural Resources?** N

**Reserve Pit**

**Site-Specific Factors**

**Site Ranking**

<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>	300 to 1320	10
<b>Native Soil Type</b>	High permeability	20
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>	10 to 20	5
<b>Affected Populations</b>	<10	0
<b>Presence Nearby Utility Conduits</b>	Not Present	0

**Final Score** 40 1 **Sensitivity Level**

**Characteristics / Requirements**

The reserve pit is proposed on the southwest portion of the location within an area of cut. Dimensions are 75' x 175' x 12' deep. Due to the formations in the area and the short distance to the River the reserve pit should be double lined with a 20-mil liner and adequately padded. To provide for early detection of potential leaks from the reserve pit, daily monitoring of the pit level and volume needs to occur.

**Closed Loop Mud Required?** N    **Liner Required?** Y    **Liner Thickness** 40    **Pit Underlayment Required?** Y

**Other Observations / Comments**

ATV's were used to access the site. GPS was not working. Snow covered the area.

Floyd Bartlett  
Evaluator

12/4/2007  
Date / Time

Casing Schematic

BHP  $0.052(7110)10.5 = 3882 \text{ psi}$   
 anticipate 3882 psi

Gas  $.12(7110) = 853$   
 $3882 - 853 = 3029 \text{ psi MASP}$

BOPE 5M ✓

Burst 3520  
 70% 2464 psi

Max P @ surf. shoe  
 $.22(48110) = 1058 \text{ psi}$   
2824 psi

9-5/8"  
 MW 8.4  
 Frac 19.3

Test to 2400 psi ✓

Stop surf. cont.

✓ Adequate <sup>ODD</sup> 4/4/08



4-1/2"  
 MW 10.5

Surface

12 3/4%

15%

Uinta

TOC @ 652.  
 to surf. w/6% ✓  
 \* STOP

1100' Green River  
 → EOG to surf, tail to 1800'

1877' tail

Surface  
 2300. MD

Proposed: ✓  
 Cont to 2100', tail to 400' above Wasatch  
 Proposed vol w/gauge hole  
 Strip #3

TOC @ 3331.

4071' Wasatch

4300' ± BMSW

4590' TOC tail

4609' Chapita Wells

5264' Buck Canyon

5947' North Horn

6324' KMV Price River

Production  
 7110. MD

Well name:	<b>2007-12 EOG NBU 642-13E</b>	
Operator:	<b>EOG Resources Inc.</b>	Project ID:
String type:	Surface	43-047-50013
Location:	Uintah County	

<b>Design parameters:</b>	<b>Minimum design factors:</b>	<b>Environment:</b>
<b>Collapse</b> Mud weight: 8.400 ppg Design is based on evacuated pipe.	<b>Collapse:</b> Design factor: 1.125	H2S considered? No Surface temperature: 75 °F Bottom hole temperature: 107 °F Temperature gradient: 1.40 °F/100ft Minimum section length: 290 ft
<b>Burst</b> Max anticipated surface pressure: 2,024 psi Internal gradient: 0.120 psi/ft Calculated BHP: 2,300 psi  No backup mud specified.	<b>Burst:</b> Design factor: 1.00	Cement top: 652 ft
	<b>Tension:</b> 8 Round STC: 1.80 (J) 8 Round LTC: 1.80 (J) Buttress: 1.60 (J) Premium: 1.50 (J) Body yield: 1.50 (B)	<b>Non-directional string.</b>
	Tension is based on buoyed weight. Neutral point: 2,014 ft	<b>Re subsequent strings:</b> Next setting depth: 7,110 ft Next mud weight: 10,500 ppg Next setting BHP: 3,878 psi Fracture mud wt: 19,250 ppg Fracture depth: 2,300 ft Injection pressure: 2,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2300	9.625	36.00	J-55	ST&C	2300	2300	8.796	998.3

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1004	2020	2.013	2300	3520	1.53	73	394	5.43 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801-538-5357  
FAX: 801-359-3940

Date: December 28, 2007  
Salt Lake City, Utah

Remarks:  
Collapse is based on a vertical depth of 2300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	<b>2007-12 EOG NBU 642-13E</b>		
Operator:	<b>EOG Resources Inc.</b>	Project ID:	43-047-50013
String type:	Production		
Location:	Uintah County		

**Design parameters:**

**Collapse**

Mud weight: 10.500 ppg  
 Design is based on evacuated pipe.

**Burst**

Max anticipated surface pressure: 2,314 psi  
 Internal gradient: 0.220 psi/ft  
 Calculated BHP 3,878 psi

No backup mud specified.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Tension:**

8 Round STC: 1.80 (J)  
 8 Round LTC: 1.80 (J)  
 Buttress: 1.60 (J)  
 Premium: 1.50 (J)  
 Body yield: 1.50 (B)

Tension is based on buoyed weight.  
 Neutral point: 5,994 ft

**Environment:**

H2S considered? No  
 Surface temperature: 75 °F  
 Bottom hole temperature: 175 °F  
 Temperature gradient: 1.40 °F/100ft  
 Minimum section length: 1,500 ft

Cement top: 3,331 ft

**Non-directional string.**

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	7110	4.5	11.60	N-80	LT&C	7110	7110	3.875	620.5
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3878	6350	1.637	3878	7780	2.01	70	223	3.21 J

Prepared by: Helen Sadik-Macdonald  
 Div of Oil, Gas & Minerals

Phone: 801-538-5357  
 FAX: 801-359-3940

Date: December 28, 2007  
 Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 7110 ft, a mud weight of 10.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

**From:** Jim Davis  
**To:** Mason, Diana  
**Date:** 7/30/2008 4:03 PM  
**Subject:** SITLA APD approval 7/30/08

**CC:** Bonner, Ed; Garrison, LaVonne  
 The following wells have been approved by SITLA including arch and paleo clearance.

Operator	Well Name	API #
Kerr McGEE	NBU 921-26M2AS	4304740113
Kerr McGEE	NBU 922-32O1T	4304740116
Kerr McGEE	NBU 922-29J	4304740119
ConocoPhillips	Utah 17-1174	4300731418
EOG Res	NBU 672-25E	4304750028
XTO Energy	St of Ut 16-8-32-23D	4301530741
XTO Energy	St of Ut 16-8-31-43D	4301530742
Gasco Prod	Gate Cyn St 12-21-11-15	4301333858
Gasco Prod	State 42-32-9-19	4304739795
National Fuel	NFC Lindisfarne St 43-35	4304739852
EOG Resources	NBU 642-13E	4304750013
EOG Resources	NBU 640-13E	4304750014
EOG Resources	NBU 663-24E	4304750010
EOG Resources	NBU 661-24E	4304750011
Kerr McGEE	NBU 921-34MT	4304739402
Kerr McGEE	NBU 1022-25H	4304739033
Kerr McGEE	State 1022-25I	4304739034
Westport O&G	State 921-32N	4304737957
Westport O&G	State 921-32O	4304737958
EOG Resources	NBU 638-13E	4304750016

-Jim Davis



JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

July 31, 2008

EOG Resources, Inc.  
1060 East Highway 40  
Verbal, UT 84078

Re: Natural Buttes Unit 642-13E Well, 1949' FNL, 858' FEL, SE NE, Sec. 13, T. 10 South, R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-50013.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Uintah County Assessor  
Bureau of Land Management, Vernal Office  
SITLA

**Operator:** EOG Resources, Inc.  
**Well Name & Number** Natural Buttes Unit 642-13E  
**API Number:** 43-047-50013  
**Lease:** U-08512-ST

**Location:** SE NE                      **Sec.** 13                      **T.** 10 South                      **R.** 22 East

### Conditions of Approval

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### 2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at:           (801) 538-5338 office           (801) 942-0871 home
- Carol Daniels at:       (801) 538-5284 office
- Dustin Doucet at:      (801) 538-5281 office           (801) 733-0983 home

#### 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
7. Surface casing shall be cemented to the surface.
8. Cement volume for the 4 1/2" production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 2100' MD in order to adequately isolate the Green River formation.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>			5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-08512-ST
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.			6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____			7. UNIT or CA AGREEMENT NAME: Natural Buttes
2. NAME OF OPERATOR: EOG Resources, Inc.			8. WELL NAME and NUMBER: Natural Buttes Unit 642-13E
3. ADDRESS OF OPERATOR: 1060 East Highway 40      City: Vernal      STATE: UT      ZIP: 84078		PHONE NUMBER: (435) 781-9145	9. API NUMBER: 43-047-50013
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1949' FNL & 858' FEL 39.950833 Lat 109.381944 Lon			10. FIELD AND POOL, OR WILDCAT: Natural Buttes
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 13 10S 22E S			COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Change Drilling Plan</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. respectfully requests authorization to change the Drilling Plan as per the attached.

Conductor size: Item 4

Logs: Item 8

Please see the attached revised Drilling Plan reflecting the purposed changes.

COPY SENT TO OPERATOR

Date: 3.5.2009

Initials: KS

NAME (PLEASE PRINT) Mickenzie Thacker TITLE Operations Clerk  
SIGNATURE Mickenzie Thacker DATE 2/13/2009

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING  
DATE: 3/4/09  
BY: [Signature] (See instructions on Reverse Side)

RECEIVED

FEB 18 2009

DIV. OF OIL, GAS & MINING

4. CASING PROGRAM:

<u>CASING</u>	<u>Hole Size</u>	<u>Length</u>	<u>Size</u>	<u>WEIGH T</u>	<u>Grade</u>	<u>Thread</u>	<u>Rating Collapse</u>	<u>Factor Burst</u>	<u>Tensile</u>
Conductor	26"	40 - 60'	16"	65#	H-40	STC	670 PSI	1640 PSI	736,000#

8. EVALUATION PROGRAM:

**Cased-hole Logs:**

Cased-hole logs will be run in lieu of open-hole logs consisting of the following: **Cement Bond / Casing Collar Locator / Variable Density and Gamma Ray**

**EIGHT POINT PLAN**

**NATURAL BUTTES UNIT 642-13E**  
**SE/NE, SEC. 13, T10S, R22E, S.L.B.&M..**  
**UINTAH COUNTY, UTAH**

**1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:**

<b>FORMATION</b>	<b>TVD-RKB (ft)</b>	<b>Objective</b>	<b>Lithology</b>	
Green River	1,100		Shale	
Wasatch	4,071	Primary	Sandstone	Gas
Chapita Wells	4,609	Primary	Sandstone	Gas
Buck Canyon	5,264	Primary	Sandstone	Gas
North Horn	5,947	Primary	Sandstone	Gas
KMV Price River	6,324	Primary	Sandstone	Gas
<b>TD</b>	<b>7,110</b>			

Estimated TD: **7,110' or 200'± TD**      **Anticipated BHP: 3,882 Psig**

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

**3. PRESSURE CONTROL EQUIPMENT:**      Production Hole – 5000 Psig  
 BOP schematic diagrams attached.

**4. CASING PROGRAM:**

<b>CASING</b>	<b>Hole Size</b>	<b>Length</b>	<b>Size</b>	<b>WEIGHT</b>	<b>Grade</b>	<b>Thread</b>	<b>Rating Collapse</b>	<b>Factor Burst</b>	<b>Tensile</b>
<b>Conductor</b>	<b>26"</b>	<b>40 - 60'</b>	<b>16"</b>	<b>65#</b>	<b>H-40</b>	<b>STC</b>	<b>670 PSI</b>	<b>1640 PSI</b>	<b>736,000#</b>
<b>Surface</b>	<b>12 ¼"</b>	<b>0' – 2,300' KB±</b>	<b>9-5/8"</b>	<b>36.0#</b>	<b>J-55</b>	<b>STC</b>	<b>2020 PSI</b>	<b>3520 Psi</b>	<b>394,000#</b>
<b>Production</b>	<b>7-7/8"</b>	<b>Surface – TD</b>	<b>4-½"</b>	<b>11.6#</b>	<b>N-80</b>	<b>LTC</b>	<b>6350 PSI</b>	<b>7780 Psi</b>	<b>233,000#</b>

## EIGHT POINT PLAN

### NATURAL BUTTES UNIT 642-13E SE/NE, SEC. 13, T10S, R22E, S.L.B.&M. UINTAH COUNTY, UTAH

**Note:** 12-1/4" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

**All casing will be new or inspected.**

#### **5. Float Equipment:**

##### **Surface Hole Procedure (0' - 2300'±)**

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5<sup>th</sup> joint to surface. (15 total)

##### **Production Hole Procedure (2300'± - TD):**

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-1/2", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2<sup>nd</sup> joint.

#### **6. MUD PROGRAM**

##### **Surface Hole Procedure (Surface - 2300'±):**

Air/air mist or aerated water.

**Production Hole Procedure (2300'± - TD):** Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

**2300'± - TD** A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

## EIGHT POINT PLAN

### NATURAL BUTTES UNIT 642-13E SE/NE, SEC. 13, T10S, R22E, S.L.B.&M. UINTAH COUNTY, UTAH

#### 7. VARIANCE REQUESTS:

**Reference:** Onshore Oil and Gas Order No. 1  
Onshore Oil and Gas Order No. 2 – Section E: Special Drilling Operations

- EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line to be 100' in length. (Where possible, a straight run blooie line will be used).
- EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be approximately 75' in length.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring dedusting equipment. Dust during air drilling operations is controlled by water mist.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring an automatic igniter or continuous pilot light on the blooie line. (Not required on aerated water system).
- EOG Resources, Inc. requests a variance that compressors are located in the opposite direction from the blooie line a minimum of 100 feet from the well bore. (Air Compressors are rig mounted).

#### 8. EVALUATION PROGRAM:

**Cased-hole Logs:** Cased-hole logs will be run in lieu of open-hole logs consisting of the following: **Cement Bond / Casing Collar Locator / Variable Density and Gamma Ray**

#### 9. CEMENT PROGRAM:

##### Surface Hole Procedure (Surface - 2300'±):

**Lead:** 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl<sub>2</sub>, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft<sup>3</sup>/sk. yield, 23 gps water.

**Tail:** 207 sks Class "G" cement with 2% CaCl<sub>2</sub>, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft<sup>3</sup>/sk., 5.2 gps water.

## EIGHT POINT PLAN

### NATURAL BUTTES UNIT 642-13E SE/NE, SEC. 13, T10S, R22E, S.L.B.&M.. UINTAH COUNTY, UTAH

**Top Out:** As necessary with Class "G" cement with 2% CaCl<sub>2</sub>, 1/4#/sk Flocele mixed at 15.6 ppg, 1.18 ft<sup>3</sup>/sk., 5.2 gps water.

**Note:** Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

#### Production Hole Procedure (2300'± - TD)

**Lead:** 101 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft<sup>3</sup>/sk., 24.5 gps water.

**Tail:** 618 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft<sup>3</sup>/sk., 5.9gps water.

**Note:** The above number of sacks is based on gauge-hole calculation.  
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.  
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

**Final Cement volumes will be based upon gauge-hole plus 45% excess.**

#### 10. ABNORMAL CONDITIONS:

##### Surface Hole (Surface - 2300'±):

Lost circulation

##### Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

#### 11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

#### 12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this

## **EIGHT POINT PLAN**

### **NATURAL BUTTES UNIT 642-13E** **SE/NE, SEC. 13, T10S, R22E, S.L.B.&M..** **UINTAH COUNTY, UTAH**

well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

(Attachment: BOP Schematic Diagram)

#### **13. Air Drilling Operations:**

1. Main Air Compressors are 1250 CFM 350 psi with 2000 psi Boosters and are rig mounted.
2. Secondary Air Compressors are 1170 CFM 350 psi with 2000 psi Boosters and are rig mounted.
3. Minimum setting depth of conductor casing will be 60' GL or 10'± into competent formation, whichever is deeper, as determined by the EOG person in charge. Exceptions must be approved by an EOG drilling superintendent or manager.
4. The diameter of the diverter flow line will be a minimum of 10" to help reduce back pressure on the well bore during uncontrolled flow.
5. Rat and Mouse hole drilling will occur only after surface casing has been set and cemented.
6. EOG Resources, Inc. will use a properly maintained and lubricated stripper head.

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: EOG RESOURCES  
Address: 1060 East Highway 40  
city VERNAL  
state UT zip 84078

Operator Account Number: N 9550  
Phone Number: (435) 781-9145

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-50057	NATURAL BUTTES UNIT 666-24E		SWSE	24	10S	20E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<i>AB</i>	99999	<i>2900</i>	2/23/2009			<i>3/5/09</i>	
Comments: WASATCH <i>NHORN = WSTC = WSMVD</i>							

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-50013	NATURAL BUTTES UNIT 642-13E		SENE	13	10S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<i>AB</i>	99999	<i>2900</i>	2/24/2009			<i>3/5/09</i>	
Comments: WASATCH/MESAVERDE							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mickenzie Thacker

Name (Please Print)

*Mickenzie Thacker*

Signature

Operator's Clerk

*2/27/2009*

Title

Date

**RECEIVED**

**MAR 02 2009**

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>			5. LEASE DESIGNATION AND SERIAL NUMBER: <b>UTU-08512-ST</b>
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.			6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>Natural Buttes</b>
1. TYPE OF WELL <b>OIL WELL</b> <input type="checkbox"/> <b>GAS WELL</b> <input checked="" type="checkbox"/> <b>OTHER</b> _____	2. NAME OF OPERATOR: <b>EOG Resources, Inc.</b>		7. UNIT or CA AGREEMENT NAME: <b>Natural Buttes</b>
3. ADDRESS OF OPERATOR: <b>1060 East Highway 40 Vernal UT 84078</b>	PHONE NUMBER: <b>(435) 781-9145</b>	8. WELL NAME and NUMBER: <b>Natural Buttes Unit 642-13E</b>	
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>1949' FNL &amp; 858' FEL 39.950833 Lat 109.381944 Lon</b>		9. API NUMBER: <b>43-047-50013</b>	
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN <b>SENE 13 10S 22E S</b>		10. FIELD AND POOL, OR WMLDCAT: <b>Natural Buttes</b>	
		COUNTY: <b>UINTAH</b>	
		STATE: <b>UTAH</b>	

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well Spud</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well was spud on 2/24/2009.

NAME (PLEASE PRINT) <u>Mickenzie Thacker</u>	TITLE <u>Operations Clerk</u>
SIGNATURE <u><i>Mickenzie Thacker</i></u>	DATE <u>2/27/2009</u>

(This space for State use only)

**RECEIVED**  
**MAR 02 2009**

**DIV. OF OIL, GAS & MINING**

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	<b>FORM 9</b>  <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> U-08512-ST
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>  <b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>1. TYPE OF WELL</b> Gas Well	<b>8. WELL NAME and NUMBER:</b> NBU 642-13E
<b>2. NAME OF OPERATOR:</b> EOG Resources, Inc.	<b>9. API NUMBER:</b> 43047500130000
<b>3. ADDRESS OF OPERATOR:</b> 1060 East Highway 40 , Vernal, UT, 84078	<b>PHONE NUMBER:</b> 435 781-9111 Ext
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1949 FNL 0858 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SENE Section: 13 Township: 10.0S Range: 22.0E Meridian: S	<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES  <b>COUNTY:</b> UINTAH  <b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 6/26/2009	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well was turned to sales on 6/26/2009. Please see the attached operations summary report for drilling and completion operations performed on the subject well.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 July 01, 2009

<b>NAME (PLEASE PRINT)</b> Mickenzie Thacker	<b>PHONE NUMBER</b> 435 781-9145	<b>TITLE</b> Operations Clerk
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/1/2009	

# WELL CHRONOLOGY REPORT

Report Generated On: 07-01-2009

<b>Well Name</b>	NBU 642-13E	<b>Well Type</b>	DEVG	<b>Division</b>	DENVER
<b>Field</b>	NATURAL BUTTES UNIT	<b>API #</b>	43-047-50013	<b>Well Class</b>	COMP
<b>County, State</b>	UINTAH, UT	<b>Spud Date</b>	04-09-2009	<b>Class Date</b>	
<b>Tax Credit</b>	N	<b>TVD / MD</b>	7,110/ 7,110	<b>Property #</b>	062349
<b>Water Depth</b>	0	<b>Last CSG</b>	0.0	<b>Shoe TVD / MD</b>	0/ 0
<b>KB / GL Elev</b>	5,322/ 5,309				
<b>Location</b>	Section 13, T10S, R22E, SENE, 1949 FNL & 858 FEL				

<b>Event No</b>	1.0	<b>Description</b>	DRILL & COMPLETE		
<b>Operator</b>	EOG RESOURCES, INC	<b>WI %</b>	100.0	<b>NRI %</b>	71.947

<b>AFE No</b>	306021	<b>AFE Total</b>	1,274,835	<b>DHC / CWC</b>	567,835/ 707,000
<b>Rig Contr</b>	ELENBURG	<b>Rig Name</b>	ELENBURG #28	<b>Start Date</b>	08-21-2008
<b>08-21-2008</b>	<b>Reported By</b>	SHEILA MALLOY			
<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Daily Total</b>	\$0
<b>Cum Costs: Drilling</b>	\$0	<b>Completion</b>	\$0	<b>Well Total</b>	\$0
<b>MD</b>	0	<b>TVD</b>	0	<b>Progress</b>	0
<b>Days</b>	0	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation :</b>	<b>PBTD : 0.0</b>		<b>Perf :</b>	<b>PKR Depth : 0.0</b>	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA
			1949' FNL & 858' FEL (SE/NE)
			SECTION 13, T10S, R22E
			UINTAH COUNTY, UTAH
			LAT 39.950833, LONG 109.381944 (NAD 83)
			LAT 39.950867, LONG 109.381265 (NAD 27)
			ELENBURG #28
			OBJECTIVE: 7110' TD, MESAVERDE
			DW/GAS
			NATURAL BUTTES PROSPECT
			DD&A: NATURAL BUTTES
			NATURAL BUTTES FIELD
			LEASE: U-08512-ST
			ELEVATION: 5313.5' NAT GL, 5308.8' PREP GL (DUE TO ROUNDING THE PREP GL WILL BE 5309') 5322' KB (13')
			EOG WI %, NRI %

02-17-2009      **Reported By**      TERRY CSERE

**DailyCosts: Drilling**      \$80,000                      **Completion**      \$0                      **Daily Total**      \$80,000  
**Cum Costs: Drilling**      \$80,000                      **Completion**      \$0                      **Well Total**      \$80,000  
**MD**              0      **TVD**              0      **Progress**      0      **Days**              0      **MW**              0.0      **Visc**              0.0  
**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION STARTED.

02-18-2009      Reported By      TERRY CSERE

**DailyCosts: Drilling**      \$0                      **Completion**      \$0                      **Daily Total**      \$0  
**Cum Costs: Drilling**      \$80,000                      **Completion**      \$0                      **Well Total**      \$80,000  
**MD**              0      **TVD**              0      **Progress**      0      **Days**              0      **MW**              0.0      **Visc**              0.0  
**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 15% COMPLETE.

02-19-2009      Reported By      TERRY CSERE

**DailyCosts: Drilling**      \$0                      **Completion**      \$0                      **Daily Total**      \$0  
**Cum Costs: Drilling**      \$80,000                      **Completion**      \$0                      **Well Total**      \$80,000  
**MD**              0      **TVD**              0      **Progress**      0      **Days**              0      **MW**              0.0      **Visc**              0.0  
**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 20% COMPLETE.

02-20-2009      Reported By      TERRY CSERE

**DailyCosts: Drilling**      \$0                      **Completion**      \$0                      **Daily Total**      \$0  
**Cum Costs: Drilling**      \$80,000                      **Completion**      \$0                      **Well Total**      \$80,000  
**MD**              0      **TVD**              0      **Progress**      0      **Days**              0      **MW**              0.0      **Visc**              0.0  
**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	ROCKED OUT. DRILLING ROCK.

02-23-2009      Reported By      TERRY CSERE

**DailyCosts: Drilling**      \$0                      **Completion**      \$0                      **Daily Total**      \$0  
**Cum Costs: Drilling**      \$80,000                      **Completion**      \$0                      **Well Total**      \$80,000  
**MD**              0      **TVD**              0      **Progress**      0      **Days**              0      **MW**              0.0      **Visc**              0.0  
**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FINAL BLADE & START CLOSED LOOP SYSTEM.

02-24-2009      Reported By      TERRY CSERE



TOP JOB #4: MIXED AND PUMPED 150 SX (31.00 BBLS) OF PREMIUM CEMENT 2% CACL, CEMENT 15.8 PPG W/ YIELD OF 1.15 CFS, HOLE FILLED AND STOOD FULL. RDMO HALLIBURTON.

PREPARED LOCATION FOR ROTARY RIG: REPORT WILL DROP UNTIL FUTURE ACTIVITY.

CRAIGS RIG TOOK 2 SURVEYS WHILE DRILLING, 1180" @ 1.5 DEGREES AND 2200 @ 2 DEGREES

DAVID FOREMAN NOTIFIED DAVE HACKFORD W/UDOGM OF THE SURFACE CASING & CEMENT JOB ON 03/24/2009 @ 18:30 HRS.

**04-10-2009**      **Reported By**                      MATT WILLIAMS

**DailyCosts: Drilling**                      \$84,273                      **Completion**                      \$0                      **Daily Total**                      \$84,273

**Cum Costs: Drilling**                      \$440,535                      **Completion**                      \$0                      **Well Total**                      \$440,535

**MD**                      2,855      **TVD**                      2,855      **Progress**                      641      **Days**                      1      **MW**                      0.0      **Visc**                      0.0

**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

**Activity at Report Time:** DRILLING @ 2855'

Start	End	Hrs	Activity Description
08:30	11:00	2.5	MOVE & RIG UP ON NEW LOCATION NBU 642-13E, .5 MILES. SET BOP TEST DTO HEAD TO 5000 PSI. W/ FMC LOCK DOWN BOP,CONTINUE RIGGING UP. INSTALL NIGHT CAP ON NBU 640-13E W/ FMC.
11:00	14:00	3.0	NIPPLE UP BOP, FLARE LINES, FUNCTION TEST BOP. RIG ON DAY WORK @ 11:00, 4/09/09.
14:00	17:30	3.5	RIG UP B&C QUICK TEST. TEST BOP, PIPE RAMS, BLIND RAMS, ALL KILL LINE VALVES,CHOKE LINE & MANIFOLD, HCR, UPPER & LOWER KELLY VALVES, SAFETY VALVE, AND DART VALVE, 250 PSI LOW & 5000 PSI HIGH. ANNULAR 250 PSI LOW, 2500 HIGH, SURFACE CSG 1500 PSI GOOD TEST.  WITNESS. JOHN SIDWELL B&C QUICK TEST.
17:30	18:00	0.5	SET WEAR BUSHING.
18:00	18:30	0.5	SERVICE RIG.
18:30	21:00	2.5	P/U & M/U BHA AND TRIP IN THE HOLE. TAG CEMENT @ 2147.
21:00	22:00	1.0	SLIP & CUT 75' OF DRILL LINE.
22:00	22:30	0.5	DRILL CEMENT AND FLOAT EQUIP + 10' OF NEW HOLE TO 2224'.
22:30	23:30	1.0	PERFORM FIT TEST. MWT 9.1, 170 PSI = 10.5 EMW.  TAKE WIRELINE SURVEY @ 2220'= 1.5 DEGREE.
23:30	06:00	6.5	DRLG F/ 2214' TO 2855', ROP 98, WOB 10/18, RPM 45/65, TQ 7500/10,000, MWT 9.1, VIS 29.  MUD LOSS LAST 24 HRS. 0 BBLS. MUD WT. 9.1, VIS.29.  ACCIDENTS NONE REPORTED. FUNCTION TEST CROWN-O-MATIC. SAFETY MEETING: TESTING BOP : TIH CREWS FULL. FUEL ON HAND: 4004 GALS. USED 814 GALS, RECEIVED 3500 GALS. FORMATION TOP: MAHOGANY. LITHOLOGY, SAND/ SHALE.
06:00			SPUD A 7 7/8" HOLE WITH ROTARY TOOL @ 22:30 HRS, 4/09/09.

**04-11-2009**      **Reported By**                      MATT WILLIAMS

**DailyCosts: Drilling**                      \$22,381                      **Completion**                      \$0                      **Daily Total**                      \$22,381

**Cum Costs: Drilling**                      \$462,916                      **Completion**                      \$0                      **Well Total**                      \$462,916

**MD** 5,503 **TVD** 5,503 **Progress** 2,648 **Days** 2 **MW** 10.1 **Visc** 35.0  
**Formation :** **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

**Activity at Report Time:** DRILLING @ 5503'

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRLG F/ 2855' TO 3852' , ROP 133, WOB 15/20, TQ 7500/10,500, MWT 9.4, VIS 34.
13:30	14:00	0.5	SERVICE RIG. CIRC FOR SURVEY.
14:00	14:30	0.5	TAKE WIRELINE SURVEY @ 3800 = 2 DEGREES.
14:30	06:00	15.5	DRLG F/ 3852' TO 5503', ROP 106, WOB 15/21, RPM 40/55, TQ 8000/10,500, MWT 10.1, VIS 35. MUD LOSS LAST 24 HRS. 0 BBLs. MUD WT. 10.1, VIS.35.  ACCIDENTS NONE REPORTED. FUNCTION TEST CROWN-O-MATIC. SAFETY MEETING: CONNECTIONS : PUMPS . CREWS FULL. FUEL ON HAND: 4004 GALS. USED 1662 GALS, RECEIVED 0 GALS. FORMATION TOP: BUCK CANYON. LITHOLOGY, SAND/ SHALE.

**04-12-2009** **Reported By** MATT WILLIAMS

<b>Daily Costs: Drilling</b>	\$47,998	<b>Completion</b>	\$1,496	<b>Daily Total</b>	\$49,494
<b>Cum Costs: Drilling</b>	\$510,914	<b>Completion</b>	\$1,496	<b>Well Total</b>	\$512,410

**MD** 7,110 **TVD** 7,110 **Progress** 1,607 **Days** 3 **MW** 10.3 **Visc** 35.0  
**Formation :** **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

**Activity at Report Time:** LD DP

Start	End	Hrs	Activity Description
06:00	17:00	11.0	DRLG F/ 5503' TO 6343' , ROP 76, WOB 16/22, RPM 40/50, TQ 8000/10500, MWT 10.1, VIS 34.
17:00	17:30	0.5	SERVICE RIG.
17:30	02:00	8.5	DRLG F/ 6343' TO 7110' , ROP 90, WOB 18/22, RPM 40/50, TQ 8000/10,500, MWT 10.3, VIS 35. TD WELL @ 02:00 ON 4/12/09.
02:00	03:00	1.0	PUMP SWEEP, CIRC CLEAN FOR SHORT TRIP.
03:00	04:00	1.0	SHORT TRIP.
04:00	05:30	1.5	PUMP SWEEP, CIRC AND COND, DROP SURVEY, SPOT 250 BBL- 11.5 PPG PILL= 10.8 EMW.
05:30	06:00	0.5	TRIP OUT OF HOLE LAYING DOWN DRILL PIPE AND BHA. MUD LOSS LAST 24 HRS. 0 BBLs. MUD WT. 10.3, VIS.35.  ACCIDENTS NONE REPORTED. FUNCTION TEST CROWN-O-MATIC. SAFETY MEETING: FORKLIFTS, MIXING CHEMICALS . CREWS FULL. FUEL ON HAND: 917 GALS. USED 1425 GALS, RECEIVED 0 GALS. FORMATION TOP: PRICE RIVER. LITHOLOGY, SAND/ SHALE.

**04-13-2009** **Reported By** MATT WILLIAMS

**Daily Costs: Drilling** \$41,045      **Completion** \$172,835      **Daily Total** \$213,880  
**Cum Costs: Drilling** \$551,960      **Completion** \$174,331      **Well Total** \$726,291  
**MD** 7,110    **TVD** 7,110    **Progress** 0    **Days** 4    **MW** 0.0    **Visc** 0.0  
**Formation :**                      **PBTD : 0.0**                      **Perf :**                      **PKR Depth : 0.0**

**Activity at Report Time:** RDRT/WO COMPLETION

Start	End	Hrs	Activity Description
06:00	11:30	5.5	TRIP OUT OF HOLE LAYING DOWN DP AND BHA.
11:30	12:00	0.5	PULL WEAR BUSHING.
12:00	13:00	1.0	HOLD PJSM. R/U CALIBER CSG EQUIPMENT.
13:00	19:00	6.0	RUN CASING. RAN 155 JTS.P-110 LTC + 2 MARKER JT. 11.6# P-110 LTC. AS FOLLOWS FLOAT SHOE 1JT.CSG. FLOAT COLLAR 25 JTS.CSG.1 MARKER JT.49 JTS.CSG.1 MARKER JT.80 JTS CSG. FLOAT SHOE BOTTOM @ 7110'. FLOAT COLLAR TOP @ 7062' MARKER JT. @ 5908'.& @ 3661'. CENTRALIZERS, 5 FT. ABOVE SHOE, TOP OF JT.#2 & EVERY 3 RD. JT. TOTAL 15 .TAG @ 7110'. LAY DOWN TAG JT. PICK UP HANGER SPACE OUT CIRC. CSG W/ RIG PUMP. RIG DOWN CALIBER CASING. LAND CSG. W/ FULL STRING WT. 75.000, WITNESS BY FMC REP.
19:00	20:00	1.0	CIRC. BOTTOMS UP SAFETY MEETING W/ HALLIBURTON AND RIG UP TO PUMP CEMENT.
20:00	22:00	2.0	R/U AND TEST LINES 5000 PSI. DROP BOTTOM PLUG PUMP 20 BBLs WATER SPACER & 20 BBLs. MUD FLUSH AHEAD. AND CEMENT 7110' 4 1/2 P-110 11.6# LTC CSG. LEAD 330 SKS. HIGHBOND 75 WITH 4% BENTINITE, 0.3% VERSASET.15# TUFF FIBER IN FIRST 50 BBL MIXED @ 11.5 PPB. YIELD 2.53 FT3/SK H20 12.03 GAL/SK. TAIL 910 SKS, EXTENDACEM WITH 0.125# POLYFLAKE/SK.@ 13.5 PPG. YIELD 1.47 FT3/SK H20 6.88 GAL/SK. SHUTDOWN WASH OUT PUMPS & LINES DROP TOP PLUG & DISP TO FLOAT COLLAR W/ FRESH WATER. 109 BBLs. AVG. DISP. RATE 8 BPM, RETURNS THROUGH OUT JOB. DROP PLUG @ 21:17, BUMPED PLUG @ 21:42 TO 2960 PSI.1250 PSI. OVER LIFT PRESS. HOLD PRESS.F/1 MINS.1 BBL. BACK, FLOAT HELD.@ 21:45 CEMENT IN PLACE. RIG DOWN HALLIBURTON LINES.
22:00	23:00	1.0	WAIT ON CEMENT & CLEAN PITS.
23:00	00:00	1.0	REMOVE CEMENT HEAD & LANDING JT.M/U & LAND PACKOFF TEST 5000 PSI. LOOSEN DTO LOCK DOWN BOLTS W/ FMC.
00:00	04:00	4.0	NIPPLE DOWN AND CLEAN PITS.
04:00	06:00	2.0	RIG DOWN AND PREPARE FOR RIG MOVE.

ACCIDENTS NONE REPORTED.  
 SAFETY MEETING: RUN CSG, CEMENT .  
 CREWS FULL.  
 FUEL ON HAND: 400 GALS. 517 USED.  
 CSG POINT COST: \$395,750.  
 END WELL COST : \$540,211.

06:00                      RIG RELEASED @ 04:00, 4/13/09.  
                                  CASING POINT COST \$553,440

**04-22-2009      Reported By      SEARLE**

**Daily Costs: Drilling** \$0      **Completion** \$37,300      **Daily Total** \$37,300  
**Cum Costs: Drilling** \$551,960      **Completion** \$211,631      **Well Total** \$763,591  
**MD** 7,110    **TVD** 7,110    **Progress** 0    **Days** 5    **MW** 0.0    **Visc** 0.0  
**Formation :**                      **PBTD : 7062.0**                      **Perf :**                      **PKR Depth : 0.0**

**Activity at Report Time:** PREP FOR FRACS

Start	End	Hrs	Activity Description
06:00	06:00	24.0	MIRU SCHLUMBERGER. LOG WITH RST/CBL/CCL/VDL/GR FROM PBTD TO 920'. EST CEMENT TOP @ 1100'. RD SCHLUMBERGER.

06-12-2009 Reported By MCCURDY

DailyCosts: Drilling \$0 Completion \$1,823 Daily Total \$1,823  
 Cum Costs: Drilling \$551,960 Completion \$213,454 Well Total \$765,414

MD 7,110 TVD 7,110 Progress 0 Days 6 MW 0.0 Visc 0.0

Formation : PBTD : 7062.0 Perf : PKR Depth : 0.0

Activity at Report Time: WO COMPLETION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	NU 10M FRAC TREE. PRESSURE TESTED FRAC TREE & CASING TO 6500 PSIG. WO COMPLETION.

06-16-2009 Reported By MCCURDY

DailyCosts: Drilling \$0 Completion \$643 Daily Total \$643  
 Cum Costs: Drilling \$551,960 Completion \$214,097 Well Total \$766,057

MD 7,110 TVD 7,110 Progress 0 Days 7 MW 0.0 Visc 0.0

Formation : MESAVERDE PBTD : 7062.0 Perf : 6804'-6996' PKR Depth : 0.0

Activity at Report Time: FRAC

Start	End	Hrs	Activity Description
06:00	06:00	24.0	RU CUTTERS WIRELINE & PERFORATE UPR FROM 6804'-05', 6811'-12', 6820'-21', 6853'-54', 6861'-62', 6916'-17', 6935'-36', 6950'-52', 6964'-65', 6985'-86', 6995'-96' @ 3 SPF @ 120 PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/42 GAL K-87 MICROBIOCIDE, 165 GAL GYPTRON T-106, 8409 GAL 16# LINEAR W/11000# 20/40 SAND @ 1-1.5 PPG, 38099 GAL 16# DELTA 140 W/128700# 20/40 SAND @ 2-4 PPG. MTP 5378 PSIG. MTR 52.4 BPM. ATP 3690 PSIG. ATR 50.2 BPM. ISIP 2143 PSIG. RD HALLIBURTON. SDFN.

06-17-2009 Reported By MCCURDY

DailyCosts: Drilling \$0 Completion \$168,365 Daily Total \$168,365  
 Cum Costs: Drilling \$551,960 Completion \$382,462 Well Total \$934,422

MD 7,110 TVD 7,110 Progress 0 Days 8 MW 0.0 Visc 0.0

Formation : MESAVERDE PBTD : 7062.0 Perf : 5092'-6996' PKR Depth : 0.0

Activity at Report Time: PREP TO MIRUSU

Start	End	Hrs	Activity Description
06:00	06:00	24.0	SICP 1881 PSIG. RUWL. SET 6K CFP AT 6775'. PERFORATE UPR FROM 6493'-94', 6501'-02', 6562'-63', 6569'-70', 6592'-93', 6635'-36', 6641'-42', 6649'-50', 6700'-01', 6711'-12', 6739'-40', 6755'-56' @ 3 SPF @ 120 PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/42 GAL K-87 MICROBIOCIDE, 165 GAL GYPTRON T-106, 8412 GAL 16# LINEAR W/11000# 20/40 SAND @ 1-1.5 PPG, 27354 GAL 16# DELTA 140 W/91300# 20/40 SAND @ 2-4 PPG. MTP 5653 PSIG. MTR 50.9 BPM. ATP 4210 PSIG. ATR 47.6 BPM. ISIP 2333 PSIG. RD HALLIBURTON.

RUWL. SET 6K CFP AT 6450'. PERFORATE NH / UPR FROM 6217'-18', 6230'-31', 6246'-47', 6293'-94', 6323'-25', 6339'-40', 6358'-59', 6377'-78', 6412'-13', 6417'-18', 6426'-27' @ 3 SPF @ 120 PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/42 GAL K-87 MICROBIOCIDE, 165 GAL GYPTRON T-106, 8394 GAL 16# LINEAR W/11100# 20/40 SAND @ 1-1.5 PPG, 43409 GAL 16# DELTA 140 W/145000# 20/40 SAND @ 2-4 PPG. MTP 4766 PSIG. MTR 51.3 BPM. ATP 3674 PSIG. ATR 47.4 BPM. ISIP 2174 PSIG. RD HALLIBURTON.

RUWL. SET 6K CFP AT 6185'. PERFORATE NORTH HORN FROM 5955'-56', 5980'-81', 5990'-91', 6008'-09', 6055'-57', 6063'-64', 6111'-12', 6117'-18', 6152'-53', 6162'-63', 6166'-67' @ 3 SPF @ 120 PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/42 GAL K-87 MICROBIOCIDE, 165 GAL GYPTRON T-106, 8460 GAL 16# LINEAR W/11100# 20/40 SAND @ 1-1.5 PPG, 35017 GAL 16# DELTA 140 W/117600# 20/40 SAND @ 2-4 PPG. MTP 4766 PSIG. MTR 51.3 BPM. ATP 3732 PSIG. ATR 50 BPM. ISIP 2099 PSIG. RD HALLIBURTON.

RUWL. SET 6K CFP AT 5740'. PERFORATE Ca/Ba FROM 5092'-93', 5110'-11', 5149'-50', 5161'-62', 5228'-29', 5282'-83', 5401'-02', 5533'-34', 5542'-43', 5577'-78', 5648'-49', 5698'-99' @ 3 SPF @ 120 PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/42 GAL K-87 MICROBIOCIDE, 26265 GAL 16# LINEAR W/38800# 20/40 SAND @ 1-2 PPG, 7482 GAL 16# DELTA 140 W/19400# 20/40 SAND @ 3 PPG. MTP 5460 PSIG. MTR 50.2 BPM. ATP 4484 PSIG. ATR 46.6 BPM. ISIP 1528 PSIG. RD HALLIBURTON.

RUWL. SET 6K CBP AT 5012'. RDWL.

<b>06-25-2009</b>		<b>Reported By</b>		HAL IVIE							
<b>Daily Costs: Drilling</b>		\$0	<b>Completion</b>		\$8,565	<b>Daily Total</b>		\$8,565			
<b>Cum Costs: Drilling</b>		\$551,960	<b>Completion</b>		\$391,027	<b>Well Total</b>		\$942,987			
<b>MD</b>	7,110	<b>TVD</b>	7,110	<b>Progress</b>	0	<b>Days</b>	9	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation : MESAVERDE</b>		<b>PBTD : 7062.0</b>		<b>Perf : 5092'-6996'</b>		<b>PKR Depth : 0.0</b>					
<b>Activity at Report Time:</b> CLEAN OUT AFTER FRAC											
<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>								
06:00	16:00	10.0	MIRUSU. ND FRAC TREE. NU BOP. RIH W/ BIT & PUMP OFF SUB TO 5012'. RU TO DRILL OUT PLUGS. SDFN.								

<b>06-26-2009</b>		<b>Reported By</b>		HAL IVIE							
<b>Daily Costs: Drilling</b>		\$0	<b>Completion</b>		\$42,217	<b>Daily Total</b>		\$42,217			
<b>Cum Costs: Drilling</b>		\$551,960	<b>Completion</b>		\$433,244	<b>Well Total</b>		\$985,204			
<b>MD</b>	7,110	<b>TVD</b>	7,110	<b>Progress</b>	0	<b>Days</b>	10	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation : MESAVERDE</b>		<b>PBTD : 7062.0</b>		<b>Perf : 5092'-6996'</b>		<b>PKR Depth : 0.0</b>					
<b>Activity at Report Time:</b> RDMO, FLOW WELL BACK.											
<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>								
06:00	06:00	24.0	SICP 0 PSIG. CLEANED OUT & DRILLED OUT PLUGS @ 5012', 5740', 6185', 6450', 6775'. RIH. CLEANED OUT TO PBTD @ 7062'. LANDED TBG AT 5092.72' KB. ND BOPE. NU TREE. PUMPED OFF BIT & SUB. RDMOSU.								

FLOWED 17 HRS. 32/64 CHOKE. FTP 1000 PSIG, CP 1950 PSIG. 60 BFPH. RECOVERED 1053 BBLS, 4609 BLWTR.

TUBING DETAIL LENGTH

PUMP OFF SUB 1.00'  
 1 JT 2-3/8 4.7# N-80 TBG YB 32.63'  
 XN NIPPLE 1.10'  
 155 JTS 2-3/8 4.7# N-80 TBG YB 5044.99'  
 BELOW KB 13.00'  
 LANDED @ 5092.72' KB

<b>06-27-2009</b>		<b>Reported By</b>		HAL IVIE							
<b>Daily Costs: Drilling</b>		\$0	<b>Completion</b>		\$4,229	<b>Daily Total</b>		\$4,229			
<b>Cum Costs: Drilling</b>		\$551,960	<b>Completion</b>		\$437,473	<b>Well Total</b>		\$989,433			
<b>MD</b>	7,110	<b>TVD</b>	7,110	<b>Progress</b>	0	<b>Days</b>	11	<b>MW</b>	0.0	<b>Visc</b>	0.0
<b>Formation : MESAVERDE</b>		<b>PBTD : 7062.0</b>		<b>Perf : 5092'-6996'</b>		<b>PKR Depth : 0.0</b>					
<b>Activity at Report Time:</b> FLOW WELL BACK THRU BRECO UNIT.											
<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>								

06:00 06:00 24.0 INITIAL PRODUCTION. OPENING PRESSURE: TP 1100 PSIG & CP 1950 PSIG. TURNED WELL OVER TO KERR-MAGEE SALES AT 12:30 PM, 6/26/09. FLOWED 1200 MCFD RATE ON 24/64" POS CHOKE. STATIC 86. KERR-MAGEE METER #985812. THROUGH BRECO UNIT.

FLOWED 23 HRS. 24/64 CHOKE. FTP- 1100 PSIG, CP- 1900 PSIG. 43 BFPH. RECOVERED 1034 BBLS, 3575 BLWTR. 1216 MCF/D. SHUT DN F/ 1 HR TO RU BRECO UNIT.

---

**06-28-2009**      **Reported By**      HAL IVIE

<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$3,429	<b>Daily Total</b>	\$3,429
<b>Cum Costs: Drilling</b>	\$551,960	<b>Completion</b>	\$440,902	<b>Well Total</b>	\$992,862

MD      7,110    **TVD**      7,110    **Progress**      0    **Days**      12    **MW**      0.0    **Visc**      0.0

**Formation : MESAVERDE**      **PBTD : 7062.0**      **Perf : 5092'-6996'**      **PKR Depth : 0.0**

**Activity at Report Time:** FLOW BACK THRU BRECO UNIT

<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>
06:00	06:00	24.0	FLOWED 24 HRS. 24/64 CHOKE. FTP- 1150 PSIG, CP- 1800 PSIG. 34 BFPH. RECOVERED 883 BBLS, 2692 BLWTR. 1381 MCF/D.

---

**06-29-2009**      **Reported By**      HAL IVIE

<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$3,429	<b>Daily Total</b>	\$3,429
<b>Cum Costs: Drilling</b>	\$551,960	<b>Completion</b>	\$444,331	<b>Well Total</b>	\$996,291

MD      7,110    **TVD**      7,110    **Progress**      0    **Days**      13    **MW**      0.0    **Visc**      0.0

**Formation : MESAVERDE**      **PBTD : 7062.0**      **Perf : 5092'-6996'**      **PKR Depth : 0.0**

**Activity at Report Time:** FLOW TEST TO SALES

<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>
06:00	06:00	24.0	FLOWED THROUGH TEST UNIT TO SALES 24 HRS. 24/64" CHOKE. FTP 1150 PSIG. CP 1750 PSIG. 32 BFPH. RECOVERED 765 BLW. 1927 BLWTR. 1556 MCFD RATE.

FLOWED 1380 MCF, 20 BC & 816 BW IN 24 HRS ON 24/64" CHOKE, TP 1200 PSIG, CP 1700 PSIG.

---

**06-30-2009**      **Reported By**      HAL IVIE

<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$3,429	<b>Daily Total</b>	\$3,429
<b>Cum Costs: Drilling</b>	\$551,960	<b>Completion</b>	\$447,760	<b>Well Total</b>	\$999,720

MD      7,110    **TVD**      7,110    **Progress**      0    **Days**      14    **MW**      0.0    **Visc**      0.0

**Formation : MESAVERDE**      **PBTD : 7062.0**      **Perf : 5092'-6996'**      **PKR Depth : 0.0**

**Activity at Report Time:** FLOW TEST TO SALES

<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>
06:00	06:00	24.0	FLOWED 24 HRS. 24/64 CHOKE. FTP 1150 PSIG. CP 1750 PSIG. 26 BFPH. RECOVERED 672 BW. 1255 BLWTR. 1661 MCFD RATE.

FLOWED 1614 MCF, 30 BC & 765 BW IN 24 HRS ON 24/64" CHOKE, TP 1150 PSIG, CP 1750 PSIG.

---

**07-01-2009**      **Reported By**      HAL IVIE

<b>Daily Costs: Drilling</b>	\$0	<b>Completion</b>	\$3,629	<b>Daily Total</b>	\$3,629
<b>Cum Costs: Drilling</b>	\$551,960	<b>Completion</b>	\$451,389	<b>Well Total</b>	\$1,003,349

MD      7,110    **TVD**      7,110    **Progress**      0    **Days**      15    **MW**      0.0    **Visc**      0.0

**Formation : MESAVERDE**      **PBTD : 7062.0**      **Perf : 5092'-6996'**      **PKR Depth : 0.0**

**Activity at Report Time:** FLOW TEST TO SALES

<b>Start</b>	<b>End</b>	<b>Hrs</b>	<b>Activity Description</b>
06:00	06:00	24.0	FLOWED THROUGH TEST UNIT TO SALES 24 HRS. 24/64 CHOKE. FTP 1150 PSIG. CP 1700 PSIG. 26 BFPH. RECOVERED 636 BLW. 619 BLWTR. 1932 MCFD RATE.  FLOWED 1728 MCF, 40 BC & 765 BW IN 24 HRS ON 24/64" CHOKE, TP 1175 PSIG, CP 1700 PSIG.

---

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-08512-ST
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: Natural Buttes
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1949' FNL & 858' FEL 39.950833 Lat 109.381944 Lon		8. WELL NAME and NUMBER: Natural Buttes Unit 642-13E
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 13 10S 22E S		9. API NUMBER: 43-047-50013
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Site facility diagram</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached please find a site facility diagram for the referenced well.

NAME (PLEASE PRINT) <u>Mary A. Maestas</u>	TITLE <u>Regulatory Assistant</u>
SIGNATURE <u>Mary A. Maestas</u>	DATE <u>8/4/2009</u>

(This space for State use only)

RECEIVED

AUG 06 2009

DIV. OF OIL, GAS & MINING

# Geogresources Site Facility Diagram



Well Name: Natural Buttes Unit 642-13E  
 1/4 1/4: SE/NE Sec: 13 T:10S R:22E  
 County:UINTAH State:UTAH  
 Lease: U-08512-ST  
 UNIT\PA#: 891008900A

Site facility diagrams & site security plans are located at the Vernal office in Vernal, Utah. The office is located at 1060 East Hwy 40 and normal business hours are 7:00 a.m. to 4:30 p.m. Mon -Thurs and 7:00 a.m. to 1:00 p.m. fridays.

Valve	Production Phase	Sales Phase	Water Drain
PV	O	SC	SC
LV	SC	O	SC
WD	SC	SC	O


DATED 8/3/2009

## Abbreviations

AM= Allocation Meter  
 AR = Access Road  
 CHT = Chemical Tank  
 COMP = Compressor  
 CON = Condensor  
 CT = Condensate Tank  
 DL = Dump Line  
 EP = Electrical Panel  
 ET = Emergency Tank  
 FW = Firewall  
 LACT = LACT Unit  
 LH = Line Heater  
 LV = Load Valve  
 MAN = Manifold  
 MB = Methanol Bath  
 O = Open  
 PL = Production Line  
 PP = Power Pole  
 PT = Propane Tank  
 PU = Pumping Unit  
 PV = Production Valve  
 PW = Produced Water  
 RL = Recycle Line  
 RP = Recycle Pump  
 RV = Recycle Valve  
 SC = Sealed Closed  
 SGS = Sales Gas Scrubber  
 SL = Sales Line  
 SM = Sales Meter  
 SO = Sealed Open  
 SP = Separator  
 SV = Sales Valve  
 T = Treater  
 TP = Trace Pump  
 WD = Water Drain  
 WDP = Water Disposal Pump  
 WFP = Water Flood Pump  
 WH = Wellhead

———— = Buried Line  
 ———— = Unburied Line

▽ = Meter Display  
 □ = Meter Tube  
 ○ = Production Valve  
 X = Valve



Division of Oil, Gas and Mining  
**OPERATOR CHANGE WORKSHEET**

**ROUTING**

1. DJJ
2. CDW

**X Change of Operator (Well Sold)**  
 Operator Name Change

Designation of Agent/Operator  
 Merger

The operator of the well(s) listed below has changed, effective: **6/1/2009**

<b>FROM:</b> (Old Operator): N9550-EOG Resources 1060 E Hwy 40 Vernal, UT 84078 Phone: 1-(435) 781-9111	<b>TO:</b> ( New Operator): N2995-Kerr-McGee Oil & Gas Onshore., LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024
---------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------

WELL NAME(S)	CA No.			Unit:		NATURAL BUTTES		
	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 642-13E	13	100S	220E	4304750013	WCR-2900	State	GW	P
NBU 639-13E	13	100S	220E	4304750019	WCR2900	State	GW	P
NBU 641-13E	13	100S	220E	4304750058	WCR 2900	State	GW	P
NBU 660-12E	12	100S	200E	4304739858	OK 2900	Federal	GW	P <i>9/8/09 file</i>

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: Completion of well
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: Completion of well
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- (R649-9-2)Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM n/a BIA n/a
- Federal and Indian Units:**  
 The BLM or BIA has approved the successor of unit operator for wells listed on: n/a
- Federal and Indian Communization Agreements ("CA"):**  
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: n/a

**DATA ENTRY:**

- Changes entered in the **Oil and Gas Database** on: 7/29/2009
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 7/29/2009
- Bond information entered in RBDMS on: 7/29/2009
- Fee/State wells attached to bond in RBDMS on: 7/9/2009
- Injection Projects to new operator in RBDMS on: n/a

**BOND VERIFICATION:**

- Federal well(s) covered by Bond Number: CO1203
- Indian well(s) covered by Bond Number: n/a
- (R649-3-1) The **NEW** operator of any state or fee well(s) listed covered by Bond Number 22013542
- The **FORMER** operator has requested a release of liability from their bond on: n/a

**COMMENTS:**

Well to transfer upon completion to Unit Operator (See 9/23/2003 letter from EOG & agreement 9/17/03 from Westport )

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

5. Lease Serial No.  
Multiple Leases

6. If Indian, Allottee or Tribe Name

**SUBMIT IN TRIPLICATE** – Other instructions on page 2.

1. Type of Well  
 Oil Well     Gas Well     Other

2. Name of Operator  
EOG Resources, Inc

3a. Address  
1060 EAST HIGHWAY 40, VERNAL, UT 84078

3b. Phone No. (include area code)  
435-781-9145

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
See Attached

7. If Unit of CA/Agreement, Name and/or No.  
Natural Buttes

8. Well Name and No.  
Multiple Wells

9. API Well No.  
See Attached

10. Field and Pool or Exploratory Area  
Natural Buttes

11. Country or Parish, State  
Utah, Utah

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Change of Operator</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

EOG Resources, Inc. has assigned all of its right, title and interest in the wells described in the attached list ("the Subject Wells") to Kerr-McGee Oil & Gas Onshore LP and will relinquish and transfer operatorship of all of the Subject Wells to Kerr-McGee Oil & Gas Onshore LP on January 1, 2010.

As of January 1, 2010, Kerr-McGee Oil & Gas Onshore LP will be considered to be the operator of each of the Subject Wells and will be responsible under the terms and conditions of the applicable lease for the operations conducted upon the leased lands. Bond coverage is provided under Kerr-McGee Oil & Gas Onshore LP's Nationwide BLM Bond No. WYB-000291.

Kerr-McGee Oil & Gas Onshore LP  
1099 18th Street, Suite 1800  
Denver, CO 80202-1918

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
For Record Only *ER 1/31/2010*

By: Michael A. Nixon Date: 12/17/2009  
Michael A. Nixon  
Agent and Attorney-in-Fact

14. I hereby certify that the foregoing is true and correct.

Name (Printed/Typed)  
J. Michael Schween

Title Agent and Attorney-in-Fact

Signature [Signature] Date 12/17/2009

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

RECEIVED

Approved by \_\_\_\_\_ Title \_\_\_\_\_ Date **DEC 24 2009**

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office **DIV. OF OIL, GAS & MINING**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Lease #	API #	Well Name	Footages	Legal Description
UTUO2270A	4304730261	NBU 1-07B	1975' FNL 1850' FWL	T10S-R21E-07-SESW
UTUO144868	4304730262	NBU 2-15B	1630' FSL 2125' FEL	T09S-R20E-15-NWSE
ML22651	4304730267	NBU 3-02B	1819' FNL 716' FWL	T10S-R22E-02-SWNW
UTUO10954A	4304730273	NBU 4-35B	2037' FNL 2539' FWL	T09S-R22E-35-SESW
ML22650	4304730272	NBU 5-36B	1023' FNL 958' FWL	T09S-R22E-36-NWNW
UTUO1791	4304730278	NBU 7-09B	330' FSL 1600' FWL	T10S-R21E-09-SESW
UTUO1207 ST	4304730274	NBU 10-29B	1100' FSL 1540' FEL	T09S-R22E-29-SWSE
UTUO1791	4304730294	NBU 13-08B	1600' FSL 1300' FEL	T10S-R21E-08-NESE
UTUO581	4304730296	NBU 15-29B	821' FNL 687' FWL	T09S-R21E-29-NWNW
UTUO1791	4304730316	NBU 16-06B	330' FSL 900' FEL	T10S-R21E-06-SESE
UTUO2270A	4304730317	NBU 17-18B	1014' FSL 2067' FEL	T10S-R21E-18-SWSE
UTUO144869	4304730328	NBU 19-21B	2015' FNL 646' FEL	T09S-R20E-21-SENE
UTUO575	4304730363	NBU 25-20B	1905' FNL 627' FWL	T09S-R21E-20-SWNW
UTU4485	4304730364	NBU 26-13B	600' FSL 661' FEL	T10S-R20E-13-SESE
UTUO1393B	4304730367	NBU 28-04B	529' FNL 2145' FWL	T10S-R21E-04-NENW
UTUO1393B	4304730368	NBU 29-05B	398' FSL 888' FWL	T10S-R21E-05-SESE
UTUO575	4304730380	NBU 30-18B	1895' FSL 685' FEL	T09S-R21E-18-NESE
ML01197A	4304730385	NBU 31-12B	565' FNL 756' FWL	T10S-R22E-12-NWNW
UTU461	4304730396	NBU 33-17B	683' FSL 739' FWL	T09S-R22E-17-SWSW
UTUO575	4304730404	NBU 34-17B	210' FNL 710' FEL	T09S-R21E-17-NENE
UTUO149767	4304730397	NBU 35-08B	1830' FNL 660' FWL	T09S-R21E-8-SWNW
UTUO144878B	4304730470	NBU 49-12B	551' FSL 1901' FEL	T09S-R20E-12-SWSE
UTUO140225	4304730473	NBU 52-01B	659' FSL 658' FEL	T09S-R21E-01-SESE
UTUO141315	4304730474	NBU 53-03B	495' FSL 601' FWL	T09S-R21E-03-SWSW
ML21510	4304730475	NBU 54-02B	660' FSL 660' FWL	T09S-R21E-02-SWSW
UTUO1193	4304730464	NBU 57-12B	676' FSL 1976' FEL	T09S-R21E-12-SWSE
UTUO1198B	4304730463	NBU 58-23B	1634' FNL 2366' FEL	T10S-R22E-23-SWNE
UTUO37167	4304730477	NBU 62-35B	760' FNL 2252' FEL	T10S-R22E-35-NWNE
UTU10186	4304730466	NBU 63-12B	1364' FNL 1358' FEL	T10S-R20E-12-SWNE
UTUO37167	4304730577	NBU 70-34B	1859' FSL 2249' FWL	T10S-R22E-34-NESW
UTU4476	4304730578	NBU 71-26B	1877' FNL 528' FEL	T10S-R20E-26-SENE
UTUO141315	4304731150	NBU 202-03	898' FSL 1580' FEL	T09S-R21E-03-SWSE
UTUO1791	4304731238	NBU 205-08	1432' FSL 1267' FWL	T10S-R21E-08-NWSW
UTUO1791	4304731165	NBU 206-09	1789' FNL 1546' FWL	T10S-R21E-09-SESW
UTUO1393B	4304731177	NBU 207-04	1366' FSL 1445' FWL	T10S-R21E-04-NESW
UTUO149076	4304731153	NBU 210-24	1000' FSL 1000' FWL	T09S-R21E-24-SWSW
UTUO284	4304731156	NBU 211-20	916' FSL 822' FEL	T09S-R22E-20-SESE
UTUO284	4304731267	NBU 212-19	289' FSL 798' FWL	T09S-R22E-19-SWSW
UTU22650	4304731268	NBU 213-36J	597' FNL 659' FEL	T09S-R22E-36-NENE
ML22651	4304731282	NBU 217-02	2045' FSL 766' FWL	T10S-R22E-02-NWSW
UTUO2270A	4304731310	NBU 218-17	2600' FNL 1500' FWL	T10S-R21E-17-SESW
UTUO149076	4304731308	NBU 219-24	1300' FNL 500' FWL	T09S-R21E-24-NWNW
UTUO149076	4304732131	NBU 301-24E	700' FSL 2450' FEL	T09S-R21E-24-SWSE
UTUO1791	4304732010	NBU 302-09E	1899' FSL 912' FWL	T10S-R21E-09-NWSW
UTUO575	4304732130	NBU 304-18E	782' FSL 1783' FEL	T09S-R21E-18-SWSE
UTUO149767	4304732135	NBU 305-07E	670' FNL 1950' FWL	T09S-R21E-07-NENW
UTUO581	4304732282	NBU 306-18E	1604' FSL 2797' FWL	T09S-R21E-18-NESW
UTUO1791	4304732014	NBU 307-06E	1979' FSL 2000' FEL	T10S-R21E-06-NWSE
UTUO284	4304732202	NBU 308-20E	1503' FSL 954' FWL	T09S-R22E-20-NWSW
UTUO575	4304732283	NBU 309-20E	930' FNL 667' FEL	T09S-R21E-20-NENE
UTUO149075	4304732203	NBU 311-23E	1101' FSL 1978' FEL	T09S-R21E-23-SWSE
UTUO581	4304732378	NBU 313-29E	1000' FNL 660' FEL	T09S-R21E-29-NENE
UTUO141315	4304732271	NBU 314-03E	1045' FSL 2584' FWL	T09S-R21E-03-SESW
UTUO575	4304732381	NBU 316-17E	1935' FNL 1067' FWL	T09S-R21E-17-SWNW
UTUO144868B	4304732362	NBU 317-12E	867' FNL 701' FEL	T09S-R20E-12-NENE
UTUO2270A	4304737511	NBU 319-17E	807' FNL 990' FWL	T10S-R21E-17-NWNW
UTUO1188	4304732379	NBU 321-10E	940' FSL 2508' FWL	T09S-R21E-10-SESW
UTUO575B	4304732376	NBU 325-08E	832' FSL 669' FWL	T09S-R21E-08-SWSW
UTUO1393B	4304733697	NBU 326-04E	1906' FNL 695' FWL	T10S-R21E-04-SWNW
UTUO1393B	4304739303	NBU 327-05E	1117' FNL 942' FEL	T10S-R21E-05-NENE (LOT 1)
UTU4485	4304732386	NBU 328-13E	1766' FSL 1944' FWL	T10S-R20E-13-NESW
UTUO1207 ST	4304732229	NBU 329-29E	2490' FNL 949' FEL	T09S-R22E-29-SENE

RECEIVED

DEC 24 2009

DIV. OF OIL, GAS & MINING

Lease #	API #	Well Name	Footages	Legal Description
UTUO10954A	4304732147	NBU 331-35E	1531' FNL 1153' FEL	T09S-R22E-35-SENE
UTUO1791	4304732148	NBU 332-08E	955' FSL 2508' FEL	T10S-R21E-08-SWSE
ML21510	4304732518	NBU 333-02E	1951' FSL 2245' FWL	T09S-R21E-02-NESW
UTUO149075	4304732265	NBU 335-23E	1419' FNL 828' FEL	T09S-R21E-23-SENE
UTUO149076	4304732264	NBU 336-24E	2024' FNL 1958' FWL	T09S-R21E-24-SENW
UTUO284	4304732281	NBU 339-19E	1890' FSL 674' FWL	T09S-R22E-19-NWSW
UTUO284B	4304732327	NBU 340-20E	1326' FSL 2569' FEL	T09S-R22E-20-NWSE
UTUO1207 ST	4304733055	NBU 341-29E	307' FSL 898' FEL	T09S-R22E-29-SESE
UTUO10954A	4304732212	NBU 342-35E	918' FNL 2563' FEL	T09S-R22E-35-NWNE
UTUO1393B	4304739338	NBU 346-05E	2233' FSL 676' FEL	T10S-R21E-05-NESE
UTUO575B	4304732326	NBU 349-07E	1641' FNL 1036' FWL	T09S-R21E-07-SWNW
UTUO1188	4304732519	NBU 352-10E	1806' FSL 842' FWL	T09S-R21E-10-NWSW
UTUO581	4304732383	NBU 356-29E	1600' FNL 1980' FEL	T09S-R21E-29-SWNE
UTUO2270A	4304732388	NBU 358-01E	736' FSL 1941' FEL	T10S-R20E-01-SWSE
UTU4485	4304750032	NBU 359-13E	661' FSL 2149' FEL	T10S-R20E-13-SWSE
UTU4485	4304732387	NBU 360-13E	1998' FSL 775' FWL	T10S-R20E-13-NWSW
ML21510	4304733782	NBU 379-02E	1967' FSL 898' FWL	T09S-R21E-02-NWSW
UTUO575	4304733064	NBU 382-18E	2030' FSL 2172' FEL	T09S-R21E-18-NWSE
UTUO149075	4304735889	NBU 384-23E	491' FSL 929' FEL	T09S-R21E-23-SESE
UTUO149076	4304733056	NBU 386-24E	450' FSL 1850' FWL	T09S-R21E-24-SESW
UTUO284	4304733057	NBU 388-19E	382' FSL 1847' FWL	T09S-R22E-19-SESW
UTUO1207 ST	4304733049	NBU 389-29E	2226' FSL 2166' FEL	T09S-R22E-29-NWSE
UTUO1393B	4304732835	NBU 390-04E	2577' FSL 1951' FWL	T10S-R21E-04-NESW
UTUO1393B	4304732988	NBU 391-05E	1215' FSL 2090' FEL	T10S-R21E-05-SWSE
UTUO1791	4304733783	NBU 392-06E	1926' FSL 611' FEL	T10S-R21E-06-NESE
UTU4485	4304733071	NBU 393-13E	1850' FSL 2141' FEL	T10S-R20E-13-NWSE
UTU4485	4304733072	NBU 394-13E	725' FSL 2027' FWL	T10S-R20E-13-SESW
UTUO1188	4304732544	NBU 400-11E	1983' FSL 1321' FWL	T09S-R21E-11-NESW
UTUO581	4304734216	NBU 421-29E	1985 FNL, 972 FEL	T09S-R21E-29-SENE
UTUO581	4304733698	NBU 422-29E	1980' FNL 785' FWL	T09S-R21E-29-SWNW
UTUO581	4304734206	NBU 423-30E	1980' FSL 660' FEL	T09S-R21E-30-NESE
ML3142	4304733699	NBU 424-32E	744' FNL 773' FEL	T09S-R21E-32-NENE
UTUO2270A	4304740049	NBU 428-07E	660' FSL 855' FWL	T10S-R21E-07-SWSW (Lot 4)
UTUO1791	4304733069	NBU 431-09E	2599' FNL 662' FWL	T10S-R21E-09-SWNW
UTUO2270A	4304738536	NBU 434-17E	1799' FNL 2176' FWL	T10S-R21E-17-SENW
UTUO2270A	4304738376	NBU 435-17E	1837' FNL 571' FWL	T10S-R21E-17-SWNW
UTUO2270A	4304734195	NBU 436-18E	1644' FSL 748' FEL	T10S-R21E-18-NESE
UTUO2270A	4304735499	NBU 437-18E	322' FSL 748' FEL	T10S-R21E-18-SESE
ML22792	4304737534	NBU 438-19E	661' FNL 1941' FEL	T10S-R21E-19-NWNE
ML22792	4304737535	NBU 439-19E	2111' FNL 1980' FWL	T10S-R21E-19-SWNE
UTUO10953	4304736279	NBU 451-01E	1965' FSL 2132' FWL	T10S-R22E-01-NESW
ML22651	4304736053	NBU 456-02E	493' FNL 1080' FWL	T10S-R22E-02-NWNW (Lot 4)
UTUO141315	4304733063	NBU 481-03E	1490' FSL 556' FEL	T09S-R21E-03-NESE
UTUO581	4304733065	NBU 483-19E	1850' FSL 1980' FWL	T09S-R21E-19-NESW
UTUO575	4304733784	NBU 484-20E	350' FNL 823' FWL	T09S-R21E-20-NWNW
UTUO2270A	4304739897	NBU 486-07E	1895 FSL' 1834' FWL	T10S-R21E-07-NESW
UTUO575B	4304733121	NBU 489-07E	763' FSL 733' FWL	T09S-R21E-07-SWSW (Lot 4)
UTUO2270A	4304733123	NBU 497-01E	2091' FSL 894' FEL	T10S-R20E-01-NESE
UTUO577A	4304733140	NBU 506-23E	720' FNL 1818' FWL	T09S-R20E-23-NENW
UTUO1791	4304733124	NBU 508-08E	915' FSL 355' FEL	T10S-R21E-08-SESE
UTUO1197A ST	4304739283	NBU 513-12EX	1850' FNL 2133' FWL	T10S-R22E-12-SENW
UTUO2270A	4304733696	NBU 516-12E	1950' FSL 1786' FEL	T10S-R20E-12-NWSE
UTUO141315	4304733779	NBU 519-03E	1749' FSL 798' FWL	T09S-R21E-03-NWSW
UTUO575B	4304733780	NBU 521-08E	2250' FSL 900' FWL	T09S-R21E-08-NWSW
UTUO1188	4304733781	NBU 522-10E	732' FSL 841' FEL	T09S-R21E-10-SESE
UTUO2270A	4304733685	NBU 523-12E	660' FSL 660' FEL	T10S-R20E-12-SESE
UTUO2270A	4304733701	NBU 524-12E	841' FSL 1795' FEL	T10S-R20E-12-SWSE
UTUO2270A	4304739722	NBU 529-07E	704' FNL 762' FWL	T10S-R21E-07-NWNW
UTUO581	4304734639	NBU 534-18E	1885' FSL 115' FWL	T09S-R21E-18-NWSW
UTUO2270A	4304735200	NBU 535-17E	1893' FSL 580' FWL	T10S-R21E-17-NWSW
ML22791	4304735252	NBU 536-18E	734' FSL 2293' FWL	T10S-R21E-18-SESW
UTUO2270A	4304735253	NBU 537-18E	1880' FSL 1830' FEL	T10S-R21E-18-NWSE

RECEIVED

DEC 24 2009

Lease #	API #	Well Name	Footages	Legal Description
UTUO284	4304735886	NBU 538-19E	1937' FSL 1833' FWL	T09S-R22E-19-NESW
UTUO149076	4304735887	NBU 539-24E	1870' FSL 477' FEL	T09S-R21E-24-NESE
UTUO10953	4304736280	NBU 546-01E	2036' FSL 699' FWL	T10S-R22E-01-NWSW
UTUO10953	4304736278	NBU 547-01E	749' FSL 598' FWL	T10S-R22E-01-SWSW
UTU474	4304737687	NBU 553-28E	767' FNL 753' FWL	T10S-R22E-28-NWNW
UTU474	4304737686	NBU 554-28E	2023' FNL 465' FWL	T10S-R22E-28-SWNW
ML22791	4304737685	NBU 555-18E	1984' FSL 1790' FWL	T10S-R21E-18-NESW
ML22791	4304737514	NBU 556-18E	1800' FSL 870' FWL	T10S-R21E-18-NWSW
ML22791	4304737513	NBU 557-18E	852' FSL 661' FWL	T10S-R21E-18-SWSW
UTUO2270A	4304737510	NBU 558-17E	748' FSL 611' FWL	T10S-R21E-17-SWSW
UTUO2278C	4304737509	NBU 559-17E	467' FSL 2065' FWL	T10S-R21E-17-SESW
UTUO2278	4304737508	NBU 560-17E	1946' FSL 1896' FWL	T10S-R21E-17-NESW
UTUO2278	4304737512	NBU 561-17E	857' FSL 1988' FEL	T10S-R21E-17-SWSE
ML22792	4304737536	NBU 562-19E	859' FNL 859' FEL	T10S-R21E-19-NENE
ML22792	4304737537	NBU 563-19E	1982' FSL 1878' FEL	T10S-R21E-19-NWSE
UTU4476	4304738962	NBU 564-26E	665' FNL 1945' FWL	T10S-R20E-26-NENW
ML22793	4304737533	NBU 565-30E	1865' FNL 1786' FEL	T10S-R21E-30-SWNE
UTUO2270A	4304738375	NBU 566-17E	538' FNL 1806' FWL	T10S-R21E-17-NENW
UTUO1791	4304738535	NBU 567-17E	690' FNL 1988' FEL	T10S-R21E-17-NWNE
UTUO1791	4304738537	NBU 568-17E	850' FNL 807' FEL	T10S-R21E-17-NENE
UTUO1791	4304738534	NBU 569-17E	2009' FNL 1809' FEL	T10S-R21E-17-SWNE
UTUO1791	4304738529	NBU 570-17E	2031' FNL 672' FEL	T10S-R21E-17-SENE
UTUO2278	4304738377	NBU 571-17E	1964' FSL 1831' FEL	T10S-R21E-17-NWSE
UTUO2278	4304738374	NBU 572-17E	1810' FSL 739' FEL	T10S-R21E-17-NESE
UTUO2278	4304738510	NBU 573-17E	813' FSL 481' FEL	T10S-R21E-17-SESE
ML22650	4304739308	NBU 602-36E	1723' FNL 719' FWL	T09S-R22E-36-SWNW
UTUO1393B	4304739305	NBU 614-05E	716' FNL 1967' FEL	T10S-R21E-05-NWNE
UTUO1393B	4304739655	NBU 615-05E	2384' FNL 1015' FEL	T10S-R21E-05-SENE
UTUO1393B	4304739337	NBU 617-04E	933' FNL 745' FWL	T10S-R21E-04-NWNW
UTUO1393B	4304739336	NBU 618-04E	998' FSL 661' FWL	T10S-R21E-04-SWSW
UTUO1393B	4304739414	NBU 625-04E	1937' FNL 1722' FWL	T10S-R21E-04-SENW
UO01197A ST	4304739192	NBU 632-12E	860' FNL 2032' FWL	T10S-R22E-12-NENW
UO01197A ST	4304739193	NBU 633-12E	789' FNL 2179' FEL	T10S-R22E-12-NWNE
UO01197A ST	4304739190	NBU 635-12E	1808' FNL 1754' FEL	T10S-R22E-12-SWNE
UTUO1197A ST	4304739191	NBU 636-12E	1824' FNL 461' FEL	T10S-R22E-12-SENE
UTUO8512 ST	4304750016	NBU 638-13E	1926' FNL 2504' FWL	T10S-R22E-13-SENW
UTUO8512 ST	4304750019	NBU 639-13E	859' FNL 1902' FEL	T10S-R22E-13-NWNE
UTUO8512 ST	4304750014	NBU 640-13E	1619' FNL 1639' FEL	T10S-R22E-13-SWNE
UTUO8512A ST	4304750058	NBU 641-13E	990' FNL 1184' FEL	T10S-R22E-13-NENE
UTUO8512 ST	4304750013	NBU 642-13E	1949' FNL 858' FEL	T10S-R22E-13-SENE
UTUO2270A	4304739957	NBU 653-07E	660' FNL 1980' FWL	T10S-R21E-07-NENW
UTUO2270A	4304739956	NBU 654-07E	1913' FNL 522' FWL	T10S-R21E-07-SWNW
UTUO2270A	4304739860	NBU 655-07E	1926' FSL 750' FWL	T10S-R21E-07-NWSW
UTUO1791	4304739856	NBU 658-01E	2177' FNL 1784' FEL	T10S-R20E-01-SWNE
UTUO2270A	4304739858	NBU 660-12E	661' FNL 691' FEL	T10S-R20E-12-NENE
ML22790	4304750011	NBU 661-24E	1734' FSL 661' FWL	T10S-R20E-24-NWSW
ML22790	4304750017	NBU 662-24E	809' FSL 807' FWL	T10S-R20E-24-SWSW
ML22790	4304750010	NBU 663-24E	810' FSL 1979' FWL	T10S-R20E-24-SESW
ML22790	4304739867	NBU 664-24E	1810' FNL 1781' FEL	T10S-R20E-24-NWSE
ML22790	4304750018	NBU 665-24E	1950' FSL 660' FEL	T10S-R20E-24-NESE
ML22790	4304750057	NBU 666-24E	1043' FSL 1722' FEL	T10S-R20E-24-SWSE
ML22790	4304750012	NBU 667-24E	660' FSL 660' FEL	T10S-R20E-24-SESE
UTUO2270A	4304739901	NBU 668-12E	859' FNL 1915' FEL	T10S-R20E-12-NWNE
UO1207 ST	4304740084	NBU 670-29E	2018' FSL 859' FEL	T09S-R22E-29-NESE
UO1207 ST	4304750027	NBU 691-29E	680' FNL 797' FEL	T09S-R22E-29-NENE
ML3140.5	4304738330	NBU 760-36E	1320' FNL 1320' FEL	T09S-R20E-36-NENE
UTU4476	4304738632	NBU 762-26E	1506' FNL 1449' FEL	T10S-R20E-26-SWNE
ML22792	4304738332	NBU 763-19E	1258' FSL 1388' FEL	T10S-R21E-19-SWSE
ML3142	4304738331	NBU 764-32E	875' FNL 667' FWL	T09S-R21E-32-NWNW
UTUO1791	4304738633	NBU 765-09E	1000' FSL 1640' FWL	T10S-R21E-09-SESW

RECEIVED

DEC 24 2009

DIV. OF OIL, GAS & MINING

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT  FORM 8  
(highlight changes)

**WELL COMPLETION OR RECOMPLETION REPORT AND LOG**

5. LEASE DESIGNATION AND SERIAL NUMBER:  
**U-08512-ST**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME  
**Natural Buttes**

8. WELL NAME and NUMBER:  
**Natural Buttes Unit 642-13E**

9. API NUMBER:  
**43-047-50013**

10. FIELD AND POOL, OR WILDCAT  
**Natural Buttes**

11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:  
**SENE 13 10S 22E S**

12. COUNTY  
**Uintah**

13. STATE  
**UTAH**

1a. TYPE OF WELL: OIL WELL  GAS WELL  DRY  OTHER \_\_\_\_\_

b. TYPE OF WORK: NEW WELL  HORIZ. LATS.  DEEP-EN  RE-ENTRY  DIFF. RESVR.  OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
**EOG Resources, Inc.**

3. ADDRESS OF OPERATOR:  
**600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202** PHONE NUMBER: **(303) 824-5526**

4. LOCATION OF WELL (FOOTAGES)  
AT SURFACE: **1949' FNL & 858' FEL 39.950833 LAT 109.381944 LON**  
AT TOP PRODUCING INTERVAL REPORTED BELOW: **Same**  
AT TOTAL DEPTH: **Same**

14. DATE SPUDDED: **2/24/2009** 15. DATE T.D. REACHED: **4/12/2009** 16. DATE COMPLETED: **6/26/2009** ABANDONED  READY TO PRODUCE

17. ELEVATIONS (DF, RKB, RT, GL):  
**5314' NAT GL**

18. TOTAL DEPTH: MD **7,110** TVD \_\_\_\_\_ 19. PLUG BACK T.D.: MD **7,062** TVD \_\_\_\_\_ 20. IF MULTIPLE COMPLETIONS, HOW MANY? \* \_\_\_\_\_ 21. DEPTH BRIDGE MD \_\_\_\_\_ PLUG SET: TVD \_\_\_\_\_

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)  
**RST/CBL/CCL/VDL/GR /Temp**

23. WAS WELL CORED? NO  YES  (Submit analysis)  
WAS DST RUN? NO  YES  (Submit report)  
DIRECTIONAL SURVEY? NO  YES  (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12.25	9.625 J-55	36.0	0	2,203		900		0	
7.875	4.5 P-110	11.6	0	7,110		1240		1100	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2.375	5,093							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Wasatch/Mesaverde	5,092	6,996			6,804 6,996		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(B)					6,493 6,756		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)					6,217 6,427		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)					5,955 6,167		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
6804-6996	46,715 GALS GELLED WATER & 139,700# 20/40 SAND
6493-6756	35,973 GALS GELLED WATER & 102,300# 20/40 SAND
6217-6427	52,010 GALS GELLED WATER & 156,100# 20/40 SAND

29. ENCLOSED ATTACHMENTS:

ELECTRICAL/MECHANICAL LOGS  GEOLOGIC REPORT  DST REPORT  DIRECTIONAL SURVEY  
 SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION  CORE ANALYSIS  OTHER: \_\_\_\_\_

30. WELL STATUS:  
**Producing**

**RECEIVED**  
**JUL 27 2009**

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 6/26/2009		TEST DATE: 7/6/2009		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL - BBL: 18	GAS - MCF: 1,053	WATER - BBL: 150	PROD. METHOD: Flows
CHOKE SIZE: 14/64"	TBG. PRESS. 1,450	CSG. PRESS. 1,850	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL: 18	GAS - MCF: 1,053	WATER - BBL: 150	INTERVAL STATUS: Producing

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Sold

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Wasatch/Mesaverde	5,092	6,996		Green River	930
				Birds Nest	1,255
				Mahogany	1,804
				Uteland Butte	3,952
				Wasatch	4,044
				Chapita Wells	4,629
				Buck Canyon	5,291
				Price River	6,316
				Middle Price River	7,089

35. ADDITIONAL REMARKS (Include plugging procedure)

See attached page for additional information.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Mary A. Maestas TITLE Regulatory Assistant  
 SIGNATURE *Mary A. Maestas* DATE 7/22/2009

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining Phone: 801-538-5340  
 1594 West North Temple, Suite 1210  
 Box 145801 Fax: 801-359-3940  
 Salt Lake City, Utah 84114-5801

**Natural Buttes Unit 642-13E - ADDITIONAL REMARKS (CONTINUED):**

**27. PERFORATION RECORD**

5092-5699	3/spf
-----------	-------

**28. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.**

5955-6167	43,684 GALS GELLED WATER & 128,700# 20/40 SAND
5092-5699	33,789 GALS GELLED WATER & 58,200# 20/40 SAND

Perforated the Upper Price River from 6804-05', 6811-12', 6820-21', 6853-54', 6861-62', 6916-17', 6935-36', 6950-52', 6964-65', 6985-86', 6995-96' w/ 3 spf.

Perforated the Upper Price River from 6493-94', 6501-02', 6562-63', 6569-70', 6592-93', 6635-36', 6641-42', 6649-50', 6700-01', 6711-12', 6739-40', 6755-56' w/ 3 spf.

Perforated the North Horn/Upper Price River from 6217-18', 6230-31', 6246-47', 6293-94', 6323-25', 6339-40', 6358-59', 6377-78', 6412-13', 6417-18', 6426-27' w/ 3 spf.

Perforated the North Horn from 5955-56', 5980-81', 5990-91', 6008-09', 6055-57', 6063-64', 6111-12', 6117-18', 6152-53', 6162-63', 6166-67' w/ 3 spf.

Perforated the Ca/Ba from 5092-93', 5110-11', 5149-50', 5161-62', 5228-29', 5282-83', 5401-02', 5533-34', 5542-43', 5577-78', 5648-49', 5698-99' w/ 3 spf.