

STATE OF UTAH
 DEPARTMENT OF NATURAL RESOURCES
 DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL				1. WELL NAME and NUMBER CWU 1253-11		
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				3. FIELD OR WILDCAT NATURAL BUTTES		
4. TYPE OF WELL Gas Well <input type="checkbox"/> Coalbed Methane Well: NO <input type="checkbox"/>				5. UNIT or COMMUNITIZATION AGREEMENT NAME CHAPITA WELLS		
6. NAME OF OPERATOR EOG Resources, Inc.				7. OPERATOR PHONE 435 781-9111		
8. ADDRESS OF OPERATOR 1060 East Highway 40, Vernal, UT, 84078				9. OPERATOR E-MAIL kaylene_gardner@eogresources.com		
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU0281		11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		
13. NAME OF SURFACE OWNER (if box 12 = 'fee')				14. SURFACE OWNER PHONE (if box 12 = 'fee')		
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')				16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')		18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>		19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	852 FNL 2115 FEL	NWNE	11	9.0 S	22.0 E	S
Top of Uppermost Producing Zone	852 FNL 2115 FEL	NWNE	11	9.0 S	22.0 E	S
At Total Depth	852 FNL 2115 FEL	NWNE	11	9.0 S	22.0 E	S
21. COUNTY UINTAH		22. DISTANCE TO NEAREST LEASE LINE (Feet) 852		23. NUMBER OF ACRES IN DRILLING UNIT 2558		
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1310		26. PROPOSED DEPTH MD: 9770 TVD: 9770		
27. ELEVATION - GROUND LEVEL 4779		28. BOND NUMBER NM2308		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-225		

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORCANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP

NAME Mary Maestas	TITLE Regulatory Assistant	PHONE 303 824-5526
SIGNATURE	DATE 05/14/2009	EMAIL mary_maestas@eogresources.com
API NUMBER ASSIGNED 43047503710000	APPROVAL  Permit Manager	

Proposed Hole, Casing, and Cement

String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	9.625	0	2300		
Pipe	Grade	Length	Weight			
	Grade J-55 ST&C	2300	36.0			

Proposed Hole, Casing, and Cement

String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	9770		
Pipe	Grade	Length	Weight			
	Grade P-110 LT&C	9770	11.6			

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,933		Shale	
Birdsnest Zone	2,060		Dolomite	
Mahogany Oil Shale Bed	2,576		Shale	
Wasatch	4,927		Sandstone	
Chapita Wells	5,533		Sandstone	
Buck Canyon	6,200		Sandstone	
North Horn	6,892		Sandstone	
KMV Price River	7,430	Primary	Sandstone	Gas
KMV Price River Middle	8,259	Primary	Sandstone	Gas
KMV Price River Lower	9,056	Primary	Sandstone	Gas
Sego	9,574		Sandstone	
TD	9,770			

Estimated TD: 9,770' or 200'± below TD

Anticipated BHP: 5,334 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
 BOP schematic diagrams attached.

4. CASING PROGRAM:

CASING	Hole Size	Length	Size	WEIGHT	Grade	Thread	Rating Collapse	Factor Burst	Tensile
Conductor	20"	40 – 60'	14"	32.5#	A252			1880 Psi	10,000#
Surface	12 ¼"	0-2,300 KB±	9 5/8"	36.0#	J-55	STC	2020 PSI	3520 PSI	394,00#
Production	7-7/8"	Surface – TD	4-1/2"	11.6#	P-110	LTC	7560 PSI	10,690 Psi	279,000#

Note: 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe
Insert Float Collar (PDC drillable)
Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD):

Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 1
Onshore Oil and Gas Order No. 2 – Section E: Special Drilling Operations

- EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line to be 100' in length. (Where possible, a straight run blooie line will be used).
- EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be approximately 75' in length.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring dedusting equipment. Dust during air drilling operations is controlled by water mist.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring an automatic igniter or continuous pilot light on the blooie line. (Not required on aerated water system).
- EOG Resources, Inc. requests a variance that compressors are located in the opposite direction from the blooie line a minimum of 100 feet from the well bore. (Air Compressors are rig mounted).

8. EVALUATION PROGRAM:

Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
CBL/CCL/VDL/GR

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

- Lead: 185 sks** Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.
- Tail: 207 sks** Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.
- Top Out:** As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.
- Note:** Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

- Lead: 146 sks:** Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.
- Tail: 934 sks:** 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.
- Note:** The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

13. Air Drilling Operations:

1. Main Air Compressors are 1250 CFM 350 psi with 2000 psi Boosters and are rig mounted.
2. Secondary Air Compressors are 1170 CFM 350 psi with 2000 psi Boosters and are rig mounted.
3. Minimum setting depth of conductor casing will be 60' GL or 10'± into competent formation, whichever is deeper, as determined by the EOG person in charge. Exceptions must be approved by an EOG drilling superintendent or manager.
4. The diameter of the diverter flow line will be a minimum of 10" to help reduce back pressure on the well bore during uncontrolled flow.
5. Rat and Mouse hole drilling will occur only after surface casing has been set and cemented.
6. EOG Resources, Inc. will use a properly maintained and lubricated stripper head.


(Attachment: BOP Schematic Diagram)

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11

**NW/NE, SEC. 11, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH**

**EOG RESOURCES 11" 5,000 PSI W.P. BOP
CONFIGURATION**




DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

EOG RESOURCES CHOKE MANIFOLD CONFIGURATION
W/ 5,000 PSI WP VALVES

PAGE 2 OF 2



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.

Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, w

4. whichever is greater.
5. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements.

T9S, R22E, S.L.B.&M.

EOG RESOURCES, INC.



Well location, CWU #1253-11, located as shown in the NW 1/4 NE 1/4 of Section 11, T9S, R22E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 20EAM LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M., TAKEN FROM THE OURAY SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.


BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT IS A TRUE AND CORRECT REPRESENTATION OF THE FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



Section Corner
Re-Established by
Double Proportion
Method (Not Set)

S 1/4 Sec. 12
1977 Brass Cap 0.5'
High, Loose Stones

S89°22'55\"W - 2654.51' (Meas.)

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.
- △ = SECTION CORNERS RE-ESTABLISHED. (Not Set On Ground)

(NAD 83)
LATITUDE = 40°03'19.58" (40.055439)
LONGITUDE = 109°24'19.01" (109.405281)
(NAD 27)
LATITUDE = 40°03'19.71" (40.055475)
LONGITUDE = 109°24'16.55" (109.404597)

UINTAH ENGINEERING & LAND SURVEYING 85 SOUTH 200 EAST - VERNAL, UTAH 84078 (435) 789-1017		
SCALE 1" = 1000'	DATE SURVEYED: 06-07-06	DATE DRAWN: 06-09-06
PARTY G.S. T.F. P.M.	REFERENCES G.L.O. PLAT	
WEATHER HOT	FILE EOG RESOURCES, INC.	

API Well No: 43047503710000

EOG RESOURCES, INC.

CWU #1253-11

SECTION 11, T9S, R22E, S.L.B.&M.



PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; PROCEED IN A SOUTHEASTERLY THEN NORTHEASTERLY DIRECTION APPROXIMATELY 2.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN RIGHT AND PROCEED IN AN EASTERLY THEN NORTHEASTERLY DIRECTION APPROXIMATELY 0.8 MILES THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN AN NORTHEASTERLY DIRECTION APPROXIMATELY 200' TO THE EXISTING #320X-11F AND THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 47.3 MILES.

EOG RESOURCES, INC.


FIGURE #1

LOCATION LAYOUT FOR
CWU #1253-11
SECTION 11, T9S, R22E, S.L.B.&M.
852' FNL 2115' FEL



SCALE: 1" = 50'
DATE: 06-09-06
Drawn By: P.M.

NOTE:
Flare Pit is to be located
a min. of 100' from the
Well Head.



EOG RESOURCES, INC.

CWU #1253-11

LOCATED IN UINTAH COUNTY, UTAH
SECTION 11, T9S, R22E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHEASTERLY




PHOTO: VIEW OF EXISTING ACCESS


CAMERA ANGLE: NORTHEASTERLY



UELS Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 435-789-1017 uels@uelsinc.com

- Since 1964 -

LOCATION PHOTOS	06	13	06	PHOTO
	MONTH	DAY	YEAR	
TAKEN BY: G.S.	DRAWN BY: B.C.	REVISED: 00-00-00		



LEGEND:

● PROPOSED LOCATION



EOG RESOURCES, INC.

CWU #1253-11
 SECTION 11, T9S, R22E, S.L.B.&M.
 852' FNL 2115' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAG (435) 789-1813

**TOPOGRAPHIC
 MAP**


06	13	06
MONTH	DAY	YEAR

SCALE: 1:100,000

DRAWN BY: B.C.

REVISED: 00-00-00





LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD




EOG RESOURCES, INC.

CWU #1253-11
SECTION 11, T9S, R22E, S.L.B.&M.
852' FNL 2115' FEL

UES
Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAG (435) 789-1813

TOPOGRAPHIC MAP
 06 MONTH 13 DAY 06 YEAR
 SCALE: 1" = 2000' DRAWN BY: B.C. REVISED: 00-00-00

B
TOPO



**PROPOSED LOCATION:
CWU #1253-11**

LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ⊗ WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

EOG RESOURCES, INC.

**CWU #1253-11
SECTION 11, T9S, R22E, S.L.B.&M.
852' FNL 2115' FEL**

UEIS
Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP 06 13 06
 MONTH DAY YEAR
 SCALE: 1" = 2000' DRAWN BY: B.C. REVISED: 00-00-00





**Chapita Wells Unit 1253-11
NWNE, Section 11, T9S, R22E
Uintah County, Utah**

SURFACE USE PLAN

The well pad is approximately 325 feet long with a 246-foot width, containing 1.84 acres more or less. New surface disturbance associated with the well pad is estimated to be 1.84 acres.

1. EXISTING ROADS:

- A. See attached Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 47.3 miles south of Vernal, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. The existing road to the northeast not needed to access the proposed location will be reclaimed.

2. PLANNED ACCESS ROAD:

- A. The existing access road for the Chapita Wells Unit 320-11X will be used to access the proposed location. No new road will be required.
- B. No additional storage areas will be needed for storing equipment, stockpiling, or vehicle parking.

All travel will be confined to existing access road rights-of-way.

Traveling off the 30-foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:

See attached TOPO map "C" for the location of wells within a one-mile radius.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

A. On Well Pad

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400-bbl vertical tanks and associated pipe.
2. Gas gathering lines – A 4” gathering line will be buried from the dehy unit to the edge of the location.

B. Off Well Pad

1. No new off-pad pipeline will be required. The existing pipeline for the Chapita Wells Unit 320-11X will be used to transport gas from the proposed location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All facilities will be painted with Carlsbad Canyon or Covert Green.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

5. LOCATION AND TYPE OF WATER SUPPLY:

- A. Water supply will be Bonanza Power Plant water source in Sec 26, T8S, R23E, Uintah County, UT (State Water Right # 49-225(A31368)).
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIALS:

- A. All construction material for this pipeline will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL:

A. METHODS AND LOCATION

1. Cuttings will be confined in the reserve pit.
2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.

3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
 4. Produced wastewater will be confined to a storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, CWU 550-30N SWD CWU 2-29 SWD, Red Wash Evaporation Ponds 1, 2, 3, 4, 5, 6, or 7, or Coyote Evaporation Ponds 1, 2, 3, or 4, or White River Evaporation Ponds 1, or 2, or Hoss SWD Facility, right-of-way UTU 86010, UTU 897093 or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit, through natural or artificial methods, or removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with **double felt**, and a **20-millimeter** plastic liner. Sufficient bedding (i.e. weed free straw, or hay; felt; polyswell or soil) will be used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the Authorized Officer (A.O.)

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well.

Furthermore, extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will not be used, produced, stored, transported, or disposed of in association with the drilling, testing or completion of the well.

8. ANCILLARY FACILITIES:

None anticipated.

9. WELL SITE LAYOUT:

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the northwest corner of the location. The flare pit will be located downwind of the prevailing wind direction on the north side of the location, a minimum of 100 feet from the wellhead and 30 feet from the reserve pit fence.

The stockpiled location topsoil will be stored in a location providing easy access for interim reclamation and protection of the topsoil. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the southwest.

The corners of the well pad will be rounded off as needed to minimize excavation.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.

- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion of construction, the fence shall be repaired to BLM or SMA specifications. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RECLAMATION OF THE SURFACE:

A. Interim Reclamation (Producing Location)

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be reseeded during interim reclamation. The reserve pit will be reclaimed within 6 months from the date of the well completion, or as soon as weather allows. Before any dirt takes place, the reserve pit must be completely dry and free of all foreign obstacles.

The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

Seed Mixture	Drilled Rate (lbs./acre PLS*)
HyCrest Wheatgrass	4.0
Fourwing Saltbush	4.0
Needle and Threadgrass	4.0

*Pure live seed (PLS) formula: percent of purity of seed mixture times percent germination of seed mixture equals portion of seed mixture that is PLS.

B. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriate surface rehabilitation conditions of approval.

The final seed mix for the proposed location will be determined upon P&A of the well.

11. SURFACE OWNERSHIP:

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

Bureau of Land Management

12. OTHER INFORMATION:

- A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:
- Whether the materials appear eligible for the National Register of Historic Places;
 - The mitigation measures the operator will likely have to undertake before the site can be used.
 - A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will

assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application or herbicides or other pesticides or possible hazardous chemicals.
- C. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.
- D. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

A cultural resources survey was conducted and submitted by Montgomery Archaeological Consultants on 6/29/2006. A paleontological survey was conducted and submitted by Intermountain Paleo on 8/3/2006.

Additional Surface Stipulations:

None.

LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

PERMITTING AGENT

Mary A. Maestas
EOG Resources, Inc.
1060 East Highway 40
Vernal, UT 84078
(435) 781-9111

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

The operator or his/her contractor shall contact the BLM office at (435) 781-4400 forty-eight (48) hours prior to construction activities.

CERTIFICATION:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the Chapita Wells Unit 1253-11 Well, located in the NWNE, of Section 11, T9S, R22E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

April 24, 2009

Date

Mary A. Maestas, Regulatory Assistant

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

May 1, 2009

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2009 Plan of Development Chapita Wells Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2009 within the Chapita Wells Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ Wasatch)		
43-047-50370	CWU 4006-22 Sec 22	T09S R22E 1997 FSL 1317 FWL
43-047-50372	CWU 784-25 Sec 25	T09S R22E 0670 FNL 0786 FWL
43-047-50373	CWU 782-23 Sec 23	T09S R22E 0642 FNL 2020 FWL
43-047-50374	CWU 4010-23 Sec 23	T09S R22E 0674 FSL 0601 FEL
43-047-50375	CWU 4009-27 Sec 27	T09S R22E 0606 FNL 1999 FWL
43-047-50376	CWU 4008-22 Sec 22	T09S R22E 0291 FNL 0147 FEL
43-047-50377	CWU 4007-22 Sec 22	T09S R22E 2442 FNL 2383 FEL

(Proposed PZ Mesaverde)

43-047-50371 CWU 1253-11 Sec 11 T09S R22E 0852 FNL 2115 FEL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Chapita Wells Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:5-1-09

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 4/24/2009

API NO. ASSIGNED: 43047503710000

WELL NAME: CWU 1253-11

OPERATOR: EOG Resources, Inc. (N9550)

PHONE NUMBER: 303 824-5526

CONTACT: Mary Maestas

PROPOSED LOCATION: NWNE 11 090S 220E

Permit Tech Review:

SURFACE: 0852 FNL 2115 FEL

Engineering Review:

BOTTOM: 0852 FNL 2115 FEL

Geology Review:

COUNTY: UINTAH

LATITUDE: 40.05547

LONGITUDE: -109.40465

UTM SURF EASTINGS: 636075.00

NORTHINGS: 4434923.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU0281

PROPOSED PRODUCING FORMATION(S): WASATCH

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- PLAT
- Bond: FEDERAL - NM2308
- Potash
- Oil Shale 190-5
- Oil Shale 190-3
- Oil Shale 190-13
- Water Permit: 49-225
- RDCC Review:
- Fee Surface Agreement
- Intent to Commingle

Commingling Approved

LOCATION AND SITING:

- R649-2-3.
Unit: CHAPITA WELLS
- R649-3-2. General
- R649-3-3. Exception
- Drilling Unit
Board Cause No: Cause 179-8
Effective Date: 8/10/1999
Siting: Suspends General Siting
- R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason
17 - Oil Shale 190-5(b) - dmason



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: CWU 1253-11
API Well Number: 43047503710000
Lease Number: UTU0281
Surface Owner: FEDERAL
Approval Date: 5/14/2009

Issued to:

EOG Resources, Inc., 1060 East Highway 40, Vernal, UT 84078

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 179-8. The expected producing formation or pool is the WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:

Notify the Division with 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office (801) 733-0983 home

Reporting Requirements:

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

Approved By:

A handwritten signature in black ink, appearing to read "Gil Hunt", written in a cursive style.

For Gil Hunt
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0281
---	--

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
--	---

1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1253-11
------------------------------------	--

2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047503710000
--	---

3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
--	--	--

4. LOCATION OF WELL FOOTAGES AT SURFACE: 0852 FNL 2115 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 11 Township: 09.0S Range: 22.0E Meridian: S	COUNTY: UINTAH STATE: UTAH
---	---

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 1/13/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. respectfully requests authorization to change the Drilling Plan as per the attached. Float Equipment: Item 5 Please see the attached revised Drilling Plan reflecting the purposed changes.

Accepted by the Utah Division of Oil, Gas and Mining

Date: January 14, 2010

By: *Derek [Signature]*

NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A		DATE 1/13/2010

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M.,
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,933		Shale	
Birdsnest Zone	2,060		Dolomite	
Mahogany Oil Shale Bed	2,576		Shale	
Wasatch	4,927		Sandstone	
Chapita Wells	5,533		Sandstone	
Buck Canyon	6,200		Sandstone	
North Horn	6,892		Sandstone	
KMV Price River	7,430	Primary	Sandstone	Gas
KMV Price River Middle	8,259	Primary	Sandstone	Gas
KMV Price River Lower	9,056	Primary	Sandstone	Gas
Sego	9,574		Sandstone	
TD	9,770			

Estimated TD: 9,770' or 200'± below TD

Anticipated BHP: 5,334 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

4. CASING PROGRAM:

CASING	Hole Size	Length	Size	WEIGHT	Grade	Thread	Rating Collapse	Factor Burst	Tensile
Conductor	20"	40 – 60'	14"	32.5#	A252			1880 Psi	10,000#
Surface	12 1/4"	0-2,300 KB±	9 5/8"	36.0#	J-55	STC	2020 PSI	3520 PSI	394,00#
Production	7-7/8"	Surface – TD	4-1/2"	11.6#	P-110	LTC	7560 PSI	10,690 Psi	279,000#

Note: 12-1/4" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11 NW/NE, SEC. 11, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-1/2", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 3rd joint to 400' above the top of primary object. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD):

Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11 NW/NE, SEC. 11, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH

7. VARIANCE REQUESTS:

**Reference: Onshore Oil and Gas Order No. 1
Onshore Oil and Gas Order No. 2 – Section E: Special Drilling Operations**

- EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line to be 100' in length. (Where possible, a straight run blooie line will be used).
- EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be approximately 75' in length.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring dedusting equipment. Dust during air drilling operations is controlled by water mist.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring an automatic igniter or continuous pilot light on the blooie line. (Not required on aerated water system).
- EOG Resources, Inc. requests a variance that compressors are located in the opposite direction from the blooie line a minimum of 100 feet from the well bore. (Air Compressors are rig mounted).

8. EVALUATION PROGRAM:

Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
CBL/CCL/VDL/GR

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11 NW/NE, SEC. 11, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

- Lead: 185 sks** Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.
- Tail: 207 sks** Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.
- Top Out:** As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.
- Note:** Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

- Lead: 146 sks:** Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.
- Tail: 934 sks:** 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.
- Note:** The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11 NW/NE, SEC. 11, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

13. Air Drilling Operations:


1. Main Air Compressors are 1250 CFM 350 psi with 2000 psi Boosters and are rig mounted.
2. Secondary Air Compressors are 1170 CFM 350 psi with 2000 psi Boosters and are rig mounted.
3. Minimum setting depth of conductor casing will be 60' GL or 10'± into competent formation, whichever is deeper, as determined by the EOG person in charge. Exceptions must be approved by an EOG drilling superintendent or manager.
4. The diameter of the diverter flow line will be a minimum of 10" to help reduce back pressure on the well bore during uncontrolled flow.
5. Rat and Mouse hole drilling will occur only after surface casing has been set and cemented.
6. EOG Resources, Inc. will use a properly maintained and lubricated stripper head.

(Attachment: [BOP Schematic Diagram](#))

DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M.,
UINTAH COUNTY, UTAH

EOG RESOURCES 11" 5,000 PSI W.P. BOP
CONFIGURATION




DRILLING PLAN

CHAPITA WELLS UNIT 1253-11
NW/NE, SEC. 11, T9S, R22E, S.L.B.&M.,
UINTAH COUNTY, UTAH

EOG RESOURCES CHOKE MANIFOLD CONFIGURATION
W/ 5,000 PSI WP VALVES

PAGE 2 OF 2



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.

Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, w

4. whichever is greater.
5. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0281
	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1253-11
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047503710000
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0852 FNL 2115 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 11 Township: 09.0S Range: 22.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Drilling Operations
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No activity has occurred since spud on May 5, 2010.

**Accepted by the
 Utah Division of
 Oil, Gas and Mining
 FOR RECORD ONLY**
 May 06, 2010

NAME (PLEASE PRINT) Michelle Robles	PHONE NUMBER 307 276-4842	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 5/6/2010	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0281
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1253-11
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047503710000
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0852 FNL 2115 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 11 Township: 09.0S Range: 22.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 5/5/2010	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input checked="" type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. respectfully requests authorization for the disposal of produced water at the following locations: 1. NBU 20-20B SWD 2. CWU 550-30N SWD 3. CWU 2-29 SWD 4. Red Wash Evaporation Ponds 1,2,3,4,5,6&7 5. White River Evaporation Ponds 1&2 6. Coyote Evaporation Ponds 1&2 7. RNI Disposal 8. Hoss SWD Wells ROW# UTU86010 & UTU897093

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 May 10, 2010

NAME (PLEASE PRINT) Michelle Robles	PHONE NUMBER 307 276-4842	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 5/6/2010	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc. Operator Account Number: N 9550
 Address: 1060 East Highway 40
city Vernal
state UT zip 84078 Phone Number: (307) 276-4842

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-50371	CHAPITA WELLS UNIT 1253-11		NWNE	11	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<i>AB</i>	99999	<i>13650</i>	5/5/2010			<i>5/18/10</i>	
Comments: <u>MESAVERDE</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Michelle Robles

Name (Please Print)

Michelle Robles

Signature

Regulatory Assistant

5/5/2010

Title

Date

RECEIVED

MAY 06 2010

(5/2000)

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0281
	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1253-11
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047503710000
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0852 FNL 2115 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 11 Township: 09.0S Range: 22.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 6/2/2010	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Please see the attached well chronology report for the referenced well showing all activity up to 6/2/2010.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 June 03, 2010

NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A	DATE 6/2/2010	

WELL CHRONOLOGY REPORT

Report Generated On: 06-01-2010

Well Name	CWU 1253-11	Well Type	DEVG	Division	DENVER
Field	CHAPITA DEEP	API #	43-047-50371	Well Class	DRIL
County, State	UINTAH, UT	Spud Date	05-26-2010	Class Date	
Tax Credit	N	TVD / MD	9,770/ 9,770	Property #	059229
Water Depth	0	Last CSG	4.5	Shoe TVD / MD	9,758/ 9,758
KB / GL Elev	4,792/ 4,779				
Location	Section 11, T9S, R22E, NWNE, 852 FNL & 2115 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	82.139

AFE No	304073	AFE Total	1,436,800	DHC / CWC	625,800/ 811,000
Rig Contr	TRUE	Rig Name	TRUE #31	Start Date	04-24-2009
04-24-2009	Reported By	SHEILA MALLOY			
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :	
				PKR Depth : 0.0	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA
			852' FNL & 2115' FEL (NW/NE)
			SECTION 11, T9S, R22E
			UINTAH COUNTY, UTAH
			LAT 40.055439, LONG 109.405281 (NAD83)
			LAT 40.055475, LONG 109.404597 (NAD27)
			TRUE #34
			OBJECTIVE: 9770' MD, MESAVERDE
			DW/GAS
			CHAPITA WELLS DEEP PROSPECT
			DD&A: NATURAL BUTTES
			NATURAL BUTTES FIELD
			LEASE: U-0281
			ELEVATION: 4779' NAT GL, 4779' PREP GL (DUE TO ROUNDING THE PREP GL IS 4779') 4795' KB (16')
			EOG WI 100%, NRI 82.139316%

05-03-2010 Reported By TERRY CSERE

DailyCosts: Drilling \$75,000 **Completion** \$0 **Daily Total** \$75,000
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION STARTED, 5/3/10.

05-04-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 90% COMPLETE. BLADING TODAY.

05-05-2010 **Reported By** TERRY CSERE/KENT DEVENPORT

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION-SPUD NOTIFICATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE. STARTING BERMS & CLOSED LOOP. CRAIGS ROUSTABOUT SERVICE SPUD A 20" HOLE ON 5/5/10 @ 10:30 AM. SET +/-60' OF 14" CONDUCTOR. CEMENT TO SURFACE WITH READY MIX. CAROL DANIELS W/UDOGM WAS NOTIFIED BY PHONE MESSAGE AND BLM WAS NOTIFIED BY EMAIL OF SPUD ON 5/4/10 @ 10:43 AM.

05-06-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: WO AIR RIG

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE. STARTING FINAL BLADE.

05-07-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00 06:00 24.0 GEL CLOSED LOOP.

05-10-2010 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$75,000	Completion	\$0	Well Total	\$75,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE, 5/10/10.

05-19-2010 Reported By KYLAN COOK

Daily Costs: Drilling	\$241,453	Completion	\$0	Daily Total	\$241,453
Cum Costs: Drilling	\$316,453	Completion	\$0	Well Total	\$316,453

MD	2,606	TVD	2,606	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: WORT

Start	End	Hrs	Activity Description
06:00	06:00	24.0	MIRU CRAIG'S AIR RIG #2 ON 5/8/2010. DRILLED 12-1/4" HOLE TO 2590' GL (+ 16' = 2606' KB). ENCOUNTERED GILSONITE @ 810'. DRILLED WITH AIR AND FOAM TO 820' THEN PUMP DRILLED TO TD WITH PARTIAL LOSSES. RAN 61 JTS (2576.91') OF 9-5/8", 36.0#, J-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 8 CENTRALIZERS SPACED MIDDLE OF SHOE JOINT AND EVERY COLLAR TILL GONE. LANDED @ 2592.91' KB. RAN 200' OF 1" PIPE DOWN BACK SIDE. RDMO CRAIG'S AIR RIG #2.
			MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 3200 PSIG. PUMPED 160 BBLs FRESH WATER & 20 BBLs GELLED WATER FLUSH AHEAD OF CEMENT.
			LEAD: MIXED AND PUMPED 250 SACKS (183 BBLs) OF PREMIUM LEAD CEMENT WITH 0.3% VARSET, 2% CAL-SEAL, AND 2% ECONOLITE. MIXED LEAD CEMENT @ 10.5 PPG WITH YIELD OF 4.1 CF/SX.
			TAIL: MIXED AND PUMPED 300 SACKS (63 BBLs) OF PREMIUM CEMENT WITH 2% CACL2 MIXED TAIL CEMENT @ 15.6 PPG WITH YIELD OF 1.18 CF/SX. DISPLACED CEMENT WITH 196 BBLs FRESH WATER. BUMPED PLUG WITH 980# @ 20:24 PM ON 5/14/10. FLOAT HELD. SHUT-IN CASING VALVE. BROKE CIRCULATION 160 BBLs INTO FRESH WATER FLUSH. LOST CIRCULATION 170 BBLs INTO DISPLACEMENT. NO CEMENT TO SURFACE.
			TOP JOB #1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 100 SX (21 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. NO RETURNS. WAIT ON CEMENT 3 HR 0 MIN.
			TOP JOB # 2: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 100 SX (21 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. HOLE FILLED AND STOOD FULL.
			PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.
			CRAIG'S RIG #2 TOOK SURVEYS WHILE DRILLING HOLE @ 750' = 1.00 DEGREE, 840' = 2.00 DEGREE, 1050' = 1.50 DEGREE, 1260' = 0.50 DEGREE, 1440' = 0.00 DEGREE, 1650' = 1.00 DEGREE, 1950' = 1.00 DEGREE, 2250' = 2.50 DEGREE, AND 2590' = 2.25 DEGREE.

KYLAN COOK NOTIFIED BLM VIA EMAIL OF THE SURFACE CASING & CEMENT JOB ON 5/11/10 @ 10:45 AM.

KYLAN COOK NOTIFIED CAROL DANIELS WITH UDOGM OF THE SURFACE CASING & CEMENT JOB VIA PHONE ON 5/11/10 @ 10:45 AM.

05-26-2010	Reported By	PAT CLARK									
Daily Costs: Drilling	\$115,982	Completion	\$0	Daily Total	\$115,982						
Cum Costs: Drilling	\$432,435	Completion	\$0	Well Total	\$432,435						
MD	2,606	TVD	2,606	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: DRILL OUT SHOE TRACK

Start	End	Hrs	Activity Description
06:00	00:00	18.0	MOVE RIG 8.4 MILES FROM CWU 1529-22. CRANE RELEASED @ 13:30, DERRICK IN AIR @ 14:00. TRUCKS RELEASED @ 14:30. RURT. TRANSFER 2 JTS 4 1/2", N-80, 11.6#, LTC CSG (42.50', 42.44') AND 2 MJ (20.32', 20.28') TRANSFER 1500 GALS DIESEL FUEL @ \$2.727/GAL.
00:00	02:30	2.5	RIG ON DAYWORK @ 00:00, 5-26-2010, HSM. NIPPLE UP & TEST BOPE. TEST HIGH 5000 PSI, UPPER AND LOWER KELLY VALVE, SAFETY AND DART VALVE, PIPE AND BLIND RAMS, HCR, KILL LINE AND VALVE, CHOKE LINE, CHOKE VALVE, MANIFOLD. TEST HIGH 1500 PSI HIGH ANNULAR PREVENTER. TEST CASING TO 1500 PSI FOR 30 MINUTES. PERFORM ACCUMULATOR FUNCTION TEST. BLM NOTIFIED OF BOP TEST BY E-MAIL ON 5-23-2010 @ 15:30. NO BLM REPRESENTATIVE TO WITNESS TEST.
02:30	05:00	2.5	HSM. R/U WEATHERFORD TRS. PICK UP BHA. TAG CEMENT @ 2550'. R/D TRS.
05:00	05:30	0.5	PRE-SPUD CHECKLIST.
05:30	06:00	0.5	DRILL CEMENT/FLOAT EQUIP. MORNING TOUR SHORT ONE MAN, NO ACCIDENTS. SAFETY MEETINGS - RURT, TEST BOP, P/U BHA. FUEL - 8868, DEL - 7600, USED - 232.

05-27-2010	Reported By	PAT CLARK									
Daily Costs: Drilling	\$33,142	Completion	\$0	Daily Total	\$33,142						
Cum Costs: Drilling	\$465,578	Completion	\$0	Well Total	\$465,578						
MD	5,040	TVD	5,040	Progress	2,448	Days	1	MW	10.1	Visc	32.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: DRILLING @ 5040'

Start	End	Hrs	Activity Description
06:00	07:00	1.0	DRILL CEMENT AND FLOAT EQUIPMENT. FC @ 2550', GS @ 2592'. DRILL 10' TO 2602' - FIT TEST FOR 10.5 EMW.
07:00	13:30	6.5	DRILL 2602' - 3367'. WOB 10K, RPM 65/73, SPP 2000 PSI, DP 350 PSI, ROP 118 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	15:30	1.5	DRILL 3367' - 3587'. SAME PARAMETERS, ROP 147 FPH.
15:30	16:00	0.5	SURVEY @ 3500 - 2.8 DEG.
16:00	23:00	7.0	DRILL 3587' - 4556'. SAME PARAMETERS, ROP 138 FPH.

23:00 23:30 0.5 SURVEY @ 4500' - 2.67 DEG.
 23:30 06:00 6.5 DRILL 4556' - 5040'. WOB 18K, RPM 62/73, SPP 2200 PSI, DP 350 PSI, ROP 74 FPH.

MORNING TOUR SHORT ONE HAND, NO ACCIDENTS.
 SAFETY MEETINGS - CONNECTIONS, CHANGING TONG DIES.
 BOP DRILL BOTH TOURS.
 FUEL - 7300, USED - 1568.
 MW - 10.6 PPG, VIS - 36 SPQ.

06:00 SPUD 7 7/8" HOLE @ 07:00 HRS, 5/26/10.

05-28-2010	Reported By	PAT CLARK									
DailyCosts: Drilling	\$25,032	Completion	\$0	Daily Total	\$25,032						
Cum Costs: Drilling	\$490,610	Completion	\$0	Well Total	\$490,610						
MD	6,120	TVD	6,120	Progress	1,080	Days	2	MW	10.7	Visc	37.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 6120'											

Start	End	Hrs	Activity Description
06:00	09:00	3.0	DRILL 5040' - 5248'. WOB 10-20K, RPM 45-60/73, SPP 2200 PSI, DP 250 PSI, ROP 69 FPH.
09:00	09:30	0.5	RIG SERVICE. CHECK COM.
09:30	06:00	20.5	DRILL 5248' - 6120'. WOB 10-20K, RPM 45-65/73, SPP 2300 PSI, DP 300 PSI, ROP 43 FPH. FULL CREWS, NO ACCIDENTS, BOP DRILL DAYLIGHTS.
SAFETY MEETINGS - CHIPPING PAINT, BOP DRILLS.			
FUEL - 5736, USED - 1564.			
MW - 10.9 PPG, VIS - 38 SPQ.			
LOST 50% CIRCULATION @ 5800' - 200 BBLS.			

05-29-2010	Reported By	PAT CLARK									
DailyCosts: Drilling	\$26,767	Completion	\$0	Daily Total	\$26,767						
Cum Costs: Drilling	\$517,377	Completion	\$0	Well Total	\$517,377						
MD	6,860	TVD	6,860	Progress	740	Days	3	MW	11.0	Visc	38.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 6860'											

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 6120' - 6417'. WOB 15-20K, RPM 40-65/73, SPP 2350 PSI, DP 200 PSI, ROP 40 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	06:00	16.0	DRILL 6417' - 6860'. SAME PARAMETERS, ROP 28 FPH. FULL CREWS, NO ACCIDENTS. SAFETY MEETINGS - PAINTING, PRESSURE WASHER. FUEL - 3850, USED - 1886. MW - 11 PPG, VIS - 38 SPQ, LOST 85 BBLS.

05-30-2010	Reported By	PAT CLARK							
DailyCosts: Drilling	\$37,524	Completion	\$0	Daily Total	\$37,524				

Cum Costs: Drilling \$554,902 **Completion** \$0 **Well Total** \$554,902
MD 7,416 **TVD** 7,416 **Progress** 556 **Days** 4 **MW** 11.1 **Visc** 37.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7416'

Start	End	Hrs	Activity Description
06:00	11:00	5.0	DRILL 6860' - 6995'. WOB 10-22K, RPM 40-65/73, SPP 2400 PSI, DP 300 PSI, ROP 27 FPH.
11:00	11:30	0.5	CIRCULATE AND CONDITION FOR TRIP. MIX AND PUMP PILL, DROP SURVEY.
11:30	14:00	2.5	TOH. L/D REAMERS, X/O BIT. RETRIEVE SURVEY - 1/2 DEG.
14:00	16:00	2.0	TIH. FILL PIPE @ 4000'.
16:00	16:30	0.5	WASH AND REAM 6950' - 6995'.
16:30	03:30	11.0	DRILL 6995' - 7363'. WOB 10-20K, RPM 40-65/70, SPP 2300 PSI, DP 250 PSI, ROP 33 FPH.
03:30	04:00	0.5	EQUIPMENT REPAIR - FIX WATER LEAK ON DRUM BRAKES.
04:00	06:00	2.0	DRILL 7363' - 7416'. SAME PARAMETERS, ROP 27 FPH.

FULL CREWS, NO ACCIDENTS, BOP DRILL BOTH TOURS.
 SAFETY MEETINGS - HOUSEKEEPING, TRIPPING.
 FUEL - 6800, DEL - 4500, USED - 1550.
 MW - 11.3 PPG, VIS - 38 SPQ, LOST 84 BBLs.

05-31-2010 **Reported By** PAT CLARK

Daily Costs: Drilling \$42,127 **Completion** \$0 **Daily Total** \$42,127
Cum Costs: Drilling \$597,030 **Completion** \$0 **Well Total** \$597,030
MD 7,948 **TVD** 7,948 **Progress** 532 **Days** 5 **MW** 11.3 **Visc** 37.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7948'

Start	End	Hrs	Activity Description
06:00	09:30	3.5	DRILL 7416' - 7540'. WOB 10-23K, RPM 40-65/67, SPP 2300 PSI, DP 200 PSI, ROP 35 FPH.
09:30	10:00	0.5	RIG SERVICE. CHECK COM.
10:00	20:30	10.5	DRILL 7540' - 7833'. SAME PARAMETERS, ROP 28 FPH.
20:30	21:00	0.5	CIRCULATE AND CONDITION F/TOH. MIX AND PUMP PILL.
21:00	00:00	3.0	TOH. X/O MM AND BIT.
00:00	03:00	3.0	TIH. FILL PIPE @ 4000'.
03:00	03:30	0.5	WASH/REAM 7800' - 7833'.
03:30	06:00	2.5	DRILL 7833' - 7948'. WOB 10-15K, RPM 55/67, SPP 2350 PSI, DP 300 PSI, ROP 46 FPH.

FULL CREWS, NO ACCIDENTS.
 SAFETY MEETINGS - L/D TOOLS, TRIPPING.
 FUEL - 5287, USED - 1463.
 MW - 11.4 PPG, VIS - 38 SPQ, LOST 75 BBLs.

06-01-2010 **Reported By** PAT CLARK

Daily Costs: Drilling \$29,927 **Completion** \$0 **Daily Total** \$29,927
Cum Costs: Drilling \$626,832 **Completion** \$0 **Well Total** \$626,832
MD 8,952 **TVD** 8,952 **Progress** 1,004 **Days** 6 **MW** 11.3 **Visc** 38.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 8952'

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 7948' - 8261'. WOB 10 - 13K, RPM 40/67, SPP 2300 PSI, DP 300 PSI, ROP 42 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	06:00	16.0	DRILL 8261' - 8952'. SAME PARAMETERS, ROP 43 FPH.

FULL CREWS. NO ACCIDENTS, BOP DRILL DAYLIGHTS.
SAFETY MEETINGS - FORKLIFT, CONNECTIONS.
MW - 11.4 PPG, VIS - 38 SPQ, LOST 73 BBLs.
FUEL - 3650, USED - 1637.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0281
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1253-11
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047503710000
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0852 FNL 2115 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 11 Township: 09.0S Range: 22.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 7/1/2010	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Please see the attached well chronology report for the referenced well showing all activity up to 7/1/2010.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 July 01, 2010

NAME (PLEASE PRINT) Michelle Robles	PHONE NUMBER 307 276-4842	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 7/1/2010	

WELL CHRONOLOGY REPORT

Report Generated On: 07-01-2010

Well Name	CWU 1253-11	Well Type	DEVG	Division	DENVER
Field	CHAPITA DEEP	API #	43-047-50371	Well Class	COMP
County, State	UINTAH, UT	Spud Date	05-26-2010	Class Date	
Tax Credit	N	TVD / MD	9,770/ 9,770	Property #	059229
Water Depth	0	Last CSG	4.5	Shoe TVD / MD	9,758/ 9,758
KB / GL Elev	4,792/ 4,779				
Location	Section 11, T9S, R22E, NWNE, 852 FNL & 2115 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	82.139

AFE No	304073	AFE Total	1,436,800	DHC / CWC	625,800/ 811,000
Rig Contr	TRUE	Rig Name	TRUE #31	Start Date	04-24-2009
04-24-2009	Reported By	SHEILA MALLOY			
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA
			852' FNL & 2115' FEL (NW/NE)
			SECTION 11, T9S, R22E
			UINTAH COUNTY, UTAH
			LAT 40.055439, LONG 109.405281 (NAD83)
			LAT 40.055475, LONG 109.404597 (NAD27)
			TRUE #34
			OBJECTIVE: 9770' MD, MESAVERDE
			DW/GAS
			CHAPITA WELLS DEEP PROSPECT
			DD&A: NATURAL BUTTES
			NATURAL BUTTES FIELD
			LEASE: U-0281
			ELEVATION: 4779' NAT GL, 4779' PREP GL (DUE TO ROUNDING THE PREP GL IS 4779'), 4795' KB (16')
			EOG WI 100%, NRI 82.139316%

05-03-2010 Reported By TERRY CSERE

DailyCosts: Drilling \$75,000 **Completion** \$0 **Daily Total** \$75,000
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION STARTED, 5/3/10.

05-04-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 90% COMPLETE. BLADING TODAY.

05-05-2010 **Reported By** TERRY CSERE/KENT DEVENPORT

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION-SPUD NOTIFICATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE. STARTING BERMS & CLOSED LOOP. CRAIGS ROUSTABOUT SERVICE SPUD A 20" HOLE ON 5/5/10 @ 10:30 AM. SET +/-60' OF 14" CONDUCTOR. CEMENT TO SURFACE WITH READY MIX. CAROL DANIELS W/UDOGM WAS NOTIFIED BY PHONE MESSAGE AND BLM WAS NOTIFIED BY EMAIL OF SPUD ON 5/4/10 @ 10:43 AM.

05-06-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: WO AIR RIG

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE. STARTING FINAL BLADE.

05-07-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00 06:00 24.0 GEL CLOSED LOOP.

05-10-2010 **Reported By** TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$75,000	Completion	\$0	Well Total	\$75,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :			PBTD : 0.0		Perf :		PKR Depth : 0.0				

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE, 5/10/10.

05-19-2010 **Reported By** KYLAN COOK

Daily Costs: Drilling	\$241,453	Completion	\$0	Daily Total	\$241,453
Cum Costs: Drilling	\$316,453	Completion	\$0	Well Total	\$316,453

MD	2,606	TVD	2,606	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :			PBTD : 0.0		Perf :		PKR Depth : 0.0				

Activity at Report Time: WORT

Start	End	Hrs	Activity Description
06:00	06:00	24.0	<p>MIRU CRAIG'S AIR RIG #2 ON 5/8/2010. DRILLED 12-1/4" HOLE TO 2590' GL (+ 16' = 2606' KB). ENCOUNTERED GILSONITE @ 810'. DRILLED WITH AIR AND FOAM TO 820' THEN PUMP DRILLED TO TD WITH PARTIAL LOSSES. RAN 61 JTS (2576.91') OF 9-5/8", 36.0#, J-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 8 CENTRALIZERS SPACED MIDDLE OF SHOE JOINT AND EVERY COLLAR TILL GONE. LANDED @ 2592.91' KB. RAN 200' OF 1" PIPE DOWN BACK SIDE. RDMO CRAIG'S AIR RIG #2.</p> <p>MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 3200 PSIG. PUMPED 160 BBLs FRESH WATER & 20 BBLs GELLED WATER FLUSH AHEAD OF CEMENT.</p> <p>LEAD: MIXED AND PUMPED 250 SACKS (183 BBLs) OF PREMIUM LEAD CEMENT WITH 0.3% VARSET, 2% CAL-SEAL, AND 2% ECONOLITE. MIXED LEAD CEMENT @ 10.5 PPG WITH YIELD OF 4.1 CF/SX.</p> <p>TAIL: MIXED AND PUMPED 300 SACKS (63 BBLs) OF PREMIUM CEMENT WITH 2% CACL2 MIXED TAIL CEMENT @ 15.6 PPG WITH YIELD OF 1.18 CF/SX. DISPLACED CEMENT WITH 196 BBLs FRESH WATER. BUMPED PLUG WITH 980# @ 20:24 PM ON 5/14/10. FLOAT HELD. SHUT-IN CASING VALVE. BROKE CIRCULATION 160 BBLs INTO FRESH WATER FLUSH. LOST CIRCULATION 170 BBLs INTO DISPLACEMENT. NO CEMENT TO SURFACE.</p> <p>TOP JOB #1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 100 SX (21 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. NO RETURNS. WAIT ON CEMENT 3 HR 0 MIN.</p> <p>TOP JOB # 2: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 100 SX (21 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. HOLE FILLED AND STOOD FULL.</p> <p>PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.</p> <p>CRAIG'S RIG #2 TOOK SURVEYS WHILE DRILLING HOLE @ 750' = 1.00 DEGREE, 840' = 2.00 DEGREE, 1050' = 1.50 DEGREE, 1260' = 0.50 DEGREE, 1440' = 0.00 DEGREE, 1650' = 1.00 DEGREE, 1950' = 1.00 DEGREE, 2250' = 2.50 DEGREE, AND 2590' = 2.25 DEGREE.</p>

KYLAN COOK NOTIFIED BLM VIA EMAIL OF THE SURFACE CASING & CEMENT JOB ON 5/11/10 @ 10:45 AM.

KYLAN COOK NOTIFIED CAROL DANIELS WITH UDOGM OF THE SURFACE CASING & CEMENT JOB VIA PHONE ON 5/11/10 @ 10:45 AM.

05-26-2010		Reported By		PAT CLARK							
Daily Costs: Drilling		\$115,982	Completion		\$0	Daily Total		\$115,982			
Cum Costs: Drilling		\$432,435	Completion		\$0	Well Total		\$432,435			
MD	2,606	TVD	2,606	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		
Activity at Report Time: DRILL OUT SHOE TRACK											
Start	End	Hrs	Activity Description								
06:00	00:00	18.0	MOVE RIG 8.4 MILES FROM CWU 1529-22. CRANE RELEASED @ 13:30, DERRICK IN AIR @ 14:00. TRUCKS RELEASED @ 14:30. RURT. TRANSFER 2 JTS 4 1/2", N-80, 11.6#, LTC CSG (42.50', 42.44') AND 2 MJ (20.32', 20.28') TRANSFER 1500 GALS DIESEL FUEL @ \$2.727/GAL.								
00:00	02:30	2.5	RIG ON DAYWORK @ 00:00, 5-26-2010, HSM. NIPPLE UP & TEST BOPE. TEST HIGH 5000 PSI, UPPER AND LOWER KELLY VALVE, SAFETY AND DART VALVE, PIPE AND BLIND RAMS, HCR, KILL LINE AND VALVE, CHOKE LINE, CHOKE VALVE, MANIFOLD. TEST HIGH 1500 PSI HIGH ANNULAR PREVENTER. TEST CASING TO 1500 PSI FOR 30 MINUTES. PERFORM ACCUMULATOR FUNCTION TEST. BLM NOTIFIED OF BOP TEST BY E-MAIL ON 5-23-2010 @ 15:30. NO BLM REPRESENTATIVE TO WITNESS TEST.								
02:30	05:00	2.5	HSM. R/U WEATHERFORD TRS. PICK UP BHA. TAG CEMENT @ 2550'. R/D TRS.								
05:00	05:30	0.5	PRE-SPUD CHECKLIST.								
05:30	06:00	0.5	DRILL CEMENT/FLOAT EQUIP. MORNING TOUR SHORT ONE MAN, NO ACCIDENTS. SAFETY MEETINGS - RURT, TEST BOP, P/U BHA. FUEL - 8868, DEL - 7600, USED - 232.								

05-27-2010		Reported By		PAT CLARK							
Daily Costs: Drilling		\$33,142	Completion		\$0	Daily Total		\$33,142			
Cum Costs: Drilling		\$465,578	Completion		\$0	Well Total		\$465,578			
MD	5,040	TVD	5,040	Progress	2,448	Days	1	MW	10.1	Visc	32.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		
Activity at Report Time: DRILLING @ 5040'											
Start	End	Hrs	Activity Description								
06:00	07:00	1.0	DRILL CEMENT AND FLOAT EQUIPMENT. FC @ 2550', GS @ 2592'. DRILL 10' TO 2602' - FIT TEST FOR 10.5 EMW.								
07:00	13:30	6.5	DRILL 2602' - 3367'. WOB 10K, RPM 65/73, SPP 2000 PSI, DP 350 PSI, ROP 118 FPH.								
13:30	14:00	0.5	RIG SERVICE. CHECK COM.								
14:00	15:30	1.5	DRILL 3367' - 3587'. SAME PARAMETERS, ROP 147 FPH.								
15:30	16:00	0.5	SURVEY @ 3500 - 2.8 DEG.								
16:00	23:00	7.0	DRILL 3587' - 4556'. SAME PARAMETERS, ROP 138 FPH.								

23:00 23:30 0.5 SURVEY @ 4500' - 2.67 DEG.
 23:30 06:00 6.5 DRILL 4556' - 5040'. WOB 18K, RPM 62/73, SPP 2200 PSI, DP 350 PSI, ROP 74 FPH.

MORNING TOUR SHORT ONE HAND, NO ACCIDENTS.
 SAFETY MEETINGS - CONNECTIONS, CHANGING TONG DIES.
 BOP DRILL BOTH TOURS.
 FUEL - 7300, USED - 1568.
 MW - 10.6 PPG, VIS - 36 SPQ.

06:00 SPUD 7 7/8" HOLE @ 07:00 HRS, 5/26/10.

05-28-2010	Reported By	PAT CLARK									
DailyCosts: Drilling	\$25,032	Completion	\$0	Daily Total	\$25,032						
Cum Costs: Drilling	\$490,610	Completion	\$0	Well Total	\$490,610						
MD	6,120	TVD	6,120	Progress	1,080	Days	2	MW	10.7	Visc	37.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 6120'											

Start	End	Hrs	Activity Description
06:00	09:00	3.0	DRILL 5040' - 5248'. WOB 10-20K, RPM 45-60/73, SPP 2200 PSI, DP 250 PSI, ROP 69 FPH.
09:00	09:30	0.5	RIG SERVICE. CHECK COM.
09:30	06:00	20.5	DRILL 5248' - 6120'. WOB 10-20K, RPM 45-65/73, SPP 2300 PSI, DP 300 PSI, ROP 43 FPH. FULL CREWS, NO ACCIDENTS, BOP DRILL DAYLIGHTS.
SAFETY MEETINGS - CHIPPING PAINT, BOP DRILLS. FUEL - 5736, USED - 1564. MW - 10.9 PPG, VIS - 38 SPQ. LOST 50% CIRCULATION @ 5800' - 200 BBLS.			

05-29-2010	Reported By	PAT CLARK									
DailyCosts: Drilling	\$26,767	Completion	\$0	Daily Total	\$26,767						
Cum Costs: Drilling	\$517,377	Completion	\$0	Well Total	\$517,377						
MD	6,860	TVD	6,860	Progress	740	Days	3	MW	11.0	Visc	38.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 6860'											

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 6120' - 6417'. WOB 15-20K, RPM 40-65/73, SPP 2350 PSI, DP 200 PSI, ROP 40 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	06:00	16.0	DRILL 6417' - 6860'. SAME PARAMETERS, ROP 28 FPH. FULL CREWS, NO ACCIDENTS. SAFETY MEETINGS - PAINTING, PRESSURE WASHER. FUEL - 3850, USED - 1886. MW - 11 PPG, VIS - 38 SPQ, LOST 85 BBLS.

05-30-2010	Reported By	PAT CLARK							
DailyCosts: Drilling	\$37,524	Completion	\$0	Daily Total	\$37,524				

Cum Costs: Drilling \$554,902 **Completion** \$0 **Well Total** \$554,902
MD 7,416 **TVD** 7,416 **Progress** 556 **Days** 4 **MW** 11.1 **Visc** 37.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7416'

Start	End	Hrs	Activity Description
06:00	11:00	5.0	DRILL 6860' - 6995'. WOB 10-22K, RPM 40-65/73, SPP 2400 PSI, DP 300 PSI, ROP 27 FPH.
11:00	11:30	0.5	CIRCULATE AND CONDITION FOR TRIP. MIX AND PUMP PILL, DROP SURVEY.
11:30	14:00	2.5	TOH. L/D REAMERS, X/O BIT. RETRIEVE SURVEY - 1/2 DEG.
14:00	16:00	2.0	TIH. FILL PIPE @ 4000'.
16:00	16:30	0.5	WASH AND REAM 6950' - 6995'.
16:30	03:30	11.0	DRILL 6995' - 7363'. WOB 10-20K, RPM 40-65/70, SPP 2300 PSI, DP 250 PSI, ROP 33 FPH.
03:30	04:00	0.5	EQUIPMENT REPAIR - FIX WATER LEAK ON DRUM BRAKES.
04:00	06:00	2.0	DRILL 7363' - 7416'. SAME PARAMETERS, ROP 27 FPH.

FULL CREWS, NO ACCIDENTS, BOP DRILL BOTH TOURS.
 SAFETY MEETINGS - HOUSEKEEPING, TRIPPING.
 FUEL - 6800, DEL - 4500, USED - 1550.
 MW - 11.3 PPG, VIS - 38 SPQ, LOST 84 BBLs.

05-31-2010 **Reported By** PAT CLARK

Daily Costs: Drilling \$42,127 **Completion** \$0 **Daily Total** \$42,127
Cum Costs: Drilling \$597,030 **Completion** \$0 **Well Total** \$597,030
MD 7,948 **TVD** 7,948 **Progress** 532 **Days** 5 **MW** 11.3 **Visc** 37.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7948'

Start	End	Hrs	Activity Description
06:00	09:30	3.5	DRILL 7416' - 7540'. WOB 10-23K, RPM 40-65/67, SPP 2300 PSI, DP 200 PSI, ROP 35 FPH.
09:30	10:00	0.5	RIG SERVICE. CHECK COM.
10:00	20:30	10.5	DRILL 7540' - 7833'. SAME PARAMETERS, ROP 28 FPH.
20:30	21:00	0.5	CIRCULATE AND CONDITION F/TOH. MIX AND PUMP PILL.
21:00	00:00	3.0	TOH. X/O MM AND BIT.
00:00	03:00	3.0	TIH. FILL PIPE @ 4000'.
03:00	03:30	0.5	WASH/REAM 7800' - 7833'.
03:30	06:00	2.5	DRILL 7833' - 7948'. WOB 10-15K, RPM 55/67, SPP 2350 PSI, DP 300 PSI, ROP 46 FPH.

FULL CREWS, NO ACCIDENTS.
 SAFETY MEETINGS - L/D TOOLS, TRIPPING.
 FUEL - 5287, USED - 1463.
 MW - 11.4 PPG, VIS - 38 SPQ, LOST 75 BBLs.

06-01-2010 **Reported By** PAT CLARK

Daily Costs: Drilling \$29,927 **Completion** \$0 **Daily Total** \$29,927
Cum Costs: Drilling \$626,832 **Completion** \$0 **Well Total** \$626,832
MD 8,952 **TVD** 8,952 **Progress** 1,004 **Days** 6 **MW** 11.3 **Visc** 38.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 8952'

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 7948' - 8261'. WOB 10 - 13K, RPM 40/67, SPP 2300 PSI, DP 300 PSI, ROP 42 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	06:00	16.0	DRILL 8261' - 8952'. SAME PARAMETERS, ROP 43 FPH.

FULL CREWS. NO ACCIDENTS, BOP DRILL DAYLIGHTS.
 SAFETY MEETINGS - FORKLIFT, CONNECTIONS.
 MW - 11.4 PPG, VIS - 38 SPQ, LOST 73 BBLs.
 FUEL - 3650, USED - 1637.

06-02-2010 **Reported By** PAT CLARK

Daily Costs: Drilling	\$43,442	Completion	\$0	Daily Total	\$43,442						
Cum Costs: Drilling	\$670,274	Completion	\$0	Well Total	\$670,274						
MD	9,770	TVD	9,770	Progress	818	Days	7	MW	11.4	Visc	38.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: PREP TO SHORT TRIP @ TD

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 8952' - 9269'. WOB 10-13K, RPM 40/67, SPP 2300 PSI, DP 250 PSI, ROP 42 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	05:00	15.0	DRILL 9269' - 9770'. WOB 10-15K, RPM 40/67, SPP 2300 PSI, DP 250 PSI, ROP 33 FPH. GAS KICK @ 9740', GAINED 80 BBLs, 20' FLARE. REACHED TD @ 05:00 HRS, 06/2/10.
05:00	06:00	1.0	CIRCULATE AND CONDITION FOR SHORT TRIP. BRING MW UP TO 11.5 PPG.

FULL CREWS, NO ACCIDENTS.
 SAFETY MEETINGS - DERRICKMAN'S RESPONSIBILITIES, CHANGE CLUTCH ON PUMP.
 FUEL - 4720, DEL - 2800, USED - 1730.

06-03-2010 **Reported By** PAT CLARK / MIKE WOOLSEY

Daily Costs: Drilling	\$131,404	Completion	\$103,480	Daily Total	\$234,885						
Cum Costs: Drilling	\$801,679	Completion	\$103,480	Well Total	\$905,160						
MD	9,770	TVD	9,770	Progress	0	Days	8	MW	11.4	Visc	40.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: RDRT/WO COMPLETION

Start	End	Hrs	Activity Description
06:00	07:00	1.0	CIRCULATE AND CONDITION - BRING MW UP TO 11.5 PPG.
07:00	08:00	1.0	SHORT TRIP F/ 9770' TO 7770', NO FILL.
08:00	09:00	1.0	CIRCULATE BTMS UP FOR LAYING DOWN PIPE.
09:00	15:00	6.0	HSM. R/U WEATHERFORD TRS. LDDP. BREAK KELLY, L/D BHA PULL WEAR BUSHING.
15:00	21:00	6.0	HSM W/ WEATHERFORD. RUN 4 1/2", 11.6#, N-80, LT&C CSG AS FOLLOWS: FLOAT SHOE @ 9758', 1 JT CSG, FLOAT COLLAR @ 9715', 54 JTS CSG, MJ @ 7436', 69 JTS CSG, MJ @ 4515', 107 JTS CSG (231 TOTAL). P/U JT # 232, TAG BOTTOM @ 9770'. L/D JT # 232. P/U MCH, LJ. INSTALL ROTATING RUBBER, LAND MCH FOR CEMENT. RAN TURBULIZERS ON BOTTOM THREE JOINTS, 25 BOW SPRING CENTRALIZERS ON EVERY THIRD JT TO 6469'. R/D TRS.

21:00 23:30 2.5 DROP THE BALL & CIRCULATE AND CONDITION F/CEMENT.
 23:30 02:30 3.0 HSM, R/U HALLIBURTON. PRESSURE TEST LINES TO 5000 PSI, CEMENT WELL AS FOLLOWS: PUMP 10 BBLS FRESH WATER, PUMP 20 BBLS MUD FLUSH, MIX AND PUMP 498 SX (163 BBLS, 893 CU/FT) LEAD HIGHBOND 75 CEMENT @ 12 PPG, 1.84 YLD, H2O 9.86 GAL/SK + 4% BENTONITE + .3% VERSASET. MIX AND PUMP 1382 SX (361 BBLS, 2029 CU/FT) TAIL EXTENDACEM CEMENT @ 13.5 PPG, 1.47 YLD, H2O 6.98 GAL/SK + .125 LBM POLY-E-FLAKE. WASH UP TO RIG TANK, DROP PLUG AND DISPLACE W/151 BBLS FRESH WATER. FULL RETURNS THROUGHOUT, NO CEMENT RETURN TO SURFACE. MAX PRESSURE 2500 PSI, BUMPED PLUG TO 4000 PSI. BLEED BACK 2.5 BBLS, FLOAT HELD. PRESSURE BACK UP TO 1000 PSI. LEAVE CEMENT HEAD SHUT IN FOR 2 HOURS. R/D HALLIBURTON. PLUG DOWN @ 0:200. R/D HALLIBURTON, CMT. BLM WAS NOTIFIED @ 16:30 ON 6-1-2010 NO REP WAS PRESENT.

02:30 04:30 2.0 CLEAN MUD TANKS.
 04:30 05:00 0.5 BLEED OFF CEMENT HEAD AND REMOVE. PACK OFF AND TEST HANGER TO 5000 PSI.
 05:00 06:00 1.0 RDRT. PREPARE TO MOVE .7 MILES TO CWU 1252-11 AT 07:00 ON 6-3-2010.

FULL CREWS, NO ACCIDENTS.

SAFETY MEETINGS - CEMENTING, BRIDAL UP.

TRANSFER 2 JTS 4 1/2", 11.6#, N-80, LTC CSG(42.78', 41.78', 41.90', THREADS OFF) 84.56' TOTAL AND 2 MJ 4 1/2", 11.6#, P-110, LTC (20.32, 10.14' THREADS OFF) 30.46' TOTAL TO CWU 1252-11.

06:00 RELEASE RIG @ 05:00 HRS, 6-3-2010.
 CASING POINT COST \$791,374

06-08-2010	Reported By	SEARLE									
DailyCosts: Drilling	\$0	Completion	\$18,500	Daily Total	\$18,500						
Cum Costs: Drilling	\$801,679	Completion	\$121,980	Well Total	\$923,660						
MD	9,770	TVD	9,770	Progress	0	Days	9	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: PREP FOR FRACS											
Start	End	Hrs	Activity Description								
06:00	06:00	24.0	MIRU CUTTERS WIRELINE. LOG WITH CBL/CCL/VDL/GR FROM 9687' TO 50'. EST CEMENT TOP @ 3230'. RDWL.								

06-24-2010	Reported By	MCCURDY									
DailyCosts: Drilling	\$0	Completion	\$1,793	Daily Total	\$1,793						
Cum Costs: Drilling	\$801,679	Completion	\$123,773	Well Total	\$925,453						
MD	9,770	TVD	9,770	Progress	0	Days	10	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: WO COMPLETION											
Start	End	Hrs	Activity Description								
06:00	06:00	24.0	NU 10M FRAC TREE. PRESSURE TESTED FRAC TREE & CASING TO 6500 PSIG. WO COMPLETION.								

06-30-2010	Reported By	HISLOP									
DailyCosts: Drilling	\$0	Completion	\$291,963	Daily Total	\$291,963						
Cum Costs: Drilling	\$801,679	Completion	\$415,737	Well Total	\$1,217,416						
MD	9,770	TVD	9,770	Progress	0	Days	11	MW	0.0	Visc	0.0
Formation :	MEASEVERDE	PBTD : 0.0			Perf :	7447- 9478'		PKR Depth : 0.0			
Activity at Report Time: PREP TO MIRUSU											

Start	End	Hrs	Activity Description
06:00	06:00	24.0	<p>STAGE #1: RU CUTTERS WIRELINE & PERFORATE LPR FROM 9200'-01', 9210'-11', 9232'-33', 9240'-41', 9250'-51', 9346'-47', 9354'-55', 9362'-63', 9388'-89', 9416'-17', 9430'-31', 9477'-78', 9488'-89', 9495'-96' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7725 GAL 16# LINEAR W/10700# 20/40 SAND @ 1-1.5 PPG, 50718 GAL 16# DELTA 200 W/172900# 20/40 SAND @ 2-5 PPG. MTP 6284 PSIG. MTR 50.6 BPM. ATP 4799 PSIG. ATR 48.4 BPM. ISIP 3234 PSIG. RD HALLIBURTON.</p> <p>STAGE #2: RUWL. SET 6K CFP AT 9145'. PERFORATE MPR/LPR FROM 8853'-54', 8867'-68', 8885'-86', 8893'-94', 8916'-17', 8949'-50', 8965'-66', 8984'-85', 9028'-29', 9034'-35', 9048'-49', 9059'-60', 9093'-94', 9120'-21' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7392 GAL 16# LINEAR W/1000# 20/40 SAND @ 1-1.5 PPG, 55937 GAL 16# DELTA 200 W/179700# 20/40 SAND @ 2-5 PPG. MTP 6056 PSIG. MTR 51.0 BPM. ATP 4994 PSIG. ATR 50.1 BPM. ISIP 3808 PSIG. RD HALLIBURTON.</p> <p>STAGE #3: RUWL. SET 6K CFP AT 8830'. PERFORATE MPR FROM 8552'-53', 8563'-64', 8602'-03', 8609'-10', 8614'-15', 8702'-03', 8728'-29', 8736'-37', 8747'-48', 8770'-71', 8795'-96', 8798'-99', 8804'-05', 8807'-08' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7448 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 37404 GAL 16# DELTA 200 W/124200# 20/40 SAND @ 2-4 PPG. MTP 6214 PSIG. MTR 50.7 BPM. ATP 5686 PSIG. ATR 47.8 BPM. ISIP 3626 PSIG. RD HALLIBURTON.</p> <p>STAGE #4: RUWL. SET 6K CFP AT 8530'. PERFORATE UPR/MPR FROM 8248'-49', 8256'-57', 8288'-89', 8298'-99', 8306'-07', 8323'-24', 8356'-57', 8372'-73', 8387'-88', 8397'-98', 8467'-68', 8472'-73', 8484'-85', 8510'-11' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7473 GAL 16# LINEAR W/9400# 20/40 SAND @ 1-1.5 PPG, 54908 GAL 16# DELTA 200 W/188700# 20/40 SAND @ 2-5 PPG. MTP 6130 PSIG. MTR 51.0 BPM. ATP 4466 PSIG. ATR 50.0 BPM. ISIP 2998 PSIG. RD HALLIBURTON.</p> <p>STAGE #5: RUWL. SET 6K CFP AT 8225'. PERFORATE UPR FROM 7969'-70', 7979'-80', 7986'-87', 7993'-94', 8030'-31', 8037'-38', 8043'-44', 8067'-68', 8076'-77', 8083'-84', 8092'-93', 8167'-68', 8172'-73', 8203'-04' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7458 GAL 16# LINEAR W/10000# 20/40 SAND @ 1-1.5 PPG, 32603 GAL 16# DELTA 200 W/110200# 20/40 SAND @ 2-5 PPG. MTP 4994 PSIG. MTR 51.2 BPM. ATP 4516 PSIG. ATR 50.1 BPM. ISIP 2620 PSIG. RD HALLIBURTON.</p> <p>STAGE #6: RUWL. SET 6K CFP AT 7930'. PERFORATE UPR FROM 7675'-76', 7692'-93', 7701'-02', 7729'-30', 7736'-37', 7752'-53', 7756'-57', 7766'-67', 7785'-86', 7805'-06', 7819'-20', 7852'-53', 7862'-63', 7903'-04' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7540 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 29665 GAL 16# DELTA 200 W/98900# 20/40 SAND @ 2-5 PPG. MTP 5896 PSIG. MTR 50.1 BPM. ATP 4715 PSIG. ATR 50.4 BPM. ISIP 3055 PSIG. RD HALLIBURTON.</p> <p>STAGE #7: RUWL. SET 6K CFP AT 7660'. PERFORATE UPR FROM 7447'-48', 7455'-56', 7480'-81', 7491'-92', 7548'-49', [SHOTS 7560'-61' MISSED FIRED], 7581'-82', 7590'-91', 7606'-07', 7613'-14', 7624'-25', 7631'-32', 7639'-40', 7647'-48' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7483 GAL 16# LINEAR W/9700# 20/40 SAND @ 1-1.5 PPG, 46386 GAL 16# DELTA 200 W/153000# 20/40 SAND @ 2-5 PPG. MTP 6468 PSIG. MTR 51.0 BPM. ATP 3912 PSIG. ATR 49.5 BPM. ISIP 2056 PSIG. RD HALLIBURTON.</p> <p>RUWL. SET 6K CBP AT 7370'. RD CUTTERS WIRELINE. SDFN.</p>

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0281
	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1253-11
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047503710000
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0852 FNL 2115 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 11 Township: 09.0S Range: 22.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/7/2010			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well was turned to sales on July 7, 2010. Please see the attached operations summary report for drilling and completion operations performed on the subject well.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 July 15, 2010

NAME (PLEASE PRINT) Michelle Robles	PHONE NUMBER 307 276-4842	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 7/8/2010	

WELL CHRONOLOGY REPORT

Report Generated On: 07-08-2010

Well Name	CWU 1253-11	Well Type	DEVG	Division	DENVER
Field	CHAPITA DEEP	API #	43-047-50371	Well Class	COMP
County, State	UINTAH, UT	Spud Date	05-26-2010	Class Date	
Tax Credit	N	TVD / MD	9,770/ 9,770	Property #	059229
Water Depth	0	Last CSG	2.375	Shoe TVD / MD	0/ 0
KB / GL Elev	4,792/ 4,779				
Location	Section 11, T9S, R22E, NWNE, 852 FNL & 2115 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	82.139

AFE No	304073	AFE Total	1,436,800	DHC / CWC	625,800/ 811,000
Rig Contr	TRUE	Rig Name	TRUE #31	Start Date	04-24-2009
04-24-2009	Reported By	SHEILA MALLOY			
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION DATA
			852' FNL & 2115' FEL (NW/NE)
			SECTION 11, T9S, R22E
			UINTAH COUNTY, UTAH
			LAT 40.055439, LONG 109.405281 (NAD83)
			LAT 40.055475, LONG 109.404597 (NAD27)
			TRUE #34
			OBJECTIVE: 9770' MD, MESAVERDE
			DW/GAS
			CHAPITA WELLS DEEP PROSPECT
			DD&A: NATURAL BUTTES
			NATURAL BUTTES FIELD
			LEASE: U-0281
			ELEVATION: 4779' NAT GL, 4779' PREP GL (DUE TO ROUNDING THE PREP GL IS 4779'), 4795' KB (16')
			EOG WI 100%, NRI 82.139316%

05-03-2010 Reported By TERRY CSERE

DailyCosts: Drilling \$75,000 **Completion** \$0 **Daily Total** \$75,000
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION STARTED, 5/3/10.

05-04-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 90% COMPLETE. BLADING TODAY.

05-05-2010 **Reported By** TERRY CSERE/KENT DEVENPORT

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION-SPUD NOTIFICATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE. STARTING BERMS & CLOSED LOOP. CRAIGS ROUSTABOUT SERVICE SPUD A 20" HOLE ON 5/5/10 @ 10:30 AM. SET +/-60' OF 14" CONDUCTOR. CEMENT TO SURFACE WITH READY MIX. CAROL DANIELS W/UDOGM WAS NOTIFIED BY PHONE MESSAGE AND BLM WAS NOTIFIED BY EMAIL OF SPUD ON 5/4/10 @ 10:43 AM.

05-06-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: WO AIR RIG

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE. STARTING FINAL BLADE.

05-07-2010 **Reported By** TERRY CSERE

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0
Cum Costs: Drilling \$75,000 **Completion** \$0 **Well Total** \$75,000
MD 0 **TVD** 0 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00 06:00 24.0 GEL CLOSED LOOP.

05-10-2010 **Reported By** TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$75,000	Completion	\$0	Well Total	\$75,000

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE, 5/10/10.

05-19-2010 **Reported By** KYLAN COOK

Daily Costs: Drilling	\$241,453	Completion	\$0	Daily Total	\$241,453
Cum Costs: Drilling	\$316,453	Completion	\$0	Well Total	\$316,453

MD	2,606	TVD	2,606	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: WORT

Start	End	Hrs	Activity Description
06:00	06:00	24.0	<p>MIRU CRAIG'S AIR RIG #2 ON 5/8/2010. DRILLED 12-1/4" HOLE TO 2590' GL (+ 16' = 2606' KB). ENCOUNTERED GILSONITE @ 810'. DRILLED WITH AIR AND FOAM TO 820' THEN PUMP DRILLED TO TD WITH PARTIAL LOSSES. RAN 61 JTS (2576.91') OF 9-5/8", 36.0#, J-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 8 CENTRALIZERS SPACED MIDDLE OF SHOE JOINT AND EVERY COLLAR TILL GONE. LANDED @ 2592.91' KB. RAN 200' OF 1" PIPE DOWN BACK SIDE. RDMO CRAIG'S AIR RIG #2.</p> <p>MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 3200 PSIG. PUMPED 160 BBLs FRESH WATER & 20 BBLs GELLED WATER FLUSH AHEAD OF CEMENT.</p> <p>LEAD: MIXED AND PUMPED 250 SACKS (183 BBLs) OF PREMIUM LEAD CEMENT WITH 0.3% VARSET, 2% CAL-SEAL, AND 2% ECONOLITE. MIXED LEAD CEMENT @ 10.5 PPG WITH YIELD OF 4.1 CF/SX.</p> <p>TAIL: MIXED AND PUMPED 300 SACKS (63 BBLs) OF PREMIUM CEMENT WITH 2% CACL2 MIXED TAIL CEMENT @ 15.6 PPG WITH YIELD OF 1.18 CF/SX. DISPLACED CEMENT WITH 196 BBLs FRESH WATER. BUMPED PLUG WITH 980# @ 20:24 PM ON 5/14/10. FLOAT HELD. SHUT-IN CASING VALVE. BROKE CIRCULATION 160 BBLs INTO FRESH WATER FLUSH. LOST CIRCULATION 170 BBLs INTO DISPLACEMENT. NO CEMENT TO SURFACE.</p> <p>TOP JOB #1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 100 SX (21 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. NO RETURNS. WAIT ON CEMENT 3 HR 0 MIN.</p> <p>TOP JOB # 2: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 100 SX (21 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. HOLE FILLED AND STOOD FULL.</p> <p>PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.</p> <p>CRAIG'S RIG #2 TOOK SURVEYS WHILE DRILLING HOLE @ 750' = 1.00 DEGREE, 840' = 2.00 DEGREE, 1050' = 1.50 DEGREE, 1260' = 0.50 DEGREE, 1440' = 0.00 DEGREE, 1650' = 1.00 DEGREE, 1950' = 1.00 DEGREE, 2250' = 2.50 DEGREE, AND 2590' = 2.25 DEGREE.</p>

KYLAN COOK NOTIFIED BLM VIA EMAIL OF THE SURFACE CASING & CEMENT JOB ON 5/11/10 @ 10:45 AM.

KYLAN COOK NOTIFIED CAROL DANIELS WITH UDOGM OF THE SURFACE CASING & CEMENT JOB VIA PHONE ON 5/11/10 @ 10:45 AM.

05-26-2010		Reported By		PAT CLARK							
Daily Costs: Drilling		\$115,982	Completion		\$0	Daily Total		\$115,982			
Cum Costs: Drilling		\$432,435	Completion		\$0	Well Total		\$432,435			
MD	2,606	TVD	2,606	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		
Activity at Report Time: DRILL OUT SHOE TRACK											
Start	End	Hrs	Activity Description								
06:00	00:00	18.0	MOVE RIG 8.4 MILES FROM CWU 1529-22. CRANE RELEASED @ 13:30, DERRICK IN AIR @ 14:00. TRUCKS RELEASED @ 14:30. RURT. TRANSFER 2 JTS 4 1/2", N-80, 11.6#, LTC CSG (42.50', 42.44') AND 2 MJ (20.32', 20.28') TRANSFER 1500 GALS DIESEL FUEL @ \$2.727/GAL.								
00:00	02:30	2.5	RIG ON DAYWORK @ 00:00, 5-26-2010, HSM. NIPPLE UP & TEST BOPE. TEST HIGH 5000 PSI, UPPER AND LOWER KELLY VALVE, SAFETY AND DART VALVE, PIPE AND BLIND RAMS, HCR, KILL LINE AND VALVE, CHOKE LINE, CHOKE VALVE, MANIFOLD. TEST HIGH 1500 PSI HIGH ANNULAR PREVENTER. TEST CASING TO 1500 PSI FOR 30 MINUTES. PERFORM ACCUMULATOR FUNCTION TEST. BLM NOTIFIED OF BOP TEST BY E-MAIL ON 5-23-2010 @ 15:30. NO BLM REPRESENTATIVE TO WITNESS TEST.								
02:30	05:00	2.5	HSM. R/U WEATHERFORD TRS. PICK UP BHA. TAG CEMENT @ 2550'. R/D TRS.								
05:00	05:30	0.5	PRE-SPUD CHECKLIST.								
05:30	06:00	0.5	DRILL CEMENT/FLOAT EQUIP. MORNING TOUR SHORT ONE MAN, NO ACCIDENTS. SAFETY MEETINGS - RURT, TEST BOP, P/U BHA. FUEL - 8868, DEL - 7600, USED - 232.								

05-27-2010		Reported By		PAT CLARK							
Daily Costs: Drilling		\$33,142	Completion		\$0	Daily Total		\$33,142			
Cum Costs: Drilling		\$465,578	Completion		\$0	Well Total		\$465,578			
MD	5,040	TVD	5,040	Progress	2,448	Days	1	MW	10.1	Visc	32.0
Formation :			PBTD : 0.0			Perf :			PKR Depth : 0.0		
Activity at Report Time: DRILLING @ 5040'											
Start	End	Hrs	Activity Description								
06:00	07:00	1.0	DRILL CEMENT AND FLOAT EQUIPMENT. FC @ 2550', GS @ 2592'. DRILL 10' TO 2602' - FIT TEST FOR 10.5 EMW.								
07:00	13:30	6.5	DRILL 2602' - 3367'. WOB 10K, RPM 65/73, SPP 2000 PSI, DP 350 PSI, ROP 118 FPH.								
13:30	14:00	0.5	RIG SERVICE. CHECK COM.								
14:00	15:30	1.5	DRILL 3367' - 3587'. SAME PARAMETERS, ROP 147 FPH.								
15:30	16:00	0.5	SURVEY @ 3500 - 2.8 DEG.								
16:00	23:00	7.0	DRILL 3587' - 4556'. SAME PARAMETERS, ROP 138 FPH.								

23:00 23:30 0.5 SURVEY @ 4500' - 2.67 DEG.
 23:30 06:00 6.5 DRILL 4556' - 5040'. WOB 18K, RPM 62/73, SPP 2200 PSI, DP 350 PSI, ROP 74 FPH.

MORNING TOUR SHORT ONE HAND, NO ACCIDENTS.
 SAFETY MEETINGS - CONNECTIONS, CHANGING TONG DIES.
 BOP DRILL BOTH TOURS.
 FUEL - 7300, USED - 1568.
 MW - 10.6 PPG, VIS - 36 SPQ.

06:00 SPUD 7 7/8" HOLE @ 07:00 HRS, 5/26/10.

05-28-2010	Reported By	PAT CLARK									
DailyCosts: Drilling	\$25,032	Completion	\$0	Daily Total	\$25,032						
Cum Costs: Drilling	\$490,610	Completion	\$0	Well Total	\$490,610						
MD	6,120	TVD	6,120	Progress	1,080	Days	2	MW	10.7	Visc	37.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 6120'											

Start	End	Hrs	Activity Description
06:00	09:00	3.0	DRILL 5040' - 5248'. WOB 10-20K, RPM 45-60/73, SPP 2200 PSI, DP 250 PSI, ROP 69 FPH.
09:00	09:30	0.5	RIG SERVICE. CHECK COM.
09:30	06:00	20.5	DRILL 5248' - 6120'. WOB 10-20K, RPM 45-65/73, SPP 2300 PSI, DP 300 PSI, ROP 43 FPH. FULL CREWS, NO ACCIDENTS, BOP DRILL DAYLIGHTS.
SAFETY MEETINGS - CHIPPING PAINT, BOP DRILLS. FUEL - 5736, USED - 1564. MW - 10.9 PPG, VIS - 38 SPQ. LOST 50% CIRCULATION @ 5800' - 200 BBLS.			

05-29-2010	Reported By	PAT CLARK									
DailyCosts: Drilling	\$26,767	Completion	\$0	Daily Total	\$26,767						
Cum Costs: Drilling	\$517,377	Completion	\$0	Well Total	\$517,377						
MD	6,860	TVD	6,860	Progress	740	Days	3	MW	11.0	Visc	38.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 6860'											

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 6120' - 6417'. WOB 15-20K, RPM 40-65/73, SPP 2350 PSI, DP 200 PSI, ROP 40 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	06:00	16.0	DRILL 6417' - 6860'. SAME PARAMETERS, ROP 28 FPH. FULL CREWS, NO ACCIDENTS. SAFETY MEETINGS - PAINTING, PRESSURE WASHER. FUEL - 3850, USED - 1886. MW - 11 PPG, VIS - 38 SPQ, LOST 85 BBLS.

05-30-2010	Reported By	PAT CLARK							
DailyCosts: Drilling	\$37,524	Completion	\$0	Daily Total	\$37,524				

Cum Costs: Drilling \$554,902 **Completion** \$0 **Well Total** \$554,902
MD 7,416 **TVD** 7,416 **Progress** 556 **Days** 4 **MW** 11.1 **Visc** 37.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7416'

Start	End	Hrs	Activity Description
06:00	11:00	5.0	DRILL 6860' - 6995'. WOB 10-22K, RPM 40-65/73, SPP 2400 PSI, DP 300 PSI, ROP 27 FPH.
11:00	11:30	0.5	CIRCULATE AND CONDITION FOR TRIP. MIX AND PUMP PILL, DROP SURVEY.
11:30	14:00	2.5	TOH. L/D REAMERS, X/O BIT. RETRIEVE SURVEY - 1/2 DEG.
14:00	16:00	2.0	TIH. FILL PIPE @ 4000'.
16:00	16:30	0.5	WASH AND REAM 6950' - 6995'.
16:30	03:30	11.0	DRILL 6995' - 7363'. WOB 10-20K, RPM 40-65/70, SPP 2300 PSI, DP 250 PSI, ROP 33 FPH.
03:30	04:00	0.5	EQUIPMENT REPAIR - FIX WATER LEAK ON DRUM BRAKES.
04:00	06:00	2.0	DRILL 7363' - 7416'. SAME PARAMETERS, ROP 27 FPH.

FULL CREWS, NO ACCIDENTS, BOP DRILL BOTH TOURS.
 SAFETY MEETINGS - HOUSEKEEPING, TRIPPING.
 FUEL - 6800, DEL - 4500, USED - 1550.
 MW - 11.3 PPG, VIS - 38 SPQ, LOST 84 BBLs.

05-31-2010 **Reported By** PAT CLARK

Daily Costs: Drilling \$42,127 **Completion** \$0 **Daily Total** \$42,127
Cum Costs: Drilling \$597,030 **Completion** \$0 **Well Total** \$597,030
MD 7,948 **TVD** 7,948 **Progress** 532 **Days** 5 **MW** 11.3 **Visc** 37.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7948'

Start	End	Hrs	Activity Description
06:00	09:30	3.5	DRILL 7416' - 7540'. WOB 10-23K, RPM 40-65/67, SPP 2300 PSI, DP 200 PSI, ROP 35 FPH.
09:30	10:00	0.5	RIG SERVICE. CHECK COM.
10:00	20:30	10.5	DRILL 7540' - 7833'. SAME PARAMETERS, ROP 28 FPH.
20:30	21:00	0.5	CIRCULATE AND CONDITION F/TOH. MIX AND PUMP PILL.
21:00	00:00	3.0	TOH. X/O MM AND BIT.
00:00	03:00	3.0	TIH. FILL PIPE @ 4000'.
03:00	03:30	0.5	WASH/REAM 7800' - 7833'.
03:30	06:00	2.5	DRILL 7833' - 7948'. WOB 10-15K, RPM 55/67, SPP 2350 PSI, DP 300 PSI, ROP 46 FPH.

FULL CREWS, NO ACCIDENTS.
 SAFETY MEETINGS - L/D TOOLS, TRIPPING.
 FUEL - 5287, USED - 1463.
 MW - 11.4 PPG, VIS - 38 SPQ, LOST 75 BBLs.

06-01-2010 **Reported By** PAT CLARK

Daily Costs: Drilling \$29,927 **Completion** \$0 **Daily Total** \$29,927
Cum Costs: Drilling \$626,832 **Completion** \$0 **Well Total** \$626,832
MD 8,952 **TVD** 8,952 **Progress** 1,004 **Days** 6 **MW** 11.3 **Visc** 38.0
Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 8952'

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 7948' - 8261'. WOB 10 - 13K, RPM 40/67, SPP 2300 PSI, DP 300 PSI, ROP 42 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	06:00	16.0	DRILL 8261' - 8952'. SAME PARAMETERS, ROP 43 FPH.

FULL CREWS. NO ACCIDENTS, BOP DRILL DAYLIGHTS.
 SAFETY MEETINGS - FORKLIFT, CONNECTIONS.
 MW - 11.4 PPG, VIS - 38 SPQ, LOST 73 BBLs.
 FUEL - 3650, USED - 1637.

06-02-2010 **Reported By** PAT CLARK

Daily Costs: Drilling	\$43,442	Completion	\$0	Daily Total	\$43,442						
Cum Costs: Drilling	\$670,274	Completion	\$0	Well Total	\$670,274						
MD	9,770	TVD	9,770	Progress	818	Days	7	MW	11.4	Visc	38.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: PREP TO SHORT TRIP @ TD

Start	End	Hrs	Activity Description
06:00	13:30	7.5	DRILL 8952' - 9269'. WOB 10-13K, RPM 40/67, SPP 2300 PSI, DP 250 PSI, ROP 42 FPH.
13:30	14:00	0.5	RIG SERVICE. CHECK COM.
14:00	05:00	15.0	DRILL 9269' - 9770'. WOB 10-15K, RPM 40/67, SPP 2300 PSI, DP 250 PSI, ROP 33 FPH. GAS KICK @ 9740', GAINED 80 BBLs, 20' FLARE. REACHED TD @ 05:00 HRS, 06/2/10.
05:00	06:00	1.0	CIRCULATE AND CONDITION FOR SHORT TRIP. BRING MW UP TO 11.5 PPG.

FULL CREWS, NO ACCIDENTS.
 SAFETY MEETINGS - DERRICKMAN'S RESPONSIBILITIES, CHANGE CLUTCH ON PUMP.
 FUEL - 4720, DEL - 2800, USED - 1730.

06-03-2010 **Reported By** PAT CLARK / MIKE WOOLSEY

Daily Costs: Drilling	\$131,404	Completion	\$103,480	Daily Total	\$234,885						
Cum Costs: Drilling	\$801,679	Completion	\$103,480	Well Total	\$905,160						
MD	9,770	TVD	9,770	Progress	0	Days	8	MW	11.4	Visc	40.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: RDRT/WO COMPLETION

Start	End	Hrs	Activity Description
06:00	07:00	1.0	CIRCULATE AND CONDITION - BRING MW UP TO 11.5 PPG.
07:00	08:00	1.0	SHORT TRIP F/ 9770' TO 7770', NO FILL.
08:00	09:00	1.0	CIRCULATE BTMS UP FOR LAYING DOWN PIPE.
09:00	15:00	6.0	HSM. R/U WEATHERFORD TRS. LDDP. BREAK KELLY, L/D BHA PULL WEAR BUSHING.
15:00	21:00	6.0	HSM W/ WEATHERFORD. RUN 4 1/2", 11.6#, N-80, LT&C CSG AS FOLLOWS: FLOAT SHOE @ 9758', 1 JT CSG, FLOAT COLLAR @ 9715', 54 JTS CSG, MJ @ 7436', 69 JTS CSG, MJ @ 4515', 107 JTS CSG (231 TOTAL). P/U JT # 232, TAG BOTTOM @ 9770'. L/D JT # 232. P/U MCH, LJ. INSTALL ROTATING RUBBER, LAND MCH FOR CEMENT. RAN TURBULIZERS ON BOTTOM THREE JOINTS, 25 BOW SPRING CENTRALIZERS ON EVERY THIRD JT TO 6469'. R/D TRS.

21:00 23:30 2.5 DROP THE BALL & CIRCULATE AND CONDITION F/CEMENT.
 23:30 02:30 3.0 HSM, R/U HALLIBURTON. PRESSURE TEST LINES TO 5000 PSI, CEMENT WELL AS FOLLOWS: PUMP 10 BBLS FRESH WATER, PUMP 20 BBLS MUD FLUSH, MIX AND PUMP 498 SX (163 BBLS, 893 CU/FT) LEAD HIGHBOND 75 CEMENT @ 12 PPG, 1.84 YLD, H2O 9.86 GAL/SK + 4% BENTONITE + .3% VERSASET. MIX AND PUMP 1382 SX (361 BBLS, 2029 CU/FT) TAIL EXTENDACEM CEMENT @ 13.5 PPG, 1.47 YLD, H2O 6.98 GAL/SK + .125 LBM POLY-E-FLAKE. WASH UP TO RIG TANK, DROP PLUG AND DISPLACE W/151 BBLS FRESH WATER. FULL RETURNS THROUGHOUT, NO CEMENT RETURN TO SURFACE. MAX PRESSURE 2500 PSI, BUMPED PLUG TO 4000 PSI. BLEED BACK 2.5 BBLS, FLOAT HELD. PRESSURE BACK UP TO 1000 PSI. LEAVE CEMENT HEAD SHUT IN FOR 2 HOURS. R/D HALLIBURTON. PLUG DOWN @ 0:200. R/D HALLIBURTON, CMT. BLM WAS NOTIFIED @ 16:30 ON 6-1-2010 NO REP WAS PRESENT.

02:30 04:30 2.0 CLEAN MUD TANKS.
 04:30 05:00 0.5 BLEED OFF CEMENT HEAD AND REMOVE. PACK OFF AND TEST HANGER TO 5000 PSI.
 05:00 06:00 1.0 RDRT. PREPARE TO MOVE .7 MILES TO CWU 1252-11 AT 07:00 ON 6-3-2010.

FULL CREWS, NO ACCIDENTS.

SAFETY MEETINGS - CEMENTING, BRIDAL UP.

TRANSFER 2 JTS 4 1/2", 11.6#, N-80, LTC CSG(42.78', 41.78', 41.90', THREADS OFF) 84.56' TOTAL AND 2 MJ 4 1/2", 11.6#, P-110, LTC (20.32, 10.14' THREADS OFF) 30.46' TOTAL TO CWU 1252-11.

06:00 RELEASE RIG @ 05:00 HRS, 6-3-2010.
 CASING POINT COST \$791,374

06-08-2010	Reported By	SEARLE									
DailyCosts: Drilling	\$0	Completion	\$18,500	Daily Total	\$18,500						
Cum Costs: Drilling	\$801,679	Completion	\$121,980	Well Total	\$923,660						
MD	9,770	TVD	9,770	Progress	0	Days	9	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: PREP FOR FRACS											
Start	End	Hrs	Activity Description								
06:00	06:00	24.0	MIRU CUTTERS WIRELINE. LOG WITH CBL/CCL/VDL/GR FROM 9687' TO 50'. EST CEMENT TOP @ 3230'. RDWL.								

06-24-2010	Reported By	MCCURDY									
DailyCosts: Drilling	\$0	Completion	\$1,793	Daily Total	\$1,793						
Cum Costs: Drilling	\$801,679	Completion	\$123,773	Well Total	\$925,453						
MD	9,770	TVD	9,770	Progress	0	Days	10	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: WO COMPLETION											
Start	End	Hrs	Activity Description								
06:00	06:00	24.0	NU 10M FRAC TREE. PRESSURE TESTED FRAC TREE & CASING TO 6500 PSIG. WO COMPLETION.								

06-30-2010	Reported By	HISLOP									
DailyCosts: Drilling	\$0	Completion	\$291,963	Daily Total	\$291,963						
Cum Costs: Drilling	\$801,679	Completion	\$415,737	Well Total	\$1,217,416						
MD	9,770	TVD	9,770	Progress	0	Days	11	MW	0.0	Visc	0.0
Formation :	MEASEVERDE	PBTD : 0.0			Perf :	7447- 9478'		PKR Depth : 0.0			
Activity at Report Time: PREP TO MIRUSU											

Start	End	Hrs	Activity Description
06:00	06:00	24.0	<p>STAGE #1: RU CUTTERS WIRELINE & PERFORATE LPR FROM 9200'-01', 9210'-11', 9232'-33', 9240'-41', 9250'-51', 9346'-47', 9354'-55', 9362'-63', 9388'-89', 9416'-17', 9430'-31', 9477'-78', 9488'-89', 9495'-96' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7725 GAL 16# LINEAR W/10700# 20/40 SAND @ 1-1.5 PPG, 50718 GAL 16# DELTA 200 W/172900# 20/40 SAND @ 2-5 PPG. MTP 6284 PSIG. MTR 50.6 BPM. ATP 4799 PSIG. ATR 48.4 BPM. ISIP 3234 PSIG. RD HALLIBURTON.</p> <p>STAGE #2: RUWL. SET 6K CFP AT 9145'. PERFORATE MPR/LPR FROM 8853'-54', 8867'-68', 8885'-86', 8893'-94', 8916'-17', 8949'-50', 8965'-66', 8984'-85', 9028'-29', 9034'-35', 9048'-49', 9059'-60', 9093'-94', 9120'-21' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7392 GAL 16# LINEAR W/1000# 20/40 SAND @ 1-1.5 PPG, 55937 GAL 16# DELTA 200 W/179700# 20/40 SAND @ 2-5 PPG. MTP 6056 PSIG. MTR 51.0 BPM. ATP 4994 PSIG. ATR 50.1 BPM. ISIP 3808 PSIG. RD HALLIBURTON.</p> <p>STAGE #3: RUWL. SET 6K CFP AT 8830'. PERFORATE MPR FROM 8552'-53', 8563'-64', 8602'-03', 8609'-10', 8614'-15', 8702'-03', 8728'-29', 8736'-37', 8747'-48', 8770'-71', 8795'-96', 8798'-99', 8804'-05', 8807'-08' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7448 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 37404 GAL 16# DELTA 200 W/124200# 20/40 SAND @ 2-4 PPG. MTP 6214 PSIG. MTR 50.7 BPM. ATP 5686 PSIG. ATR 47.8 BPM. ISIP 3626 PSIG. RD HALLIBURTON.</p> <p>STAGE #4: RUWL. SET 6K CFP AT 8530'. PERFORATE UPR/MPR FROM 8248'-49', 8256'-57', 8288'-89', 8298'-99', 8306'-07', 8323'-24', 8356'-57', 8372'-73', 8387'-88', 8397'-98', 8467'-68', 8472'-73', 8484'-85', 8510'-11' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7473 GAL 16# LINEAR W/9400# 20/40 SAND @ 1-1.5 PPG, 54908 GAL 16# DELTA 200 W/188700# 20/40 SAND @ 2-5 PPG. MTP 6130 PSIG. MTR 51.0 BPM. ATP 4466 PSIG. ATR 50.0 BPM. ISIP 2998 PSIG. RD HALLIBURTON.</p> <p>STAGE #5: RUWL. SET 6K CFP AT 8225'. PERFORATE UPR FROM 7969'-70', 7979'-80', 7986'-87', 7993'-94', 8030'-31', 8037'-38', 8043'-44', 8067'-68', 8076'-77', 8083'-84', 8092'-93', 8167'-68', 8172'-73', 8203'-04' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7458 GAL 16# LINEAR W/10000# 20/40 SAND @ 1-1.5 PPG, 32603 GAL 16# DELTA 200 W/110200# 20/40 SAND @ 2-5 PPG. MTP 4994 PSIG. MTR 51.2 BPM. ATP 4516 PSIG. ATR 50.1 BPM. ISIP 2620 PSIG. RD HALLIBURTON.</p> <p>STAGE #6: RUWL. SET 6K CFP AT 7930'. PERFORATE UPR FROM 7675'-76', 7692'-93', 7701'-02', 7729'-30', 7736'-37', 7752'-53', 7756'-57', 7766'-67', 7785'-86', 7805'-06', 7819'-20', 7852'-53', 7862'-63', 7903'-04' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7540 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 29665 GAL 16# DELTA 200 W/98900# 20/40 SAND @ 2-5 PPG. MTP 5896 PSIG. MTR 50.1 BPM. ATP 4715 PSIG. ATR 50.4 BPM. ISIP 3055 PSIG. RD HALLIBURTON.</p> <p>STAGE #7: RUWL. SET 6K CFP AT 7660'. PERFORATE UPR FROM 7447'-48', 7455'-56', 7480'-81', 7491'-92', 7548'-49', [SHOTS 7560'-61' MISSED FIRED], 7581'-82', 7590'-91', 7606'-07', 7613'-14', 7624'-25', 7631'-32', 7639'-40', 7647'-48' @ 2 SPF & 180 DEGREE PHASING. RDWL. RU HALLIBURTON, FRAC DOWN CASING W/55 GAL (BIO 500), 165 GAL (WSI 7360), 7483 GAL 16# LINEAR W/9700# 20/40 SAND @ 1-1.5 PPG, 46386 GAL 16# DELTA 200 W/153000# 20/40 SAND @ 2-5 PPG. MTP 6468 PSIG. MTR 51.0 BPM. ATP 3912 PSIG. ATR 49.5 BPM. ISIP 2056 PSIG. RD HALLIBURTON.</p>

RUWL. SET 6K CBP AT 7370'. RD CUTTERS WIRELINE. SDFN.

07-03-2010		Reported By	HISLOP	
DailyCosts: Drilling	\$0	Completion	\$19,778	Daily Total \$19,778
Cum Costs: Drilling	\$801,679	Completion	\$435,515	Well Total \$1,237,194
MD	9,770	TVD	9,770	Progress 0 Days 12 MW 0.0 Visc 0.0

Formation : MEASEVERDE **PBTD : 0.0** Perf : 7447- 9478' **PKR Depth : 0.0**

Activity at Report Time: DRILL PLUGS

Start	End	Hrs	Activity Description
06:00	06:00	24.0	SICP 0 PSIG. MIRUSU. ND FRAC TREE & NU BOP. RIH W/BIT & PUMP OFF SUB TO 7370'. RU TO DRILL OUT PLUGS. SDFN.

07-07-2010 Reported By HISLOP

Daily Costs: Drilling	\$0	Completion	\$58,626	Daily Total	\$58,626
Cum Costs: Drilling	\$801,679	Completion	\$494,141	Well Total	\$1,295,820

MD 9,770 TVD 9,770 Progress 0 Days 13 MW 0.0 Visc 0.0

Formation : MEASEVERDE **PBTD : 0.0** Perf : 7447- 9478' **PKR Depth : 0.0**

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	SICP 0 PSIG. CLEANED OUT & DRILLED OUT PLUGS @ 7370', 7660', 7930', 8225', 8530', 8830', & 9145'. CLEANED OUT TO 9604'. LANDED TUBING @ 8224' KB. ND BOP & NU TREE. PUMPED OFF BIT & SUB. RDMOSU.

FLOWED 14 HRS. 24/64" CHOKE. FTP 1400 PSIG. CP 2150 PSIG. 64 BFPH. RECOVERED 898 BLW. 8502 BLWTR.

TUBING DETAIL LENGTH

- PUMP OFF BIT SUB .91'
- 1 JT 2-3/8" 4.7# N-80 TBG 31.40'
- XN NIPPLE 1.30'
- 260 JTS 2-3/8" 4.7# N-80 TBG 8174.11'
- BELOW KB 16.00'
- LANDED @ 8223.72' KB

07-08-2010 Reported By HISLOP/DUANE COOK

Daily Costs: Drilling	\$0	Completion	\$2,835	Daily Total	\$2,835
Cum Costs: Drilling	\$801,679	Completion	\$496,976	Well Total	\$1,298,655

MD 9,770 TVD 9,770 Progress 0 Days 14 MW 0.0 Visc 0.0

Formation : MEASEVERDE **PBTD : 9713.0** Perf : 7447- 9478' **PKR Depth : 0.0**

Activity at Report Time: FLOW TEST TO SALES

Start	End	Hrs	Activity Description
06:00	06:00	24.0	INITIAL PRODUCTION. OPENING PRESSURE: TP 1350 PSIG & CP 2300 PSIG. TURNED WELL OVER TO QUESTAR SALES AT 10:30 AM, 7/7/10. FLOWED 1200 MCFD RATE ON 24/64" POS CHOKE. STATIC 211. QUESTAR METER #008500.

FLOWED THROUGH TEST UNIT TO SALES 24 HRS. 24/64" CHOKE. FTP 1300 PSIG. CP 2450 PSIG. 56 BFPH. RECOVERED 1321 BLW. 7181 BLWTR. 1117 MCFD RATE.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU0281

1a. Type of Well Oil Well Gas Well Dry Other
 b. Type of Completion New Well Work Over Deepen Plug Back Diff. Resvr.
 Other _____

2. Name of Operator: EOG RESOURCES, INC. Contact: MICHELLE E ROBLES
 E-Mail: MICHELLE_ROBLES@EOGRESOURCES.COM

3. Address: 1060 EAST HIGHWAY 40 VERNAL, UT 84078
 3a. Phone No. (include area code) Ph: 307-276-4842

4. Location of Well (Report location clearly and in accordance with Federal requirements)*
 At surface NWNE 852FNL 2115FEL 40.05544 N Lat, 109.40528 W Lon
 At top prod interval reported below NWNE 852FNL 2115FEL 40.05544 N Lat, 109.40528 W Lon
 At total depth NWNE 852FNL 2115FEL 40.05544 N Lat, 109.40528 W Lon

14. Date Spudded: 05/05/2010
 15. Date T.D. Reached: 06/02/2010
 16. Date Completed: D & A Ready to Prod. 07/07/2010

6. If Indian, Allottee or Tribe Name
 7. Unit or CA Agreement Name and No. CHAPITA WELLS
 8. Lease Name and Well No. CHAPITA WELLS UNIT 1253-11
 9. API Well No. 43-047-50371
 10. Field and Pool, or Exploratory NATURAL BUTTES
 11. Sec., T., R., M., or Block and Survey or Area Sec 11 T9S R22E Mer SLB
 12. County or Parish UINTAH
 13. State UT
 17. Elevations (DF, KB, RT, GL)* 4779 GL

18. Total Depth: MD 9770 TVD
 19. Plug Back T.D.: MD 9713 TVD
 20. Depth Bridge Plug Set: MD TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
 EBL/CCL/VDL/GR

22. Was well cored? No Yes (Submit analysis)
 Was DST run? No Yes (Submit analysis)
 Directional Survey? No Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12.250	9.625 J55	36.0	0	2593		750		0	
7.875	4.500 N-80	11.6	0	9758		1880		3230	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375		8224						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	7447	9496	9200 TO 9496		2	
B)			8853 TO 9121		2	
C)			8552 TO 8808		2	
D)			8248 TO 8511		2	

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
9200 TO 9496	58,663 GALS GELLED WATER AND 183,600# 20/40 SAND
8853 TO 9121	63,549 GALS GELLED WATER AND 180,700# 20/40 SAND
8552 TO 8808	45,072 GALS GELLED WATER AND 133,800# 20/40 SAND
8248 TO 8511	62,601 GALS GELLED WATER AND 198,100# 20/40 SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
07/07/2010	07/16/2010	24	→	75.0	1048.0	275.0			FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
24/64	SI 650	1200.0	→	75	1048	275		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
	SI		→						

(See Instructions and spaces for additional data on reverse side)
 ELECTRONIC SUBMISSION #90977 VERIFIED BY THE BLM WELL INFORMATION SYSTEM
**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

RECEIVED
 AUG 09 2010
 DIV. OF OIL, GAS & MINING

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: EOG RESOURCES INC

Well Name: CWU 1253-11

Api No: 43-047-50371 Lease Type: FEDERAL

Section 11 Township 09S Range 22E County UINTAH

Drilling Contractor CRAIG'S ROUSTABOUT SERV RIG # BUCKET

SPUDDED:

Date 05/05/2010

Time 10:30 AM

How DRY

Drilling will Commence: _____

Reported by KENT DAVENPORT

Telephone # (435) 828- 8200

Date 05/05/2010 Signed CHD

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APR 24 2009

APPLICATION FOR PERMIT TO DRILL OR REENTER

BLM

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU0281
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator EOG RESOURCES INC		7. If Unit or CA Agreement, Name and No. UTU63013BF
Contact: MARY A. MAESTAS E-Mail: mary_maestas@eogresources.com		8. Lease Name and Well No. CWU 1253-11
3a. Address 1060 EAST HIGHWAY 40 VERNAL, UT 84078	3b. Phone No. (include area code) Ph: 303-824-5526	9. API Well No. 43 047 50371
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWNE 852FNL 2115FEL 40.05544 N Lat, 109.40528 W Lon At proposed prod. zone NWNE 852FNL 2115FEL 40.05544 N Lat, 109.40528 W Lon		10. Field and Pool, or Exploratory NATURAL BUTTES
11. Sec., T., R., M., or Blk. and Survey or Area Sec 11 T9S R22E Mer SLB SME: BLM		12. County or Parish UINTAH
13. State UT		14. Distance in miles and direction from nearest town or post office* 47.3 MILES SOUTH OF VERNAL, UT
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 852'	16. No. of Acres in Lease 2557.84	17. Spacing Unit dedicated to this well
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1310'	19. Proposed Depth 9770 MD	20. BLM/BIA Bond No. on file NM2308
21. Elevations (Show whether DF, KB, RT, GL, etc.) 4779 GL	22. Approximate date work will start	23. Estimated duration 45 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature (Electronic Submission)	Name (Printed/Typed) MARY A. MAESTAS Ph: 303-824-5526	Date 04/24/2009
--	--	--------------------

Title
REGULATORY ASSISTANT

Approved by (Signature) <i>Mary Maestas</i>	Name (Printed/Typed) Mary Maestas	Date 7/29/2009
--	--------------------------------------	-------------------

Title
Assistant Field Manager
Lands & Mineral Resources

Office
VERNAL FIELD OFFICE

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

NOTICE OF APPROVAL

Electronic Submission #69342 verified by the BLM Well Information System
For EOG RESOURCES INC, sent to the Vernal
Committed to AFMSS for processing by GAIL JENKINS on 04/24/2009 (09GXJ4110AE)

RECEIVED

AUG 03 2009

DIV. OF OIL, GAS & MINING

** BLM REVISED **



098273181AE N03-03-04-2009



**UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE**

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: EOG Resources, Inc.
Well No: CWU 1253-11
API No: 43-047-50371

Location: NWNE, Sec. 11, T9S, R22E
Lease No: UTU-0281
Agreement: Chapita Wells Unit

Title	Name	Office Phone Number	Cell Phone Number
Petroleum Engineer:	Matt Baker	(435) 781-4490	(435) 828-4470
Petroleum Engineer:	Michael Lee	(435) 781-4432	(435) 828-7875
Petroleum Engineer:	Ryan Angus	(435) 781-4430	(435) 828-7368
Supervisory Petroleum Technician:	Jamie Sparger	(435) 781-4502	(435) 828-3913
Supervisory NRS:	Karl Wright	(435) 781-4484	
NRS/Enviro Scientist:	Christine Cimiluca	(435) 781-4475	
NRS/Enviro Scientist:	Dan Emmett	(435) 781-3414	(435) 828-4029
NRS/Enviro Scientist:	Anna Figueroa	(435) 781-3407	(435) 828-3548
NRS/Enviro Scientist:	Lori Ford	(435) 781-4406	
NRS/Enviro Scientist:	David Gordon	(435) 781-4424	
NRS/Enviro Scientist:	James Hereford	(435) 781-3412	(435) 828-3546
NRS/Enviro Scientist:	Chuck Macdonald	(435) 781-4441	(435) 828-7481
NRS/Enviro Scientist:	Nathan Packer	(435) 781-3405	(435) 828-3545
NRS/Enviro Scientist:	Paul Percival	(435) 781-4493	(435) 828-7381
NRS/Enviro Scientist:	Verlyn Pindell	(435) 781-3402	(435) 828-3547
NRS/Enviro Scientist:	Holly Villa	(435) 781-4404	(435) 828-3544

Fax: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.
- Prevent fill and stock piles from entering drainages.
- The access road shall be crowned and ditched. Flat-bladed roads are not allowed.
- The authorized officer may prohibit surface disturbing activities during severe winter, wet, or muddy conditions to minimize watershed damage. This limitation does not apply to operation and maintenance of producing wells.
- If additional erosion occurs during the life of this project, more culverts, low water crossings, berms, wing ditches, or gravel (from a private or commercial source) etc. shall be needed to control the erosion. Low-water crossings and culverts shall be appropriately constructed to avoid sedimentation of drainage ways and other water resources.
- Bury pipelines at all low water crossings.
- Surface pipelines will be placed 5-10 feet outside of the borrow area.
- Surface pipelines will be placed in such a way that they will not wander into the borrow area.
- Pipelines will be buried at all major road and drainage crossings
- The pit liner is to be cut 5 feet below ground surface or at the level of the cuttings, whichever is deeper, and the excess liner material is to be disposed of at an authorized disposal site.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- The production casing cement shall extend a minimum of 200 feet above the surface casing shoe.
- A formation integrity test shall be performed at the surface casing shoe.
- Gamma Ray Log shall be run from Total Depth to Surface.

Variances Granted

Air Drilling

- Dust suppression equipment. Variance granted for water mist system to substitute for the dust suppression equipment.
- Blooie line discharge 100' from the well bore, variance granted for blooie line discharge to be 75' from the well bore.
- Compressors located in the opposite direction from the blooie line a minimum of 100' from the well bore. Variance granted for truck/trailer mounted air compressors.
- Straight run blooie line. Variance granted for targeted "T's" at bends.
- Automatic igniter. Variance granted for igniter due to water mist.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil &

Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.

- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or

data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.