

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3


AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER NBU 921-30D3DS	
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT NATURAL BUTTES	
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME NATURAL BUTTES	
6. NAME OF OPERATOR KERR-MCGEE OIL & GAS ONSHORE, L.P.						7. OPERATOR PHONE 720 929-6587	
8. ADDRESS OF OPERATOR P.O. Box 173779, Denver, CO, 80217						9. OPERATOR E-MAIL mary.mondragon@anadarko.com	
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU 0581			11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>	
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')	
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')	
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>	
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN	
LOCATION AT SURFACE	759 FNL 887 FWL	NWNW	30	9.0 S	21.0 E	S	
Top of Uppermost Producing Zone	1152 FNL 665 FWL	NWNW	30	9.0 S	21.0 E	S	
At Total Depth	1152 FNL 665 FWL	NWNW	30	9.0 S	21.0 E	S	
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 665			23. NUMBER OF ACRES IN DRILLING UNIT 2400	
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 450			26. PROPOSED DEPTH MD: 10331 TVD: 10290	
27. ELEVATION - GROUND LEVEL 4847			28. BOND NUMBER WYB000291			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Permit #43-8496	
ATTACHMENTS							
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES							
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER				<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN			
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)				<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER			
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)				<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP			
NAME Danielle Piernot			TITLE Regulatory Analyst			PHONE 720 929-6156	
SIGNATURE			DATE 08/14/2009			EMAIL danielle.piernot@anadarko.com	
API NUMBER ASSIGNED 43047506480000			APPROVAL  Permit Manager				

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	10331		
Pipe	Grade	Length	Weight			
	Grade HCP-110 LT&C	640	11.6			
	Grade I-80 Buttress	9691	11.6			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	9.625	0	2580		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	2580	36.0			


T9S, R21E, S.L.B.&M.



NOTES:


- ▲ = Section Corners Located
- 1. Well footages are measured at right angles to the Section Lines.
- 2. G.L.O. distances are shown in feet or chains. 1 chain = 66 feet.
- 3. The Bottom of hole bears S28°55'13"W 451.15' from the Surface Position.
- 4. Bearings are based on Global Positioning Satellite observations.
- 5. Basis of elevation is the Northwest Corner of Section 12, T9S, R20E, S.L.B.&M. The elevation of this Section Corner is shown on the Ouray SE 7.5 Min. Quadrangle as being 4676'.

Kerr-McGee
Oil & Gas Onshore, LP
 1099 18th Street - Denver, Colorado 80202



SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF AGRICULTURAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



REGISTERED LAND SURVEYOR
 REGISTRATION NO. 362251
 STATE OF UTAH

NBU 921-30D3DS
WELL PLAT
 1152' FNL, 665' FWL (Bottom Hole)
 LOT 1 OF SECTION 30, T9S, R21E,
 S.L.B.&M. UTAH COUNTY, UTAH.




CONSULTING, LLC
 371 Coffeen Avenue
 Sheridan WY 82801
 Phone 307-674-0609
 Fax 307-674-0182

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
 209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 12-11-08	SURVEYED BY: M.S.B.	SHEET 2 OF 13
DATE DRAWN: 01-20-09	DRAWN BY: E.M.S.	
SCALE: 1" = 1000'	Date Last Revised: 04-17-09	



Well Name: P_NBU 921-30D3DS
 Surface Location: UINTAH_NBU 921-30D PAD
 NAD 1927 (NADCON CONUS) Universal Transverse Mercator (US Survey Feet)
 UTAH - UTM (feet), NAD27, Zone 12N
 Ground Elevation: 4847.0
 Northing 14533537.27 Easting 2032058.25 Latitude 40.012136°N Longitude 109.601348°W



SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0
2	2550.0	0.00	0.00	2550.0	0.0	0.0	0.00	0.00	0.0
3	3125.0	11.50	208.95	3121.1	-50.3	-27.8	2.00	208.95	57.5
4	4712.8	11.50	208.95	4677.0	-327.3	-181.1	0.00	0.00	374.1
5	5479.4	0.00	0.00	5438.6	-394.4	-218.2	1.50	180.00	450.7
6	10330.9	0.00	0.00	10290.0	-394.4	-218.2	0.00	0.00	450.7



Azimuths to True North
 Magnetic North: 11.37°

Magnetic Field
 Strength: 52559.4snT
 Dip Angle: 65.92°
 Date: 5/6/2009
 Model: IGRF200510

ROCKIES - PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

UINTAH_NBU 921-30D PAD

P_NBU 921-30D3DS

P_NBU 921-30D3DS

Plan: Plan #1 05-06-09 ZJRA6

Standard Planning Report - Geographic

06 May, 2009

APC Planning Report - Geographic

Database: apc_edmp	Local Co-ordinate Reference: Well P_NBU 921-30D3DS
Company: ROCKIES - PLANNING	TVD Reference: WELL @ 4847.0ft (Original Well Elev)
Project: UTAH - UTM (feet), NAD27, Zone 12N	MD Reference: WELL @ 4847.0ft (Original Well Elev)
Site: UINTAH_NBU 921-30D PAD	North Reference: True
Well: P_NBU 921-30D3DS	Survey Calculation Method: Minimum Curvature
Wellbore: P_NBU 921-30D3DS	
Design: Plan #1 05-06-09 ZJRA6	

Project UTAH - UTM (feet), NAD27, Zone 12N	
Map System: Universal Transverse Mercator (US Survey Fee	System Datum: Mean Sea Level
Geo Datum: NAD 1927 (NADCON CONUS)	
Map Zone: Zone 12N (114 W to 108 W)	

Site UINTAH_NBU 921-30D PAD		
Site Position:	Northing: 14,533,548.66ft	Latitude: 40.012168°N
From: Lat/Long	Easting: 2,032,041.55ft	Longitude: 109.601407°W
Position Uncertainty: 0.0 ft	Slot Radius: "	Grid Convergence: 0.90 °

Well P_NBU 921-30D3DS			
Well Position	+N/-S 0.0 ft	Northing: 14,533,537.27 ft	Latitude: 40.012136°N
	+E/-W 0.0 ft	Easting: 2,032,058.25 ft	Longitude: 109.601348°W
Position Uncertainty	0.0 ft	Wellhead Elevation: ft	Ground Level: 4,847.0 ft

Wellbore P_NBU 921-30D3DS					
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	5/6/2009	11.37	65.92	52,559

Design Plan #1 05-06-09 ZJRA6				
Audit Notes:				
Version:	Phase: PLAN	Tie On Depth: 0.0		
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	10,290.0	0.0	0.0	208.95

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,550.0	0.00	0.00	2,550.0	0.0	0.0	0.00	0.00	0.00	0.00	
3,125.0	11.50	208.95	3,121.1	-50.3	-27.8	2.00	2.00	0.00	208.95	
4,712.8	11.50	208.95	4,677.0	-327.3	-181.1	0.00	0.00	0.00	0.00	
5,479.4	0.00	0.00	5,438.6	-394.4	-218.2	1.50	-1.50	0.00	180.00	
10,330.9	0.00	0.00	10,290.0	-394.4	-218.2	0.00	0.00	0.00	0.00	PBHL_NBU 921-30

APC

Planning Report - Geographic

Database:	apc_edmp	Local Co-ordinate Reference:	Well P_NBU 921-30D3DS
Company:	ROCKIES - PLANNING	TVD Reference:	WELL @ 4847.0ft (Original Well Elev)
Project:	UTAH - UTM (feet), NAD27, Zone 12N	MD Reference:	WELL @ 4847.0ft (Original Well Elev)
Site:	UINTAH_NBU 921-30D PAD	North Reference:	True
Well:	P_NBU 921-30D3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	P_NBU 921-30D3DS		
Design:	Plan #1 05-06-09 ZJRA6		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude	
0.0	0.00	0.00	0.0	0.0	0.0	14,533,537.27	2,032,058.25	40.012136°N	109.601348°W	
1,625.0	0.00	0.00	1,625.0	0.0	0.0	14,533,537.27	2,032,058.25	40.012136°N	109.601348°W	
Green River										
2,400.0	0.00	0.00	2,400.0	0.0	0.0	14,533,537.27	2,032,058.25	40.012136°N	109.601348°W	
Surface Casing										
2,550.0	0.00	0.00	2,550.0	0.0	0.0	14,533,537.27	2,032,058.25	40.012136°N	109.601348°W	
3,125.0	11.50	208.95	3,121.1	-50.3	-27.8	14,533,486.51	2,032,031.21	40.011998°N	109.601447°W	
4,712.8	11.50	208.95	4,677.0	-327.3	-181.1	14,533,207.14	2,031,882.36	40.011237°N	109.601994°W	
4,998.6	7.21	208.95	4,959.0	-368.0	-203.5	14,533,166.14	2,031,860.51	40.011126°N	109.602075°W	
Wasatch										
5,479.4	0.00	0.00	5,438.6	-394.4	-218.2	14,533,139.47	2,031,846.30	40.011053°N	109.602127°W	
8,105.9	0.00	0.00	8,065.0	-394.4	-218.2	14,533,139.47	2,031,846.30	40.011053°N	109.602127°W	
Mesaverde										
10,330.9	0.00	0.00	10,290.0	-394.4	-218.2	14,533,139.47	2,031,846.30	40.011053°N	109.602127°W	

Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude	
PBHL_NBU 921-30D3DS - hit/miss target - Shape - Point	0.00	0.00	10,290.0	-394.4	-218.2	14,533,139.47	2,031,846.30	40.011053°N	109.602127°W	

Casing Points						
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")		
2,400.0	2,400.0	Surface Casing	9-5/8	12-1/4		

Formations						
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
1,625.0	1,625.0	Green River		0.00		
8,105.9	8,065.0	Mesaverde		0.00		
4,998.6	4,959.0	Wasatch		0.00		

NBU 921-30D3DS

Pad: NBU 921-30D

Surface: 759' FNL 887' FWL (NW/4NW/4) Lot 1

BHL: 1,152' FNL 665' FWL (NW/4NW/4) Lot 1

Sec. 30 T9S R21E

Uintah, Utah

Mineral Lease: UTU 0581

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. – 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 – Surface	
Green River	1,625'	
Birds Nest	1,864'	Water
Mahogany	2,376'	Water
Wasatch	4,959'	Gas
Mesaverde	8,065'	Gas
MVU2	8,978'	Gas
MVL1	9,449'	Gas
TVD	10,290'	
TD	10,331'	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program.

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program.

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program.

6. **Evaluation Program:**

Please refer to the attached Drilling Program.

7. Abnormal Conditions:

Maximum anticipated bottomhole pressure calculated at 10,290' TD, approximately equals 6,436 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 4,147 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12-1/4 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 12-1/4 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 9-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). The air rig operation utilizes a 5M BOPE when drilling. This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

10. Other Information:

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP
DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3,520	2,020	453,000
SURFACE	9-5/8"	0 to 2,580	36.00	J-55	LTC	0.82	1.67	6.21
PRODUCTION	4-1/2"	0 to 9,691	11.60	I-80	BTC	7,780	6,350	278,000
	4-1/2"	9,691 to 10,331	11.60	HCP-110	LTC	1.82	1.08	2.85
						10,690	8,650	279,000
						75.92	1.33	46.19

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)
 (Burst Assumptions: TD = 12.2 ppg) 0.22 psi/ft = gradient for partially evac wellbore
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)
MASP 4,147 psi

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD
 (Burst Assumptions: TD = 12.2 ppg) 0.62 psi/ft = bottomhole gradient
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)
MABHP 6,436 psi

CEMENT PROGRAM

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD 500'	Premium cmt + 2% CaCl + 0.25 pps flocele	215	60%	15.60	1.18
	TOP OUT CMT (6 jobs) 1,200'	20 gals sodium silicate + Premium cmt + 2% CaCl + 0.25 pps flocele Premium cmt + 2% CaCl	380	0%	15.60	1.18
NOTE: If well will circulate water to surface, option 2 will be utilized						
SURFACE Option 2	LEAD 2,080'	65/35 Poz + 6% Gel + 10 pps gilsonite + 0.25 pps Flocele + 3% salt BWOW	490	35%	12.60	1.81
	TAIL 500'	Premium cmt + 2% CaCl + 0.25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD 4,451'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	420	40%	11.00	3.38
	TAIL 5,880'	50/50 Poz/G + 10% salt + 2% gel + 0.1% R-3	1,440	40%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.


Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER: _____ **DATE:** _____
 John Huycke / Emile Goodwin

DRILLING SUPERINTENDENT: _____ **DATE:** _____
 John Merkel / Lovel Young

EXHIBIT A NBU 921-30D3DS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

WELL PAD INTERFERENCE PLAT

DIRECTIONAL PAD - NBU 921-30D



LATITUDE & LONGITUDE		
Surface Position - (NAD 83)		
WELL	N. LATITUDE	W. LONGITUDE
921-30D2DS	40°00'43.679" 40.012133°	109°36'07.550" 109.602097°
921-30D3DS	40°00'43.564" 40.012101°	109°36'07.339" 109.602039°
921-30E2AS	40°00'43.448" 40.012069°	109°36'07.130" 109.601981°
921-30C3CS	40°00'43.334" 40.012037°	109°36'06.921" 109.601923°
Existing Well NBU 921-30D	40°00'43.794" 40.012165°	109°36'07.758" 109.602155°

RELATIVE COORDINATES		
From Surface Position to Bottom Hole		
WELL	NORTH	EAST
NBU 921-30D2DS	285'	-209'
NBU 921-30D3DS	-395'	-218'
NBU 921-30E2AS	-753'	-231'
NBU 921-30C3CS	-200'	1068'

BOTTOM HOLE FOOTAGES

- NBU 921-30D2DS
460' FNL, 665' FWL

- NBU 921-30D3DS
1152' FNL, 665' FWL

- NBU 921-30E2AS
1522' FNL, 665' FWL

- NBU 921-30C3CS
993' FNL, 1985' FWL

SURFACE POSITION FOOTAGES:

- NBU 921-30D2DS
747' FNL, 871' FWL

- NBU 921-30D3DS
759' FNL, 887' FWL

- NBU 921-30E2AS
771' FNL, 903' FWL

- NBU 921-30C3CS
783' FNL, 920' FWL

- NBU 921-30D (Existing Well Head)
736' FNL, 855' FWL

LATITUDE & LONGITUDE		
Bottom Hole - (NAD 83)		
WELL	N. LATITUDE	W. LONGITUDE
921-30D2DS	40°00'46.499" 40.012916°	109°36'10.234" 109.602843°
921-30D3DS	40°00'39.663" 40.011017°	109°36'10.144" 109.602818°
921-30E2AS	40°00'36.007" 40.010002°	109°36'10.095" 109.602804°
921-30C3CS	40°00'41.359" 40.011489°	109°35'53.205" 109.598112°

LATITUDE & LONGITUDE		
Surface Position - (NAD 27)		
WELL	N. LATITUDE	W. LONGITUDE
921-30D2DS	40°00'43.806" 40.012168°	109°36'05.064" 109.601407°
921-30D3DS	40°00'43.691" 40.012136°	109°36'04.854" 109.601348°
921-30E2AS	40°00'43.575" 40.012104°	109°36'04.644" 109.601290°
921-30C3CS	40°00'43.461" 40.012072°	109°36'04.435" 109.601232°
Existing Well NBU 921-30D	40°00'43.921" 40.012200°	109°36'05.272" 109.601465°

LATITUDE & LONGITUDE		
Bottom Hole - (NAD 27)		
WELL	N. LATITUDE	W. LONGITUDE
921-30D2DS	40°00'46.626" 40.012952°	109°36'07.748" 109.602152°
921-30D3DS	40°00'39.790" 40.011053°	109°36'07.658" 109.602127°
921-30E2AS	40°00'36.134" 40.010037°	109°36'07.610" 109.602114°
921-30C3CS	40°00'41.486" 40.011524°	109°35'50.720" 109.597422°

BASIS OF BEARINGS IS THE EAST LINE OF THE NE 1/4 OF SECTION 25, T9S, R20E, S.L.B.&M. WHICH IS TAKEN FROM GLOBAL POSITIONING SATELLITE OBSERVATIONS TO BEAR N00°35'44"W.

Kerr-McGee
Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202





CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

DATE SURVEYED: 12-11-08	SURVEYED BY: M.S.B.
DATE DRAWN: 01-26-09	DRAWN BY: E.M.S.
	REVISED: 04-17-09


Timberline (435) 789-1365
Engineering & Land Surveying, Inc.
209 NORTH 300 WEST VERNAL, UTAH 84078

SHEET
5
OF 13

NBU 921-30D2DS, NBU 921-30D3DS,
NBU 921-30E2AS & NBU 921-30C3CS
LOCATED IN SECTION 30, T9S, R21E,
S.L.B.&M. UINTAH COUNTY, UTAH.



NBU 921-30D2DS, NBU 921-30D3DS,
NBU 921-30E2AS & NBU 921-30C3CS
LOCATED IN SECTION 30, T9S, R21E,
S.L.B.&M. UINTAH COUNTY, UTAH.



WELL PAD NBU 921-30D QUANTITIES

EXISTING GRADE @ CENTER OF WELL PAD = 4847.2'
 FINISHED GRADE ELEVATION = 4846.7'
 CUT SLOPES = 1.5:1
 FILL SLOPES = 1.5:1

TOTAL CUT FOR WELL PAD = 10,774 C.Y.
 TOTAL FILL FOR WELL PAD = 187 C.Y.
 TOPSOIL @ 6" DEPTH = 1,844 C.Y.
 EXCESS MATERIAL = 10,587 C.Y.
 TOTAL DISTURBANCE = 3.67 ACRES
 SHRINKAGE FACTOR = 1.10
 SWELL FACTOR = 1.00
 RESERVE PIT CAPACITY (2' OF FREEBOARD)
 +/- 28,730 BARRELS
 RESERVE PIT VOLUME
 +/- 7,720 CY
 BACKFLOW PIT CAPACITY (2' OF FREEBOARD)
 +/- 9,490 BARRELS
 BACKFLOW PIT VOLUME
 +/- 2,660 CY

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)



HORIZONTAL 1" = 60'
 2' CONTOURS

**KERR-MCGEE OIL & GAS
 ONSHORE L.P.**

1099 18th Street - Denver, Colorado 80202




CONSULTING, LLC
 371 Coffeen Avenue
 Sheridan WY 82801
 Phone 307-674-0609
 Fax 307-674-0182


WELL PAD - LOCATION LAYOUT
 NBU 921-30D2DS, NBU 921-30D3DS,
 NBU 921-30E2AS & NBU 921-30C3CS
 LOCATED IN SECTION 30, T.9S., R.21E.
 S.L.B.&M., UINTAH COUNTY, UTAH

Scale: 1"=60'	Date: 3/5/09	SHEET NO:
REVISED: RAW 4/24/09	BY DATE	6 6 OF 13

Timberline Engineering & Land Surveying, Inc. (435) 789-1365
 38 WEST 100 NORTH VERNAL, UTAH 84078



CROSS SECTION A-A'



CROSS SECTION B-B'

NOTE: CROSS SECTION B-B' DEPICTS
MAXIMUM RESERVE PIT DEPTH.


KERR-MCGEE OIL & GAS
ONSHORE L.P.
1099 18th Street - Denver, Colorado 80202

WELL PAD - CROSS SECTIONS
NBU 921-30D2DS, NBU 921-30D3DS,
NBU 921-30E2AS & NBU 921-30C3CS
LOCATED IN SECTION 30, T.9S., R.21E.
S.L.B.&M., Uintah County, Utah



CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

Scale: 1"=100'	Date: 3/5/09	SHEET NO:
REVISD: RAW 4/24/09	BY DATE	7 7 OF 13



Timberline (435) 789-1365
Engineering & Land Surveying, Inc.
38 WEST 100 NORTH VERNAL, UTAH 84078












PHOTO VIEW: FROM EXISTING WELL TO LOCATION STAKES

CAMERA ANGLE: SOUTHEASTERLY



PHOTO VIEW: FROM EXISTING ACCESS ROAD

CAMERA ANGLE: NORTHWESTERLY

**Kerr-McGee
Oil & Gas Onshore, LP**

1099 18th Street - Denver, Colorado 80202

NBU 921-30D2DS, NBU 921-30D3DS,
NBU 921-30E2AS & NBU 921-30C3CS
LOCATED IN SECTION 30, T9S, R21E,
S.L.B.&M. UINTAH COUNTY, UTAH.



CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

LOCATION PHOTOS

TAKEN BY: M.S.B.

DRAWN BY: E.M.S.

DATE TAKEN: 12-11-08

DATE DRAWN: 01-26-09

REVISED: 04-17-09

Timberline

Engineering & Land Surveying, Inc.
209 NORTH 300 WEST VERNAL, UTAH 84078

(435) 789-1365

SHEET
8
OF 13

Kerr-McGee Oil & Gas Onshore, LP
NBU 921-30D2DS NBU 921-30D3DS NBU 921-30E2AS NBU 921-30C3CS
Section 30, T9S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 13.9 MILES TO THE JUNCTION OF STATE HIGHWAY 88. EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 88 APPROXIMATELY 16.8 MILES TO OURAY, UTAH. FROM OURAY, PROCEED IN A SOUTHERLY DIRECTION ALONG THE SEEP RIDGE ROAD (COUNTY B ROAD 2810) APPROXIMATELY 5.3 MILES TO THE INTERSECTION OF AN EXISTING ROAD TO THE EAST. EXIT LEFT AND PROCEED IN A NORTHEASTERLY THEN SOUTHEASTERLY DIRECTION ALONG THE EXISTING ROAD APPROXIMATELY 5.5 MILES TO THE EXISTING ACCESS ROAD. EXIT RIGHT AND PROCEED IN A WESTERLY, THEN NORTHWESTERLY DIRECTION ALONG THE ACCESS ROAD APPROXIMATELY 0.9 MILES TO THE NBU 921-30D WELL PAD.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 42.4 MILES IN A SOUTHERLY DIRECTION.

NBU 921-30C3CS

Surface: 783' FNL 920' FWL (NW/4NW/4) Lot 1
BHL: 993' FNL 1,985' FWL (NE/4NW/4)

NBU 921-30D2DS

Surface: 747' FNL 871' FWL (NW/4NW/4) Lot 1
BHL: 460' FNL 665' FWL (NW/4NW/4) Lot 1

NBU 921-30D3DS

Surface: 759' FNL 887' FWL (NW/4NW/4) Lot 1
BHL: 1,152' FNL 665' FWL (NW/4NW/4) Lot 1

NBU 921-30E2AS

Surface: 771' FNL 903' FWL (NW/4NW/4) Lot 1
BHL: 1,522' FNL 665' FWL (SW/4NW/4) Lot 2

Pad: NBU 921-30D
Sec. 30 T9S R21E

Uintah, Utah

ONSHORE ORDER NO. 1

***MULTI-POINT SURFACE USE & OPERATIONS PLAN
SUBMITTED WITH SITE-SPECIFIC INFORMATION***

This Application for Permit to Drill (APD) is filed under the Notice of Staking (NOS) process as stated in Onshore Order No. 1 (OSO #1) and supporting Bureau of Land Management (BLM) documents. An NOS was submitted on March 17, 2009 showing the surface locations in NW/4 NW/4 of Section 30 T9S R21E. At the time the NOS was submitted, the following wells had the following well names:

NBU 921-30C3Cs was fka NBU 921-30C3BS
NBU 921-30D2DS was fka NBU 921-30D2AS

This Surface Use Plan of Operations (SUPO) or 13-point plan provides the site-specific information for the above-referenced wells. This information is to be incorporated by reference into the Master Development Plan (MDP) for Kerr-McGee Oil & Gas Onshore LP (Kerr-McGee). The MDP is available upon request from the BLM-Vernal Field Office.

To schedule an onsite please contact Raleen White at 720-929-6666.

Directional Drilling:

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, this well will be directionally drilled in order to access portions of our lease which are otherwise inaccessible due to topography.

1. **Existing Roads:**

- A) Refer to Topo Map A for directions to the location.
- B) Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

2. **Planned Access Roads:**

See MDP for additional details on road construction.

No new access road is proposed. Please refer to the attached Topo Map B. No pipelines will be crossed with the new construction.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site and are typically shown on the attached Exhibits and Topo maps.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing and Proposed Facilities:**

See MDP for additional details on Existing and Proposed Facilities.

This pad will expand the existing pad for the NBU 921-30D, which is a producing well according to Utah Division of Oil, Gas and Mining (UDOGM) records.

The following guidelines will apply if the well is productive.

Approximately ±5,590' (±1.06 miles) of pipeline is proposed. The existing pipeline, as shown on Topo D, will be upgraded to accommodate anticipated production from the proposed wells. The upgraded pipeline will follow the same route as the existing pipeline. Pipeline segments will be welded or zaplocked together on disturbed areas in or near the location, whenever possible, and dragged into place.

5. **Location and Type of Water Supply:**

See MDP for additional details on Location and Type of Water Supply.

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

See MDP for additional details on Source of Construction Materials.

7. Methods of Handling Waste Materials:

See MDP for additional details on Methods of Handling Waste Materials.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E

NBU #159 in Sec. 35 T9S R21E

Ace Oilfield in Sec. 2 T6S R20E

MC&MC in Sec. 12 T6S R19E

Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

8. Ancillary Facilities:

See MDP for additional details on Ancillary Facilities.

None are anticipated.

9. Well Site Layout: (See Location Layout Diagram)

See MDP for additional details on Well Site Layout.

All pits will be fenced according to the following minimum standards:

- Net wire (39-inch) will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.
- Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.
- All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

10. Plans for Reclamation of the Surface:

See MDP for additional details on Plans for Reclamation of the Surface.

11. Surface/Mineral Ownership:

United States of America

Bureau of Land Management

170 South 500 East

Vernal, UT 84078

(435)781-4400

12. Other Information:

See MDP for additional details on Other Information.

13. Lessee's or Operators' Representative & Certification:

Kathy Schneebeck Dulnoan
Regulatory Analyst
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6007

Tommy Thompson
General Manager, Drilling
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.



Kathy Schneebeck Dulnoan

August 13, 2009

Date



Kerr-McGee Oil & Gas Onshore LP
P.O. Box 173779
Denver, CO 80217-3779

June 9, 2009

Diana Mason
Utah Department of Oil, Gas & Mining
P.O. Box 145801
Salt Lake City, Utah 54114-6100

RE: Directional Drilling Letter R649-3-11
NBU 921-30D3DS
T9S-R21E
Section 30: NW/4NW/4 surface and bottom hole
759' FNL, 887' FWL (surface)
1152' FNL, 665' FWL (bottom hole)
Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.

- Kerr-McGee's NBU 921-30D3DS is located within the Natural Buttes Unit Area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit to be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joe Matney
Senior Staff Landman

'APIWellNo:43047506480000'

CLASS I REVIEW OF KERR-MCGEE OIL & GAS
ONSHORE LP'S 51 PROPOSED WELL LOCATIONS
(T9S, R21E, SECTIONS 7, 8, 10, 11, 12,
17, 18, 19, 20, 23, 25, AND 30)
IN UINTAH COUNTY, UTAH

By:

Jacki A. Montgomery

Prepared For:

Ute Tribal Land
Uintah and Ouray Agency

Bureau of Land Management
Vernal Field Office

Prepared Under Contract With:

Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, Utah 84078

Prepared By:

Montgomery Archaeological Consultants, Inc.
P.O. Box 219
Moab, Utah 84532

MOAC Report No. 09-39

May 11, 2009

United States Department of Interior (FLPMA)
Permit No. 09-UT-60122

Public Lands Policy Coordination Office
Archaeological Survey Permit No. 117

Ute Tribal Permit No. A09-363

IPC #09-41

Paleontological Reconnaissance Survey Report

Survey of Kerr McGee's Proposed Multi-Well Pads, Access Roads, Pipelines and Pipeline Upgrades for "NBU #921-28C4CS, C4BS, C1CS & D1BS, #921-28K, L1CS, L1BS & M1CS, #921-30N1AS, P2AS, P3DS & P2DS, & NBU #921-30C3CS, E2AS, D3DS & D2DS" (Sec. 28-30, T 9 S, R 21 E)

Ouray SE
Topographic Quadrangle
Uintah County, Utah



March 26, 2009

Prepared by Stephen D. Sandau
Paleontologist for
Intermountain Paleo-Consulting
P. O. Box 1125
Vernal, Utah 84078

API Number: 4304750648
Well Name: NBU 921-30D3DS
Township 09.0 S Range 21.0 E Section 30
Meridian: SLBM
 Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared:
 Map Produced by Diana Mason

- | | |
|---------------|------------------------------|
| Units | Wells Query Events |
| STATUS | X -<all other values> |
| ACTIVE | -NUL- |
| EXPLORATORY | APD |
| GAS STORAGE | DRL |
| NF PP OIL | GI |
| NF SECONDARY | GS |
| PI OIL | LA |
| PP GAS | NEW |
| PP GEOTHERM | OPS |
| PP OIL | PA |
| SECONDARY | PGW |
| TERMINATED | POW |
| | RET |
| Fields | SGW |
| STATUS | SOW |
| ACTIVE | TA |
| COMBINED | TW |
| Sections | WD |
| | WI |
| | WS |



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

**3160
(UT-922)**

August 28, 2009

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2009 Plan of Development Natural Buttes Unit Uintah
County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2009 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-50640	NBU 1022-8B1DS	Sec 08 T10S R22E 0931 FNL 1709 FEL
	BHL	Sec 08 T10S R22E 0367 FNL 1518 FEL
43-047-50641	NBU 1022-8B4AS	Sec 08 T10S R22E 0919 FNL 1693 FEL
	BHL	Sec 08 T10S R22E 0744 FNL 1518 FEL
43-047-50642	NBU 1022-8C1AS	Sec 08 T10S R22E 0943 FNL 1725 FEL
	BHL	Sec 08 T10S R22E 0102 FNL 2415 FWL
43-047-50643	NBU 1022-8C1CS	Sec 08 T10S R22E 0955 FNL 1742 FEL
	BHL	Sec 08 T10S R22E 0418 FNL 2252 FWL
43-047-50644	NBU 922-30C3S	Sec 30 T09S R22E 1253 FNL 0663 FWL
	BHL	Sec 30 T09S R22E 1238 FNL 1154 FWL
43-047-50645	NBU 922-30D3AS	Sec 30 T09S R22E 1232 FNL 0607 FWL
	BHL	Sec 30 T09S R22E 0680 FNL 0382 FWL
43-047-50646	NBU 921-30C3CS	Sec 30 T09S R21E 0783 FNL 0920 FWL
	BHL	Sec 30 T09S R21E 0993 FNL 1985 FWL
43-047-50647	NBU 921-30D2DS	Sec 30 T09S R21E 0747 FNL 0871 FWL
	BHL	Sec 30 T09S R21E 0460 FNL 0665 FWL

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-50648	NBU 921-30D3DS	Sec 30 T09S R21E 0759 FNL 0887 FWL BHL Sec 30 T09S R21E 1152 FNL 0665 FWL
43-047-50649	NBU 921-30E2AS	Sec 30 T09S R21E 0771 FNL 0903 FWL BHL Sec 30 T09S R21E 1522 FNL 0665 FWL
43-047-50650	NBU 1022-7N1S	Sec 07 T10S R22E 0089 FSL 1920 FEL BHL Sec 07 T10S R22E 0895 FSL 1870 FWL
43-047-50651	NBU 1022-7N4S	Sec 07 T10S R22E 0097 FSL 1938 FEL BHL Sec 07 T10S R22E 0595 FSL 1740 FWL
43-047-50652	NBU 1022-7O4AS	Sec 07 T10S R22E 0081 FSL 1902 FEL BHL Sec 07 T10S R22E 0550 FSL 1560 FEL
43-047-50653	NBU 1022-7O4DS	Sec 07 T10S R22E 0074 FSL 1883 FEL BHL Sec 07 T10S R22E 0230 FSL 1650 FEL
43-047-50655	NBU 922-30D3DS	Sec 30 T09S R22E 1226 FNL 0588 FWL BHL Sec 30 T09S R22E 1314 FNL 0352 FWL
43-047-50656	NBU 922-30E2AS	Sec 30 T09S R22E 1246 FNL 0645 FWL BHL Sec 30 T09S R22E 1636 FNL 0352 FWL
43-047-50678	NBU 922-31G4BS	Sec 31 T09S R22E 2317 FSL 0188 FEL BHL Sec 31 T09S R22E 1994 FNL 1808 FEL
43-047-50679	NBU 922-31G4CS	Sec 31 T09S R22E 2316 FSL 0198 FEL BHL Sec 31 T09S R22E 2353 FNL 1796 FEL
43-047-50680	NBU 922-31I1AS	Sec 31 T09S R22E 2317 FSL 0178 FEL BHL Sec 31 T09S R22E 2483 FSL 0243 FEL
43-047-50681	NBU 922-31I1DS	Sec 31 T09S R22E 2317 FSL 0168 FEL BHL Sec 31 T09S R22E 2137 FSL 0264 FEL
43-047-50682	NBU 921-12J	Sec 12 T09S R21E 1959 FSL 2051 FEL
43-047-50684	NBU 1022-6I3AS	Sec 06 T10S R22E 1160 FSL 1584 FEL BHL Sec 06 T10S R22E 1684 FSL 1167 FEL
43-047-50685	NBU 1022-6J4CS	Sec 06 T10S R22E 1178 FSL 1593 FEL BHL Sec 06 T10S R22E 1535 FSL 1760 FEL
43-047-50686	NBU 1022-6O1BS	Sec 06 T10S R22E 1124 FSL 1567 FEL BHL Sec 06 T10S R22E 1197 FSL 1811 FEL

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-50687	NBU 1022-6P1CS	Sec 06 T10S R22E 1142 FSL 1575 FEL BHL Sec 06 T10S R22E 0989 FSL 0541 FEL
43-047-50691	NBU 921-29A3AS	Sec 29 T09S R21E 0299 FNL 2630 FEL BHL Sec 29 T09S R21E 0700 FNL 0885 FEL
43-047-50692	NBU 921-29A3DS	Sec 29 T09S R21E 0303 FNL 2628 FWL BHL Sec 29 T09S R21E 1193 FNL 0885 FEL
43-047-50694	NBU 921-29A2AS	Sec 29 T09S R21E 0296 FNL 2611 FEL BHL Sec 29 T09S R21E 0209 FNL 0885 FEL
43-047-50693	NBU 921-29B2CS	Sec 29 T09S R21E 0307 FNL 2608 FWL BHL Sec 29 T09S R21E 0443 FNL 2635 FEL
43-047-50695	NBU 921-12N	Sec 12 T09S R21E 0441 FSL 2236 FWL
43-047-50698	NBU 921-19F	Sec 19 T09S R21E 2236 FNL 2285 FWL
43-047-50699	NBU 921-17C	Sec 17 T09S R21E 0656 FNL 2004 FWL
43-047-50700	NBU 921-17D	Sec 17 T09S R21E 0985 FNL 0418 FWL
43-047-50701	NBU 921-17G	Sec 17 T09S R21E 1500 FNL 2262 FEL
43-047-50702	NBU 921-17H	Sec 17 T09S R21E 2100 FNL 0553 FEL
43-047-50703	NBU 921-18P	Sec 18 T09S R21E 1080 FSL 0197 FEL
43-047-50704	NBU 921-19E	Sec 19 T09S R21E 2061 FNL 0842 FWL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File – Natural Buttes Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron

Fluid Chron

MCoulthard:mc:8-28-09

**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 8/14/2009

API NO. ASSIGNED: 43047506480000

WELL NAME: NBU 921-30D3DS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995)

PHONE NUMBER: 720 929-6156

CONTACT: Danielle Piernot

PROPOSED LOCATION: NWNW 30 090S 210E

Permit Tech Review:

SURFACE: 0759 FNL 0887 FWL

Engineering Review:

BOTTOM: 1152 FNL 0665 FWL

Geology Review:

COUNTY: UINTAH

LATITUDE: 40.01202

LONGITUDE: -109.60130

UTM SURF EASTINGS: 619377.00

NORTHINGS: 4429818.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU 0581

PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- PLAT
- Bond: FEDERAL - WYB000291
- Potash
- Oil Shale 190-5
- Oil Shale 190-3
- Oil Shale 190-13
- Water Permit: Permit #43-8496
- RDCC Review:
- Fee Surface Agreement
- Intent to Commingle

Commingle Approved

LOCATION AND SITING:

- R649-2-3.
Unit: NATURAL BUTTES
- R649-3-2. General
- R649-3-3. Exception
- Drilling Unit
Board Cause No: Cause 173-14
Effective Date: 12/2/1999
Siting: 460' fr u bdry & uncomm. tract
- R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations:
1 - Exception Location - dmason
3 - Commingle - ddoucet
4 - Federal Approval - dmason
15 - Directional - dmason
17 - Oil Shale 190-5(b) - dmason



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 921-30D3DS
API Well Number: 43047506480000
Lease Number: UTU 0581
Surface Owner: FEDERAL
Approval Date: 8/31/2009

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

Commingle:

In accordance with Board Cause No. 173-14 commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale

Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:


- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)
- OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:



Gil Hunt
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0581
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 921-30D3DS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.	9. API NUMBER: 43047506480000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6007 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0759 FNL 0887 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 30 Township: 09.0S Range: 21.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/31/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.

Approved by the Utah Division of Oil, Gas and Mining

Date: August 31, 2010

By:

NAME (PLEASE PRINT) Danielle Piernot	PHONE NUMBER 720 929-6156	TITLE Regulatory Analyst
SIGNATURE N/A		DATE 8/31/2010



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047506480000

API: 43047506480000

Well Name: NBU 921-30D3DS

Location: 0759 FNL 0887 FWL QTR NWNW SEC 30 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 8/31/2009

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No


**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Danielle Piernot

Date: 8/31/2010

Title: Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date: August 31, 2010

By: 

RECEIVED August 31, 2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0581
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 921-30D3DS	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.	9. API NUMBER: 43047506480000	
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0759 FNL 0887 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 30 Township: 09.0S Range: 21.0E Meridian: S	COUNTY: UINTAH	
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/12/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> APD EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER OTHER: <input style="width: 100px; height: 15px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
<p>Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.</p> <div style="text-align: right; margin-top: 20px;"> <p>Approved by the Utah Division of Oil, Gas and Mining</p> <p>Date: <u>07/12/2011</u></p> <p>By: </p> </div>		
NAME (PLEASE PRINT) Gina Becker	PHONE NUMBER 720 929-6086	TITLE Regulatory Analyst II
SIGNATURE N/A	DATE 7/12/2011	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047506480000

API: 43047506480000

Well Name: NBU 921-30D3DS

Location: 0759 FNL 0887 FWL QTR NWNW SEC 30 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 8/31/2009

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No

- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No

- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No

- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No

- Has the approved source of water for drilling changed? Yes No

- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No

- Is bonding still in place, which covers this proposed well? Yes No

Signature: Gina Becker

Date: 7/12/2011

Title: Regulatory Analyst II **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0581
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 921-30D3DS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.	9. API NUMBER: 43047506480000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6511 9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0759 FNL 0887 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 30 Township: 09.0S Range: 21.0E Meridian: S	COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/30/2012	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input checked="" type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.

Approved by the Utah Division of Oil, Gas and Mining
Date: September 13, 2012
By:

NAME (PLEASE PRINT) Danielle Piernot	PHONE NUMBER 720 929-6156	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 8/30/2012	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047506480000

API: 43047506480000

Well Name: NBU 921-30D3DS

Location: 0759 FNL 0887 FWL QTR NWNW SEC 30 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 8/31/2009

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
- Has the approved source of water for drilling changed? Yes No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
- Is bonding still in place, which covers this proposed well? Yes No

Signature: Danielle Piernot

Date: 8/30/2012

Title: Regulatory Analyst Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.



United States Department of the Interior



BUREAU OF LAND MANAGEMENT

Green River District
Vernal Field Office
170 South 500 East
Vernal, UT 84078

<http://www.blm.gov/ut/st/en/fo/vernal.html>

April 1, 2013

IN REPLY REFER TO:
3160 (UTG011)

Julie Jacobson
Kerr McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779

43 047 506A8

Re: Request to Return APD
Well No. NBU 921-30D3DS
NWSW, Sec. 30, T9S, R21E
Uintah County, Utah
Lease No. UTU-0581
Natural Buttes Unit

Dear Julie:

The Application for Permit to Drill (APD) for the above referenced well received in this office on August 25, 2009, is being returned unapproved per your request to this office in an email message to Natural Resource Specialist Tyler Cox received on March 7, 2013. If you intend to drill at this location at a future date, a new APD must be submitted.

If you have any questions regarding APD processing, please contact Robin R. Hansen at (435) 781-3428.

Sincerely,

/s/ Jerry Kenczka

Jerry Kenczka
Assistant Field Manager
Lands & Resource Minerals

Enclosures

cc: UDOGM

bcc: Well File

RECEIVED

MAY 01 2013

DIV. OF OIL, GAS & MINING



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

July 23, 2013

Teena Paulo
Anadarko Petroleum
1099 18th Street, Suite 600
Denver, CO 80202

Re: APDs Rescinded for Anadarko Petroleum, Uintah County

Dear Ms. Paulo:

Enclosed find the list of APDs that you requested to be rescinded. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded, effective July 22, 2013.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

Diana Mason
Environmental Scientist

cc: Well File
Bureau of Land Management, Vernal

43-047-50623	NBU 921-28C1CS
43-047-50624	NBU 921-28C4BS
43-047-50625	NBU 921-28C4CS
43-047-50626	NBU 921-28D1BS
43-047-50632	NBU 920-21I
43-047-36948	NBU 540-24E
43-047-40330	NBU 681-26E
43-047-50649	NBU 921-30E2AS
43-047-50646	NBU 921-30C3CS
43-047-50647	NBU 921-30D2DS
43-047-50648	NBU 921-30D3DS
43-047-36999	NBU 920-25L



dianawhitney@utah.gov

Mail

More

9 of 109

COMPOSE

Good Morning Diana,

Paulo, Teena

teena.paulo@anadarko.com

Please see the below list of wells for the APD's that Kerr-McGee requests to rescind with UDOGM.

Show details

Well Name	API Number
NBU 921-28C1CS	4304750623
NBU 921-28C4BS	4304750624
NBU 921-28C4CS	4304750625
NBU 921-28D1BS	4304750626
NBU 920-21I	4304750632
NBU 540-24E	4304736948
NBU 681-26E	4304740330
NBU 921-30E2AS	4304750649
NBU 921-30C3CS	4304750646
NBU 921-30D2DS	4304750647
NBU 921-30D3DS	4304750648
NBU 920-25L	4304736999

