

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Chapita Wells Unit 1544-26D				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT NATURAL BUTTES				
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME CHAPITA WELLS				
6. NAME OF OPERATOR EOG Resources, Inc.						7. OPERATOR PHONE 435 781-9111				
8. ADDRESS OF OPERATOR 600 17th Street, Suite 1000 N, Denver, CO, 80202						9. OPERATOR E-MAIL kaylene_gardner@egoresources.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU0285A			11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		447 FNL 501 FEL		NENE	26	9.0 S	22.0 E	S		
Top of Uppermost Producing Zone		1240 FNL 624 FEL		NENE	26	9.0 S	22.0 E	S		
At Total Depth		1240 FNL 624 FEL		NENE	26	9.0 S	22.0 E	S		
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 923			23. NUMBER OF ACRES IN DRILLING UNIT 1800				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 580			26. PROPOSED DEPTH MD: 9415 TVD: 9310				
27. ELEVATION - GROUND LEVEL 5015			28. BOND NUMBER NM2308			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-225				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	12.25	9.625	0 - 2300	36.0	J-55 ST&C	10.5	Class G	150	3.82	11.0
							Class G	135	1.18	15.6
PROD	7.875	4.5	0 - 9415	11.6	N-80 LT&C	10.5	Hi Lift "G"	130	3.91	11.0
							50/50 Poz	910	1.28	14.1
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Mickenzie Gates			TITLE Operations Clerk			PHONE 435 781-9145				
SIGNATURE			DATE 06/24/2011			EMAIL mickenzie_gates@egoresources.com				
API NUMBER ASSIGNED 43047517310000			APPROVAL  Permit Manager							



DRILLING PLAN
MULTI-WELL PAD:
CWU 1541-26D, CWU 1542-26D, CWU 1543-26D,
CWU 1544-26D, CWU 1545-26D, CWU 1546-26D
NE/NE, SEC. 26, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	CWU 1541-26D		CWU 1542-26D		CWU 1543-26D		CWU 1544-26D	
	TVD	MD	TVD	MD	TVD	MD	TVD	MD
Green River	1540	1546	1514	1528	1517	1532	1520	1536
Birdsnest	1754	1762	1730	1750	1717	1735	1716	1743
Mahogany Oil Shale Bed	2296	2307	2281	2315	2276	2304	2268	2327
Wasatch	4653	4667	4625	4677	4617	4661	4600	4705
Chapita Wells	5241	5255	5215	5268	5208	5252	5193	5298
Buck Canyon	5903	5916	5870	5923	5852	5896	5812	5917
North Horn	6608	6622	6586	6639	6587	6632	6593	6698
KMV Price River	6985	6998	6941	6994	6934	6978	6920	7025
KMV Price River Middle	7855	7868	7813	7865	7807	7851	7795	7900
KMV Price River Lower	8636	8650	8602	8654	8596	8640	8586	8691
Sego	9148	9162	9112	9164	9114	9158	9107	9212
TD	9350	9364	9315	9367	9315	9359	9310	9415
ANTICIPATED BHP (PSI)	5105		5086		5086		5083	

FORMATION	CWU 1545-26D		CWU 1546-26D					
	TVD	MD	TVD	MD				
Green River	1530	1546	1543	1565				
Birdsnest	1726	1750	1738	1770				
Mahogany Oil Shale Bed	2280	2323	2288	2344				
Wasatch	4623	4691	4641	4732				
Chapita Wells	5213	5281	5229	5320				
Buck Canyon	5852	5921	5886	5977				
North Horn	6594	6662	6595	6686				
KMV Price River	6951	7020	6979	7070				
KMV Price River Middle	7821	7889	7843	7933				
KMV Price River Lower	8611	8679	8632	8722				
Sego	9139	9208	9146	9237				
TD	9340	9409	9350	9441				
ANTICIPATED BHP (PSI)	5100		5105					

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.



DRILLING PLAN
MULTI-WELL PAD:
CWU 1541-26D, CWU 1542-26D, CWU 1543-26D,
CWU 1544-26D, CWU 1545-26D, CWU 1546-26D
NE/NE, SEC. 26, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

3. **PRESSURE CONTROL EQUIPMENT:** Production Hole – 5000 Psig
 BOP schematic diagrams attached.

4. **CASING PROGRAM:**

Casing	Hole Size	Length	Size	Weight	Grade	Thread	Rating Collapse	Rating Burst	Tensile
Conductor	20"	0 – 60'	14"	32.5#	A252			1800 PSI	10,000#
Surface	12 ¼"	0 – 2,300'±	9 ¾"	36.0#	J-55	STC	2020 PSI	3520 PSI	394,000#
Production	7 7/8"	Surface – TD	4 ½"	11.6#	N-80	LTC	6350 PSI	7780 PSI	223,000#

Note: 12 ¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-¾" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

5. **Float Equipment:**

Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 3rd joint to 400' above the top of primary objective. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. **MUD PROGRAM**

Surface Hole Procedure (Surface - 2300'±):

0' - 2300'± Air/Air mist/Aerated water
 or

A closed mud system will be utilized with a gelled bentonite system. LCM sweeps, additions, etc. will be utilized as necessary.



DRILLING PLAN
MULTI-WELL PAD:
CWU 1541-26D, CWU 1542-26D, CWU 1543-26D,
CWU 1544-26D, CWU 1545-26D, CWU 1546-26D
NE/NE, SEC. 26, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

Production Hole Procedure (2300'± - TD):

Anticipated mud weight 9.5-10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 1
Onshore Oil and Gas Order No. 2 – Section E: Special Drilling Operations

- EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line to be 100' in length. (Where possible, a straight run blooie line will be used).
- EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be approximately 75' in length.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring dedusting equipment. Dust during air drilling operations is controlled by water mist.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring an automatic igniter or continuous pilot light on the blooie line. (Not required on aerated water system).
- EOG Resources, Inc. requests a variance that compressors are located in the opposite direction from the blooie line a minimum of 100 feet from the well bore. (Air Compressors are rig mounted).

8. EVALUATION PROGRAM:

Logs: None
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Gamma Ray



DRILLING PLAN
MULTI-WELL PAD:
CWU 1541-26D, CWU 1542-26D, CWU 1543-26D,
CWU 1544-26D, CWU 1545-26D, CWU 1546-26D
NE/NE, SEC. 26, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: 150 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: 135 sks Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: The above number of sacks is based on gauge-hole calculation
 Lead volume to be calculated to bring cement to surface.
 Tail volume to be calculated to bring cement to 500' above the shoe.

Production Hole Procedure (2300'± - TD)

Lead: 130 sks: Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.

Tail: 910 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9 gps water.

Note: The above number of sacks is based on gauge-hole calculation.
 Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
 Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.



DRILLING PLAN
MULTI-WELL PAD:
CWU 1541-26D, CWU 1542-26D, CWU 1543-26D,
CWU 1544-26D, CWU 1545-26D, CWU 1546-26D
NE/NE, SEC. 26, T9S, R22E, S.L.B.&M..
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:


No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

13. Air Drilling Operations:

1. Main Air Compressors are 1250 CFM 350 psi with 2000 psi Boosters and are rig mounted.
2. Secondary Air Compressors are 1170 CFM 350 psi with 2000 psi Boosters and are rig mounted.
3. Minimum setting depth of conductor casing will be 60' GL or 10'± into competent formation, whichever is deeper, as determined by the EOG person in charge. Exceptions must be approved by an EOG drilling superintendent or manager.
4. The diameter of the diverter flow line will be a minimum of 10" to help reduce back pressure on the well bore during uncontrolled flow.
5. Rat and Mouse hole drilling will occur only after surface casing has been set and cemented.
6. EOG Resources, Inc. will use a properly maintained and lubricated stripper head.


(Attachment: BOP Schematic Diagram)

CWU 1544-26D
Section 26 T9S R22E
Uintah County, UT



Vertical Section at 188.63deg (1500 ft/in)

Surface Location			
NAD 1927 (NADCON CONUS)		Utah North 4301	
Ground Elevation: 5015.00 RIG @ 5034.00ft (True 34)			
Northing	Easting	Latitude	Longitude
-109577.33	2588618.06	40°0' 46.958 N	109°23' 55.900 W



Project: T9S-R22E Sec 26
 Site: CWU 1541-1546 26D (Pad D1_CWU 905-26_Set 13)
 Well: 1544-26D
 Plan: APD



Azimuths to True North
 Magnetic North: 11.24°
 Magnetic Field
 Strength: 52551.5snT
 Dip Angle: 65.95°
 Date: 9/21/2009
 Model: IGRF200510

SECTION DETAILS											
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target	
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
2	400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00		
3	1666.67	19.00	188.63	1643.58	-205.75	-31.23	1.50	188.63	208.10		
4	2531.37	19.00	188.63	2461.17	-484.08	-73.47	0.00	0.00	489.62		
5	4431.38	0.00	0.00	4326.55	-792.70	-120.31	1.00	180.00	801.78		
6	7104.83	0.00	0.00	7000.00	-792.70	-120.31	0.00	0.00	801.78	CWU 1544-26D	
7	9414.83	0.00	0.00	9310.00	-792.70	-120.31	0.00	0.00	801.78		

TARGET DETAILS									
Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape	
CWU 1544-26D	7000.00	-792.70	-120.31	-110372.71	2588516.96	40°0' 39.126 N	109°23' 57.445 W	Circle (Radius: 5 0.00)	

Denver Division - Utah

T9S-R22E Sec 26

CWU 1541-1546 26D (Pad D1_CWU 905-26_Set 13)

1544-26D

Wellbore #1

Plan: APD

Standard Planning Report

21 September, 2010

EOG RESOURCES INC.

Planning Report

Database:	EDM	Local Co-ordinate Reference:	Well 1544-26D
Company:	Denver Division - Utah	TVD Reference:	RIG @ 5034.00ft (True 34)
Project:	T9S-R22E Sec 26	MD Reference:	RIG @ 5034.00ft (True 34)
Site:	CWU 1541-1546 26D (Pad D1_CWU 905-26_Se	North Reference:	True
Well:	1544-26D	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	APD		

Project	T9S-R22E Sec 26		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah North 4301		

Site	CWU 1541-1546 26D (Pad D1_CWU 905-26_Set 13)				
Site Position:		Northing:	-109,625.48ft	Latitude:	40° 0' 46.480 N
From:	Lat/Long	Easting:	2,588,631.00ft	Longitude:	109° 23' 55.748 W
Position Uncertainty:	0.00 ft	Slot Radius:	"	Grid Convergence:	1.39 deg

Well	1544-26D					
Well Position	+N/-S	0.00 ft	Northing:	-109,577.33 ft	Latitude:	40° 0' 46.958 N
	+E/-W	0.00 ft	Easting:	2,588,618.06 ft	Longitude:	109° 23' 55.900 W
Position Uncertainty	0.00 ft		Wellhead Elevation:	ft	Ground Level:	5,015.00 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (deg)	Dip Angle (deg)	Field Strength (nT)
	IGRF200510	9/21/2009	11.24	65.95	52,552

Design	APD			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (deg)
	0.00	0.00	0.00	188.63

Plan Sections										
Measured Depth (ft)	Inclination (deg)	Azimuth (deg)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (deg)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,666.67	19.00	188.63	1,643.58	-205.75	-31.23	1.50	1.50	0.00	188.63	
2,531.37	19.00	188.63	2,461.17	-484.08	-73.47	0.00	0.00	0.00	0.00	
4,431.38	0.00	0.00	4,326.55	-792.70	-120.31	1.00	-1.00	0.00	180.00	
7,104.83	0.00	0.00	7,000.00	-792.70	-120.31	0.00	0.00	0.00	0.00	CWU 1544-26D
9,414.83	0.00	0.00	9,310.00	-792.70	-120.31	0.00	0.00	0.00	0.00	

EOG RESOURCES INC.

Planning Report

Database:	EDM	Local Co-ordinate Reference:	Well 1544-26D
Company:	Denver Division - Utah	TVD Reference:	RIG @ 5034.00ft (True 34)
Project:	T9S-R22E Sec 26	MD Reference:	RIG @ 5034.00ft (True 34)
Site:	CWU 1541-1546 26D (Pad D1_CWU 905-26_Se	North Reference:	True
Well:	1544-26D	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	APD		

Planned Survey

Measured Depth (ft)	Inclination (deg)	Azimuth (deg)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	1.50	188.63	499.99	-1.29	-0.20	1.31	1.50	1.50	0.00
600.00	3.00	188.63	599.91	-5.18	-0.79	5.23	1.50	1.50	0.00
700.00	4.50	188.63	699.69	-11.64	-1.77	11.77	1.50	1.50	0.00
800.00	6.00	188.63	799.27	-20.69	-3.14	20.92	1.50	1.50	0.00
900.00	7.50	188.63	898.57	-32.31	-4.90	32.68	1.50	1.50	0.00
1,000.00	9.00	188.63	997.54	-46.49	-7.06	47.03	1.50	1.50	0.00
1,100.00	10.50	188.63	1,096.09	-63.24	-9.60	63.96	1.50	1.50	0.00
1,200.00	12.00	188.63	1,194.16	-82.52	-12.52	83.47	1.50	1.50	0.00
1,300.00	13.50	188.63	1,291.70	-104.34	-15.84	105.54	1.50	1.50	0.00
1,400.00	15.00	188.63	1,388.62	-128.68	-19.53	130.15	1.50	1.50	0.00
1,500.00	16.50	188.63	1,484.86	-155.52	-23.60	157.30	1.50	1.50	0.00
1,600.00	18.00	188.63	1,580.36	-184.83	-28.05	186.95	1.50	1.50	0.00
1,666.67	19.00	188.63	1,643.58	-205.75	-31.23	208.10	1.50	1.50	0.00
1,700.00	19.00	188.63	1,675.10	-216.48	-32.85	218.96	0.00	0.00	0.00
1,800.00	19.00	188.63	1,769.65	-248.66	-37.74	251.51	0.00	0.00	0.00
1,900.00	19.00	188.63	1,864.20	-280.85	-42.63	284.07	0.00	0.00	0.00
2,000.00	19.00	188.63	1,958.75	-313.04	-47.51	316.63	0.00	0.00	0.00
2,100.00	19.00	188.63	2,053.30	-345.23	-52.40	349.18	0.00	0.00	0.00
2,200.00	19.00	188.63	2,147.86	-377.42	-57.28	381.74	0.00	0.00	0.00
2,300.00	19.00	188.63	2,242.41	-409.61	-62.17	414.30	0.00	0.00	0.00
2,400.00	19.00	188.63	2,336.96	-441.79	-67.05	446.85	0.00	0.00	0.00
2,500.00	19.00	188.63	2,431.51	-473.98	-71.94	479.41	0.00	0.00	0.00
2,531.37	19.00	188.63	2,461.17	-484.08	-73.47	489.62	0.00	0.00	0.00
2,600.00	18.31	188.63	2,526.20	-505.79	-76.76	511.58	1.00	-1.00	0.00
2,700.00	17.31	188.63	2,621.40	-536.03	-81.35	542.17	1.00	-1.00	0.00
2,800.00	16.31	188.63	2,717.12	-564.63	-85.69	571.10	1.00	-1.00	0.00
2,900.00	15.31	188.63	2,813.34	-591.57	-89.78	598.35	1.00	-1.00	0.00
3,000.00	14.31	188.63	2,910.01	-616.85	-93.62	623.91	1.00	-1.00	0.00
3,100.00	13.31	188.63	3,007.12	-640.46	-97.20	647.79	1.00	-1.00	0.00
3,200.00	12.31	188.63	3,104.63	-662.38	-100.53	669.97	1.00	-1.00	0.00
3,300.00	11.31	188.63	3,202.51	-682.62	-103.60	690.44	1.00	-1.00	0.00
3,400.00	10.31	188.63	3,300.73	-701.17	-106.42	709.20	1.00	-1.00	0.00
3,500.00	9.31	188.63	3,399.27	-718.02	-108.98	726.25	1.00	-1.00	0.00
3,600.00	8.31	188.63	3,498.08	-733.17	-111.27	741.57	1.00	-1.00	0.00
3,700.00	7.31	188.63	3,597.15	-746.61	-113.31	755.16	1.00	-1.00	0.00
3,800.00	6.31	188.63	3,696.45	-758.34	-115.09	767.03	1.00	-1.00	0.00
3,900.00	5.31	188.63	3,795.93	-768.36	-116.61	777.16	1.00	-1.00	0.00
4,000.00	4.31	188.63	3,895.58	-776.65	-117.87	785.55	1.00	-1.00	0.00
4,100.00	3.31	188.63	3,995.35	-783.23	-118.87	792.20	1.00	-1.00	0.00
4,200.00	2.31	188.63	4,095.23	-788.08	-119.61	797.11	1.00	-1.00	0.00
4,300.00	1.31	188.63	4,195.18	-791.21	-120.08	800.27	1.00	-1.00	0.00
4,400.00	0.31	188.63	4,295.17	-792.62	-120.30	801.69	1.00	-1.00	0.00
4,431.38	0.00	0.00	4,326.55	-792.70	-120.31	801.78	1.00	-1.00	0.00
4,500.00	0.00	0.00	4,395.17	-792.70	-120.31	801.78	0.00	0.00	0.00
4,600.00	0.00	0.00	4,495.17	-792.70	-120.31	801.78	0.00	0.00	0.00
4,700.00	0.00	0.00	4,595.17	-792.70	-120.31	801.78	0.00	0.00	0.00
4,800.00	0.00	0.00	4,695.17	-792.70	-120.31	801.78	0.00	0.00	0.00
4,900.00	0.00	0.00	4,795.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,000.00	0.00	0.00	4,895.17	-792.70	-120.31	801.78	0.00	0.00	0.00

EOG RESOURCES INC.

Planning Report

Database:	EDM	Local Co-ordinate Reference:	Well 1544-26D
Company:	Denver Division - Utah	TVD Reference:	RIG @ 5034.00ft (True 34)
Project:	T9S-R22E Sec 26	MD Reference:	RIG @ 5034.00ft (True 34)
Site:	CWU 1541-1546 26D (Pad D1_CWU 905-26_Se	North Reference:	True
Well:	1544-26D	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	APD		

Planned Survey

Measured Depth (ft)	Inclination (deg)	Azimuth (deg)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,100.00	0.00	0.00	4,995.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,200.00	0.00	0.00	5,095.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,300.00	0.00	0.00	5,195.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,400.00	0.00	0.00	5,295.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,500.00	0.00	0.00	5,395.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,600.00	0.00	0.00	5,495.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,700.00	0.00	0.00	5,595.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,800.00	0.00	0.00	5,695.17	-792.70	-120.31	801.78	0.00	0.00	0.00
5,900.00	0.00	0.00	5,795.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,000.00	0.00	0.00	5,895.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,100.00	0.00	0.00	5,995.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,200.00	0.00	0.00	6,095.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,300.00	0.00	0.00	6,195.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,400.00	0.00	0.00	6,295.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,500.00	0.00	0.00	6,395.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,600.00	0.00	0.00	6,495.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,700.00	0.00	0.00	6,595.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,800.00	0.00	0.00	6,695.17	-792.70	-120.31	801.78	0.00	0.00	0.00
6,900.00	0.00	0.00	6,795.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,000.00	0.00	0.00	6,895.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,100.00	0.00	0.00	6,995.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,104.83	0.00	0.00	7,000.00	-792.70	-120.31	801.78	0.00	0.00	0.00
CWU 1544-26D									
7,200.00	0.00	0.00	7,095.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,300.00	0.00	0.00	7,195.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,400.00	0.00	0.00	7,295.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,500.00	0.00	0.00	7,395.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,600.00	0.00	0.00	7,495.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,700.00	0.00	0.00	7,595.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,800.00	0.00	0.00	7,695.17	-792.70	-120.31	801.78	0.00	0.00	0.00
7,900.00	0.00	0.00	7,795.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,000.00	0.00	0.00	7,895.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,100.00	0.00	0.00	7,995.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,200.00	0.00	0.00	8,095.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,300.00	0.00	0.00	8,195.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,400.00	0.00	0.00	8,295.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,500.00	0.00	0.00	8,395.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,600.00	0.00	0.00	8,495.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,700.00	0.00	0.00	8,595.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,800.00	0.00	0.00	8,695.17	-792.70	-120.31	801.78	0.00	0.00	0.00
8,900.00	0.00	0.00	8,795.17	-792.70	-120.31	801.78	0.00	0.00	0.00
9,000.00	0.00	0.00	8,895.17	-792.70	-120.31	801.78	0.00	0.00	0.00
9,100.00	0.00	0.00	8,995.17	-792.70	-120.31	801.78	0.00	0.00	0.00
9,200.00	0.00	0.00	9,095.17	-792.70	-120.31	801.78	0.00	0.00	0.00
9,300.00	0.00	0.00	9,195.17	-792.70	-120.31	801.78	0.00	0.00	0.00
9,400.00	0.00	0.00	9,295.17	-792.70	-120.31	801.78	0.00	0.00	0.00
9,414.83	0.00	0.00	9,310.00	-792.70	-120.31	801.78	0.00	0.00	0.00

EOG RESOURCES INC.

Planning Report

Database:	EDM	Local Co-ordinate Reference:	Well 1544-26D
Company:	Denver Division - Utah	TVD Reference:	RIG @ 5034.00ft (True 34)
Project:	T9S-R22E Sec 26	MD Reference:	RIG @ 5034.00ft (True 34)
Site:	CWU 1541-1546 26D (Pad D1_CWU 905-26_Se	North Reference:	True
Well:	1544-26D	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	APD		

Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(deg)	(deg)	(ft)	(ft)	(ft)	(ft)	(ft)		
CWU 1544-26D	0.00	0.00	7,000.00	-792.70	-120.31	-110,372.71	2,588,516.96	40° 0' 39.126 N	109° 23' 57.445 W
- plan hits target center									
- Circle (radius 50.00)									



**Chapita Wells Unit 1541-26D through 1546-26D
Surface Use Plan
Section 26, T9S, R22E
Uintah County, Utah**

EOG Resources, Inc.'s (EOG) conventional oil/gas wells are located approximately 51.3 miles south of Vernal, Utah within Uintah County. This project consists of six (6) new wells to be constructed on the existing well pad for Chapita Wells Unit 905-26, and Chapita Wells Unit 36-26.

The proposed wells are located on federal surface. Title to the oil and gas mineral interest is federally owned and is administered by the Vernal Field Office of the Bureau of Land Management (BLM).

The proposed wells are conventional gas wells producing from the Mesaverde formation. Unproductive drill holes will be plugged and abandoned as soon as evaluation of the production intervals is conclusive.

This project applies to the following new proposed wells.

Well Name & Number	QTR	Section	Township	Range	Total Depth
Chapita Wells Unit 1541-26D	NENE	26	9S	22E	
Chapita Wells Unit 1542-26D	NENE	26	9S	22E	
Chapita Wells Unit 1543-26D	NENE	26	9S	22E	
Chapita Wells Unit 1544-26D	NENE	26	9S	22E	
Chapita Wells Unit 1545-26D	NENE	26	9S	22E	
Chapita Wells Unit 1546-26D	NENE	26	9S	22E	

The proposed action is to directionally drill five conventional gas wells to the Mesaverde formation.

The proposed action involves:

Activity	Length (ft)	Width (ft)	Acres of Disturbance
Existing Disturbance	270	180	2.469
New Disturbance	300	70	0.48
Cut/fills & Topsoil/spoil stockpile	Varies	Varies	
Access Road	Existing	Existing	0
Total New Disturbance			0.48

EOG will build each pad to accommodate up to six wells. The acres of disturbance provided above are the maximum disturbance expected for each pad.

The proposed well locations require the construction of six (6) engineered (cut & fill) well pads. The total surface disturbance associated with the construction of these locations is approximately 2.95 acres. This figure includes disturbance associated with the well pads, the spoil and topsoils storage areas, and the construction equipment and vehicle disturbance.

1. EXISTING ROADS:

Refer to Sheet # 4 and Sheet # 5 for location of existing access roads.

The proposed locations are approximately 50.8 miles from Vernal, Utah.

Directions to the proposed locations are provided on the front page of the location plats.

The existing roads will be maintained in the same or better condition as existed prior to the commencement of operations. Maintenance of the roads to the proposed locations will continue until abandonment and reclamation of the wells.

A federal road right of way is not required, Uintah County roads and authorized Unit roads will be used to access the proposed well site.

2. Access Roads to be Constructed:

No new roads will be required to access the proposed well site.

Roads and associated drainage structures will be maintained in accordance with guidelines contained in the joint BLM/USFS publication: *Surface Operating Standards for Oil and Gas Exploration and Development*, Fourth Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

If existing access road, proposed access road and/or well pad are dry during construction, drilling and/or completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:

Please refer to Topo C for the location of existing wells within a one-mile radius of the proposed wells.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

See the proposed *Production Facility Layout* diagrams showing the proposed production facilities to be utilized on Figure 3.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope.

All permanent (on site for six months or longer) structures constructed or installed (including

pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All facilities will be painted with Carlsbad Canyon.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded

Containment berms will be constructed completely around production facilities designed to hold fluids (i.e., production tanks, produced water tanks, and/or heater/treater). The containment berms will be constructed of compacted subsoil, be sufficiently impervious, hold 110 percent of the capacity of the largest tank, and be independent of the back cut.

All safety measures have been considered in the design, construction, operation, and maintenance of the facility. EOG will have a designated representative present during construction. Any accidents to persons or property on federal lands will immediately be reported to the Authorized Officer.

Production facilities will be set on location if the wells are successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) to eight (8) 400-bbl and one (1) 300-bbl vertical tanks and attaching piping.

Gas gathering lines – A 4" gathering line will be buried from dehy to the edge of the location.

5. LOCATION AND TYPE OF WATER SUPPLY:

Water supply will be Bonanza Power Plant water source in Sec 26, T8S, R23E, Uintah County, UT (State Water Right # 49-225(A31368)).

Water will be hauled by a licensed trucking company.

No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIALS:

Any construction materials that may be required for surfacing of the drill pads and access roads will be obtained from a contractor having a permitted source of materials within the general area.

No construction materials will be removed from Federal or Indian lands without prior approval from the appropriate surface management agency.

7. METHODS OF HANDLING WASTE DISPOSAL:

Cuttings and drilling fluids will be contained within the closed loop system. Cutting will be dried on site hauled to an authorized disposal site and/or spread on the access road and well pad.

Fracture stimulation fluids will be flowed back into (above ground tanks) closed loop system and hauled to a DEQ authorized disposal site

A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at an authorized site.

well. Disposal will be at an authorized site.

All garbage and non-flammable waste materials will be contained in a self-contained, portable dumpster or trash cage. Upon completion of operations, or as needed, the accumulated trash will be transported to a state approved waste disposal site. No trash will be placed in the reserve pit.

Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location. Any open pits will be fenced during drilling operations and said fencing will be maintained until such time as the pits have been backfilled.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

8. ANCILLARY FACILITIES:

None anticipated.

9. WELL SITE LAYOUT:

See the attached diagrams showing the proposed drill pad cross sections and cut and fills in relation to topographic features as well as access onto the pad and soil stockpiles.

All equipment and vehicles will be confined to the approved disturbed areas of this APD (i.e., access road, well pad, and spoil and topsoil storage areas).

If necessary, in order to divert surface runoff, a drainage ditch will be constructed around the upslope side of the well site.

The fill section of the pad that supports the drilling rig and any other heavy equipment will be compacted.

Closed Loop System:

The closed loop system will be installed in a manner that preventing leaks, breaks, or discharge. Drill cutting will be contained in an area approximately 50' x 100'. The surface drill cuttings pile will be bermed and lined with bentonite. Drill cuttings will be dried and spread on location. More stringent protective requirements may be deemed necessary by the A.O.

The closed loop system will be constructed in a way that minimizes the accumulation of

surface precipitation runoff into the cuttings containment area. This may be accomplished by appropriate placement of subsoil/topsoil storage areas and/or construction of berms or ditches.

The closed loop system will be fenced on three sides during drilling operations and the fourth side will be fenced after the drilling rig moves off the location. This fence will be either: (1) woven wire at least 28 inches high and within 4 inches of ground surface with 2 strands of barbed wire above the woven wire with 10 inch spacing, or (2) at least 4 strands of barbed wire spaced, starting from the ground, at approximately 6, 8, 10, and 12 inch intervals.

Siphons, catchments, drip pans, and absorbent pads will be installed to keep hydrocarbons produced by the drilling and/or completion rigs from entering the closed loop system. Hydrocarbons and contaminated pads will be disposed of in accordance with Utah DEQ requirements.

10. PLANS FOR RECLAMATION OF THE SURFACE:

A. Interim Reclamation:

Rat and mouse holes will be filled and compacted from bottom to top immediately upon release of the drilling rig from the location.

Topsoil from the berms and/or storage piles will be spread along the road's cut and fill slopes. Drainage ditches or culverts will not be blocked with topsoil and associated organic matter. The unused area of the pad will be recontoured and topsoil spread six inches deep. The area on the contour will be ripped one foot deep using ripper teeth set on one-foot centers. The topsoil areas and reclaimed area of the well pad will be seeded as stated below.

All disturbed areas will be seeded using a drill equipped with a depth regulator. All seed will be drilled on the contour. The seed will be planted between one-quarter and one-half inch deep. Where drilling is not possible (i.e., too steep or rocky), the seed will be broadcast and the area raked or chained to cover the seed. If the seed mixture is broadcast, the rate will be doubled. EOG will use a seed mixture and application rate approved by the landowners.

Seeding will be done in compliance with EOG's approved reclamation plan. Seeding shall be repeated until a satisfactory stand, as determined by the authorized officer, is obtained. The first evaluation of growth will be made following completion of the first growing season after seeding.

The average size of the pads after reclamation is approximately 1.39 to 2.00 acres (see the attached *Production Facility Layout*).

B. Final Reclamation:

Upon final abandonment of the well, EOG will submit a sundry notice describing the proposed reclamation plan for approval by the Authorized Officer.

Configuration of the re-shaped topography will be returned, as near as possible, to the original condition. Cut and fill slopes will be 3 to 1 or less. All topsoil will be re-stripped from interim reclamation and redistributed over the entire location. The entire location

The reclaimed locations and access roads will be re-seeded with the recommended seed mixture.

Monitoring will be conducted by a qualified Operator representative (in coordination with the BLM) following initial rehabilitation work. Monitoring areas will be re-examined at the end of the first growing season. Results will be documented in a report to the BLM. Problem areas identified during monitoring will receive follow-up rehabilitation/erosion control measures. The seeding shall be repeated until a satisfactory stand, as determined by the authorized officer, is obtained.

11. SURFACE OWNERSHIP:

Surface ownership of the proposed well sites, is as follows:

Bureau of Land Management

12. OTHER INFORMATION:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Weeds will be controlled on disturbed areas within the exterior limits of the access road and well pad. The control methods shall be in accordance with guidelines established by the EPA, BLM, state, and local authorities. Approval will be obtained from the Authorized Officer prior to use of pesticides.

EOG will inform all persons in the area who are associated with this project that they may be subject to prosecution for knowingly disturbing historic or archaeological sites or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials and contact the Authorized officer. If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

A cultural resources survey was conducted and submitted by Montgomery Archaeological Consultants on 7/11/2007. A paleontological survey was conducted and submitted by Intermountain Paleo on 7/11/2007.

LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

PERMITTING AGENT

Kaylene R. Gardner
EOG Resources, Inc.
1060 East Highway 40
Vernal, UT 84078
(435) 781-9111

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

The operator or his/her contractor shall contact the BLM office at (435) 781-4400 forty-eight (48) hours prior to construction activities.

CERTIFICATION:


I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the referenced wells, located in the NENE, of Section 26, T9S, R22E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

6/17/11
Date



Sr. Regulatory Specialist

EOG RESOURCES 11" 5,000 PSI W.P. BOP CONFIGURATION



**EOG RESOURCES CHOKE MANIFOLD CONFIGURATION
W/ 5,000 PSI WP VALVES**

PAGE 2 OF 2



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, **whichever is greater.**
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.

T9S, R22E, S. L. B. & M.

EOG RESOURCES, INC.



Well location, CWU #1544-26D, located as shown in the NE 1/4 NE 1/4 of Section 26, T9S, R22E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 20EAM LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ROBERT L. DRYDEN
 No. 161319
 REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

Revised: 11-16-09 D.R.B.

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

LEGEND:

- 90° SYMBOL
- PROPOSED WELL HEAD.
- SECTION CORNERS LOCATED.
- SECTION CORNERS RE-ESTAB. (Not Set on Ground)



NAD 83 (TARGET BOTTOM HOLE)		NAD 83 (SURFACE LOCATION)	
LATITUDE = 40°00'39.00" (40.010833)	LATITUDE = 40°00'46.84" (40.013011)		
LONGITUDE = 109°23'59.90" (109.399972)	LONGITUDE = 109°23'58.35" (109.399542)		
NAD 27 (TARGET BOTTOM HOLE)		NAD 27 (SURFACE LOCATION)	
LATITUDE = 40°00'39.13" (40.010868)	LATITUDE = 40°00'46.96" (40.013044)		
LONGITUDE = 109°23'57.45" (109.399290)	LONGITUDE = 109°23'55.90" (109.398861)		

SCALE	1" = 1000'	DATE SURVEYED:	10-05-09	DATE DRAWN:	10-22-09
PARTY	G.S. C.R. D.R.B.	REFERENCES	G.L.O. PLAT		
WEATHER	COOL	FILE	EOG RESOURCES, INC.		

API Number: 4304751731
Well Name: Chapita Wells Unit 1544-26D
Township T0.9 . Range R2.2 . Section 26
Meridian: SLBM
Operator: EOG RESOURCES, INC.

Map Prepared:
 Map Produced by Diana Mason

Units STATUS	Wells Query Status
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NP PP OIL	GS - Gas Storage
NP SECONDARY	LA - Location Abandoned
PI OIL	LOC - New Location
PP GAS	OPS - Operation Suspended
PP GEOTHERMAL	PA - Plugged Abandoned
PP OIL	PGW - Producing Gas Well
SECONDARY	POW - Producing Oil Well
TERMINATED	RET - Returned APD
Unknown	SGW - Shut-in Gas Well
ABANDONED	SOW - Shut-in Oil Well
ACTIVE	TA - Temp. Abandoned
COMBINED	TO - Test Well
INACTIVE	WDW - Water Disposal
STORAGE	WIW - Water Injection Well
TERMINATED	WSW - Water Supply Well
Sections	
Township	



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

August 3, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2011 Plan of Development Chapita Wells Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Chapita Wells Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ MESA VERDE)		
43-047-51741	CWU 1543-26D	Sec 26 T09S R22E 0447 FNL 0491 FEL BHL Sec 26 T09S R22E 0857 FNL 0210 FEL
43-047-51731	CWU 1544-26D	Sec 26 T09S R22E 0447 FNL 0501 FEL BHL Sec 26 T09S R22E 1240 FNL 0624 FEL
43-047-51739	CWU 1546-26D	Sec 26 T09S R22E 0445 FNL 0531 FEL BHL Sec 26 T09S R22E 0639 FNL 1255 FEL
43-047-51740	CWU 1545-26D	Sec 26 T09S R22E 0446 FNL 0521 FEL BHL Sec 26 T09S R22E 0923 FNL 0936 FEL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2011.08.03 11:43:26 -06'00'

bcc: File - Chapita Wells Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:8-3-11

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 6/24/2011**API NO. ASSIGNED:** 43047517310000**WELL NAME:** Chapita Wells Unit 1544-26D**OPERATOR:** EOG Resources, Inc. (N9550)**PHONE NUMBER:** 435 781-9145**CONTACT:** Mickenzie Gates**PROPOSED LOCATION:** NENE 26 090S 220E**Permit Tech Review:** **SURFACE:** 0447 FNL 0501 FEL**Engineering Review:** **BOTTOM:** 1240 FNL 0624 FEL**Geology Review:** **COUNTY:** Uintah**LATITUDE:** 40.01307**LONGITUDE:** -109.39879**UTM SURF EASTINGS:** 636659.00**NORTHINGS:** 4430226.00**FIELD NAME:** NATURAL BUTTES**LEASE TYPE:** 1 - Federal**LEASE NUMBER:** UTU0285A**PROPOSED PRODUCING FORMATION(S):** MESA VERDE**SURFACE OWNER:** 1 - Federal**COALBED METHANE:** NO**RECEIVED AND/OR REVIEWED:**

- PLAT
- Bond: FEDERAL - NM2308
- Potash
- Oil Shale 190-5
- Oil Shale 190-3
- Oil Shale 190-13
- Water Permit: 49-225
- RDCC Review:
- Fee Surface Agreement
- Intent to Commingle

Commingle Approved**LOCATION AND SITING:**

- R649-2-3.
- Unit:** CHAPITA WELLS
- R649-3-2. General
- R649-3-3. Exception
- Drilling Unit
- Board Cause No:** Cause 179-08
- Effective Date:** 8/10/1999
- Siting:** Suspends General Siting
- R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason
15 - Directional - dmason
17 - Oil Shale 190-5(b) - dmason



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Chapita Wells Unit 1544-26D
API Well Number: 43047517310000
Lease Number: UTU0285A
Surface Owner: FEDERAL
Approval Date: 8/3/2011

Issued to:

EOG Resources, Inc., 600 17th Street, Suite 1000 N, Denver, CO 80202

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 179-08. The expected producing formation or pool is the MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written in a cursive style.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
SUNDRY NOTICES AND REPORTS ON WELLS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well		8. WELL NAME and NUMBER: CWU 1544-26D
2. NAME OF OPERATOR: EOG Resources, Inc.		9. API NUMBER: 43047517310000
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/8/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
		<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. EOG Resources, Inc. respectfully requests authorization to change the Drilling Plan as per the attached: Float Equipment: Item 5, Mud Program: Item 6 and Cement Program: Item 9.		
NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A		DATE 12/8/2011

5. Float Equipment:

Surface Hole (0' - 2200'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1 in middle of shoe joint, then top of every joint for next 7 joints. (8 total)

Production Hole (2200'± - TD):

Float shoe, 1 joint of casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. 1 turbulizer to be placed 5' above shoe on joint #1 and on the middle of joints #2 & #3. Conventional bow-spring centralizer on top of joint #4, then every 3rd joint to 400' above the top of primary objective. Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole (Surface - 2200'±):

Air/Air mist/Aerated water* (*A standby water source will be available at all times to act as a kill medium when conducting air drilling operations)

or

A closed-loop system utilizing a gelled bentonite mud will be employed.
LCM sweeps, additions, etc. will be used as necessary.

Production Hole (2200'± - TD):

Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15 cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

9. CEMENT PROGRAM:**Surface Hole (Surface - 2200'±):**

Lead: Lead volume to be calculated to bring cement from 500' above casing shoe to surface. Lead cement will be:

130 sx. HES VariCem (Type III) + 2% Cal-Seal (Thixotropic Additive) + 0.3% Versaset (Thixotropic Additive) + 2% Econolite (Light Weight Additive), mixed at 10.5 ppg, 4.10 cfps, 26.88 gps fresh water

Tail: Tail volume to be calculated to bring cement 500' above casing shoe. Tail cement will be:

135 sx. HES HalCem (Type V) + 2% CaCl₂ (Accelerator), mixed at 15.6 ppg, 1.18 cfps, 5.05 gps fresh water

Top Out: As necessary with:

HES HalCem (Type V) + 2% CaCl₂ (Accelerator), mixed at 15.6 ppg, 1.18 cfps, 5.05 gps fresh water

Note: The above number of sacks are calculated based on gauge hole. Final field cement volumes will be based on gauge hole plus 70% excess on the lead slurry and gauge hole plus 100% excess on the tail slurry.

Production Hole (2200'± - TD)

Lead: Lead volume to be calculated to bring cement from 400' above top of Wasatch Formation to 200'± above 9 5/8" surface casing shoe. For improved mud displacement, lead slurry weight will be a minimum of 0.5 ppg over mud weight utilized at well TD and vary from 11.0 – 13.0 ppg.

If lead slurry weight required is 11.0 ppg – 12.5 ppg, cement will be:

HES Highbond 75 (75/25 Poz/G) + 6% Bentonite (Extender) + 0.3% Versaset (Thixotropic Additive) + 2% Microbond (Expansion Additive)

Calculated sacks with corresponding mixed slurry weights, yields and water requirements for above cement will be as follows:

- **210 sx. if 11.0 ppg, 2.52 cfps, 14.96 gps fresh water**
- **245 sx. if 11.5 ppg, 2.12 cfps, 11.98 gps fresh water**
- **285 sx. if 12.0 ppg, 1.83 cfps, 9.82 gps fresh water**
- **325 sx. if 12.5 ppg, 1.61 cfps, 8.17 gps fresh water**

If lead slurry weight required is 13.0 ppg, cement will be:

320 sx. HES ExtendaCem (50/50 Poz/G) + 0.125 pps Pol-E-Flake (Lost Circulation Additive), mixed at 13.0 ppg, 1.63 cfps, 8.16 gps fresh water

Tail: Tail volume to be calculated to bring cement from TD to 400' above top of Wasatch Formation. Tail cement will be:

810 sx. HES ExtendaCem (50/50 Poz/G) + 0.125 pps Pol-E-Flake (Lost Circulation Additive), mixed at 13.5 ppg, 1.47 cfps, 6.98 gps fresh water

Note: The above number of sacks in all cases are calculated based on gauge hole. Final field cement volumes will be based on gauge hole plus 50% excess on the lead slurry and gauge hole plus 70% excess on the tail slurry.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

RECEIVED
JUN 22 2011
BLM Vernal Utah

5. Lease Serial No.
UTU0285A

6. If Indian, Allottee or Tribe Name

1a. Type of work: DRILL REENTER

7. If Unit or CA Agreement, Name and No.
CHAPITA WELLS UNIT

1b. Type of Well: Oil Well Gas Well Other Single Zone Multiple Zone

8. Lease Name and Well No.
CHAPITA WELLS UNIT 1544-26D

2. Name of Operator EOG Resources, Inc.

9. API Well No.
43 047 51731

3a. Address 1060 East Highway 40, Vernal UT 84078

3b. Phone No. (include area code)
435-781-9111

10. Field and Pool, or Exploratory
NATURAL BUTTES

4. Location of Well (Report location clearly and in accordance with any State requirements. *)
At surface (NENE) 447 FNL, 501 FEL, 40.013011 Lat, 109.399542 Lon
At proposed prod. zone (NENE) 1240 FNL, 624 FEL, 40.010868 Lat, 109.99290 Lon

11. Sec., T. R. M. or Blk. and Survey or Area
SEC 26, T9S, R22E, S.L.B.&M.

14. Distance in miles and direction from nearest town or post office*
50.8 MILES FROM VERNAL

12. County or Parish
UINTAH

13. State
UT

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)
624

16. No. of acres in lease
1800

17. Spacing Unit dedicated to this well

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.
620

19. Proposed Depth
9310 TVD, 9415 MD

20. BLM/BIA Bond No. on file
NM2308

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
5015 NAT GL


22. Approximate date work will start*

23. Estimated duration
45 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- 1. Well plat certified by a registered surveyor.
- 2. A Drilling Plan.
- 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- 5. Operator certification
- 6. Such other site specific information and/or plans as may be required by the BLM.

25. Signature 
Name (Printed/Typed) Kaylene R. Gardner
Date 06/16/2011
Title Sr. Regulatory Specialist

Approved by (Signature) 
Name (Printed/Typed) Jerry Kenczka
Date DEC 12 2011
Title Assistant Field Manager
Office VERNAL FIELD OFFICE
Lands & Mineral Resources

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

NOTICE OF APPROVAL

UDOGM

RECEIVED
DEC 14 2011
DIV. OF OIL, GAS & MINING



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: EOG Resources, Inc.
Well No: CWU 1544-26D
API No: 43-047-51731

Location: NENE, Sec. 26, T9S, R22E
Lease No: UTU-0285A
Agreement:

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm ut vn opreport@blm.gov
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.
- Surface pipelines will be placed 5-10 feet outside of the borrow area.
- Monitor the initial ground disturbing construction of the well pad by a qualified permitted paleontologist and thereafter spot-monitor the location during the remainder of the construction process. Report all mitigation-curation of vertebrates and other scientifically significant fossils that may be affected by the construction.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- Cement for the surface casing shall be circulated to surface and/or topped off.
- Gamma ray Log shall be run from Total Depth to Surface.
- Cement for the production casing must be brought to at least 200' above the surface casing shoe.

- **Variations Granted: Air Drilling**
- Properly lubricated and maintained rotating head. Variance granted to use a properly maintained and lubricated diverter bowl in place of a rotating head.
- Blooie line discharge 100' from the well bore. Variations granted for blooie line discharge to be 75' from the well bore and may not be straight.
- Compressors located in the opposite direction from the blooie line a minimum of 100' from the well bore. Variance granted for rig mounted air compressors located within 40' of the well.
- In lieu of mud products on location, operator will have sufficient water on location for the mud kill medium during air drilling operations.
- Automatic igniter. Variance granted for igniter, a diffuser will be used instead. Operator will mount a deflector at the end of the blooie line to change direction and reduce the velocity of the cuttings flow to the reserve pit.
- De-dusting Equipment. Variance granted, dust controlled by water mist during air drilling operations.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.

- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid,

and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU0285A

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
CHAPITA WELLS

1. TYPE OF WELL
Gas Well

8. WELL NAME and NUMBER:
CWU 1544-26D

2. NAME OF OPERATOR:
EOG Resources, Inc.

9. API NUMBER:
43047517310000

3. ADDRESS OF OPERATOR:
1060 East Highway 40 , Vernal, UT, 84078

PHONE NUMBER:
435 781-9111 Ext

9. FIELD and POOL or WILDCAT:
NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE:
0447 FNL 0501 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:
Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S

COUNTY:
UINTAH

STATE:
UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 12/18/2011	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
The referenced well was spud on 12/18/2011.

NAME (PLEASE PRINT) Nanette Lupcho	PHONE NUMBER 435 781-9157	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 12/19/2011	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU0285A

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
CHAPITA WELLS

1. TYPE OF WELL
Gas Well

8. WELL NAME and NUMBER:
CWU 1544-26D

2. NAME OF OPERATOR:
EOG Resources, Inc.

9. API NUMBER:
43047517310000

3. ADDRESS OF OPERATOR:
1060 East Highway 40 , Vernal, UT, 84078

PHONE NUMBER:
435 781-9111 Ext

9. FIELD and POOL or WILDCAT:
NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE:
0447 FNL 0501 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:
Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S

COUNTY:
UINTAH

STATE:
UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/18/2011	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
No activity has occurred since spud on 12/18/2011.

NAME (PLEASE PRINT)
Nanette Lupcho

PHONE NUMBER
435 781-9157

TITLE
Regulatory Assistant

SIGNATURE
N/A

DATE
12/19/2011

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc. Operator Account Number: N 9550
 Address: 1060 East Highway 40
city Vernal
state UT zip 84078 Phone Number: (435) 781-9157

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-51731	CHAPITA WELLS UNIT1544-26D		NENE	26	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>A/B</i>	99999	<i>13650</i>	12/18/2011		<i>12/21/11</i>		
Comments: <u>MESAVERDE</u> <i>BHL = NENE</i>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED

DEC 20 2011

Nanette Lupcho

Name (Please Print)

Signature

Regulatory Assistant

Title

12/19/2011

Date

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1544-26D	
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047517310000	
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S	COUNTY: UINTAH	
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 1/3/2012	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	
<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
No activity has occurred since spud on 12/18/2011 to 01/03/2012.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Nanette Lupcho	PHONE NUMBER 435 781-9157	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 1/3/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1544-26D
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047517310000
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078	PHONE NUMBER: 435 781-9111 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/18/2011	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input checked="" type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. respectfully requests authorization for the disposal of produced water at the following locations: NBU 20-20B SWD, CWU 550-30N SWD & CWU 2-29 SWD ROW# UTU85038, Red Wash Evaporation Ponds 1,2,3,4,5,6&7, White River Evaporation Ponds 1&2, Coyote Evaporation Ponds 1&2, Coyote 1-16 SWD and Hoss SWD Wells ROW# UTU86010 & UTU89701.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY

NAME (PLEASE PRINT) Nanette Lupcho	PHONE NUMBER 435 781-9157	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 12/19/2011	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1544-26D	
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047517310000	
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1000 N , Denver, CO, 80202	PHONE NUMBER: 435 781-9111 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 2/2/2012	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER
	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
<p>The referenced well reached TD on 01/17/2012, please see the attached well chronology report for the referenced well showing all activity up to 02/02/2012.</p>		
<p>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 02, 2012</p>		
NAME (PLEASE PRINT) Nanette Lupcho	PHONE NUMBER 435 781-9157	TITLE Regulatory Assistant
SIGNATURE N/A	DATE 2/2/2012	

06:00 06:00 24.0 0 0 LOCATION IS 85% COMPLETE.

12-23-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$38,700 **Completion** \$0 **Well Total** \$38,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 LOCATION IS 85% COMPLETE. HAULING CLOSED LOOP MATERIAL.

12-26-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$38,700 **Completion** \$0 **Well Total** \$38,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 LOCATION IS 90% COMPLETE. HAULING CLOSED LOOP MATERIAL.

12-27-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$38,700 **Completion** \$0 **Well Total** \$38,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 WAITING ON AIR RIG, HAULING MATERIAL FOR CLOSED LOOP.

12-28-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$38,700 **Completion** \$0 **Well Total** \$38,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 LOCATION IS 100%. FINISH UP CLOSED LOOP TODAY.

01-14-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$17,455 **Completion** \$0 **Daily Total** \$17,455

Cum Costs: Drilling \$56,155 **Completion** \$0 **Well Total** \$56,155

MD 386 **TVD** 386 **Progress** 67 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 386'

Start **End** **Hrs** **From** **To** **Activity Description**

16:00 23:00 7.0 0 0 MURI ON CWU 1544-26D.
 23:00 23:30 0.5 0 0 RIG ON DAY WORK @ 23:00 PM ON 01/13/2012.
 TALLY BHA.
 WELL PREDRILLED FROM 79' TO 319' KOP.
 THIS WELL PLANNED AZIMUTH 188.62*, INC 19.00*.
 MUD MOTOR 1.75 DEGREE BEND, RPG .16, BIT TO BEND 7.08', BIT TO MWD 59'.
 23:30 04:00 4.5 0 0 PICK UP BHA AND ORIENT MWD. TRIP IN HOLE TO 319' KOP.
 04:00 06:00 2.0 319 386 DRILL ROTATE AND SLIDE FROM 319' TO 386'. 67'. ROP 33.5' FPH.
 WOB ROTATE 8K, WOB SLIDE 8K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 600, DIFF PSI 100.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: RIGGING UP.
 FUEL USED 300 GALLONS.

01-15-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$27,756 **Completion** \$0 **Daily Total** \$27,756
Cum Costs: Drilling \$83,911 **Completion** \$0 **Well Total** \$83,911

MD 1,196 **TVD** 1,187 **Progress** 810 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 1196'

Start	End	Hrs	From	To	Activity Description
06:00	18:00	12.0	386	836	DRILL ROTATE AND SLIDE FROM 386' TO 836'. 450'. ROP 37.5' FPH. WOB ROTATE 12K, WOB SLIDE 15K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 900, DIFF PSI 50. 2' LOW AND 5' RIGHT OF LINE. ROTATE 17% SLIDE 83%. TFO 20L.
18:00	06:00	12.0	836	1196	DRILL ROTATE AND SLIDE FROM 836' TO 1196'. 360'. ROP 30' FPH. WOB ROTATE 10K, WOB SLIDE 12K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1000, DIFF PSI 100. 9' HIGH AND 9' RIGHT OF LINE. ROTATE 38% SLIDE 62%. TFO 30L.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: MAKING CONNECTIONS AND PUMP SAFETY.
 FUEL USED 1000 GALLONS.

01-16-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$26,889 **Completion** \$0 **Daily Total** \$26,889
Cum Costs: Drilling \$110,800 **Completion** \$0 **Well Total** \$110,800

MD 1,676 **TVD** 1,651 **Progress** 480 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 1676'

Start	End	Hrs	From	To	Activity Description
06:00	18:00	12.0	1196	1476	DRILL ROTATE AND SLIDE FROM 1196' TO 1476'. 280'. ROP 23' FPH. WOB ROTATE 12K, WOB SLIDE 15K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1000, DIFF PSI 100. 9' HIGH AND 7' RIGHT OF LINE. ROTATE 80% SLIDE 20%. TFO 10R.
18:00	06:00	12.0	1476	1676	DRILL ROTATE AND SLIDE FROM 1476' TO 1676'. 200'. ROP 16.6' FPH.

WOB ROTATE 11K, WOB SLIDE 14K. ROTARY RPM 45, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 4' LOW AND 5' RIGHT OF LINE. ROTATE 70% SLIDE 30%. TFO 0G.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'

NO ACCIDENTS REPORTED.

SAFTEY MEETING: PPE AND SKID STEER SAFETY.

FUEL USED 1350 GALLONS.

01-17-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$27,728 **Completion** \$0 **Daily Total** \$27,728

Cum Costs: Drilling \$138,528 **Completion** \$0 **Well Total** \$138,528

MD 2,066 **TVD** 2,033 **Progress** 390 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 2066'

Start **End** **Hrs** **From** **To** **Activity Description**

06:00	20:00	14.0	1676	2006	DRILL ROTATE AND SLIDE FROM 1676' TO 2006'. 330'. ROP 23.5' FPH. WOB ROTATE 20K, WOB SLIDE 18-20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 26' LOW AND 2' LEFT OF LINE. ROTATE 88% SLIDE 12%. TFO 10R.
20:00	23:30	3.5	0	0	WORK ON PUMP. START CLEANING MUD TANKS WHILE SHUT DOWN WORKING ON PUMP.
23:30	00:30	1.0	0	0	FINISH CLEANING MUD TANKS.
00:30	03:30	3.0	0	0	WORK STUCK PIPE AND CIRCULATE. TRIPPED OFF BOTTOM 150' BEFORE WORKING ON PUMP. ALSO MOVED PIPE EVERY 5-10 MIN WHILE WORKING ON PUMP AND CLEANING TANKS. STARTED PUMPING TO TRIP BACK TO BOTTOM, HAD FULL CIRCULATION BUT COULD NOT MOVE PIPE UP, DOWN, OR ROTATE.
03:30	06:00	2.5	2006	2066	DRILL ROTATE AND SLIDE FROM 2006' TO 2066'. 60'. ROP 24' FPH. WOB ROTATE 20K, WOB SLIDE 18-20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 26' LOW AND 2' LEFT OF LINE. ROTATE 88% SLIDE 12%. TFO 10R.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'

NO ACCIDENTS REPORTED.

SAFTEY MEETING: SLIPS, TRIPS, & FALLS AND HIGH PRESSURE LINES.

FUEL USED 1100 GALLONS.

01-18-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$35,831 **Completion** \$0 **Daily Total** \$35,831

Cum Costs: Drilling \$174,359 **Completion** \$0 **Well Total** \$174,359

MD 2,273 **TVD** 2,233 **Progress** 207 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: TOH

Start **End** **Hrs** **From** **To** **Activity Description**

06:00	09:30	3.5	2066	2096	DRILL ROTATE AND SLIDE FROM 2066' TO 2096'. (TRYING TO SLIDE).
09:30	12:00	2.5	2096	2096	CHANGE OUT UNION AT TOP OF POWER HEAD. (UNION WAS WASHED OUT).
12:00	17:00	5.0	2096	2273	DRILL ROTATE FROM 2096' TO 2273'. 177'. ROP 35' FPH. WOB ROTATE 20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 59' LOW AND 37' LEFT OF LINE. TD @ 17:00 PM ON 01/17/2012.
17:00	18:30	1.5	2273	2273	CIRCULATE FOR WIPER TRIP.
18:30	21:30	3.0	2273	2273	TRIP OUT OF HOLE WITH DIRECTIONAL TOOLS. A FEW TIGHT SPOTS FROM 1466' OUT TO 986'.

21:30	22:30	1.0	2273	2273	WORK ON WINCH LINE ON RIG.
22:30	01:00	2.5	2273	2273	FINISH TRIPPING OUT OF HOLE WITH DIRECTIONAL TOOLS.
01:00	05:00	4.0	2273	2273	TALLY BHA WITH TRI-CONE AND REAMER. TRIP BACK TO BOTTOM.
05:00	06:00	1.0	2273	2273	CIRCULATE TO TRIP OUT OF HOLE AND RUN CASING.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: TRIPPING PIPE AND WINCH LINE SAFTEY.
 FUEL USED 850 GALLONS.

01-19-2012		Reported By		KYLAN COOK							
Daily Costs: Drilling	\$103,203	Completion	\$0	Daily Total	\$103,203						
Cum Costs: Drilling	\$277,562	Completion	\$0	Well Total	\$277,562						
MD	2,273	TVD	2,233	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTB : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: WORT

Start	End	Hrs	From	To	Activity Description
06:00	07:00	1.0	0	0	CIRCULATE TO TRIP OUT OF HOLE AND RUN CASING.
07:00	11:30	4.5	0	0	TRIP OUT OF HOLE TO RUN CASING.
11:30	13:30	2.0	0	0	RIG UP TO RUN CASING.
13:30	18:00	4.5	0	0	RUN 54 JTS (2244.69') OF 9-5/8", 36.0#, K-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 12 CENTRALIZERS SPACED 10' FROM THE SHOE, ON TOP OF JOINTS #2 AND #3 THEN EVERY 5TH COLLAR TO SURFACE. ALSO 2 CENTRALIZERS AT KOP. LANDED @ 2223.69' TVD / 2263.69' MD.
18:00	19:00	1.0	0	0	RUN 200' OF 1" PIPE.
19:00	20:00	1.0	0	0	RDMO CRAIG'S PRESET RIG. RELEASE RIG @ 20:00 PM ON 01/18/12. MOVING TO CWU 1543-26D.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETINGS: TRIPPING PIPE AND RUNNING CASING.
 FUEL USED 150 GALLONS.

20:00	06:00	10.0	0	0	CEMENT JOB: MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 4000 PSIG. PUMPED 30 BBLs FRESH WATER & 20 BBLs GELLED WATER FLUSH AHEAD OF CEMENT.
-------	-------	------	---	---	--

LEAD: MIXED AND PUMPED 250 SACKS (183 BBLs) OF PREMIUM LEAD CEMENT WITH 0.3% VERSASET, 2% CAL-SEAL, AND 2% ECONOLITE. MIXED LEAD CEMENT @ 10.5 PPG WITH YIELD OF 4.1 CF/SX. TAIL: MIXED AND PUMPED 300 SACKS (63 BBLs) OF PREMIUM CEMENT WITH 2% CACL2 MIXED TAIL CEMENT @ 15.6 PPG WITH YIELD OF 1.2 CF/SX. DISPLACED CEMENT WITH 170 BBLs DIRTY WATER. BUMPED PLUG WITH 1000# @ 23:49 PM ON 01/18/12. FLOAT HELD. SHUT-IN CASING VALVE. BROKE CIRCULATION 130 BBLs INTO LEAD CEMENT, LEAD CEMENT TO SURFACE 70 BBLs INTO DISPLACEMENT. CIRCULATED ABOUT 100 BBLs OF LEAD CEMENT TO SURFACE. WOC 1 HR 30 MIN.

TOP JOB #1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 75 SX (15 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. GOOD CEMENT TO SURFACE. HOLE STOOD FULL.

PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.

KYLAN COOK NOTIFIED BLM VIA E-MAIL OF THE SURFACE CASING & CEMENT JOB ON 01/17/12 @ 14:45 PM. KYLAN COOK NOTIFIED CAROL DANIELS WITH UDOGM VIA PHONE OF THE SURFACE CASING & CEMENT JOB ON 01/17/12 @ 14:45 PM.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: EOG Resources, Inc.		7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
3. ADDRESS OF OPERATOR: 1060 East Highway 40 , Vernal, UT, 84078		8. WELL NAME and NUMBER: CWU 1544-26D
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047517310000
PHONE NUMBER: 435 781-9111 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/7/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The referenced well shares a pad with Chapita Wells Unit 1541-26D, 1542-26D, 1543-26D and 1546-26D. Surface casing on the referenced well has been set. Please see the attached well chronology report for the referenced well showing all activity up to 3/7/2012.		
		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 07, 2012
NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A	DATE 3/7/2012	

WELL CHRONOLOGY REPORT

Report Generated On: 03-06-2012

Well Name	CWU 1544-26D	Well Type	DEVG	Division	DENVER
Field	CHAPITA DEEP	API #	43-047-51731	Well Class	DRIL
County, State	UINTAH, UT	Spud Date		Class Date	
Tax Credit	N	TVD / MD	9,310/ 9,415	Property #	066346
Water Depth	0	Last CSG	9.625	Shoe TVD / MD	2,223/ 2,263
KB / GL Elev	5,034/ 5,015				
Location	Section 26-T9S-R22E, NENE, 447 FNL & 501 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	82.139316

AFE No	310498	AFE Total	1,598,100	DHC / CWC	751,800/ 846,300
---------------	--------	------------------	-----------	------------------	------------------

Rig Contr	TRUE	Rig Name	TRUE #34	Start Date	12-01-2011	Release Date	
------------------	------	-----------------	----------	-------------------	------------	---------------------	--

12-01-2011	Reported By	SHARON CAUDILL
-------------------	--------------------	----------------

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
------------------------------	-----	-------------------	-----	--------------------	-----

Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0
----------------------------	-----	-------------------	-----	-------------------	-----

MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
-----------	---	------------	---	-----------------	---	-------------	---	-----------	-----	-------------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
--------------------	-------------------	---------------	------------------------

Activity at Report Time: LOCATION DATA

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	06:00	24.0	0	0	LOCATION DATA 447' FNL & 501' FEL (NE/NE) SECTION 26, T9S, R22E UINTAH COUNTY, UTAH
-------	-------	------	---	---	--

LAT 40 DEG 00' 46.84", LONG 109 DEG 23' 58.35" (NAD 83)

LAT 40 DEG 00' 46.96", LONG 109 DEG 23' 55.90" (NAD 27)

BHL: 1240' FNL & 501' FEL (NENE)

SECTION 26, T9S, R22E

UINTAH COUNTY, UTAH

TRUE #34

OBJECTIVE: 9415' MD, 9310' TVD, MESAVERDE

DW/GAS

CHAPITA WELLS DEEP PROSPECT

DD&A: CHAPITA DEEP

NATURAL BUTTES FIELD

LEASE: FEDERAL UTU0285A

ELEVATION: 5015.3' NAT GL, 5015.3' PREP GL (DUE TO ROUNDING PREP GL IS 5015'), 5034' KB (19')

MULTI PAD CWU 1541-26D, CWU 1542-26DX, CWU 1543-26D, CWU 1544-26D, CWU 1545-26D, CWU 1546-26D

EOG WI 100%, NRI 82.139316%

12-19-2011 **Reported By** GERALD ASHCRAFT/ROBERT WILKINS

DailyCosts: Drilling \$53,700 **Completion** \$0 **Daily Total** \$53,700

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: SPUD NOTIFICATION/LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	60	CRAIG'S BUCKET RIG SPUD A 20" HOLE ON 12/18/11 @ 08:00 AM, SET 60' OF 14" CONDUCTOR. CEMENT TO SURFACE WITH READY MIX.

BLM WAS NOTIFIED BY EMAIL OF SPUD ON 12/16/11 @ 10:58 AM.

06:00 0 0 LOCATION BUILD STARTED 12/16/11. PUSHING ON LOCATION (55% COMPLETE).

12-20-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	LOCATION IS 75% COMPLETE.

12-21-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	LOCATION IS 80% COMPLETE.

12-22-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	LOCATION IS 85% COMPLETE.

12-23-2011 Reported By ROBERT WILKINS

DailyCosts: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$53,700	Completion	\$0	Well Total	\$53,700

MD	60	TVD	60	Progress	0	Days	0	MW	0.0	Visc	0.0
----	----	-----	----	----------	---	------	---	----	-----	------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	06:00	24.0	0	0	LOCATION IS 85% COMPLETE. HAULING CLOSED LOOP MATERIAL.
-------	-------	------	---	---	---

12-26-2011 Reported By ROBERT WILKINS

DailyCosts: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$53,700	Completion	\$0	Well Total	\$53,700

MD	60	TVD	60	Progress	0	Days	0	MW	0.0	Visc	0.0
----	----	-----	----	----------	---	------	---	----	-----	------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	06:00	24.0	0	0	LOCATION IS 90% COMPLETE. HAULING CLOSED LOOP MATERIAL.
-------	-------	------	---	---	---

12-27-2011 Reported By ROBERT WILKINS

DailyCosts: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$53,700	Completion	\$0	Well Total	\$53,700

MD	60	TVD	60	Progress	0	Days	0	MW	0.0	Visc	0.0
----	----	-----	----	----------	---	------	---	----	-----	------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	06:00	24.0	0	0	WAITING ON AIR RIG, HAULING MATERIAL FOR CLOSED LOOP.
-------	-------	------	---	---	---

12-28-2011 Reported By ROBERT WILKINS

DailyCosts: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$53,700	Completion	\$0	Well Total	\$53,700

MD	60	TVD	60	Progress	0	Days	0	MW	0.0	Visc	0.0
----	----	-----	----	----------	---	------	---	----	-----	------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	06:00	24.0	0	0	LOCATION IS 100%. FINISH UP CLOSED LOOP TODAY.
-------	-------	------	---	---	--

01-14-2012 Reported By KYLAN COOK

DailyCosts: Drilling	\$17,455	Completion	\$0	Daily Total	\$17,455
Cum Costs: Drilling	\$71,155	Completion	\$0	Well Total	\$71,155

MD	386	TVD	386	Progress	67	Days	0	MW	0.0	Visc	0.0
----	-----	-----	-----	----------	----	------	---	----	-----	------	-----

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: DRILLING @ 386'

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

16:00	23:00	7.0	0	0	MURI ON CWU 1544-26D.
-------	-------	-----	---	---	-----------------------

23:00 23:30 0.5 0 0 RIG ON DAY WORK @ 23:00 PM ON 01/13/2012.
 TALLY BHA.
 WELL PREDRILLED FROM 79' TO 319' KOP.
 THIS WELL PLANNED AZIMUTH 188.62*, INC 19.00*.
 MUD MOTOR 1.75 DEGREE BEND, RPG .16, BIT TO BEND 7.08', BIT TO MWD 59'.

23:30 04:00 4.5 0 0 PICK UP BHA AND ORIENT MWD. TRIP IN HOLE TO 319' KOP.

04:00 06:00 2.0 319 386 DRILL ROTATE AND SLIDE FROM 319' TO 386'. 67'. ROP 33.5' FPH.
 WOB ROTATE 8K, WOB SLIDE 8K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 600, DIFF PSI 100.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: RIGGING UP.
 FUEL USED 300 GALLONS.

01-15-2012	Reported By	KYLAN COOK									
DailyCosts: Drilling	\$27,756	Completion	\$0	Daily Total	\$27,756						
Cum Costs: Drilling	\$98,911	Completion	\$0	Well Total	\$98,911						
MD	1,196	TVD	1,187	Progress	810	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 1196'											

Start	End	Hrs	From	To	Activity Description
06:00	18:00	12.0	386	836	DRILL ROTATE AND SLIDE FROM 386' TO 836'. 450'. ROP 37.5' FPH. WOB ROTATE 12K, WOB SLIDE 15K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 900, DIFF PSI 50. 2' LOW AND 5' RIGHT OF LINE. ROTATE 17% SLIDE 83%. TFO 20L.
18:00	06:00	12.0	836	1196	DRILL ROTATE AND SLIDE FROM 836' TO 1196'. 360'. ROP 30' FPH. WOB ROTATE 10K, WOB SLIDE 12K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1000, DIFF PSI 100. 9' HIGH AND 9' RIGHT OF LINE. ROTATE 38% SLIDE 62%. TFO 30L.
ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19' NO ACCIDENTS REPORTED. SAFTEY MEETING: MAKING CONNECTIONS AND PUMP SAFETY. FUEL USED 1000 GALLONS.					

01-16-2012	Reported By	KYLAN COOK									
DailyCosts: Drilling	\$26,889	Completion	\$0	Daily Total	\$26,889						
Cum Costs: Drilling	\$125,800	Completion	\$0	Well Total	\$125,800						
MD	1,676	TVD	1,651	Progress	480	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 1676'											

Start	End	Hrs	From	To	Activity Description
06:00	18:00	12.0	1196	1476	DRILL ROTATE AND SLIDE FROM 1196' TO 1476'. 280'. ROP 23' FPH. WOB ROTATE 12K, WOB SLIDE 15K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1000, DIFF PSI 100. 9' HIGH AND 7' RIGHT OF LINE. ROTATE 80% SLIDE 20%. TFO 10R.
18:00	06:00	12.0	1476	1676	DRILL ROTATE AND SLIDE FROM 1476' TO 1676'. 200'. ROP 16.6' FPH. WOB ROTATE 11K, WOB SLIDE 14K. ROTARY RPM 45, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 4' LOW AND 5' RIGHT OF LINE. ROTATE 70% SLIDE 30%. TFO 0G.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: PPE AND SKID STEER SAFETY.
 FUEL USED 1350 GALLONS.

01-17-2012		Reported By		KYLAN COOK							
DailyCosts: Drilling	\$27,728	Completion	\$0	Daily Total	\$27,728						
Cum Costs: Drilling	\$153,528	Completion	\$0	Well Total	\$153,528						
MD	2,066	TVD	2,033	Progress	390	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: DRILLING @ 2066'											
Start	End	Hrs	From	To	Activity Description						
06:00	20:00	14.0	1676	2006	DRILL ROTATE AND SLIDE FROM 1676' TO 2006'. 330'. ROP 23.5' FPH. WOB ROTATE 20K, WOB SLIDE 18-20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 26' LOW AND 2' LEFT OF LINE. ROTATE 88% SLIDE 12%. TFO 10R.						
20:00	23:30	3.5	0	0	WORK ON PUMP. START CLEANING MUD TANKS WHILE SHUT DOWN WORKING ON PUMP.						
23:30	00:30	1.0	0	0	FINISH CLEANING MUD TANKS.						
00:30	03:30	3.0	0	0	WORK STUCK PIPE AND CIRCULATE. TRIPPED OFF BOTTOM 150' BEFORE WORKING ON PUMP. ALSO MOVED PIPE EVERY 5-10 MIN WHILE WORKING ON PUMP AND CLEANING TANKS. STARTED PUMPING TO TRIP BACK TO BOTTOM, HAD FULL CIRCULATION BUT COULD NOT MOVE PIPE UP, DOWN, OR ROTATE.						
03:30	06:00	2.5	2006	2066	DRILL ROTATE AND SLIDE FROM 2006' TO 2066'. 60'. ROP 24' FPH. WOB ROTATE 20K, WOB SLIDE 18-20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 26' LOW AND 2' LEFT OF LINE. ROTATE 88% SLIDE 12%. TFO 10R.						

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: SLIPS, TRIPS, & FALLS AND HIGH PRESSURE LINES.
 FUEL USED 1100 GALLONS.

01-18-2012		Reported By		KYLAN COOK							
DailyCosts: Drilling	\$35,831	Completion	\$0	Daily Total	\$35,831						
Cum Costs: Drilling	\$189,359	Completion	\$0	Well Total	\$189,359						
MD	2,273	TVD	2,233	Progress	207	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						
Activity at Report Time: TOH											
Start	End	Hrs	From	To	Activity Description						
06:00	09:30	3.5	2066	2096	DRILL ROTATE AND SLIDE FROM 2066' TO 2096'. (TRYING TO SLIDE).						
09:30	12:00	2.5	2096	2096	CHANGE OUT UNION AT TOP OF POWER HEAD. (UNION WAS WASHED OUT).						
12:00	17:00	5.0	2096	2273	DRILL ROTATE FROM 2096' TO 2273'. 177'. ROP 35' FPH. WOB ROTATE 20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 59' LOW AND 37' LEFT OF LINE. TD @ 17:00 PM ON 01/17/2012.						
17:00	18:30	1.5	2273	2273	CIRCULATE FOR WIPER TRIP.						
18:30	21:30	3.0	2273	2273	TRIP OUT OF HOLE WITH DIRECTIONAL TOOLS. A FEW TIGHT SPOTS FROM 1466' OUT TO 986'.						
21:30	22:30	1.0	2273	2273	WORK ON WINCH LINE ON RIG.						
22:30	01:00	2.5	2273	2273	FINISH TRIPPING OUT OF HOLE WITH DIRECTIONAL TOOLS.						

01:00 05:00 4.0 2273 2273 TALLY BHA WITH TRI-CONE AND REAMER. TRIP BACK TO BOTTOM.
 05:00 06:00 1.0 2273 2273 CIRCULATE TO TRIP OUT OF HOLE AND RUN CASING.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: TRIPPING PIPE AND WINCH LINE SAFTEY.
 FUEL USED 850 GALLONS.

01-19-2012	Reported By	KYLAN COOK									
Daily Costs: Drilling	\$108,610	Completion	\$0	Daily Total	\$108,610						
Cum Costs: Drilling	\$297,969	Completion	\$0	Well Total	\$297,969						
MD	2,273	TVD	2,233	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: WORT

Start	End	Hrs	From	To	Activity Description
06:00	07:00	1.0	0	0	CIRCULATE TO TRIP OUT OF HOLE AND RUN CASING.
07:00	11:30	4.5	0	0	TRIP OUT OF HOLE TO RUN CASING.
11:30	13:30	2.0	0	0	RIG UP TO RUN CASING.
13:30	18:00	4.5	0	0	RUN 54 JTS (2244.69') OF 9-5/8", 36.0#, K-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 12 CENTRALIZERS SPACED 10' FROM THE SHOE, ON TOP OF JOINTS #2 AND #3 THEN EVERY 5TH COLLAR TO SURFACE. ALSO 2 CENTRALIZERS AT KOP. LANDED @ 2223.69' TVD / 2263.69' MD.
18:00	19:00	1.0	0	0	RUN 200' OF 1" PIPE.
19:00	20:00	1.0	0	0	RDMO CRAIG'S PRESET RIG. RELEASE RIG @ 20:00 PM ON 01/18/12. MOVING TO CWU 1543-26D.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETINGS: TRIPPING PIPE AND RUNNING CASING.
 FUEL USED 150 GALLONS.

20:00 06:00 10.0 0 0 CEMENT JOB: MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 4000 PSIG. PUMPED 30 BBLS FRESH WATER & 20 BBLS GELLED WATER FLUSH AHEAD OF CEMENT.

LEAD: MIXED AND PUMPED 250 SACKS (183 BBLS) OF PREMIUM LEAD CEMENT WITH 0.3% VERSASET, 2% CAL-SEAL, AND 2% ECONOLITE. MIXED LEAD CEMENT @ 10.5 PPG WITH YIELD OF 4.1 CF/SX. TAIL: MIXED AND PUMPED 300 SACKS (63 BBLS) OF PREMIUM CEMENT WITH 2% CACL2 MIXED TAIL CEMENT @ 15.6 PPG WITH YIELD OF 1.2 CF/SX. DISPLACED CEMENT WITH 170 BBLS DIRTY WATER. BUMPED PLUG WITH 1000# @ 23:49 PM ON 01/18/12. FLOAT HELD. SHUT-IN CASING VALVE. BROKE CIRCULATION 130 BBLS INTO LEAD CEMENT, LEAD CEMENT TO SURFACE 70 BBLS INTO DISPLACEMENT. CIRCULATED ABOUT 100 BBLS OF LEAD CEMENT TO SURFACE. WOC 1 HR 30 MIN.

TOP JOB #1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 75 SX (15 BBLS) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. GOOD CEMENT TO SURFACE. HOLE STOOD FULL.

PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.

KYLAN COOK NOTIFIED BLM VIA E-MAIL OF THE SURFACE CASING & CEMENT JOB ON
01/17/12 @ 14:45 PM. KYLAN COOK NOTIFIED CAROL DANIELS WITH UDOGM VIA PHONE OF
THE SURFACE CASING & CEMENT JOB ON 01/17/12 @ 14:45 PM.

BLM - Vernal Field Office - Notification Form

Operator EOG RESOURCES Rig Name/# TRUE 34
 Submitted By JOHNNY TURNER Phone Number 877-352-0710
 Well Name/Number CWU 1544-26D
 Qtr/Qtr NE/NE Section 26 Township 9S Range 22E
 Lease Serial Number UTU0285A
 API Number 43-047-51731

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time _____ AM PM

Casing – Please report time casing run starts, not cementing times.

- Surface Casing
 Intermediate Casing
 Production Casing
 Liner
 Other

RECEIVED

MAR 20 2012

DIV. OF OIL, GAS & MINING

Date/Time 3-16-2012 16:00 AM PM

BOPE

- Initial BOPE test at surface casing point
 BOPE test at intermediate casing point
 30 day BOPE test
 Other

Date/Time _____ AM PM

Remarks Approximate Time.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
2. NAME OF OPERATOR: EOG Resources, Inc.		8. WELL NAME and NUMBER: CWU 1544-26D
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1000 N , Denver, CO, 80202		9. API NUMBER: 43047517310000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 4/25/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well reached TD on 3-16-12, waiting on completion operations. Please see the attached well chronology.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
May 09, 2012**

NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A	DATE 4/25/2012	

KYLAN COOK NOTIFIED BLM VIA E-MAIL OF THE SURFACE CASING & CEMENT JOB ON 01/17/12 @ 14:45 PM. KYLAN COOK NOTIFIED CAROL DANIELS WITH UDOGM VIA PHONE OF THE SURFACE CASING & CEMENT JOB ON 01/17/12 @ 14:45 PM.

03-08-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$29,087	Completion	\$0	Daily Total	\$29,087						
Cum Costs: Drilling	\$327,057	Completion	\$0	Well Total	\$327,057						
MD	2,273	TVD	2,233	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :		PKR Depth : 0.0						

Activity at Report Time: RURT

Start	End	Hrs	From	To	Activity Description
22:00	00:00	2.0	0	0	RIG DOWN & SKID BACK 10' TO CWU 1544-26D.
00:00	01:00	1.0	0	0	RIG UP.
01:00	02:00	1.0	0	0	NIPPLE UP BOP. RIG ACCEPTED FOR DAYWORK @ 01:00 3/8/2012.
02:00	06:00	4.0	0	0	TEST UPPER & LOWER KELLY VALVES, FLOOR VALVES, CHOKE VALVES, CHOKE MANIFOLD, CHECK VALVE, PIPE RAMS & BLIND RAMS TO 5000 PSI HIGH, 250 LOW, ANNULAR 2500 PSI HIGH, 250 LOW, CASING 1500 PSI.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING, SKIDDING RIG
 FUEL 4144 GALS., USED 336 GALS.
 TRANSFER 4480 GALS FROM THE CWU 1541-26D

03-09-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$41,792	Completion	\$0	Daily Total	\$41,792						
Cum Costs: Drilling	\$368,849	Completion	\$0	Well Total	\$368,849						
MD	3,400	TVD	3,340	Progress	1,117	Days	1	MW	10.5	Visc	34.0
Formation :	PBTD : 0.0		Perf :		PKR Depth : 0.0						

Activity at Report Time: DRILLING @ 3400'

Start	End	Hrs	From	To	Activity Description
06:00	06:30	0.5	0	0	TEST CASING TO 1500#.
06:30	07:00	0.5	0	0	INSTALL WEAR BUSHING.
07:00	08:00	1.0	0	0	PICK UP DIRECTIONAL TOOLS & OREINT MWD.
08:00	10:00	2.0	0	0	PICK UP HWDP & TRIP IN HOLE W/ DRILLPIPE.
10:00	11:00	1.0	0	0	SLIP & CUT 95' OF DRILLING LINE.
11:00	12:30	1.5	0	0	DRILL CEMENT/FLOAT EQUIP. & 10' OF NEW HOLE.
12:30	13:00	0.5	2273	2283	F.I.T. TO 145# W/ 10.8 MUD WIEGHT= 12.0# ESTIMATED MUD WIEGHT.
13:00	16:30	3.5	2283	2578	ROTATE & SLIDE 2283' - 2578' = 295', ROP 84.3 FPH, WOB 15-25K, RPM 55/65, MM 68, SPP 1325 PSI, DIFF. 200-400, 457 GPM. 82% ROTATE, 18% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327'. SPUD @ 13:00 3/8/12.
16:30	17:00	0.5	0	0	SERVICE RIG.
17:00	06:00	13.0	2578	3400	ROTATE & SLIDE 2578' TO 3400.= 822', ROP 63.2 FPH, WOB 15-25K, RPM 55/65, MM 68, SPP 1525 PSI, DIFF. 200-400, 457 GPM. 62% ROTATE, 38% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327'.

NO INCIDENT NO ACCIDENT
 FULL CREWS

SAFETY MEETING, PICKING UP BHA, OPERATING FORK LIFT
 COM CHECK TRIPPING & DRILLING
 BOP DRILL NIGHT CREW
 FUEL 2800 GALS., USED 1344 GALS.

06:00 0 0 SPUD 7 7/8' SURFACE HOLE @ 13:00 HRS ON 3/8/12.

03-10-2012		Reported By		JOHNNY TURNER							
DailyCosts: Drilling	\$67,082	Completion	\$0	Daily Total	\$67,082						
Cum Costs: Drilling	\$435,931	Completion	\$0	Well Total	\$435,931						
MD	4,820	TVD	4,740	Progress	1,420	Days	2	MW	10.5	Visc	34.0
Formation :		PBTD : 0.0			Perf :		PKR Depth : 0.0				
Activity at Report Time: DRILLING @ 4820'											

Start	End	Hrs	From	To	Activity Description
06:00	16:00	10.0	3400	4136	ROTATE & SLIDE 3400' TO 4136' = 736', ROP 73.6 FPH, WOB 15-25K, RPM 55/65, MM 68, SPP 1750 PSI, DIFF. 200-400, 457 GPM. 82% ROTATE, 18% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327', WASATCH 4705'.
16:00	16:30	0.5	0	0	SERVICE RIG.
16:30	06:00	13.5	4136	4820	ROTATE & SLIDE 4136' TO 4820' = 684', ROP 50.7 FPH, WOB 15-25K, RPM 55/65, MM 68, SPP 2000 PSI, DIFF. 200-400, 457 GPM. 83% ROTATE, 17% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327', WASATCH 4705', CHAPITA WELLS 5298'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING, MIXING CHEMICALS, SERVICING RIG
 COM CHECK DRILLING
 BOP DRILL DAY CREW
 FUEL 8624 GALS USED 1676
 RECIEVED 7500 GALS OF FUEL

03-11-2012		Reported By		JOHNNY TURNER							
DailyCosts: Drilling	\$33,429	Completion	\$0	Daily Total	\$33,429						
Cum Costs: Drilling	\$469,360	Completion	\$0	Well Total	\$469,360						
MD	5,666	TVD	5,586	Progress	846	Days	3	MW	10.6	Visc	34.0
Formation :		PBTD : 0.0			Perf :		PKR Depth : 0.0				
Activity at Report Time: DRILLING @ 5666'											

Start	End	Hrs	From	To	Activity Description
06:00	16:30	10.5	4820	5229	ROTATE & SLIDE 4820' TO 5229' = 409', ROP 38.9 FPH, WOB 15-25K, RPM 55/65, MM 68, SPP 2050 PSI, DIFF. 200-400, 457 GPM. 98% ROTATE, 2% SLIDE, WASATCH 4705', CHAPITA WELLS 5298', BUCK CANYON 5917'.
16:30	17:00	0.5	0	0	SERVICE RIG.
17:00	02:00	9.0	5229	5557	ROTATE & SLIDE TO 5229' TO 5557' = 328', ROP 36.4 FPH, WOB 15-25K, RPM 55/65, MM 67, SPP 2050 PSI, DIFF. 100-350, 450 GPM. 96.5% ROTATE, 3.5% SLIDE, WASATCH 4705', CHAPITA WELLS 5298', BUCK CANYON 5917'. MOVE CLOCK FORWARD FOR DLS.
03:00	06:00	3.0	5557	5666	ROTATE & SLIDE TO 5557' TO 5666' = 109', ROP 36.3 FPH, WOB 15-25K, RPM 55/65, MM 67, SPP 2050 PSI, DIFF. 100-350, 450 GPM. 89.5% ROTATE, 10.5% SLIDE, WASATCH 4705', CHAPITA WELLS 5298', BUCK CANYON 5917'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 COM CHECK DRILLING
 SAFETY MEETING, PROPER LIFTING, USING WINCHED
 FUEL 6944 GALS, USED 1680 GALS.
 LOST 1 HR DUE TO TIME CHANGE.

03-12-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$35,482	Completion	\$0	Daily Total	\$35,482
Cum Costs: Drilling	\$504,842	Completion	\$0	Well Total	\$504,842

MD 6,620 **TVD** 6,540 **Progress** 954 **Days** 4 **MW** 10.7 **Visc** 34.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 6620'

Start	End	Hrs	From	To	Activity Description
06:00	15:30	9.5	5666	6072	ROTATE & SLIDE 5666' TO 6072' = 406', ROP 42.7 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2100 PSI, DIFF. 100-350, 450 GPM. 97% ROTATE, 3% SLIDE,CHAPITA WELLS 5298', BUCK CANYON 5917', NORTH HORN 6698'.
15:30	16:00	0.5	0	0	SERVICE RIG.
16:00	06:00	14.0	6072	6620	ROTATE & SLIDE 6072' TO 6620' = 548', ROP 39.1 FPH, WOB 15-25K, RPM 55/65, MM 67, SPP 2150 PSI, DIFF. 100-350, 446 GPM. 96% ROTATE, 4% SLIDE, BUCK CANYON 5917', NORTH HORN 6698', PRICE RIVER 7025'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING, USING PRESSURE WASHER, CLEANING LIGHT PLANT.
 COM CHECK DRILLING
 FUEL 5152 GALS, USED 1792 GALS.

03-13-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$34,519	Completion	\$4,370	Daily Total	\$38,890
Cum Costs: Drilling	\$539,362	Completion	\$4,370	Well Total	\$543,733

MD 7,260 **TVD** 7,180 **Progress** 640 **Days** 5 **MW** 11.0 **Visc** 36.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7260'

Start	End	Hrs	From	To	Activity Description
06:00	16:30	10.5	6620	6919	ROTATE & SLIDE 6620' TO 6919 = 299', ROP 28.5 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2200 PSI, DIFF. 100-350, 446 GPM. 97% ROTATE, 3% SLIDE, BUCK CANYON 5917', NORTH HORN 6698', PRICE RIVER 7025'.
16:30	17:00	0.5	0	0	SERVICE RIG.
17:00	06:00	13.0	6919	7260	ROTATE & SLIDE 6919' TO 7260' = 341', ROP 26.2 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2200 PSI, DIFF. 80-350, 446 GPM. 97% ROTATE, 3% SLIDE, NORTH HORN 6698', PRICE RIVER 7025', PRICE RIVER MIDDLE 7900'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING, UNLOADING CASING, DRIVING TO & FROM WORK.
 COM CHECK DRILLING.
 FUEL 3420 GALS., USED 1732 GALS.

03-14-2012 Reported By JOHNNY TURNER

DailyCosts: Drilling \$70,569 Completion \$0 Daily Total \$70,569
 Cum Costs: Drilling \$609,932 Completion \$4,370 Well Total \$614,303

MD 8,015 TVD 7,935 Progress 755 Days 6 MW 11.1 Visc 37.0

Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: DRILLING @ 8015'

Start	End	Hrs	From	To	Activity Description
06:00	15:30	9.5	7260	7581	ROTATE & SLIDE 7260' TO 7581' = 321', ROP 33.8 FPH,WOB 15-25K, RPM 55/65, MM 66, SPP 2050 PSI, DIFF. 80-350, 442 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER 7025', PRICE RIVER MIDDLE 7900'.
15:30	16:00	0.5	0	0	SERVICE RIG.
16:00	06:00	14.0	7581	8015	ROTATE & SLIDE 7581' TO 8015 = 434', ROP 31 FPH,WOB 15-25K, RPM 55/65, MM 64, SPP 2150 PSI, DIFF. 80-350, 428 GPM. 97.5% ROTATE, 2.5% SLIDE, PRICE RIVER 7025', PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 COM CHECK DRILLING
 SAFETY MEETING, LAST DAY AWARENESS, LOCK OUT TAG OUT.
 RECIEVED 7200 GALS FUEL
 FUEL 8736 GALS, USED 1884 GALS.

03-15-2012 Reported By JOHNNY TURNER

DailyCosts: Drilling \$55,759 Completion \$2,135 Daily Total \$57,895
 Cum Costs: Drilling \$665,692 Completion \$6,506 Well Total \$672,198

MD 8,682 TVD 8,602 Progress 667 Days 7 MW 11.4 Visc 38.0

Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: TOH

Start	End	Hrs	From	To	Activity Description
06:00	15:00	9.0	8015	8392	ROTATE & SLIDE 8015' TO 8392' = 377', ROP 41.9 FPH,WOB 15-25K, RPM 50/65, MM 64, SPP 2250 PSI, DIFF. 80-350, 428 GPM. 97% ROTATE, 3% SLIDE, PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691'.
15:00	15:30	0.5	0	0	RIG SERVICE.
15:30	04:30	13.0	8392	8682	ROTATE & SLIDE 8392' TO 8682' = 290', ROP 22.3 FPH,WOB 15-25K, RPM 40/65, MM 64, SPP 2250 PSI, DIFF. 80-350, 428 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691', SEGO 9212'.
04:30	05:00	0.5	0	0	CIRCULATE & BUILD SLUG TO TRIP OUT OF HOLE FOR BIT#3.
05:00	06:00	1.0	0	0	PUMP DRY JOB, BLOW DOWN KELLY & TRIP OUT OF HOLE FOR BIT #3.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 COM CHECK DRILLING & TRIPPING
 SAFETY MEETING, MIXING CHEMICALS,LOCK OUT TAG OUT
 FUEL 6954 GALS., USED 1782 GALS

03-16-2012 Reported By JOHNNY TURNER

DailyCosts: Drilling \$35,147 Completion \$268 Daily Total \$35,415

Cum Costs: Drilling	\$700,840	Completion	\$6,774	Well Total	\$707,614						
MD	9,105	TVD	9,025	Progress	423	Days	8	MW	11.5	Visc	38.0
Formation :	PBTD : 0.0		Perf :		PKR Depth : 0.0						

Activity at Report Time: DRILLING @ 9105'

Start	End	Hrs	From	To	Activity Description
06:00	10:00	4.0	0	0	TRIP OUT OF HOLE W/ BIT #3, (WORK TIGHT HOLE FROM 4600' TO 4860')
10:00	11:30	1.5	0	0	LAY DOWN BIT & MUD MOTOR, & MWD & REPROGRAM MWD.(FUNCTION BLIND RAMS)
11:30	17:00	5.5	0	0	PICK UP FRESH MUD MOTOR & BIT, SCRIBE MWD & TRIP IN HOLE (WASH THROUGH BRIDGES @ 6840', 7350' & WASH 30' TO BOTTOM.
17:00	18:30	1.5	8682	8737	ROTATE & SLIDE 8682' TO 8737' = 55', ROP 36.7 FPH,WOB 15-25K, RPM 50/65, MM 62, SPP 2350 PSI, DIFF. 100-250, 411 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691', SEGO 9212'.
18:30	19:00	0.5	0	0	SERVICE RIG.
19:00	06:00	11.0	8737	9105	ROTATE & SLIDE TO 8737' TO 9105' = 368', ROP 33.5 FPH,WOB 15-25K, RPM 50/65, MM 62, SPP 2400 PSI, DIFF. 100-250, 412 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER LOWER 8691', SEGO 9212'.

NO INCIDENT NO ACCIDENT

FULL CREWS

COM CHECK DRILLING & TRIPPING

SAFETY MEETING, MAKING CONNECTIONS, TRIPPING PIPE

FUEL 5700 GALS, USED 1254 GALS.

03-17-2012 Reported By JOHNNY TURNER

Daily Costs: Drilling	\$38,252	Completion	\$0	Daily Total	\$38,252						
Cum Costs: Drilling	\$739,092	Completion	\$6,774	Well Total	\$745,867						
MD	9,391	TVD	9,310	Progress	286	Days	9	MW	12.0	Visc	39.0
Formation :	PBTD : 0.0		Perf :		PKR Depth : 0.0						

Activity at Report Time: PREP TO LD DP

Start	End	Hrs	From	To	Activity Description
06:00	15:30	9.5	9105	9391	ROTATE & SLIDE TO 9105' TO 9391' = 286', ROP 30.1 FPH,WOB 15-25K, RPM 50/65, MM 62, SPP 2375 PSI, DIFF. 100-250, 411 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER LOWER 8691', SEGO 9212'. TD @ 9391' @ 16:00 3/16/2012.
15:30	16:00	0.5	0	0	SERVICE RIG.
16:00	18:30	2.5	0	0	CIRCULATE @ TD (9391') FOR WIPER TRIP.
18:30	22:00	3.5	0	0	PUMP DRY JOB & TRIP OUT OF HOLE FOR WIPER TRIP.
22:00	23:00	1.0	0	0	LAY DOWN DIRECTIONAL TOOLS.
23:00	03:30	4.5	0	0	MAKE UP BIT SUB & BIT & TRIP IN HOLE. FILL PIPE @ 2300', 5173', & 8380'.
03:30	04:00	0.5	0	0	WASH & REAM 50' TO BOTTOM, 10' OF FILL.
04:00	06:00	2.0	0	0	CIRCULATE & CODITION HOLE TO LAY DOWN DRILLPIPE. 15-20' FLARE FOR 20 MIN. W/ BOTTOMS UP.

NO INCIDENT NO ACCIDENT

FULL CREWS

SAFETY MEETING, WORK PLACE SAFETY, TRIPPING & LAYING DOWN TOOLS

COM CHECK DRILLING & TRIPPING

FUEL 3990 GALS, USED 1910 GALS.

03-18-2012 Reported By JOHNNY TURNER

DailyCosts: Drilling \$33,657 Completion \$167,773 Daily Total \$201,431

Cum Costs: Drilling \$772,750 Completion \$174,548 Well Total \$947,298

MD 9,391 TVD 9,310 Progress 0 Days 10 MW 12.0 Visc 39.0

Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: RDRT/WO COMPLETION

Start	End	Hrs	From	To	Activity Description
06:00	11:30	5.5	0	0	LAY DOWN DRILL PIPE & TRIP OUT, STAND BACK 11 STANDS OF DRILL PIPE, HWDP & DRILL COLLARS.
11:30	12:00	0.5	0	0	PULL WEAR BUSHING.
12:00	19:30	7.5	0	0	RUN TOTAL OF 209 JTS OF CASING (207 FULL JTS OF 4.5", 11.6#, N-80, LT&C + 2 MARKER JOINTS 11.6#, P-110, LT&C) AS FOLLOWS: FLOAT SHOE, 1 JT CASING, FLOAT COLLAR, 51 JTS OF CASING, MARKER JOINT, @ TOP OF PRICE RIVER, 60 JTS, CASING, MARKER JOINT, @ 400' ABOVE WASATCH, 95 JTS CASING. RAN 3 TURBILIZERS (5' ABOVE SHOE AND MIDDLE OF JTS #2 & #3) + 1 BOW CENTRALIZER EVERY 3RD JOINT THEREAFTER TO 400' ABOVE WASATCH (TOTAL OF 40) TAG BOTTOM , LAY DOWN TAG JOINT, PICK UP MANDREL & LAND CASING W/ 82K STRING WEIGHT @ 9380'. CASING WENT TO BOTTOM W/ NO HOLE PROBLEMS.
CASING LANDED AS FOLLOWS (DEPTHS SHOWN ARE TOPS OF COMPONENTS UNLESS OTHERWISE STATED): FLOAT SHOE (BOTTOM): 9380' FLOAT COLLAR: 9333' MARKER JOINT: 7007' MARKER JOINT: 4288'					
19:30	23:00	3.5	0	0	CIRCULATE CASING ON BOTTOM, LAST 200 BBLS W/ 0.5 GPT ALDICIDE. 10-15' FLARE FOR 20 MIN.
23:00	01:30	2.5	0	0	TEST LINE TO 7000#, PUMP 20BBLS OF CHEMICAL FLUSH W/ 0.5 GPT XCIDE, 10 FRESH WATER W/ 0.5 GPT XCIDE, PUMP 515 SKS (148 BBLS) OF 12.5#, 1.61 YIELD W/ 4% BENTONITE, 0.3% VERSASET, 0.5% HR-5 OF LEAD CEMENT, 1345 SKS (352 BBLS) OF 13.5#, 1.47 YIELD W/ 0.125 LBM POLY-E-FLAKE OF TAIL CEMENT, DISPLACED W/ 147 BBLS OF FRESH WATER W/ .5 GPT MYACIDE, DISPLACED @ 8 BBLS MIN., SLOWED TO 3 BBLS MIN W/ 137BBLS GONE, FCP 2320#, BUMPED PLUG & PRESSURED UP TO 3330#, BLEED OFF & CHECK FLOAT, FLOATS HELD. FULL RETURNS THROUGH OUT JOB.
01:30	02:30	1.0	0	0	PRESSURE BACK UP TO 1000# & HOLD ON CASING FOR 1 HR.
02:30	03:30	1.0	0	0	REMOVE CEMENT HEAD & LANDING JOINT, INSTALL PACKOFF & TEST TO 5000 PSI.
03:30	04:30	1.0	0	0	RIG DOWN TO MOVE TO CWU 1543-26D.
04:30	06:00	1.5	0	0	NIPPLE DOWN BOP.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING LAYING DOWN DRILLPIPE, RUNNING CASING
 FUEL 3420 GALS, USED 570 GALS
 TRANSFERED 3420 GALS FUEL TO CWU 1543-26D

06:00 0 0 RIG RELEASED @ 06:00 HRS, 3-18-2012.
 CASING POINT COST \$772,751

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Gas Well		7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
2. NAME OF OPERATOR: EOG Resources, Inc.		8. WELL NAME and NUMBER: CWU 1544-26D
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1000 N , Denver, CO, 80202		9. API NUMBER: 43047517310000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 5/21/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Completion operations for the referenced well began on 5-12-12.
Please see the attached well chronology.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
May 21, 2012**

NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A	DATE 5/21/2012	

04-12-2012 Reported By SEARLE

DailyCosts: Drilling \$0 Completion \$16,000 Daily Total \$16,000

Cum Costs: Drilling \$782,231 Completion \$190,548 Well Total \$972,779

MD 9,391 TVD 9,310 Progress 0 Days 11 MW 0.0 Visc 0.0

Formation : PBTBTD : 9318.0 Perf : PKR Depth : 0.0

Activity at Report Time: PREP FOR FRACS

Start End Hrs From To Activity Description

06:00 0 0 MIRU CUTTERS WIRELINE. LOG WITH CBL/CCL/VDL/GR FORM 9317' TO 70'. EST CEMENT TOP @ 1100'. RDWL.

05-12-2012 Reported By MCCURDY

DailyCosts: Drilling \$0 Completion \$205 Daily Total \$205

Cum Costs: Drilling \$782,231 Completion \$190,753 Well Total \$972,984

MD 9,391 TVD 9,310 Progress 0 Days 12 MW 0.0 Visc 0.0

Formation : MESAVERDE PBTBTD : 9318.0 Perf : 8839'-9067' PKR Depth : 0.0

Activity at Report Time: FRAC

Start End Hrs From To Activity Description

06:00 06:00 24.0 0 0 FRAC TANKS PRE MIXED W/BIOCIDE (BE 6) @ 3# PER TANK.

STAGE 1. MIRU CUTTERS WIRELINE & MIRU HALLIBURTON, PERFORATE LPR FROM 9066'-67', 9055'-56', 8992'-93', 8965'-66', 8942'-43', 8911'-12', 8888'-89', 8875'-76', 8865'-66', 8857'-58', 8846'-47', 8839'-40' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 110 GAL OF NALCO 6106, PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCIDE (BACKTRON KW31 @ 2GPT), 592 GAL 16# LINEAR PAD, 7440 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 23775 GAL 16# DELTA 200 W/ 80300# 20/40 SAND @ 2-5 PPG. MTP 5704 PSIG. MTR 50.2 BPM. ATP 4415 PSIG. ATR 48 BPM. ISIP 2694 PSIG. RD HALLIBURTON. SDFN.

05-13-2012 Reported By MCCURDY

DailyCosts: Drilling \$0 Completion \$205 Daily Total \$205

Cum Costs: Drilling \$782,231 Completion \$190,958 Well Total \$973,189

MD 9,391 TVD 9,310 Progress 0 Days 13 MW 0.0 Visc 0.0

Formation : MESAVERDE PBTBTD : 9318.0 Perf : 8436'-9067' PKR Depth : 0.0

Activity at Report Time: FRAC

Start End Hrs From To Activity Description

06:00 06:00 24.0 0 0 STAGE 2. SICP 2106 PSIG. RUWL. SET 6K CFP AT 8820'. PERFORATE MPR/LPR FROM 8802'-03, 8791'-92', 8785'-86', 8774'-75', 8752'-53', 8740'-41', 8696'-97', 8686'-87', 8674'-75', 8653'-54', 8645'-46', 8636'-37' @ 3 SPF & 120 DEG PHASING. RDWL. RU WIDE SPREAD. PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 110 GAL OF NALCO 6106 PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCIDE (BACKTRON KW31 @ 2GPT). 803 GAL 16# LINEAR PAD, 7433 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 35052 GAL 16# DELTA 200 W/120300# 20/40 SAND @ 2-5 PPG. MTP 5506 PSIG. MTR 50.5 BPM. ATP 4129 PSIG. ATR 49.6 BPM. ISIP 3255 PSIG. RD HALLIBURTON.

STAGE 3. RUWL. SET 6K CFP AT 8612'. PERFORATE MPR FROM 8588'-89', 8576'-77', 8567'-68', 8553'-54', 8541'-42', 8526'-27, 8520'-21', 8502'-03, 8475'-76', 8463'-64', 8444'-45', 8436'-37' @ 3 SPF & 120 DEG PHASING. RDWL. RU WIDE SPREAD. PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER. PUMP 110 GAL OF NALCO 6106 PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 718 GAL 16# LINEAR PAD, 7430 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 35491 GAL 16# DELTA 200 W/122300# 20/40 SAND @ 2-5 PPG. MTP 5884 PSIG. MTR 50.9 BPM. ATP 4424 PSIG. ATR 49.3 BPM. ISIP 3085 PSIG. RD HALLIBURTON. SDFN.

05-14-2012 Reported By MCCURDY

Daily Costs: Drilling	\$0	Completion	\$376,787	Daily Total	\$376,787
Cum Costs: Drilling	\$782,231	Completion	\$567,745	Well Total	\$1,349,977

MD	9,391	TVD	9,310	Progress	0	Days	14	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation :	MESAVERDE	PBTD :	9318.0	Perf :	7050'-9067'	PKR Depth :	0.0
--------------------	-----------	---------------	--------	---------------	-------------	--------------------	-----

Activity at Report Time: MIRUSU CLEAN OUT SAND AND DRILL OUT FRAC PLUGS.

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	12:00	6.0	0	0	STAGE 4. INTIAL PRESSURE 1856 PSIG. RUWL. SET 6K CFP AT 8422'. PERFORATE MPR FROM 8401'-02', 8391'-92', 8362'-63', 8353'-54', 8339'-40', 8328'-29', 8314'-15', 8301'-02', 8291'-92', 8276'-77', 8265'-66', 8250'-51' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 750 GAL 16# LINEAR PAD, 7412 GAL 16# LINEAR W/9500# 20/40 SAND @ 1-1.5 PPG, 44403 GAL 16# DELTA 200 W/153800# 20/40 SAND @ 2-5 PPG. MTP 5563 PSIG. MTR 50.3 BPM. ATP 3857 PSIG. ATR 50 BPM. ISIP 3232 PSIG. RD HALLIBURTON.
-------	-------	-----	---	---	--

STAGE 5. RUWL. SET 6K CFP AT 8212'. PERFORATE MPR FROM 8191'-92', 8181'-82', 8166'-67', 8156'-57', 8143'-44', 8128'-29', 8117'-18', 8096'-97', 8081'-82', 8072'-73', 8058'-59', 8038'-39' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 951 GAL 16# LINEAR PAD, 7394 GAL 16# LINEAR W/9500# 20/40 SAND @ 1-1.5 PPG, 53724 GAL 16# DELTA 200 W/186900# 20/40 SAND @ 2-5 PPG. MTP 4924 PSIG. MTR 50.4 BPM. ATP 3541 PSIG. ATR 50 BPM. ISIP 2488 PSIG. RD HALLIBURTON.

STAGE 6. RUWL. SET 6K CFP AT 8014'. PERFORATE UPR/MPR FROM 7994'-95', 7966'-67', 7953'-54', 7909'-10', (7903'-04' MISFIRED), 7891'-92', 7880'-81', 7868'-69', 7849'-50', 7840'-41', 7820'-21', 7795'-96' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 1021 GAL 16# LINEAR PAD, 7427 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 31262 GAL 16# DELTA 200 W/107100# 20/40 SAND @ 2-5 PPG. MTP 5665 PSIG. MTR 50.3 BPM. ATP 4010 PSIG. ATR 49.5 BPM. ISIP 2497 PSIG. RD HALLIBURTON.

STAGE 7. RUWL. SET 6K CFP AT 7770'. PERFORATE UPR FROM 7748'-49', 7736'-37', 7721'-22', 7715'-16', 7699'-7700', 7645'-46', 7616'-17', 7594'-95', 7585'-86', 7574'-75', 7525'-26', 7513'-14' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 740 GAL 16# LINEAR PAD, 7425 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 32205 GAL 16# DELTA 200 W/110000# 20/40 SAND @ 2-5 PPG. MTP 5414 PSIG. MTR 50.4 BPM. ATP 3924 PSIG. ATR 49.9 BPM. ISIP 2670 PSIG. RD HALLIBURTON.

12:00 06:00 18.0 0 0 STAGE 8. RUWL. SET 6K CFP AT 7478'. PERFORATE UPR FROM 7456'-57', 7446'-47', 7435'-36', 7418'-19', 7407'-08', 7393'-94', 7382'-83', 7357'-58', 7348'-49', 7338'-39', 7321'-22', 7292'-93' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 983 GAL 16# LINEAR PAD, 7469 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 27988 GAL 16# DELTA 200 W/95600# 20/40 SAND @ 2-5 PPG. MTP 5930 PSIG. MTR 50.3 BPM. ATP 4361 PSIG. ATR 47.2 BPM. ISIP 2222 PSIG. RD HALLIBURTON.

STAGE 9. RUWL. SET 6K CFP AT 7252'. PERFORATE UPR FROM 7230'-31', 7220'-21', 7210'-11', 7202'-03', 7183'-84', 7131'-32', 7116'-17', 7093'-94', 7084'-85, 7076'-77', 7064'-65', 7050'-51' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 372 GAL 16# LINEAR PAD, 7446 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 36218 GAL 16# DELTA 200 W/124500# 20/40 SAND @ 2-5 PPG. MTP 4545 PSIG. MTR 50.7 BPM. ATP 3455 PSIG. ATR 48.1 BPM. ISIP 1881 PSIG. RD HALLIBURTON.

RUWL. SET 6K CBP AT 7000'. BLED WELL TO 0 PSIG. RDMO CUTTERS WIRELINE & HALIBURTON SERVICES. SWIFN.

05-18-2012	Reported By	BAUSCH / BASTAIN									
Daily Costs: Drilling	\$0	Completion	\$58,712	Daily Total	\$58,712						
Cum Costs: Drilling	\$782,231	Completion	\$626,457	Well Total	\$1,408,689						
MD	9,391	TVD	9,310	Progress	0	Days	15	MW	0.0	Visc	0.0
Formation :	MESAVERDE	PBTD :	9318.0	Perf :	7050'-9067'	PKR Depth :	0.0				

Activity at Report Time: POST FRAC CLEAN OUT

Start	End	Hrs	From	To	Activity Description
18:00	06:00	12.0	0	0	MIRUSU. SICP 0 PSIG. ND FRAC VALVES. NU BOPE. PRESSURE TEST BOP & FLOWLINES TO 2000 PSIG. RIH W/POBS TO CBP @ 7000'. CLEANED OUT & DRILLED OUT PLUGS @ 7000', 7252', 7478', 7770', 8014', 8212' & 8422'.

05-19-2012	Reported By	BAUSCH / BASTAIN									
Daily Costs: Drilling	\$0	Completion	\$21,275	Daily Total	\$21,275						
Cum Costs: Drilling	\$782,231	Completion	\$647,732	Well Total	\$1,429,964						
MD	9,391	TVD	9,310	Progress	0	Days	16	MW	0.0	Visc	0.0
Formation :	MESAVERDE	PBTD :	9318.0	Perf :	7050'-9067'	PKR Depth :	0.0				

Activity at Report Time: PREP TO FLOW TEST

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	DRILLED OUT PLUGS @ 8612' & 8820'. CLEANED OUT TO PBTD @ 9130'. LANDED TBG AT 7716' KB. ND BOPE. NU TREE. PUMPED OFF BIT & SUB. RDMOSU.

TUBING DETAIL LENGTH

PUMP OFF SUB 1.00'
 1 JT 2-3/8 4.7# L-80 TBG 32.67'
 XN NIPPLE 1.30' @ 7681'
 235 JTS 2-3/8 4.7# L-80 TBG 7662.22'
 BELOW KB 19.00'
 LANDED @ 7716.19' KB

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU0285A
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME: CHAPITA WELLS
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: CWU 1544-26D	
2. NAME OF OPERATOR: EOG Resources, Inc.	9. API NUMBER: 43047517310000	
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1000 N , Denver, CO, 80202	PHONE NUMBER: 435 781-9111 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0447 FNL 0501 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 26 Township: 09.0S Range: 22.0E Meridian: S	COUNTY: UINTAH	
	STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/21/2012 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	
		OTHER: <input type="text" value="05/21/2012"/>
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
<p>The referenced well was turned to sales on 05/21/2012. Please see the attached operations summary report for drilling and completion operations performed on the subject well.</p> <div style="text-align: right;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>FOR RECORD ONLY</p> <p>May 23, 2012</p> </div>		
NAME (PLEASE PRINT) Mickenzie Gates	PHONE NUMBER 435 781-9145	TITLE Operations Clerk
SIGNATURE N/A	DATE 5/23/2012	

WELL CHRONOLOGY REPORT

Report Generated On: 05-23-2012

Well Name	CWU 1544-26D	Well Type	DEVG	Division	DENVER
Field	CHAPITA DEEP	API #	43-047-51731	Well Class	1SA
County, State	UINTAH, UT	Spud Date	03-08-2012	Class Date	05-21-2012
Tax Credit	N	TVD / MD	9,310/ 9,415	Property #	066346
Water Depth	0	Last CSG	2.375	Shoe TVD / MD	7,716/ 7,716
KB / GL Elev	5,034/ 5,015				
Location	Section 26-T9S-R22E, NENE, 447 FNL & 501 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	82.139

AFE No	310498	AFE Total	1,598,100	DHC / CWC	751,800/ 846,300						
Rig Contr	POWELL SER. INC	Rig Name	RIG 1	Start Date	05-18-2012	Release Date	05-18-2012				
Rig Contr	TRUE	Rig Name	TRUE #34	Start Date	12-01-2011	Release Date	03-18-2012				
12-01-2011	Reported By	SHARON CAUDILL									
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :		PKR Depth : 0.0						

Activity at Report Time: LOCATION DATA

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	LOCATION DATA
					447' FNL & 501' FEL (NE/NE)
					SECTION 26, T9S, R22E
					UINTAH COUNTY, UTAH
					LAT 40 DEG 00' 46.84", LONG 109 DEG 23' 58.35" (NAD 83)
					LAT 40 DEG 00' 46.96", LONG 109 DEG 23' 55.90" (NAD 27)
					BHL: 1240' FNL & 501' FEL (NENE)
					SECTION 26, T9S, R22E
					UINTAH COUNTY, UTAH
					TRUE #34
					OBJECTIVE: 9415' MD, 9310' TVD, MESAVERDE
					DW/GAS
					CHAPITA WELLS DEEP PROSPECT
					DD&A: CHAPITA DEEP
					NATURAL BUTTES FIELD

LEASE: FEDERAL UTU0285A

ELEVATION: 5015.3' NAT GL, 5015.3' PREP GL (DUE TO ROUNDING PREP GL IS 5015'), 5034' KB (19')

MULTI PAD CWU 1541-26D, CWU 1542-26DX, CWU 1543-26D, CWU 1544-26D, CWU 1545-26D, CWU 1546-26D

EOG WI 100%, NRI 82.139316%

12-19-2011 **Reported By** GERALD ASHCRAFT/ROBERT WILKINS

Daily Costs: Drilling \$53,700 **Completion** \$0 **Daily Total** \$53,700

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD :** 0.0 **Perf :** **PKR Depth :** 0.0

Activity at Report Time: SPUD NOTIFICATION/LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	60	CRAIG'S BUCKET RIG SPUD A 20" HOLE ON 12/18/11 @ 08:00 AM, SET 60' OF 14" CONDUCTOR. CEMENT TO SURFACE WITH READY MIX.

BLM WAS NOTIFIED BY EMAIL OF SPUD ON 12/16/11 @ 10:58 AM.

06:00			0	0	LOCATION BUILD STARTED 12/16/11. PUSHING ON LOCATION (55% COMPLETE).
-------	--	--	---	---	--

12-20-2011 **Reported By** ROBERT WILKINS

Daily Costs: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD :** 0.0 **Perf :** **PKR Depth :** 0.0

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	LOCATION IS 75% COMPLETE.

12-21-2011 **Reported By** ROBERT WILKINS

Daily Costs: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD :** 0.0 **Perf :** **PKR Depth :** 0.0

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	LOCATION IS 80% COMPLETE.

12-22-2011 **Reported By** ROBERT WILKINS

Daily Costs: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD :** 0.0 **Perf :** **PKR Depth :** 0.0

Activity at Report Time: LOCATION BUILD

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00 06:00 24.0 0 0 LOCATION IS 85% COMPLETE.

12-23-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 LOCATION IS 85% COMPLETE. HAULING CLOSED LOOP MATERIAL.

12-26-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 LOCATION IS 90% COMPLETE. HAULING CLOSED LOOP MATERIAL.

12-27-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 WAITING ON AIR RIG, HAULING MATERIAL FOR CLOSED LOOP.

12-28-2011 **Reported By** ROBERT WILKINS

DailyCosts: Drilling \$0 **Completion** \$0 **Daily Total** \$0

Cum Costs: Drilling \$53,700 **Completion** \$0 **Well Total** \$53,700

MD 60 **TVD** 60 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: LOCATION BUILD

Start **End** **Hrs** **From** **To** **Activity Description**

06:00 06:00 24.0 0 0 LOCATION IS 100%. FINISH UP CLOSED LOOP TODAY.

01-14-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$17,455 **Completion** \$0 **Daily Total** \$17,455

Cum Costs: Drilling \$71,155 **Completion** \$0 **Well Total** \$71,155

MD 386 **TVD** 386 **Progress** 67 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 386'

Start **End** **Hrs** **From** **To** **Activity Description**

16:00 23:00 7.0 0 0 MURI ON CWU 1544-26D.
 23:00 23:30 0.5 0 0 RIG ON DAY WORK @ 23:00 PM ON 01/13/2012.
 TALLY BHA.
 WELL PREDRILLED FROM 79' TO 319' KOP.
 THIS WELL PLANNED AZIMUTH 188.62*, INC 19.00*.
 MUD MOTOR 1.75 DEGREE BEND, RPG .16, BIT TO BEND 7.08', BIT TO MWD 59'.
 23:30 04:00 4.5 0 0 PICK UP BHA AND ORIENT MWD. TRIP IN HOLE TO 319' KOP.
 04:00 06:00 2.0 319 386 DRILL ROTATE AND SLIDE FROM 319' TO 386'. 67'. ROP 33.5' FPH.
 WOB ROTATE 8K, WOB SLIDE 8K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 600, DIFF PSI 100.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: RIGGING UP.
 FUEL USED 300 GALLONS.

01-15-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$27,756 **Completion** \$0 **Daily Total** \$27,756
Cum Costs: Drilling \$98,911 **Completion** \$0 **Well Total** \$98,911

MD 1,196 **TVD** 1,187 **Progress** 810 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 1196'

Start	End	Hrs	From	To	Activity Description
06:00	18:00	12.0	386	836	DRILL ROTATE AND SLIDE FROM 386' TO 836'. 450'. ROP 37.5' FPH. WOB ROTATE 12K, WOB SLIDE 15K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 900, DIFF PSI 50. 2' LOW AND 5' RIGHT OF LINE. ROTATE 17% SLIDE 83%. TFO 20L.
18:00	06:00	12.0	836	1196	DRILL ROTATE AND SLIDE FROM 836' TO 1196'. 360'. ROP 30' FPH. WOB ROTATE 10K, WOB SLIDE 12K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1000, DIFF PSI 100. 9' HIGH AND 9' RIGHT OF LINE. ROTATE 38% SLIDE 62%. TFO 30L.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: MAKING CONNECTIONS AND PUMP SAFETY.
 FUEL USED 1000 GALLONS.

01-16-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$26,889 **Completion** \$0 **Daily Total** \$26,889
Cum Costs: Drilling \$125,800 **Completion** \$0 **Well Total** \$125,800

MD 1,676 **TVD** 1,651 **Progress** 480 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 1676'

Start	End	Hrs	From	To	Activity Description
06:00	18:00	12.0	1196	1476	DRILL ROTATE AND SLIDE FROM 1196' TO 1476'. 280'. ROP 23' FPH. WOB ROTATE 12K, WOB SLIDE 15K. ROTARY RPM 40, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1000, DIFF PSI 100. 9' HIGH AND 7' RIGHT OF LINE. ROTATE 80% SLIDE 20%. TFO 10R.
18:00	06:00	12.0	1476	1676	DRILL ROTATE AND SLIDE FROM 1476' TO 1676'. 200'. ROP 16.6' FPH.

WOB ROTATE 11K, WOB SLIDE 14K. ROTARY RPM 45, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 4' LOW AND 5' RIGHT OF LINE. ROTATE 70% SLIDE 30%. TFO 0G.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'

NO ACCIDENTS REPORTED.

SAFTEY MEETING: PPE AND SKID STEER SAFETY.

FUEL USED 1350 GALLONS.

01-17-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$27,728 **Completion** \$0 **Daily Total** \$27,728

Cum Costs: Drilling \$153,528 **Completion** \$0 **Well Total** \$153,528

MD 2,066 **TVD** 2,033 **Progress** 390 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 2066'

Start **End** **Hrs** **From** **To** **Activity Description**

06:00	20:00	14.0	1676	2006	DRILL ROTATE AND SLIDE FROM 1676' TO 2006'. 330'. ROP 23.5' FPH. WOB ROTATE 20K, WOB SLIDE 18-20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 26' LOW AND 2' LEFT OF LINE. ROTATE 88% SLIDE 12%. TFO 10R.
20:00	23:30	3.5	0	0	WORK ON PUMP. START CLEANING MUD TANKS WHILE SHUT DOWN WORKING ON PUMP.
23:30	00:30	1.0	0	0	FINISH CLEANING MUD TANKS.
00:30	03:30	3.0	0	0	WORK STUCK PIPE AND CIRCULATE. TRIPPED OFF BOTTOM 150' BEFORE WORKING ON PUMP. ALSO MOVED PIPE EVERY 5-10 MIN WHILE WORKING ON PUMP AND CLEANING TANKS. STARTED PUMPING TO TRIP BACK TO BOTTOM, HAD FULL CIRCULATION BUT COULD NOT MOVE PIPE UP, DOWN, OR ROTATE.
03:30	06:00	2.5	2006	2066	DRILL ROTATE AND SLIDE FROM 2006' TO 2066'. 60'. ROP 24' FPH. WOB ROTATE 20K, WOB SLIDE 18-20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 26' LOW AND 2' LEFT OF LINE. ROTATE 88% SLIDE 12%. TFO 10R.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'

NO ACCIDENTS REPORTED.

SAFTEY MEETING: SLIPS, TRIPS, & FALLS AND HIGH PRESSURE LINES.

FUEL USED 1100 GALLONS.

01-18-2012 **Reported By** KYLAN COOK

DailyCosts: Drilling \$35,831 **Completion** \$0 **Daily Total** \$35,831

Cum Costs: Drilling \$189,359 **Completion** \$0 **Well Total** \$189,359

MD 2,273 **TVD** 2,233 **Progress** 207 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: TOH

Start **End** **Hrs** **From** **To** **Activity Description**

06:00	09:30	3.5	2066	2096	DRILL ROTATE AND SLIDE FROM 2066' TO 2096'. (TRYING TO SLIDE).
09:30	12:00	2.5	2096	2096	CHANGE OUT UNION AT TOP OF POWER HEAD. (UNION WAS WASHED OUT).
12:00	17:00	5.0	2096	2273	DRILL ROTATE FROM 2096' TO 2273'. 177'. ROP 35' FPH. WOB ROTATE 20K. ROTARY RPM 20, MOTOR RPM 83. PUMP STROKES 136, GPM 517. PSI 1200, DIFF PSI 100. 59' LOW AND 37' LEFT OF LINE. TD @ 17:00 PM ON 01/17/2012.
17:00	18:30	1.5	2273	2273	CIRCULATE FOR WIPER TRIP.
18:30	21:30	3.0	2273	2273	TRIP OUT OF HOLE WITH DIRECTIONAL TOOLS. A FEW TIGHT SPOTS FROM 1466' OUT TO 986'.

21:30	22:30	1.0	2273	2273	WORK ON WINCH LINE ON RIG.
22:30	01:00	2.5	2273	2273	FINISH TRIPPING OUT OF HOLE WITH DIRECTIONAL TOOLS.
01:00	05:00	4.0	2273	2273	TALLY BHA WITH TRI-CONE AND REAMER. TRIP BACK TO BOTTOM.
05:00	06:00	1.0	2273	2273	CIRCULATE TO TRIP OUT OF HOLE AND RUN CASING.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETING: TRIPPING PIPE AND WINCH LINE SAFTEY.
 FUEL USED 850 GALLONS.

01-19-2012		Reported By		KYLAN COOK							
DailyCosts: Drilling		\$108,610		Completion		\$0		Daily Total		\$108,610	
Cum Costs: Drilling		\$297,969		Completion		\$0		Well Total		\$297,969	
MD	2,273	TVD	2,233	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :			PBT D : 0.0			Perf :			PKR Depth : 0.0		

Activity at Report Time: WORT

Start	End	Hrs	From	To	Activity Description
06:00	07:00	1.0	0	0	CIRCULATE TO TRIP OUT OF HOLE AND RUN CASING.
07:00	11:30	4.5	0	0	TRIP OUT OF HOLE TO RUN CASING.
11:30	13:30	2.0	0	0	RIG UP TO RUN CASING.
13:30	18:00	4.5	0	0	RUN 54 JTS (2244.69') OF 9-5/8", 36.0#, K-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 12 CENTRALIZERS SPACED 10' FROM THE SHOE, ON TOP OF JOINTS #2 AND #3 THEN EVERY 5TH COLLAR TO SURFACE. ALSO 2 CENTRALIZERS AT KOP. LANDED @ 2223.69' TVD / 2263.69' MD.
18:00	19:00	1.0	0	0	RUN 200' OF 1" PIPE.
19:00	20:00	1.0	0	0	RDMO CRAIG'S PRESET RIG. RELEASE RIG @ 20:00 PM ON 01/18/12. MOVING TO CWU 1543-26D.

ALL SURVEYS AND DEPTHS ADJUSTED TO TRUE #34 RKB=19'
 NO ACCIDENTS REPORTED.
 SAFTEY MEETINGS: TRIPPING PIPE AND RUNNING CASING.
 FUEL USED 150 GALLONS.

20:00	06:00	10.0	0	0	CEMENT JOB: MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 4000 PSIG. PUMPED 30 BBLs FRESH WATER & 20 BBLs GELLED WATER FLUSH AHEAD OF CEMENT.
-------	-------	------	---	---	--

LEAD: MIXED AND PUMPED 250 SACKS (183 BBLs) OF PREMIUM LEAD CEMENT WITH 0.3% VERSASET, 2% CAL-SEAL, AND 2% ECONOLITE. MIXED LEAD CEMENT @ 10.5 PPG WITH YIELD OF 4.1 CF/SX. TAIL: MIXED AND PUMPED 300 SACKS (63 BBLs) OF PREMIUM CEMENT WITH 2% CACL2 MIXED TAIL CEMENT @ 15.6 PPG WITH YIELD OF 1.2 CF/SX. DISPLACED CEMENT WITH 170 BBLs DIRTY WATER. BUMPED PLUG WITH 1000# @ 23:49 PM ON 01/18/12. FLOAT HELD. SHUT-IN CASING VALVE. BROKE CIRCULATION 130 BBLs INTO LEAD CEMENT, LEAD CEMENT TO SURFACE 70 BBLs INTO DISPLACEMENT. CIRCULATED ABOUT 100 BBLs OF LEAD CEMENT TO SURFACE. WOC 1 HR 30 MIN.

TOP JOB #1: PUMP DOWN 200' OF 1" PIPE. MIXED & PUMPED 75 SX (15 BBLs) OF PREMIUM CEMENT WITH 2% CACL2. MIXED CEMENT @ 15.8 PPG WITH YIELD OF 1.15 CF/SX. GOOD CEMENT TO SURFACE. HOLE STOOD FULL.

PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.

KYLAN COOK NOTIFIED BLM VIA E-MAIL OF THE SURFACE CASING & CEMENT JOB ON 01/17/12 @ 14:45 PM. KYLAN COOK NOTIFIED CAROL DANIELS WITH UDOGM VIA PHONE OF THE SURFACE CASING & CEMENT JOB ON 01/17/12 @ 14:45 PM.

03-08-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$29,087	Completion	\$0	Daily Total	\$29,087
Cum Costs: Drilling	\$327,057	Completion	\$0	Well Total	\$327,057

MD 2,273 **TVD** 2,233 **Progress** 0 **Days** 0 **MW** 0.0 **Visc** 0.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: RURT

Start	End	Hrs	From	To	Activity Description
22:00	00:00	2.0	0	0	RIG DOWN & SKID BACK 10' TO CWU 1544-26D.
00:00	01:00	1.0	0	0	RIG UP.
01:00	02:00	1.0	0	0	NIPPLE UP BOP. RIG ACCEPTED FOR DAYWORK @ 01:00 3/8/2012.
02:00	06:00	4.0	0	0	TEST UPPER & LOWER KELLY VALVES, FLOOR VALVES, CHOKE VALVES, CHOKE MANIFOLD, CHECK VALVE, PIPE RAMS & BLIND RAMS TO 5000 PSI HIGH, 250 LOW, ANNULAR 2500 PSI HIGH, 250 LOW, CASING 1500 PSI.

NO INCIDENT NO ACCIDENT

FULL CREWS

SAFETY MEETING, SKIDDING RIG

FUEL 4144 GALS., USED 336 GALS.

TRANSFER 4480 GALS FROM THE CWU 1541-26D

03-09-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$41,792	Completion	\$0	Daily Total	\$41,792
Cum Costs: Drilling	\$368,849	Completion	\$0	Well Total	\$368,849

MD 3,400 **TVD** 3,340 **Progress** 1,117 **Days** 1 **MW** 10.5 **Visc** 34.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 3400'

Start	End	Hrs	From	To	Activity Description
06:00	06:30	0.5	0	0	TEST CASING TO 1500#.
06:30	07:00	0.5	0	0	INSTALL WEAR BUSHING.
07:00	08:00	1.0	0	0	PICK UP DIRECTIONAL TOOLS & OREINT MWD.
08:00	10:00	2.0	0	0	PICK UP HWDP & TRIP IN HOLE W/ DRILLPIPE.
10:00	11:00	1.0	0	0	SLIP & CUT 95' OF DRILLING LINE.
11:00	12:30	1.5	0	0	DRILL CEMENT/FLOAT EQUIP. & 10' OF NEW HOLE.
12:30	13:00	0.5	2273	2283	F.I.T. TO 145# W/ 10.8 MUD WIEGHT= 12.0# ESTIMATED MUD WIEGHT.
13:00	16:30	3.5	2283	2578	ROTATE & SLIDE 2283' - 2578' = 295', ROP 84.3 FPH, WOB 15-25K, RPM 55/65, MM 68, SPP 1325 PSI, DIFF. 200-400, 457 GPM. 82% ROTATE, 18% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327'. SPUD @ 13:00 3/8/12.
16:30	17:00	0.5	0	0	SERVICE RIG.
17:00	06:00	13.0	2578	3400	ROTATE & SLIDE 2578' TO 3400 = 822', ROP 63.2 FPH, WOB 15-25K, RPM 55/65, MM 68, SPP 1525 PSI, DIFF. 200-400, 457 GPM. 62% ROTATE, 38% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327'.

NO INCIDENT NO ACCIDENT

FULL CREWS

SAFETY MEETING, PICKING UP BHA, OPERATING FORK LIFT

COM CHECK TRIPPING & DRILLING

BOP DRILL NIGHT CREW

FUEL 2800 GALS., USED 1344 GALS.

06:00 0 0 SPUD 7 7/8' SURFACE HOLE @ 13:00 HRS ON 3/8/12.

03-10-2012 Reported By JOHNNY TURNER

DailyCosts: Drilling \$67,082 Completion \$0 Daily Total \$67,082

Cum Costs: Drilling \$435,931 Completion \$0 Well Total \$435,931

MD 4,820 TVD 4,740 Progress 1,420 Days 2 MW 10.5 Visc 34.0

Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: DRILLING @ 4820'

Start End Hrs From To Activity Description

06:00 16:00 10.0 3400 4136 ROTATE & SLIDE 3400' TO 4136' = 736', ROP 73.6 FPH,WOB 15-25K, RPM 55/65, MM 68, SPP 1750 PSI, DIFF. 200-400, 457 GPM. 82% ROTATE, 18% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327', WASATCH 4705'.

16:00 16:30 0.5 0 0 SERVICE RIG.

16:30 06:00 13.5 4136 4820 ROTATE & SLIDE 4136' TO 4820' = 684', ROP 50.7 FPH,WOB 15-25K, RPM 55/65, MM 68, SPP 2000 PSI, DIFF. 200-400, 457 GPM. 83% ROTATE, 17% SLIDE, MAHOGANY OIL SHALE FORMATION TOP 2327', WASATCH 4705', CHAPITA WELLS 5298'.

NO INCIDENT NO ACCIDENT

FULL CREWS

SAFETY MEETING, MIXING CHEMICALS, SERVICING RIG

COM CHECK DRILLING

BOP DRILL DAY CREW

FUEL 8624 GALS USED 1676

RECIEVED 7500 GALS OF FUEL

03-11-2012 Reported By JOHNNY TURNER

DailyCosts: Drilling \$33,429 Completion \$0 Daily Total \$33,429

Cum Costs: Drilling \$469,360 Completion \$0 Well Total \$469,360

MD 5,666 TVD 5,586 Progress 846 Days 3 MW 10.6 Visc 34.0

Formation : PBTB : 0.0 Perf : PKR Depth : 0.0

Activity at Report Time: DRILLING @ 5666'

Start End Hrs From To Activity Description

06:00 16:30 10.5 4820 5229 ROTATE & SLIDE 4820' TO 5229' = 409', ROP 38.9 FPH,WOB 15-25K, RPM 55/65, MM 68, SPP 2050 PSI, DIFF. 200-400, 457 GPM. 98% ROTATE, 2% SLIDE, WASATCH 4705', CHAPITA WELLS 5298', BUCK CANYON 5917'.

16:30 17:00 0.5 0 0 SERVICE RIG.

17:00 02:00 9.0 5229 5557 ROTATE & SLIDE TO 5229' TO 5557' = 328', ROP 36.4 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2050 PSI, DIFF. 100-350, 450 GPM. 96.5% ROTATE, 3.5% SLIDE, WASATCH 4705', CHAPITA WELLS 5298', BUCK CANYON 5917'. MOVE CLOCK FORWARD FOR DLS.

03:00 06:00 3.0 5557 5666 ROTATE & SLIDE TO 5557' TO 5666' = 109', ROP 36.3 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2050 PSI, DIFF. 100-350, 450 GPM. 89.5% ROTATE, 10.5% SLIDE, WASATCH 4705', CHAPITA WELLS 5298', BUCK CANYON 5917'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 COM CHECK DRILLING
 SAFETY MEETING, PROPER LIFTING, USING WINCHED
 FUEL 6944 GALS, USED 1680 GALS.
 LOST 1 HR DUE TO TIME CHANGE.

03-12-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$35,482	Completion	\$0	Daily Total	\$35,482
Cum Costs: Drilling	\$504,842	Completion	\$0	Well Total	\$504,842

MD 6,620 **TVD** 6,540 **Progress** 954 **Days** 4 **MW** 10.7 **Visc** 34.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 6620'

Start	End	Hrs	From	To	Activity Description
06:00	15:30	9.5	5666	6072	ROTATE & SLIDE 5666' TO 6072' = 406', ROP 42.7 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2100 PSI, DIFF. 100-350, 450 GPM. 97% ROTATE, 3% SLIDE,CHAPITA WELLS 5298', BUCK CANYON 5917', NORTH HORN 6698'.
15:30	16:00	0.5	0	0	SERVICE RIG.
16:00	06:00	14.0	6072	6620	ROTATE & SLIDE 6072' TO 6620' = 548', ROP 39.1 FPH, WOB 15-25K, RPM 55/65, MM 67, SPP 2150 PSI, DIFF. 100-350, 446 GPM. 96% ROTATE, 4% SLIDE, BUCK CANYON 5917', NORTH HORN 6698', PRICE RIVER 7025'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING, USING PRESSURE WASHER, CLEANING LIGHT PLANT.
 COM CHECK DRILLING
 FUEL 5152 GALS, USED 1792 GALS.

03-13-2012 **Reported By** JOHNNY TURNER

DailyCosts: Drilling	\$34,519	Completion	\$4,370	Daily Total	\$38,890
Cum Costs: Drilling	\$539,362	Completion	\$4,370	Well Total	\$543,733

MD 7,260 **TVD** 7,180 **Progress** 640 **Days** 5 **MW** 11.0 **Visc** 36.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: DRILLING @ 7260'

Start	End	Hrs	From	To	Activity Description
06:00	16:30	10.5	6620	6919	ROTATE & SLIDE 6620' TO 6919 = 299', ROP 28.5 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2200 PSI, DIFF. 100-350, 446 GPM. 97% ROTATE, 3% SLIDE, BUCK CANYON 5917', NORTH HORN 6698', PRICE RIVER 7025'.
16:30	17:00	0.5	0	0	SERVICE RIG.
17:00	06:00	13.0	6919	7260	ROTATE & SLIDE 6919' TO 7260' = 341', ROP 26.2 FPH,WOB 15-25K, RPM 55/65, MM 67, SPP 2200 PSI, DIFF. 80-350, 446 GPM. 97% ROTATE, 3% SLIDE, NORTH HORN 6698', PRICE RIVER 7025', PRICE RIVER MIDDLE 7900'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING, UNLOADING CASING, DRIVING TO & FROM WORK.
 COM CHECK DRILLING.

FUEL 3420 GALS., USED 1732 GALS.

03-14-2012	Reported By	JOHNNY TURNER									
DailyCosts: Drilling	\$70,569	Completion	\$0	Daily Total	\$70,569						
Cum Costs: Drilling	\$609,932	Completion	\$4,370	Well Total	\$614,303						
MD	8,015	TVD	7,935	Progress	755	Days	6	MW	11.1	Visc	37.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: DRILLING @ 8015'

Start	End	Hrs	From	To	Activity Description
06:00	15:30	9.5	7260	7581	ROTATE & SLIDE 7260' TO 7581' = 321', ROP 33.8 FPH,WOB 15-25K, RPM 55/65, MM 66, SPP 2050 PSI, DIFF. 80-350, 442 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER 7025', PRICE RIVER MIDDLE 7900'.
15:30	16:00	0.5	0	0	SERVICE RIG.
16:00	06:00	14.0	7581	8015	ROTATE & SLIDE 7581' TO 8015 = 434', ROP 31 FPH,WOB 15-25K, RPM 55/65, MM 64, SPP 2150 PSI, DIFF. 80-350, 428 GPM. 97.5% ROTATE, 2.5% SLIDE, PRICE RIVER 7025', PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691'.

NO INCIDENT NO ACCIDENT

FULL CREWS

COM CHECK DRILLING

SAFETY MEETING, LAST DAY AWARENESS, LOCK OUT TAG OUT.

RECIEVED 7200 GALS FUEL

FUEL 8736 GALS, USED 1884 GALS.

03-15-2012	Reported By	JOHNNY TURNER									
DailyCosts: Drilling	\$55,759	Completion	\$2,135	Daily Total	\$57,895						
Cum Costs: Drilling	\$665,692	Completion	\$6,506	Well Total	\$672,198						
MD	8,682	TVD	8,602	Progress	667	Days	7	MW	11.4	Visc	38.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: TOH

Start	End	Hrs	From	To	Activity Description
06:00	15:00	9.0	8015	8392	ROTATE & SLIDE 8015' TO 8392' = 377', ROP 41.9 FPH,WOB 15-25K, RPM 50/65, MM 64, SPP 2250 PSI, DIFF. 80-350, 428 GPM. 97% ROTATE, 3% SLIDE, PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691'.
15:00	15:30	0.5	0	0	RIG SERVICE.
15:30	04:30	13.0	8392	8682	ROTATE & SLIDE 8392' TO 8682' = 290', ROP 22.3 FPH,WOB 15-25K, RPM 40/65, MM 64, SPP 2250 PSI, DIFF. 80-350, 428 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691', SEGO 9212'.
04:30	05:00	0.5	0	0	CIRCULATE & BUILD SLUG TO TRIP OUT OF HOLE FOR BIT#3.
05:00	06:00	1.0	0	0	PUMP DRY JOB, BLOW DOWN KELLY & TRIP OUT OF HOLE FOR BIT #3.

NO INCIDENT NO ACCIDENT

FULL CREWS

COM CHECK DRILLING & TRIPPING

SAFETY MEETING, MIXING CHEMICALS,LOCK OUT TAG OUT

FUEL 6954 GALS., USED 1782 GALS

03-16-2012	Reported By	JOHNNY TURNER							
-------------------	--------------------	---------------	--	--	--	--	--	--	--

DailyCosts: Drilling	\$35,147	Completion	\$268	Daily Total	\$35,415						
Cum Costs: Drilling	\$700,840	Completion	\$6,774	Well Total	\$707,614						
MD	9,105	TVD	9,025	Progress	423	Days	8	MW	11.5	Visc	38.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: DRILLING @ 9105'

Start	End	Hrs	From	To	Activity Description
06:00	10:00	4.0	0	0	TRIP OUT OF HOLE W/ BIT #3, (WORK TIGHT HOLE FROM 4600' TO 4860')
10:00	11:30	1.5	0	0	LAY DOWN BIT & MUD MOTOR, & MWD & REPROGRAM MWD.(FUNCTION BLIND RAMS)
11:30	17:00	5.5	0	0	PICK UP FRESH MUD MOTOR & BIT, SCRIBE MWD & TRIP IN HOLE (WASH THROUGH BRIDGES @ 6840', 7350' & WASH 30' TO BOTTOM.
17:00	18:30	1.5	8682	8737	ROTATE & SLIDE 8682' TO 8737' = 55', ROP 36.7 FPH,WOB 15-25K, RPM 50/65, MM 62, SPP 2350 PSI, DIFF. 100-250, 411 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER MIDDLE 7900', PRICE RIVER LOWER 8691', SEGO 9212'.
18:30	19:00	0.5	0	0	SERVICE RIG.
19:00	06:00	11.0	8737	9105	ROTATE & SLIDE TO 8737' TO 9105' = 368', ROP 33.5 FPH,WOB 15-25K, RPM 50/65, MM 62, SPP 2400 PSI, DIFF. 100-250, 412 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER LOWER 8691', SEGO 9212'.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 COM CHECK DRILLING & TRIPPING
 SAFETY MEETING, MAKING CONNECTIONS, TRIPPING PIPE
 FUEL 5700 GALS, USED 1254 GALS.

03-17-2012 Reported By JOHNNY TURNER

DailyCosts: Drilling	\$38,252	Completion	\$0	Daily Total	\$38,252						
Cum Costs: Drilling	\$739,092	Completion	\$6,774	Well Total	\$745,867						
MD	9,391	TVD	9,310	Progress	286	Days	9	MW	12.0	Visc	39.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0							

Activity at Report Time: PREP TO LD DP

Start	End	Hrs	From	To	Activity Description
06:00	15:30	9.5	9105	9391	ROTATE & SLIDE TO 9105' TO 9391' = 286', ROP 30.1 FPH,WOB 15-25K, RPM 50/65, MM 62, SPP 2375 PSI, DIFF. 100-250, 411 GPM. 100% ROTATE, 0% SLIDE, PRICE RIVER LOWER 8691', SEGO 9212'. TD @ 9391' @ 16:00 3/16/2012.
15:30	16:00	0.5	0	0	SERVICE RIG.
16:00	18:30	2.5	0	0	CIRCULATE @ TD (9391') FOR WIPER TRIP.
18:30	22:00	3.5	0	0	PUMP DRY JOB & TRIP OUT OF HOLE FOR WIPER TRIP.
22:00	23:00	1.0	0	0	LAY DOWN DIRECTIONAL TOOLS.
23:00	03:30	4.5	0	0	MAKE UP BIT SUB & BIT & TRIP IN HOLE. FILL PIPE @ 2300', 5173', & 8380'.
03:30	04:00	0.5	0	0	WASH & REAM 50' TO BOTTOM, 10' OF FILL.
04:00	06:00	2.0	0	0	CIRCULATE & CODITION HOLE TO LAY DOWN DRILLPIPE. 15-20' FLARE FOR 20 MIN. W/ BOTTOMS UP.

NO INCIDENT NO ACCIDENT
 FULL CREWS
 SAFETY MEETING, WORK PLACE SAFETY, TRIPPING & LAYING DOWN TOOLS
 COM CHECK DRILLING & TRIPPING

FUEL 3990 GALS, USED 1910 GALS.

03-18-2012	Reported By	JOHNNY TURNER									
Daily Costs: Drilling	\$43,138	Completion	\$167,773	Daily Total	\$210,912						
Cum Costs: Drilling	\$782,231	Completion	\$174,548	Well Total	\$956,779						
MD	9,391	TVD	9,310	Progress	0	Days	10	MW	12.0	Visc	39.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: RDRT/WO COMPLETION

Start	End	Hrs	From	To	Activity Description
06:00	11:30	5.5	0	0	LAY DOWN DRILL PIPE & TRIP OUT, STAND BACK 11 STANDS OF DRILL PIPE, HWDP & DRILL COLLARS.
11:30	12:00	0.5	0	0	PULL WEAR BUSHING.
12:00	19:30	7.5	0	0	RUN TOTAL OF 209 JTS OF CASING (207 FULL JTS OF 4.5", 11.6#, N-80, LT&C + 2 MARKER JOINTS 11.6#, P-110, LT&C) AS FOLLOWS: FLOAT SHOE, 1 JT CASING, FLOAT COLLAR, 51 JTS OF CASING, MARKER JOINT, @ TOP OF PRICE RIVER, 60 JTS, CASING, MARKER JOINT, @ 400' ABOVE WASATCH, 95 JTS CASING. RAN 3 TURBILIZERS (5' ABOVE SHOE AND MIDDLE OF JTS #2 & #3) + 1 BOW CENTRALIZER EVERY 3RD JOINT THEREAFTER TO 400' ABOVE WASATCH (TOTAL OF 40) TAG BOTTOM , LAY DOWN TAG JOINT, PICK UP MANDREL & LAND CASING W/ 82K STRING WEIGHT @ 9380'. CASING WENT TO BOTTOM W/ NO HOLE PROBLEMS.
CASING LANDED AS FOLLOWS (DEPTHS SHOWN ARE TOPS OF COMPONENTS UNLESS OTHERWISE STATED):					
FLOAT SHOE (BOTTOM): 9380'					
FLOAT COLLAR: 9333'					
MARKER JOINT: 7007'					
MARKER JOINT: 4288'					
19:30	23:00	3.5	0	0	CIRCULATE CASING ON BOTTOM, LAST 200 BBLS W/ 0.5 GPT ALDICIDE. 10-15' FLARE FOR 20 MIN.
23:00	01:30	2.5	0	0	TEST LINE TO 7000#, PUMP 20BBLS OF CHEMICAL FLUSH W/ 0.5 GPT XCIDE, 10 FRESH WATER W/ 0.5 GPT XCIDE, PUMP 515 SKS (148 BBLS) OF 12.5#, 1.61 YIELD W/ 4% BENTONITE, 0.3% VERSASET, 0.5% HR-5 OF LEAD CEMENT, 1345 SKS (352 BBLS) OF 13.5#, 1.47 YIELD W/ 0.125 LBM POLY-E-FLAKE OF TAIL CEMENT, DISPLACED W/ 147 BBLS OF FRESH WATER W/ .5 GPT MYACIDE, DISPLACED @ 8 BBLS MIN., SLOWED TO 3 BBLS MIN W/ 137BBLS GONE, FCP 2320#, BUMPED PLUG & PRESSURED UP TO 3330#, BLEED OFF & CHECK FLOAT, FLOATS HELD. FULL RETURNS THROUGH OUT JOB.
01:30	02:30	1.0	0	0	PRESSURE BACK UP TO 1000# & HOLD ON CASING FOR 1 HR.
02:30	03:30	1.0	0	0	REMOVE CEMENT HEAD & LANDING JOINT, INSTALL PACKOFF & TEST TO 5000 PSI.
03:30	04:30	1.0	0	0	RIG DOWN TO MOVE TO CWU 1543-26D.
04:30	06:00	1.5	0	0	NIPPLE DOWN BOP.

NO INCIDENT NO ACCIDENT

FULL CREWS

SAFETY MEETING LAYING DOWN DRILLPIPE, RUNNING CASING

FUEL 3420 GALS, USED 570 GALS

TRANSFERED 3420 GALS FUEL TO CWU 1543-26D

06:00		0	0	RIG RELEASED @ 06:00 HRS, 3-18-2012.
				CASING POINT COST \$782,232

04-12-2012 Reported By SEARLE

DailyCosts: Drilling	\$0	Completion	\$16,000	Daily Total	\$16,000
Cum Costs: Drilling	\$782,231	Completion	\$190,548	Well Total	\$972,779

MD	9,391	TVD	9,310	Progress	0	Days	11	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation :	PBTD : 9318.0	Perf :	PKR Depth : 0.0
--------------------	----------------------	---------------	------------------------

Activity at Report Time: PREP FOR FRACS

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00			0	0	MIRU CUTTERS WIRELINE. LOG WITH CBL/CCL/VDL/GR FORM 9317' TO 70'. EST CEMENT TOP @ 1100'. RDWL.
-------	--	--	---	---	---

05-12-2012 Reported By MCCURDY

DailyCosts: Drilling	\$0	Completion	\$205	Daily Total	\$205
Cum Costs: Drilling	\$782,231	Completion	\$190,753	Well Total	\$972,984

MD	9,391	TVD	9,310	Progress	0	Days	12	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation : MESAVERDE	PBTD : 9318.0	Perf : 8839'-9067'	PKR Depth : 0.0
------------------------------	----------------------	---------------------------	------------------------

Activity at Report Time: FRAC

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	06:00	24.0	0	0	FRAC TANKS PRE MIXED W/BIOCIDE (BE 6) @ 3# PER TANK.
-------	-------	------	---	---	--

STAGE 1. MIRU CUTTERS WIRELINE & MIRU HALLIBURTON, PERFORATE LPR FROM 9066'-67', 9055'-56', 8992'-93', 8965'-66', 8942'-43', 8911'-12', 8888'-89', 8875'-76', 8865'-66', 8857'-58', 8846'-47', 8839'-40' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 110 GAL OF NALCO 6106, PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCIDE (BACKTRON KW31 @ 2GPT), 592 GAL 16# LINEAR PAD, 7440 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 23775 GAL 16# DELTA 200 W/ 80300# 20/40 SAND @ 2-5 PPG. MTP 5704 PSIG. MTR 50.2 BPM. ATP 4415 PSIG. ATR 48 BPM. ISIP 2694 PSIG. RD HALLIBURTON. SDFN.

05-13-2012 Reported By MCCURDY

DailyCosts: Drilling	\$0	Completion	\$205	Daily Total	\$205
Cum Costs: Drilling	\$782,231	Completion	\$190,958	Well Total	\$973,189

MD	9,391	TVD	9,310	Progress	0	Days	13	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation : MESAVERDE	PBTD : 9318.0	Perf : 8436'-9067'	PKR Depth : 0.0
------------------------------	----------------------	---------------------------	------------------------

Activity at Report Time: FRAC

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	06:00	24.0	0	0	STAGE 2. SICP 2106 PSIG. RUWL. SET 6K CFP AT 8820'. PERFORATE MPR/LPR FROM 8802'-03, 8791'-92', 8785'-86', 8774'-75', 8752'-53', 8740'-41', 8696'-97', 8686'-87', 8674'-75', 8653'-54', 8645'-46', 8636'-37' @ 3 SPF & 120 DEG PHASING. RDWL. RU WIDE SPREAD. PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 110 GAL OF NALCO 6106 PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCIDE (BACKTRON KW31 @ 2GPT). 803 GAL 16# LINEAR PAD, 7433 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 35052 GAL 16# DELTA 200 W/120300# 20/40 SAND @ 2-5 PPG. MTP 5506 PSIG. MTR 50.5 BPM. ATP 4129 PSIG. ATR 49.6 BPM. ISIP 3255 PSIG. RD HALLIBURTON.
-------	-------	------	---	---	---

STAGE 3. RUWL. SET 6K CFP AT 8612'. PERFORATE MPR FROM 8588'-89', 8576'-77', 8567'-68', 8553'-54', 8541'-42', 8526'-27, 8520'-21', 8502'-03, 8475'-76', 8463'-64', 8444'-45', 8436'-37' @ 3 SPF & 120 DEG PHASING. RDWL. RU WIDE SPREAD. PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER. PUMP 110 GAL OF NALCO 6106 PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 718 GAL 16# LINEAR PAD, 7430 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 35491 GAL 16# DELTA 200 W/122300# 20/40 SAND @ 2-5 PPG. MTP 5884 PSIG. MTR 50.9 BPM. ATP 4424 PSIG. ATR 49.3 BPM. ISIP 3085 PSIG. RD HALLIBURTON. SDFN.

05-14-2012 Reported By MCCURDY

Daily Costs: Drilling	\$0	Completion	\$376,787	Daily Total	\$376,787
Cum Costs: Drilling	\$782,231	Completion	\$567,745	Well Total	\$1,349,977

MD	9,391	TVD	9,310	Progress	0	Days	14	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation :	MESAVERDE	PBTD :	9318.0	Perf :	7050'-9067'	PKR Depth :	0.0
--------------------	-----------	---------------	--------	---------------	-------------	--------------------	-----

Activity at Report Time: MIRUSU CLEAN OUT SAND AND DRILL OUT FRAC PLUGS.

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00	12:00	6.0	0	0	STAGE 4. INTIAL PRESSURE 1856 PSIG. RUWL. SET 6K CFP AT 8422'. PERFORATE MPR FROM 8401'-02', 8391'-92', 8362'-63', 8353'-54', 8339'-40', 8328'-29', 8314'-15', 8301'-02', 8291'-92', 8276'-77', 8265'-66', 8250'-51' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 750 GAL 16# LINEAR PAD, 7412 GAL 16# LINEAR W/9500# 20/40 SAND @ 1-1.5 PPG, 44403 GAL 16# DELTA 200 W/153800# 20/40 SAND @ 2-5 PPG. MTP 5563 PSIG. MTR 50.3 BPM. ATP 3857 PSIG. ATR 50 BPM. ISIP 3232 PSIG. RD HALLIBURTON.
-------	-------	-----	---	---	--

STAGE 5. RUWL. SET 6K CFP AT 8212'. PERFORATE MPR FROM 8191'-92', 8181'-82', 8166'-67', 8156'-57', 8143'-44', 8128'-29', 8117'-18', 8096'-97', 8081'-82', 8072'-73', 8058'-59', 8038'-39' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 951 GAL 16# LINEAR PAD, 7394 GAL 16# LINEAR W/9500# 20/40 SAND @ 1-1.5 PPG, 53724 GAL 16# DELTA 200 W/186900# 20/40 SAND @ 2-5 PPG. MTP 4924 PSIG. MTR 50.4 BPM. ATP 3541 PSIG. ATR 50 BPM. ISIP 2488 PSIG. RD HALLIBURTON.

STAGE 6. RUWL. SET 6K CFP AT 8014'. PERFORATE UPR/MPR FROM 7994'-95', 7966'-67', 7953'-54', 7909'-10', (7903'-04' MISFIRED), 7891'-92', 7880'-81', 7868'-69', 7849'-50', 7840'-41', 7820'-21', 7795'-96' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 1021 GAL 16# LINEAR PAD, 7427 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 31262 GAL 16# DELTA 200 W/107100# 20/40 SAND @ 2-5 PPG. MTP 5665 PSIG. MTR 50.3 BPM. ATP 4010 PSIG. ATR 49.5 BPM. ISIP 2497 PSIG. RD HALLIBURTON.

STAGE 7. RUWL. SET 6K CFP AT 7770'. PERFORATE UPR FROM 7748'-49', 7736'-37', 7721'-22', 7715'-16', 7699'-7700', 7645'-46', 7616'-17', 7594'-95', 7585'-86', 7574'-75', 7525'-26', 7513'-14' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLs FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLs FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 740 GAL 16# LINEAR PAD, 7425 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 32205 GAL 16# DELTA 200 W/110000# 20/40 SAND @ 2-5 PPG. MTP 5414 PSIG. MTR 50.4 BPM. ATP 3924 PSIG. ATR 49.9 BPM. ISIP 2670 PSIG. RD HALLIBURTON.

12:00 06:00 18.0 0 0 STAGE 8. RUWL. SET 6K CFP AT 7478'. PERFORATE UPR FROM 7456'-57', 7446'-47', 7435'-36', 7418'-19', 7407'-08', 7393'-94', 7382'-83', 7357'-58', 7348'-49', 7338'-39', 7321'-22', 7292'-93' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 983 GAL 16# LINEAR PAD, 7469 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 27988 GAL 16# DELTA 200 W/95600# 20/40 SAND @ 2-5 PPG. MTP 5930 PSIG. MTR 50.3 BPM. ATP 4361 PSIG. ATR 47.2 BPM. ISIP 2222 PSIG. RD HALLIBURTON.

STAGE 9. RUWL. SET 6K CFP AT 7252'. PERFORATE UPR FROM 7230'-31', 7220'-21', 7210'-11', 7202'-03', 7183'-84', 7131'-32', 7116'-17', 7093'-94', 7084'-85, 7076'-77', 7064'-65', 7050'-51' @ 3 SPF & 120 DEGREE PHASING. RDWL. RU WIDE SPREAD PUMP 165 GAL OF NALCO EC 6707 SCALE INHIBITOR PLUS 5 BBLS FRESH WATER . PUMP 55 GAL OF NALCO 6106, PLUS 5 BBLS FRESH WATER. FRAC LPR DOWN CASING W/15 GAL BIOCID (BACKTRON KW31 @ 2GPT), 372 GAL 16# LINEAR PAD, 7446 GAL 16# LINEAR W/9600# 20/40 SAND @ 1-1.5 PPG, 36218 GAL 16# DELTA 200 W/124500# 20/40 SAND @ 2-5 PPG. MTP 4545 PSIG. MTR 50.7 BPM. ATP 3455 PSIG. ATR 48.1 BPM. ISIP 1881 PSIG. RD HALLIBURTON.

RUWL. SET 6K CBP AT 7000'. BLED WELL TO 0 PSIG. RDMO CUTTERS WIRELINE & HALIBURTON SERVICES. SWIFN.

05-18-2012	Reported By	BAUSCH / BASTAIN									
DailyCosts: Drilling	\$0	Completion	\$58,712	Daily Total	\$58,712						
Cum Costs: Drilling	\$782,231	Completion	\$626,457	Well Total	\$1,408,689						
MD	9,391	TVD	9,310	Progress	0	Days	15	MW	0.0	Visc	0.0
Formation :	MESAVERDE	PBTD :	9318.0	Perf :	7050'-9067'	PKR Depth :	0.0				

Activity at Report Time: POST FRAC CLEAN OUT

Start	End	Hrs	From	To	Activity Description
18:00	06:00	12.0	0	0	MIRUSU. SICP 0 PSIG. ND FRAC VALVES. NU BOPE. PRESSURE TEST BOP & FLOWLINES TO 2000 PSIG. RIH W/POBS TO CBP @ 7000'. CLEANED OUT & DRILLED OUT PLUGS @ 7000', 7252', 7478', 7770', 8014', 8212' & 8422'.

05-19-2012	Reported By	BAUSCH / BASTAIN									
DailyCosts: Drilling	\$0	Completion	\$21,275	Daily Total	\$21,275						
Cum Costs: Drilling	\$782,231	Completion	\$647,732	Well Total	\$1,429,964						
MD	9,391	TVD	9,310	Progress	0	Days	16	MW	0.0	Visc	0.0
Formation :	MESAVERDE	PBTD :	9318.0	Perf :	7050'-9067'	PKR Depth :	0.0				

Activity at Report Time: PREP TO FLOW TEST

Start	End	Hrs	From	To	Activity Description
06:00	06:00	24.0	0	0	DRILLED OUT PLUGS @ 8612' & 8820'. CLEANED OUT TO PBTD @ 9130'. LANDED TBG AT 7716' KB. ND BOPE. NU TREE. PUMPED OFF BIT & SUB. RDMOSU.

TUBING DETAIL LENGTH

PUMP OFF SUB 1.00'
 1 JT 2-3/8 4.7# L-80 TBG 32.67'
 XN NIPPLE 1.30' @ 7681'
 235 JTS 2-3/8 4.7# L-80 TBG 7662.22'
 BELOW KB 19.00'
 LANDED @ 7716.19' KB

05-22-2012 Reported By SEARLE

Daily Costs: Drilling	\$0	Completion	\$1,750	Daily Total	\$1,750
Cum Costs: Drilling	\$782,231	Completion	\$649,482	Well Total	\$1,431,714

MD	9,391	TVD	9,310	Progress	0	Days	17	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation : MESAVERDE	PBTD : 9318.0	Perf : 7050'-9067'	PKR Depth : 0.0
------------------------------	----------------------	---------------------------	------------------------

Activity at Report Time: FLOW TEST/INITIAL PRODUCTION

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00			0	0	RU TEST UNIT. FLOWED THROUGH TES UNIT 14 HRS. 16/64" CHOKE. FTP 1850 PSIG, CP 2600 PSIG. 21 BPH, RECOVERED 308 BLW. 10347 BLWTR. 1762 MCFD RATE.
-------	--	--	---	---	--

INITIAL PRODUCTION: TURNED WELL TO QUESTAR SALES AT 11:50 AM, 5/21/12. FLOWING 1380 MCFD ON 18/64" CK. FTP 1800 PSIG & FCP 2800 PSIG.

05-23-2012 Reported By SEARLE

Daily Costs: Drilling	\$0	Completion	\$1,750	Daily Total	\$1,750
Cum Costs: Drilling	\$782,231	Completion	\$651,232	Well Total	\$1,433,464

MD	9,391	TVD	9,310	Progress	0	Days	18	MW	0.0	Visc	0.0
-----------	-------	------------	-------	-----------------	---	-------------	----	-----------	-----	-------------	-----

Formation : MESAVERDE	PBTD : 9318.0	Perf : 7050'-9067'	PKR Depth : 0.0
------------------------------	----------------------	---------------------------	------------------------

Activity at Report Time: FLOW TEST

Start	End	Hrs	From	To	Activity Description
-------	-----	-----	------	----	----------------------

06:00			0	0	FLOWED THROUGH TES UNIT 14 HRS. 16/64" CHOKE. FTP 1750 PSIG, CP 2450 PSIG. 18 BPH, RECOVERED 424 BLW. 9923 BLWTR. 1749 MCFD RATE.
-------	--	--	---	---	---

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU0285A

1a. Type of Well Oil Well Gas Well Dry Other
 b. Type of Completion New Well Work Over Deepen Plug Back Diff. Resv. Other _____

6. If Indian, Allottee or Tribe Name _____

7. Unit or CA Agreement Name and No.
CHAPITA WELLS

2. Name of Operator **EOG RESOURCES, INC.** Contact: **MICKENZIE GATES**
E-Mail: **MICKENZIE_GATES@EOGRESOURCES.COM**

8. Lease Name and Well No.
CWU 1544-26D ✓

3. Address **600 17TH SREET SUITE 1000N DENVER, CO 80202** 3a. Phone No. (include area code) Ph: **435-781-9145**

9. API Well No. **43-047-51731**

4. Location of Well (Report location clearly and in accordance with Federal requirements)*
 At surface **NENE 447FNL 501FEL 40.013011 N Lat, 109.399544 W Lon**
 At top prod interval reported below **NENE 447FNL 501FEL 40.013011 N Lat, 109.399544 W Lon**
 At total depth **NENE 447FNL 504FEL 40.013011 N Lat, 109.399544 W Lon** *BHL by HSM*

10. Field and Pool, or Exploratory **NATURAL BUTTES**

11. Sec., T., R., M., or Block and Survey or Area **Sec 26 T9S R22E Mer SLB**

12. County or Parish **UINTAH** 13. State **UT**

14. Date Spudded **12/18/2011** 15. Date T.D. Reached **03/16/2012** 16. Date Completed D & A Ready to Prod. **05/21/2012**

17. Elevations (DF, KB, RT, GL)* **5015 GL**

18. Total Depth: MD **9391** TVD **9311** 19. Plug Back T.D.: MD **9318** TVD **9233** 20. Depth Bridge Plug Set: MD **9318** TVD **9255**

21. Type Electric & Other Mechanical Logs Run (Submit copy of each) **CBL/CCL/VDL/GR** 22. Was well cored? No Yes (Submit analysis)
 Was DST run? No Yes (Submit analysis)
 Directional Survey? No Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12.250	9.625 K-55	36.0		2264		625		0	
7.875	4.500 N-80	11.6		9380		1860		1100	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	7716							

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	7050	9067	8839 TO 9067		36	OPEN
B)			8636 TO 8803		36	OPEN
C)			8436 TO 8589		36	OPEN
D)			8250 TO 8402		36	OPEN

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
8839 TO 9067	774 BARRELS OF GELLED WATER & 89,900# 20/40 SAND
8636 TO 8803	1,046 BARRELS OF GELLED WATER & 129,900# 20/40 SAND
8436 TO 8589	1,056 BARRELS OF GELLED WATER & 131,900# 20/40 SAND
8250 TO 8402	1,267 BARRELS OF GELLED WATER & 163,300# 20/40 SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
05/21/2012	06/04/2012	24	→	30.0	1342.0	104.0			FLows FROM WELL
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
20/64	1100	1650.0	→	30	1342	104		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

(See Instructions and spaces for additional data on reverse side)
ELECTRONIC SUBMISSION #141934 VERIFIED BY THE BLM WELL INFORMATION SYSTEM
**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

RECEIVED
JUL 05 2012

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
MESAVERDE	7050	9067		GREEN RIVER BIRDS NEST MAHOGANY UTELAND BUTTE WASATCH CHAPITA WELLS BUCK CANYON PRICE RIVER	1406 1721 2316 4579 4700 5301 5992 7009

32. Additional remarks (include plugging procedure):
Please see the attached.


33. Circle enclosed attachments:

- 1. Electrical/Mechanical Logs (1 full set req'd.)
- 2. Geologic Report
- 3. DST Report
- 4. Directional Survey
- 5. Sundry Notice for plugging and cement verification
- 6. Core Analysis
- 7 Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #141934 Verified by the BLM Well Information System.
For EOG RESOURCES, INC., sent to the Vernal**

Name (please print) MICKENZIE GATES Title REGULATORY ASSISTANT

Signature  Date 06/29/2012

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

CHAPITA WELLS UNIT 1544-26D- ADDITIONAL REMARKS :

26. PERFORATION RECORD

8038-8192	36	OPEN
7795-7995	33	OPEN
7513-7749	36	OPEN
7292-7457	36	OPEN
7050-7231	36	OPEN

27. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.

8038-8192	1,493 BARRELS GELLED WATER & 196,400# 20/40 SAND
7795-7995	961 BARRELS GELLED WATER & 116,700# 20/40 SAND
7513-7749	977 BARRELS GELLED WATER & 119,600# 20/40 SAND
7292-7457	883 BARRELS GELLED WATER & 105,200# 20/40 SAND
7050-7231	1,064 BARRELS GELLED WATER & 134,100# 20/40 SAND

32. FORMATION (LOG) MARKERS

Middle Price River	7867
Lower Price River	8689
Sego	9204



Survey Certification Sheet

Company: EOG Resources
API # 43-047-51731
Well Name: Chapita Well Unit #1544-26D
SURFACE LOCATION
Uintah County, Utah
Sec. 26-T9S-R22E
447' From North Line, 501' From East Line
BOTTOM HOLE LOCATION @
9391' Measured Depth
9310.82' True Vertical Depth
-804.15' South, -102.12' West from Surface Location
Crescent Job Number: CA 12029 and CA 12143

Surveyed from a depth of 0.0' - 9391' MD
Type of survey: Crescent MWD (Measurement While Drilling)
Last Survey Date: March 16, 2012
Directional Supervisor: John Stringfellow

To whom it may concern,
I attached surveys in pdf and text format of the Chapita Well Unit 1544-26D well.

The data and calculations for this survey have been checked by me and conform to the standards and procedures set forth by Crescent Directional Drilling. This report represents a true and correct Directional Survey of this well based on the original data obtained at the well site. Wellbore Coordinates are calculated using minimum curvature.

A handwritten signature in black ink that reads "John Stringfellow". The signature is written in a cursive style.

John Stringfellow
Directional Coordinator
Rocky Mtn. Region
Crescent Directional Drilling
Off. (307)266-6500
Cell. (307)259-7827

EOG Resources



Uintah County Utah
 Chapita Well Unit 1541- 1546-26D
 CWU #1542-26D Control Well
 Latitude 40° 0' 46.951 N
 Longitude 109° 23' 55.640 W
 True #34 @ 5034.0ft (RKB Elev.)
 Ground Level 5015.0
 Utah Central 4302
 NAD 1927 (NADCON CONUS)
 Magnetic North is 10.97° East of True North (Magnetic Declination)



Azimuths to True North
 Magnetic North: 10.97°

Magnetic Field
 Strength: 52300.4snT
 Dip Angle: 65.88°
 Date: 2011/12/09
 Model: IGRF2010

Chapita Well Unit 1541- 1546-26D







EOG Resources
 Uintah County Utah
 Chapita Well Unit 1541- 1546-26D
 CWU #1544-26D
 Latitude 40° 0' 46.958 N
 Longitude 109° 23' 55.900 W
 True #34 @ 5034.0ft (RKB Elev.)
 Ground Level 5015.0
 Utah Central 4302
 NAD 1927 (NADCON CONUS)
 Magnetic North is 10.97° East of True North (Magnetic Declination)



ANNOTATIONS		
TVD	MD	Annotation
2173.1	2213.0	Tie into Surface Hole surveys
9310.8	9391.0	Projection to TD

WELLBORE TARGET DETAILS				
Name	TVD	+N/-S	+E/-W	Shape
Wasatch #1544	4600.0	-792.6	-120.2	Point
Price River #1544	6920.0	-792.6	-120.2	Circle (Radius: 50.0)
PBHL #1544	9310.0	-792.6	-120.2	Point





EOG Resources

**Uintah County Utah
Chapita Well Unit 1541- 1546-26D
CWU #1544-26D
Wellbore #1**

Design: Wellbore #1

Standard Survey Report

30 April, 2012



Company:	EOG Resources	Local Co-ordinate Reference:	Well CWU #1544-26D
Project:	Uintah County Utah	TVD Reference:	True #34 @ 5034.0ft (RKB Elev.)
Site:	Chapita Well Unit 1541- 1546-26D	MD Reference:	True #34 @ 5034.0ft (RKB Elev.)
Well:	CWU #1544-26D	North Reference:	True
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Wellbore #1	Database:	EDM 2003.16 Single User Db

Project	Uintah County Utah		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		

Site	Chapita Well Unit 1541- 1546-26D				
Site Position:		Northing:	618,708.27ft	Latitude:	40° 0' 46.951 N
From:	Lat/Long	Easting:	2,588,474.21ft	Longitude:	109° 23' 55.640 W
Position Uncertainty:	0.0 ft	Spot Radius:	"	Grid Convergence:	1.35 °

Well	CWU #1544-26D					
Well Position	+N/-S	0.0 ft	Northing:	618,708.51 ft	Latitude:	40° 0' 46.958 N
	+E/-W	0.0 ft	Easting:	2,588,454.03 ft	Longitude:	109° 23' 55.900 W
Position Uncertainty	0.0 ft		Wellhead Elevation:	ft	Ground Level:	5,015.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	12/09/11	10.97	65.88	52,300

Design	Wellbore #1				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.0	0.0	0.0	186.28	

Survey Program	Date	04/12/12			
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
326.0	2,213.0	Surface Hole Surveys (Wellbore #1)	MWD	MWD - Standard	
2,337.0	9,391.0	7 7/8" Hole Surveys (Wellbore #1)	MWD	MWD - Standard	

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
326.0	0.44	243.40	326.0	-0.6	-1.1	0.7	0.13	0.13	0.00
356.0	0.75	222.00	356.0	-0.8	-1.4	0.9	1.25	1.03	-71.33
386.0	0.90	221.00	386.0	-1.1	-1.6	1.3	0.50	0.50	-3.33
416.0	1.30	223.00	416.0	-1.5	-2.0	1.7	1.34	1.33	6.67
446.0	1.50	212.00	446.0	-2.1	-2.5	2.3	1.11	0.67	-36.67
476.0	1.80	205.00	476.0	-2.9	-2.9	3.1	1.20	1.00	-23.33
506.0	2.10	207.40	505.9	-3.8	-3.3	4.1	1.04	1.00	8.00
536.0	2.80	201.00	535.9	-4.9	-3.8	5.3	2.50	2.33	-21.33
566.0	3.30	194.30	565.9	-6.5	-4.3	6.9	2.04	1.67	-22.33
596.0	3.90	192.30	595.8	-8.3	-4.7	8.8	2.04	2.00	-6.67
626.0	4.80	195.50	625.7	-10.5	-5.3	11.0	3.11	3.00	10.67

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
656.0	5.40	193.90	655.6	-13.1	-6.0	13.7	2.06	2.00	-5.33
686.0	5.80	195.70	685.5	-15.9	-6.7	16.5	1.46	1.33	6.00
716.0	6.50	197.90	715.3	-19.0	-7.7	19.7	2.46	2.33	7.33
746.0	7.10	198.40	745.1	-22.4	-8.8	23.2	2.01	2.00	1.67
776.0	7.80	196.80	774.8	-26.1	-9.9	27.0	2.43	2.33	-5.33
806.0	8.70	194.50	804.5	-30.2	-11.1	31.2	3.19	3.00	-7.67
836.0	9.40	193.90	834.1	-34.8	-12.3	35.9	2.35	2.33	-2.00
866.0	10.20	190.70	863.7	-39.8	-13.3	41.0	3.23	2.67	-10.67
896.0	11.10	190.40	893.2	-45.2	-14.3	46.5	3.01	3.00	-1.00
926.0	12.00	190.00	922.6	-51.1	-15.4	52.5	3.01	3.00	-1.33
956.0	12.50	190.00	951.9	-57.4	-16.5	58.9	1.67	1.67	0.00
986.0	13.30	190.30	981.1	-64.0	-17.7	65.5	2.68	2.67	1.00
1,016.0	13.20	191.80	1,010.3	-70.7	-19.0	72.4	1.19	-0.33	5.00
1,046.0	13.20	190.70	1,039.6	-77.5	-20.3	79.2	0.84	0.00	-3.67
1,076.0	13.60	191.00	1,068.7	-84.3	-21.7	86.2	1.35	1.33	1.00
1,106.0	14.20	190.00	1,097.9	-91.4	-23.0	93.3	2.15	2.00	-3.33
1,136.0	14.20	188.10	1,126.9	-98.6	-24.1	100.7	1.55	0.00	-6.33
1,166.0	14.80	187.30	1,156.0	-106.1	-25.1	108.2	2.11	2.00	-2.67
1,196.0	14.60	188.10	1,185.0	-113.6	-26.2	115.8	0.95	-0.67	2.67
1,226.0	14.60	187.00	1,214.0	-121.1	-27.1	123.4	0.92	0.00	-3.67
1,256.0	14.60	186.30	1,243.1	-128.6	-28.0	130.9	0.59	0.00	-2.33
1,286.0	14.30	185.90	1,272.1	-136.1	-28.8	138.4	1.05	-1.00	-1.33
1,316.0	14.60	186.50	1,301.2	-143.5	-29.6	145.9	1.12	1.00	2.00
1,346.0	14.50	187.90	1,330.2	-151.0	-30.6	153.4	1.22	-0.33	4.67
1,376.0	14.50	187.30	1,359.3	-158.4	-31.6	160.9	0.50	0.00	-2.00
1,406.0	14.40	185.80	1,388.3	-165.9	-32.4	168.4	1.29	-0.33	-5.00
1,436.0	14.30	187.20	1,417.4	-173.3	-33.3	175.9	1.20	-0.33	4.67
1,466.0	14.30	186.20	1,446.4	-180.6	-34.1	183.3	0.82	0.00	-3.33
1,496.0	14.20	186.00	1,475.5	-188.0	-34.9	190.7	0.37	-0.33	-0.67
1,526.0	14.10	187.90	1,504.6	-195.3	-35.8	198.0	1.58	-0.33	6.33
1,556.0	14.10	187.40	1,533.7	-202.5	-36.8	205.3	0.41	0.00	-1.67
1,586.0	14.40	185.70	1,562.8	-209.8	-37.6	212.7	1.72	1.00	-5.67
1,616.0	14.70	185.50	1,591.8	-217.3	-38.3	220.2	1.01	1.00	-0.67
1,646.0	14.60	185.70	1,620.8	-224.9	-39.1	227.8	0.37	-0.33	0.67
1,676.0	14.70	185.80	1,649.9	-232.4	-39.8	235.4	0.34	0.33	0.33
1,706.0	14.70	185.50	1,678.9	-240.0	-40.6	243.0	0.25	0.00	-1.00
1,736.0	14.40	184.00	1,707.9	-247.5	-41.2	250.5	1.61	-1.00	-5.00
1,766.0	14.10	183.70	1,737.0	-254.9	-41.7	257.9	1.03	-1.00	-1.00
1,796.0	13.90	184.70	1,766.1	-262.1	-42.2	265.2	1.05	-0.67	3.33
1,826.0	13.70	181.80	1,795.2	-269.3	-42.7	272.3	2.40	-0.67	-9.67
1,856.0	13.80	182.90	1,824.4	-276.4	-42.9	279.4	0.93	0.33	3.67
1,886.0	13.80	182.50	1,853.5	-283.5	-43.3	286.6	0.32	0.00	-1.33
1,916.0	13.60	180.40	1,882.7	-290.6	-43.5	293.7	1.79	-0.67	-7.00
1,946.0	13.30	179.50	1,911.8	-297.6	-43.5	300.6	1.22	-1.00	-3.00
1,976.0	13.30	178.80	1,941.0	-304.5	-43.4	307.4	0.54	0.00	-2.33
2,006.0	12.80	177.70	1,970.3	-311.3	-43.2	314.1	1.86	-1.67	-3.67
2,036.0	12.70	178.50	1,999.5	-317.9	-42.9	320.7	0.68	-0.33	2.67
2,066.0	12.10	175.40	2,028.8	-324.3	-42.6	327.1	2.99	-2.00	-10.33
2,096.0	11.80	175.00	2,058.2	-330.5	-42.1	333.1	1.04	-1.00	-1.33
2,126.0	11.00	172.30	2,087.6	-336.4	-41.4	338.9	3.20	-2.67	-9.00
2,156.0	10.70	170.60	2,117.0	-342.0	-40.6	344.4	1.46	-1.00	-5.67
2,186.0	10.30	169.50	2,146.5	-347.4	-39.6	349.6	1.49	-1.33	-3.67
2,213.0	10.00	168.30	2,173.1	-352.1	-38.7	354.2	1.36	-1.11	-4.44

Tie into Surface Hole surveys

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
2,337.0	8.60	163.50	2,295.5	-371.5	-33.9	373.0	1.29	-1.13	-3.87	
2,368.0	8.30	162.30	2,326.1	-375.8	-32.6	377.2	1.12	-0.97	-3.87	
2,399.0	8.40	163.90	2,356.8	-380.2	-31.3	381.3	0.82	0.32	5.16	
2,431.0	8.90	166.80	2,388.5	-384.8	-30.0	385.8	2.07	1.56	9.06	
2,461.0	9.40	170.80	2,418.1	-389.5	-29.1	390.3	2.70	1.67	13.33	
2,493.0	9.50	173.20	2,449.6	-394.7	-28.4	395.4	1.27	0.31	7.50	
2,523.0	9.50	173.70	2,479.2	-399.6	-27.8	400.3	0.28	0.00	1.67	
2,555.0	9.30	176.60	2,510.8	-404.8	-27.4	405.4	1.61	-0.62	9.06	
2,587.0	9.50	178.50	2,542.4	-410.0	-27.2	410.5	1.15	0.62	5.94	
2,618.0	9.80	180.10	2,572.9	-415.2	-27.1	415.7	1.30	0.97	5.16	
2,649.0	9.90	181.30	2,603.5	-420.5	-27.2	421.0	0.74	0.32	3.87	
2,680.0	9.90	182.40	2,634.0	-425.9	-27.3	426.3	0.61	0.00	3.55	
2,712.0	9.80	183.40	2,665.5	-431.3	-27.6	431.8	0.62	-0.31	3.12	
2,743.0	10.10	185.40	2,696.1	-436.7	-28.0	437.1	1.48	0.97	6.45	
2,774.0	10.50	187.80	2,726.6	-442.2	-28.7	442.7	1.89	1.29	7.74	
2,806.0	10.90	189.00	2,758.0	-448.0	-29.5	448.6	1.43	1.25	3.75	
2,836.0	11.30	191.00	2,787.5	-453.7	-30.5	454.4	1.85	1.33	6.67	
2,868.0	11.70	195.10	2,818.8	-459.9	-32.0	460.7	2.84	1.25	12.81	
2,900.0	12.00	198.00	2,850.1	-466.2	-33.9	467.1	2.08	0.94	9.06	
2,931.0	12.10	200.90	2,880.5	-472.3	-36.0	473.4	1.98	0.32	9.35	
2,963.0	12.00	201.30	2,911.7	-478.6	-38.4	479.9	0.41	-0.31	1.25	
2,994.0	12.00	199.60	2,942.1	-484.6	-40.7	486.2	1.14	0.00	-5.48	
3,024.0	12.20	199.50	2,971.4	-490.5	-42.8	492.3	0.67	0.67	-0.33	
3,056.0	12.90	200.30	3,002.6	-497.1	-45.1	499.0	2.25	2.19	2.50	
3,087.0	13.40	202.70	3,032.8	-503.6	-47.7	505.8	2.39	1.61	7.74	
3,119.0	13.80	203.70	3,063.9	-510.5	-50.7	513.0	1.45	1.25	3.12	
3,149.0	13.80	203.30	3,093.1	-517.1	-53.5	519.9	0.32	0.00	-1.33	
3,179.0	13.40	201.60	3,122.2	-523.6	-56.2	526.6	1.88	-1.33	-5.67	
3,210.0	13.10	201.30	3,152.4	-530.2	-58.8	533.5	0.99	-0.97	-0.97	
3,242.0	13.30	199.30	3,183.5	-537.1	-61.4	540.6	1.56	0.62	-6.25	
3,274.0	13.60	198.20	3,214.7	-544.1	-63.8	547.9	1.23	0.94	-3.44	
3,304.0	13.70	199.40	3,243.8	-550.8	-66.0	554.8	1.00	0.33	4.00	
3,336.0	13.60	202.10	3,274.9	-557.9	-68.7	562.1	2.02	-0.31	8.44	
3,366.0	13.00	201.50	3,304.1	-564.3	-71.3	568.7	2.05	-2.00	-2.00	
3,398.0	12.90	201.90	3,335.3	-571.0	-73.9	575.6	0.42	-0.31	1.25	
3,428.0	12.90	201.50	3,364.5	-577.2	-76.4	582.1	0.30	0.00	-1.33	
3,460.0	12.80	199.80	3,395.7	-583.9	-78.9	589.0	1.22	-0.31	-5.31	
3,490.0	13.00	199.70	3,425.0	-590.2	-81.2	595.5	0.67	0.67	-0.33	
3,522.0	13.10	202.10	3,456.2	-596.9	-83.8	602.5	1.72	0.31	7.50	
3,552.0	12.60	202.00	3,485.4	-603.1	-86.3	608.9	1.67	-1.67	-0.33	
3,583.0	12.10	200.60	3,515.7	-609.3	-88.7	615.3	1.88	-1.61	-4.52	
3,613.0	12.10	199.80	3,545.0	-615.2	-90.9	621.4	0.56	0.00	-2.67	
3,644.0	12.40	200.90	3,575.3	-621.3	-93.1	627.8	1.23	0.97	3.55	
3,675.0	12.90	201.10	3,605.6	-627.7	-95.6	634.4	1.62	1.61	0.65	
3,706.0	12.60	199.80	3,635.8	-634.1	-98.0	641.0	1.34	-0.97	-4.19	
3,736.0	11.80	198.70	3,665.1	-640.1	-100.1	647.2	2.78	-2.67	-3.67	
3,768.0	11.60	198.60	3,696.5	-646.2	-102.1	653.5	0.63	-0.62	-0.31	
3,799.0	11.40	198.10	3,726.8	-652.1	-104.1	659.6	0.72	-0.65	-1.61	
3,831.0	11.00	197.70	3,758.2	-658.0	-106.0	665.6	1.27	-1.25	-1.25	
3,863.0	11.20	197.10	3,789.6	-663.9	-107.8	671.7	0.72	0.62	-1.87	
3,894.0	11.10	197.60	3,820.0	-669.6	-109.6	677.6	0.45	-0.32	1.61	
3,925.0	10.50	196.30	3,850.5	-675.2	-111.3	683.3	2.09	-1.94	-4.19	
3,957.0	9.80	194.90	3,882.0	-680.6	-112.8	688.8	2.32	-2.19	-4.37	
3,989.0	9.60	197.30	3,913.5	-685.8	-114.3	694.2	1.41	-0.62	7.50	
4,019.0	9.60	201.60	3,943.1	-690.5	-116.0	699.0	2.39	0.00	14.33	

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,051.0	9.30	202.70	3,974.7	-695.3	-118.0	704.1	1.09	-0.94	3.44
4,081.0	8.80	201.90	4,004.3	-699.7	-119.8	708.6	1.72	-1.67	-2.67
4,113.0	8.40	200.50	4,035.9	-704.2	-121.5	713.2	1.41	-1.25	-4.37
4,143.0	8.10	200.20	4,065.6	-708.2	-123.0	717.4	1.01	-1.00	-1.00
4,175.0	7.70	198.70	4,097.3	-712.4	-124.5	721.7	1.41	-1.25	-4.69
4,207.0	7.30	197.40	4,129.1	-716.3	-125.8	725.8	1.36	-1.25	-4.06
4,239.0	7.00	196.80	4,160.8	-720.1	-126.9	729.7	0.97	-0.94	-1.87
4,269.0	6.90	196.50	4,190.6	-723.6	-128.0	733.3	0.35	-0.33	-1.00
4,301.0	6.50	198.30	4,222.4	-727.2	-129.1	736.9	1.41	-1.25	5.62
4,332.0	6.10	201.40	4,253.2	-730.4	-130.2	740.2	1.69	-1.29	10.00
4,363.0	5.60	202.00	4,284.0	-733.3	-131.4	743.3	1.62	-1.61	1.94
4,395.0	5.10	200.40	4,315.9	-736.1	-132.5	746.2	1.63	-1.56	-5.00
4,425.0	4.60	201.00	4,345.8	-738.5	-133.4	748.6	1.68	-1.67	2.00
4,457.0	3.80	205.60	4,377.7	-740.6	-134.3	750.9	2.71	-2.50	14.37
4,487.0	2.90	207.60	4,407.6	-742.2	-135.1	752.5	3.02	-3.00	6.67
4,519.0	2.40	207.60	4,439.6	-743.5	-135.8	753.9	1.56	-1.56	0.00
4,549.0	2.40	206.70	4,469.6	-744.6	-136.3	755.1	0.13	0.00	-3.00
4,581.0	2.40	207.60	4,501.6	-745.8	-136.9	756.3	0.12	0.00	2.81
4,613.0	2.10	203.60	4,533.5	-746.9	-137.5	757.5	1.06	-0.94	-12.50
4,643.0	1.50	206.20	4,563.5	-747.8	-137.9	758.4	2.02	-2.00	8.67
4,675.0	1.10	176.60	4,595.5	-748.5	-138.0	759.1	2.40	-1.25	-92.50
4,680.4	1.07	170.85	4,600.9	-748.6	-138.0	759.2	2.09	-0.49	-107.06
Wasatch #1544									
4,705.0	1.10	143.50	4,625.5	-749.0	-137.9	759.6	2.09	0.11	-111.05
4,737.0	1.30	137.30	4,657.5	-749.5	-137.4	760.0	0.74	0.62	-19.37
4,768.0	1.00	144.20	4,688.5	-750.0	-137.0	760.5	1.06	-0.97	22.26
4,799.0	0.80	148.10	4,719.5	-750.4	-136.8	760.8	0.67	-0.65	12.58
4,831.0	0.70	145.10	4,751.5	-750.7	-136.5	761.2	0.34	-0.31	-9.37
4,862.0	0.30	102.90	4,782.5	-750.9	-136.3	761.3	1.67	-1.29	-136.13
4,924.0	0.40	17.40	4,844.5	-750.7	-136.1	761.1	0.78	0.16	-137.90
5,019.0	0.40	12.30	4,939.5	-750.1	-136.0	760.5	0.04	0.00	-5.37
5,112.0	0.30	5.20	5,032.5	-749.5	-135.9	759.9	0.12	-0.11	-7.63
5,205.0	0.40	12.80	5,125.5	-749.0	-135.8	759.3	0.12	0.11	8.17
5,297.0	0.30	205.90	5,217.5	-748.9	-135.8	759.2	0.76	-0.11	-181.41
5,390.0	0.60	183.60	5,310.5	-749.6	-135.9	760.0	0.37	0.32	-23.98
5,485.0	0.70	180.00	5,405.5	-750.7	-136.0	761.0	0.11	0.11	-3.79
5,579.0	1.00	181.30	5,499.5	-752.1	-136.0	762.4	0.32	0.32	1.38
5,673.0	0.60	163.40	5,593.4	-753.4	-135.9	763.7	0.50	-0.43	-19.04
5,766.0	0.80	163.70	5,686.4	-754.4	-135.5	764.7	0.22	0.22	0.32
5,861.0	0.80	161.80	5,781.4	-755.7	-135.1	766.0	0.03	0.00	-2.00
5,956.0	0.80	165.70	5,876.4	-757.0	-134.8	767.2	0.06	0.00	4.11
6,049.0	0.30	102.40	5,969.4	-757.7	-134.4	767.8	0.77	-0.54	-68.06
6,144.0	0.50	119.80	6,064.4	-757.9	-133.8	768.0	0.24	0.21	18.32
6,239.0	0.60	130.10	6,159.4	-758.5	-133.0	768.4	0.15	0.11	10.84
6,333.0	0.60	132.60	6,253.4	-759.1	-132.3	769.0	0.03	0.00	2.66
6,427.0	0.70	133.50	6,347.4	-759.8	-131.5	769.7	0.11	0.11	0.96
6,521.0	1.10	129.40	6,441.4	-760.8	-130.4	770.5	0.43	0.43	-4.36
6,616.0	0.70	180.20	6,536.4	-762.0	-129.7	771.6	0.90	-0.42	53.47
6,708.0	0.90	174.60	6,628.4	-763.2	-129.6	772.8	0.23	0.22	-6.09
6,802.0	0.70	162.60	6,722.4	-764.5	-129.4	774.1	0.28	-0.21	-12.77
6,896.0	0.80	170.50	6,816.3	-765.7	-129.1	775.2	0.15	0.11	8.40
6,991.0	0.90	179.80	6,911.3	-767.1	-129.0	776.6	0.18	0.11	9.79
7,000.0	0.86	179.20	6,920.3	-767.3	-129.0	776.8	0.44	-0.43	-6.68
Price River #1544									

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
7,086.0	0.50	168.80	7,006.3	-768.3	-128.9	777.8	0.44	-0.42	-12.09
7,180.0	0.40	145.50	7,100.3	-768.9	-128.7	778.4	0.22	-0.11	-24.79
7,274.0	0.60	166.10	7,194.3	-769.7	-128.4	779.1	0.28	0.21	21.91
7,368.0	0.70	165.20	7,288.3	-770.7	-128.1	780.1	0.11	0.11	-0.96
7,462.0	0.90	167.50	7,382.3	-772.0	-127.8	781.3	0.22	0.21	2.45
7,558.0	1.20	164.50	7,478.3	-773.7	-127.3	783.0	0.32	0.31	-3.12
7,651.0	0.90	161.00	7,571.3	-775.3	-126.9	784.6	0.33	-0.32	-3.76
7,746.0	1.10	161.60	7,666.3	-776.9	-126.3	786.1	0.21	0.21	0.63
7,838.0	1.20	161.20	7,758.2	-778.7	-125.7	787.7	0.11	0.11	-0.43
7,932.0	1.30	159.30	7,852.2	-780.6	-125.0	789.6	0.12	0.11	-2.02
8,026.0	1.20	150.00	7,946.2	-782.4	-124.2	791.3	0.24	-0.11	-9.89
8,119.0	1.40	156.50	8,039.2	-784.3	-123.2	793.1	0.27	0.22	6.99
8,212.0	1.60	148.40	8,132.1	-786.5	-122.1	795.1	0.31	0.22	-8.71
8,306.0	1.10	133.20	8,226.1	-788.2	-120.7	796.7	0.65	-0.53	-16.17
8,399.0	1.10	122.60	8,319.1	-789.3	-119.3	797.6	0.22	0.00	-11.40
8,493.0	1.00	131.30	8,413.1	-790.3	-118.0	798.5	0.20	-0.11	9.26
8,589.0	1.00	136.50	8,509.1	-791.5	-116.8	799.5	0.09	0.00	5.42
8,627.0	0.90	136.00	8,547.1	-791.9	-116.3	799.9	0.26	-0.26	-1.32
8,681.0	0.90	126.00	8,601.1	-792.5	-115.7	800.4	0.29	0.00	-18.52
8,774.0	1.40	128.90	8,694.0	-793.6	-114.2	801.4	0.54	0.54	3.12
8,868.0	1.10	127.90	8,788.0	-794.9	-112.6	802.5	0.32	-0.32	-1.06
8,963.0	1.30	142.10	8,883.0	-796.3	-111.2	803.7	0.38	0.21	14.95
9,057.0	1.30	149.40	8,977.0	-798.1	-110.0	805.3	0.18	0.00	7.77
9,151.0	1.70	130.30	9,070.9	-799.9	-108.4	807.0	0.68	0.43	-20.32
9,245.0	1.90	122.20	9,164.9	-801.6	-106.0	808.4	0.34	0.21	-8.62
9,336.0	1.80	122.90	9,255.8	-803.2	-103.6	809.7	0.11	-0.11	0.77
9,389.5	1.80	122.90	9,309.3	-804.1	-102.2	810.5	0.00	0.00	0.00
PBHL #1544									
9,391.0	1.80	122.90	9,310.8	-804.1	-102.1	810.5	0.00	0.00	0.00
Projection to TD									

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Targets

Target Name

- hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
PBHL #1544 - actual wellpath misses target center by 21.4ft at 9389.5ft MD (9309.3 TVD, -804.1 N, -102.2 E) - Point	0.00	0.00	9,310.0	-792.6	-120.2	617,913.32	2,588,352.52	40° 0' 39.125 N	109° 23' 57.444 W
Wasatch #1544 - actual wellpath misses target center by 47.5ft at 4680.4ft MD (4600.9 TVD, -748.6 N, -138.0 E) - Point	0.00	0.00	4,600.0	-792.6	-120.2	617,913.32	2,588,352.52	40° 0' 39.125 N	109° 23' 57.444 W
Price River #1544 - actual wellpath misses target center by 26.8ft at 7000.0ft MD (6920.3 TVD, -767.3 N, -129.0 E) - Circle (radius 50.0)	0.00	0.00	6,920.0	-792.6	-120.2	617,913.32	2,588,352.52	40° 0' 39.125 N	109° 23' 57.444 W

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
2,213.0	2,173.1	-352.1	-38.7	Tie into Surface Hole surveys
9,391.0	9,310.8	-804.1	-102.1	Projection to TD

Checked By: _____ Approved By: _____ Date: _____



EOG Resources

**Uintah County Utah
Chapita Well Unit 1541- 1546-26D
CWU #1544-26D
Wellbore #1**

Design: Wellbore #1

Survey Report - Geographic

30 April, 2012



Company:	EOG Resources	Local Co-ordinate Reference:	Well CWU #1544-26D
Project:	Uintah County Utah	TVD Reference:	True #34 @ 5034.0ft (RKB Elev.)
Site:	Chapita Well Unit 1541- 1546-26D	MD Reference:	True #34 @ 5034.0ft (RKB Elev.)
Well:	CWU #1544-26D	North Reference:	True
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Wellbore #1	Database:	EDM 2003.16 Single User Db

Project	Uintah County Utah		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		

Site	Chapita Well Unit 1541- 1546-26D		
Site Position:		Northing:	618,708.27 ft
From:	Lat/Long	Easting:	2,588,474.21 ft
Position Uncertainty:	0.0 ft	Slot Radius:	"
		Latitude:	40° 0' 46.951 N
		Longitude:	109° 23' 55.640 W
		Grid Convergence:	1.35 °

Well	CWU #1544-26D		
Well Position	+N/-S	0.0 ft	Northing:
	+E/-W	0.0 ft	618,708.51 ft
Position Uncertainty	0.0 ft	Wellhead Elevation:	ft
		Latitude:	40° 0' 46.958 N
		Longitude:	109° 23' 55.900 W
		Ground Level:	5,015.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	12/09/11	10.97	65.88	52,300

Design	Wellbore #1				
Audit Notes:		Phase:	ACTUAL	Tie On Depth:	0.0
Version:	1.0				
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.0	0.0	0.0	186.28	

Survey Program	Date	04/12/12			
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
326.0	2,213.0	Surface Hole Surveys (Wellbore #1)	MWD	MWD - Standard	
2,337.0	9,391.0	7 7/8" Hole Surveys (Wellbore #1)	MWD	MWD - Standard	

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
0.0	0.00	0.00	0.0	0.0	0.0	618,708.51	2,588,454.03	40° 0' 46.958 N	109° 23' 55.900 W
326.0	0.44	243.40	326.0	-0.6	-1.1	618,707.92	2,588,452.93	40° 0' 46.953 N	109° 23' 55.914 W
356.0	0.75	222.00	356.0	-0.8	-1.4	618,707.72	2,588,452.70	40° 0' 46.951 N	109° 23' 55.917 W
386.0	0.90	221.00	386.0	-1.1	-1.6	618,707.39	2,588,452.42	40° 0' 46.948 N	109° 23' 55.921 W
416.0	1.30	223.00	416.0	-1.5	-2.0	618,706.95	2,588,452.04	40° 0' 46.943 N	109° 23' 55.926 W
446.0	1.50	212.00	446.0	-2.1	-2.5	618,706.36	2,588,451.62	40° 0' 46.938 N	109° 23' 55.931 W
476.0	1.80	205.00	476.0	-2.9	-2.9	618,705.59	2,588,451.23	40° 0' 46.930 N	109° 23' 55.937 W
506.0	2.10	207.40	505.9	-3.8	-3.3	618,704.67	2,588,450.80	40° 0' 46.921 N	109° 23' 55.942 W
536.0	2.80	201.00	535.9	-4.9	-3.8	618,703.48	2,588,450.31	40° 0' 46.909 N	109° 23' 55.949 W
566.0	3.30	194.30	565.9	-6.5	-4.3	618,701.95	2,588,449.87	40° 0' 46.894 N	109° 23' 55.955 W
596.0	3.90	192.30	595.8	-8.3	-4.7	618,700.11	2,588,449.48	40° 0' 46.876 N	109° 23' 55.961 W
626.0	4.80	195.50	625.7	-10.5	-5.3	618,697.89	2,588,448.98	40° 0' 46.854 N	109° 23' 55.968 W
656.0	5.40	193.90	655.6	-13.1	-6.0	618,695.29	2,588,448.37	40° 0' 46.829 N	109° 23' 55.976 W
686.0	5.80	195.70	685.5	-15.9	-6.7	618,692.45	2,588,447.68	40° 0' 46.801 N	109° 23' 55.986 W
716.0	6.50	197.90	715.3	-19.0	-7.7	618,689.35	2,588,446.82	40° 0' 46.771 N	109° 23' 55.998 W
746.0	7.10	198.40	745.1	-22.4	-8.8	618,685.95	2,588,445.80	40° 0' 46.737 N	109° 23' 56.012 W
776.0	7.80	196.80	774.8	-26.1	-9.9	618,682.22	2,588,444.71	40° 0' 46.701 N	109° 23' 56.027 W
806.0	8.70	194.50	804.5	-30.2	-11.1	618,678.05	2,588,443.65	40° 0' 46.660 N	109° 23' 56.042 W
836.0	9.40	193.90	834.1	-34.8	-12.3	618,673.44	2,588,442.60	40° 0' 46.614 N	109° 23' 56.057 W
866.0	10.20	190.70	863.7	-39.8	-13.3	618,668.43	2,588,441.64	40° 0' 46.565 N	109° 23' 56.071 W
896.0	11.10	190.40	893.2	-45.2	-14.3	618,662.96	2,588,440.75	40° 0' 46.511 N	109° 23' 56.084 W
926.0	12.00	190.00	922.6	-51.1	-15.4	618,657.02	2,588,439.83	40° 0' 46.453 N	109° 23' 56.098 W
956.0	12.50	190.00	951.9	-57.4	-16.5	618,650.73	2,588,438.87	40° 0' 46.391 N	109° 23' 56.112 W
986.0	13.30	190.30	981.1	-64.0	-17.7	618,644.11	2,588,437.85	40° 0' 46.326 N	109° 23' 56.127 W
1,016.0	13.20	191.80	1,010.3	-70.7	-19.0	618,637.34	2,588,436.69	40° 0' 46.259 N	109° 23' 56.144 W
1,046.0	13.20	190.70	1,039.6	-77.5	-20.3	618,630.59	2,588,435.51	40° 0' 46.193 N	109° 23' 56.161 W
1,076.0	13.60	191.00	1,068.7	-84.3	-21.7	618,623.73	2,588,434.36	40° 0' 46.125 N	109° 23' 56.178 W
1,106.0	14.20	190.00	1,097.9	-91.4	-23.0	618,616.62	2,588,433.22	40° 0' 46.055 N	109° 23' 56.195 W
1,136.0	14.20	188.10	1,126.9	-98.6	-24.1	618,609.32	2,588,432.23	40° 0' 45.983 N	109° 23' 56.210 W
1,166.0	14.80	187.30	1,156.0	-106.1	-25.1	618,601.86	2,588,431.40	40° 0' 45.910 N	109° 23' 56.223 W
1,196.0	14.60	188.10	1,185.0	-113.6	-26.2	618,594.29	2,588,430.56	40° 0' 45.835 N	109° 23' 56.236 W
1,226.0	14.60	187.00	1,214.0	-121.1	-27.1	618,586.78	2,588,429.74	40° 0' 45.761 N	109° 23' 56.249 W
1,256.0	14.60	186.30	1,243.1	-128.6	-28.0	618,579.25	2,588,429.04	40° 0' 45.687 N	109° 23' 56.260 W
1,286.0	14.30	185.90	1,272.1	-136.1	-28.8	618,571.79	2,588,428.42	40° 0' 45.613 N	109° 23' 56.270 W
1,316.0	14.60	186.50	1,301.2	-143.5	-29.6	618,564.33	2,588,427.79	40° 0' 45.540 N	109° 23' 56.280 W
1,346.0	14.50	187.90	1,330.2	-151.0	-30.6	618,556.83	2,588,427.02	40° 0' 45.466 N	109° 23' 56.293 W
1,376.0	14.50	187.30	1,359.3	-158.4	-31.6	618,549.36	2,588,426.20	40° 0' 45.392 N	109° 23' 56.305 W
1,406.0	14.40	185.80	1,388.3	-165.9	-32.4	618,541.91	2,588,425.52	40° 0' 45.319 N	109° 23' 56.316 W
1,436.0	14.30	187.20	1,417.4	-173.3	-33.3	618,534.50	2,588,424.85	40° 0' 45.246 N	109° 23' 56.327 W
1,466.0	14.30	186.20	1,446.4	-180.6	-34.1	618,527.13	2,588,424.16	40° 0' 45.173 N	109° 23' 56.338 W
1,496.0	14.20	186.00	1,475.5	-188.0	-34.9	618,519.77	2,588,423.55	40° 0' 45.100 N	109° 23' 56.348 W
1,526.0	14.10	187.90	1,504.6	-195.3	-35.8	618,512.47	2,588,422.83	40° 0' 45.028 N	109° 23' 56.360 W
1,556.0	14.10	187.40	1,533.7	-202.5	-36.8	618,505.21	2,588,422.03	40° 0' 44.957 N	109° 23' 56.372 W
1,586.0	14.40	185.70	1,562.8	-209.8	-37.6	618,497.85	2,588,421.36	40° 0' 44.884 N	109° 23' 56.383 W
1,616.0	14.70	185.50	1,591.8	-217.3	-38.3	618,490.34	2,588,420.80	40° 0' 44.810 N	109° 23' 56.392 W
1,646.0	14.60	185.70	1,620.8	-224.9	-39.1	618,482.77	2,588,420.24	40° 0' 44.736 N	109° 23' 56.402 W
1,676.0	14.70	185.80	1,649.9	-232.4	-39.8	618,475.20	2,588,419.66	40° 0' 44.661 N	109° 23' 56.412 W
1,706.0	14.70	185.50	1,678.9	-240.0	-40.6	618,467.61	2,588,419.09	40° 0' 44.586 N	109° 23' 56.421 W
1,736.0	14.40	184.00	1,707.9	-247.5	-41.2	618,460.09	2,588,418.64	40° 0' 44.512 N	109° 23' 56.429 W
1,766.0	14.10	183.70	1,737.0	-254.9	-41.7	618,452.71	2,588,418.32	40° 0' 44.439 N	109° 23' 56.436 W
1,796.0	13.90	184.70	1,766.1	-262.1	-42.2	618,445.46	2,588,417.95	40° 0' 44.368 N	109° 23' 56.443 W
1,826.0	13.70	181.80	1,795.2	-269.3	-42.7	618,438.31	2,588,417.72	40° 0' 44.297 N	109° 23' 56.448 W
1,856.0	13.80	182.90	1,824.4	-276.4	-42.9	618,431.19	2,588,417.59	40° 0' 44.227 N	109° 23' 56.452 W
1,886.0	13.80	182.50	1,853.5	-283.5	-43.3	618,424.03	2,588,417.42	40° 0' 44.156 N	109° 23' 56.456 W
1,916.0	13.60	180.40	1,882.7	-290.6	-43.5	618,416.93	2,588,417.41	40° 0' 44.086 N	109° 23' 56.458 W

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
1,946.0	13.30	179.50	1,911.8	-297.6	-43.5	618,409.95	2,588,417.58	40° 0' 44.017 N	109° 23' 56.458 W
1,976.0	13.30	178.80	1,941.0	-304.5	-43.4	618,403.06	2,588,417.84	40° 0' 43.949 N	109° 23' 56.457 W
2,006.0	12.80	177.70	1,970.3	-311.3	-43.2	618,396.29	2,588,418.21	40° 0' 43.882 N	109° 23' 56.454 W
2,036.0	12.70	178.50	1,999.5	-317.9	-42.9	618,389.68	2,588,418.58	40° 0' 43.816 N	109° 23' 56.451 W
2,066.0	12.10	175.40	2,028.8	-324.3	-42.6	618,383.26	2,588,419.07	40° 0' 43.753 N	109° 23' 56.447 W
2,096.0	11.80	175.00	2,058.2	-330.5	-42.1	618,377.08	2,588,419.74	40° 0' 43.691 N	109° 23' 56.440 W
2,126.0	11.00	172.30	2,087.6	-336.4	-41.4	618,371.21	2,588,420.52	40° 0' 43.633 N	109° 23' 56.432 W
2,156.0	10.70	170.60	2,117.0	-342.0	-40.6	618,365.65	2,588,421.49	40° 0' 43.578 N	109° 23' 56.421 W
2,186.0	10.30	169.50	2,146.5	-347.4	-39.6	618,360.29	2,588,422.56	40° 0' 43.525 N	109° 23' 56.409 W
2,213.0	10.00	168.30	2,173.1	-352.1	-38.7	618,355.64	2,588,423.59	40° 0' 43.479 N	109° 23' 56.397 W
Tie into Surface Hole surveys									
2,337.0	8.60	163.50	2,295.5	-371.5	-33.9	618,336.32	2,588,428.86	40° 0' 43.287 N	109° 23' 56.335 W
2,368.0	8.30	162.30	2,326.1	-375.8	-32.6	618,332.00	2,588,430.30	40° 0' 43.244 N	109° 23' 56.318 W
2,399.0	8.40	163.90	2,356.8	-380.2	-31.3	618,327.73	2,588,431.71	40° 0' 43.201 N	109° 23' 56.301 W
2,431.0	8.90	166.80	2,388.5	-384.8	-30.0	618,323.10	2,588,433.03	40° 0' 43.155 N	109° 23' 56.286 W
2,461.0	9.40	170.80	2,418.1	-389.5	-29.1	618,318.45	2,588,434.06	40° 0' 43.109 N	109° 23' 56.274 W
2,493.0	9.50	173.20	2,449.6	-394.7	-28.4	618,313.26	2,588,434.92	40° 0' 43.057 N	109° 23' 56.265 W
2,523.0	9.50	173.70	2,479.2	-399.6	-27.8	618,308.36	2,588,435.60	40° 0' 43.009 N	109° 23' 56.257 W
2,555.0	9.30	176.60	2,510.8	-404.8	-27.4	618,303.17	2,588,436.16	40° 0' 42.957 N	109° 23' 56.252 W
2,587.0	9.50	178.50	2,542.4	-410.0	-27.2	618,297.95	2,588,436.51	40° 0' 42.906 N	109° 23' 56.249 W
2,618.0	9.80	180.10	2,572.9	-415.2	-27.1	618,292.76	2,588,436.69	40° 0' 42.854 N	109° 23' 56.248 W
2,649.0	9.90	181.30	2,603.5	-420.5	-27.2	618,287.46	2,588,436.75	40° 0' 42.802 N	109° 23' 56.249 W
2,680.0	9.90	182.40	2,634.0	-425.9	-27.3	618,282.13	2,588,436.70	40° 0' 42.749 N	109° 23' 56.251 W
2,712.0	9.80	183.40	2,665.5	-431.3	-27.6	618,276.65	2,588,436.55	40° 0' 42.695 N	109° 23' 56.255 W
2,743.0	10.10	185.40	2,696.1	-436.7	-28.0	618,271.31	2,588,436.27	40° 0' 42.642 N	109° 23' 56.260 W
2,774.0	10.50	187.80	2,726.6	-442.2	-28.7	618,265.79	2,588,435.76	40° 0' 42.588 N	109° 23' 56.268 W
2,806.0	10.90	189.00	2,758.0	-448.0	-29.5	618,259.89	2,588,435.03	40° 0' 42.530 N	109° 23' 56.279 W
2,836.0	11.30	191.00	2,787.5	-453.7	-30.5	618,254.18	2,588,434.16	40° 0' 42.474 N	109° 23' 56.292 W
2,868.0	11.70	195.10	2,818.8	-459.9	-32.0	618,247.94	2,588,432.86	40° 0' 42.412 N	109° 23' 56.311 W
2,900.0	12.00	198.00	2,850.1	-466.2	-33.9	618,241.60	2,588,431.13	40° 0' 42.350 N	109° 23' 56.335 W
2,931.0	12.10	200.90	2,880.5	-472.3	-36.0	618,235.45	2,588,429.12	40° 0' 42.290 N	109° 23' 56.362 W
2,963.0	12.00	201.30	2,911.7	-478.6	-38.4	618,229.17	2,588,426.87	40° 0' 42.228 N	109° 23' 56.393 W
2,994.0	12.00	199.60	2,942.1	-484.6	-40.7	618,223.08	2,588,424.76	40° 0' 42.169 N	109° 23' 56.422 W
3,024.0	12.20	199.50	2,971.4	-490.5	-42.8	618,217.10	2,588,422.79	40° 0' 42.110 N	109° 23' 56.449 W
3,056.0	12.90	200.30	3,002.6	-497.1	-45.1	618,210.51	2,588,420.58	40° 0' 42.045 N	109° 23' 56.480 W
3,087.0	13.40	202.70	3,032.8	-503.6	-47.7	618,203.89	2,588,418.15	40° 0' 41.981 N	109° 23' 56.513 W
3,119.0	13.80	203.70	3,063.9	-510.5	-50.7	618,196.91	2,588,415.34	40° 0' 41.912 N	109° 23' 56.551 W
3,149.0	13.80	203.30	3,093.1	-517.1	-53.5	618,190.28	2,588,412.65	40° 0' 41.847 N	109° 23' 56.588 W
3,179.0	13.40	201.60	3,122.2	-523.6	-56.2	618,183.70	2,588,410.11	40° 0' 41.783 N	109° 23' 56.622 W
3,210.0	13.10	201.30	3,152.4	-530.2	-58.8	618,177.03	2,588,407.66	40° 0' 41.718 N	109° 23' 56.656 W
3,242.0	13.30	199.30	3,183.5	-537.1	-61.4	618,170.12	2,588,405.29	40° 0' 41.650 N	109° 23' 56.688 W
3,274.0	13.60	198.20	3,214.7	-544.1	-63.8	618,163.02	2,588,403.07	40° 0' 41.580 N	109° 23' 56.719 W
3,304.0	13.70	199.40	3,243.8	-550.8	-66.0	618,156.26	2,588,400.94	40° 0' 41.514 N	109° 23' 56.749 W
3,336.0	13.60	202.10	3,274.9	-557.9	-68.7	618,149.14	2,588,398.43	40° 0' 41.444 N	109° 23' 56.783 W
3,366.0	13.00	201.50	3,304.1	-564.3	-71.3	618,142.68	2,588,396.02	40° 0' 41.381 N	109° 23' 56.816 W
3,398.0	12.90	201.90	3,335.3	-571.0	-73.9	618,135.95	2,588,393.53	40° 0' 41.315 N	109° 23' 56.850 W
3,428.0	12.90	201.50	3,364.5	-577.2	-76.4	618,129.67	2,588,391.20	40° 0' 41.254 N	109° 23' 56.882 W
3,460.0	12.80	199.80	3,395.7	-583.9	-78.9	618,122.96	2,588,388.85	40° 0' 41.188 N	109° 23' 56.914 W
3,490.0	13.00	199.70	3,425.0	-590.2	-81.2	618,116.60	2,588,386.73	40° 0' 41.125 N	109° 23' 56.943 W
3,522.0	13.10	202.10	3,456.2	-596.9	-83.8	618,109.80	2,588,384.31	40° 0' 41.059 N	109° 23' 56.976 W
3,552.0	12.60	202.00	3,485.4	-603.1	-86.3	618,103.56	2,588,381.95	40° 0' 40.998 N	109° 23' 57.008 W
3,583.0	12.10	200.60	3,515.7	-609.3	-88.7	618,097.32	2,588,379.69	40° 0' 40.937 N	109° 23' 57.039 W
3,613.0	12.10	199.80	3,545.0	-615.2	-90.9	618,091.37	2,588,377.66	40° 0' 40.878 N	109° 23' 57.067 W
3,644.0	12.40	200.90	3,575.3	-621.3	-93.1	618,085.15	2,588,375.51	40° 0' 40.817 N	109° 23' 57.097 W
3,675.0	12.90	201.10	3,605.6	-627.7	-95.6	618,078.76	2,588,373.23	40° 0' 40.755 N	109° 23' 57.128 W

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude	
3,706.0	12.60	199.80	3,635.8	-634.1	-98.0	618,072.30	2,588,370.99	40° 0' 40.691 N	109° 23' 57.159 W	
3,736.0	11.80	198.70	3,665.1	-640.1	-100.1	618,066.27	2,588,369.04	40° 0' 40.632 N	109° 23' 57.186 W	
3,768.0	11.60	198.60	3,696.5	-646.2	-102.1	618,060.07	2,588,367.11	40° 0' 40.571 N	109° 23' 57.212 W	
3,799.0	11.40	198.10	3,726.8	-652.1	-104.1	618,054.16	2,588,365.30	40° 0' 40.513 N	109° 23' 57.237 W	
3,831.0	11.00	197.70	3,758.2	-658.0	-106.0	618,048.20	2,588,363.53	40° 0' 40.455 N	109° 23' 57.262 W	
3,863.0	11.20	197.10	3,789.6	-663.9	-107.8	618,042.28	2,588,361.83	40° 0' 40.397 N	109° 23' 57.285 W	
3,894.0	11.10	197.60	3,820.0	-669.6	-109.6	618,036.52	2,588,360.18	40° 0' 40.340 N	109° 23' 57.308 W	
3,925.0	10.50	196.30	3,850.5	-675.2	-111.3	618,030.93	2,588,358.61	40° 0' 40.285 N	109° 23' 57.330 W	
3,957.0	9.80	194.90	3,882.0	-680.6	-112.8	618,025.46	2,588,357.22	40° 0' 40.232 N	109° 23' 57.350 W	
3,989.0	9.60	197.30	3,913.5	-685.8	-114.3	618,020.25	2,588,355.85	40° 0' 40.180 N	109° 23' 57.369 W	
4,019.0	9.60	201.60	3,943.1	-690.5	-116.0	618,015.50	2,588,354.30	40° 0' 40.134 N	109° 23' 57.390 W	
4,051.0	9.30	202.70	3,974.7	-695.3	-118.0	618,010.58	2,588,352.43	40° 0' 40.086 N	109° 23' 57.416 W	
4,081.0	8.80	201.90	4,004.3	-699.7	-119.8	618,006.18	2,588,350.74	40° 0' 40.043 N	109° 23' 57.439 W	
4,113.0	8.40	200.50	4,035.9	-704.2	-121.5	618,001.68	2,588,349.12	40° 0' 39.999 N	109° 23' 57.461 W	
4,143.0	8.10	200.20	4,065.6	-708.2	-123.0	617,997.61	2,588,347.71	40° 0' 39.959 N	109° 23' 57.480 W	
4,175.0	7.70	198.70	4,097.3	-712.4	-124.5	617,993.43	2,588,346.35	40° 0' 39.918 N	109° 23' 57.499 W	
4,207.0	7.30	197.40	4,129.1	-716.3	-125.8	617,989.43	2,588,345.14	40° 0' 39.878 N	109° 23' 57.516 W	
4,239.0	7.00	196.80	4,160.8	-720.1	-126.9	617,985.59	2,588,344.06	40° 0' 39.841 N	109° 23' 57.531 W	
4,269.0	6.90	196.50	4,190.6	-723.6	-128.0	617,982.09	2,588,343.10	40° 0' 39.806 N	109° 23' 57.544 W	
4,301.0	6.50	198.30	4,222.4	-727.2	-129.1	617,978.51	2,588,342.07	40° 0' 39.771 N	109° 23' 57.559 W	
4,332.0	6.10	201.40	4,253.2	-730.4	-130.2	617,975.28	2,588,341.00	40° 0' 39.740 N	109° 23' 57.573 W	
4,363.0	5.60	202.00	4,284.0	-733.3	-131.4	617,972.32	2,588,339.90	40° 0' 39.711 N	109° 23' 57.588 W	
4,395.0	5.10	200.40	4,315.9	-736.1	-132.5	617,969.51	2,588,338.88	40° 0' 39.683 N	109° 23' 57.602 W	
4,425.0	4.60	201.00	4,345.8	-738.5	-133.4	617,967.12	2,588,338.04	40° 0' 39.660 N	109° 23' 57.614 W	
4,457.0	3.80	205.60	4,377.7	-740.6	-134.3	617,964.94	2,588,337.18	40° 0' 39.638 N	109° 23' 57.626 W	
4,487.0	2.90	207.60	4,407.6	-742.2	-135.1	617,963.36	2,588,336.43	40° 0' 39.623 N	109° 23' 57.636 W	
4,519.0	2.40	207.60	4,439.6	-743.5	-135.8	617,962.03	2,588,335.78	40° 0' 39.610 N	109° 23' 57.644 W	
4,549.0	2.40	206.70	4,469.6	-744.6	-136.3	617,960.90	2,588,335.23	40° 0' 39.599 N	109° 23' 57.652 W	
4,581.0	2.40	207.60	4,501.6	-745.8	-136.9	617,959.69	2,588,334.65	40° 0' 39.587 N	109° 23' 57.660 W	
4,613.0	2.10	203.60	4,533.5	-746.9	-137.5	617,958.55	2,588,334.13	40° 0' 39.576 N	109° 23' 57.667 W	
4,643.0	1.50	206.20	4,563.5	-747.8	-137.9	617,957.68	2,588,333.76	40° 0' 39.567 N	109° 23' 57.672 W	
4,675.0	1.10	176.60	4,595.5	-748.5	-138.0	617,957.00	2,588,333.61	40° 0' 39.561 N	109° 23' 57.674 W	
4,680.4	1.07	170.85	4,600.9	-748.6	-138.0	617,956.90	2,588,333.62	40° 0' 39.560 N	109° 23' 57.674 W	
Wasatch #1544										
4,705.0	1.10	143.50	4,625.5	-749.0	-137.9	617,956.48	2,588,333.81	40° 0' 39.556 N	109° 23' 57.671 W	
4,737.0	1.30	137.30	4,657.5	-749.5	-137.4	617,955.98	2,588,334.25	40° 0' 39.550 N	109° 23' 57.666 W	
4,768.0	1.00	144.20	4,688.5	-750.0	-137.0	617,955.51	2,588,334.65	40° 0' 39.546 N	109° 23' 57.661 W	
4,799.0	0.80	148.10	4,719.5	-750.4	-136.8	617,955.11	2,588,334.94	40° 0' 39.542 N	109° 23' 57.657 W	
4,831.0	0.70	145.10	4,751.5	-750.7	-136.5	617,954.77	2,588,335.17	40° 0' 39.538 N	109° 23' 57.654 W	
4,862.0	0.30	102.90	4,782.5	-750.9	-136.3	617,954.60	2,588,335.37	40° 0' 39.537 N	109° 23' 57.652 W	
4,924.0	0.40	17.40	4,844.5	-750.7	-136.1	617,954.78	2,588,335.58	40° 0' 39.538 N	109° 23' 57.649 W	
5,019.0	0.40	12.30	4,939.5	-750.1	-136.0	617,955.42	2,588,335.74	40° 0' 39.545 N	109° 23' 57.647 W	
5,112.0	0.30	5.20	5,032.5	-749.5	-135.9	617,955.98	2,588,335.82	40° 0' 39.550 N	109° 23' 57.646 W	
5,205.0	0.40	12.80	5,125.5	-749.0	-135.8	617,956.54	2,588,335.90	40° 0' 39.556 N	109° 23' 57.645 W	
5,297.0	0.30	205.90	5,217.5	-748.9	-135.8	617,956.64	2,588,335.86	40° 0' 39.557 N	109° 23' 57.645 W	
5,390.0	0.60	183.60	5,310.5	-749.6	-135.9	617,955.93	2,588,335.74	40° 0' 39.550 N	109° 23' 57.647 W	
5,485.0	0.70	180.00	5,405.5	-750.7	-136.0	617,954.85	2,588,335.74	40° 0' 39.539 N	109° 23' 57.647 W	
5,579.0	1.00	181.30	5,499.5	-752.1	-136.0	617,953.46	2,588,335.75	40° 0' 39.525 N	109° 23' 57.647 W	
5,673.0	0.60	163.40	5,593.4	-753.4	-135.9	617,952.17	2,588,335.90	40° 0' 39.512 N	109° 23' 57.646 W	
5,766.0	0.80	163.70	5,686.4	-754.4	-135.5	617,951.09	2,588,336.25	40° 0' 39.502 N	109° 23' 57.642 W	
5,861.0	0.80	161.80	5,781.4	-755.7	-135.1	617,949.83	2,588,336.67	40° 0' 39.489 N	109° 23' 57.637 W	
5,956.0	0.80	165.70	5,876.4	-757.0	-134.8	617,948.57	2,588,337.07	40° 0' 39.477 N	109° 23' 57.632 W	
6,049.0	0.30	102.40	5,969.4	-757.7	-134.4	617,947.90	2,588,337.49	40° 0' 39.470 N	109° 23' 57.627 W	
6,144.0	0.50	119.80	6,064.4	-757.9	-133.8	617,947.65	2,588,338.10	40° 0' 39.467 N	109° 23' 57.619 W	
6,239.0	0.60	130.10	6,159.4	-758.5	-133.0	617,947.14	2,588,338.85	40° 0' 39.462 N	109° 23' 57.609 W	

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
6,333.0	0.60	132.60	6,253.4	-759.1	-132.3	617,946.51	2,588,339.60	40° 0' 39.456 N	109° 23' 57.600 W
6,427.0	0.70	133.50	6,347.4	-759.8	-131.5	617,945.80	2,588,340.40	40° 0' 39.448 N	109° 23' 57.590 W
6,521.0	1.10	129.40	6,441.4	-760.8	-130.4	617,944.86	2,588,341.53	40° 0' 39.439 N	109° 23' 57.576 W
6,616.0	0.70	180.20	6,536.4	-762.0	-129.7	617,943.72	2,588,342.26	40° 0' 39.427 N	109° 23' 57.567 W
6,708.0	0.90	174.60	6,628.4	-763.2	-129.6	617,942.44	2,588,342.36	40° 0' 39.415 N	109° 23' 57.566 W
6,802.0	0.70	162.60	6,722.4	-764.5	-129.4	617,941.16	2,588,342.63	40° 0' 39.402 N	109° 23' 57.563 W
6,896.0	0.80	170.50	6,816.3	-765.7	-129.1	617,939.97	2,588,342.94	40° 0' 39.390 N	109° 23' 57.559 W
6,991.0	0.90	179.80	6,911.3	-767.1	-129.0	617,938.57	2,588,343.08	40° 0' 39.376 N	109° 23' 57.558 W
7,000.0	0.86	179.20	6,920.3	-767.3	-129.0	617,938.44	2,588,343.09	40° 0' 39.375 N	109° 23' 57.558 W
Price River #1544									
7,086.0	0.50	168.80	7,006.3	-768.3	-128.9	617,937.42	2,588,343.19	40° 0' 39.365 N	109° 23' 57.557 W
7,180.0	0.40	145.50	7,100.3	-768.9	-128.7	617,936.76	2,588,343.47	40° 0' 39.358 N	109° 23' 57.553 W
7,274.0	0.60	166.10	7,194.3	-769.7	-128.4	617,936.02	2,588,343.80	40° 0' 39.351 N	109° 23' 57.549 W
7,368.0	0.70	165.20	7,288.3	-770.7	-128.1	617,934.99	2,588,344.09	40° 0' 39.341 N	109° 23' 57.546 W
7,462.0	0.90	167.50	7,382.3	-772.0	-127.8	617,933.72	2,588,344.42	40° 0' 39.328 N	109° 23' 57.542 W
7,558.0	1.20	164.50	7,478.3	-773.7	-127.3	617,932.03	2,588,344.89	40° 0' 39.311 N	109° 23' 57.536 W
7,651.0	0.90	161.00	7,571.3	-775.3	-126.9	617,930.41	2,588,345.43	40° 0' 39.295 N	109° 23' 57.530 W
7,746.0	1.10	161.60	7,666.3	-776.9	-126.3	617,928.85	2,588,346.00	40° 0' 39.280 N	109° 23' 57.523 W
7,838.0	1.20	161.20	7,758.2	-778.7	-125.7	617,927.12	2,588,346.63	40° 0' 39.262 N	109° 23' 57.516 W
7,932.0	1.30	159.30	7,852.2	-780.6	-125.0	617,925.21	2,588,347.37	40° 0' 39.243 N	109° 23' 57.507 W
8,026.0	1.20	150.00	7,946.2	-782.4	-124.2	617,923.38	2,588,348.28	40° 0' 39.225 N	109° 23' 57.495 W
8,119.0	1.40	156.50	8,039.2	-784.3	-123.2	617,921.51	2,588,349.26	40° 0' 39.206 N	109° 23' 57.483 W
8,212.0	1.60	148.40	8,132.1	-786.5	-122.1	617,919.39	2,588,350.45	40° 0' 39.185 N	109° 23' 57.469 W
8,306.0	1.10	133.20	8,226.1	-788.2	-120.7	617,917.69	2,588,351.83	40° 0' 39.168 N	109° 23' 57.452 W
8,399.0	1.10	122.60	8,319.1	-789.3	-119.3	617,916.63	2,588,353.26	40° 0' 39.157 N	109° 23' 57.434 W
8,493.0	1.00	131.30	8,413.1	-790.3	-118.0	617,915.64	2,588,354.66	40° 0' 39.147 N	109° 23' 57.416 W
8,589.0	1.00	136.50	8,509.1	-791.5	-116.8	617,914.50	2,588,355.89	40° 0' 39.136 N	109° 23' 57.400 W
8,627.0	0.90	136.00	8,547.1	-791.9	-116.3	617,914.06	2,588,356.34	40° 0' 39.131 N	109° 23' 57.395 W
8,681.0	0.90	126.00	8,601.1	-792.5	-115.7	617,913.52	2,588,356.99	40° 0' 39.126 N	109° 23' 57.387 W
8,774.0	1.40	128.90	8,694.0	-793.6	-114.2	617,912.41	2,588,358.49	40° 0' 39.114 N	109° 23' 57.368 W
8,868.0	1.10	127.90	8,788.0	-794.9	-112.6	617,911.18	2,588,360.13	40° 0' 39.102 N	109° 23' 57.347 W
8,963.0	1.30	142.10	8,883.0	-796.3	-111.2	617,909.80	2,588,361.54	40° 0' 39.088 N	109° 23' 57.329 W
9,057.0	1.30	149.40	8,977.0	-798.1	-110.0	617,908.07	2,588,362.78	40° 0' 39.070 N	109° 23' 57.314 W
9,151.0	1.70	130.30	9,070.9	-799.9	-108.4	617,906.29	2,588,364.43	40° 0' 39.052 N	109° 23' 57.293 W
9,245.0	1.90	122.20	9,164.9	-801.6	-106.0	617,904.61	2,588,366.85	40° 0' 39.035 N	109° 23' 57.263 W
9,336.0	1.80	122.90	9,255.8	-803.2	-103.6	617,903.09	2,588,369.36	40° 0' 39.020 N	109° 23' 57.231 W
9,389.5	1.80	122.90	9,309.3	-804.1	-102.2	617,902.21	2,588,370.80	40° 0' 39.011 N	109° 23' 57.213 W
PBHL #1544									
9,391.0	1.80	122.90	9,310.8	-804.1	-102.1	617,902.18	2,588,370.84	40° 0' 39.010 N	109° 23' 57.212 W
Projection to TD									

Company: EOG Resources
Project: Uintah County Utah
Site: Chapita Well Unit 1541- 1546-26D
Well: CWU #1544-26D
Wellbore: Wellbore #1
Design: Wellbore #1

Local Co-ordinate Reference: Well CWU #1544-26D
TVD Reference: True #34 @ 5034.0ft (RKB Elev.)
MD Reference: True #34 @ 5034.0ft (RKB Elev.)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 Single User Db

Targets
Target Name

- hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
PBHL #1544 - actual wellpath misses target center by 21.4ft at 9389.5ft MD (9309.3 TVD, -804.1 N, -102.2 E) - Point	0.00	0.00	9,310.0	-792.6	-120.2	617,913.32	2,588,352.52	40° 0' 39.125 N	109° 23' 57.444 W
Wasatch #1544 - actual wellpath misses target center by 47.5ft at 4680.4ft MD (4600.9 TVD, -748.6 N, -138.0 E) - Point	0.00	0.00	4,600.0	-792.6	-120.2	617,913.32	2,588,352.52	40° 0' 39.125 N	109° 23' 57.444 W
Price River #1544 - actual wellpath misses target center by 26.8ft at 7000.0ft MD (6920.3 TVD, -767.3 N, -129.0 E) - Circle (radius 50.0)	0.00	0.00	6,920.0	-792.6	-120.2	617,913.32	2,588,352.52	40° 0' 39.125 N	109° 23' 57.444 W

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
2,213.0	2,173.1	-352.1	-38.7	Tie into Surface Hole surveys
9,391.0	9,310.8	-804.1	-102.1	Projection to TD

Checked By: _____ Approved By: _____ Date: _____